



- GENERAL NOTES**
- THIS DRAWING SHOWS WORK FOR THE RELOCATION OF THE EXISTING CROSSTOWN PLATFORM PERMITS OBTAINED BY OTHERS.
  - WORK SHOWN ON THIS DRAWING SHALL BE IN ACCORDANCE WITH S.E.C. 570 TO 700 AND 705.
  - CROSSTOWN PLATFORM AND CART SHALL HAVE A SLIP RESISTANT SURFACE OF PAINT OR ANOTHER MATERIAL AS SHOWN ON THIS DRAWING.
  - STEEL LOCATED WITH HP12(5S) DENOTES EXISTING STEEL.
  - ALL STEEL SHALL BE ASTM A36 UNLESS OTHERWISE SPECIFIED. ALL WELDING SHALL BE ELECTRODE BENT.
  - ALL WORK INDICATED AS NEW SHALL BE FURNISHED & INSTALLED PER SPEC. X-2007.
  - INSTALLATION TORQUE FOR ASTM A307 BOLTS SHALL BE HAND TIGHT.
  - FOR CROSSTOWN CART SEE DWG. E-601.
- ERECTION PROCEDURE**
- REMOVE REMOVABLE BLOCK WALL ON COLUMN LINES 29 OR (17).
  - ERECT CROSSTOWN PLATFORM SECTIONS A AND N SAME RELATIVE POS. AS SHOWN ON LOCATION PLAN AT ELEV. 017.0 (THIS DWG.).
  - PLACE MOVABLE CART ON CROSSTOWN PLATFORM ORIENTED WITH EXISTING STEEL PAD LOCATED AS SHOWN ON THIS DWG. ATTACH SIDE GUIDES TO CART (SEE NEW DET. Q).
  - CHECK CART MOVEMENT TO ASSURE ITS ALIGNMENT OVER THE CROSSTOWN PLATFORM.
  - EQUIPMENT BEING MOVED SHALL BE PLACED IN CENTER OF 11'2\"/>

DRAWING RELEASE RECORD						DRAWING RELEASE RECORD					
REV.	SPEC. NO.	DATE	DRAWN	CHECKED	ENGR. APPROVAL	REV.	SPEC. NO.	DATE	DRAWN	CHECKED	ENGR. APPROVAL
1		7-11-75	M. J. ...								
2		11-6-75	M. J. ...								
3		4-6-76	M. J. ...								
4		11-19-81	M. J. ...								
5		07-16-84	M. J. ...								
6		04-19-85	M. J. ...								

**PROJECT NUMBER**  
5752-12  
5000-13  
5700-00  
6954-00

FUEL HANDLING BUILDING  
EQUIPMENT REMOVAL CROSSTOWN PLATFORM  
ZION STATION UNIT 1 & 2  
COMMONWEALTH EDISON CO.  
CHICAGO, ILLINOIS

**SARGENT & LUNDY**  
ENGINEERS  
CHICAGO

CONDITION OF ORIGINAL DRAWING - FAIR - REPRODUCTION CONSULTANTS LTD. . . 4-88-30X D48