

GSI-191 Fibrous Debris Characterization Bench-Top Test Program

Overview

- Bench-Top Test Objective
- Methodology
- Fiber Preparation
- Parameters
- Bench-Top Testing
- Report



Bench-Top Test Objective

- Establish a fiber length distribution to represent the prototypical fiber that may bypass containment ECCS strainers.
 - Inputs to testing based on the results from a PWROG industry survey
 - Testing will be generic, but will use parameters important to bypass testing to determine appropriate length distribution(s) (reduced scale) for use in future fuel testing
 - The objective is <u>not</u> to determine the quantity of fiber bypass



Methodology

- Fiber-only bypass tests on a bench-top test loop
- Incremental fiber introduction NEI Fiber Prep
- Isokinetic debris sampling
 - Not used to quantify bypass
- Debris capture downstream of the sampling ports to prevent debris re-circulation using filter bags
- Post-test microscopic analysis of bypassed fiber to determine the length distribution(s)



Fiber Preparation

- NEI Debris Preparation: "ZOI Fibrous Debris Preparation: Processing, Storage, and Handling"
 - Pressure washer
- Will use representative fiber types



Parameters – Not Important


- Strainer configuration / location within the plant
 - Debris prepared by NEI fiber prep only
- Plant specific strainer area
 - Not a head loss or bypass quantity test
- Quantity of fiber debris generated
 - Debris addition only up to an established fiber bed
- Rate of fiber arrival
 - Small incremental batches of NEI debris prepared fiber will provide the data required to meet the test objective




Parameters – Evaluated

- Based on the results of the PWROG survey
- Strainer perforation hole size
- Screen surface velocity
- Water temperature
- Water chemistry Tap, DI Buffer/Borated
- Localized Flow Conditions
 - Different shaped filter media to change the flow approach angle of attack











Test Tank: ≈10"W x 12"D x 36"L






Iso of Filter Media in Tank





Iso of Filter Media in Tank





Iso of Filter Media in Tank



- Debris addition sequence
- All fiber tested will be assume to be Low Density Fiber Glass (LDFG)

| Batch # | Fiber Addition (bed thickness in inches) | Total Bed Thickness (inches) |
|---------|---|---------------------------------|
| | 1/16 | 1/16 |
| 2 | 1/16 | 2/16 |
| 3 | 1/16 | 3/16 |
| 4 | 1/16 | 2/8 |
| 5 | 1/8 | 3/8 |
| 6 | 1/8 | 1/2 |



- Introduce debris
- Wait 10 turnovers and take downstream samples
- Sample timing
- Repeat the process until a ½ inch thick bed has been introduced
- After last batch, visually confirm a fiber bed, wait 10 turnovers and terminate



Report

- Microscopic characterization of fiber length
- Categorization into "bins"
 - 20 microns and less
 - 20-40 microns
 - 40-1000 microns (best fit categorization)



Questions



COVER SHEET FOR CORRESPONDENCE

USE THIS COVER SHEET TO PROTECT ORIGINALS OF MULTI-PAGE CORRESPONDENCE