

ENCLOSURE 2 TO AEP-NRC-2012-105

Decommissioning study of the D.C. Cook Nuclear Power Plant

Decommissioning Study of the D. C. Cook Nuclear Power Plant

Prepared for Indiana Michigan Power Company

Knight Cost Engineering Services, LLC
December, 2012

TABLE OF CONTENTS

1.0 INTRODUCTION	5
1.1 DONALD C. COOK UNITS 1 AND 2 PLANT SITE.....	5
1.2 OVERVIEW OF SCENARIOS.....	5
2.0 SUMMARY.....	7
2.1 DECOMMISSIONING ALTERNATIVES.....	7
3.0 DECOMMISSIONING COST ESTIMATING METHODOLOGIES.....	11
3.1 DECON.....	11
3.2 SAFSTOR.....	11
3.3 SPENT FUEL ACTIVITIES.....	12
3.4 OFF-SITE DRY STORAGE.....	14
3.5 DECOMMISSIONING MANAGEMENT.....	15
3.6 COLD & DARK.....	15
3.7 DECONTAMINATION PROCESS.....	15
3.8 CONTINGENCY.....	17
4.0 ASSUMPTIONS.....	19
5.0 SCENARIO DESCRIPTIONS.....	23
5.1 SCENARIO 1 - DECON WITH INDEFINITE ON-SITE DRY STORAGE.....	23
5.2 SCENARIO 2 - DECON WITH INDEFINITE OFF-SITE DRY STORAGE.....	24
5.3 SCENARIO 3 – DECON WITH ON-SITE DRY STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE	26
5.4 SCENARIO 4 - SAFSTOR WITH INDEFINITE ON-SITE DRY STORAGE.....	28
5.5 SCENARIO 5 – DECON WITH WET STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE.....	29
6.0 SCHEDULES.....	32
6.1 SCENARIO 1 - DECON WITH INDEFINITE ON-SITE DRY STORAGE.....	32
6.2 SCENARIO 2 - DECON WITH INDEFINITE OFF-SITE DRY STORAGE.....	34
6.3 SCENARIO 3 – DECON WITH ON-SITE DRY STORAGE, MODIFIED SYSTEMS,	

REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE	35
6.4 SCENARIO 4 - SAFSTOR WITH INDEFINITE ON-SITE DRY STORAGE.....	38
6.5 SCENARIO 5 – DECON WITH WET STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE	39
7.0 PROJECT MANAGEMENT.....	42
7.1 UTILITY STAFF.....	42
7.2 DECOMMISSIONING GENERAL CONTRACTOR.....	43
7.3 SECURITY.....	43
7.4 SCENARIO 1 - DECON WITH INDEFINITE ON-SITE DRY STORAGE.....	44
7.5 SCENARIO 2 - DECON WITH INDEFINITE OFF-SITE DRY STORAGE.....	45
7.6 SCENARIO 3 – DECON WITH ON-SITE DRY STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE	45
7.7 SCENARIO 4 - SAFSTOR WITH INDEFINITE ON-SITE DRY STORAGE.....	46
7.8 SCENARIO 5 – DECON WITH WET STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE	47
8.0 WASTE DISPOSAL.....	49
8.1 LOW LEVEL WASTE DISPOSAL BACKGROUND.....	49
8.2 CLASS A WASTE DISPOSAL.....	49
8.3 CLASS B & C WASTE DISPOSAL.....	50
8.4 DISPOSAL OF WASTE GREATER THAN CLASS C.....	50
8.5 RADIOACTIVE WASTE VOLUMES PER 10CFR61 CLASSIFICATIONS.....	51
8.6 PROJECTION OF NON-RADIOACTIVE WASTE QUANTITIES.....	51
9.0 COST SUMMARIES.....	52
9.1 ESTIMATING APPROACH.....	52
9.2 SCENARIO 1 - DECON WITH INDEFINITE ON-SITE DRY STORAGE.....	53
9.3 SCENARIO 2 - DECON WITH INDEFINITE OFF-SITE DRY STORAGE.....	54
9.4 SCENARIO 3 – DECON WITH ON-SITE DRY STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE	55
9.5 SCENARIO 4 - SAFSTOR WITH INDEFINITE ON-SITE DRY STORAGE.....	56

9.6 SCENARIO 5 – DECON WITH WET STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE	57
10.0 REFERENCES.....	59

1.0 INTRODUCTION

1.1 DONALD C. COOK UNITS 1 AND 2 PLANT SITE

The Donald C. Cook Plant Nuclear Power Plant (D.C. Cook Plant) is a nuclear-powered electrical generating facility located in Bridgman, Michigan. D.C. Cook Plant consists of two pressurized water reactors (PWR). Its electrical rating is 1020 Mwe for reactor Unit 1 and 1090 Mwe for reactor Unit 2. D.C. Cook Plant has been granted a twenty year license extension by the Nuclear Regulatory Commission (NRC). Based on the terms of this extension, Unit 1 is scheduled for shutdown on October 25, 2034; Unit 2 is scheduled for shutdown on December 23, 2037. Units 1 & 2 are planned to be decommissioned in series following shut down.

This study is an update of the 2009 site-specific Decommissioning Cost Estimate of the D.C. Cook Nuclear Power Plant, Units 1 & 2, prepared for the Indiana Michigan Power Company (the Company). As such, it reflects site specific plant information and cost factors. The most current decommissioning experience and logic have been incorporated into this estimate, including spent fuel acceptance rates, spent fuel storage issues, decommissioning methodologies, decommissioning management and waste disposal.

1.2 OVERVIEW OF SCENARIOS

This study consists of five decommissioning scenarios, comprised of four DECON scenarios and one SAFSTOR scenario.

Two of the DECON scenarios assume on-site dry spent fuel storage as follows: one with spent fuel remaining on-site indefinitely and one with a 2032 spent fuel shipping start and at the most recent acceptance rate. One DECON scenario assumes off-site dry spent fuel storage with spent fuel remaining off-site facility indefinitely. The final DECON scenarios assume wet spent fuel storage 2032 spent fuel shipping start and at the most recent acceptance rate.

The SAFSTOR scenario assumes on-site dry storage with spent fuel remaining on-site indefinitely.

The cost estimates contained herein were developed based on a May, 2012 configuration. They utilize previously-developed site specific plant systems and building inventory, and have been modified as appropriate. Costs have been determined for removal, packaging, transportation and disposal.

The decommissioning activities contained herein were previously developed and have been modified as required, with costs determined for each activity. The critical path schedule was previously developed and has been modified based on new spent fuel shipping assumptions and new and modified task durations. Period-dependent costs include utility staff, decommissioning general contractor staff, security, insurance, energy and others. Cost levels were determined

based on specific periods or groups of activities per the schedule. Total period dependent costs were determined by the scenario-specific durations. Activity and period dependent costs were totaled to determine overall costs for each scenario.

The purpose of this study is to provide a range of decommissioning costs for financial planning. All costs are in summer, 2012 dollars. All costs are based on the aforementioned spent fuel shipping and storage assumptions. The selected assumptions are then applied to one of two basic decommissioning scenarios.

Utilizing the above estimating methodology, costs range from \$1,316,367,800 to \$1,954,519,300. This range encompasses the initial decommissioning cost and 60 years of on or off site spent fuel storage.

2.0 SUMMARY

Decommissioning is the safe removal of a facility or site from service and the reduction of radioactivity to a level that permits either the release of the property for unrestricted use and NRC license termination; or a restricted release of the property and NRC license termination.

2.1 DECOMMISSIONING ALTERNATIVES

The NRC allows three types of scenarios in estimating the decommissioning of a nuclear site, DECON, SAFSTOR and ENTOMB. The first, DECON, occurs soon after shutdown. It assumes that all systems, structures and contaminated site areas will be removed or decontaminated and that the facility's license will be terminated.

For the second type of scenario, SAFSTOR, preparations occur soon after shutdown. It assumes limited site decontamination and dismantlement; that all liquid will be drained from systems; that the facility will be placed in a safe and stable condition; that all spent fuel will be held in storage or shipped from the site; and that the site will be decontaminated and its license terminated within sixty years.

In the third type of scenario, ENTOMB, preparations occur soon after shutdown. It assumes limited site decontamination and dismantlement; that all liquid will be drained from systems; that the remaining radioactive systems and structures will be encased inside an entombment structure; that the facility will be continuously monitored; that spent fuel will be held in storage or shipped from the site; that the site will be decontaminated and license terminated within 60 years; and that most reactors will have radionuclides in concentrations exceeding the limits for unrestricted release after 100 years. This study does not consider the ENTOMB scenario.

Per NRC regulations, there are specific reporting requirements for decommissioning and spent fuel storage. Regulation 10 CFR 50.75, *Reporting and Recordkeeping for Decommissioning Planning*, requires a decommissioning report certifying that financial assurance will be available for decommissioning. The amount funded must be adjusted annually. A report on the status of funding must be submitted every two years. Costs not associated with decommissioning, such as spent fuel storage and clean removal costs, are specifically excluded.

Regulation 10 CFR 50.54(bb) requires a program by which the licensee plans to manage and provide funding for the management of spent fuel following permanent cessation. This is required within two years of permanent cessation or within five years before license expiration. The licensee must demonstrate the actions will be consistent with NRC requirements and will be implemented on a timely basis according to these requirements.

While neither of the above NRC regulations require Greenfield or clean system and structure removal costs, these costs may be required by local authorities to minimize liability. Removal of

clean systems and structures may also be required to access contaminated components and structures. Therefore, Greenfield costs have been included in this study.

Table 2-1 provides a summary of costs for the five scenarios. Each summary of costs is based on one of two decommissioning scenarios. Costs are separated into the three cost categories based on the aforementioned spent fuel shipping and storage assumptions and have been determined based on the described estimating methodology.

**TABLE 2-1
SUMMARY OF COSTS**

Scenario 1	DECON, Indefinite On-Site Dry Storage and Modified Spent Fuel Pool Systems				
	Decommissioning Alternative	Fuel Storage and Decommissioning Cost	Dormancy Period Cost	Delayed Dismantling Cost	Total Program Cost
	10 CFR 50.75(c)	\$793,192,081	N/A	N/A	\$793,192,081
	10 CFR 50.54(bb)	\$386,210,019	N/A	N/A	\$386,210,019
	Greenfield	\$142,003,089	N/A	N/A	\$142,003,089
				total:	\$1,321,405,189
	Annual ISFSI	\$4,477,802			\$4,477,802
Scenario 2	DECON, Indefinite Off-Site Dry Storage and Modified Spent Fuel Pool Systems				
	Decommissioning Alternative	Fuel Storage and Decommissioning Cost	Dormancy Period Cost	Delayed Dismantling Cost	Total Program Cost
	10 CFR 50.75(c)	\$791,899,423	N/A	N/A	\$791,899,423
	10 CFR 50.54(bb)	\$349,807,122	N/A	N/A	\$349,807,122
	Greenfield	\$143,715,003	N/A	N/A	\$143,715,003
				total:	\$1,285,421,548
	Annual ISFSI	\$6,604,893			\$6,604,893
Scenario 3	DECON, On-Site Dry Storage, Modified Systems, 2032 Repository and Recent DOE Acceptance Rate				
	Decommissioning Alternative	Fuel Storage and Decommissioning Cost	Dormancy Period Cost	Delayed Dismantling Cost	Total Program Cost
	10 CFR 50.75(c)	\$792,522,613	N/A	N/A	\$792,522,613
	10 CFR 50.54(bb)	\$428,426,257	N/A	N/A	\$428,426,257
	Greenfield	\$142,032,743	N/A	N/A	\$142,032,743
				total:	\$1,362,981,613
Scenario 4	SAFSTOR, Indefinite On-Site Dry Storage and Modified Spent Fuel Pool Systems				
	Decommissioning Alternative	Fuel Storage and Decommissioning Cost	Dormancy Period Cost	Delayed Dismantling Cost	Total Program Cost
	10 CFR 50.75(c)	\$144,497,666	\$223,368,512	\$533,460,886	\$901,327,065
	10 CFR 50.54(bb)	\$193,393,386	\$416,521,135	\$30,271,567	\$640,186,089
	Greenfield	N/A	N/A	\$143,414,045	\$143,414,045
				total:	\$1,684,927,198
	Annual ISFSI	\$4,493,201			\$4,493,201

Scenario 5	DECON, On-Site Wet Storage, Modified Systems, 2032 Repository and Recent DOE Acceptance Rate				
	Decommissioning Alternative	Fuel Storage and Decommissioning Cost	Dormancy Period Cost	Delayed Dismantling Cost	Total Program Cost
	10 CFR 50.75(c)	\$814,816,904	N/A	N/A	\$814,816,904
	10 CFR 50.54(bb)	\$359,209,532	N/A	N/A	\$359,209,532
	Greenfield	\$142,341,328	N/A	N/A	\$142,341,328
				total:	\$1,316,367,763

3.0 DECOMMISSIONING COST ESTIMATING METHODOLOGIES

3.1 DECON

There are typically six periods associated with the DECON methodology of decommissioning cost estimating. Period one consists of decommissioning planning prior to shutdown. Period two involves post-shutdown preparations. These include isolation of spent fuel; decontamination of the primary system; flushing and draining of all systems; implementation of cold and dark; and characterization surveys. Period three consists of removal of reactor internals and removal of the reactor vessel. The critical path task for period three is the removal, packaging, shipping and disposal of the reactor internals and the reactor vessel. Also in period three, the steam generators, pressurizers, contaminated systems and structures are removed, packaged, shipped and disposed of. Additionally, clean structures and systems are removed as they become unnecessary. In period four, the buildings undergo decontamination. This includes decontamination of the reactor building(s), removal, packaging, shipping and disposition of spent fuel racks after spent fuel has been removed from the spent fuel pool, decontamination of the spent fuel pool and the balance of the auxiliary building(s), a formal site survey of any remaining buildings, and termination of 10 CFR Part 50 license. Period five consists of demolition of clean buildings. In this period, all clean structures are removed with the exception of any required to support spent fuel storage. Period six consists of site restoration. In this period, the site is graded and landscaped to conform to the natural surroundings. Depending on the spent fuel storage assumptions, these periods may be separated by a wet spent fuel storage period, a dry spent fuel storage period, and/or a combination of both.

Four of the five scenarios in this study utilize the DECON methodology.

There are advantages to utilizing the DECON methodology. This methodology provides quick termination of the NRC license. Knowledgeable employees who are familiar with the site will still be available. There is no need for long-term security and surveillance. The DECON method provides a greater certainty of regulatory requirements due to the inherent uncertainty in trying to assess future regulatory requirements. Finally, the total cost will be lower as it is incurred in current dollars and there is no extended dormancy period.

Disadvantages of the DECON methodology include the following: the short time period that elapses following shut-down means less radioactive decay and therefore a higher worker dose. The initial cash outlay will be larger. There is less time for funds to accrue, which means a larger present value; and work will have to be performed in proximity to the on-site storage of spent fuel.

3.2 SAFSTOR

There are typically eight periods associated with the SAFSTOR methodology of decommissioning cost estimating. Period one consists of planning prior to shutdown. Period two

is post-shutdown preparations. These include isolation of spent fuel; decontamination of the primary system; flushing and draining of all systems; general cleanup and decontamination of site buildings; and characterization surveys. Period three is a period of dormancy. There may be a storage period during dormancy when spent fuel remains in the spent fuel pool, on-site in dry storage, or a combination of both. Period four consists of decommissioning planning during the dormancy period. Period five involves removal of reactor vessel internals and removal of the reactor vessel. The critical path task for period five is the removal, packaging, shipping and disposal of the reactor internals and the reactor vessel. Also in period five, the steam generators, pressurizers, contaminated systems and structures are removed, packaged, shipped and disposed of as they become available. Additionally, clean structures and systems are removed as they become unnecessary. In period six, the building undergoes decontamination. This includes decontamination of the reactor building(s), removal, packaging, shipping and disposition of spent fuel racks after spent fuel has been removed from the spent fuel pool, decontamination of the spent fuel pool and the balance of the auxiliary building(s), a formal site survey of any remaining buildings, and termination of 10 CFR Part 50 license. During period seven, all clean structures are demolished and removed with the exception of those required to support spent fuel storage. During period eight, the site is restored by being graded and landscaped to conform to the natural surroundings.

One of the five scenarios in this study assumes the SAFSTOR methodology.

There are advantages to using the SAFSTOR methodology of decommissioning cost estimating. As a result of decay, there will be a reduction in the amount of radioactivity present, meaning a reduced worker dose. There will be a smaller initial cash outlay and a smaller present value due to more time for funds to accrue interest. On-site spent fuel storage will most likely occur during dormancy, allowing decommissioning to proceed without the constraints imposed by spent fuel storage.

Disadvantages of utilizing the SAFSTOR methodology include the following: employees familiar with site history will no longer be available; this methodology necessitates ongoing maintenance and surveillance; there will be inherent uncertainties regarding regulatory requirements and uncertainties around low-level waste disposal facility availability.

3.3 SPENT FUEL ACTIVITIES

There are many uncertainties associated with the Department of Energy's (DOE) acceptance of spent fuel. The Department of Energy (DOE) originally contracted to begin accepting spent fuel from nuclear power plants no later than January 31, 1998. To date, no spent fuel has been taken by the DOE. Many utilities have brought legal proceedings against the DOE for their breach of contract with the majority winning court ordered compensation. Recently, all activity at Yucca Mountain has been shutdown and, at least in the near term, has been removed as a potential spent fuel repository. It appears unlikely that that spent fuel shipments to a Federal repository will

occur anytime in the foreseeable future. In light of this fact, all nuclear utilities should be prepared to store spent fuel on-site for a long period of time. Three scenarios in the study assume indefinite storage, two on-site and one off-site.

There has been some renewed discussion on interim storage at privately funded facility, Private Fuel Storage (PFS). In July 2010 a U. S. District Court rejected two U.S. Department of Interior decisions that placed the PFS on hold. Based on this ruling, the Interior's decisions have been remanded to the agency for further consideration. Should interim storage come to fruition, some spent fuel acceptance rate, short of that currently published, would most likely be implemented. One scenario in the study assumes spent fuel will be transferred off-site to a PFS.

With the shutdown of Yucca Mountain there is currently no published DOE acceptance schedule of spent fuel. The most recent DOE acceptance schedule is outlined in *DOE/RW-0591 Total System Life Cycle Cost Report, July 2008*. The following are the assumed acceptance rates:

- Year 1: 400 Metric Tons Heavy Metal (MTHM)
- Year 2: 600 MTHM
- Year 3: 1,200 MTHM
- Year 4: 2,000 MTHM
- Year 5: 3,000 MTHM
- Any year after year 5: 3,000 MTHM

This rate has been utilized in two scenarios within this study.

Considering the current status of Yucca Mountain and the lack of alternatives for the DOE's retrieval of spent fuel a spent fuel shipping start date is an unknown at this time. Two of the scenarios in this study assume a start date twenty years in the future, 2032. Twenty years should be sufficient time to develop at least an interim storage facility should progress begin in the near term.

One scenario within study assumes spent fuel will remain in the spent fuel pool for an extended storage period versus transfer to dry storage. While dry storage will be required during operations to maintain full core discharge capabilities, no additional dry storage will be purchased after shutdown.

In order to minimize post-shutdown spent fuel storage costs the spent fuel island concept will be implemented. Modifications to the site will provide self contained fuel pool cooling, cleanup, monitoring, control and electrical power systems. This will isolate the spent fuel pool from the remainder of the site and will allow decommissioning to continue safely on the balance of site.

Three scenarios within study assume spent fuel will be transferred to an on-site Independent Spent Fuel Storage Installation (ISFSI) after shutdown. Dry storage will be required during operations to maintain full core discharge capabilities. The ISFSI will be expanded after shutdown to accommodate the long term storage of spent fuel. The storage system is anticipated

to be licensed for both storage and transportation facilitating the eventual transfer to the DOE site.

It is assumed that spent fuel cannot be transferred to dry storage until it has cooled a minimum of five years in the spent fuel pool. In order to minimize post-shutdown spent fuel storage costs during this five year period the spent fuel island concept, as discussed above, will be implemented. This option will provide the low cost option for the long term on-site storage of spent fuel.

Per ISFSI Licensing requirements, a 10 CFR part 72 license will be required in order to terminate the 10 CFR Part 50 license. Systems approved for use under the provisions of 10 CFR part 72 Subpart K, a Certificate of Compliance, may be used on a site with a 10 CFR part 50 license without a 10 CFR Part 72 Subpart C license. The process to obtain a 10 CFR Part 72 license will be simplified by utilizing a storage system with a Certificate of Compliance. For this reason, this study assumes the dry storage system utilized will have a Certificate of Compliance.

A site re-evaluation is not required to obtain the Part 72 subpart C ISFSI license if it is shown that original site findings have not changed. A reevaluation would only be required if new information is available that alters the original findings. It is assumed that the system utilized for dry storage will meet or could be modified to meet the original site design conditions.

3.4 OFF-SITE DRY STORAGE

One scenario in this study assumes spent fuel will be transferred to and stored in an off-site dry storage facility. Private Fuel Storage LLC (PFS) has been licensed by the NRC to store spent fuel at an away-from plant-facility. PFS, a consortium of eight nuclear utilities including AEP, is located on property belonging to the Goshute Indian Tribe. This land is in Tooele County, Utah. The construction and operation of this facility is currently being held up by court actions. Maximum storage capacity of this facility will be 40,000 MTHM of spent fuel from U.S. commercial power reactors.

One scenario of this study assumes that the PFS facility will be in operation and available to accept spent fuel from D. C. Cook in 2035. Spent fuel will be stored in on-site dry storage during operations to maintain full core off load capability. This fuel, along with all spent fuel stored in the spent fuel pool after Unit 2 shutdown, will be transferred to off-site storage after cooling a minimum of five years in the spent fuel pool. It is assumed that all spent fuel in the pool will be off-site approximately five and one half years after shutdown. Initial cost to AEP for shipping to the off-site facility and the storage casks is estimated to be \$128.37/kgU. Additionally, an estimated cost of \$200/kgU will be incurred for annual storage fees.

3.5 DECOMMISSIONING MANAGEMENT

The utility staff will retain certain of their ongoing functions during decommissioning, including the following:

- Shipment of low-level waste remaining from plant operations
- Radiological health and safety
- Security
- Quality assurance
- Health physics monitoring
- Defueling of the reactor
- Draining and de-energizing of all systems
- Continued safe on-site storage of spent fuel
- Management of the decommissioning general contractor.

The number of staff during each period depends on the major work planned for each period. Details are provided in section seven of this report.

This study assumes that the utility will hire an experienced decommissioning general contractor (DGC) who will be responsible for performing the decommissioning activities. The DGC in turn will hire and be responsible for subcontractors hired to perform activities, such as primary system decontamination flush and large component removal. The number of staff during each period depends on the major work planned for each period. Details are provided in section seven of this report.

3.6 COLD & DARK

To simplify the removal of systems and structures, a “cold & dark” status will be implemented. The cold & dark status will allow component removal without individually verifying that each component has been de-energized. To implement cold & dark, all systems will be drained and electrical power to components will be removed as appropriate. After the spent fuel pool isolation has been completed, a new minimized control room will be constructed. Construction power will be supplied to the site for decommissioning and to operate essential loads with color coded wire. This process ensures that all energy sources are removed prior to the beginning of decommissioning activities, simplifying the removal process and greatly increasing safety during the decommissioning process.

3.7 DECONTAMINATION PROCEDURES

To facilitate the removal of contaminated large components, contamination control envelopes (CCE's) will be set up inside the reactor building. CCEs will have integral ventilation systems for contamination control and to maintain negative pressure. Cutting stations, including for underwater cutting, will be set up within the reactor building.

The reactor vessel internals will be removed from the vessel and transferred to the fuel transfer canal. Once in the transfer canal, they will be segmented and loaded underwater into shipping liners. The liner outer surfaces will be washed and loaded into shipping casks for transport to the disposal facility.

The reactor vessel will be cut into ring segments with each segment transferred to the fuel transfer canal. Here, each segment will be further segmented and loaded into shipping cask liners. The outer surfaces of the liners will be washed and then loaded into shipping casks for transport to the disposal facility.

With the exception of the upper shell, the steam generator will be removed intact. A steam generator transfer system and support equipment will be installed to remove the steam generator from the reactor building. A CCE and ventilation system, scaffolding, temporary lighting and shielding will also be installed. The insulation will be removed from the steam generators, followed by cutting of the main steam, feedwater and miscellaneous piping. Next the upper shell and components will be cut and removed. These will be surveyed, decontaminated and released if possible.

A steel plate will be welded to the top of the lower shell. The lower shell will be removed, transferred from the building, prepared for transport and transported to the disposal facility.

The pressurizer will be removed in a similar fashion, excluding segmentation.

The following process will be used for removal and disposal of contaminated systems, previously drained by the utility staff: Contaminated pipe and components will be cut free and segmented as necessary. The components will be transferred to a packaging area where a crew will package them, survey the containers and prepare the containers for shipment.

Clean pipe and components will be cut free and segmented when necessary. The components will be transferred to a packaging area where a crew will package the material into containers and prepare for them for shipment. It is assumed that clean waste will be disposed of at a local landfill.

With the exception of the reactor building interior, contaminated concrete surfaces will be decontaminated by partial surface removal. In some cases entire walls and/or floors will be removed. The remaining structures will be surveyed for conformance to release limits. Depending on the results of the survey, more decontamination may be required. Bulk removal of the reactor building interior floors and walls will be performed with all of the material being sent out for off-site processing. This leads to a large disposal volume; however, at a lower rate for bulk processing than for direct burial. In addition, there will be far less characterization and iterative decontamination.

Clean structures will be demolished using explosives and/or mechanical means and disposed of at a local landfill.

3.8 CONTINGENCY

Contingencies are applied to cost estimates primarily to account for unknown or unplanned events that experience tells us are likely to occur. These events include increased radioactive waste materials in volumes exceeding the amount anticipated; equipment breakdowns; weather delays; labor strikes, etc. Estimates are based on assumed values of cost which in reality are subject to variability. The actual costs may be higher or lower than the estimated value; however, they usually go higher. The amount of contingency to be added is directly related to the level of detail and uncertainty contained in the estimate.

The U.S. Department of Energy (DOE) Cost Estimating Guide, DOE G 430.1-1, 3-28-97; defines contingency as follows: "Covers costs that may result from incomplete design, unforeseen and unpredictable conditions, or uncertainties within the defined project scope. The amount of contingency will depend on the status of design, procurement, and construction; and the complexity and uncertainties of the component parts of the project. Contingency is not to be used to avoid making an accurate assessment of expected costs."

DOE G 430.1-1 provides a recommended range of contingencies as a function of program design:

<u>Time of Estimate</u>	<u>Contingency Range as a % of Total Estimate</u>
Planning Phase	20-30
Budget	15-25
Title I	10-20
Title II	5-15

The AACE International Certification Study Guide, Second Edition - Revised, 2003, defines contingency as follows: "Contingency is a cost element of an estimate to cover a statistical probability of the occurrence of unforeseeable elements of cost within the defined project scope due to a combination of uncertainties, intangibles and unforeseen, highly-unlikely occurrences of future events based on management decisions to assume certain risks."

AIF/NESP-0036 "Guidelines for Producing Nuclear Plant Decommissioning Cost Estimates" (AIF) is another source for published contingency values. This document identifies contingencies for activities specific to nuclear power plant decommissioning. Except for system decontamination, reactor vessel removal and disposal and reactor internals removal and disposal, the contingencies presented in AIF are consistent with the values presented in DOE G 430.1-1 for a Budget/Title I estimate. The contingencies identified in AIF for system decontamination and reactor vessel and reactor internals removal and disposal are higher than the ranges identified in DOE G 430.1-1. This is in part due to the lack of actual decommissioning work performed during the time period the AIF document was published.

An estimate of the nature developed for D. C. Cook would be considered somewhere between a Budget estimate (based on conceptual design) and a Title I (based on more detailed site specific design). As such, an overall contingency in the 15% to 25% range would be appropriate. Knight Cost Engineering Services, LLC (KCES) has determined contingency values specific to DC Cook utilizing the information presented in AIF and consistent with DOE G 430.1-1. There are a number of large scale decommissioning projects in progress or nearing completion. The DC Cook decommissioning cost estimate incorporates the lessons learned from these projects. As such, costs can be estimated with a greater degree of confidence than was true at the time AIF was published. This increased level of confidence allows for a downward adjustment to the recommended contingency. The following table provides a summary of the contingency values that were applied to each activity for each cost category.

TABLE 3.1

	<u>Staff Labor</u>	<u>Craft Labor</u>	<u>Equip & Mtls</u>	<u>Pkging</u>	<u>Trans- portation</u>	<u>Clean Disposal</u>	<u>Contam- inated Disposal</u>	<u>Energy</u>	<u>Other</u>
Engineering and Project Management	15%								
Contaminated removal		25%		10%	15%		25%		
Reactor Vessel and Internals		50%		25%	25%		50%		
Clean removal		15%		10%	25%	10%			
Supplies and consumables			25%						
Other								15%	15%

There is some variation associated with the contingency analysis for on-site spent fuel storage. The activity costs associated with spent fuel storage, such as the purchase and construction of the ISFSI, the modification of the spent fuel pool and the transfer of spent fuel pool to the ISFSI are subject to many of the unknown or unplanned occurrences for which contingency is based. As such, the above methodology will be applied. During periods of spent fuel storage only, either wet or dry, the operating costs of the spent fuel storage facility include only a ten percent contingency because of the higher degree of knowledge and confidence in the factors comprising the operation of the wet or dry storage facility. Any variability in the duration of the fuel storage period due to failed DOE schedules is excluded from the contingency. This is treated by the different spent fuel shipping scenarios.

4.0 ASSUMPTIONS

Following is a list of assumptions developed by KCES in completing this study. These assumptions are based on the most current decommissioning methodologies and site-specific considerations.

1. **Component quantities** were previously developed from actual plant inventory listings.
2. **Concrete volumes** were previously obtained from plant construction records and detailed drawings.
3. **The utility staff** is assumed to be the same size at the time of Unit 2 shutdown as it was in July, 2012.
4. **Subcontractor base labor rates and fringe benefits** were supplied by AEP for most crafts. These rates were current as of June, 2012. The overhead and profit structure for these rates was developed by KCES.
5. **Craft labor rates** for positions not supplied by the Company were determined by KCES.
6. **Utility staff positions and costs** were supplied by the Company and represent July, 2012 salary and benefit data.
7. **Activity labor** costs do not include any allowance for delays between activities, nor is there any cost allowance for craft labor retained on-site while waiting for work to become available.
8. All **skilled laborers** will be supplied by the local union hall and hired by the Decommissioning General Contractor (DGC).
9. The **professional personnel** used for the planning and preparation activities will be paid per diem at the rate of \$131.00/day. Since the skilled laborers are being supplied by local union hall they will not be paid per diem.
10. The cost for **Utility personnel** assisting the DGC to develop decommissioning activity specifications is included in the Utility Staff costs.
11. **Health Physics technicians** used during vessel and internal removal will be supplied by the Utility Staff.
12. **The separate DGC staff salaries**, including overhead and profit, were determined by KCES.
13. **Transportation** costs are based on actual mileage from D. C. Cook to each disposal or processing facility utilized in the estimate.

14. **Class B & C radioactive waste base disposal costs** are based on actual out of compact disposal rates and fees incurred at the WCS facility in Andrews, TX. In addition, the disposal costs of the >C waste, e.g., the core shroud, include present day curie surcharges as imposed at the WCS facility to more accurately reflect handling costs for highly radioactive material.
15. **Class A waste** will be disposed of at the *EnergySolutions* facility in Utah, *EnergySolutions* metal melt facility in Tennessee or the Studsvik processing facility in Tennessee. Waste is assumed to be transported to the lowest cost facility for which it qualifies. Further details on these processes are presented in Section 8.1.
16. **Clean waste** is assumed to be disposed of at a local landfill at a cost of \$90.00 per ton.
17. It is assumed that **all radioactive waste** generated during operations and stored on-site will be disposed of prior to shutdown. The cost of disposal of this material is considered an operating expense and is assumed not to be a decommissioning cost.
18. **Greater than Class C waste** will be removed from the reactor vessel, segmented and packaged in containers of similar size and shape to the spent fuel assemblies. The containers will be stored in the spent fuel pool or transferred to the ISFSI. The additional containers are assumed to be shipped offsite with the spent fuel and are included in the spent fuel shipping analysis. Eighty-four containers will be filled per unit for all scenarios except Scenario 3, which will fill 16 per unit.
19. **All costs** used in these calculations were current on July, 2012.
20. The costs of all **required safety analyses and safety measures** for the protection of the general public, the environment, and decommissioning workers are included in the cost estimates.
21. All post shutdown costs necessitated by the presence of **stored spent fuel** are presented separately.
22. It is assumed that **Unit 1 will shutdown** in October, 2034 and that **Unit 2 will remain operational** until December 2037.
23. **On-site dry storage** will utilize the Holtec Vertical Concrete Casks (VCC) and Multi-Purpose Canister (MPC) system. Each MPC is designed to store and transport 32 spent fuel assemblies. Separate overpacks will be used for transportation and disposal.
24. It is assumed that spent fuel will cool five years in the spent fuel pool prior to being transferred to the ISFSI.
25. Only the costs for the **expanded storage pad, canister and overpacks** projected to be purchased after Unit 2 shutdown are included in this study as a spent fuel storage expense. Any canister and overpacks required during operations, in order to maintain full

- core discharge capabilities, are assumed to be an operations expense. The cost per canister and storage overpack is estimated to be \$1,929,750, including closure services.
26. **For Scenario 2 only**, it is assumed that the off-site dry storage facility will be available to begin accepting spent fuel in 2035. Spent fuel will be transferred to on-site dry storage during operations.
 27. **Spent fuel shipments to a DOE facility** are based on D.C. Cook Plant spent fuel inventory, the constraints imposed by each scenario and the July 2004 Acceptance Priority Ranking & Annual Capacity Report.
 28. All **spent fuel** must remain in the spent fuel pool a minimum of five years before either being shipped to the DOE facility or being transferred to the dry storage facility.
 29. **Spent fuel assemblies to be shipped to the DOE facility** will be taken from the spent fuel pool when possible. By removing as much of the spent fuel from the spent fuel pool a minimum number of assemblies will remain in the pool five years after shutdown of Unit 2.
 30. **The Unit 1 and Unit 2 reactor vessel and internals** will be removed sequentially.
 31. **The Unit 1 and reactor vessel and internals** are considered identical.
 32. **Vessel and internals curie estimates** were derived from the values for the Reference PWR vessel and internals in NUREG/CR-0130. These values were adjusted for MWt rating, weight and decay period.
 33. It has been assumed for purpose of this study that **property taxes** for the D.C. Cook Plant will be zero after shutdown.
 34. No **PCBs** will be on-site at shutdown.
 35. It is assumed that all **asbestos insulation** will have been removed during the operating life of the plant.
 36. **Clean building walls and foundations** more than three feet below grade may be left in place if there are no voids.
 37. KCES has assumed that for the **on-site dry storage** scenarios, a site specific 10 CFR Part 72 license will be required for the balance of the dry storage period prior to terminating the 10 CFR Part 50 operating license.
 38. The decommissioning will be performed under the **current regulations**. These regulations require a Post-Shutdown Decommissioning Activities Report (PSDAR) to be submitted prior to or within two years of after shutdown. In addition, certificates for permanent cessation of operations and permanent removal of fuel from the vessel must be

submitted to the NRC 90 days after the PSDAR submittal. Major decommissioning activities that meet the criteria of 10 CFR Part 50.59, may be performed provided NRC agrees with the PSDAR.

5.0 SCENARIO DESCRIPTIONS

Five decommissioning scenarios have been analyzed for this report. Utilizing the above described estimating methodology costs range from \$1,323,204,200 to \$1,961,355,500. The assumptions pertinent to each are described in the following sections.

5.1 SCENARIO 1 -DECON WITH INDEFENITE ON-SITE DRY STORAGE

This scenario includes Unit 1 shutdown on Oct 25, 2034 and Unit 2 on Dec 23, 2037. The transfer of spent fuel remaining in the spent fuel pool to the dry storage facility will begin in 2036. The existing ISFSI will be expanded to accommodate all spent fuel remaining on-site. With the exception of the last core load of fuel assemblies, transfer of all remaining fuel to the ISFSI will be completed within five years after shutdown. The transfer of the last core load of 193 assemblies and a few remaining assemblies will occur immediately after the required five year cooling period. The site will remain as an Independent Spent Fuel Storage Installation indefinitely.

The spent fuel pool will be modified immediately after shutdown to isolate it from the remainder of the facility. The capital cost of the skid mounted pool support systems package is included in this estimate. This will allow decommissioning to proceed exclusive of the spent fuel pool. Once all spent fuel has been removed from the spent fuel pool, the spent fuel pool island will be decommissioned. As soon as all spent fuel is transferred to dry storage, the balance of the D.C. Cook Plant will be decommissioned. All spent fuel will be stored on-site in Holtec's VCC and MPC system.

The six sequential periods in this scenario and the major activities occurring in each are as follows:

<u>Period</u>	<u>Description</u>	<u>Period Duration, Months</u>
1	BETWEEN SHUTDOWN OF UNIT 1 AND SHUTDOWN OF UNIT 2 • Planning for spent fuel pool modifications • Planning for cold and dark • Planning for primary systems flush • Select DGC • Planning for decommissioning	38
2	POST-SHUTDOWN ACTIVITIES • Transfer spent fuel from pool to the ISFSI • Modification of spent fuel pool systems • Primary system decontamination flush • Flush and drain non-essential systems • Perform characterization survey • Implement cold and dark • Vessel and Internals removal preparations	12

3	REMOVAL OF MAJOR COMPONENTS	38
	• Transfer spent fuel from pool to the ISFSI • Removal of Unit 1 and Unit 2 reactor vessels and internals • Removal of Unit 1 and Unit 2 steam generators • Removal of Unit 1 contaminated systems • Remove Unit 1 clean systems • Decontaminate Unit 1 Reactor Building • Begin Unit 1 and Unit 2 structures decontamination	
4	DECON BALANCE OF SITE	29
	• Removal of Unit 2 contaminated systems • Remove Unit 2 clean systems • Decontaminate Unit 2 Reactor Building • Remove spent fuel racks • Decontaminate spent fuel storage building • Completion of Unit 1 and Unit 2 structures decontamination • Final site survey of reactor plant confirming satisfactory removal	
5	CLEAN STRUCTURES DEMOLITION	16
	• Demolition of decontaminated Unit 1 and Unit 2 structures	
6	RESTORATION OF PLANT SITE	2
	• Backfill, grading and landscaping of Unit 1 and Unit 2 sites	

In this scenario, decommissioning and site restoration will be complete approximately 97 months or 8 years after Unit 2 shutdown. Spent fuel will remain on-site indefinitely.

5.2 SCENARIO 2 - DECON WITH INDEFINITE OFF-SITE DRY STORAGE

This scenario includes Unit 1 shutdown on Oct 25, 2034 and Unit 2 on Dec 23, 2037. The transfer of spent fuel remaining in the spent fuel pool to the dry storage facility will begin in 2036. With the exception of the last core load of fuel assemblies, transfer of all remaining fuel to the ISFSI will be completed within five years after shutdown. The transfer of the last core load of 193 assemblies and a few remaining assemblies will occur immediately after the required five year cooling period. In addition, the spent fuel stored in the on-site ISFSI will be transferred to the off-site ISFSI. Spent fuel will remain at the off-site storage facility indefinitely.

In this scenario, it is assumed that all spent fuel will be transferred to an off-site dry storage facility. The Utility will be responsible for the initial cost of \$128.37/kgU covering shipping, storage casks and transportation as well as an annual cost of \$2.00/kgU. The canister will be transferred directly from the storage facility to a shipping cask and individual handling of the fuel assemblies will be avoided. While the Company is currently investigating PFS, the ultimate success of PFS is subject to on-going regulatory and other uncertainties.

There are seven sequential periods in this scenario as follows:

<u>Period</u>	<u>Description</u>	<u>Period Duration, Months</u>
1	BETWEEN SHUTDOWN OF UNIT 1 AND SHUTDOWN OF UNIT 2 • Planning for spent fuel pool modifications • Planning for cold and dark • Planning for primary systems flush • Select DGC • Planning for decommissioning	38
2	POST-SHUTDOWN ACTIVITIES • Transfer spent fuel from the existing ISFSI and/or spent fuel pool to the off-site ISFSI • Modification of spent fuel pool systems • Primary system decontamination flush • Flush and drain non-essential systems • Perform characterization survey • Implement cold and dark • Vessel and Internals removal preparations	12
3	REMOVAL OF MAJOR COMPONENTS • Transfer spent fuel from existing ISFSI and/or spent fuel pool to the off-site ISFSI • Removal of Unit 1 and Unit 2 reactor vessels and internals • Removal of Unit 1 and Unit 2 steam generators • Removal of Unit 1 contaminated systems • Remove Unit 1 clean systems • Decontaminate Unit 1 Reactor Building • Begin Unit 1 and Unit 2 structures decontamination	38
4	DECON BALANCE OF SITE • Removal of Unit 2 contaminated systems • Remove Unit 2 clean systems • Decontaminate Unit 2 Reactor Building • Remove spent fuel racks • Decontaminate spent fuel storage building • Completion of Unit 1 and Unit 2 structures decontamination • Final site survey of reactor plant confirming satisfactory removal	29
5	CLEAN STRUCTURES DEMOLITION • Demolition of decontaminated Unit 1 and Unit 2 structures	16

6 RESTORATION OF PLANT SITE

2

- Backfill, grading and landscaping of Unit 1 and Unit 2 sites

In this scenario, decommissioning and site restoration will be complete approximately 97 months or 8 years after Unit 2 shutdown. Spent fuel will remain at the off-site facility indefinitely.

5.3 SCENARIO 3 - DECON WITH ON-SITE DRY STORAGE, REPOSITORY OPEN IN 2032 & RECENT ACCEPTANCE RATE

This scenario includes Unit 1 shutdown on Oct 25, 2034 and Unit 2 on Dec 23, 2037, a spent fuel repository open in 2032 with the first assemblies leaving the D.C. Cook Plant in 2035. The existing ISFSI will be expanded to accommodate all spent fuel remaining on-site. The transfer of spent fuel remaining in the spent fuel pool to the dry storage facility will begin in 2036. With the exception of the last core load of fuel assemblies, transfer of all remaining fuel to the ISFSI will be completed within five years after shutdown. The transfer of the last core load of 193 assemblies and a few remaining assemblies will occur immediately after the required five year cooling period.

The spent fuel pool systems will be modified as in Scenario 1 to reduce the costs of operating and maintaining the spent fuel pool after plant shutdown. As soon as all spent fuel is transferred to dry storage, the balance of the D.C. Cook Plant will be decommissioned. All spent fuel will be stored on-site in Holtec's VCC and MPC system.

The eight sequential periods in this scenario and the major activities occurring in each are as follows:

<u>Period</u>	<u>Description</u>	<u>Period Duration, Months</u>
1	BETWEEN SHUTDOWN OF UNIT 1 AND SHUTDOWN OF UNIT 2 • Continue spent fuel shipments from pool to DOE • Planning for spent fuel pool modifications • Planning for cold and dark • Planning for primary systems flush • Select DGC • Planning for decommissioning	38
2	POST-SHUTDOWN ACTIVITIES • Continuation of spent fuel shipment from pool to DOE • Transfer spent fuel from pool to the ISFSI • Modification of spent fuel pool systems • Primary system decontamination flush • Flush and drain non-essential systems • Perform characterization survey • Implement cold and dark • Vessel and Internals removal preparations	12

3	REMOVAL OF MAJOR COMPONENTS	38
	• Continuation of spent fuel shipment from pool to DOE • Transfer spent fuel from pool to the ISFSI • Removal of Unit 1 and Unit 2 reactor vessels and internals • Removal of Unit 1 and Unit 2 steam generators • Removal of Unit 1 contaminated systems • Remove Unit 1 clean systems • Decontaminate Unit 1 Reactor Building • Begin Unit 1 and Unit 2 structures decontamination	
4	DECON BALANCE OF SITE	29
	• Continue spent fuel shipments from ISFSI to DOE • Removal of Unit 2 contaminated systems • Remove Unit 2 clean systems • Decontaminate Unit 2 Reactor Building • Remove spent fuel racks • Decontaminate spent fuel storage building • Completion of Unit 1 and Unit 2 structures decontamination • Final site survey of reactor plant confirming satisfactory removal	
5	CLEAN STRUCTURES DEMOLITION	16
	• Continue spent fuel shipments from ISFSI to DOE • Demolition of decontaminated Unit 1 and Unit 2 structures	
6	RESTORATION OF PLANT SITE	2
	• Continue spent fuel shipments from ISFSI to DOE • Backfill, grading and landscaping of Unit 1 and Unit 2 sites	
7	DRY STORAGE	438
	• Completion of spent fuel shipment from dry storage to DOE	
8	RESTORATION OF ISFSI SITE	3
	• Decontaminate ISFSI • Remove casks and pad	

In this scenario, there will be an extended period of time, approximately 36.5 years, following shutdown when the activities on site will consist mainly of the ISFSI, Period 7. Cask loading activities for off-site spent fuel shipments will also be occurring on a periodic basis. All spent fuel will be removed from site, decommissioning complete and the site restored to native vegetation by October, 2082, 538 months or 45 years after Unit 2 shutdown.

5.4 SCENARIO 4 – SAFSTOR WITH INDEFINITE ON-SITE DRY STORAGE

This scenario includes Unit 1 shutdown on Oct 25, 2034 and Unit 2 on Dec 23, 2037. The transfer of spent fuel remaining in the spent fuel pool to the dry storage facility will begin in 2036. The existing ISFSI will be expanded to accommodate all spent fuel remaining on-site. With the exception of the last core load of fuel assemblies, transfer of all remaining fuel to the ISFSI will be completed within five years after shutdown. The transfer of the last core load of 193 assemblies and a few remaining assemblies will occur immediately after the required five year cooling period. The site will remain as an Independent Spent Fuel Storage Installation indefinitely.

The spent fuel pool systems will be modified to reduce the costs of operating and maintaining the spent fuel pool after plant shutdown. As soon as all spent fuel is transferred to dry storage, the balance of the D.C. Cook Plant will be decommissioned. All spent fuel will be stored on-site in Holtec's VCC and MPC system.

The first 53 months of SAFSTOR dormancy will include both wet and dry storage of spent fuel. Once the spent fuel pool has been emptied, approximately 5 years and 5 months after Unit 2 shutdown dormancy preparations will be completed. There will then be a dormancy period of approximately 589 months with spent fuel remaining in the on-site in the ISFSI.

Decommissioning will not begin until approximately 54 years after Unit 2 shutdown. In accordance with the NRC's Final Rule on decommissioning all residual radioactivity will be removed within 60 years of shutdown.

The nine sequential periods in this scenario and the major activities occurring in each are as follows:

<u>Period</u>	<u>Description</u>	<u>Period Duration, Months</u>
1	BETWEEN SHUTDOWN OF UNIT 1 AND SHUTDOWN OF UNIT 2 • Planning for spent fuel pool modifications • Planning for primary systems flush • Select SAFSTOR contractor • Planning for dormancy	38
2	POST-SHUTDOWN ACTIVITIES • Modification of spent fuel pool systems • Primary system decontamination flush • Flush and drain non-essential systems • Perform characterization survey • Decontaminate and clean up plant areas	12
3	DORMANCY WITH WET & DRY SPENT FUEL STORAGE • Perform routine surveillance of the site	53

4	DORMANCY WITH DRY SPENT FUEL STORAGE	537
	• Perform routine surveillance of the site	
5	DECOMMISSIONING PLANNING DURING DORMANCY	53
	• Planning for cold and dark	
	• Select DGC	
	• Planning for decommissioning	
	• Perform characterization survey	
	• Implement cold and dark	
	• Vessel and Internals removal preparations	
6	REMOVAL OF MAJOR COMPONENTS	38
	• Removal of Unit 1 and Unit 2 reactor vessels and internals	
	• Removal of Unit 1 and Unit 2 steam generators	
	• Removal of Unit 1 contaminated systems	
	• Remove Unit 1 clean systems	
	• Decontaminate Unit 1 Reactor Building	
	• Begin Unit 1 and Unit 2 structures decontamination	
7	DECON BALANCE OF SITE	29
	• Removal of Unit 2 contaminated systems	
	• Remove Unit 2 clean systems	
	• Decontaminate Unit 2 Reactor Building	
	• Remove spent fuel racks	
	• Decontaminate spent fuel storage building	
	• Completion of Unit 1 and Unit 2 structures decontamination	
	• Final site survey of reactor plant confirming satisfactory removal	
8	CLEAN STRUCTURES DEMOLITION	16
	• Demolition of decontaminated Unit 1 and Unit 2 structures	
9	RESTORATION OF PLANT SITE	2
	• Backfill, grading and landscaping of Unit 1 and Unit 2 sites	

5.5 SCENARIO 5 - DECON WITH WET STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT ACCEPTANCE RATE

This scenario includes Unit 1 shutdown on Oct 25, 2034 and Unit 2 on Dec 23, 2037, a spent fuel repository open in 2032 with the first assemblies leaving the D.C. Cook Plant in 2035. The existing ISFSI will be maintained until all spent fuel pool has been removed from the spent fuel pool. Spent fuel shipments to the DOE facility will be from the spent fuel pool first. The pool will be empty in 2060 at which time shipments will be from the ISFSI. All spent fuel will be removed from site in 2082.

The spent fuel pool systems will be modified as in Scenario 1 to reduce the costs of operating and maintaining the spent fuel pool after plant shutdown. As soon as all spent fuel is transferred to dry storage, the balance of the D.C. Cook Plant will be decommissioned.

The 10 sequential periods in this scenario and the major activities occurring in each are as follows:

<u>Period</u>	<u>Description</u>	<u>Period Duration, Months</u>
1	BETWEEN SHUTDOWN OF UNIT 1 AND SHUTDOWN OF UNIT 2 - Continue spent fuel shipments from pool to DOE - Planning for spent fuel pool modifications - Planning for cold and dark - Planning for primary systems flush - Select DGC - Planning for decommissioning	38
2	POST-SHUTDOWN ACTIVITIES - Continuation of spent fuel shipment from pool to DOE - Transfer spent fuel from pool to the ISFSI - Modification of spent fuel pool systems - Primary system decontamination flush - Flush and drain non-essential systems - Perform characterization survey - Implement cold and dark - Vessel and Internals removal preparations	12
3	REMOVAL OF MAJOR COMPONENTS - Continuation of spent fuel shipment from pool to DOE - Transfer spent fuel from pool to the ISFSI - Removal of Unit 1 and Unit 2 reactor vessels and internals - Removal of Unit 1 and Unit 2 steam generators - Removal of Unit 1 contaminated systems - Remove Unit 1 clean systems - Decontaminate Unit 1 Reactor Building - Begin Unit 1 and Unit 2 structures decontamination	38
4	DECON BALANCE OF SITE - Continue spent fuel shipments from ISFSI to DOE - Removal of Unit 2 contaminated systems - Remove Unit 2 clean systems - Decontaminate Unit 2 Reactor Building - Remove spent fuel racks - Decontaminate spent fuel storage building	29

	• Completion of Unit 1 and Unit 2 structures decontamination • Final site survey of reactor plant confirming satisfactory removal	
5	CLEAN STRUCTURES DEMOLITION	16
	• Continue spent fuel shipments from pool to DOE • Demolition of decontaminated Unit 1 and Unit 2 structures	
6	RESTORATION OF PLANT SITE	2
	• Continue spent fuel shipments from pool to DOE • Backfill, grading and landscaping of Unit 1 and Unit 2 sites	
7	WET FUEL STORAGE	188
	• Continue on-site wet storage of spent fuel • Completion of spent fuel shipment from pool to DOE	
8	DECON SPENT FUEL STORAGE BUILDING	12
	• Complete spent fuel shipment from dry storage to DOE • Remove spent fuel racks • Decontaminate spent fuel storage building • Final survey of spent fuel storage building and remove	
9	DRY STORAGE	240
	• Completion of spent fuel shipment from dry storage to DOE	
10	RESTORATION OF ISFSI SITE	3
	• Decontaminate ISFSI • Remove casks and pad	

In this scenario, Period 7 reflects an extended period of time following shutdown, approximately 16 years, when the activities on site will consist mainly of the operation and maintenance of the skid mounted cooling systems required to support the spent fuel pool. Cask loading activities for off-site spent fuel shipments will also be occurring on a periodic basis. Once the spent fuel pool has been emptied and the building removed there will be a period of dry storage, approximately 20 years, with periodic shipments off-site, Period 9. All spent fuel will be removed from site, decommissioning is complete and the site is restored to native vegetation by October, 2082, 540 months or 45 years after Unit 2 shutdown.

6.0 SCHEDULES

A scenario-specific schedule has been developed for each of the ten decommissioning scenarios in this study. Each schedule is based on some combination of the following assumptions:

- DECON or SAFSTOR
- Spent fuel shipping start date
- Spent fuel shipping rate
- Wet storage, on-site dry storage or off-site dry storage

The first step in determining each schedule is assessment of the spent fuel disposition for each of the scenarios. These spent fuel disposition schedules will have a major influence on the overall schedule critical path. The spent fuel disposition analysis will then be combined with the decommissioning activities to determine the overall project schedule.

Activity durations are determined based on the unit cost factor approach. Once the plant material inventory has been determined specific unit rates for cost, man hours and schedule hours for a specific activity, such as surface decontamination, are applied to the inventory. From this calculation the removal or decontamination cost, total man hours and total schedule hours are determined for an activity. The schedule hours are then entered into the schedule to determine project duration. The schedule will be divided into multiple periods depending on the activities occurring during that time period. The separation into multiple periods allows for better control in determining the period dependent costs such as staffing, insurance and security.

The spent fuel disposition analysis for Unit 1 and Unit 2 are presented in Tables 6.1 through 6.5 for scenarios 1 through 5, respectively. Scenarios 3 and 5 incorporate a recent DOE acceptance rate for spent fuel to a repository and a shipping start date of 2032. Spent fuel will be complete in 2082 for these scenarios. Scenarios 1 and 4 assume an indefinite on-site storage period. Scenario 2 assumes an indefinite off-site storage period.

Detailed decommissioning schedules for the five scenarios studied, based upon these spent fuel transfer schedules and a critical path analysis of the decommissioning activities, are presented in Appendix A.

6.1 SCENARIO 1 -DECON WITH ON-SITE DRY STORAGE AND NO SPENT FUEL SHIPPING

Spent fuel is assumed to remain on-site in dry storage indefinitely. The schedule of spent fuel movements is reflected in Table 6.1. The detailed project schedule is present in Appendix A. The decommissioning schedule has been optimized within the limitations imposed by the spent fuel storage requirements. Program periods and durations for Scenario 1 are as follows:

<u>Period</u>	<u>Description</u>	<u>Duration, months</u>
1	U1 & U2 Decommissioning Planning Cost:	38
2	Post-Shutdown Activities Costs:	12

3	Vessel and Internals Removal Costs:	38
4	Decontaminate Balance of Site Costs:	29
5	Clean Structure Demolition Costs:	16
6	Restore Site Costs:	2
7	Dry Storage (Indefinitely)	

Decommissioning of the site will be complete in 2046, which is 97 months after the shutdown of Unit 2. Spent fuel will remain on site in dry storage indefinitely.

TABLE 6.1
SPENT FUEL SHIPPING SCHEDULE

Year	Unit 1 Fuel Discharged	Unit 2 Fuel Discharged	Total Assemblies & other items on Site	Assemblies to Dry Storage	Total Assemblies in Dry Storage	Pool Locations Occupied
2012			3355	448 ^{note 4}	448	2907
2013	89	104 ^{note 1}	3548	0	448	3100
2014	89	0	3637	0	448	3189
2015	0	104	3741	512	960	2781
2016	89	104	3934	0	960	2974
2017	89	0	4023	0	960	3063
2018	0	104	4127	512	1472	2655
2019	89	104	4320	0	1472	2848
2020	89	0	4409	0	1472	2937
2021	0	104	4513	320	1792	2721
2022	89	104	4706	0	1792	2914
2023	89	0	4795	0	1792	3003
2024	0	104	4899	320	2112	2787
2025	89	104	5092	0	2112	2980
2026	89	0	5181	0	2112	3069
2027	0	104	5285	320	2432	2853
2028	89	104	5478	0	2432	3046
2029	89	0	5567	0	2432	3135
2030	0	104	5671	320	2752	2919
2031	89	104	5864	0	2752	3112
2032	89	0	5953	0	2752	3201
2033	0	104	6057	320	3072	2985
2034	89	104	6250	0	3072	3178
2035	193	0	6443	0	3072	3371
2036		104	6547	320	3392	3155
2037		193	6740	384	3776	2964
2038			6740	512	4288	2452
2039		42 ^{note 2}	6782	512	4800	1982
2040		84	6866	704	5504	1362
2041		42	6908	704	6208	700
2042			6908	700	6908	0
2043			6908 ^{note 3}		6908	0

NOTES:

1. Discharge schedule presented in Dry Cask Storage Master Plan 2012.
2. 84 spent fuel baskets loaded with GTCC will be discharged into the spent fuel pool, from each unit, during internals removal.
3. Spent fuel will remain on-site indefinitely.
4. Assemblies to dry storage determined by AEP through, 2033. Assemblies to dry storage after Unit 1 shutdown determined by KCES
5. Max number of casks required: 216
6. Casks purchased after shutdown 120

6.2 SCENARIO 2 - DECON WITH INDEFINITE OFF-SITE DRY STORAGE

The spent fuel movements in and out of the pool are presented in Table 6.2. The detailed project schedule is present in Appendix A. The decommissioning schedule has been optimized within the limitations imposed by the spent fuel storage requirements. Program periods and durations for Scenario 9 are as follows:

<u>Period</u>	<u>Description</u>	<u>Duration, months</u>
1	U1 & U2 Decommissioning Planning Cost:	38
2	Post-Shutdown Activities Costs:	12
3	Vessel and Internals Removal Costs:	38
4	Decontaminate Balance of Site Costs:	29
5	Clean Structure Demolition Costs:	16
6	Restore Site Costs:	2
7	Off Site Dry Storage (Indefinitely)	

Decommissioning of the site will be complete in 2046, which is 97 months after the shutdown of Unit 2. Spent fuel will remain off-site in dry storage indefinitely.

TABLE 6.2
SPENT FUEL SHIPPING SCHEDULE

Year	Unit 1 Fuel Discharged	Unit 2 Fuel Discharged	Total Assemblies & other items on Site	Assemblies to Dry Storage	Total Assemblies in Dry Storage	Assemblies To Off-site Dry Storage from ISFSI	Assemblies To Off-site Dry Storage from pool	Number of Assemblies in Off-site Dry Storage
2012			3355	448 ^{note 4}	448			
2013	89	104 ^{note 1}	3548	0	448		0	0
2014	89	0	3637	0	448		0	0
2015	0	104	3741	512	960		0	0
2016	89	104	3934	0	960		0	0
2017	89	0	4023	0	960		0	0

2018	0	104	4127	512	1472		0	0
2019	89	104	4320	0	1472		0	0
2020	89	0	4409	0	1472		0	0
2021	0	104	4513	320	1792		0	0
2022	89	104	4706	0	1792		0	0
2023	89	0	4795	0	1792		0	0
2024	0	104	4899	320	2112		0	0
2025	89	104	5092	0	2112		0	0
2026	89	0	5181	0	2112		0	0
2027	0	104	5285	320	2432		0	0
2028	89	104	5478	0	2432		0	0
2029	89	0	5567	0	2432		0	0
2030	0	104	5671	320	2752		0	0
2031	89	104	5864	0	2752		0	0
2032	89	0	5953	0	2752		0	0
2033	0	104	6057	320	3072		0	0
2034	89	104	6250		3072		0	0
2035	193	0	6443		3072		0	0
2036		104	5779		2624	448	320	768
2037		193	5140		2176	448	384	1600
2038			4180		1728	448	512	2560
2039		42 ^{note 2}	3262		1280	448	512	3520
2040		84	2194		832	448	704	4672
2041		42	1084		384	448	704	5824
2042			0		0	384	700	6908
2043			0		0			6908 ^{note 3}

NOTES:

1. Discharge schedule presented in Dry Cask Storage Master Plan 2012.
2. 84 spent fuel baskets loaded with GTCC will be discharged into the spent fuel pool, from each unit, during internals removal.
3. Spent fuel will remain in off-site storage indefinitely.
4. Assemblies to dry storage determined by AEP through, 2033.
5. Max number of casks required: 96

6.3 SCENARIO 3 - DECON WITH ON-SITE DRY STORAGE, REPOSITORY OPEN IN 2032 & RECENT ACCEPTANCE RATE

The spent fuel movements in and out of the pool are presented in Table 6.3. The detailed project schedule is present in Appendix A. The decommissioning schedule has been optimized within the limitations imposed by the spent fuel storage requirements. Program periods and durations for Scenario 3 are as follows:

<u>Period</u>	<u>Description</u>	<u>Duration, months</u>
1	U1 & U2 Decommissioning Planning Cost:	38
2	Post-Shutdown Activities Costs:	12
3	Vessel and Internals Removal Costs:	38
4	Decontaminate Balance of Site Costs:	29
5	Clean Structure Demolition Costs:	16
6	Restore Site Costs:	2
7	Dry Storage	438
8	Decontaminate and Remove ISFSI	3

The total period of time that spent fuel will be in dry storage following the shutdown of Unit 2 will be 535 months or about 44.5 years. During this time spent fuel cooling will be performed by on-site dry storage.

Scenario 3 concludes in 2082, which is 538 months after the shutdown of Unit 2.

TABLE 6.3
SPENT FUEL SHIPPING SCHEDULE

Year	Unit 1 Fuel Discharged	Unit 2 Fuel Discharged	Assemblies To DOE	Total Assemblies & other items on Site	Assemblies to Dry Storage	Total Assemblies in Dry Storage	Locations Occupied
2012				3355	448 ^{note 5}	448	2907
2013	89	104 ^{note 1}		3548	0	448	3100
2014	89	0		3637	0	448	3189
2015	0	104		3741	512	960	2781
2016	89	104		3934	0	960	2974
2017	89	0		4023	0	960	3063
2018	0	104		4127	512	1472	2655
2019	89	104		4320	0	1472	2848
2020	89	0		4409	0	1472	2937
2021	0	104		4513	320	1792	2721
2022	89	104		4706	0	1792	2914
2023	89	0		4795	0	1792	3003
2024	0	104		4899	320	2112	2787
2025	89	104		5092	0	2112	2980
2026	89	0		5181	0	2112	3069
2027	0	104		5285	320	2432	2853
2028	89	104		5478	0	2432	3046
2029	89	0		5567	0	2432	3135
2030	0	104		5671	320	2752	2919
2031	89	104		5864	0	2752	3112
2032	89	0	0 ^{note 2}	5953	0	2752	3201
2033	0	104	0	6057	320	3072	2985
2034	89	104	0	6250	0	3072	3178
2035	193	0	127	6316	0	3072	3244
2036		104	294	6126	0	3072	3054
2037		193	275	6044	0	3072	2972

2038			274	5770	320	3392	2378
2039		42 ^{note 4}	80	5732	448	3640	1892
2040		84	152	5664	512	4352	1312
2041		42	166	5540	576	4928	612
2042			155	5385	457	5385	0
2043			80	5305	0	5305	0
2044			159	5146	0	5146	0
2045			82	5064	0	5064	0
2046			188	4876	0	4876	0
2047			0	4876	0	4876	0
2048			0	4876	0	4876	0
2049			166	4710	0	4710	0
2050			128 ^{note 3}	4582	0	4582	0
2051			160	4422	0	4422	0
2052			128	4294	0	4294	0
2053			160	4134	0	4134	0
2054			128	4006	0	4006	0
2055			160	3846	0	3846	0
2056			128	3718	0	3718	0
2057			160	3558	0	3558	0
2058			128	3430	0	3430	0
2059			160	3270	0	3270	0
2060			128	3142	0	3142	0
2061			160	2982	0	2982	0
2062			128	2854	0	2854	0
2063			160	2694	0	2694	0
2064			128	2566	0	2566	0
2065			160	2406	0	2406	0
2066			128	2278	0	2278	0
2067			160	2118	0	2118	0
2068			128	1990	0	1990	0
2069			160	1830	0	1830	0
2070			128	1702	0	1702	0
2071			160	1542	0	1542	0
2072			128	1414	0	1414	0
2073			160	1254	0	1254	0
2074			128	1126	0	1126	0
2075			160	966	0	966	0
2076			128	838	0	838	0
2077			160	678	0	678	0
2078			128	550	0	550	0
2079			160	390	0	390	0
2080			128	262	0	262	0
2081			160	102	0	102	0
2082			102	0	0	0	0

NOTES:

1. Discharge schedule presented in Dry Cask Storage Master Plan 2012.
2. Acceptance rate is based on the following assumptions: 400 MTUs shipped in year 1, 600 MTUs in year 2 & 1200 MTUs in year 3, 2000 MTUs in year 4 and 3000 MTUs from year 5 on. This acceptance rate plotted against the July 2004 Acceptance Priority Ranking, DOE/RW-0567
3. The average number of assemblies shipped in years 5 - 18 is 148. Since all spent fuel in dry storage, shipments will be in multiples of 32, alternating 128 and 160 per year.
4. 84 spent fuel baskets loaded with GTCC will be discharged into the spent fuel pool, from each unit, during internals removal.
5. Assemblies to dry storage determined by AEP through, 2033. Assemblies to dry storage after Unit 1 shutdown determined by KCES.
6. Max number of casks required: 168
7. Casks purchased after shutdown 72

6.4 SCENARIO 4 – SAFSTOR WITH INDEFINITE ON-SITE DRY STORAGE

This scenario assumes license termination within 60 years of Unit 2 shut down, on-site dry spent fuel storage and delayed decommissioning. Spent fuel will be stored in the spent fuel pool with modified systems for the first five years after shutdown. The spent fuel movements in and out of the pool and to the DOE facility are the same as those presented in Table 6.1. The decommissioning schedule is presented in Appendix A.

There are two dormancy only periods in this scenario, one with fuel on-site in the spent fuel pool, 53 months and one with spent fuel in dry storage, 537 months.

Program periods and durations for Scenario 3 are as follows:

<u>Period</u>	<u>Description</u>	<u>Duration, months</u>
1	U1 & U2 Decommissioning Planning Cost:	38
2	Post-Shutdown Activities Costs:	12
3	Dormancy with Wet & Dry Spent Fuel Storage:	53
4	Dormancy with Dry Spent Fuel Storage:	537
5	Dormancy with Decommissioning Planning Cost:	53
6	Vessel and Internals Removal Costs:	38
7	Decontaminate Balance of Site Costs:	29
8	Clean Structure Demolition Costs:	16
9	Restore Site Costs:	2
10	Dry Storage (Indefinitely)	

Spent fuel will remain on-site indefinitely following the shutdown of Unit 2.

Scenario 4 decommissioning will conclude in 2099 which is 740 months

6.5 SCENARIO 5 – DECON WITH WET STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE

The spent fuel movements in and out of the pool are presented in Table 6.4. The detailed project schedule is present in Appendix A. The decommissioning schedule has been optimized within the limitations imposed by the spent fuel storage requirements. Program periods and durations for Scenario 1 are as follows:

<u>Period</u>	<u>Description</u>	<u>Duration, months</u>
1	U1 & U2 Decommissioning Planning Cost:	38
2	Post-Shutdown Activities Costs:	12
3	Vessel and Internals Removal Costs:	38
4	Decontaminate Balance of Site Costs:	27
5	Clean Structure Demolition Costs:	16
6	Restore Site Costs:	2
7	Wet & Dry Storage Costs:	188
8	Auxiliary Building Removal Costs:	12
9	Dry Storage	240
10	Decontaminate and Remove ISFSI	3

The total period that spent fuel will be on-site in the pool following the shutdown of Unit 2 will be 283 months or about 23.5 years. Spent fuel will continue to be transferred from dry storage for another 252 months or 21 years. During wet storage the modified systems required to support the spent fuel storage pool will be operated and maintained.

Scenario 4 concludes in 2082, which is 538 months after the shutdown of Unit 2.

TABLE 6.4
SPENT FUEL SHIPPING SCHEDULE

Year	Unit 1 Fuel Discharged	Unit 2 Fuel Discharged	Assemblies To DOE	Total Assemblies & other items on Site	Assemblies to Dry Storage	Total Assemblies in Dry Storage	Assemblies in Pool
2012				3355	448	2907	2907
2013	89	104 ^{note 1}		3548	0	448	3100
2014	89	0		3637	0	448	3189
2015	0	104		3741	512	960	2781
2016	89	104		3934	0	960	2974
2017	89	0		4023	0	960	3063
2018	0	104		4127	512	1472	2655
2019	89	104		4320	0	1472	2848
2020	89	0		4409	0	1472	2937
2021	0	104		4513	320	1792	2721
2022	89	104		4706	0	1792	2914
2023	89	0		4795	0	1792	3003
2024	0	104		4899	320	2112	2787

2025	89	104		5092	0	2112	2980
2026	89	0		5181	0	2112	3069
2027	0	104		5285	320	2432	2853
2028	89	104		5478	0	2432	3046
2029	89	0		5567	0	2432	3135
2030	0	104		5671	320	2752	2919
2031	89	104		5864	0	2752	3112
2032	89	0	0 note 2	5953	0	2752	3201
2033	0	104	0	6057	320	3072	2985
2034	89	104	0	6250	0	3072	3178
2035	193	0	127	6316	0	3072	3244
2036		104	294	6126	0	3072	3054
2037		193	275	6044	0	3072	2972
2038			274	5770	0	3072	2698
2039		42 note 4	80	5732	0	3072	2660
2040		84	152	5664	0	3072	2592
2041		42	166	5540	0	3072	2468
2042			155	5385	0	3072	2313
2043			80	5305	0	3072	2233
2044			159	5146	0	3072	2074
2045			82	5064	0	3072	1992
2046			188	4876	0	3072	1804
2047			0	4876	0	3072	1804
2048			0	4876	0	3072	1804
2049			166	4710	0	3072	1638
2050			128 note 3	4582	0	3072	1510
2051			160	4422	0	3072	1350
2052			128	4294	0	3072	1222
2053			160	4134	0	3072	1062
2054			128	4006	0	3072	934
2055			160	3846	0	3072	774
2056			128	3718	0	3072	646
2057			160	3558	0	3072	486
2058			128	3430	0	3072	358
2059			160	3270	0	3072	198
2060			128	3142	0	3072	70
2061			160	2982	0	2982	0
2062			128	2854	0	2854	0
2063			160	2694	0	2694	0
2064			128	2566	0	2566	0
2065			160	2406	0	2406	0
2066			128	2278	0	2278	0
2067			160	2118	0	2118	0
2068			128	1990	0	1990	0
2069			160	1830	0	1830	0
2070			128	1702	0	1702	0
2071			160	1542	0	1542	0
2072			128	1414	0	1414	0

2073			160	1254	0	1254	0
2074			128	1126	0	1126	0
2075			160	966	0	966	0
2076			128	838	0	838	0
2077			160	678	0	678	0
2078			128	550	0	550	0
2079			160	390	0	390	0
2080			128	262	0	262	0
2081			160	102	0	102	0
2082			102	0	0	0	0

NOTES:

1. Discharge schedule presented in Dry Cask Storage Master Plan 2012.
2. Acceptance rate is based on the following assumptions: 400 MTUs shipped in year 1, 600 MTUs in year 2 & 1200 MTUs in year 3, 2000 MTUs in year 4 and 3000 MTUs from year 5 on. This acceptance rate plotted against the July 2004 Acceptance Priority Ranking, DOE/RW-0567
3. The average number of assemblies shipped in years 5 - 18 is 148. Since all spent fuel in dry storage, shipments will be in multiples of 32, alternating 128 and 160 per year.
4. 84 spent fuel baskets loaded with GTCC will be discharged into the spent fuel pool, from each unit, during internals removal.
5. Max number of casks required: 96

7.0 PROJECT MANAGEMENT

There are three components to project management during decommissioning, Utility Staff (staff), Decommissioning General Contractor Staff (DGC) and Security. Each of these is further broken down into that required for decommissioning and that required for spent fuel storage. The person levels for each are specific to each scenario and decommissioning period.

7.1 UTILITY STAFF

The staff size at Unit 1 shutdown is assumed to be the same size and composition as it was in the spring of 2012. Immediately after Unit 1 shutdown, the staff is reduced approximately 33%, with the majority of the remaining staff attributed to the operation of Unit 2. Upon shutdown of Unit 2 this staff is reduced to the level required for decommissioning operations and spent fuel storage. All severed employees will receive a severance package based on the existing severance policy.

There are two components to the staff, decommissioning and spent fuel storage. The majority of the staff during the early part of the decommissioning process will be attributed to decommissioning. During the DECON scenarios, a staff level of 11.5 full time employees (FTE) will be required during period 1, between Unit 1 and Unit 2 shutdown. Upon shutdown of Unit 2, period 2, approximately 145 FTEs will be required to prepare the site for decommissioning, including the spent fuel pool, security and control room modifications. Once these modifications have been made the staff will be reduced to 96 FTEs to support the reactor internals and reactor vessel removal, period 3. The staff will be further reduced to 78 FTEs, 7 FTEs and 3 FTEs for period 4 site decontamination, period 5 structures removal and period 6 site restorations, respectively. These values represent the dry storage scenarios, there may be some variation in these values between the wet and dry storage due to sharing of upper management with spent fuel storage activities. Details are provided below. Additionally, a staff of 23.75 FTEs will be required for the decontamination and removal of the spent fuel pool and Auxiliary Building, period 8 of the wet storage scenario; after all spent fuel has been removed.

During the SAFSTOR scenario the decommissioning staff levels will be the same as DECON for periods 1 and 2. For this scenario there is no decommissioning staff required during Dormancy, with or without spent fuel. For SAFSTOR, there will be a decommissioning staff of 49.5 FTE during period 5 decommissioning planning. This staff will be increased to 99 FTEs during period 6 reactor internals and reactor vessel removal. The staff will be reduced to 79 FTEs, 10 FTEs and 5 FTEs for period 7 site decontamination, period 8 structures removal and period 9 site restorations, respectively.

During the decommissioning process there is a need to manage the safe operations of the spent fuel storage facilities, whether spent fuel is in wet storage or dry storage. The Utility staff will maintain responsibility for these actions. In all scenarios spent fuel will remain in the spent fuel pool for a minimum of five years, longer in the wet storage scenario. Also, in all scenarios there will be an existing ISFSI, required during operations to maintain full core off load capabilities. As such, there are two on-site spent fuel storage scenarios, wet and dry storage in operations at the same time and dry storage only. During the wet and dry storage periods the Utility staff will

be 33 FTEs and during dry storage only the Utility staff will consist of 14.25 FTEs. There will be some fluctuation in these staffs due to sharing of upper management personnel with the decommissioning staff. A staff of 10 FTEs is attributed to spent fuel storage during the ISFSI removal.

7.2 DECOMMISSIONING GENERAL CONTRACTOR

The DGC is assumed to have no role in the post shutdown management of the spent fuel storage facility. For all scenarios, upon selection of a DGC or Dormancy preparation contractor, the contractor will begin to mobilize on site. A DGC staff of 27 FTEs is assumed to be on site during the last 12 months of period 1, between Unit 1 and Unit 2 shutdown. For the DECON scenarios a DGC staff of 76 FTEs will be on site to prepare for decommissioning during period 2 site preparations. The DGC staff will be increased to 89 FTEs to support the reactor internals and reactor vessel removal, period 3. The DGC staff will be reduced to 76 FTEs, 34 FTEs and 15 FTEs for period 4 site decontamination, period 5 structures removal and period 6 site restorations, respectively. For wet storage scenario, a DGC staff of 40 FTEs will be required for the decontamination and removal of the spent fuel pool and Auxiliary Building, period 8, after all spent fuel has been removed. This DGC staff will begin to arrive on site during the final six months of period 7.

During the SAFSTOR scenario, the DGC staff levels will be the same as DECON for period 1. The DGC staff will remain at this level, 27 FTEs for the entire dormancy preparation period, period 2. For SAFSTOR, there will be a DGC staff of 89 FTEs during period 7 reactor internals and reactor vessel removal. The DGC staff will be reduced to 76 FTEs, 34 FTEs and 15 FTEs for period 8 site decontamination, period 9 structures removal and period 10 site restorations, respectively.

7.3 SECURITY

There are two components to the security staff, decommissioning and spent fuel storage. The majority of the security staff during the early part of the decommissioning process will be attributed to decommissioning. During the DECON scenarios, a security staff level of 3.5 full time employees (FTE) will be required during period 1, between Unit 1 and Unit 2 shutdown. Upon shutdown of Unit 2, period 2, approximately 60 FTEs will be required during preparations for decommissioning. Once modifications have been made to the spent fuel pool, security and control room the security staff will be reduced to 28 FTEs to support the reactor internals and reactor vessel removal, period 3 and site decontamination, period 4. The staff will be further reduced to 6 FTEs and 2 FTEs for period 5 structures removal and period 6 site restorations, respectively. For wet storage scenario, a security staff of 18 FTEs will be required for the decontamination and removal of the spent fuel pool and Auxiliary Building, period 8, after all spent fuel has been removed.

During the SAFSTOR scenario, the security staff levels will be the same as DECON for periods 1 and 2. For both of these scenarios there is a security staff of six attributed to decommissioning during all Dormancy periods. For SAFSTOR, there will be a security staff of 28 FTE during period 7 reactor internals and reactor vessel removal and site decontamination, period 8. The

security staff will be reduced to 7 FTEs and 3 FTEs for period 9 structures removal and period 10 site restorations, respectively.

During the decommissioning process there will be a need to manage the safe operations of the spent fuel storage facilities, whether spent fuel is in wet storage or dry storage. A dedicated security staff will be assigned to both the wet and dry storage facility. In all scenarios spent fuel will remain in the spent fuel pool for a minimum of five years, longer in the wet storage scenario. Also, in all scenarios there will be an existing ISFSI, required during operations to maintain full core off load capabilities. As such, there are two on-site spent fuel storage scenarios, wet and dry storage in operations at the same time and dry storage only. During the wet and dry storage periods the security staff will be 21 FTEs and during dry storage only the security staff will consist of 12 FTEs. A security staff of 6 FTEs is attributed to spent fuel storage during the ISFSI removal.

The following is a summary of the utility staff, DGC and security staff levels required for each scenario.

7.4 SCENARIO 1 - DECON WITH INDEFINITE DRY STORAGE

Table 7.1 summarizes the staff level for Decommissioning and Table 7.2 summarizes the staff levels for spent fuel storage as defined above, by period.

TABLE 7-1 DECOMMISSIONING STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>	<u>7</u>
Health Physics	2.25	29	24	24	0	0	0
Engineering	1.25	20	11	10	2	1	0
Maintenance Services	2.75	19	5	5	3	0	0
Operations	0.75	38	14	5	0	0	0
Projects	3.25	13	29	22	0	0	0
Administration	<u>1.25</u>	<u>26</u>	<u>13</u>	<u>12</u>	<u>2</u>	<u>2</u>	<u>0</u>
	11.5	145	96	78	7	3	0
DGC	27	76	89	76	34	15	
Security Guards	3.5	60	28	28	6	2	

TABLE 7-2 SPENT FUEL STORAGE STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>	<u>7</u>
Health Physics	0	5	5	1.25	1.25	1.25	1.25
Engineering	0	1	1	0	0	0	0
Maintenance Services	0	5	5	2	2	2	2
Operations	0	13	13	5	5	5	5
Projects	0	0	0	2	2	2	2

Administration	<u>0</u>	<u>9</u>	<u>9</u>	<u>4</u>	<u>4</u>	<u>4</u>	<u>4</u>
	0	33	33	14.25	14.25	14.25	14.25
DGC	0	0	0	0	0	0	0
Security Guards	0	21	21	12	12	12	12

7.5 SCENARIO 2 - DECON WITH INDEFINITE OFF-SITE DRY STORAGE

Table 7.3 summarizes the staff level for Decommissioning and Table 7.4 summarizes the staff levels for spent fuel storage as defined above, by period.

TABLE 7-3 DECOMMISSIONING STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>
Health Physics	2.25	29	24	24	0	0
Engineering	1.25	20	11	10	2	1
Maintenance Services	2.75	19	5	5	3	0
Operations	0.75	38	14	5	0	0
Projects	3.25	13	29	22	0	0
Administration	<u>1.25</u>	<u>26</u>	<u>13</u>	<u>12</u>	<u>2</u>	<u>2</u>
	11.5	145	96	78	7	3
DGC	27	76	89	76	34	15
Security Guards	3.5	60	28	28	6	2

TABLE 7-4 SPENT FUEL STORAGE STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>
Health Physics	0	5	5	5	0	0
Engineering	0	1	1	1	0	0
Maintenance Services	0	5	5	5	0	0
Operations	0	13	13	13	0	0
Projects	0	0	0	0	0	0
Administration	<u>0</u>	<u>9</u>	<u>9</u>	<u>9</u>	<u>0</u>	<u>0</u>
	0	33	33	33	0	0
DGC	0	0	0	0	0	0
Security Guards	0	21	21	21	0	0

7.6 SCENARIO 3 - DECON WITH ON-SITE DRY STORAGE, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE

Table 7.5 summarizes the staff level for Decommissioning and Table 7.6 summarizes the staff levels for spent fuel storage as defined above, by period.

TABLE 7-5 DECOMMISSIONING STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>
Health Physics	2.25	29	24	24	0	0
Engineering	1.25	20	11	10	2	1
Maintenance Services	2.75	19	5	5	3	0
Operations	0.75	38	14	5	0	0
Projects	3.25	13	29	22	0	0
Administration	<u>1.25</u>	<u>26</u>	<u>13</u>	<u>12</u>	<u>2</u>	<u>2</u>
	11.5	145	96	78	7	3
DGC	27	76	89	76	34	15
Security Guards	3.5	60	28	28	6	2

TABLE 7-6 SPENT FUEL STORAGE STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>	<u>7</u>	<u>8</u>
Health Physics	0	5	5	1.25	1.25	1.25	1.25	0
Engineering	0	1	1	0	0	0	0	2
Maintenance Services	0	5	5	2	2	2	2	0
Operations	0	13	13	5	5	5	5	0
Projects	0	0	0	2	2	2	2	4
Administration	<u>0</u>	<u>9</u>	<u>9</u>	<u>4</u>	<u>4</u>	<u>4</u>	<u>4</u>	<u>4</u>
	0	33	33	14.25	14.25	14.25	14.25	10
DGC	0	0	0	0	0	0	0	11
Security Guards	0	21	21	12	12	12	12	6

7.7 SCENARIO 4 – SAFSTOR WITH INDEFINITE ON-SITE DRY STORAGE

Table 7.7 summarizes the staff level for Decommissioning and Table 7.8 summarizes the staff levels for spent fuel storage as defined above, by period.

TABLE 7-7 DECOMMISSIONING STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>	<u>7</u>	<u>8</u>	<u>9</u>
Health Physics	2.25	29	0	0	12	24	24	0	0
Engineering	1.25	20	0	0	5.5	11	10	1	1
Maintenance Services	2.75	19	0	0	2.5	5	5	4	0
Operations	0.75	38	0	0	7.5	15	6	0	0
Projects	3.25	13	0	0	14.5	29	22	0	0
Administration	<u>1.25</u>	<u>26</u>	<u>0</u>	<u>0</u>	<u>7.5</u>	<u>15</u>	<u>12</u>	<u>5</u>	<u>4</u>
	11.5	145	0	0	49.5	99	79	10	5

DGC	27	27	0	0	0	89	76	34	15
Security Guards	3.5	60	6	6	6	28	28	7	3

TABLE 7-8 SPENT FUEL STORAGE STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>	<u>7</u>	<u>8</u>	<u>9</u>	<u>10</u>
Health Physics	0	5	5	1.25	1.25	1.25	1.25	1.25	1.25	1.25
Engineering	0	1	1	0	0	0	0	0	0	0
Maintenance Services	0	5	5	2	2	2	2	2	2	2
Operations	0	13	13	5	5	5	5	5	5	5
Projects	0	0	0	2	2	2	2	2	2	2
Administration	<u>0</u>	<u>9</u>	<u>9</u>	<u>4</u>	<u>4</u>	<u>4</u>	<u>4</u>	<u>4</u>	<u>4</u>	<u>4</u>
	0	33	33	14.25	14.25	14.25	14.25	14.25	14.25	14.25
DGC	0	0	0	0	0	0	0	0	0	0
Security Guards	0	21	21	12	12	12	12	12	12	12

7.8 SCENARIO 5 - DECON WITH ON-SITE WET STORAGE, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE

Table 7.9 summarizes the staff level for Decommissioning. Table 7.10 summarizes the staff levels for spent fuel storage as defined above, by period.

TABLE 7-9 DECOMMISSIONING STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>	<u>7</u>	<u>8</u>
Health Physics	2.25	29	24	24	0	0	0	6.75
Engineering	1.25	20	11	10	2	1	0	2
Maintenance Services	2.75	19	5	5	3	0	0	2
Operations	0.75	38	14	5	0	0	0	8
Projects	3.25	13	29	22	0	0	0	0
Administration	<u>1.25</u>	<u>26</u>	<u>13</u>	<u>9</u>	<u>1</u>	<u>1</u>	<u>0</u>	<u>5</u>
	11.5	145	96	75	6	2	0	23.75
DGC	27	76	89	76	34	15	13.5	40
Security Guards	3.5	60	28	28	6	2	0	18

TABLE 7-10 SPENT FUEL STORAGE STAFF SUMMARY

<u>Position:</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>	<u>7</u>	<u>8</u>	<u>9</u>	<u>10</u>
Health Physics	0	5	5	5	5	5	5	1.25	1.25	0
Engineering	0	1	1	1	1	1	1	0	0	2
Maintenance Services	0	5	5	5	5	5	5	2	2	0
Operations	0	13	13	13	13	13	13	5	5	0
Projects	0	0	0	0	0	0	0	2	2	4
Administration	<u>0</u>	<u>9</u>	<u>9</u>	<u>9</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>3</u>	<u>4</u>	<u>4</u>
	0	33	33	33	34	34	34	13.25	14.25	10
DGC	0	0	0	0	0	0	0	0	0	0
Security Guards	0	21	21	21	21	21	21	12	12	6

8.0 WASTE DISPOSAL

8.1 LOW LEVEL WASTE DISPOSAL BACKGROUND

The Low-Level Waste Policy Act (LLWPA), passed by Congress in 1980 and the Low-Level Waste Policy Amendments Act of 1985 encouraged states to form compacts for the disposal of low-level radioactive waste. The Acts made each state responsible for disposing of their own radioactive waste. The formation of compacts allowed states to limit their disposal facility to compact members thereby limiting the amount of waste accepted. On the other hand, the Acts also required that states not participating in the process would be required to take title to waste generated within that state. This provision was overturned by the U. S. Supreme Court in 1992 thus eliminating the need for states to develop their own disposal facility, including those already in a compact. The compact process has been anything but successful; to date there has been just one new disposal facility licensed to accept all low level radioactive waste, including Class A, B & C.

There are currently three facilities licensed to accept all low level radioactive waste: the Barnwell, South Carolina facility operated by EnergySolutions, LLC; the Waste Control Specialists, LLC (WCS) facility in Andrews, TX and the Hanford, Washington facility operated by U. S. Ecology. There is one other site in Clive, Utah owned and operated by EnergySolutions, LLC; however, this facility is currently licensed to accept only Class A radioactive waste. As of July 1, 2008 the Barnwell facility will only accept waste from the Atlantic Compact states. The Atlantic Compact member states include South Carolina, Connecticut and New Jersey. The Hanford facility only accepts waste from the Northwest Compact and the Rocky Mountain Compact; this has been the case since 1993. The Northwest Compact and Rocky Mountain Compact member states include Alaska, Colorado, Hawaii, Idaho, Montana, Nevada, New Mexico, Oregon, Utah, Washington and Wyoming. While the WCS facility is the compact disposal facility for Texas and Vermont it will accept waste from out of compact. WCS is licensed to accept Class A, B and C radioactive waste, as such this estimate assumes that Class B & C waste will be disposed of at this facility with the costs based on the current rate structure for out of compact waste.

8.2 CLASS A WASTE DISPOSAL

There are currently multiple options for the disposition of Class A waste. These include metal melt, direct burial and waste processing. Table 8-1 provides a summary of waste disposition options for class A waste and their unit rates considered in this estimate. KCES assumes that each waste stream will be transported to the least cost option for which it qualifies. Packaging and transportation costs have been calculated based on these specific locations.

Table 8-1
Class A Waste Disposal Options

<u>Description</u>	<u>Disposal Cost, \$/cu. ft.</u>
ENERGYSOLUTIONS disposal	\$158.54 per cubic foot
ENERGYSOLUTIONS METAL MELT	\$2.10 per pound
WCS disposal	\$208.79 per cubic foot
Studsvik processing	\$0.13 per pound

KCES assumed that the reactor building internal floors and walls will be removed in bulk and sent for processing at the Studsvik facility in Memphis TN. This approach will produce a large volume of waste compared to the traditional decontamination, survey and release methodology but at a lower rate. In addition, the approach will reduce the amount of characterization and iterative decontamination. Other contaminated structures will follow the decontamination, survey and release approach due to the smaller areas of potentially contaminated surfaces.

8.3 CLASS B & C WASTE

As discussed above, the WCS facility is licensed to accept Class B and C waste. This study assumes that all Class B & C waste will be disposed of at WCS. There is currently only a published fee and surcharge structure for in compact generators. Based on guidance from WCS personnel, increasing the published fees and surcharges by 20% would be representative the rates that would be charged to out of compact generators. The base disposal rate, including the 20% is \$208.79/cubic foot.

Additionally, there is a dose rate surcharge and a millicurie charge that must be added. The basic millicurie charge is \$0.55 per millicurie up to \$220,000 per shipment. There is also a weight surcharge, up to \$20,000 per shipment; a dose rate surcharge, up to \$400 per cu. ft.; an irradiated hardware there is an additional surcharge of \$75,000 per shipment and a cask handling surcharge of \$2,500 per cask. Finally there are State and County fees of 5% each. This estimate includes all applicable surcharges and fees.

8.4 DISPOSAL OF WASTES GREATER THAN CLASS C

While waste identified as Class A, B and C, according to 10 CFR 61, may be disposed of at a near-surface disposal facility, certain components may exceed the radionuclide concentration limitations for 10 CFR 61 Class C waste. These components cannot be disposed in a near-surface radioactive waste disposal facility based on 10 CFR 61 definitions. They will have to be transferred to a geologic repository or a similar site approved by the NRC.

The KCES site-specific classification of radioactive wastes for the D.C. Cook Plant identified that the Spent Fuel Assemblies and two components within each reactor vessel (the Core Baffle and the Lower Core Grid Plate) will exceed Class C limitations. Like the spent fuel assemblies, the reactor vessel components will be stored with the spent fuel either in wet or dry storage. Here they will wait for transportation to a DOE geologic disposal facility for disposal. The costs

for disposing of these components was estimated based upon the maximum curie surcharges currently in effect at the WCS disposal facility. Prior to placing in storage with the spent fuel, these components will be segmented and the pieces placed into spent fuel sized containers, it is estimated that 168 containers will be generated from the two units.

8.5 RADIOACTIVE WASTE VOLUMES PER 10 CFR 61 CLASSIFICATIONS

KCES has determined the classifications of radioactive wastes resulting from decommissioning the D.C. Cook Plant. The radioactive waste associated with each decommissioning activity is based upon the site-specific decommissioning calculations prepared for this cost estimate. The total volumes of 10 CFR 61 wastes for Units 1 and 2 are presented in Table 8.2. These volumes represent waste volumes generated at the site, for both units.

Table 8-2
10 CFR 61 Radioactive Waste Volumes (cubic feet)

Class A	3,374,145
Class B	5,480
Class C	2,340
Greater Than Class C	<u>1,411</u>
Total:	3,383,376

8.6 PROJECTION OF NON-RADIOACTIVE WASTE QUANTITIES

KCES has included the cost for disposal of all non-contaminated waste at a local landfill. As seen in the Maine Yankee decommissioning, on-site use of concrete rubble to fill below grade voids can be problematic. Maine Yankee originally intended to utilize remediated concrete to fill below grade voids. Many felt that this would essentially be considered on-site disposal of radioactive material since the concrete, although below the limits specified in the License Termination Plan (LTP), might still be slightly radioactive. Maine Yankee decided to eliminate potential legacy waste by transporting and disposing of this material in a licensed landfill. For this reason KCES has assumed that all non-contaminated waste, including pipe and components will be disposed of in a licensed landfill at a rate of \$0.045 per pound. Table 8-3 presents the total volumes of non-contaminated waste resulting from the decommissioning program.

Table 8-3
Non-Contaminated Waste (pounds)

Structures	517,810,100
Systems	50,960,230

9.0 COST SUMMARIES

9.1. ESTIMATING APPROACH

The estimating methodology utilized in the development of the cost estimates for the various scenarios in this study is consistent with that presented in both *Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates*, AIF/NESP-036, May 1986 and *Revised Analysis of Decommissioning for the Reference Pressurized Water Reactor Power Station*, NUREG/CR-5884, PNL-8742, November, 1995. Specifically the estimating methodology used by KCES herein is based on the Unit Cost Factor (UCF) approach. In addition, current experience from recently completed decommissioning projects has been considered in developing the estimating methodology.

KCES has developed a database of unit cost factors specific to the work activities associated with decommissioning a nuclear power reactor such as the cutting of a section of six inch contaminated pipe. These UCFs define the duration of an activity on a unit basis, including for the example above, contamination control set-up, cutting, capping pipe ends, removal from area, removal of contamination control and productivity adjustment factors. From the durations, removal costs are determined, including associated consumable costs. Material waste volumes, man-hours, disposal costs, packaging costs and transportation costs are also determined, again on a unit basis for each UCF. Each UCF is adjusted based on site specific factors such as labor rates, transportation costs and disposal rates.

The first step in developing the site specific activity removal and disposal cost is to develop a site specific plant inventory. KCES used the system and structures inventories developed for the previous estimates, incorporating any changes or modifications identified by the company. These quantities were originally determined by reviewing plant system inventory records, drawings, construction records and visiting the plant site. The plant system inventory list was separated into contaminated and non-contaminated components and unique unit cost factors were developed for each radiological condition. The site specific material quantities are then multiplied by the appropriate UCF to determine the total activity cost and removal man-hours.

The decommissioning activities are inserted into a project schedule and sequenced based on order of performance. The schedule hours, as determined by the UCFs for each activity are then incorporated in the project schedule to determine the critical path of the project. The schedule is then divided into several periods. Each period is defined by an activity or group of activities requiring a specific amount of oversight or support. For instance during the vessel internals and reactor vessel removal activities both the Utility staff, DGC staff and security staff are required to be maintained at a certain level. Once these activities are complete the levels may change based on the controlling activities.

Period dependent costs are those costs that are not specific to the decommissioning activities but are required as support. Costs such as those for the Utility staff, DGC staff, security staff, insurance, health physics supplies and energy are calculated on a monthly basis based on the major activities defining a given period. Many of the monthly costs are the same from scenario to scenario for similar periods. These monthly costs are then multiplied by the duration of the

respective period to determine period dependent costs. The activity and period dependent costs are then summed to determine total decommissioning costs.

These activity and period dependent costs are either spent fuel storage related (10 CFR 50.54(bb)), decommissioning related (10 CFR 50.75(c)), greenfield (g) or a combination of the three. KCES has separated costs in each of these categories during the estimating process.

Detailed decommissioning cost tables for the five scenarios are presented in Appendix B and are summarized below. All costs are presented in 2012 dollars. The summarized costs include contingency.

9.2 SCENARIO 1 - DECON WITH INDEFINITE ON-SITE DRY STORAGE

The total cost for this scenario is **\$1,321.4** million fixed and **\$4.5** million annual, as shown in Table 9.1. A total of \$386.2 million fixed is attributed to the preparation and transfer of spent fuel to the ISFSI. An annual cost of \$4.5 million will be incurred for the continuing maintenance and surveillance of the ISFSI. A total of \$793.2 million is attributed to the decommissioning, and \$142.0 million for greenfield. For this scenario, there is a large fixed cost required for the design, license, cask procurement, and construction and installation of the dry storage facility. There are also annual surveillance costs, NRC license fees and NRC inspection fees. The cost attributed to the operation and maintenance of the spent fuel pool has been optimized by minimizing the spent fuel support systems.

An ISFSI will have been constructed during operations in order to maintain full core offload capabilities in the spent fuel pool. The existing facility will be expanded shortly after Unit 1 shutdown to accommodate the long term storage of spent fuel. The transfer of the spent fuel assemblies remaining in the spent fuel pool at shutdown, to the ISFSI, will begin just after Unit 2 shutdown. This transfer will proceed at a rate sufficient to allow the spent fuel pool to be empty approximately 5.5 years after Unit 2 shutdown. The maximum number of spent fuel assemblies stored at the ISFSI at any time will be approximately 6,740 requiring 210 storage casks, 96 of which will have been purchased to maintain full core offload capability and are an operations expense. In addition to the spent fuel, 168 spent fuel size containers loaded with GTCC will be stored at the ISFSI, requiring an additional six casks.

The existing ISFSI and infrastructure will have to be expanded to accommodate the post shutdown transfer of spent fuel. The additional pad and infrastructure will cost approximately \$25.1 million, before contingency. It is assumed that the Holtec vertical storage system will be utilized in the ISFSI at a cost of \$1,929,750 per 32 assembly PWR canister and overpack, including welding services. All casks purchased during operations to maintain full core offload capability are considered an operations expense. A total of 120 casks will be purchased after Unit 2 shutdown at a cost of \$231.6 million, before contingency. All costs associated with the operation of the ISFSI such as staff oversight, maintenance costs, insurance costs, etc. are included in the 10 CFR 50.54(bb) costs.

TABLE 9.1

		50.75(c)	50.54(bb)	Greenfield	Total
PERIOD	DESCRIPTION	Cost	Cost	Cost	Cost
1	U1 & U2 DECOMMISSIONING PLANNING COST:	\$58,118,473	\$34,535,807		\$92,654,280
2	POST-SHUTDOWN ACTIVITIES COSTS:	\$108,536,051	\$159,622,558		\$268,158,609
3	VESSEL AND INTERNALS REMOVAL COSTS:	\$419,098,715	\$175,173,464	\$13,811,461	\$608,083,640
4	DECONTAMINATE BALANCE OF SITE COSTS:	\$207,438,841	\$10,364,213	\$25,142,731	\$242,945,785
5	CLEAN STRUCTURE DEMOLITION COSTS:		\$5,854,160	\$101,444,398	\$107,298,558
6	RESTORE SITE COSTS:		\$659,818	\$1,604,499	\$2,264,317
	TOTAL COSTS:	\$793,192,081	\$386,210,019	\$142,003,089	\$1,321,405,189
7	ANNUAL DRY STORAGE		\$4,477,802		\$4,477,802

9.3 SCENARIO 2 - DECON WITH INDEFINITE OFF-SITE DRY STORAGE

The total cost for this scenario is **\$1,285.4** million fixed and **\$6.6** million annual as shown in Table 9.2. A total of \$349.8 million is attributable to spent fuel storage, and \$791.9 million is the cost of decommissioning, and \$143.7 million is attributable to clean removal. The costs for this scenario are similar to those for Scenario 1. The difference in costs is due to the incorporation of off-site dry storage; therefore, no additional on-site dry storage will be required.

An ISFSI will have been constructed during operations in order to maintain full core offload capabilities in the spent fuel pool. The off-site storage facility is assumed to be available in 2036 therefore; no additional on-site dry storage will be required. The transfer of all spent fuel assemblies from the site to the off-site ISFSI, will begin just after Unit 2 shutdown. This transfer will proceed at a rate sufficient to allow all spent fuel to be removed from site approximately 5.5 years after Unit 2 shutdown. The maximum number of spent fuel assemblies stored at the on-site ISFSI at any time will be approximately 3,072 requiring 96 storage casks.

TABLE 9.2

		50.75(c)	50.54(bb)	Greenfield	Total
<u>PERIOD</u>	<u>DESCRIPTION</u>	<u>Cost</u>	<u>Cost</u>	<u>Cost</u>	<u>Cost</u>
1	U1 & U2 DECOMMISSIONING PLANNING COST:	\$58,118,473	\$50,949,011		\$109,067,485
2	POST-SHUTDOWN ACTIVITIES COSTS:	\$108,492,361	\$50,321,492		\$158,813,854
3	VESSEL AND INTERNALS REMOVAL COSTS:	\$418,881,715	\$178,546,101	\$14,003,361	\$611,431,178
4	DECONTAMINATE BALANCE OF SITE COSTS:	\$206,406,873	\$58,481,929	\$25,081,831	\$289,970,633
5	CLEAN STRUCTURE DEMOLITION COSTS:		\$10,357,740	\$103,026,711	\$113,384,450
6	RESTORE SITE COSTS:		\$1,150,849	\$1,603,099	\$2,753,948
	TOTAL COSTS:	\$791,899,423	\$349,807,122	\$143,715,003	\$1,285,421,548
7	ANNUAL OFF-SITE DRY STORAGE COSTS:		\$6,604,893		\$6,604,893

9.4 SCENARIO 3 – DECON WITH ON-SITE DRY STORAGE, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE

The total cost for decommissioning utilizing dry storage is **\$1,363.0** million as shown in Table 9.3. The fuel storage component of this cost is \$428.4 million, decommissioning cost at \$792.5 million and greenfield costs at \$142.0 million. For this scenario, there is a large fixed cost required for the design, license, cask procurement, and construction and installation of the dry storage facility. There are also annual surveillance costs, NRC license fees and NRC inspection fees. The cost attributed to the operation and maintenance of the spent fuel pool has been optimized by minimizing the spent fuel support systems.

An ISFSI will have been constructed during operations in order to maintain full core offload capabilities in the spent fuel pool. The existing facility will be expanded shortly after Unit 1 shutdown to accommodate the long term storage of spent fuel. The transfer of the spent fuel assemblies remaining in the spent fuel pool at shutdown, to the ISFSI, will begin just after Unit 2 shutdown. This transfer will proceed at a rate sufficient to allow the spent fuel pool to be empty approximately 5.5 years after Unit 2 shutdown. The maximum number of spent fuel assemblies stored at the ISFSI at any time will be approximately 5,217 requiring 163 storage casks, 96 of

which will have been purchased to maintain full core offload capability and are an operations expense. In addition to the spent fuel, 168 spent fuel size container loaded with GTCC will be stored at the ISFSI, requiring an additional six casks.

The existing ISFSI and infrastructure will have to be expanded to accommodate the post shutdown transfer of spent fuel. The additional pad and infrastructure will cost approximately \$17 million, before contingency. It is assumed that the Holtec vertical storage system will be utilized in the ISFSI at a cost of \$1,929,750 per 32 assembly PWR canister and overpack, including welding services. All casks purchased during operations to maintain full core offload capability are considered an operations expense. A total of 72 casks will be purchased after Unit 2 shutdown at a cost of \$138.9 million, before contingency. All costs associated with the operation of the ISFSI such as staff oversight, maintenance costs, insurance costs, etc. are included in the 10 CFR 50.54(bb) costs.

TABLE 9.3

		50.75(c)	50.54(bb)	Greenfield	Total
PERIOD	DESCRIPTION	Cost	Cost	Cost	Cost
1	U1 & U2 DECOMMISSIONING PLANNING COST:	\$58,118,473	\$24,511,300		\$82,629,774
2	POST-SHUTDOWN ACTIVITIES COSTS:	\$108,521,861	\$101,728,039		\$210,249,900
3	VESSEL AND INTERNALS REMOVAL COSTS:	\$418,991,715	\$117,278,066	\$14,029,561	\$550,299,343
4	DECONTAMINATE BALANCE OF SITE COSTS:	\$206,890,563	\$10,361,927	\$25,129,931	\$242,382,422
5	CLEAN STRUCTURE DEMOLITION COSTS:		\$5,852,864	\$101,422,398	\$107,275,261
6	RESTORE SITE COSTS:		\$659,694	\$1,450,853	\$2,110,546
7	DRY STORAGE		\$163,422,919		\$163,422,919
8	DECON AND REMOVE ISFSI		\$4,611,447		\$4,611,447
	TOTAL COSTS:	\$792,522,613	\$428,426,257	\$142,032,743	\$1,362,981,613

9.5 SCENARIO 4 - SAFSTOR WITH INDEFINITE ON-SITE DRY STORAGE

The total cost for this scenario is **\$1,684.9** million fixed and **\$4.5** million annual as shown in Table 9.4. A total of \$640.2 million is attributable to spent fuel storage; \$901.3 million is the

cost of decommissioning and \$143.4 million for clean removal. This scenario follows the NRC requirement that decommissioning be completed within sixty years of shutdown. SAFSTOR dormancy includes a period with wet and dry spent fuel storage, period 3; and a period with dry spent fuel storage, period 4. Decommissioning will follow the dormancy periods and be completed within the sixty year time frame.

TABLE 9.4

		50.75(c)	50.54(bb)	Greenfield	Total
<u>PERIOD</u>	<u>DESCRIPTION</u>	<u>Cost</u>	<u>Cost</u>	<u>Cost</u>	<u>Cost</u>
1	DECOMMISSIONING PLANNING COST:	\$55,919,351	\$34,548,223		\$90,467,574
2	POST-SHUTDOWN ACTIVITIES COSTS:	\$88,578,315	\$158,845,163		\$247,423,478
3	DORMANCY WITH WET & DRY SPENT FUEL STORAGE:	\$21,443,378	\$193,749,929		\$215,193,308
4	DORMANCY WITH DRY SPENT FUEL STORAGE:	\$132,350,127	\$203,899,560		\$336,249,687
5	DORMANCY WITH DECOMMISSIONING PLANNING COST:	\$69,575,007	\$18,871,646		\$88,446,653
6	VESSEL AND INTERNALS REMOVAL COSTS:	\$325,166,750	\$13,575,773	\$13,815,661	\$352,558,184
7	DECONTAMINATE BALANCE OF SITE COSTS:	\$208,294,136	\$10,214,186	\$25,150,731	\$243,659,054
8	CLEAN STRUCTURE DEMOLITION COSTS:		\$5,820,232	\$102,553,018	\$108,373,250
9	RESTORE SITE COSTS:		\$661,376	\$1,894,634	\$2,556,010
	TOTAL COSTS:	\$901,327,065	\$640,186,089	\$143,414,045	\$1,684,927,198
10	ANNUAL DRY STORAGE		\$4,493,201		\$4,493,201

9.6 SCENARIO 5 – DECON WITH WET STORAGE, MODIFIED SYSTEMS, REPOSITORY OPEN IN 2032 & RECENT DOE ACCEPTANCE RATE

The total cost for this scenario is **\$1,316.4** million as summarized in Table 9.5. A total of \$359.2 million is attributable to the 282 months of post shutdown in-pool spent fuel storage and 534

months of post shutdown dry spent fuel storage. Dry storage is required prior to shutdown to maintain full core offload capabilities. The capital costs for these casks are assumed to be an operations expense. The decommissioning cost is \$814.8 million and is reflected as 50.75(c) costs in Table 9.5 while clean removal costs, \$142.3 million, are shown as greenfield cost. The cost attributed to the operation and maintenance of the spent fuel pool has been optimized by minimizing the spent fuel support systems.

TABLE 9.5

		50.75(c)	50.54(bb)	Greenfield	Total
<u>PERIOD</u>	<u>DESCRIPTION</u>	<u>Cost</u>	<u>Cost</u>	<u>Cost</u>	<u>Cost</u>
1	U1 & U2 DECOMMISSIONING PLANNING COST:	\$58,685,955	\$3,372,905		\$62,058,860
2	POST-SHUTDOWN ACTIVITIES COSTS:	\$109,764,930	\$14,675,868		\$124,440,798
3	VESSEL AND INTERNALS REMOVAL COSTS:	\$424,009,276	\$30,420,973	\$13,782,361	\$468,212,610
4	DECONTAMINATE BALANCE OF SITE COSTS:	\$183,613,141	\$21,379,071	\$25,089,431	\$230,081,644
5	CLEAN STRUCTURE DEMOLITION COSTS:		\$13,303,604	\$68,722,852	\$82,026,457
6	RESTORE SITE COSTS:		\$1,453,694	\$1,531,535	\$2,985,228
7	WET & DRY STORAGE COSTS:	\$1,394,159	\$177,042,240		\$178,436,399
8	AUXILIARY BUILDING REMOVAL COSTS:	\$37,349,443	\$3,981,075	\$33,215,149	\$74,545,666
9	DRY STORAGE		\$90,658,111		\$90,658,111
10	DECON AND REMOVE ISFSI		\$2,921,990		\$2,921,990
	TOTAL COSTS:	\$814,816,904	\$359,209,532	\$142,341,328	\$1,316,367,763

10.0 References

1. Radiation Safety and Control Services, Inc.
2. Smith, R. I., et. al., *Revised Analysis of Decommissioning for the Reference Pressurizer Water Reactor Power Station*, NUREG/CR-5884, PNL-8742, Volumes 1 & 2, November 1995
3. Laquardia, Thomas S., et. al., *Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates*, AIF/NESP-036, Volumes 1 & 2, May 1986
4. Taboas, Anibal L., et. al., *The Decommissioning Handbook*, ASME, 2004
5. New Horizon Scientific, LLC, *Maine Yankee Decommissioning Experience Report, Detailed Experiences 1997 – 2004*, 2005
6. R.S. Means, Inc, *Building Construction Cost Data*, Kingston, Massachusetts, 2012.
7. *NRC Rules and Regulations*, 10 CFR 50, 61, 71, 72, 170, 171
8. *Cost Estimating Guide*, DOE G 430.1-1, March 1997
9. McMaster-Carr Supply Co., Internet catalog 2012
10. DOE/RW-0567 *Acceptance Priority Ranking & Annual Capacity Report*, July 2004
11. U.S.NRC, Office of Public Affairs, *Decommissioning Nuclear Power Plants Fact Sheet*, 2008
12. American Nuclear Society, *Disposal of Low Level Radioactive Waste, Background Information*, revised February 2009
13. South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, *Status of the Barnwell Low-Level Radioactive Waste Disposal Facility*, February 2007
14. Gregory B. Jaczko, *The Need for Alternatives in Low-Level Radioactive Waste Disposal*, June 26, 2007
15. U.S. Dept of Energy Office of Civilian Radioactive Waste Management, *Total System Life Cycle Cost Report*, July 2008
16. U.S. Department of Energy Office of Civilian Radioactive Waste Management, *Report to Congress on the Demonstration of the Interim Storage of Spent Nuclear Fuel from Decommissioned Nuclear Power Reactor Sites*, December 2008


APPENDIX A

SCHEDULES

2012 D. G. Cook
Scenario 1:


ID	Task Name	Duration	Start	Finish
1	Dry spent fuel storage	1874 wks	Fri 7/11/11	Thu 5/30/47
2	Post-shutdown wet storage	426 wks	Wed 10/25/34	Tue 12/23/42
3	Transfer remaining assemblies to ISFSI	13 wks	Wed 12/24/42	Tue 3/24/43
4	Unit 1 Down	0 days	Wed 10/25/34	Wed 10/25/34
5	Period 1 Decommissioning Planning	825 days	Wed 10/25/34	Tue 12/22/37
6	Modify spent fuel support systems	576 days	Wed 10/25/34	Wed 1/7/37
7	Define systems modification	168 days	Wed 10/25/34	Fri 6/15/35
8	Design systems modification and equipment specifications	168 days	Mon 6/18/35	Wed 2/6/36
9	Prepare installation procedures	80 days	Thu 2/7/36	Wed 5/28/36
10	Prepare test procedures	80 days	Thu 5/29/36	Wed 9/17/36
11	Prepare maintenance procedures	80 days	Thu 9/18/36	Wed 1/7/37
12	Control room relocation	624 days	Wed 10/25/34	Mon 3/16/37
13	Define control room equipment	168 days	Wed 10/25/34	Fri 6/15/35
14	Design control room modification and equipment specifications	216 days	Mon 6/18/35	Mon 4/14/36
15	Prepare installation procedures	80 days	Tue 4/15/36	Mon 8/4/36
16	Prepare test procedures	80 days	Tue 8/5/36	Mon 11/24/36
17	Prepare maintenance procedures	80 days	Tue 11/25/36	Mon 3/16/37
18	Design spent fuel storage security modifications	504 days	Wed 10/25/34	Mon 9/29/36
19	Define modification	88 days	Wed 10/25/34	Fri 2/23/35
20	Design modification and equipment specifications	176 days	Mon 2/26/35	Mon 10/29/35
21	Prepare installation procedures	80 days	Tue 10/30/35	Mon 2/18/36
22	Prepare test procedures	80 days	Tue 2/19/36	Mon 6/9/36
23	Prepare maintenance procedures	80 days	Tue 6/10/36	Mon 9/29/36
24	Primary system decontamination	520 days	Wed 10/25/34	Tue 10/21/36
25	Define scope	80 days	Wed 10/25/34	Tue 2/13/35
26	Evaluate processes	120 days	Wed 2/14/35	Tue 7/31/35
27	Prepare bid specifications and RFP	160 days	Wed 6/1/35	Tue 3/11/36
28	Qualify Contractors	80 days	Wed 3/12/36	Tue 7/1/36
29	Evaluate Proposals	80 days	Wed 7/2/36	Tue 10/21/36
30	Select Decommissioning General Contractor	640 days	Wed 10/25/34	Tue 4/7/37
31	Define scope	200 days	Wed 10/25/34	Tue 7/31/35
32	Prepare bid specifications and RFP	240 days	Wed 8/1/35	Tue 7/1/36
33	Qualify Contractors	120 days	Wed 7/2/36	Tue 12/16/36
34	Evaluate Proposals	80 days	Wed 12/17/36	Tue 4/7/37
35	U1 & U2 cold and dark site repowering	680 days	Wed 10/25/34	Tue 6/2/37
36	Define scope	160 days	Wed 10/25/34	Tue 6/5/35
37	Design modification and equipment specifications	200 days	Wed 6/6/35	Tue 3/11/36
38	Prepare installation procedures	240 days	Wed 3/12/36	Tue 2/10/37
39	Prepare test procedures	80 days	Wed 2/11/37	Tue 6/2/37

2012 D. C. Cook Scenario 1						
ID	Task Name	Duration	Start	Finish	30	31
40	Modify U1 & U2 containment access	280 days	Wed 10/25/34	Tue 11/20/35		
41	Select new access location	80 days	Wed 10/25/34	Tue 2/13/36		
42	Design access and equipment specifications	200 days	Wed 2/14/35	Tue 11/20/36		
43	U1 & U2 Site Characterization	590 days	Wed 12/27/34	Tue 3/31/37		
44	Define scoops	120 days	Wed 12/27/34	Tue 6/12/35		
45	Prepare bid specifications and RFP	120 days	Wed 6/13/35	Tue 11/27/35		
46	Qualify Contractors	120 days	Wed 9/19/35	Tue 3/4/36		
47	Evaluate Proposals	80 days	Wed 3/5/36	Tue 6/24/36		
48	Prepare procedures	200 days	Wed 6/25/36	Tue 3/31/37		
49	ADMINISTRATIVE ACTIVITIES	825 days	Wed 10/25/34	Tue 12/22/37		
50	Develop staff transition plan	120 days	Wed 10/25/34	Tue 4/10/35		
51	Develop severance and retention policy	120 days	Wed 4/11/35	Tue 9/25/35		
52	Prepare project administrative procedures	80 days	Wed 9/26/35	Tue 1/15/36		
53	Develop area based decommissioning cost estimate	320 days	Wed 2/20/36	Tue 5/12/37		
54	Develop project budget and schedule controls	160 days	Wed 5/13/37	Tue 12/22/37		
55	Assemble plant drawings	120 days	Wed 10/25/34	Tue 4/10/35		
56	Define end product	120 days	Wed 10/25/34	Tue 4/10/35		
57	Develop technical approach and detailed project plans	320 days	Wed 4/11/35	Tue 7/1/36		
58	LICENSING/PERMITTING DOCUMENTATION	1000 days	Wed 10/25/34	Tue 8/24/38		
59	Insurance exemption	120 days	Wed 10/25/34	Tue 4/10/35		
60	Prepare Post-Shutdown Decommissioning Activities Report	240 days	Wed 10/25/34	Tue 9/25/35		
61	Prepare certification of permanent cessation of operations	24 days	Wed 10/25/34	Mon 11/27/34		
62	Prepare certification of permanent reactor defueling	24 days	Wed 10/25/34	Mon 11/27/34		
63	Prepare post-shutdown technical specification modifications	440 days	Wed 10/25/34	Tue 7/1/36		
64	Update FSAR	400 days	Wed 10/25/34	Tue 5/6/36		
65	Develop certified fuel handler program	120 days	Wed 10/25/34	Tue 4/10/35		
66	Prepare post-shutdown emergency plan	400 days	Wed 10/25/34	Tue 5/6/36		
67	Prepare post-shutdown QA plan	320 days	Wed 10/25/34	Tue 1/15/36		
68	Prepare post-shutdown security plan	320 days	Wed 10/25/34	Tue 1/15/36		
69	Prepare post-shutdown fire protection plan	320 days	Wed 10/25/34	Tue 1/15/36		
70	Prepare post-shutdown radiation protection manual	320 days	Wed 10/25/34	Tue 1/15/36		
71	Prepare and submit state and local permits	320 days	Wed 10/25/34	Tue 1/15/36		
72	Respond to NRC questions on PSDAR	24 days	Wed 9/26/35	Mon 10/29/35		
73	Prepare detailed resource loaded project schedule	480 days	Wed 10/25/34	Tue 8/26/36		
74	Perform 50.59 unreviewed safety questions	240 days	Wed 10/25/34	Tue 9/25/35		
75	Prepare activity specifications	1000 days	Wed 10/25/34	Tue 8/24/38		
76	Prepare detailed work procedures	1000 days	Wed 10/25/34	Tue 8/24/38		
77	Select shipping casks and obtain permits	240 days	Wed 10/25/34	Tue 9/25/35		
78	LICENSE TERMINATION PLAN	1144 days	Wed 10/25/34	Mon 3/14/39		




2012 D. C. Cook
Scenario 1

ID	Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
79	General information	16 days	Wed 10/25/34	Wed 11/15/34																			
80	Site Characterization	80 days	Thu 11/16/34	Wed 3/7/35																			
81	Identification of remaining site dismantlement activities	80 days	Thu 3/8/35	Wed 6/27/35																			
82	Remediation Plans	40 days	Thu 6/28/35	Wed 8/22/35																			
83	Final Radiation Survey Plan	480 days	Thu 8/23/35	Wed 6/24/37																			
84	Compliance with the radiological criteria for license termination	320 days	Thu 11/27/36	Wed 2/17/38																			
85	Update decommissioning cost estimate	80 days	Thu 11/16/34	Wed 3/7/35																			
86	Supplement to the environmental report	80 days	Thu 2/18/38	Wed 6/9/38																			
87	Respond to NRC questions	80 days	Thu 6/10/38	Wed 9/29/38																			
88	Update LTP	118 days	Thu 9/30/38	Mon 3/14/39																			
89	Unit 2 Down	0 days	Wed 12/23/37	Wed 12/23/37																			
90	Period 2 Post-Shutdown Activities	260 days	Wed 12/23/37	Tue 12/21/38																			
91	Modify Spent Fuel Cooling System	173 days	Wed 12/23/37	Fri 8/20/38																			
92	Modify control room	173 days	Mon 3/1/38	Wed 10/27/38																			
93	Modify security system	173 days	Mon 3/1/38	Wed 10/27/38																			
94	Primary System Decon	40 days	Wed 12/23/37	Tue 2/16/38																			
95	Flush & Drain Systems	60 days	Wed 12/23/37	Tue 3/16/38																			
96	Implement cold & dark	240 days	Wed 12/23/37	Tue 11/23/38																			
97	Modify U1 Containment Access	160 days	Wed 12/23/37	Tue 8/3/38																			
98	Modify U2 Containment Access	160 days	Wed 5/12/38	Tue 12/21/38																			
99	Historical Site Assessment	240 days	Wed 12/23/37	Tue 11/23/38																			
100	Vessel and internals activation analysis	215 days	Wed 12/23/37	Tue 10/19/38																			
101	Characterization survey	250 days	Wed 12/23/37	Tue 12/7/38																			
102	Test special equipment and training	215 days	Wed 12/23/37	Tue 10/19/38																			
103	End Period 2	0 days	Tue 12/21/38	Tue 12/21/38																			
104	Period 3 Reactor Vessel and Internals Removal	825 days	Wed 12/22/38	Tue 2/18/42																			
105	Remove Unit 1 reactor vessel internals and reactor vessel	240 days	Wed 12/22/38	Tue 11/22/39																			
106	Transfer Equipment to Unit 2	4 wks	Wed 11/23/39	Tue 12/20/39																			
107	Remove Unit 2 reactor vessel internals and reactor vessel	240 days	Wed 12/21/39	Tue 11/20/40																			
108	Remove Unit 1 steam generators	65 wks	Wed 11/23/39	Tue 2/19/41																			
109	Remove Unit 2 steam generators	65 wks	Wed 11/21/40	Tue 2/18/42																			
110	Remove Unit 1 contaminated systems	105 days	Wed 11/23/39	Tue 4/17/40																			
111	Remove Unit 1 clean systems	103 days	Wed 11/23/39	Fri 4/13/40																			
112	Decon Unit 1 reactor building	56 days	Wed 4/18/40	Wed 7/4/40																			
113	Remove miscellaneous structures	8 days	Wed 12/22/38	Fri 12/31/38																			
114	End Period 3	0 days	Tue 2/18/42	Tue 2/18/42																			
115	Period 4 Building Decontamination	631 days	Wed 2/19/42	Wed 7/20/44																			
116	Remove Spent fuel storage racks	8 wks	Wed 3/25/43	Tue 5/19/43																			
117	Remove Unit 2 contaminated systems	194 days	Thu 9/18/42	Tue 6/16/43																			



2012 D. C. Cook
Scenario 1

ID	Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
118	Remove Unit 2 clean systems	190 days	Wed 2/19/42	Tue 11/11/42																			
119	Decon Steam Generator Storage Building	35 days	Wed 2/19/42	Tue 4/8/42																			
120	Decon Unit 2 Reactor Building	56 days	Wed 6/17/43	Wed 9/2/43																			
121	Decon Auxiliary Building	47 days	Wed 6/17/43	Thu 8/20/43																			
122	Perform final radiological survey of all structures	36 wks	Thu 4/16/43	Wed 12/23/43																			
123	Perform final survey of the site	36 wks	Thu 11/12/43	Wed 7/20/44																			
124	Obtain NRC approval	0 days	Wed 7/20/44	Wed 7/20/44																			
125	End Period 4	0 days	Wed 7/20/44	Wed 7/20/44																			
126	Period 5 Clean Removal	348 days	Thu 7/21/44	Mon 11/20/45																			
127	Remove Unit 1 reactor building	80 days	Thu 7/21/44	Wed 11/9/44																			
128	Remove Unit 2 reactor building	80 days	Thu 11/10/44	Wed 3/1/45																			
129	Remove Auxiliary Building	132 days	Thu 3/2/45	Fri 9/1/45																			
130	Remove Turbine Building	188 days	Thu 3/2/45	Mon 11/20/45																			
131	Remove Steam Generator Storage Building	40 days	Thu 7/21/44	Wed 9/14/44																			
132	Remove Administration building	31 days	Thu 7/21/44	Thu 9/1/44																			
133	Remove Low Level Radwaste building	66 days	Thu 7/21/44	Thu 10/20/44																			
134	End Period 5	0 days	Mon 11/20/45	Mon 11/20/45																			
135	Period 6 Restore site	40 days	Tue 11/21/45	Mon 1/15/46																			
136	Restore site	8 wks	Tue 11/21/45	Mon 1/15/46																			
137	Period 7 Dry Storage	260 days	Tue 1/16/46	Mon 1/14/47																			
138	Dry Storage	52 wks	Tue 1/16/46	Mon 1/14/47																			




30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

ID	Task Name	Duration	Start	Finish
1	On-site dry spent fuel storage	1591 wks	Sun 7/1/12	Fri 12/26/42
2	Off-site spent fuel storage	524 wks	Tue 7/1/36	Mon 7/16/46
3	Post-shutdown wet storage	426 wks	Wed 10/25/34	Tue 12/23/42
4	Transfer remaining assemblies to off-site	13 wks	Wed 12/24/42	Tue 3/24/43
5	Unit 1 Down	0 days	Wed 10/25/34	Wed 10/25/34
6	Period 1 Decommissioning Planning	825 days	Wed 10/25/34	Tue 12/22/37
7	Modify spent fuel support systems	576 days	Wed 10/25/34	Wed 1/7/37
8	Define systems modification	168 days	Wed 10/25/34	Fri 6/15/35
9	Design systems modification and equipment specifications	168 days	Mon 6/18/35	Wed 2/6/36
10	Prepare installation procedures	80 days	Thu 2/7/36	Wed 5/28/36
11	Prepare test procedures	80 days	Thu 5/29/36	Wed 9/17/36
12	Prepare maintenance procedures	80 days	Thu 9/18/36	Wed 1/7/37
13	Control room relocation	624 days	Wed 10/25/34	Mon 3/16/37
14	Define control room equipment	168 days	Wed 10/25/34	Fri 6/15/35
15	Design control room modification and equipment specifications	216 days	Mon 6/18/35	Mon 4/14/36
16	Prepare installation procedures	80 days	Tue 4/15/36	Mon 8/4/36
17	Prepare test procedures	80 days	Tue 8/5/36	Mon 11/24/36
18	Prepare maintenance procedures	80 days	Tue 11/25/36	Mon 3/16/37
19	Design spent fuel storage security modifications	504 days	Wed 10/25/34	Mon 9/29/36
20	Define modification	88 days	Wed 10/25/34	Fri 2/23/35
21	Design modification and equipment specifications	176 days	Mon 2/26/35	Mon 10/29/35
22	Prepare installation procedures	80 days	Tue 10/30/35	Mon 2/18/36
23	Prepare test procedures	80 days	Tue 2/19/36	Mon 6/9/36
24	Prepare maintenance procedures	80 days	Tue 6/10/36	Mon 9/29/36
25	Primary system decontamination	520 days	Wed 10/25/34	Tue 10/21/36
26	Define scope	80 days	Wed 10/25/34	Tue 2/13/35
27	Evaluate processes	120 days	Wed 2/14/35	Tue 7/31/35
28	Prepare bid specifications and RFP	160 days	Wed 8/1/35	Tue 3/11/36
29	Qualify Contractors	80 days	Wed 3/12/36	Tue 7/1/36
30	Evaluate Proposals	80 days	Wed 7/2/36	Tue 10/21/36
31	Select Decommissioning General Contractor	640 days	Wed 10/25/34	Tue 4/7/37
32	Define scope	200 days	Wed 10/25/34	Tue 7/31/35
33	Prepare bid specifications and RFP	240 days	Wed 8/1/35	Tue 7/1/36
34	Qualify Contractors	120 days	Wed 7/2/36	Tue 12/16/36
35	Evaluate Proposals	80 days	Wed 12/17/36	Tue 4/7/37
36	U1 & U2 cold and dark site repowering	680 days	Wed 10/25/34	Tue 6/2/37
37	Define scope	160 days	Wed 10/25/34	Tue 6/5/35
38	Design modification and equipment specifications	200 days	Wed 6/6/35	Tue 3/11/36
39	Prepare installation procedures	240 days	Wed 3/12/36	Tue 2/10/37


2012 D. C. Cook
Scenario 2

ID	Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
40	Prepare test procedures	60 days	Wed 2/11/37	Tue 6/2/37																			
41	Modify U1 & U2 containment access	280 days	Wed 10/25/34	Tue 11/20/35																			
42	Select new access location	60 days	Wed 10/25/34	Tue 2/13/35																			
43	Design access and equipment specifications	200 days	Wed 2/14/35	Tue 1/20/35																			
44	U1 & U2 Site Characterization	590 days	Wed 12/27/34	Tue 3/31/37																			
45	Define scope	120 days	Wed 12/27/34	Tue 6/12/35																			
46	Prepare bid specifications and RFP	120 days	Wed 6/13/35	Tue 1/27/35																			
47	Qualify Contractors	120 days	Wed 8/19/35	Tue 3/4/36																			
48	Evaluate Proposals	60 days	Wed 3/5/36	Tue 6/24/36																			
49	Prepare procedures	200 days	Wed 6/25/36	Tue 3/31/37																			
50	ADMINISTRATIVE ACTIVITIES	825 days	Wed 10/25/34	Tue 12/22/37																			
51	Develop staff transition plan	120 days	Wed 10/25/34	Tue 4/10/35																			
52	Develop severance and retention policy	120 days	Wed 4/11/35	Tue 9/25/35																			
53	Prepare project administrative procedures	60 days	Wed 9/26/35	Tue 1/15/36																			
54	Develop area based decommissioning cost estimate	320 days	Wed 2/20/36	Tue 5/12/37																			
55	Develop project budget and schedule controls	160 days	Wed 5/13/37	Tue 12/22/37																			
56	Assemble plant drawings	120 days	Wed 10/25/34	Tue 4/10/35																			
57	Define end product	120 days	Wed 10/25/34	Tue 4/10/35																			
58	Develop technical approach and detailed project plans	320 days	Wed 4/11/35	Tue 7/1/36																			
59	LICENSING/PERMITTING DOCUMENTATION	1000 days	Wed 10/25/34	Tue 8/24/38																			
60	Insurance exemption	120 days	Wed 10/25/34	Tue 4/10/35																			
61	Prepare Post-Shutdown Decommissioning Activities Report	240 days	Wed 10/25/34	Tue 9/25/35																			
62	Prepare certification of permanent cessation of operations	24 days	Wed 10/25/34	Mon 11/27/34																			
63	Prepare certification of permanent reactor defueling	24 days	Wed 10/25/34	Mon 11/27/34																			
64	Prepare post-shutdown technical specification modifications	440 days	Wed 10/25/34	Tue 7/1/36																			
65	Update FSAR	400 days	Wed 10/25/34	Tue 5/6/36																			
66	Develop certified fuel handler program	120 days	Wed 10/25/34	Tue 4/10/35																			
67	Prepare post-shutdown emergency plan	400 days	Wed 10/25/34	Tue 5/6/36																			
68	Prepare post-shutdown QA plan	320 days	Wed 10/25/34	Tue 1/15/36																			
69	Prepare post-shutdown security plan	320 days	Wed 10/25/34	Tue 1/15/36																			
70	Prepare post-shutdown fire protection plan	320 days	Wed 10/25/34	Tue 1/15/36																			
71	Prepare post-shutdown radiation protection manual	320 days	Wed 10/25/34	Tue 1/15/36																			
72	Prepare and submit state and local permits	320 days	Wed 10/25/34	Tue 1/15/36																			
73	Respond to NRC questions on PSDAR	24 days	Wed 9/26/35	Mon 10/29/35																			
74	Prepare detailed resource loaded project schedule	480 days	Wed 10/25/34	Tue 8/26/36																			
75	Perform 50.59 unreviewed safety questions	240 days	Wed 10/25/34	Tue 9/25/35																			
76	Prepare activity specifications	1000 days	Wed 10/25/34	Tue 8/24/38																			
77	Prepare detailed work procedures	1000 days	Wed 10/25/34	Tue 8/24/38																			
78	Select shipping casks and obtain permits	240 days	Wed 10/25/34	Tue 9/25/35																			




2012 D. C. Cook
Scenario 2

ID	Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
79	LICENSE TERMINATION PLAN	1144 days	Wed 10/25/34	Mon 3/14/39																			
80	General Information	16 days	Wed 10/25/34	Wed 11/15/34																			
81	Site Characterization	80 days	Thu 11/16/34	Wed 3/7/35																			
82	Identification of remaining site dismantlement activities	80 days	Thu 3/8/35	Wed 6/27/35																			
83	Remediation Plans	40 days	Thu 6/28/35	Wed 8/22/35																			
84	Final Radiation Survey Plan	480 days	Thu 8/23/35	Wed 6/24/37																			
85	Compliance with the radiological criteria for license termination	320 days	Thu 11/27/36	Wed 2/17/38																			
86	Update decommissioning cost estimate	80 days	Thu 11/16/34	Wed 3/7/35																			
87	Supplement to the environmental report	80 days	Thu 2/18/38	Wed 6/8/38																			
88	Respond to NRC questions	80 days	Thu 6/10/38	Wed 9/26/38																			
89	Update LTP	118 days	Thu 9/30/38	Mon 3/14/39																			
90	Unit 2 Down	0 days	Wed 12/23/37	Wed 12/23/37																			
91	Period 2 Post-Shutdown Activities	260 days	Wed 12/23/37	Tue 12/21/38																			
92	Modify Spent Fuel Cooling System	173 days	Wed 12/23/37	Fri 8/20/38																			
93	Modify control room	173 days	Mon 3/1/38	Wed 10/27/38																			
94	Modify security system	173 days	Mon 3/1/38	Wed 10/27/38																			
95	Primary System Decon	40 days	Wed 12/23/37	Tue 2/16/38																			
96	Flush & Drain Systems	60 days	Wed 12/23/37	Tue 3/16/38																			
97	Implement cold & dark	240 days	Wed 12/23/37	Tue 11/23/38																			
98	Modify U1 Containment Access	160 days	Wed 12/23/37	Tue 8/3/38																			
99	Modify U2 Containment Access	160 days	Wed 5/12/38	Tue 12/21/38																			
100	Historical Site Assessment	240 days	Wed 12/23/37	Tue 11/23/38																			
101	Vessel and Internals activation analysis	215 days	Wed 12/23/37	Tue 10/19/38																			
102	Characterization survey	250 days	Wed 12/23/37	Tue 12/7/38																			
103	Test special equipment and training	215 days	Wed 12/23/37	Tue 10/19/38																			
104	End Period 2	0 days	Tue 12/21/38	Tue 12/21/38																			
105	Period 3 Reactor Vessel and Internals Removal	825 days	Wed 12/22/38	Tue 2/18/42																			
106	Remove Unit 1 reactor vessel internals and reactor vessel	240 days	Wed 12/22/38	Tue 11/22/39																			
107	Transfer Equipment to Unit 2	4 wks	Wed 11/23/39	Tue 12/20/39																			
108	Remove Unit 2 reactor vessel internals and reactor vessel	240 days	Wed 12/21/39	Tue 11/20/40																			
109	Remove Unit 1 steam generators	65 wks	Wed 11/23/39	Tue 2/19/41																			
110	Remove Unit 2 steam generators	65 wks	Wed 11/21/40	Tue 2/18/42																			
111	Remove Unit 1 contaminated systems	105 days	Wed 11/23/39	Tue 4/17/40																			
112	Remove Unit 1 clean systems	103 days	Wed 11/23/39	Fri 4/13/40																			
113	Decon Unit 1 reactor building	56 days	Wed 4/18/40	Wed 7/4/40																			
114	Remove miscellaneous structures	8 days	Wed 12/22/38	Fri 12/31/38																			
115	End Period 3	0 days	Tue 2/18/42	Tue 2/18/42																			
116	Period 4 Building Decontamination	631 days	Wed 2/19/42	Wed 7/20/44																			
117	Remove Spent fuel storage racks	8 wks	Wed 3/25/43	Tue 5/10/43																			



2012 D. C. Cook
Scenario 2

ID	Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
118	Remove Unit 2 contaminated systems	194 days	Thu 9/18/42	Tue 6/16/43																			
119	Remove Unit 2 clean systems	190 days	Wed 2/19/42	Tue 11/11/42																			
120	Decon Steam Generator Storage Building	35 days	Wed 2/19/42	Tue 4/8/42																			
121	Decon Unit 2 Reactor Building	56 days	Wed 6/17/43	Wed 9/2/43																			
122	Decon Auxiliary Building	47 days	Wed 6/17/43	Thu 8/20/43																			
123	Perform final radiological survey of all structures	36 wks	Thu 4/16/43	Wed 12/23/43																			
124	Perform final survey of the site	36 wks	Thu 11/12/43	Wed 7/20/44																			
125	Obtain NRC approval	0 days	Wed 7/20/44	Wed 7/20/44																			
126	End Period 4	0 days	Wed 7/20/44	Wed 7/20/44																			
127	Period 5 Clean Removal	348 days	Thu 7/21/44	Mon 11/20/45																			
128	Remove Unit 1 reactor building	80 days	Thu 7/21/44	Wed 11/9/44																			
129	Remove Unit 2 reactor building	80 days	Thu 11/10/44	Wed 3/1/45																			
130	Remove Auxiliary Building	132 days	Thu 3/2/45	Fri 9/1/45																			
131	Remove Turbine Building	188 days	Thu 3/2/45	Mon 11/20/45																			
132	Remove Steam Generator Storage Building	40 days	Thu 7/21/44	Wed 9/14/44																			
133	Remove Administration building	31 days	Thu 7/21/44	Thu 9/1/44																			
134	Remove Low Level Radwaste building	68 days	Thu 7/21/44	Thu 10/20/44																			
135	End Period 5	0 days	Mon 11/20/45	Mon 11/20/45																			
136	Period 6 Restore site	40 days	Tue 11/21/45	Mon 1/15/46																			
137	Restore site	8 wks	Tue 11/21/45	Mon 1/15/46																			
138	Period 7 Off-Site Dry Storage	260 days	Tue 1/16/46	Mon 1/14/47																			
139	Dry Storage	52 wks	Tue 1/16/46	Mon 1/14/47																			




2012 D. C. Cook
Scenario 3

ID	Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
1	Dry spent fuel storage (Add 34 year to end date)	1931.25 wks	Fri 7/1/11	Mon 7/6/46																			
2	Spent Fuel Shipping (Add 34 year to end date)	1481.25 wks	Wed 7/1/20	Thu 7/2/48																			
3	Post-shutdown wet storage	426 wks	Wed 10/25/34	Tue 12/23/42																			
4	Transfer remaining assemblies to ISFSI	13 wks	Wed 12/24/42	Tue 3/24/43																			
5	Unit 1 Down	0 days	Wed 10/25/34	Wed 10/25/34																			
6	Period 1 Decommissioning Planning	825 days	Wed 10/25/34	Tue 12/22/37																			
7	Modify spent fuel support systems	576 days	Wed 10/25/34	Wed 1/7/37																			
8	Define systems modification	168 days	Wed 10/25/34	Fri 6/15/35																			
9	Design systems modification and equipment specifications	168 days	Mon 6/18/35	Wed 2/6/36																			
10	Prepare installation procedures	80 days	Thu 2/7/36	Wed 5/28/36																			
11	Prepare test procedures	80 days	Thu 5/29/36	Wed 9/17/36																			
12	Prepare maintenance procedures	80 days	Thu 9/18/36	Wed 1/7/37																			
13	Control room relocation	624 days	Wed 10/25/34	Mon 3/16/37																			
14	Define control room equipment	168 days	Wed 10/25/34	Fri 6/15/35																			
15	Design control room modification and equipment specifications	216 days	Mon 6/18/35	Mon 4/14/36																			
16	Prepare installation procedures	80 days	Tue 4/15/36	Mon 8/4/36																			
17	Prepare test procedures	80 days	Tue 8/5/36	Mon 11/24/36																			
18	Prepare maintenance procedures	80 days	Tue 11/25/36	Mon 3/16/37																			
19	Design spent fuel storage security modifications	504 days	Wed 10/25/34	Mon 9/29/36																			
20	Define modification	88 days	Wed 10/25/34	Fri 2/23/35																			
21	Design modification and equipment specifications	176 days	Mon 2/26/35	Mon 10/29/35																			
22	Prepare installation procedures	80 days	Tue 10/30/35	Mon 2/18/36																			
23	Prepare test procedures	80 days	Tue 2/19/36	Mon 6/9/36																			
24	Prepare maintenance procedures	80 days	Tue 6/10/36	Mon 9/29/36																			
25	Primary system decontamination	520 days	Wed 10/25/34	Tue 10/21/36																			
26	Define scope	80 days	Wed 10/25/34	Tue 2/13/35																			
27	Evaluate processes	120 days	Wed 2/14/35	Tue 7/31/35																			
28	Prepare bid specifications and RFP	180 days	Wed 8/1/35	Tue 3/11/36																			
29	Qualify Contractors	80 days	Wed 3/12/36	Tue 7/1/36																			
30	Evaluate Proposals	80 days	Wed 7/2/36	Tue 10/21/36																			
31	Select Decommissioning General Contractor	640 days	Wed 10/25/34	Tue 4/7/37																			
32	Define scope	200 days	Wed 10/25/34	Tue 7/31/35																			
33	Prepare bid specifications and RFP	240 days	Wed 8/1/35	Tue 7/1/36																			
34	Qualify Contractors	120 days	Wed 7/2/36	Tue 12/16/36																			
35	Evaluate Proposals	80 days	Wed 12/17/36	Tue 4/7/37																			
36	U1 & U2 cold and dark site repowering	680 days	Wed 10/25/34	Tue 6/2/37																			
37	Define scope	160 days	Wed 10/25/34	Tue 6/5/35																			
38	Design modification and equipment specifications	200 days	Wed 6/6/35	Tue 3/11/36																			
39	Prepare installation procedures	240 days	Wed 3/12/36	Tue 2/10/37																			


2012 D. C. Cook
Scenario 3

ID	Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
40	Prepare test procedures	80 days	Wed 2/11/37	Tue 6/2/37																			
41	Modify U1 & U2 containment access.	280 days	Wed 10/25/34	Tue 11/20/35																			
42	Select new access location	80 days	Wed 10/25/34	Tue 2/13/35																			
43	Design access and equipment specifications	200 days	Wed 2/14/35	Tue 11/20/35																			
44	U1 & U2 Site Characterization	590 days	Wed 12/27/34	Tue 3/31/37																			
45	Define scope	120 days	Wed 12/27/34	Tue 6/12/35																			
46	Prepare bid specifications and RFP	120 days	Wed 6/13/35	Tue 11/27/35																			
47	Qualify Contractors	120 days	Wed 9/19/35	Tue 3/4/36																			
48	Evaluate Proposals	80 days	Wed 3/5/36	Tue 6/24/36																			
49	Prepare procedures	200 days	Wed 6/25/36	Tue 3/31/37																			
50	ADMINISTRATIVE ACTIVITIES	825 days	Wed 10/25/34	Tue 12/22/37																			
51	Develop staff transition plan	120 days	Wed 10/25/34	Tue 4/10/35																			
52	Develop severance and retention policy	120 days	Wed 4/11/35	Tue 9/25/35																			
53	Prepare project administrative procedures	80 days	Wed 9/26/35	Tue 1/15/36																			
54	Develop area based decommissioning cost estimate	320 days	Wed 2/20/36	Tue 5/12/37																			
55	Develop project budget and schedule controls	160 days	Wed 5/13/37	Tue 12/22/37																			
56	Assemble plant drawings	120 days	Wed 10/25/34	Tue 4/10/35																			
57	Define end product	120 days	Wed 10/25/34	Tue 4/10/35																			
58	Develop technical approach and detailed project plans	320 days	Wed 4/11/35	Tue 7/1/36																			
59	LICENSING/PERMITTING DOCUMENTATION	1000 days	Wed 10/25/34	Tue 8/24/38																			
60	Insurance exemption	120 days	Wed 10/25/34	Tue 4/10/35																			
61	Prepare Post-Shutdown Decommissioning Activities Report	240 days	Wed 10/25/34	Tue 9/25/35																			
62	Prepare certification of permanent cessation of operations	24 days	Wed 10/25/34	Mon 11/27/34																			
63	Prepare certification of permanent reactor defueling	24 days	Wed 10/25/34	Mon 11/27/34																			
64	Prepare post-shutdown technical specification modifications	440 days	Wed 10/25/34	Tue 7/1/36																			
65	Update FSAR	400 days	Wed 10/25/34	Tue 5/6/36																			
66	Develop certified fuel handler program	120 days	Wed 10/25/34	Tue 4/10/35																			
67	Prepare post-shutdown emergency plan	400 days	Wed 10/25/34	Tue 5/6/36																			
68	Prepare post-shutdown QA plan	320 days	Wed 10/25/34	Tue 1/15/36																			
69	Prepare post-shutdown security plan	320 days	Wed 10/25/34	Tue 1/15/36																			
70	Prepare post-shutdown fire protection plan	320 days	Wed 10/25/34	Tue 1/15/36																			
71	Prepare post-shutdown radiation protection manual	320 days	Wed 10/25/34	Tue 1/15/36																			
72	Prepare and submit state and local permits	320 days	Wed 10/25/34	Tue 1/15/36																			
73	Respond to NRC questions on PSDAR	24 days	Wed 9/26/35	Mon 10/29/35																			
74	Prepare detailed resource loaded project schedule	480 days	Wed 10/25/34	Tue 8/26/36																			
75	Perform 50.59 unreviewed safety questions	240 days	Wed 10/25/34	Tue 9/25/35																			
76	Prepare activity specifications	1000 days	Wed 10/25/34	Tue 8/24/38																			
77	Prepare detailed work procedures	1000 days	Wed 10/25/34	Tue 8/24/38																			
78	Select shipping casks and obtain permits	240 days	Wed 10/25/34	Tue 9/25/35																			




2012 D. C. Cook
Scenario 3

ID	Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
79	LICENSE TERMINATION PLAN	1144 days	Wed 10/25/34	Mon 3/14/39																			
80	General information	16 days	Wed 10/25/34	Wed 11/15/34																			
81	Site Characterization	80 days	Thu 1/16/35	Wed 3/7/35																			
82	Identification of remaining site dismantlement activities	80 days	Thu 3/8/35	Wed 6/27/35																			
83	Remediation Plans	40 days	Thu 6/28/35	Wed 8/22/35																			
84	Final Radiation Survey Plan	480 days	Thu 8/23/35	Wed 6/24/37																			
85	Compliance with the radiological criteria for license termination	320 days	Thu 11/27/36	Wed 2/17/38																			
86	Update decommissioning cost estimate	80 days	Thu 11/16/34	Wed 3/7/35																			
87	Supplement to the environmental report	80 days	Thu 2/18/38	Wed 6/9/38																			
88	Respond to NRC questions	80 days	Thu 6/10/38	Wed 9/29/38																			
89	Update LTP	118 days	Thu 9/30/38	Mon 3/14/39																			
90	Unit 2 Down	0 days	Wed 12/23/37	Wed 12/23/37																			
91	Period 2 Post-Shutdown Activities	260 days	Wed 12/23/37	Tue 12/21/38																			
92	Modify Spent Fuel Cooling System	173 days	Wed 12/23/37	Fri 8/20/38																			
93	Modify control room	173 days	Mon 3/1/38	Wed 10/27/38																			
94	Modify security system	173 days	Mon 3/1/38	Wed 10/27/38																			
95	Primary System Decon	40 days	Wed 12/23/37	Tue 2/16/38																			
96	Flush & Drain Systems	60 days	Wed 12/23/37	Tue 3/16/38																			
97	Implement cold & dark	240 days	Wed 12/23/37	Tue 11/23/38																			
98	Modify U1 Containment Access	160 days	Wed 12/23/37	Tue 8/3/38																			
99	Modify U2 Containment Access	160 days	Wed 5/12/38	Tue 12/21/38																			
100	Historical Site Assessment	240 days	Wed 12/23/37	Tue 11/23/38																			
101	Vessel and internals activation analysis	215 days	Wed 12/23/37	Tue 10/19/38																			
102	Characterization survey	250 days	Wed 12/23/37	Tue 12/7/38																			
103	Test special equipment and training	215 days	Wed 12/23/37	Tue 10/19/38																			
104	End Period 2	0 days	Tue 12/21/38	Tue 12/21/38																			
105	Period 3 Reactor Vessel and Internals Removal	825 days	Wed 12/22/38	Tue 2/18/42																			
106	Remove Unit 1 reactor vessel internals and reactor vessel	240 days	Wed 12/22/38	Tue 11/22/39																			
107	Transfer Equipment to Unit 2	4 wks	Wed 11/23/39	Tue 12/20/39																			
108	Remove Unit 2 reactor vessel internals and reactor vessel	240 days	Wed 12/21/39	Tue 11/20/40																			
109	Remove Unit 1 steam generators	65 wks	Wed 11/23/39	Tue 2/19/41																			
110	Remove Unit 2 steam generators	65 wks	Wed 11/21/40	Tue 2/18/42																			
111	Remove Unit 1 contaminated systems	105 days	Wed 11/23/39	Tue 4/17/40																			
112	Remove Unit 1 clean systems	103 days	Wed 11/23/39	Fri 4/13/40																			
113	Decon Unit 1 reactor building	56 days	Wed 4/18/40	Wed 7/4/40																			
114	Remove miscellaneous structures	8 days	Wed 12/22/38	Fri 12/31/38																			
115	End Period 3	0 days	Tue 2/18/42	Tue 2/18/42																			
116	Period 4 Building Decontamination	631 days	Wed 2/19/42	Wed 7/20/44																			
117	Remove Spent fuel storage racks	8 wks	Wed 3/25/43	Tue 5/19/43																			



2012 D. C. Cook
Scenario 3

ID	Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
118	Remove Unit 2 contaminated systems	194 days	Thu 9/18/42	Tue 6/16/43																			
119	Remove Unit 2 clean systems	190 days	Wed 2/19/42	Tue 11/11/42																			
120	Decon Steam Generator Storage Building	35 days	Wed 2/19/42	Tue 4/8/42																			
121	Decon Unit 2 Reactor Building	56 days	Wed 6/17/43	Wed 8/2/43																			
122	Decon Auxiliary Building	47 days	Wed 6/17/43	Thu 8/20/43																			
123	Perform final radiological survey of all structures	36 wks	Thu 4/16/43	Wed 12/23/43																			
124	Perform final survey of the site	36 wks	Thu 11/12/43	Wed 7/20/44																			
125	Obtain NRC approval	0 days	Wed 7/20/44	Wed 7/20/44																			
126	End Period 4	0 days	Wed 7/20/44	Wed 7/20/44																			
127	Period 5 Clean Removal	348 days	Thu 7/21/44	Mon 11/20/45																			
128	Remove Unit 1 reactor building	80 days	Thu 7/21/44	Wed 11/9/44																			
129	Remove Unit 2 reactor building	80 days	Thu 11/10/44	Wed 3/1/45																			
130	Remove Auxiliary Building	132 days	Thu 3/2/45	Fri 9/1/45																			
131	Remove Turbine Building	188 days	Thu 3/2/45	Mon 11/20/45																			
132	Remove Steam Generator Storage Building	40 days	Thu 7/21/44	Wed 9/14/44																			
133	Remove Administration building	31 days	Thu 7/21/44	Thu 9/1/44																			
134	Remove Low Level Radwaste building	66 days	Thu 7/21/44	Thu 10/20/44																			
135	End Period 5	0 days	Mon 11/20/45	Mon 11/20/45																			
136	Period 6 Restore site	40 days	Tue 11/21/45	Mon 1/15/46																			
137	Restore site	8 wks	Tue 11/21/45	Mon 1/15/46																			
138	Period 7 Dry Storage (Add 34 to end date)	645 days	Tue 1/16/46	Mon 7/6/48																			
139	Dry Storage	129 wks	Tue 1/16/46	Mon 7/6/48																			
140	Period 10 ISFSI Removal (Add 34 years to all dates)	60 days	Tue 7/7/48	Mon 9/28/48																			
141	Decon and remove ISFSI	8 wks	Tue 7/7/48	Mon 8/31/48																			
142	Restore site	4 wks	Tue 9/1/48	Mon 9/28/48																			



2012 D. C. Cook
Scenario 4 - SAFSTOR

ID	Task Name	Duration	Start	Finish
1	Dry spent fuel storage (Add 51 year to end date)	1358 wks	Sun 7/1/12	Fri 7/6/38
2	Post-shutdown wet storage (Add 20 years to all dates)	428 wks	Mon 10/27/14	Fri 12/23/22
3	Transfer remaining assemblies to ISFSI (Add 20 years to all dates)	13 wks	Mon 12/28/22	Fri 3/24/23
4	Unit 1 Down	0 days	Sat 10/25/14	Sat 10/25/14
5	Period 1 Decommissioning Planning (Add 20 years to all dates)	825 days	Mon 10/27/14	Fri 12/22/17
6	Modify spent fuel support systems	576 days	Mon 10/27/14	Mon 1/9/17
7	Define systems modification	168 days	Mon 10/27/14	Wed 6/17/15
8	Design systems modification and equipment specifications	168 days	Thu 6/18/15	Mon 2/6/16
9	Prepare installation procedures	80 days	Tue 2/9/16	Mon 5/30/16
10	Prepare test procedures	80 days	Tue 5/3/16	Mon 9/19/16
11	Prepare maintenance procedures	80 days	Tue 9/20/16	Mon 1/9/17
12	Control room relocation	624 days	Mon 10/27/14	Thu 3/16/17
13	Define control room equipment	168 days	Mon 10/27/14	Wed 6/17/15
14	Design control room modification and equipment specifications	216 days	Thu 6/18/15	Thu 4/14/16
15	Prepare installation procedures	80 days	Fri 4/15/16	Thu 8/4/16
16	Prepare test procedures	80 days	Fri 8/5/16	Thu 11/24/16
17	Prepare maintenance procedures	80 days	Fri 11/25/16	Thu 3/16/17
18	Design spent fuel storage security modifications	504 days	Mon 10/27/14	Thu 9/28/16
19	Define modification	88 days	Mon 10/27/14	Wed 2/25/15
20	Design modification and equipment specifications	176 days	Thu 2/26/15	Thu 10/29/15
21	Prepare installation procedures	80 days	Fri 10/30/15	Thu 2/18/16
22	Prepare test procedures	80 days	Fri 2/19/16	Thu 6/9/16
23	Prepare maintenance procedures	80 days	Fri 6/10/16	Thu 9/29/16
24	Primary system decontamination	520 days	Mon 10/27/14	Fri 10/21/16
25	Define scope	80 days	Mon 10/27/14	Fri 2/13/15
26	Evaluate processes	120 days	Mon 2/16/15	Fri 7/31/15
27	Prepare bid specifications and RFP	160 days	Mon 8/3/15	Fri 3/11/16
28	Qualify Contractors	80 days	Mon 3/14/16	Fri 7/1/16
29	Evaluate Proposals	80 days	Mon 7/4/16	Fri 10/21/16
30	Select SAFSTOR Contractor	640 days	Mon 10/27/14	Fri 4/7/17
31	Define scope	200 days	Mon 10/27/14	Fri 7/31/15
32	Prepare bid specifications and RFP	240 days	Mon 8/3/15	Fri 7/1/16
33	Qualify Contractors	120 days	Mon 7/4/16	Fri 12/18/16
34	Evaluate Proposals	80 days	Mon 12/19/16	Fri 4/7/17
35	U1 & U2 Site Characterization	590 days	Mon 12/28/14	Fri 3/31/17
36	Define scope	120 days	Mon 12/29/14	Fri 6/12/15
37	Prepare bid specifications and RFP	120 days	Mon 6/15/15	Fri 11/27/15
38	Qualify Contractors	120 days	Mon 9/21/15	Fri 3/4/16
39	Evaluate Proposals	80 days	Mon 3/7/16	Fri 6/24/16
40	Prepare procedures	200 days	Mon 6/27/16	Fri 3/31/17
41	ADMINISTRATIVE ACTIVITIES	825 days	Mon 10/27/14	Fri 12/22/17
42	Develop staff transition plan	120 days	Mon 10/27/14	Fri 4/10/15
43	Develop severance and retention policy	120 days	Mon 4/13/15	Fri 9/25/15
44	Prepare project administrative procedures	80 days	Mon 9/28/15	Fri 1/15/16
45	Develop area based decommissioning cost estimate	320 days	Mon 2/22/16	Fri 5/12/17

2012 D. C. Cook
Scenario 4 - SAFSTOR


ID	Task Name	Duration	Start	Finish
46	Develop project budget and schedule controls	160 days	Mon 5/15/17	Fri 12/22/17
47	Assemble plant drawings	120 days	Mon 10/27/14	Fri 4/10/15
48	Define end product	120 days	Mon 10/27/14	Fri 4/10/15
49	Develop technical approach and detailed project plans	320 days	Mon 4/13/15	Fri 7/1/16
50	LICENSING/PERMITTING DOCUMENTATION	1000 days	Mon 10/27/14	Fri 8/24/18
51	Insurance exemption	120 days	Mon 10/27/14	Fri 4/10/15
52	Prepare Post-Shutdown Decommissioning Activities Report	240 days	Mon 10/27/14	Fri 9/25/15
53	Prepare certification of permanent cessation of operations	24 days	Mon 10/27/14	Thu 11/27/14
54	Prepare certification of permanent reactor defueling	24 days	Mon 10/27/14	Thu 11/27/14
55	Prepare post-shutdown technical specification modifications	440 days	Mon 10/27/14	Fri 7/1/16
56	Update FSAR	400 days	Mon 10/27/14	Fri 5/8/16
57	Develop certified fuel handler program	120 days	Mon 10/27/14	Fri 4/10/15
58	Prepare post-shutdown emergency plan	400 days	Mon 10/27/14	Fri 5/8/16
59	Prepare post-shutdown QA plan	320 days	Mon 10/27/14	Fri 1/15/16
60	Prepare post-shutdown security plan	320 days	Mon 10/27/14	Fri 1/15/16
61	Prepare post-shutdown fire protection plan	320 days	Mon 10/27/14	Fri 1/15/16
62	Prepare post-shutdown radiation protection manual	320 days	Mon 10/27/14	Fri 1/15/16
63	Prepare and submit state and local permits	320 days	Mon 10/27/14	Fri 1/15/16
64	Respond to NRC questions on PSDAR	24 days	Mon 9/28/15	Thu 10/29/15
65	Prepare detailed resource loaded project schedule	480 days	Mon 10/27/14	Fri 8/26/16
66	Perform 50.59 unreviewed safety questions	240 days	Mon 10/27/14	Fri 9/25/15
67	Prepare activity specifications	1000 days	Mon 10/27/14	Fri 8/24/18
68	Prepare detailed work procedures	1000 days	Mon 10/27/14	Fri 8/24/18
69	Select shipping casks and obtain permits	240 days	Mon 10/27/14	Fri 9/25/15
70	Unit 2 Down	0 days	Sat 12/23/17	Sat 12/23/17
71	Period 2 Post-Shutdown Activities (Add 20 years to all dates)	221 days	Mon 12/25/17	Mon 10/29/18
72	Modify Spent Fuel Cooling System	173 days	Mon 12/25/17	Wed 8/22/18
73	Modify control room	173 days	Thu 3/1/18	Mon 10/29/18
74	Modify security system	173 days	Thu 3/1/18	Mon 10/29/18
75	Primary System Decon	40 days	Mon 12/25/17	Fri 2/16/18
76	Flush & Drain Systems	60 days	Mon 12/25/17	Fri 3/16/18
77	Decontaminate and clean up reactor buildings	126 days	Mon 12/25/17	Mon 6/18/18
78	Install environmental monitors	185 days	Mon 12/25/17	Fri 9/7/18
79	Prepare SAFSTOR report	80 days	Mon 12/25/17	Fri 4/13/18
80	End Period 2	0 days	Mon 10/29/18	Mon 10/29/18
81	Period 3 Dormancy with Wet Storage (Add 20 years to all dates)	1150 days	Tue 10/30/18	Mon 3/27/23
82	Dormancy with Wet Storage	230 wks	Tue 10/30/18	Mon 3/27/23
83	Period 4 Dormancy with Dry Storage (Add 20 years to start date and 51 years to end date)	3595 days	Tue 3/28/23	Mon 1/5/37
84	Dormancy with Dry Storage	719 wks	Tue 3/28/23	Mon 1/5/37
85	Period 5 Decommissioning Planning (Add 51 years to all dates)	1144 days	Tue 1/6/37	Fri 5/24/41
86	Select SAFSTOR Contractor	640 days	Tue 1/6/37	Mon 6/20/39
87	Define scope	200 days	Tue 1/6/37	Mon 10/12/37
88	Prepare bid specifications and RFP	240 days	Tue 10/13/37	Mon 9/13/38
89	Qualify Contractors	120 days	Tue 9/14/38	Mon 2/28/39
90	Evaluate Proposals	80 days	Tue 3/1/39	Mon 6/20/39

ID	Task Name	Duration	Start	Finish
91	U1 & U2 cold and dark site repowering	680 days	Tue 1/6/37	Mon 8/15/39
92	Define scope	150 days	Tue 1/6/37	Mon 8/17/37
93	Design modification and equipment specifications	200 days	Tue 8/18/37	Mon 5/24/38
94	Prepare installation procedures	240 days	Tue 5/25/38	Mon 4/25/39
95	Prepare test procedures	90 days	Tue 4/26/39	Mon 8/15/39
96	Modify U1 & U2 containment access	280 days	Tue 1/6/37	Mon 2/1/38
97	Select new access location	80 days	Tue 1/6/37	Mon 4/27/37
98	Design access and equipment specifications	200 days	Tue 4/28/37	Mon 2/1/38
99	U1 & U2 Site Characterization	590 days	Tue 3/10/37	Mon 6/13/39
100	Define scope	120 days	Tue 3/10/37	Mon 8/24/37
101	Prepare bid specifications and RFP	120 days	Tue 8/25/37	Mon 2/6/38
102	Qualify Contractors	120 days	Tue 12/1/37	Mon 5/17/38
103	Evaluate Proposals	80 days	Tue 5/18/38	Mon 9/6/38
104	Prepare procedures	200 days	Tue 9/7/38	Mon 6/13/39
105	ADMINISTRATIVE ACTIVITIES	826 days	Tue 1/6/37	Mon 3/5/40
106	Develop staff transition plan	120 days	Tue 1/6/37	Mon 6/22/37
107	Develop severance and retention policy	120 days	Tue 6/23/37	Mon 12/7/37
108	Prepare project administrative procedures	80 days	Tue 12/8/37	Mon 3/29/38
109	Develop area based decommissioning cost estimate	320 days	Tue 5/4/38	Mon 7/25/39
110	Develop project budget and schedule controls	160 days	Tue 7/26/39	Mon 3/5/40
111	Assemble plant drawings	120 days	Tue 1/6/37	Mon 8/22/37
112	Define end product	120 days	Tue 1/6/37	Mon 6/22/37
113	Develop technical approach and detailed project plans	320 days	Tue 6/23/37	Mon 9/13/38
114	LICENSING/PERMITTING DOCUMENTATION	1000 days	Tue 1/6/37	Mon 11/5/40
115	Insurance exemption	120 days	Tue 1/6/37	Mon 6/22/37
116	Prepare Post-Shutdown Decommissioning Activities Report	240 days	Tue 1/6/37	Mon 12/7/37
117	Prepare certification of permanent cessation of operations	24 days	Tue 1/6/37	Fri 2/6/37
118	Prepare certification of permanent reactor defueling	24 days	Tue 1/6/37	Fri 2/6/37
119	Prepare post-shutdown technical specification modifications	440 days	Tue 1/6/37	Mon 9/13/38
120	Update FSAR	400 days	Tue 1/6/37	Mon 7/19/38
121	Develop certified fuel handler program	120 days	Tue 1/6/37	Mon 6/22/37
122	Prepare post-shutdown emergency plan	400 days	Tue 1/6/37	Mon 7/19/38
123	Prepare post-shutdown QA plan	320 days	Tue 1/6/37	Mon 3/29/38
124	Prepare post-shutdown security plan	320 days	Tue 1/6/37	Mon 3/29/38
125	Prepare post-shutdown fire protection plan	320 days	Tue 1/6/37	Mon 3/29/38
126	Prepare post-shutdown radiation protection manual	320 days	Tue 1/6/37	Mon 3/29/38
127	Prepare and submit state and local permits	320 days	Tue 1/6/37	Mon 3/29/38
128	Respond to NRC questions on PSDAR	24 days	Tue 12/8/37	Fri 1/8/38
129	Prepare detailed resource loaded project schedule	480 days	Tue 1/6/37	Mon 11/8/38
130	Perform 50.59 unreviewed safety questions	240 days	Tue 1/6/37	Mon 12/7/37
131	Prepare activity specifications	1000 days	Tue 1/6/37	Mon 11/5/40
132	Prepare detailed work procedures	1000 days	Tue 1/6/37	Mon 11/5/40
133	Select shipping casks and obtain permits	240 days	Tue 1/6/37	Mon 12/7/37
134	LICENSE TERMINATION PLAN	1144 days	Tue 1/6/37	Fri 5/24/41
135	General Information	16 days	Tue 1/6/37	Tue 1/27/37

ID	Task Name	Duration	Start	Finish
136	Site Characterization	80 days	Wed 1/28/37	Tue 5/19/37
137	Identification of remaining site dismantlement activities	80 days	Wed 5/20/37	Tue 9/8/37
138	Remediation Plans	40 days	Wed 9/9/37	Tue 11/3/37
139	Final Radiation Survey Plan	480 days	Wed 11/4/37	Tue 9/8/39
140	Compliance with the radiological criteria for license termination	320 days	Wed 2/9/39	Tue 5/1/40
141	Update decommissioning cost estimate	80 days	Wed 1/28/37	Tue 5/19/37
142	Supplement to the environmental report	80 days	Wed 5/2/40	Tue 8/21/40
143	Respond to NRC questions	80 days	Wed 8/22/40	Tue 12/11/40
144	Update LTP	118 days	Wed 12/12/40	Fri 5/24/41
145	End Period 6	0 days	Fri 5/24/41	Fri 5/24/41
146	Period 6 Reactor Vessel and Internals Removal (Add 51 years to all dates)	825 days	Mon 5/27/41	Fri 7/22/44
147	Remove Unit 1 reactor vessel internals and reactor vessel	240 days	Mon 5/27/41	Fri 4/25/42
148	Transfer Equipment to Unit 2	4 wks	Mon 4/28/42	Fri 5/23/42
149	Remove Unit 2 reactor vessel Internals and reactor vessel	240 days	Mon 5/26/42	Fri 4/24/43
150	Remove Unit 1 steam generators	85 wks	Mon 4/28/42	Fri 7/24/43
151	Remove Unit 2 steam generators	85 wks	Mon 4/27/43	Fri 7/22/44
152	Remove Unit 1 contaminated systems	105 days	Mon 4/28/42	Fri 9/19/42
153	Remove Unit 1 clean systems	103 days	Mon 4/28/42	Wed 9/17/42
154	Decon Unit 1 reactor building	56 days	Mon 9/22/42	Mon 12/8/42
155	Remove miscellaneous structures	8 days	Mon 5/27/41	Wed 8/5/41
156	End Period 7	0 days	Fri 7/22/44	Fri 7/22/44
157	Period 7 Building Decontamination (Add 51 years to all dates)	820 days	Mon 7/25/44	Fri 12/7/48
158	Remove Spent fuel storage racks	8 wks	Mon 7/25/44	Fri 9/16/44
159	Remove Unit 2 contaminated systems	194 days	Mon 9/19/44	Thu 8/15/45
160	Remove Unit 2 clean systems	180 days	Mon 7/25/44	Fri 4/14/45
161	Decon Steam Generator Storage Building	35 days	Mon 7/25/44	Fri 9/9/44
162	Decon Unit 2 Reactor Building	56 days	Fri 6/16/45	Fri 9/1/45
163	Decon Auxiliary Building	47 days	Fri 6/16/45	Mon 8/21/45
164	Perform final radiological survey of all structures	36 wks	Mon 9/4/45	Fri 5/11/46
165	Perform final survey of the site	36 wks	Mon 4/2/46	Fri 12/7/48
166	Obtain NRC approval	0 days	Fri 12/7/46	Fri 12/7/46
167	End Period 8	0 days	Fri 12/7/46	Fri 12/7/46
168	Period 8 Clean Removal (Add 51 years to all dates)	348 days	Mon 12/10/48	Wed 4/8/48
169	Remove Unit 1 reactor building	80 days	Mon 12/10/46	Fri 3/29/47
170	Remove Unit 2 reactor building	80 days	Mon 4/1/47	Fri 7/19/47
171	Remove Auxiliary Building	132 days	Mon 7/22/47	Tue 1/21/48
172	Remove Turbine Building	188 days	Mon 7/22/47	Wed 4/8/48
173	Remove Steam Generator Storage Building	40 days	Mon 12/10/46	Fri 2/4/47
174	Remove Administration building	31 days	Mon 12/10/46	Mon 1/21/47
175	Remove Low Level Radwaste building	66 days	Mon 12/10/46	Mon 3/11/47
176	End Period 9	0 days	Wed 4/8/48	Wed 4/8/48
177	Period 9 Restore site (Add 51 years to all dates)	40 days	Thu 4/9/48	Wed 6/3/48
178	Restore site	8 wks	Thu 4/9/48	Wed 6/3/48
179	Period 10 Continued spent fuel storage	260 days	Thu 6/4/48	Wed 6/2/49
180	Dry Storage	52 wks	Thu 6/4/48	Wed 6/2/49


2012 D. C. Cook
Scenario 5

Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
Dry spent fuel storage (Add 34 year to end date)	1931.25 wks	Fri 7/1/11	Mon 7/6/48																			
Spent Fuel Shipping (Add 34 year to end date)	1461.25 wks	Wed 7/1/20	Thu 7/2/48																			
Post-shutdown wet storage (Add 13 years to end date)	715 wks	Wed 10/25/34	Tue 7/7/48																			
Unit 1 Down	0 days	Wed 10/25/34	Wed 10/25/34																			
Period 1 Decommissioning Planning	825 days	Wed 10/25/34	Tue 12/22/37																			
Modify spent fuel support systems	576 days	Wed 10/25/34	Wed 1/7/37																			
Define systems modification	168 days	Wed 10/25/34	Fri 6/15/35																			
Design systems modification and equipment specifications	168 days	Mon 6/18/35	Wed 2/6/36																			
Prepare installation procedures	80 days	Thu 2/7/36	Wed 5/28/36																			
Prepare test procedures	80 days	Thu 5/29/36	Wed 9/17/36																			
Prepare maintenance procedures	80 days	Thu 9/18/36	Wed 1/7/37																			
Control room relocation	624 days	Wed 10/25/34	Mon 3/16/37																			
Define control room equipment	168 days	Wed 10/25/34	Fri 6/15/35																			
Design control room modification and equipment specifications	216 days	Mon 6/18/35	Mon 4/14/36																			
Prepare installation procedures	80 days	Tue 4/15/36	Mon 8/4/36																			
Prepare test procedures	80 days	Tue 8/5/36	Mon 11/24/36																			
Prepare maintenance procedures	80 days	Tue 11/25/36	Mon 3/16/37																			
Design spent fuel storage security modifications	504 days	Wed 10/25/34	Mon 9/29/38																			
Define modification	88 days	Wed 10/25/34	Fri 2/23/35																			
Design modification and equipment specifications	176 days	Mon 2/26/35	Mon 10/29/35																			
Prepare installation procedures	80 days	Tue 10/30/35	Mon 2/18/36																			
Prepare test procedures	80 days	Tue 2/19/36	Mon 6/9/36																			
Prepare maintenance procedures	80 days	Tue 6/10/36	Mon 9/29/36																			
Primary system decontamination	520 days	Wed 10/25/34	Tue 10/21/36																			
Define scope	80 days	Wed 10/25/34	Tue 2/13/35																			
Evaluate processes	120 days	Wed 2/14/35	Tue 7/31/35																			
Prepare bid specifications and RFP	160 days	Wed 8/1/35	Tue 3/11/36																			
Qualify Contractors	80 days	Wed 3/12/36	Tue 7/1/36																			
Evaluate Proposals	80 days	Wed 7/2/36	Tue 10/21/36																			
Select Decommissioning General Contractor	640 days	Wed 10/25/34	Tue 4/7/37																			
Define scope	200 days	Wed 10/25/34	Tue 7/31/35																			
Prepare bid specifications and RFP	240 days	Wed 8/1/35	Tue 7/1/36																			
Qualify Contractors	120 days	Wed 7/2/36	Tue 12/16/36																			
Evaluate Proposals	80 days	Wed 12/17/36	Tue 4/7/37																			
U1 & U2 cold and dark site repowering	680 days	Wed 10/25/34	Tue 6/2/37																			
Define scope	160 days	Wed 10/25/34	Tue 6/5/35																			
Design modification and equipment specifications	200 days	Wed 6/5/35	Tue 3/11/36																			
Prepare Installation procedures	240 days	Wed 3/12/36	Tue 2/10/37																			




2012 D. C. Cook
Scenario 5

Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
Prepare test procedures	80 days	Wed 2/11/37	Tue 6/2/37																			
Modify U1 & U2 containment access	280 days	Wed 10/25/34	Tue 11/20/35																			
Select new access location	80 days	Wed 10/25/34	Tue 2/13/35																			
Design access and equipment specifications	200 days	Wed 2/14/35	Tue 11/20/35																			
U1 & U2 Site Characterization	590 days	Wed 12/27/34	Tue 3/31/37																			
Define scope	120 days	Wed 12/27/34	Tue 6/12/35																			
Prepare bid specifications and RFP	120 days	Wed 6/13/35	Tue 11/27/35																			
Qualify Contractors	120 days	Wed 9/19/35	Tue 3/4/36																			
Evaluate Proposals	80 days	Wed 3/5/36	Tue 6/24/36																			
Prepare procedures	200 days	Wed 6/26/36	Tue 3/31/37																			
ADMINISTRATIVE ACTIVITIES	828 days	Wed 10/26/34	Tue 12/22/37																			
Develop staff transition plan	120 days	Wed 10/26/34	Tue 4/10/35																			
Develop severance and retention policy	120 days	Wed 4/11/35	Tue 9/26/35																			
Prepare project administrative procedures	80 days	Wed 9/26/35	Tue 1/15/36																			
Develop area based decommissioning cost estimate	320 days	Wed 2/20/36	Tue 5/12/37																			
Develop project budget and schedule controls	160 days	Wed 5/13/37	Tue 12/22/37																			
Assemble plant drawings	120 days	Wed 10/25/34	Tue 4/10/35																			
Define end product	120 days	Wed 10/25/34	Tue 4/10/35																			
Develop technical approach and detailed project plans	320 days	Wed 4/11/35	Tue 7/1/36																			
LICENSING/PERMITTING DOCUMENTATION	1000 days	Wed 10/25/34	Tue 8/24/38																			
Insurance exemption	120 days	Wed 10/25/34	Tue 4/10/35																			
Prepare Post-Shutdown Decommissioning Activities Report	240 days	Wed 10/25/34	Tue 9/25/35																			
Prepare certification of permanent cessation of operations	24 days	Wed 10/25/34	Mon 11/27/34																			
Prepare certification of permanent reactor defueling	24 days	Wed 10/25/34	Mon 11/27/34																			
Prepare post-shutdown technical specification modifications	440 days	Wed 10/25/34	Tue 7/1/36																			
Update FSAR	400 days	Wed 10/25/34	Tue 5/6/36																			
Develop certified fuel handler program	120 days	Wed 10/25/34	Tue 4/10/35																			
Prepare post-shutdown emergency plan	400 days	Wed 10/25/34	Tue 5/6/36																			
Prepare post-shutdown QA plan	320 days	Wed 10/25/34	Tue 1/15/36																			
Prepare post-shutdown security plan	320 days	Wed 10/25/34	Tue 1/15/36																			
Prepare post-shutdown fire protection plan	320 days	Wed 10/25/34	Tue 1/15/36																			
Prepare post-shutdown radiation protection manual	320 days	Wed 10/25/34	Tue 1/15/36																			
Prepare and submit state and local permits	320 days	Wed 10/25/34	Tue 1/15/36																			
Respond to NRC questions on PSDAR	24 days	Wed 9/26/35	Mon 10/29/35																			
Prepare detailed resource loaded project schedule	480 days	Wed 10/25/34	Tue 8/28/36																			
Perform 50.59 unreviewed safety questions	240 days	Wed 10/25/34	Tue 9/25/35																			
Prepare activity specifications	1000 days	Wed 10/25/34	Tue 8/24/38																			
Prepare detailed work procedures	1000 days	Wed 10/25/34	Tue 8/24/38																			



2012 D. C. Cook
Scenario 5

Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
Select shipping casks and obtain permits	240 days	Wed 10/25/34	Tue 9/25/35																			
LICENSE TERMINATION PLAN	1144 days	Wed 10/25/34	Mon 3/14/39																			
General information	16 days	Wed 10/25/34	Wed 11/15/34																			
Site Characterization	80 days	Thu 11/16/34	Wed 3/7/35																			
Identification of remaining site dismantlement activities	80 days	Thu 3/8/35	Wed 6/27/35																			
Remediation Plans	40 days	Thu 6/28/35	Wed 8/22/35																			
Final Radiation Survey Plan	480 days	Thu 8/23/35	Wed 6/24/37																			
Compliance with the radiological criteria for license termination	320 days	Thu 11/27/36	Wed 2/17/38																			
Update decommissioning cost estimate	80 days	Thu 11/16/34	Wed 3/7/35																			
Supplement to the environmental report	80 days	Thu 2/18/38	Wed 6/9/38																			
Respond to NRC questions	80 days	Thu 6/10/38	Wed 9/29/38																			
Update LTP	118 days	Thu 9/30/38	Mon 3/14/39																			
Unit 2 Down	0 days	Wed 12/23/37	Wed 12/23/37																			
Period 2 Post-Shutdown Activities	260 days	Wed 12/23/37	Tue 12/21/38																			
Modify Spent Fuel Cooling System	173 days	Wed 12/23/37	Fri 8/20/38																			
Modify control room	173 days	Mon 3/1/38	Wed 10/27/38																			
Modify security system	173 days	Mon 3/1/38	Wed 10/27/38																			
Primary System Decon	40 days	Wed 12/23/37	Tue 2/16/38																			
Flush & Drain Systems	60 days	Wed 12/23/37	Tue 3/16/38																			
Implement cold & dark	240 days	Wed 12/23/37	Tue 11/23/38																			
Modify U1 Containment Access	160 days	Wed 12/23/37	Tue 8/3/38																			
Modify U2 Containment Access	160 days	Wed 5/12/38	Tue 12/21/38																			
Historical Site Assessment	240 days	Wed 12/23/37	Tue 11/23/38																			
Vessel and Internals activation analysis	215 days	Wed 12/23/37	Tue 10/19/38																			
Characterization survey	250 days	Wed 12/23/37	Tue 12/7/38																			
Test special equipment and training	215 days	Wed 12/23/37	Tue 10/19/38																			
End Period 2	0 days	Tue 12/21/38	Tue 12/21/38																			
Period 3 Reactor Vessel and Internals Removal	825 days	Wed 12/22/38	Tue 2/18/42																			
Remove Unit 1 reactor vessel internals and reactor vessel	240 days	Wed 12/22/38	Tue 11/22/39																			
Transfer Equipment to Unit 2	4 wks	Wed 11/23/39	Tue 12/20/39																			
Remove Unit 2 reactor vessel internals and reactor vessel	240 days	Wed 12/21/39	Tue 11/20/40																			
Remove Unit 1 steam generators	65 wks	Wed 11/23/39	Tue 2/19/41																			
Remove Unit 2 steam generators	65 wks	Wed 11/21/40	Tue 2/18/42																			
Remove Unit 1 contaminated systems	105 days	Wed 11/23/39	Tue 4/17/40																			
Remove Unit 1 clean systems	103 days	Wed 11/23/39	Fri 4/13/40																			
Decon Unit 1 reactor building	56 days	Wed 4/18/40	Wed 7/4/40																			
Remove miscellaneous structures	8 days	Wed 12/22/38	Fri 12/31/38																			
End Period 3	0 days	Tue 2/18/42	Tue 2/18/42																			



2012 D. C. Cook
Scenario 5

Task Name	Duration	Start	Finish	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
Period 4 Building Decontamination	680 days	Wed 2/19/42	Tue 5/10/44																			
Remove Unit 2 contaminated systems	194 days	Wed 2/19/42	Mon 11/17/42																			
Remove Unit 2 clean systems	180 days	Wed 2/19/42	Tue 11/11/42																			
Decon Steam Generator Storage Building	35 days	Wed 2/19/42	Tue 4/8/42																			
Decon Unit 2 Reactor Building	56 days	Tue 11/18/42	Tue 2/3/43																			
Perform final radiological survey of all structures	36 wks	Wed 2/4/43	Tue 10/13/43																			
Perform final survey of the site	36 wks	Wed 9/2/43	Tue 5/10/44																			
Obtain NRC approval	0 days	Tue 5/10/44	Tue 5/10/44																			
End Period 4	0 days	Tue 5/10/44	Tue 5/10/44																			
Period 5 Clean Removal	348 days	Wed 5/11/44	Fri 9/8/45																			
Remove Unit 1 reactor building	80 days	Wed 5/11/44	Tue 8/30/44																			
Remove Unit 2 reactor building	80 days	Wed 8/31/44	Tue 12/20/44																			
Remove Turbine Building	188 days	Wed 12/21/44	Fri 9/8/45																			
Remove Steam Generator Storage Building	40 days	Wed 5/11/44	Tue 7/5/44																			
Remove Administration building	31 days	Wed 5/11/44	Wed 6/22/44																			
Remove Low Level Radwaste building	66 days	Wed 5/11/44	Wed 8/10/44																			
End Period 5	0 days	Fri 9/8/45	Fri 9/8/45																			
Period 6 Restore Site	40 days	Mon 9/11/45	Fri 11/3/45																			
Restore site	8 wks	Mon 9/11/45	Fri 11/3/45																			
Period 7 Wet Storage (Add 15 years to end date)	175 days	Mon 11/6/45	Fri 7/6/46																			
Wet Storage	35 wks	Mon 11/6/45	Fri 7/6/46																			
Period 8 Balance of Decontamination (Add 15 years to all dates)	259 days	Mon 7/9/46	Thu 7/4/47																			
Remove Spent fuel storage racks	8 wks	Mon 7/9/46	Fri 8/31/46																			
Decon Auxiliary Building	47 days	Mon 9/3/46	Tue 11/6/46																			
Remove Auxiliary Building	132 days	Wed 1/2/47	Thu 7/4/47																			
Final Survey	8 wks	Wed 11/7/46	Tue 1/1/47																			
Period 9 Dry Storage (Add 15 years to start date and 34 to end date)	260 days	Fri 7/5/47	Thu 7/2/48																			
Dry Storage	52 wks	Fri 7/5/47	Thu 7/2/48																			
Period 10 ISFSI Removal	60 days	Fri 7/3/48	Thu 9/24/48																			
Decon and remove ISFSI	8 wks	Fri 7/3/48	Thu 8/27/48																			
Restore site	4 wks	Fri 8/28/48	Thu 9/24/48																			

APPENDIX B
COST TABLES

2012 D.C. Cost
Scenario 1
DECON and Permanent Dry-Site Dry Storage

Task	Staff Labor	Craft Labor	Equipment Material	Permitting	Transportation	Clean Demolition	Contaminated Demolition	Remediation	Construction	Subcontractor	Construction	Test with Construction	Staff Materials	Clean Craft Materials	Contaminated Craft Materials
PERIOD 1 - U1 & U2 DECOMMISSIONING PLANNING COST:															
SPENT FUEL ACTIVITIES															
1 A 50.54(a) Modify spent fuel support systems										\$62,772	\$0.00	\$72,172			608
1 A 50.54(a) Define systems modification	\$62,772														
1 A 50.54(a) Design systems modification and equipment specifications	\$147,689									\$147,689	\$22,500	\$100,600			1,068
1 A 50.54(a) Prepare installation procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
1 A 50.54(a) Prepare test procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
1 A 50.54(a) Prepare maintenance procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
1 A 50.54(b) Control room relocation										\$62,772	\$0.00	\$72,172			608
1 A 50.54(b) Define control room equipment	\$62,772														
1 A 50.54(b) Design control room modification and equipment specifications	\$170,962									\$170,962	\$26,800	\$106,782			1,068
1 A 50.54(b) Prepare installation procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
1 A 50.54(b) Prepare test procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
1 A 50.54(b) Prepare maintenance procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
1 A 50.54(b) Design spent fuel storage security modifications										\$28,405	\$4,400	\$33,905			288
1 A 50.54(b) Define modification	\$28,405														
1 A 50.54(b) Design modification and equipment specifications	\$183,741									\$183,741	\$15,400	\$119,141			1,018
1 A 50.54(b) Prepare installation procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
1 A 50.54(b) Prepare test procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
1 A 50.54(b) Prepare maintenance procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
1 A 50.54(b) NPSI Pad Construction		\$25,102,477								\$25,102,477	\$5,746,000	\$30,848,077			182
SUBTOTAL - SPENT FUEL ACTIVITIES	\$748,487	\$25,102,477								\$25,851,964	\$6,899,400	\$31,711,364			7,804
SPENT FUEL PERIOD DEPENDENT															
1 PD 50.54(a) Utility Staff															
1 PD 50.54(a) Security															
1 PD 50.54(a) Insurance										\$2,183,119	\$2,183,119	\$92,500			\$2,410,619
1 PD 50.54(a) O & M Budget Items															
1 PD 50.54(a) Permits & Fees															
1 PD 50.54(a) Waste Transfer and Loading															
1 PD 50.54(a) Energy															
1 PD 50.54(a) Spent Fuel Storage Maintenance Supplies															
1 PD 50.54(a) Shop Tools			\$251,029							\$251,029	\$62,800	\$313,828			
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT			\$251,029							\$2,434,148	\$186,300	\$2,620,448			
DECOMMISSIONING ACTIVITIES															
Primary System Decommissioning															
1 A 50.75(a) Define scope	\$41,838									\$41,838	\$6,200	\$47,838			308
1 A 50.75(a) Evaluate proposals	\$53,024									\$53,024	\$8,000	\$61,024			448
1 A 50.75(a) Prepare bid specifications and RFP	\$52,989									\$52,989	\$7,800	\$60,789			512
1 A 50.75(a) Quality Contractors	\$14,104									\$14,104	\$2,100	\$16,204			112
1 A 50.75(a) Evaluate Proposals	\$38,336									\$38,336	\$5,900	\$44,136			248
Secondary System Decommissioning General Contractor															
1 A 50.75(b) Define scope	\$78,885									\$78,885	\$11,800	\$90,685			738
1 A 50.75(b) Prepare bid specifications and RFP	\$54,019									\$54,019	\$8,000	\$62,019			778
1 A 50.75(b) Quality Contractors	\$21,546									\$21,546	\$3,200	\$24,746			178
1 A 50.75(b) Evaluate Proposals	\$38,336									\$38,336	\$5,800	\$44,136			248
U1 & U2 cask and dry site recovery															
1 A 50.75(c) Define scope	\$94,277									\$94,277	\$13,300	\$107,577			818
1 A 50.75(c) Design modification and equipment specifications	\$150,932									\$150,932	\$22,600	\$173,532			1,568
1 A 50.75(c) Prepare installation procedures	\$212,724									\$212,724	\$31,800	\$244,524			2,088
1 A 50.75(c) Prepare test procedures	\$18,348									\$18,348	\$2,800	\$21,148			182
Modify U1 & U2 containment system															
1 A 50.75(d) Select new access location	\$30,251									\$30,251	\$4,500	\$34,751			288
1 A 50.75(d) Design access and equipment specifications	\$191,593									\$191,593	\$28,000	\$219,593			1,938
U1 & U2 site Characterization															
1 A 50.75(e) Define scope	\$47,781									\$47,781	\$7,200	\$54,981			408
1 A 50.75(e) Prepare bid specifications and RFP	\$53,465									\$53,465	\$8,000	\$61,465			468
1 A 50.75(e) Quality Contractors	\$21,846									\$21,846	\$3,200	\$25,046			178
1 A 50.75(e) Evaluate Proposals	\$38,336									\$38,336	\$5,800	\$44,136			248
1 A 50.75(e) Prepare procedures	\$133,000									\$133,000	\$19,800	\$152,800			1,298
ADMINISTRATIVE ACTIVITIES															
1 A 50.75(f) Develop staff transition plan	\$41,832									\$41,832	\$6,200	\$47,732			382
1 A 50.75(f) Develop evidence and retention policy	\$41,832									\$41,832	\$6,200	\$47,732			382
1 A 50.75(f) Develop project administrative procedures	\$45,028									\$45,028	\$6,800	\$51,828			488
1 A 50.75(f) Develop area based decommissioning cost estimate	\$208,838									\$208,838	\$31,400	\$240,238			2,248
1 A 50.75(f) Develop project budget and schedule controls	\$80,924									\$80,924	\$12,100	\$93,024			848
1 A 50.75(f) Assemble plot drawings	\$24,307									\$24,307	\$3,600	\$27,907			288
1 A 50.75(f) Define end product	\$36,216									\$36,216	\$5,400	\$41,616			388
1 A 50.75(f) Develop technical approach and detailed project plans	\$223,884									\$223,884	\$33,600	\$257,484			2,448

2012 D.C. Cost
Scenario 1
DECON and Remediation On-Site Dry Storage

Line	Item	Staff Labor	Craft Labor	Equipment & Materials	Permitting	Transportation	Class Cleanup	Certification Disposal	Insurance	Other	without Contingency	Contingency	with Contingency	Staff Manpower	Craft Manpower	Craft Machinery
LICENSING/PERMITTING DOCUMENTATION																
1	A 50.75(c) Insurance stipulation	\$48,144									\$48,144	\$6,000	\$54,144	378		
1	A 50.75(c) Prepare Post-Shutdown Decommissioning Activities Report	\$134,089									\$134,089	\$20,200	\$154,289	1,400		
1	A 50.75(c) Prepare certification of permanent cessation of operations	\$8,143									\$8,143	\$600	\$8,743	40		
1	A 50.75(c) Prepare certification of permanent reactor defueling	\$8,143									\$8,143	\$600	\$8,743	40		
1	A 50.75(c) Prepare post-shutdown technical specification modifications	\$355,240									\$355,240	\$50,300	\$405,540	3,600		
1	A 50.75(c) Update PSA	\$211,424									\$211,424	\$48,700	\$260,124	3,900		
1	A 50.75(c) Develop certified fuel handler program	\$38,168									\$38,168	\$5,400	\$43,568	308		
1	A 50.75(c) Prepare post-shutdown emergency plan	\$182,778									\$182,778	\$24,400	\$207,178	1,400		
1	A 50.75(c) Prepare post-shutdown QA plan	\$104,130									\$104,130	\$15,800	\$119,930	1,000		
1	A 50.75(c) Prepare post-shutdown security plan	\$104,130									\$104,130	\$15,800	\$119,930	1,000		
1	A 50.75(c) Prepare post-shutdown fire protection plan	\$104,130									\$104,130	\$15,800	\$119,930	1,000		
1	A 50.75(c) Prepare post-shutdown radiation protection manual	\$104,130									\$104,130	\$15,800	\$119,930	1,000		
1	A 50.75(c) Prepare and submit state and local permits	\$85,422									\$85,422	\$14,200	\$99,622	980		
1	A 50.75(c) Respond to NRC questions re PSDAR	\$4,143									\$4,143	\$800	\$4,943	40		
1	A 50.75(c) Prepare detailed reaction needed project schedule	\$258,157									\$258,157	\$36,400	\$294,557	2,400		
1	A 50.75(c) Perform SDUA reviewed safety questions	\$92,271									\$92,271	\$13,000	\$105,271	700		
1	A 50.75(c) Prepare activity specifications	\$1,700,771									\$1,700,771	\$255,100	\$1,955,871	18,000		
1	A 50.75(c) Prepare detailed work procedures	\$1,604,383									\$1,604,383	\$240,700	\$1,845,083	16,000		
1	A 50.75(c) Select shipping casks and obtain permits	\$24,032									\$24,032	\$3,000	\$27,032	240		
LICENSE TERMINATION PLAN																
1	A 50.75(c) General Information	\$1,380									\$1,380	\$200	\$1,580	18		
1	A 50.75(c) Site Characterization	\$33,067									\$33,067	\$5,100	\$38,167	328		
1	A 50.75(c) Identification of remaining site decommissioning activities	\$33,067									\$33,067	\$5,100	\$38,167	328		
1	A 50.75(c) Remediation Plan	\$17,800									\$17,800	\$2,700	\$20,500	178		
1	A 50.75(c) Final Redaction Survey Plan	\$336,813									\$336,813	\$50,300	\$387,113	3,400		
1	A 50.75(c) Compliance with the radiological criteria for license termination	\$27,508									\$27,508	\$4,100	\$31,608	2,400		
1	A 50.75(c) Update decommissioning cost estimate	\$55,404									\$55,404	\$8,300	\$63,704	568		
1	A 50.75(c) Supplement to the environmental report	\$55,404									\$55,404	\$8,300	\$63,704	568		
1	A 50.75(c) Respond to NRC questions	\$25,883									\$25,883	\$3,800	\$29,683	200		
1	A 50.75(c) Update LTP	\$51,042									\$51,042	\$7,700	\$58,742	628		
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS																
		\$6,088,742									\$6,088,742	\$1,213,000	\$7,301,742	61,348		
DECOMMISSIONING PERIOD DEPENDENT																
1	PD 50.75(c) Utility Staff	\$4,428,012									\$4,428,012	\$684,400	\$5,112,412	78,876		
1	PD 50.75(c) DGC Staff	\$4,483,043									\$4,483,043	\$674,100	\$5,157,143	80,188		
1	PD 50.75(c) Security	\$892,900									\$892,900	\$102,400	\$995,300	23,001		
1	PD 50.75(c) HF Supplies			\$287,900								\$287,900	\$359,800			
1	PD 50.75(c) Equipment			\$192,707								\$192,707	\$240,900			
1	PD 50.75(c) Unit 1 Insulation									\$844,078		\$844,078	\$128,800			
1	PD 50.75(c) Unit 2 Insulation															
1	PD 50.75(c) O & M Budget Items			\$12,095,438							\$12,095,438	\$3,023,000	\$15,118,438			
1	PD 50.75(c) Permits & Fees									\$1,505,191		\$1,505,191	\$225,200			
1	PD 50.75(c) Waste Transfer and Loading															
1	PD 50.75(c) Freight								\$1,292,388		\$1,292,388	\$183,800	\$1,476,188			
1	PD 50.75(c) Scaffolding	\$15,871,828									\$15,871,828	\$2,335,000	\$18,206,828			
1	PD 50.75(c) Scaffolding															
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT																
		\$28,177,442		\$12,538,137					\$1,292,388	\$2,382,287	\$41,368,322	\$7,487,600	\$48,855,922	184,736		
TOTAL PERIOD 1 - 10 CFR 50.75(a)(1) DECOMMISSIONING PLANNING COST																
		\$94,616,870	\$25,102,477	\$17,787,183					\$1,292,388	\$4,535,385	\$77,734,080	\$14,820,500	\$92,554,580	740,980		
ACTIVITY																
UNIT 1 - PERIOD 1 COSTS																
Unit 1 Subtotal 10 CFR 50.75(c):																
Unit 1 Subtotal 10 CFR 50.54(b):																
UNIT 2																
Unit 2 Subtotal 10 CFR 50.75(c):																
Unit 2 Subtotal 10 CFR 50.54(b):																
Common																
Total 10 CFR 50.75(c):																
Total 10 CFR 50.54(b):																
PERIOD DEPENDENT																
UNIT 1 - PERIOD 1 COSTS																
Unit 1 Subtotal 10 CFR 50.75(c):																
Unit 1 Subtotal 10 CFR 50.54(b):																
UNIT 2																
Unit 2 Subtotal 10 CFR 50.75(c):																
Unit 2 Subtotal 10 CFR 50.54(b):																
Common																

2012 D. O. Cores
Scenario 1
BEOC and Permanent On-Off City Storage

Type	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Exclusion \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	Waste Contingency \$	Construction Contingency \$	Waste Contingency \$	Staff Materials	Craft Materials	Craft Materials
Total 10 CFR 50.75(c): Total 10 CFR 50.54(b):			\$261,026						\$2,183,118	\$2,434,143	\$390,390	\$2,934,443			
Unit 1, Unit 2 & Common Total 10 CFR 50.75(c): Total 10 CFR 50.54(b):	\$93,497,183 \$748,487		\$18,896,197 \$261,026					\$1,882,084	\$2,985,287 \$2,183,118	\$40,447,973 \$28,386,167	\$6,070,600 \$6,348,790	\$46,116,479 \$14,639,807	\$28,079 7,884		
PERIOD 2 - POST-SHUTDOWN ACTIVITIES COSTS:															
SPENT FUEL ACTIVITIES															
2 A 50.54(b) Modify Spent Fuel Cooling System			\$834,094	\$1,188,000						\$1,766,094	\$458,430	\$2,224,524		9,360	
2 A 50.54(b) Modify control room			\$582,042	\$800,000						\$1,382,042	\$203,230	\$1,585,272		8,360	
2 A 50.54(b) Modify security system			\$458,755	\$505,000						\$963,755	\$229,830	\$1,193,585		7,280	
2 A 50.54(b) Purchase ISPS seats				\$115,788,000						\$115,788,000	\$28,846,300	\$144,634,300		7,280	
SUBTOTAL - SPENT FUEL ACTIVITIES			\$1,874,891	\$118,278,000						\$118,044,891	\$29,064,560	\$146,938,451		32,280	
SPENT FUEL PERIOD DEPENDENT															
2 PD 50.54(b) Utility Staff	\$4,096,895									\$4,096,895	\$814,800	\$4,911,695	\$8,408		
2 PD 50.54(b) Security	\$1,818,274									\$1,818,274	\$242,400	\$2,060,674	\$3,911		
2 PD 50.54(b) Insurance									\$1,177,888	\$1,177,888	\$178,790	\$1,356,678			
2 PD 50.54(b) O & M Budget Items															
2 PD 50.54(b) Permits & Fees									\$607,100	\$607,100	\$121,100	\$728,200			
2 PD 50.54(b) Waste Transfer and Loading															
2 PD 50.54(b) Energy								\$249,904		\$249,904	\$37,800	\$287,704			
2 PD 50.54(b) Spent Fuel Storage Maintenance Supplies			\$445,472							\$445,472	\$112,100	\$557,572			
2 PD 50.54(b) Small Tools			\$10,719							\$10,719	\$4,300	\$15,019			
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$5,915,069		\$465,191					\$249,904	\$1,885,004	\$8,416,367	\$1,808,830	\$10,734,167	\$11,857		
DECOMMISSIONING ACTIVITIES															
2 A 50.75(c) Primary System Decom Unit 1 & 2			\$8,548,040	\$1,117,080			\$8,665,120			\$18,920,760	\$8,868,850	\$27,789,610			
2 A 50.75(c) Flush & Drain Systems (PERFORMED BY UTILITY STAFF)															
2 A 50.75(c) Equipment cost & drive			\$781,098	\$1,800,000						\$2,581,098	\$524,300	\$3,105,398		11,630	
2 A 50.75(c) Modify UI Containment Access			\$345,437	\$528,000						\$871,437	\$210,800	\$1,082,237		8,760	
2 A 50.75(c) Modify/ID Containment Access			\$345,437	\$528,000						\$871,437	\$210,800	\$1,082,237		8,760	
2 A 50.75(c) Historical Site Assessment		\$276,882								\$276,882	\$66,400	\$343,282		4,860	
2 A 50.75(c) Vessel and Hermalin activation analysis		\$108,308								\$108,308	\$16,400	\$124,708		640	
2 A 50.75(c) Characterization survey		\$768,088								\$768,088	\$118,400	\$886,488		12,880	
2 A 50.75(c) Test special equipment and training			\$938,733							\$938,733	\$215,100	\$1,153,833		13,440	
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$1,274,306	\$10,838,872	\$4,467,880				\$8,966,840			\$28,247,887	\$7,088,280	\$35,336,167	\$8,460	38,460	
DECOMMISSIONING PERIOD DEPENDENT															
2 PD 50.75(c) Utility Staff	\$18,243,380									\$18,243,380	\$2,730,000	\$20,973,380	\$60,870		
2 PD 50.75(c) DDO Staff	\$11,702,745									\$11,702,745	\$1,768,400	\$13,471,145	\$17,040		
2 PD 50.75(c) Security	\$3,208,464									\$3,208,464	\$481,000	\$3,689,464	\$14,374		
2 PD 50.75(c) HP Supplies			\$788,880							\$788,880	\$160,800	\$949,680			
2 PD 50.75(c) Equipment			\$1,019,850							\$1,019,850	\$255,000	\$1,274,850			
2 PD 50.75(c) Unit 1 Insurance									\$284,242	\$284,242	\$88,800	\$373,042			
2 PD 50.75(c) Unit 2 Insurance									\$284,242	\$284,242	\$88,800	\$373,042			
2 PD 50.75(c) O & M Budget Items			\$2,888,773							\$2,888,773	\$721,400	\$3,610,173			
2 PD 50.75(c) Permits & Fees									\$2,075,053	\$2,075,053	\$311,300	\$2,386,353			
2 PD 50.75(c) Waste Transfer and Loading															
2 PD 50.75(c) Energy								\$1,892,489		\$1,892,489	\$288,000	\$2,180,489			
2 PD 50.75(c) Insurance	\$28,300,809									\$28,300,809	\$3,480,100	\$31,780,909			
2 PD 50.75(c) Small Tools			\$218,793							\$218,793	\$34,700	\$253,493			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$48,883,364		\$4,883,883					\$1,892,489	\$2,607,538	\$65,836,454	\$10,381,700	\$76,218,154	\$82,464		
TOTAL PERIOD 2 - POST-SHUTDOWN ACTIVITIES COSTS:	\$69,342,898	\$12,811,063	\$127,840,864				\$8,966,840	\$2,442,372	\$4,692,642	\$218,448,489	\$48,712,200	\$286,188,809	\$72,821	88,760	
ACTIVITY															
UNIT 1															
Unit 1 Subtotal 10 CFR 50.75(c): Unit 1 Subtotal 10 CFR 50.54(b):			\$4,818,457	\$1,233,840			\$4,489,360			\$10,338,317	\$3,083,800	\$13,422,117		8,760	
UNIT 2															
Unit 2 Subtotal 10 CFR 50.75(c): Unit 2 Subtotal 10 CFR 50.54(b):			\$4,818,457	\$1,233,840			\$4,489,360			\$10,338,317	\$3,083,800	\$13,422,117		8,760	
Common															
Common Subtotal - 10 CFR 50.75(c): Common Subtotal - 10 CFR 50.54(b):	\$1,274,306	\$1,790,787	\$1,890,000							\$4,875,092	\$888,600	\$5,763,692	\$6,460	24,880	
		\$1,871,881	\$118,278,000							\$118,044,891	\$29,064,560	\$146,938,451		32,280	

DECON and Permanent On-Site Dry Storage

[illegible]

2012 D. C. Cook
Scenario 1
DECON and Permanent On-Site Dry Storage

Type			Slab Labor	Craft Labor	Equipment & Materials	Permitting	Insurance	Clean Closure	Contaminated Material	Energy	Other	Weld	Contingency	Wm Contingency	Slab Material	Craft Material	Craft Material
PERIOD 6 - CLEAN STRUCTURE DEMOLITION COSTS:																	
SPENT FUEL PERIOD DEPENDENT																	
5	PD 00.54(04)	Utility Staff	\$0,836,932										\$2,836,932	\$305,800	\$0,004,730	\$0,520	
5	PD 00.54(04)	Security	\$1,331,411										\$1,331,411	\$188,700	\$1,531,111	\$3,280	
5	PD 00.54(04)	HP Supplies			\$105,207								\$105,207	\$28,200	\$131,307	\$3,280	
5	PD 00.54(04)	Equipment															
5	PD 00.54(04)	Insurance															
5	PD 00.54(04)	O & M Budget Items										\$266,674	\$266,674	\$40,000	\$306,674		
5	PD 00.54(04)	Permits & Fees															
5	PD 00.54(04)	Waste Transfer and Loading										\$013,393	\$013,393	\$77,000	\$90,393		
5	PD 00.54(04)	Energy								\$6,378				\$6,378	\$1,300	\$8,678	
5	PD 00.54(04)	Spent Fuel Storage Maintenance Supplies			\$280,005								\$280,005	\$50,000	\$330,005		
5	PD 00.54(04)	Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT			\$1,378,344		\$385,272					\$6,378	\$780,067	\$6,044,080	\$780,106	\$5,864,180	\$10,681		
DECOMMISSIONING ACTIVITIES																	
5	A Greenfield	Remove Unit 1 Reactor Building	\$1,491,598	\$803,412			\$041,176	\$3,143,738				\$5,949,921	\$972,100	\$6,942,021		\$4,370	
5	A Greenfield	Remove Unit 2 Reactor Building	\$1,491,598	\$803,412			\$041,176	\$3,143,738				\$5,949,921	\$972,100	\$6,942,021		\$4,370	
5	A Greenfield	Remove Auxiliary Building	\$42,108,553	\$4,013,267			\$1,004,741	\$0,322,088				\$27,005,840	\$5,285,700	\$33,291,540		\$92,452	
5	A Greenfield	Remove Turbine Building	\$6,845,268	\$3,503,651			\$1,143,834	\$6,627,787				\$18,917,639	\$3,785,800	\$23,685,739		\$37,370	
5	A Greenfield	Remove Steam Generator Storage Building	\$198,400	\$88,087			\$52,487	\$304,804				\$843,888	\$109,300	\$953,188		\$3,181	
5	A Greenfield	Remove Electrical Transformers	\$01,083	\$2,808			\$15,844	\$61,000				\$116,815	\$10,800	\$127,615		\$1,889	
5	A Greenfield	Removal of Unit 1 Turbine Generator	\$152,800	\$7,899			\$7,749	\$45,000				\$213,249	\$43,100	\$256,349		\$2,697	
5	A Greenfield	Removal of Unit 1 Main Condenser	\$1,332,869	\$7,427			\$85,013	\$483,546				\$1,618,284	\$374,900	\$2,043,184		\$2,580	
5	A Greenfield	Removal of Unit 2 Turbine Generator	\$152,800	\$7,899			\$7,749	\$45,000				\$213,249	\$43,100	\$256,349		\$2,697	
5	A Greenfield	Removal of Unit 2 Main Condenser	\$1,332,869	\$7,427			\$85,013	\$483,546				\$1,618,284	\$374,900	\$2,043,184		\$2,580	
5	A Greenfield	Removal of Steam Dryer Condensate	\$30,412	\$6,447			\$3,324	\$13,500				\$52,652	\$18,400	\$71,052		\$32	
5	A Greenfield	Remove Administration Building	\$300,780	\$100,703								\$401,483	\$84,800	\$486,283		\$4,489	
5	A Greenfield	Remove Low Level Address Building	\$1,127,891	\$170,868			\$136,818	\$794,863				\$2,210,569	\$438,800	\$2,649,369		\$18,068	
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:				\$28,405,870	\$10,442,813		\$4,218,147	\$24,908,406				\$67,878,738	\$12,481,709	\$80,360,446		\$86,046	
DECOMMISSIONING PERIOD DEPENDENT																	
5	PD Greenfield	Utility Staff	\$1,106,793										\$1,106,793	\$180,800	\$1,287,593	\$9,413	
5	PD Greenfield	DOO Staff	\$7,464,615										\$7,464,615	\$1,203,900	\$8,668,515	\$4,204	
5	PD Greenfield	Security	\$611,912										\$611,912	\$78,800	\$690,712	\$6,640	
5	PD Greenfield	HP Supplies															
5	PD Greenfield	Equipment			\$2,223,437								\$2,223,437	\$950,900	\$3,174,337		
5	PD Greenfield	Unit 1 Insurance										\$291,890	\$291,890	\$39,300	\$331,190		
5	PD Greenfield	Unit 2 Insurance										\$291,890	\$291,890	\$39,300	\$331,190		
5	PD Greenfield	O & M Budget Items			\$62,408												
5	PD Greenfield	Permits & Fees															
5	PD Greenfield	Waste Transfer and Loading			\$2,199,730							\$177,368	\$177,368	\$26,000	\$203,368		
5	PD Greenfield	Energy								\$148,182				\$148,182	\$17,300	\$165,482	
5	PD Greenfield	Insurance	\$3,155,871										\$3,155,871	\$473,400	\$3,629,271		\$1,005
5	PD Greenfield	Small Tools			\$612,100								\$612,100	\$183,000	\$795,100		
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT			\$12,249,139	\$2,199,730	\$2,887,861					\$148,182	\$791,266	\$18,133,482	\$3,182,800	\$21,385,282	\$30,349	\$41,808	
TOTAL PERIOD 6 - CLEAN STRUCTURE DEMOLITION COSTS:			\$16,119,674	\$30,605,600	\$13,440,134		\$4,218,147	\$24,908,406		\$180,894	\$1,461,332	\$86,012,220	\$16,664,509	\$101,676,729	\$38,629	\$88,654	
ACTIVITY																	
UNIT 1																	
Unit 1 Subtotal Greenfield (g):																	
Unit 1 Subtotal 10 CFR 50.54(b):			\$2,867,188	\$010,738	\$633,894		\$3,682,682					\$8,102,421	\$1,380,100	\$9,482,521		\$8,647	
UNIT 2																	
Unit 2 Subtotal Greenfield (g):																	
Unit 2 Subtotal 10 CFR 50.54(b):			\$2,867,188	\$010,738	\$633,894		\$3,682,682					\$8,102,421	\$1,380,100	\$9,482,521		\$8,647	
COMMON																	
Common Subtotal Greenfield (g):																	
Common Subtotal 10 CFR 50.54(b):			\$33,471,587	\$8,808,134			\$2,861,378	\$17,144,242				\$61,371,805	\$8,701,500	\$70,073,305		\$87,791	
PERIOD DEPENDENT																	
UNIT 1																	
Unit 1 Subtotal Greenfield (g):																	
Unit 1 Subtotal 10 CFR 50.54(b):																	
UNIT 2																	
Unit 2 Subtotal Greenfield (g):																	
Unit 2 Subtotal 10 CFR 50.54(b):																	

2012 D.C. Cook
Scenario 1
OSCON and Personnel On-Site Dry Storage

Task	Staff Labor \$	Crane Labor \$	Equipment & Materials \$	Excavation \$	Transportation \$	Clean Channel \$	Contaminated Disposal \$	Remediation \$	Other \$	Without Contamination \$	Contamination \$	With Contamination \$	Staff Materials	Cost Materials	Cost Materials
Common															
Common Subtotal Greenfield (g)	\$12,246,330	\$2,199,735	\$2,887,581					\$148,162	\$701,285	\$18,155,442	\$3,192,500	\$21,385,982	130,348	41,808	
Common Subtotal 10 CFR 80.54(b):	\$3,970,344		\$595,872					\$6,378	\$780,087	\$5,064,060	\$790,100	\$6,854,160	108,091		
Unit 1, Unit 2 & Common															
Total Greenfield (g):	\$12,246,330	\$28,405,263	\$13,349,864		\$4,218,147	\$24,659,408		\$154,540	\$771,285	\$23,770,199	\$15,614,200	\$101,644,398	140,348	486,653	
Total 10 CFR 80.54(b):	\$3,970,344		\$595,872					\$6,378	\$780,087	\$5,064,060	\$790,100	\$6,854,160	108,091		
PERIOD 6 - RESTORE SITE COSTS:										ERROR				ERROR	
SPENT FUEL PERIOD DEPENDENT															
8 PD 80.54(b) Utility Staff	\$296,031									\$296,031	\$44,720	\$340,751	4,463		
8 PD 80.54(b) Security	\$150,385									\$150,385	\$27,600	\$177,985	3,758		
8 PD 80.54(b) HP Supplies			\$10,690							\$10,690	\$2,780	\$13,470	3,739		
8 PD 80.54(b) Insurance									\$30,117	\$30,117	\$4,560	\$34,677			
8 PD 80.54(b) Equipment															
8 PD 80.54(b) O & M Budget Items															
8 PD 80.54(b) Permits & Fees									\$87,981	\$87,981	\$8,700	\$96,681			
8 PD 80.54(b) Waste Transfer and Loading															
8 PD 80.54(b) Energy			\$22,588					\$840		\$840	\$100	\$940			
8 PD 80.54(b) Spent Fuel Storage Maintenance Supplies										\$22,588	\$5,000	\$27,588			
8 PD 80.54(b) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$446,396		\$32,677					\$840	\$88,968	\$670,919	\$88,860	\$859,819	11,960		
DECOMMISSIONING ACTIVITIES															
8 A Greenfield Build, grade and landscape etc		\$168,109								\$168,109	\$38,000	\$206,109		1,757	
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:		\$168,109								\$168,109	\$38,000	\$206,109		1,757	
DECOMMISSIONING PERIOD DEPENDENT															
8 PD Greenfield Utility Staff	\$57,051									\$57,051	\$7,800	\$64,851	640		
8 PD Greenfield OGC Staff	\$260,828									\$260,828	\$86,670	\$347,498	4,698		
8 PD Greenfield Security	\$14,516									\$14,516	\$2,200	\$16,716	628		
8 PD Greenfield HP Supplies															
8 PD Greenfield Equipment			\$74,824							\$74,824	\$18,700	\$93,524			
8 PD Greenfield Unit 1 Insurance									\$39,572	\$39,572	\$4,400	\$43,972			
8 PD Greenfield Unit 2 Insurance									\$28,572	\$28,572	\$4,400	\$32,972			
8 PD Greenfield O & M Budget Items			\$7,949							\$7,949	\$1,600	\$9,549			
8 PD Greenfield Permits & Fees									\$20,054	\$20,054	\$3,000	\$23,054			
8 PD Greenfield Waste Transfer and Loading		\$248,430								\$248,430	\$80,300	\$328,730		4,899	
8 PD Greenfield Energy								\$5,593		\$5,593	\$1,000	\$6,593			
8 PD Greenfield Demolition	\$311,142									\$311,142	\$46,730	\$357,872			
8 PD Greenfield Small Tools			\$8,261							\$8,261	\$3,100	\$11,361			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$768,636	\$248,430	\$83,085					\$6,593	\$79,199	\$1,182,711	\$207,800	\$1,490,511	5,264	4,899	
TOTAL PERIOD 6 - RESTORE SITE COSTS:	\$1,217,932	\$414,539	\$123,440					\$7,593	\$167,286	\$1,835,817	\$234,500	\$2,070,317	16,264	9,499	
ACTIVITY															
UNIT 1															
Unit 1 Subtotal Greenfield (g):															
Unit 1 Subtotal 10 CFR 80.54(b):															
UNIT 2															
Unit 2 Subtotal Greenfield (g):															
Unit 2 Subtotal 10 CFR 80.54(b):															
Common															
Common Subtotal Greenfield (g)		\$185,169								\$185,169	\$38,000	\$223,169		1,757	
Common Subtotal 10 CFR 80.54(b):															
PERIOD DEPENDENT															
UNIT 1															
Unit 1 Subtotal Greenfield (g):															
Unit 1 Subtotal 10 CFR 80.54(b):															
UNIT 2															
Unit 2 Subtotal Greenfield (g):															
Unit 2 Subtotal 10 CFR 80.54(b):															
Common															
Common Subtotal Greenfield (g)	\$768,636	\$248,430	\$83,085					\$6,593	\$79,199	\$1,182,711	\$207,800	\$1,490,511	5,264	4,899	

2012 D. C. Cost
Scenario 1
DECON and Permanent On-Site Dry Storage

Item	Staff Labor \$	Crane Labor \$	Equipment Materials \$	Paints/Seals \$	Transportation \$	Clean Materials \$	Construction Materials \$	Excavation \$	Other \$	without Containment \$	Containment \$	with Containment \$	Steel Manhours	Crane Manhours	Crane Manhours
SUBTOTAL COMMON 10 CFR 50.54(b)(1) COSTS FOR PERIODS 1-6	\$38,443,937		\$2,838,898					\$788,057	\$12,742,173	\$81,813,165	\$3,058,880	\$89,895,965	782,734		
SUBTOTAL COMMON GREENFIELD COSTS FOR PERIODS 1-6	\$13,014,967	\$2,448,103	\$2,807,814					\$164,745	\$790,484	\$18,389,249	\$9,400,160	\$27,789,409	136,612	46,807	
ANNUAL SPENT FUEL STORAGE	\$2,977,876		\$361,409					\$9,289	\$685,034	\$3,936,422	\$643,460	\$4,477,882	\$4,600		
UNIT 1, UNIT 2 & COMMON															
GRAND TOTAL ACTIVITY COSTS FOR PERIODS 1-6	\$10,214,127	\$162,191,735	\$256,872,885	\$1,282,783	\$26,960,377	\$26,960,369	\$191,363,181			\$678,873,067	\$193,712,100	\$869,785,167	108,100	1,977,447	1,162,726
GRAND TOTAL PERIOD DEPENDENT COSTS FOR PERIODS 1-6	\$290,488,152	\$17,351,170	\$52,154,832					\$14,052,471	\$31,659,487	\$388,684,182	\$69,839,906	\$451,524,088	\$,565,492	46,307	289,814
ANNUAL SPENT FUEL STORAGE	\$2,977,876		\$361,409					\$8,282	\$985,034	\$3,936,422	\$643,460	\$4,477,882	\$4,600		
GRAND TOTAL	\$290,700,379	\$182,123,905	\$309,437,187	\$1,282,783	\$28,585,377	\$28,585,369	\$191,363,181	\$14,052,471	\$31,659,487	\$1,071,767,189	\$268,848,906	\$1,341,605,498	\$,658,492	1,129,754	1,392,642
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 50.75(d)	\$26,177,442	\$27,368,348	\$16,482,497	\$581,884	\$10,823,303		\$87,544,088	\$1,292,388	\$2,952,267	\$171,842,940	\$60,206,660	\$232,049,510	154,736	8,785	431,164
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (g)		\$12,585,492	\$1,319,137		\$793,182	\$4,498,326				\$19,187,007	\$3,853,600	\$23,040,607		240,864	
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 50.75(d)	\$61,281	\$95,601,548	\$4,327,430	\$640,627	\$10,383,879		\$84,851,389			\$148,968,303	\$47,320,660	\$196,288,963		8,785	688,787
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 50.84(b)(1)															
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (g)		\$25,784,486	\$1,785,182		\$929,425	\$5,197,350				\$28,706,583	\$9,828,000	\$38,534,583		405,621	
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 50.75(d)	\$216,283,215	\$32,420,758	\$36,440,191	\$30,222	\$282,353		\$8,487,851	\$11,817,283	\$15,784,054	\$311,484,818	\$68,261,860	\$379,746,678	2,398,816	24,980	378,711
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 50.84(b)(1)	\$96,183,424	\$28,774,968	\$236,889,898					\$780,067	\$12,742,173	\$813,817,018	\$73,815,000	\$887,632,018	770,020	93,280	
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (g)	\$13,014,967	\$25,139,610	\$11,835,997		\$2,882,184	\$17,287,483		\$154,745	\$785,484	\$71,182,430	\$13,184,600	\$84,367,030	126,612	407,808	
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 50.75(d)	\$241,491,958	\$54,790,661	\$57,269,463	\$1,282,783	\$21,800,435		\$91,363,181	\$13,106,649	\$18,195,201	\$329,654,061	\$142,076,860	\$471,730,921	\$,151,942	35,490	1,195,642
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 50.84(b)(1)	\$36,193,424	\$28,774,968	\$236,889,898					\$798,067	\$12,742,173	\$815,567,018	\$73,815,000	\$889,382,018	770,020	93,280	
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (g)	\$13,014,967	\$25,139,610	\$11,835,997		\$2,882,184	\$17,287,483		\$154,745	\$790,484	\$71,182,430	\$13,184,600	\$84,367,030	126,612	1,063,894	
GRAND TOTAL	\$290,700,379	\$182,123,905	\$309,437,187	\$1,282,783	\$28,585,377	\$28,585,369	\$191,363,181	\$14,052,471	\$31,659,487	\$1,071,767,189	\$268,848,906	\$1,341,605,498	\$,658,492	1,129,754	1,392,642

2012 D. C. Cook
Scenario 2
DECON, Permanent Off-Site Dry Storage

Type	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	Subtotal without Contingency \$	Contingency \$	Total with Contingency \$	Staff Manhours	Clean Craft Manhours	Contaminated Craft Manhours
PERIOD 1 - U1 & U2 DECOMMISSIONING PLANNING COST:															
SPENT FUEL ACTIVITIES															
1 A 50.54(ba) Modify spent fuel support systems										882,772	\$0.00	\$72,172	808		
1 A 50.54(ba) Define systems modification										\$147,893	\$22,200	\$169,893	1,588		
1 A 50.54(ba) Design systems modification and equipment specifications										\$16,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Prepare installation procedures										\$16,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Prepare test procedures										\$16,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Prepare maintenance procedures										\$16,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Control room relocation										882,772	\$0.00	\$72,172	808		
1 A 50.54(ba) Define control room equipment										\$178,862	\$28,800	\$205,762	1,880		
1 A 50.54(ba) Design control room modification and equipment specifications										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Prepare installation procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Prepare test procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Prepare maintenance procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Design spent fuel storage security modifications										\$29,408	\$4,400	\$33,808	208		
1 A 50.54(ba) Define modification										\$102,741	\$15,400	\$118,141	1,016		
1 A 50.54(ba) Design modification and equipment specifications										\$16,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Prepare installation procedures										\$16,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Prepare test procedures										\$16,349	\$2,800	\$21,149	192		
1 A 50.54(ba) Prepare maintenance procedures										\$16,349	\$2,800	\$21,149	192		
SUBTOTAL - SPENT FUEL ACTIVITIES										\$748,487	\$112,800	\$862,287	7,712		
SPENT FUEL PERIOD DEPENDENT															
1 PD 50.54(ba) Utility Staff															
1 PD 50.54(ba) Security															
1 PD 50.54(ba) Insurance									\$2,183,119	\$2,183,119	\$327,500	\$2,510,619			
1 PD 50.54(ba) O & M Budget Items															
1 PD 50.54(ba) Permits & Fees															
1 PD 50.54(ba) Waste Transfer and Loading															
1 PD 50.54(ba) Energy															
1 PD 50.54(ba) Spent Fuel Storage Maintenance Supplies															
1 PD 50.54(ba) Offsite spent fuel storage									\$41,370,806	\$41,370,806	\$6,205,000	\$47,575,106			
1 PD 50.54(ba) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT									\$43,553,825	\$43,553,825	\$6,833,100	\$50,386,925			
DECOMMISSIONING ACTIVITIES															
1 A 50.75(e) Primary system decontamination															
1 A 50.75(e) Define scope										\$41,838	\$6,200	\$47,538	328		
1 A 50.75(e) Evaluate processes										\$53,024	\$8,000	\$61,024	448		
1 A 50.75(e) Prepare bid specifications and RFP										\$52,888	\$7,900	\$60,788	612		
1 A 50.75(e) Qualify Contractors										\$14,104	\$2,100	\$16,204	112		
1 A 50.75(e) Evaluate Proposals										\$36,338	\$5,600	\$41,138	248		
1 A 50.75(e) Select Decommissioning General Contractor										\$79,863	\$11,900	\$91,563	736		
1 A 50.75(e) Define scope										\$64,613	\$12,000	\$76,613	770		
1 A 50.75(e) Prepare bid specifications and RFP										\$21,646	\$3,200	\$24,846	176		
1 A 50.75(e) Qualify Contractors										\$36,338	\$5,600	\$41,138	248		
1 A 50.75(e) Evaluate Proposals										\$68,277	\$10,200	\$78,477	618		
1 A 50.75(e) U1 & U2 cold and dark site repowering										\$150,932	\$22,900	\$173,832	1,580		
1 A 50.75(e) Define scope										\$212,724	\$31,600	\$244,624	2,060		
1 A 50.75(e) Design modification and equipment specifications										\$18,349	\$2,800	\$21,149	192		
1 A 50.75(e) Prepare installation procedures															
1 A 50.75(e) Prepare test procedures															
1 A 50.75(e) Prepare maintenance procedures															
1 A 50.75(e) Modify U1 & U2 containment access										\$30,351	\$4,600	\$34,751	208		
1 A 50.75(e) Select new access location										\$133,533	\$20,000	\$153,533	1,320		
1 A 50.75(e) Design access and equipment specifications															
1 A 50.75(e) U1 & U2 Site Characterization										\$47,781	\$7,200	\$54,981	408		
1 A 50.75(e) Define scope										\$63,488	\$9,000	\$72,488	496		
1 A 50.75(e) Prepare bid specifications and RFP										\$21,848	\$3,200	\$24,848	176		
1 A 50.75(e) Qualify Contractors										\$36,338	\$5,600	\$41,138	248		
1 A 50.75(e) Evaluate Proposals										\$133,000	\$19,900	\$152,900	1,280		
1 A 50.75(e) Prepare procedures															
ADMINISTRATIVE ACTIVITIES															
1 A 50.75(e) Develop staff transition plan										\$41,532	\$6,200	\$47,732	362		
1 A 50.75(e) Develop severance and retention policy										\$41,532	\$6,200	\$47,732	362		
1 A 50.75(e) Prepare project administrative procedures										\$45,028	\$6,800	\$51,828	408		
1 A 50.75(e) Develop area based decommissioning cost estimates										\$209,036	\$31,400	\$240,436	2,240		
1 A 50.75(e) Develop project budget and schedule controls										\$60,924	\$9,100	\$70,024	648		

2012 D. C. Cook
Scenario 2
DECON, Permanent Off-Site Dry Storage

Type	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	without Contingency \$	Contingency \$	with Contingency \$	Staff Manhours	Craft Manhours	Craft Manhours
1 A 60.75(c) Assemble plant drawings	\$24,307									\$24,307	\$3,800	\$27,907	280		
1 A 60.75(c) Define and produce	\$38,216									\$38,216	\$5,400	\$41,816	280		
1 A 60.75(c) Develop technical approach and detailed project plan	\$223,854									\$223,854	\$33,000	\$257,454	2,440		
LICENSING/PERMITTING DOCUMENTATION															
1 A 60.75(c) Insurance exemption	\$46,144									\$46,144	\$6,900	\$53,044	370		
1 A 60.75(c) Prepare Post-Shutdown Decommissioning Activities Report	\$134,588									\$134,588	\$20,200	\$154,788	1,400		
1 A 60.75(c) Prepare certification of permanent cessation of operations	\$6,143									\$6,143	\$900	\$7,043	40		
1 A 60.75(c) Prepare certification of permanent reactor shuttling	\$6,143									\$6,143	\$900	\$7,043	40		
1 A 60.75(c) Prepare post-shutdown technical specification modifications	\$335,240									\$335,240	\$50,300	\$385,540	3,800		
1 A 60.75(c) Update FSAR	\$311,424									\$311,424	\$46,700	\$358,124	3,300		
1 A 60.75(c) Develop certified fuel handler program	\$36,168									\$36,168	\$5,400	\$41,568	336		
1 A 60.75(c) Prepare post-shutdown emergency plan	\$152,776									\$152,776	\$24,400	\$177,176	1,400		
1 A 60.75(c) Prepare post-shutdown QA plan	\$104,136									\$104,136	\$15,800	\$119,736	1,000		
1 A 60.75(c) Prepare post-shutdown security plan	\$104,136									\$104,136	\$15,800	\$119,736	1,000		
1 A 60.75(c) Prepare post-shutdown fire protection plan	\$104,136									\$104,136	\$15,800	\$119,736	1,000		
1 A 60.75(c) Prepare post-shutdown radiation protection manual	\$104,136									\$104,136	\$15,800	\$119,736	1,000		
1 A 60.75(c) Prepare and submit state and local permits	\$95,422									\$95,422	\$14,300	\$109,722	960		
1 A 60.75(c) Respond to NRC questions on PSDAR	\$6,143									\$6,143	\$900	\$7,043	40		
1 A 60.75(c) Prepare detailed resources loaded project schedule	\$256,157									\$256,157	\$38,400	\$294,557	2,480		
1 A 60.75(c) Perform 50.55 unreviewed safety questions	\$62,271									\$62,271	\$13,800	\$76,071	736		
1 A 60.75(c) Prepare activity specific costs	\$1,700,771									\$1,700,771	\$255,100	\$1,955,871	18,080		
1 A 60.75(c) Prepare detailed work procedures	\$1,804,383									\$1,804,383	\$240,700	\$2,045,083	18,080		
1 A 60.75(c) Select shipping casks and obtain permits	\$24,032									\$24,032	\$3,800	\$27,832	240		
LICENSE TERMINATION PLAN															
1 A 60.75(c) Generate information	\$1,350									\$1,350	\$200	\$1,550	16		
1 A 60.75(c) Site Characterization	\$33,967									\$33,967	\$5,100	\$39,067	336		
1 A 60.75(c) Identification of remaining site dismantlement activities	\$33,967									\$33,967	\$5,100	\$39,067	336		
1 A 60.75(c) Remediation Plans	\$17,880									\$17,880	\$2,700	\$20,580	176		
1 A 60.75(c) Final Radiation Survey Plan	\$330,813									\$330,813	\$50,800	\$381,613	3,020		
1 A 60.75(c) Compliance with the radiological criteria for license termination	\$227,508									\$227,508	\$34,100	\$261,608	2,440		
1 A 60.75(c) Update decommissioning cost estimate	\$55,404									\$55,404	\$8,300	\$63,704	696		
1 A 60.75(c) Supplement to the environmental report	\$55,404									\$55,404	\$8,300	\$63,704	696		
1 A 60.75(c) Respond to NRC questions	\$25,860									\$25,860	\$3,900	\$29,760	200		
1 A 60.75(c) Update LTP	\$51,042									\$51,042	\$7,700	\$58,742	536		
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:															
	\$8,889,742									\$8,889,742	\$1,213,900	\$10,103,642	81,340		
DECOMMISSIONING PERIOD DEPENDENT															
1 PD 60.75(c) Utility Staff	\$4,429,012									\$4,429,012	\$684,400	\$5,113,412	75,075		
1 PD 60.75(c) DGC Staff	\$4,493,843									\$4,493,843	\$674,100	\$5,167,943	58,168		
1 PD 60.75(c) Security	\$802,860									\$802,860	\$102,400	\$905,260	20,061		
1 PD 60.75(c) HP Supplies	\$287,905		\$287,905							\$287,905	\$72,000	\$359,905			
1 PD 60.75(c) Equipment	\$162,797		\$162,797							\$162,797	\$38,200	\$199,997			
1 PD 60.75(c) Unit 1 Insurance									\$844,078		\$126,800	\$670,678			
1 PD 60.75(c) Unit 2 Insurance															
1 PD 60.75(c) O & M Budget Items			\$12,095,435							\$12,095,435	\$3,023,900	\$15,119,335			
1 PD 60.75(c) Permits & Fees									\$1,508,191	\$1,508,191	\$228,200	\$1,736,391			
1 PD 60.75(c) Waste Transfer and Loading															
1 PD 60.75(c) Energy								\$1,292,388		\$1,292,388	\$193,800	\$1,486,188			
1 PD 60.75(c) Severance	\$10,571,825									\$10,571,825	\$2,339,800	\$12,911,625			
1 PD 60.75(c) Small Tools															
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT															
	\$26,177,442		\$12,834,137					\$1,292,388	\$2,352,287	\$41,268,232	\$7,487,890	\$48,816,732	154,738		
TOTAL PERIOD 1 - U1 & U2 DECOMMISSIONING PLANNING COSTS:															
	\$34,816,879		\$12,834,137					\$1,292,388	\$46,098,891	\$93,781,884	\$16,316,488	\$110,097,486	243,788		
ACTIVITY															
UNIT 1 - PERIOD 1 COSTS															
Unit 1 Subtotal 10 CFR 60.75(c):															
Unit 1 Subtotal 10 CFR 60.44(b):															
UNIT 2															
Unit 2 Subtotal 10 CFR 60.75(c):															
Unit 2 Subtotal 10 CFR 60.44(b):															
Common															
Total 10 CFR 60.75(c):															
Total 10 CFR 60.44(b):															
PERIOD DEPENDENT															
UNIT 1 - PERIOD 1 COSTS															
Unit 1 Subtotal 10 CFR 60.75(c):															
Unit 1 Subtotal 10 CFR 60.44(b):															

2012 D. C. Cook
Scenario 2
DECON. Permanent Off-Site Dry Storage

Time	Staff Labor	Craft Labor	Equipment & Materials	Packaging	Transportation	Clean Disposal	Contaminated Disposal	Energy	Other	without Contingency	Contingency	with Contingency	Staff Manhours	Craft Manhours	Craft Manhours
UNIT 2															
Unit 2 Subtotal 10 CFR 60.76(c):															
Unit 2 Subtotal 10 CFR 60.64(d):															
Common															
Total 10 CFR 60.76(c):															
Total 10 CFR 60.64(d):															
Unit 1, Unit 2 & Common															
Total 10 CFR 60.76(c):															
Total 10 CFR 60.64(d):															
PERIOD 2 - POST-SHUTDOWN ACTIVITIES COSTS:															
SPENT FUEL ACTIVITIES															
2	A 50.54(b)	Modify Spent Fuel Cooling System	\$514,094	\$1,165,000						\$1,799,094	\$434,200	\$2,233,294		9,360	
2	A 50.54(b)	Modify control room	\$692,042	\$690,000						\$1,382,042	\$301,800	\$1,713,842		8,300	
2	A 50.54(b)	Modify security system	\$465,785	\$525,000						\$980,785	\$234,000	\$1,214,785		7,280	
SUBTOTAL - SPENT FUEL ACTIVITIES															
SPENT FUEL PERIOD DEPENDENT															
2	PD 50.54(b)	Utility Staff	\$4,068,895							\$4,068,895	\$614,300	\$4,713,795	68,408		
2	PD 50.54(b)	Security	\$1,010,274							\$1,010,274	\$242,400	\$1,058,674	43,531		
2	PD 50.54(b)	Insurance							\$1,177,898	\$1,177,898	\$178,700	\$1,356,598			
2	PD 50.54(b)	O & M Budget Items													
2	PD 50.54(b)	Permits & Fees							\$807,108	\$807,108	\$121,100	\$928,208			
2	PD 50.54(b)	Waste Transfer and Loading													
2	PD 50.54(b)	Energy						\$247,858		\$247,858	\$37,200	\$285,058			
2	PD 50.54(b)	Spent Fuel Storage Maintenance Supplies		\$448,472						\$448,472	\$112,100	\$560,572			
2	PD 50.54(b)	Critical spent fuel storage							\$30,015,880	\$30,015,880	\$4,822,400	\$35,458,280			
2	PD 50.54(b)	Small Tools		\$16,719						\$16,719	\$4,200	\$20,919			
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT															
DECOMMISSIONING ACTIVITIES															
2	A 50.76(c)	Primary System Decon Unit 1 & 2	\$5,546,040	\$1,417,080			\$8,000,840			\$18,020,780	\$5,852,500	\$24,582,280			
2	A 50.76(c)	Flash & Drain Systems (PERFORMED BY UTILITY STAFF)													
2	A 50.76(c)	Implement cold & start	\$761,035	\$1,000,000						\$2,261,035	\$571,800	\$2,832,835		11,620	
2	A 50.76(c)	Modify U1 Containment Access	\$346,437	\$626,000						\$971,437	\$269,400	\$1,080,837		5,780	
2	A 50.76(c)	Modify U2 Containment Access	\$346,437	\$625,000						\$971,437	\$269,400	\$1,080,837		5,780	
2	A 50.76(c)	Hydrological Site Assessment	\$575,862							\$575,862	\$88,400	\$664,262	4,680		
2	A 50.76(c)	Vessel and Internals activation analysis	\$109,335							\$109,335	\$16,400	\$125,735	940		
2	A 50.76(c)	Characterization survey	\$769,089							\$769,089	\$118,400	\$907,489	12,880		
2	A 50.76(c)	Test special equipment and training		\$836,723						\$836,723	\$211,500	\$1,051,023		13,440	
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:															
DECOMMISSIONING PERIOD DEPENDENT															
2	PD 50.76(c)	Utility Staff	\$18,243,380							\$18,243,380	\$2,756,650	\$20,979,880	305,570		
2	PD 50.76(c)	DGC Staff	\$11,702,745							\$11,702,745	\$1,785,400	\$13,488,145	157,540		
2	PD 50.76(c)	Security	\$3,206,454							\$3,206,454	\$491,000	\$3,697,454	124,374		
2	PD 50.76(c)	HP Supplies		\$756,500						\$756,500	\$186,000	\$942,500			
2	PD 50.76(c)	Equipment		\$1,016,796						\$1,016,796	\$254,700	\$1,271,496			
2	PD 50.76(c)	Unit 1 Insurance							\$286,242	\$286,242	\$39,900	\$326,142			
2	PD 50.76(c)	Unit 2 Insurance							\$286,242	\$286,242	\$39,900	\$326,142			
2	PD 50.76(c)	O & M Budget Items		\$2,686,773						\$2,686,773	\$721,400	\$3,408,173			
2	PD 50.76(c)	Permits & Fees							\$2,075,053	\$2,075,053	\$311,300	\$2,386,353			
2	PD 50.76(c)	Waste Transfer and Loading													
2	PD 50.76(c)	Energy						\$1,892,469		\$1,892,469	\$298,300	\$2,201,369			
2	PD 50.76(c)	Severance	\$23,200,808							\$23,200,808	\$3,480,100	\$26,680,908			
2	PD 50.76(c)	Small Tools		\$218,793						\$218,793	\$54,700	\$273,493			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT															
TOTAL PERIOD 2 - POST-SHUTDOWN ACTIVITIES COSTS:															
ACTIVITY															
UNIT 1:															
Unit 1 Subtotal 10 CFR 60.76(c):															
Unit 1 Subtotal 10 CFR 60.64(d):															
UNIT 2															
Unit 2 Subtotal 10 CFR 60.76(c):															
Unit 2 Subtotal 10 CFR 60.64(d):															
UNIT 1, Unit 2 & Common															
Total 10 CFR 60.76(c):															
Total 10 CFR 60.64(d):															

2012 D. C. Cook
Scenario 2
DECON, Permanent Off-Site Dry Storage

Type	Staff Labor, \$	Craft Labor, \$	Equipment & Materials, \$	Packaging, \$	Impedation, \$	Clean Disposal, \$	Contaminated Disposal, \$	Energy, \$	Other, \$	without Contingency, \$	Contingency, \$	with Contingency, \$	Staff Manhours	Craft Manhours	Craft Manhours
UNIT 1 Subtotal to CFR 60.54(bb):															
UNIT 2															
Unit 2 Subtotal to CFR 60.75(c):		\$4,619,467	\$1,233,540				\$4,483,328			\$40,338,217	\$3,638,668	\$13,371,887		6,710	
Unit 2 Subtotal to CFR 60.54(bb):															
Common															
Common Subtotal - 10 CFR 60.75(c):	\$1,274,308	\$1,708,737	\$1,608,009							\$4,876,062	\$974,708	\$5,850,770	18,400	24,990	
Common Subtotal - 10 CFR 60.54(bb):		\$1,871,891	\$2,490,909							\$4,161,891	\$998,309	\$5,160,200		25,000	
PERIOD DEPENDENT															
UNIT 1															
Unit 1 Subtotal to CFR 60.75(c):															
Unit 1 Subtotal to CFR 60.54(bb):															
UNIT 2															
Unit 2 Subtotal to CFR 60.75(c):															
Unit 2 Subtotal to CFR 60.54(bb):															
Common															
Common Subtotal - 10 CFR 60.75(c):	\$26,383,264		\$4,811,883					\$1,992,488	\$2,407,438	\$66,336,264	\$10,363,400	\$76,188,664	882,484		
Common Subtotal - 10 CFR 60.54(bb):	\$8,718,285		\$468,191					\$247,888	\$32,800,883	\$38,229,282	\$5,830,909	\$44,160,191	111,837		
Unit 1, Unit 2 & Common															
Total - 10 CFR 60.75(c):	\$37,627,888	\$19,838,872	\$8,948,873				\$8,398,449	\$1,992,488	\$2,407,438	\$81,882,961	\$17,408,400	\$108,482,361	890,884	35,430	
Total - 10 CFR 60.54(bb):	\$9,718,285	\$1,871,891	\$2,959,091					\$247,888	\$32,800,883	\$43,361,682	\$6,830,400	\$50,192,082	111,837	26,030	
PERIOD 3 VESSEL AND INTERNALS REMOVAL COSTS:															
SPENT FUEL PERIOD DEPENDENT															
3 PD 60.54(bb) Utility Staff	\$12,095,168									\$12,095,168	\$1,949,300	\$14,044,468	216,688		
3 PD 60.54(bb) Security	\$5,124,120									\$5,124,120	\$788,600	\$5,912,720	104,010		
3 PD 60.54(bb) Insurance									\$3,734,324	\$3,734,324	\$500,100	\$4,234,424			
3 PD 60.54(bb) O & M Budget Items															
3 PD 60.54(bb) Permits & Fees									\$2,558,793	\$2,558,793	\$383,800	\$2,942,593			
3 PD 60.54(bb) Waste Transfer and Loading															
3 PD 60.54(bb) Energy								\$507,172		\$507,172	\$76,100	\$583,272			
3 PD 60.54(bb) Spent Fuel Storage Maintenance Supplies			\$1,421,805							\$1,421,805	\$358,500	\$1,777,305			
3 PD 60.54(bb) Offsite spent fuel storage									\$128,782,421	\$128,782,421	\$19,318,900	\$148,101,321			
3 PD 60.54(bb) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$18,119,288		\$1,421,805					\$507,172	\$136,086,538	\$166,153,891	\$23,412,300	\$178,646,191	406,878		
DECOMMISSIONING ACTIVITIES															
UNIT 1															
3 A 50.75(c) Install all reactor operating floor contamination control envelopes (CCEn), support structures, piping, internal work platforms and process equipment (BY UTILITY STAFF)															
3 A 50.75(c) Finalize Radiological Inventory (WITH SITE CHARACTERIZATION)															
3 A 50.75(c) Finalize Internals and Vessel Segmentation Details (WITH ACTIVATION ANALYSIS)															
3 A 50.75(c) Remove, pack, ship and bury Unit 1 Pressurizer		\$1,018,043		\$800	\$72,384		\$889,362			\$1,880,590	\$583,500	\$2,574,080		18,775	
3 A 50.75(c) Decom, remove, package, ship and bury Unit 1 steam generators		\$4,280,772	\$1,092,887	\$12,800	\$633,257		\$12,054,598			\$18,284,094	\$5,955,500	\$24,239,594		78,183	
3 A 50.75(c) Remove Unit 1 equipment hatch closure (BY UTILITY STAFF)															
3 A 50.75(c) Remove Unit 1 control rod drive and reactor cavity missile shields (BY UTILITY STAFF)															
3 A 50.75(c) Remove Unit 1 CRD mechanisms and cables, air ducts, and reactor spent head (BY UTILITY STAFF)															
3 A 50.75(c) Remove, segment, package and bury Unit 1 vessel & vessel head insulation		\$174,720					\$380,040			\$554,760	\$171,000	\$725,760			
3 A 50.75(c) Prepare Unit 1 vessel head for shipment as its own container (WITH VESSEL REMOVAL)															
3 A 50.75(c) Decontaminate and clean up Unit 1 plant areas (BY UTILITY STAFF)															
3 A 50.75(c) Process liquid and solid radioactive wastes (BY UTILITY STAFF)															
3 A 50.75(c) Decom, remove, package, ship and dispose of Unit 1 contaminated systems		\$9,905,752	\$432,990	\$58,855	\$431,288		\$10,778,182			\$18,002,067	\$5,280,900	\$23,282,967		182,216	182,371
3 A Greenfield Remove, package, ship and dispose of Unit 1 clean systems		\$9,508,705	\$800,388		\$158,718		\$819,444			\$11,084,598	\$2,638,100	\$13,730,698			
3 A 50.75(c) Install Unit 1 water cleanup system in fuel transfer canal (BY UTILITY STAFF)															
3 A 50.75(c) Segment, package and ship Unit 1 internals as radioactive waste		\$2,591,854	\$802,830	\$81,000	\$4,574,880		\$33,431,861			\$41,182,335	\$14,283,700	\$55,466,035		47,380	
3 A 50.75(c) Decontaminate internal work platforms and store (BY UTILITY STAFF)															
3 A 50.75(c) Install Unit 1 vessel support structure (WITH VESSEL REMOVAL)															
3 A 50.75(c) Segment and process Unit 1 reactor vessel and associated equipment as LLW		\$1,352,522	\$141,451	\$24,000	\$2,636,282		\$14,827,158			\$18,164,413	\$6,385,800	\$24,470,213		24,820	
3 A 50.75(c) Decontaminate reactor vessel platform and store															
3 A 50.75(c) Decontaminate Unit 1 reactor building		\$4,416,224	\$553,223	\$416,430	\$2,672,802		\$19,022,464			\$21,960,182	\$7,091,300	\$28,051,482		80,878	
UNIT 2															
3 A 50.75(c) Finalize Radiological Inventory (WITH SITE CHARACTERIZATION)															

2012 O. C. Cook
Scenario 2
DECON, Permanent Off-Site Dry Storage

	Type	Finalize Internals and Vessel Segmenting Details (WITH ACTIVATION ANALYSIS)	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Package \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	without Contingency \$	Contingency \$	with Contingency \$	Unit Measures	Craft Machines	Craft Manhours
3	A 50.75(a)	Finalize Internals and Vessel Segmenting Details (WITH ACTIVATION ANALYSIS)															
3	A 50.75(a)	Revise Integrated Work Sequences and Schedule	\$51,231									\$51,231	\$7,700	\$58,931			
3	A 50.75(a)	Transfer all reactor operating floor COCs support structures, rigging, internals, work platforms and process equipment to position and install (BY UTILITY STAFF)															
3	A 50.75(a)	Remove Unit 2 equipment hatch covers (BY UTILITY STAFF)															
3	A 50.75(a)	Remove Unit 2 CRD missile and reactor cavity missile shields (BY UTILITY STAFF)															
3	A 50.75(a)	Remove Unit 2 CRD neocenters and cables, air ducts, and reactor vessel head (BY UTILITY STAFF)															
3	A 50.75(a)	Remove, rigging, package and bury Unit 2 vessel & vessel head insulation		\$174,720					\$350,040			\$524,760	\$171,000	\$695,760			
3	A 50.75(a)	Prepare Unit 2 vessel head for shipment on its own cradle (WITH VESSEL REMOVAL)															
3	A 50.75(a)	Decontaminate and clean up Unit 2 plant areas (BY UTILITY STAFF)															
3	A 50.75(a)	Process liquid and solid radioactive wastes (BY UTILITY STAFF)															
3	A 50.75(a)	Install Unit 2 water cleanup system to fuel transfer canal (BY UTILITY STAFF)															
3	A 50.75(a)	Segment, package and ship Unit 2 internals to radioactive waste	\$2,691,654		\$502,630	\$81,000	\$4,574,650		\$33,431,961			\$41,132,335	\$14,253,700	\$55,386,035			47,360
3	A 50.75(a)	Decontaminate internal work platform and process as LLW (BY UTILITY STAFF)															
3	A 50.75(a)	Install Unit 2 vessel support structure (WITH VESSEL REMOVAL)															
3	A 50.75(a)	Segment and process Unit 2 reactor vessel and associated equipment as LLW	\$1,362,572		\$141,461	\$24,000	\$2,338,204		\$14,627,150			\$16,194,413	\$6,235,000	\$22,429,413			24,620
3	A 50.75(a)	Decon reactor vessel outlet equipment and work platform, package and process as LLW (WT)															
3	A 50.75(a)	Decon, rigging, package, ship and bury Unit 2 clean generators	\$4,200,772		\$1,002,667	\$12,600	\$833,267		\$12,664,809			\$16,294,094	\$5,255,800	\$21,549,894			70,100
3	A 50.75(a)	Remove, pack, ship and bury Unit 2 Pressurizer	\$1,018,043		\$800	\$72,094			\$890,252			\$1,690,589	\$533,500	\$2,224,089			18,775
3	A 50.75(a)	Decontaminate non-essential structures	\$136,263		\$66,649	\$10,496	\$42,704		\$121,095			\$108,222	\$138,400	\$246,622			2,242
3	A Greenfield	Remove non-essential structures	\$111,101		\$42,947	\$10,897		\$63,241				\$228,175	\$44,500	\$272,675		1,694	
		SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$41,321	\$42,422,487	\$4,204,686	\$720,900	\$10,378,647	\$63,241	\$146,790,826			\$212,687,817	\$89,942,890	\$302,630,707		\$85,911	\$63,323
		DECOMMISSIONING PERIOD DEPENDENT															
3	PD 50.75(a)	Utility Staff	\$39,965,935									\$39,965,935	\$5,000,400	\$44,966,335	630,860		
3	PD 50.75(a)	DGC Staff	\$44,280,851									\$44,280,851	\$8,842,100	\$53,122,951	594,088		
3	PD 50.75(a)	Security	\$5,202,258									\$5,202,258	\$793,000	\$6,000,000	104,010		
3	PD 50.75(a)	HP Supplies			\$8,000,157							\$8,000,157	\$2,001,300	\$10,001,457			
3	PD 50.75(a)	Equipment			\$4,776,051							\$4,776,051	\$1,104,800	\$5,880,851			
3	PD 50.75(a)	Unit 1 Insurance									\$844,076	\$844,076	\$126,600	\$970,676			
3	PD 50.75(a)	Unit 2 Insurance									\$844,076	\$844,076	\$126,600	\$970,676			
3	PD 50.75(a)	O & M Budget Items			\$2,077,376							\$2,077,376	\$516,300	\$2,593,676			
3	PD 50.75(a)	Permits & Fees									\$6,157,842	\$6,157,842	\$923,790	\$7,081,632			
3	PD 50.75(a)	Waste Transfer and Loading		\$6,435,653								\$6,435,653	\$1,802,300	\$8,237,953			164,323
3	PD 50.75(a)	Energy								\$2,640,807		\$2,640,807	\$646,100	\$3,286,907			
3	PD 50.75(a)	Severance	\$2,177,995									\$2,177,995	\$326,700	\$2,504,695			
3	PD 50.75(a)	Small Tools			\$1,000,183							\$1,000,183	\$252,300	\$1,252,483			
		SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$91,737,140	\$6,435,653	\$16,875,787					\$6,640,807	\$7,845,893	\$128,800,340	\$21,848,090	\$150,648,340	1,399,787		164,323
		TOTAL PERIOD 3 VESSEL AND INTERNALS REMOVAL COSTS:	\$101,877,647	\$48,858,141	\$21,080,473	\$720,900	\$10,378,647	\$63,241	\$146,790,826	\$6,640,807	\$144,636,719	\$231,488,157	\$111,690,880	\$343,178,937	1,800,668	\$85,911	\$79,646
		ACTIVITY															
		UNIT 1															
		Unit 1 Subtotal 10 CFR 50.75(c):		\$22,748,687	\$2,722,966	\$591,804	\$10,933,903		\$33,440,706			\$126,146,411	\$39,871,790	\$166,018,111			421,184
		Unit 1 Subtotal 10 CFR 50.54(b):															
		Unit 1 Subtotal Greenfield:		\$9,596,326	\$929,398		\$109,115		\$9,734,839			\$11,094,086	\$2,434,190	\$13,528,276		182,118	
		UNIT 2															
		Unit 2 Subtotal 10 CFR 50.75(c):	\$51,231	\$6,437,611	\$1,736,747	\$159,808	\$7,419,515		\$81,363,120			\$88,217,413	\$27,287,200	\$115,504,613			165,917
		Unit 2 Subtotal 10 CFR 50.54(b):															
		Unit 2 Subtotal Greenfield:															
		Correction															
		Total 10 CFR 50.75(c):		\$194,384	\$99,645	\$10,496	\$82,724		\$131,694			\$196,322	\$169,400	\$365,722			2,242
		Total 10 CFR 50.54(b):															
		Total Greenfield:		\$111,401	\$42,947	\$10,897	\$63,241					\$228,175	\$44,500	\$272,675		1,694	
		PERIOD DEPENDENT															
		UNIT 1															
		Unit 1 Subtotal 10 CFR 50.75(c):															
		Unit 1 Subtotal 10 CFR 50.54(b):															
		UNIT 2															
		Unit 2 Subtotal 10 CFR 50.75(c):															
		Unit 2 Subtotal 10 CFR 50.54(b):															
		Correction															
		Total 10 CFR 50.75(c):	\$91,737,140	\$6,435,653	\$16,875,787					\$6,640,807	\$7,845,893	\$128,800,340	\$21,848,090	\$150,648,340	1,399,787		164,323
		Total 10 CFR 50.54(b):		\$16,118,298	\$1,421,806					\$697,172	\$138,089,838	\$169,135,861	\$23,411,300	\$192,547,161	400,878		
		Unit 1, Unit 2 & Correction															
		Total 10 CFR 50.75(c):	\$91,737,140	\$46,740,714	\$18,297,593	\$720,900	\$10,378,647		\$144,944,980	\$6,640,807	\$7,845,893	\$230,286,419	\$28,114,390	\$258,400,809	1,399,787		787,846

2012 U. C. Cook
Scenario 2
DECON, Permanent Off-Site Dry Storage

Type	Staff Labor, \$	Craft Labor, \$	Equipment & Materials, \$	Permitting, \$	Transportation, \$	Clean Disposal, \$	Contaminated Disposal, \$	Energy, \$	Other, \$	without Contingency, \$	Contingency, \$	with Contingency, \$	Staff Mechanics	Craft Mechanics	Craft Mechanics
Total 10 CFR 60.54(bb): Total Greenfield	\$18,110,288	\$9,710,428	\$1,421,895	\$863,348	\$175,104	\$65,341	\$818,544	\$997,172	\$128,088,638	\$166,113,891	\$23,880,880	\$178,644,191	400,878	163,111	
PERIOD 4 DECONTAMINATE BALANCE OF SITE COSTS:															
SPENT FUEL PERIOD DEPENDENT															
4 PD 60.54(bb) Utility Staff	\$4,493,129									\$4,493,129	\$974,000	\$5,167,129	165,752		
4 PD 60.54(bb) Security	\$1,771,685									\$1,771,685	\$285,600	\$2,057,485	105,476		
4 PD 60.54(bb) Insurance									\$1,291,157	\$1,291,157	\$193,700	\$1,484,857			
4 PD 60.54(bb) O & M Budget Items									\$894,713	\$894,713	\$132,700	\$1,027,413			
4 PD 60.54(bb) Permits & Fees															
4 PD 60.54(bb) Waste Transfer and Loading															
4 PD 60.54(bb) Energy								\$175,387		\$175,387	\$26,390	\$201,657			
4 PD 60.54(bb) Spent Fuel Storage Maintenance Supplies			\$491,535							\$491,595	\$122,900	\$614,495			
4 PD 60.54(bb) Offsite spent fuel storage									\$41,703,394	\$41,703,394	\$5,266,500	\$47,000,894			
4 PD 60.54(bb) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$8,264,214		\$491,535					\$175,387	\$43,879,364	\$50,811,029	\$7,678,990	\$58,481,528	271,231		
DECOMMISSIONING ACTIVITIES															
4 A 60.75(c) Decon, remove, package, ship and dispose of Unit 2 contaminated systems		\$16,538,283	\$804,125	\$105,587	\$800,963		\$15,182,461			\$33,432,411	\$8,826,000	\$43,258,411			334,974
4 A Greenfield Remove, package, ship and dispose of Unit 2 clean systems		\$17,827,316	\$968,464		\$205,601	\$1,514,798				\$20,804,231	\$4,477,600	\$25,081,831		358,973	
4 A 60.75(c) Decon Steam Generator Storage Building		\$80,083	\$27,858	\$409	\$6,024		\$273,060			\$387,433	\$128,000	\$515,433			1,858
4 A 60.75(c) Decon Unit 2 Reactor Building		\$4,415,224	\$653,223	\$415,439	\$2,672,802		\$13,022,484			\$21,980,142	\$7,001,300	\$28,981,442			80,876
4 A 60.75(c) Remove Spent fuel storage racks		\$2,591,493	\$80,370	\$8,348	\$43,305		\$1,295,798			\$4,348,314	\$1,192,400	\$5,540,714			49,874
4 A 60.75(c) Decon Auxiliary Building		\$1,568,938	\$865,318	\$10,880	\$150,888		\$8,517,858			\$8,803,790	\$3,002,100	\$11,805,890			32,024
4 A 60.75(c) Perform final radiological survey of all structures		\$1,828,500	\$34,180							\$1,862,720	\$420,900	\$2,283,620			
4 A 60.75(c) Perform final survey of the site		\$8,831,680	\$219,900							\$9,051,580	\$2,227,000	\$11,278,580			
4 A 60.75(c) Obtain NRC approval															
4 A 60.75(c) Prepare final report of dismantling program	\$49,362									\$49,362	\$7,400	\$56,762	459		
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$49,362	\$14,482,623	\$1,311,487	\$541,783	\$3,949,883	\$1,514,798	\$97,451,490			\$101,321,044	\$25,283,790	\$126,604,734	459	358,973	499,406
DECOMMISSIONING PERIOD DEPENDENT															
4 PD 60.75(c) Utility Staff	\$24,754,291									\$24,754,291	\$3,713,100	\$28,467,391	391,778		
4 PD 60.75(c) DGC Staff	\$28,306,652									\$28,306,652	\$4,283,500	\$32,610,152	381,732		
4 PD 60.75(c) Security	\$4,044,953									\$4,044,953	\$608,700	\$4,653,653	140,838		
4 PD 60.75(c) HP Supplies			\$5,288,820							\$5,288,820	\$1,867,200	\$7,156,020			
4 PD 60.75(c) Equipment			\$5,042,647							\$5,042,647	\$1,209,700	\$6,252,347			
4 PD 60.75(c) Unit 1 Insurance									\$645,125	\$645,125	\$98,800	\$743,925			
4 PD 60.75(c) Unit 2 Insurance									\$645,125	\$645,125	\$98,800	\$743,925			
4 PD 60.75(c) O & M Budget Items			\$582,817							\$582,817	\$145,700	\$728,517			
4 PD 60.75(c) Permits & Fees									\$4,040,772	\$4,040,772	\$908,100	\$4,948,872			
4 PD 60.75(c) Waste Transfer and Loading		\$9,447,354								\$9,447,354	\$1,454,000	\$10,901,354			125,562
4 PD 60.75(c) Energy								\$4,194,007		\$4,194,007	\$627,800	\$4,821,807			
4 PD 60.75(c) Services	\$800,080									\$800,080	\$128,000	\$928,080			
4 PD 60.75(c) Small Tools			\$1,218,598							\$1,218,598	\$304,600	\$1,523,198			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$37,665,886	\$9,447,354	\$13,112,882	\$541,783	\$3,949,883	\$1,514,798	\$37,451,490	\$4,194,007	\$8,331,823	\$58,231,181	\$14,882,880	\$73,114,061	514,148		125,562
TOTAL PERIOD 4 DECONTAMINATE BALANCE OF SITE COSTS:	\$84,276,682	\$29,859,883	\$16,315,343	\$541,783	\$3,949,883	\$1,514,798	\$37,451,490	\$4,368,394	\$58,210,289	\$109,552,225	\$28,961,670	\$138,513,905	1,185,836	368,973	\$24,997
ACTIVITY															
UNIT 1															
Unit 1 Subtotal 10 CFR 60.75(c):															
Unit 1 Subtotal 10 CFR 60.54(bb):															
Unit 1 Subtotal Greenfield:															
UNIT 2															
Unit 2 Subtotal 10 CFR 60.75(c):															
Unit 2 Subtotal 10 CFR 60.54(bb):															
Unit 2 Subtotal Greenfield:															
Common															
Common Subtotal 10 CFR 60.75(c):															
Common Subtotal 10 CFR 60.54(bb):															
Common Subtotal Greenfield:															
PERIOD DEPENDENT															
UNIT 1															
Unit 1 Subtotal 10 CFR 60.75(c):															
Unit 1 Subtotal 10 CFR 60.54(bb):															

2012 D. C. Cook
Scenario 2
DECON Permanent Off-Site Dry Storage

Task	Staff Labor	Craft Assist	Equipment & Materials	Perception	Transportation	Clean Removal	Contaminated Removal	Storage	Other	Without Contingency	With Contingency	With Contingency	Staff Materials	Craft Materials	Craft Manpower
UNIT 2															
Unit 2 Subtotal 10 CFR 60.54pp:															
Unit 2 Subtotal 10 CFR 60.54pp:															
Common															
Common Subtotal 10 CFR 60.54pp:	147,888,836	56,447,384	113,112,883					84,184,887	56,351,023	187,891,181	154,882,849	150,188,961	914,148		123,882
Common Subtotal 10 CFR 60.54pp:	147,888,836	56,447,384	113,112,883					84,184,887	56,351,023	187,891,181	154,882,849	150,188,961	914,148		123,882
Unit 3, Unit 2 & Common															
Total 10 CFR 60.54pp:	147,888,836	56,447,384	113,112,883	884,1793	13,873,293		937,481,680	84,184,887	56,351,023	187,891,181	154,882,849	150,188,961	914,148		123,882
Total 10 CFR 60.54pp:	147,888,836	56,447,384	113,112,883	884,1793	13,873,293		937,481,680	84,184,887	56,351,023	187,891,181	154,882,849	150,188,961	914,148		123,882
Total Greenfield	117,827,216	888,194			828,871	11,614,788				828,824,351	84,477,698	828,824,351		888,872	
PERIOD 8 - CLEAN STRUCTURE DEMOLITION COSTS:															
SPENT FUEL PERIOD DEPENDENT															
5 PD 60.54pp	Utility Staff														
5 PD 60.54pp	Security														
5 PD 60.54pp	HP Supplies														
5 PD 60.54pp	Equipment														
5 PD 60.54pp	Insurance														
5 PD 60.54pp	O & M Budget Items														
5 PD 60.54pp	Permits & Fees														
5 PD 60.54pp	Waste Transfer and Loading														
5 PD 60.54pp	Energy														
5 PD 60.54pp	Spent Fuel Storage Maintenance Supplies														
5 PD 60.54pp	Offsite spent fuel storage									56,005,740	83,006,740	1,381,000	110,367,740		
5 PD 60.54pp	Small Tools														
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT															
DECOMMISSIONING ACTIVITIES															
5 A Greenfield	Remove Unit 1 reactor building	51,481,588	889,412			554,178	53,143,738			55,986,921	597,000	35,288,921			24,370
5 A Greenfield	Remove Unit 2 reactor building	51,481,588	889,412			554,178	53,143,738			55,986,921	597,000	35,288,921			24,370
5 A Greenfield	Remove Auxiliary Building	512,108,553	14,882,567			51,884,741	53,322,889			127,268,548	35,244,400	193,210,049			162,482
5 A Greenfield	Remove Turbine Building	55,545,288	53,593,851			11,140,854	55,527,137			118,917,339	33,738,400	323,854,238			137,370
5 A Greenfield	Remove Steam Generator Storage Building	51,084,400	888,007			182,487	53,044,304			5843,888	108,700	1782,888			3,181
5 A Greenfield	Remove Electrical Transformers	51,084,400	888,007			182,487	53,044,304			5843,888	108,700	1782,888			3,181
5 A Greenfield	Removal of Unit 1 Turbine Generator	51,084,400	888,007			182,487	53,044,304			5843,888	108,700	1782,888			3,181
5 A Greenfield	Removal of Unit 1 Main Condenser	51,084,400	888,007			182,487	53,044,304			5843,888	108,700	1782,888			3,181
5 A Greenfield	Removal of Unit 2 Turbine Generator	51,084,400	888,007			182,487	53,044,304			5843,888	108,700	1782,888			3,181
5 A Greenfield	Removal of Unit 2 Main Condenser	51,084,400	888,007			182,487	53,044,304			5843,888	108,700	1782,888			3,181
5 A Greenfield	Removal of Standby Diesel Generator	51,084,400	888,007			182,487	53,044,304			5843,888	108,700	1782,888			3,181
5 A Greenfield	Removal of Administration Building	51,084,400	888,007			182,487	53,044,304			5843,888	108,700	1782,888			3,181
5 A Greenfield	Removal Low Level Radiolabel Building	51,084,400	888,007			182,487	53,044,304			5843,888	108,700	1782,888			3,181
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:															
DECOMMISSIONING PERIOD DEPENDENT															
5 PD Greenfield	Utility Staff	31,108,739								31,108,739	168,550	11,274,203	18,113		
5 PD Greenfield	DGC Staff	57,488,815								57,488,815	1,120,306	98,549,118	94,384		
5 PD Greenfield	Security	5511,512								5511,512	179,669	3596,712	18,040		
5 PD Greenfield	HP Supplies														
5 PD Greenfield	Equipment			52,223,437						52,223,437	155,800	82,779,207			
5 PD Greenfield	Unit 1 Insurance								5261,550	5261,550	330,300	5301,150			
5 PD Greenfield	Unit 2 Insurance								5261,550	5261,550	330,300	5301,150			
5 PD Greenfield	O & M Budget Items			503,408						503,408	113,091	178,098			
5 PD Greenfield	Permits & Fees									177,508	128,800	104,498			
5 PD Greenfield	Waste Transfer and Loading			52,169,739						52,169,739	148,109	12,088,893			41,808
5 PD Greenfield	Energy								1148,182	1148,182	122,208	1170,382			
5 PD Greenfield	Security	54,822,884								54,822,884	988,409	55,318,084			
5 PD Greenfield	Small Tools			5012,109						5012,109	168,009	1788,109			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT															
TOTAL PERIOD 8 - CLEAN STRUCTURE DEMOLITION COSTS:															
ACTIVITY															
UNIT 1															

2012 D. C. Cook
Scenario 2
DECOR, Permanent Off-Site Dry Storage

Type	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Permitting \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	without Contingency \$	Contingency \$	with Contingency \$	Staff Manhours	Craft Manhours	Craft Manhours
Unit 1 Subtotal Greenfield (g): Unit 1 Subtotal 10 CFR 60.54(bb):		\$2,967,196	\$818,738		\$933,934	\$3,682,892				\$8,182,421	\$1,279,999	\$9,462,421		48,647	
UNIT 2 Unit 2 Subtotal Greenfield (g): Unit 2 Subtotal 10 CFR 60.54(bb):		\$2,967,196	\$818,738		\$933,934	\$3,682,892				\$8,182,421	\$1,279,999	\$9,462,421		48,647	
Common Common Subtotal Greenfield (g): Common Subtotal 10 CFR 60.54(bb):		\$22,471,237	\$9,806,198		\$2,861,279	\$17,144,342				\$61,371,803	\$9,894,846	\$71,266,649		387,751	
PERIOD DEPENDENT UNIT 1 Unit 1 Subtotal Greenfield (g): Unit 1 Subtotal 10 CFR 60.54(bb):															
UNIT 2 Unit 2 Subtotal Greenfield (g): Unit 2 Subtotal 10 CFR 60.54(bb):															
Common Common Subtotal Greenfield (g): Common Subtotal 10 CFR 60.54(bb):	\$13,713,144	\$2,189,731	\$8,887,851					\$148,182	\$701,268	\$16,040,278	\$3,406,009	\$19,446,287	139,348	41,808	
Unit 1, Unit 2 & Common Total Greenfield (g): Total 10 CFR 60.54(bb):	\$13,713,144	\$29,809,303	\$15,346,684		\$4,219,147	\$24,808,406		\$148,182	\$701,268	\$67,237,811	\$16,786,780	\$84,024,591	139,348	408,853	
PERIOD 6 - RESTORE SITE COSTS:															SARFOR
SPENT FUEL PERIOD DEPENDENT															
6 PD 60.54(bb) Utility Staff															
6 PD 60.54(bb) Security															
6 PD 60.54(bb) HP Supplies															
6 PD 60.54(bb) Insurance															
6 PD 60.54(bb) Equipment															
6 PD 60.54(bb) O & M Budget Items															
6 PD 60.54(bb) Permits & Fees															
6 PD 60.54(bb) Waste Transfer and Loading															
6 PD 60.54(bb) Energy															
6 PD 60.54(bb) Spent Fuel Storage Maintenance Supplies															
6 PD 60.54(bb) Offsite spent fuel storage										\$1,000,749	\$1,000,749	\$150,100		\$1,150,849	
6 PD 60.54(bb) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT										\$1,000,749	\$1,000,749	\$150,100		\$1,150,849	
DECOMMISSIONING ACTIVITIES															
6 A Greenfield Backfill, grade and landscape site		\$106,109								\$106,109	\$37,600	\$203,609		1,757	
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:		\$106,109								\$106,109	\$37,600	\$203,609		1,757	
DECOMMISSIONING PERIOD DEPENDENT															
6 PD Greenfield Utility Staff	\$52,051									\$52,051	\$7,000	\$59,051	940		
6 PD Greenfield DDC Staff	\$390,926									\$390,926	\$58,500	\$449,426	4,598		
6 PD Greenfield Security	\$14,310									\$14,310	\$2,200	\$16,510	628		
6 PD Greenfield HP Supplies															
6 PD Greenfield Equipment			\$74,824							\$74,824	\$19,700	\$94,524			
6 PD Greenfield Unit 1 Insurance									\$29,572	\$29,572	\$4,400	\$33,972			
6 PD Greenfield Unit 2 Insurance									\$29,572	\$29,572	\$4,400	\$33,972			
6 PD Greenfield O & M Budget Items			\$7,048							\$7,048	\$1,800	\$8,848			
6 PD Greenfield Permits & Fees										\$20,054	\$3,000	\$23,054			
6 PD Greenfield Waste Transfer and Loading		\$248,430								\$248,430	\$98,000	\$346,430		4,599	
6 PD Greenfield Energy								\$8,583		\$8,583	\$1,000	\$9,583			
6 PD Greenfield Governance	\$311,142									\$311,142	\$48,700	\$359,842			
6 PD Greenfield Small Tools			\$8,201							\$8,201	\$2,100	\$10,301			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$768,836	\$248,430	\$88,883					\$8,583	\$78,196	\$1,182,791	\$206,700	\$1,389,491	6,284	4,699	
TOTAL PERIOD 6 - RESTORE SITE COSTS:	\$768,836	\$414,539	\$88,883					\$8,583	\$1,079,947	\$2,369,646	\$394,300	\$2,763,946	6,284	6,499	
ACTIVITY															

2012 D. C. Cook
Scenario 2
DECON Permanent Off-Site Dry Storage

Line	Start Labor	Unit Labor	Equipment & Materials	Perkins	Transportation	Clean	Contaminated	Storage	Salvage	Remediation	Construction	Off-Site	Staff	Crane	Crane
UNIT 1															
Unit 1 Subtotal Greenfield (g):															
Unit 1 Subtotal 10 CFR 60.54(bb):															
UNIT 2															
Unit 2 Subtotal Greenfield (g):															
Unit 2 Subtotal 10 CFR 60.54(bb):															
Common															
Common Subtotal Greenfield (g):		\$166,109								\$166,109	\$37,669	\$203,609		1,767	
Common Subtotal 10 CFR 60.54(bb):															
PERIOD DEPENDENT															
UNIT 1															
Unit 1 Subtotal Greenfield (g):															
Unit 1 Subtotal 10 CFR 60.54(bb):															
UNIT 2															
Unit 2 Subtotal Greenfield (g):															
Unit 2 Subtotal 10 CFR 60.54(bb):															
Common															
Common Subtotal Greenfield (g):	\$758,636	\$246,430	\$99,863					\$6,863	\$78,198	\$1,192,791	\$206,750	\$1,309,491	6,264	4,898	
Common Subtotal 10 CFR 60.54(bb):									\$1,000,749	\$1,090,749	\$166,109	\$1,166,858			
Unit 1, Unit 2 & Common															
Total Greenfield (g):	\$758,636	\$414,859	\$99,863					\$6,863	\$78,198	\$1,385,589	\$244,305	\$1,601,098	6,264	6,496	
Total 10 CFR 60.54(bb):									\$1,000,749	\$1,090,749	\$166,109	\$1,166,858			
PERIOD 7 - ANNUAL OFF-SITE DRY STORAGE COSTS:															
SPENT FUEL ACTIVITIES															
7 A 60.54(bb) Continue to ship fuel to repository															
SUBTOTAL - SPENT FUEL ACTIVITIES															
SPENT FUEL PERIOD DEPENDENT															
7 PD 60.54(bb) Utility Staff															
7 PD 60.54(bb) Security															
7 PD 60.54(bb) Insurance															
7 PD 60.54(bb) O & M Budget Items															
7 PD 60.54(bb) Permits & Fees															
7 PD 60.54(bb) Waste Transfer and Loading															
7 PD 60.54(bb) Energy															
7 PD 60.54(bb) Equipment															
7 PD 60.54(bb) HP Supplies															
7 PD 60.54(bb) Spent Fuel Storage Maintenance Supplies															
7 PD 60.54(bb) Offsite spent fuel storage										\$9,004,493	\$9,004,493	\$900,400	\$9,904,893		
7 PD 60.54(bb) Salvage															
7 PD 60.54(bb) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT										\$9,004,493	\$9,004,493	\$900,400	\$9,904,893		
TOTAL PERIOD 7 - DRY STORAGE COSTS:										\$9,004,493	\$9,004,493	\$900,400	\$9,904,893		
ACTIVITY															
Common															
Common Subtotal 10 CFR 60.78(c):															
Common Subtotal 10 CFR 60.54(bb):															
PERIOD DEPENDENT															
Common															
Common Subtotal 10 CFR 60.78(c):															
Common Subtotal 10 CFR 60.54(bb):										\$9,004,493	\$9,004,493	\$900,400	\$9,904,893		
Unit 1, Unit 2 & Common															
Total 10 CFR 60.78(c):															
Total 10 CFR 60.54(bb):										\$9,004,493	\$9,004,493	\$900,400	\$9,904,893		
TOTAL ACTIVITY COSTS:										\$9,004,493	\$9,004,493	\$900,400	\$9,904,893		

2012 D. C. Cook
Scenario 2
DECON: Permanent Off-Site Dry Storage

Type	Staff Labor \$	Crift Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	without Contingency \$	Contingency \$	with Contingency \$	Staff Manhours	Crift Manhours	Crift Manhours
UNIT 1															
SUBTOTAL UNIT 1 10 CFR 61.76(c) COSTS FOR PERIODS 1 - 8		\$27,398,346	\$5,868,640	\$69,184	\$10,623,903		\$87,944,088			\$130,484,728	\$42,067,386	\$173,082,078		8,780	431,164
SUBTOTAL UNIT 1 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 1 GREENFIELD COSTS FOR PERIODS 1 - 8		\$12,686,483	\$1,338,137		\$793,182	\$3,882,682	\$816,844			\$18,187,007	\$4,018,000	\$23,213,007		240,864	
UNIT 2															
SUBTOTAL UNIT 2 10 CFR 61.76(c) COSTS FOR PERIODS 1 - 8	\$81,231	\$38,001,846	\$4,327,838	\$648,827	\$10,893,679		\$94,861,388			\$148,988,303	\$47,160,160	\$196,116,463		8,780	888,767
SUBTOTAL UNIT 2 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 2 GREENFIELD COSTS FOR PERIODS 1 - 8		\$28,784,485	\$1,788,192		\$828,828	\$6,187,350				\$38,708,653	\$6,867,800	\$45,664,163		408,621	
COMMON															
SUBTOTAL COMMON 10 CFR 61.76(c) COSTS FOR PERIODS 1 - 8	\$8,413,469	\$17,637,763	\$1,866,308	\$30,332	\$282,963		\$8,487,631			\$38,388,288	\$8,214,900	\$47,043,188	100,194	24,968	88,787
SUBTOTAL COMMON 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 8	\$749,487	\$1,874,991	\$2,466,036							\$4,811,377	\$1,112,300	\$6,512,677	7,712	28,000	
SUBTOTAL COMMON GREENFIELD COSTS FOR PERIODS 1 - 8		\$23,748,447	\$4,866,053		\$2,962,184	\$17,207,483				\$51,788,177	\$9,706,900	\$61,473,677		281,203	
TOTAL PERIOD DEPENDENT COSTS															
UNIT 1															
SUBTOTAL UNIT 1 10 CFR 61.76(c) COSTS FOR PERIODS 1 - 8	\$28,177,442		\$12,836,137					\$1,282,384	\$2,342,247	\$41,868,232	\$7,487,800	\$48,816,732	164,736		
SUBTOTAL UNIT 1 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 1 GREENFIELD COSTS FOR PERIODS 1 - 8															
UNIT 2															
SUBTOTAL UNIT 2 10 CFR 61.76(c) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 2 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 2 GREENFIELD COSTS FOR PERIODS 1 - 8															
COMMON															
SUBTOTAL COMMON 10 CFR 61.76(c) COSTS FOR PERIODS 1 - 8	\$286,016,380	\$14,883,007	\$33,864,842					\$11,817,283	\$16,784,664	\$282,386,776	\$48,868,280	\$338,231,976	3,898,420		280,814
SUBTOTAL COMMON 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 8	\$30,049,348	\$2,578,891	\$2,466,036					\$830,387	\$286,338,788	\$286,736,148	\$48,048,360	\$343,783,448	784,040		
SUBTOTAL COMMON GREENFIELD COSTS FOR PERIODS 1 - 8	\$14,481,780	\$2,446,183	\$2,887,814					\$164,745	\$780,464	\$20,843,088	\$3,611,700	\$24,464,788	138,612	46,307	
	\$286,949,107												4,079,721		
UNIT 1, UNIT 2 & COMMON															
GRAND TOTAL ACTIVITY COSTS FOR PERIODS 1-8	\$10,214,127	\$137,888,288	\$25,402,888	\$1,282,763	\$28,884,277	\$26,887,416	\$182,178,748			\$418,490,630	\$119,726,180	\$538,226,810	107,808	1,479,187	1,102,728
GRAND TOTAL PERIOD DEPENDENT COSTS FOR PERIODS 1-8	\$276,774,680	\$17,231,179	\$61,788,103					\$14,184,801	\$284,244,083	\$643,313,217	\$102,883,780	\$746,288,917	3,871,813	46,307	288,314
ANNUAL SPENT FUEL STORAGE									\$8,004,483	\$8,004,483	\$880,400	\$8,884,883			
GRAND TOTAL	\$286,949,107	\$186,020,428	\$77,171,038	\$1,282,763	\$28,884,277	\$26,887,416	\$182,178,748	\$14,184,801	\$284,244,083	\$1,082,713,748	\$223,787,880	\$1,306,421,648	4,079,721	1,118,474	1,392,842
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 61.76(c):	\$28,177,442	\$27,398,346	\$16,482,837	\$69,184	\$10,623,903		\$87,944,088	\$1,282,388	\$2,382,247	\$17,184,280	\$50,084,880	\$221,807,810	164,736	8,780	431,164
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.54(b):															
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (d):		\$12,686,482	\$1,338,137		\$793,182	\$3,882,682	\$816,844			\$18,187,007	\$4,018,000	\$23,213,007		240,864	
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 61.76(c):	\$81,231	\$38,001,846	\$4,327,838	\$648,827	\$10,893,679		\$94,861,388			\$148,988,303	\$47,160,160	\$196,116,463		8,780	888,767
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.54(b):															
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (d):		\$28,784,485	\$1,788,192		\$828,828	\$6,187,350				\$38,708,653	\$6,867,800	\$45,664,163		408,621	
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 61.76(c):	\$218,428,788	\$32,428,788	\$36,821,888	\$30,332	\$282,963		\$8,487,631	\$11,817,283	\$16,784,664	\$20,738,081	\$88,140,100	\$276,876,181	2,898,416	24,968	378,711
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.54(b):	\$30,049,348	\$1,674,991	\$2,466,036					\$830,387	\$286,338,788	\$286,648,622	\$48,048,360	\$343,687,122	781,787	28,000	
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (d):	\$14,481,780	\$28,194,810	\$11,838,897		\$2,962,184	\$17,207,483		\$164,745	\$780,464	\$72,818,243	\$12,318,900	\$85,137,143	138,612	467,808	
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 61.76(c):	\$240,658,472	\$84,788,861	\$87,342,121	\$1,282,763	\$21,888,436		\$181,363,101	\$13,189,888	\$18,138,821	\$83,844,323	\$163,386,100	\$291,896,423	3,167,282	36,480	1,392,842
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.54(b):	\$30,049,348	\$1,674,991	\$2,466,036					\$830,387	\$286,338,788	\$286,648,622	\$48,048,360	\$343,687,122	781,787	28,000	
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (d):	\$14,481,780	\$28,194,810	\$11,838,897		\$2,962,184	\$17,207,483		\$164,745	\$780,464	\$72,818,243	\$12,318,900	\$85,137,143	138,612	467,808	
GRAND TOTAL	\$286,949,107	\$186,020,428	\$77,171,038	\$1,282,763	\$28,884,277	\$26,887,416	\$182,178,748	\$14,184,801	\$284,244,083	\$1,082,713,748	\$223,787,880	\$1,306,421,648	4,079,721	1,118,474	1,392,842

2012 B. C. Cook
Scenario 3
DECON, On-Site Dry Storage, 2032 Reprofit and Current Acceptance Rate

TYPE	SPENT	Cost	Equipment &	Permitting	Transportation	Clean	Contaminated	Energy	Other	Subtotal	Total	Staff	Clean	Contaminated
PERIOD 1 - U1 & U2 DECOMMISSIONING PLANNING COST:	LABOR	LABOR	MATERIALS	\$	\$	\$	\$	\$	\$	Costs	Costs	Months	Cost	Cost
SPENT FUEL ACTIVITIES														
Mostly spent fuel support systems														
1 A 50.54(bb)	Define systems modification	\$82,772								\$82,772	\$0,400	\$72,172	608	
1 A 50.54(bb)	Design systems modification and equipment specifications	\$147,683								\$147,683	\$22,200	\$169,883	1,568	
1 A 50.54(bb)	Prepare installation procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
1 A 50.54(bb)	Prepare test procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
1 A 50.54(bb)	Prepare maintenance procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
Control room relocation														
1 A 50.54(bb)	Define control room equipment	\$82,772								\$82,772	\$0,400	\$72,172	608	
1 A 50.54(bb)	Design control room modification and equipment specifications	\$178,962								\$178,962	\$28,800	\$208,762	1,888	
1 A 50.54(bb)	Prepare installation procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
1 A 50.54(bb)	Prepare test procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
1 A 50.54(bb)	Prepare maintenance procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
Design spent fuel storage security modifications														
1 A 50.54(bb)	Define modification	\$29,406								\$29,406	\$4,400	\$33,806	288	
1 A 50.54(bb)	Design modification and equipment specifications	\$102,741								\$102,741	\$16,400	\$119,141	1,016	
1 A 50.54(bb)	Prepare installation procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
1 A 50.54(bb)	Prepare test procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
1 A 50.54(bb)	Prepare maintenance procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
1 A 50.54(bb)	ISF in Pld Construction									\$17,037,421	\$3,888,000	\$20,925,421	192	
SUBTOTAL - SPENT FUEL ACTIVITIES														
		\$749,487								\$17,786,808	\$4,896,800	\$22,683,608	7,804	
SPENT FUEL PERIOD DEPENDENT														
1 PD 50.54(bb)	Utility Staff													
1 PD 50.54(bb)	Security													
1 PD 50.54(bb)	Insurance													
1 PD 50.54(bb)	O & M Budget Items									\$2,183,119	\$2,183,119	\$37,500	\$2,810,619	
1 PD 50.54(bb)	Permits & Fees													
1 PD 50.54(bb)	Waste Transfer and Loading													
1 PD 50.54(bb)	Energy													
1 PD 50.54(bb)	Spent Fuel Storage Maintenance Supplies													
1 PD 50.54(bb)	Small Tools									\$170,374	\$42,800	\$212,974		
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT														
										\$2,183,119	\$2,383,483	\$37,500	\$2,723,683	
DECOMMISSIONING ACTIVITIES														
Primary system decontamination														
1 A 50.75(b)	Define scope	\$41,638								\$41,638	\$8,200	\$47,638	328	
1 A 50.75(b)	Evaluate processes	\$53,024								\$53,024	\$8,000	\$61,024	448	
1 A 50.75(b)	Prepare bid specifications and RFP	\$82,899								\$82,899	\$7,200	\$90,099	512	
1 A 50.75(b)	Qualify Contractors	\$14,104								\$14,104	\$2,100	\$16,204	112	
1 A 50.75(b)	Evaluate Proposals	\$38,335								\$38,335	\$5,000	\$44,335	248	
Select Decommissioning General Contractor														
1 A 50.75(b)	Define scope	\$78,863								\$78,863	\$11,600	\$91,063	736	
1 A 50.75(b)	Prepare bid specifications and RFP	\$84,013								\$84,013	\$12,800	\$96,813	776	
1 A 50.75(b)	Qualify Contractors	\$51,848								\$51,848	\$5,200	\$57,048	416	
1 A 50.75(b)	Evaluate Proposals	\$38,335								\$38,335	\$5,000	\$44,335	248	
U1 & U2 cold and dry site repowering														
1 A 50.75(b)	Define scope	\$88,277								\$88,277	\$10,200	\$78,477	616	
1 A 50.75(b)	Design modification and equipment specifications	\$150,930								\$150,930	\$22,800	\$173,730	1,500	
1 A 50.75(b)	Prepare installation procedures	\$215,724								\$215,724	\$31,900	\$244,624	2,080	
1 A 50.75(b)	Prepare test procedures	\$18,349								\$18,349	\$2,800	\$21,149	192	
Modify U1 & U2 containment enclosures														
1 A 50.75(b)	Select new enclosures location	\$30,281								\$30,281	\$4,500	\$34,781	288	
1 A 50.75(b)	Design enclosures and equipment specifications	\$133,633								\$133,633	\$20,000	\$153,633	1,320	
U1 & U2 Site Characterization														
1 A 50.75(b)	Define scope	\$47,761								\$47,761	\$7,200	\$54,961	408	
1 A 50.75(b)	Prepare bid specifications and RFP	\$53,465								\$53,465	\$8,000	\$61,465	468	
1 A 50.75(b)	Qualify Contractors	\$21,848								\$21,848	\$3,200	\$24,648	176	
1 A 50.75(b)	Evaluate Proposals	\$38,335								\$38,335	\$5,000	\$44,335	248	
1 A 50.75(b)	Prepare procedures	\$133,000								\$133,000	\$19,800	\$152,800	1,288	
ADMINISTRATIVE ACTIVITIES														
1 A 50.75(b)	Develop staff transition plan	\$41,832								\$41,832	\$8,200	\$47,732	384	
1 A 50.75(b)	Develop insurance and retention policy	\$41,832								\$41,832	\$8,200	\$47,732	384	
1 A 50.75(b)	Prepare project administrative procedures	\$45,028								\$45,028	\$8,000	\$51,028	408	
1 A 50.75(b)	Develop area based decommissioning cost estimate	\$209,039								\$209,039	\$31,400	\$240,439	2,040	
1 A 50.75(b)	Develop project budget and schedule controls	\$89,824								\$89,824	\$13,100	\$70,024	548	
1 A 50.75(b)	Assess past drawings	\$24,307								\$24,307	\$3,600	\$27,907	208	
1 A 50.75(b)	Define end product	\$39,215								\$39,215	\$5,400	\$41,615	288	

2019 D. C. Cook
Scenario 3
DECON, On-Site Dry Storage, NIS2 Repository and Current Acceptance Rule

		Staff	Craft	Equipment &	Pickup/drop	Transportation	Clean	Contaminated	Emuls	Other	Without	Contingency	With	Staff	Craft	Craft
		Labor	Labor	Materials			Decontam.	Decontam.			Contingency		Contingency	Materials	Machinist	Machinist
1	A 50.75(c)	Develop technical approach and detailed project plans	\$223,854											2,440		
LICENSING/PERMITTING DOCUMENTATION																
1	A 50.75(c)	Insurance execution	\$46,144								\$46,144	\$5,900	\$52,044	376		
1	A 50.75(c)	Prepare Post-Shutdown Decommissioning Activities Report	\$134,588								\$134,588	\$20,200	\$154,788	1,400		
1	A 50.75(c)	Prepare certification of permanent cessation of operations	\$5,143								\$5,143	\$600	\$5,743	40		
1	A 50.75(c)	Prepare certification of permanent reactor defueling	\$5,143								\$5,143	\$500	\$5,643	40		
1	A 50.75(c)	Prepare post-shutdown technical specification modifications	\$335,249								\$335,249	\$50,300	\$385,549	3,900		
1	A 50.75(c)	Update FSAR	\$311,424								\$311,424	\$46,700	\$358,124	3,300		
1	A 50.75(c)	Develop certified fuel handler program	\$36,160								\$36,160	\$5,400	\$41,560	356		
1	A 50.75(c)	Prepare post-shutdown emergency plan	\$162,778								\$162,778	\$24,400	\$187,178	1,400		
1	A 50.75(c)	Prepare post-shutdown QA plan	\$104,139								\$104,139	\$15,800	\$119,939	1,000		
1	A 50.75(c)	Prepare post-shutdown security plan	\$104,139								\$104,139	\$15,800	\$119,939	1,000		
1	A 50.75(c)	Prepare post-shutdown fire protection plan	\$104,139								\$104,139	\$15,800	\$119,939	1,000		
1	A 50.75(c)	Prepare post-shutdown radiation protection manual	\$104,139								\$104,139	\$15,800	\$119,939	1,000		
1	A 50.75(c)	Prepare and submit state and local permits	\$95,422								\$95,422	\$14,300	\$109,722	960		
1	A 50.75(c)	Respond to NRC questions on PSDAR	\$6,143								\$6,143	\$800	\$6,943	40		
1	A 50.75(c)	Prepare detailed resource loaded project schedule	\$256,157								\$256,157	\$39,400	\$295,557	2,480		
1	A 50.75(c)	Perform 50-50 unreviewed safety questions	\$62,871								\$62,871	\$13,000	\$75,871	736		
1	A 50.75(c)	Prepare activity specifications	\$1,700,771								\$1,700,771	\$255,100	\$1,955,871	18,080		
1	A 50.75(c)	Prepare detailed work procedures	\$1,604,383								\$1,604,383	\$240,700	\$1,845,083	16,080		
1	A 50.75(c)	Select shipping casks and obtain permits	\$24,032								\$24,032	\$3,600	\$27,632	240		
LICENSE TERMINATION PLAN																
1	A 50.75(c)	General information	\$1,350								\$1,350	\$200	\$1,550	15		
1	A 50.75(c)	Site Characterization	\$33,867								\$33,867	\$5,100	\$38,967	336		
1	A 50.75(c)	Identification of remaining site dismantlement activities	\$33,867								\$33,867	\$5,100	\$38,967	336		
1	A 50.75(c)	Remediation Plans	\$17,880								\$17,880	\$2,700	\$20,580	176		
1	A 50.75(c)	Final Radiation Survey Plan	\$238,813								\$238,813	\$36,000	\$274,813	3,820		
1	A 50.75(c)	Compliance with the radiological criteria for license termination	\$227,506								\$227,506	\$34,100	\$261,606	2,440		
1	A 50.75(c)	Update decommissioning cost estimate	\$55,404								\$55,404	\$8,500	\$63,904	596		
1	A 50.75(c)	Supplement to the environmental report	\$55,404								\$55,404	\$8,500	\$63,904	596		
1	A 50.75(c)	Respond to NRC questions	\$25,693								\$25,693	\$3,900	\$29,593	250		
1	A 50.75(c)	Update LTP	\$51,042								\$51,042	\$7,700	\$58,742	536		
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:																
			\$3,889,742								\$3,889,742	\$1,113,890	\$5,003,632	51,340		
DECOMMISSIONING PERIOD DEPENDENT																
1	PD 60.75(c)	Utility Staff	\$4,420,812								\$4,420,812	\$684,420	\$5,105,232	75,875		
1	PD 60.75(c)	DGC Staff	\$4,483,843								\$4,483,843	\$694,100	\$5,177,943	181,159		
1	PD 60.75(c)	Security	\$882,680								\$882,680	\$132,400	\$1,015,080	23,801		
1	PD 60.75(c)	HP Supplies		\$287,305							\$287,305	\$72,000	\$359,305			
1	PD 60.75(c)	Equipment		\$162,737							\$162,737	\$36,200	\$208,937			
1	PD 60.75(c)	Unit 1 Insurance								\$844,078	\$544,078	\$128,600	\$672,678			
1	PD 60.75(c)	Unit 2 Insurance														
1	PD 60.75(c)	O & M Budget Items		\$12,085,435							\$12,085,435	\$3,023,600	\$15,109,035			
1	PD 60.75(c)	Permits & Fees								\$1,505,191	\$1,505,191	\$226,200	\$1,731,391			
1	PD 60.75(c)	Waste Transfer and Loading														
1	PD 60.75(c)	Energy							\$1,292,388		\$1,292,388	\$193,800	\$1,486,188			
1	PD 60.75(c)	Severance	\$15,571,825								\$15,571,825	\$2,335,800	\$17,907,625			
1	PD 60.75(c)	Small Tools														
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT																
			\$35,177,442		\$12,696,157				\$1,292,388	\$2,382,387	\$41,568,332	\$7,487,699	\$49,056,031	184,736		
TOTAL PERIOD 1 - U1 & U2 DECOMMISSIONING PLANNING COST:																
			\$34,616,679		\$17,697,421				\$1,292,388	\$4,636,388	\$89,689,274	\$13,041,489	\$102,730,763	245,880		
ACTIVITY																
UNIT 1 - PERIOD 1 COSTS																
Unit 1 Subtotal 10 CFR 60.75(c):																
Unit 1 Subtotal 10 CFR 60.84(b)(1):																
UNIT 2																
Unit 2 Subtotal 10 CFR 60.75(c):																
Unit 2 Subtotal 10 CFR 60.84(b)(1):																
Common																
Total 10 CFR 60.75(c):																
Total 10 CFR 60.84(b)(1):																
PERIOD DEPENDENT																
UNIT 1 - PERIOD 1 COSTS																
Unit 1 Subtotal 10 CFR 60.75(c):																
Unit 1 Subtotal 10 CFR 60.84(b)(1):																
UNIT 2																

2012 D. C. Cost
DECON, On-Site Dry Storage, RCX Reproduct and Current Acceptance Rate

TYPE	Unit 1 Subtotal to CFR 80.75(a): Unit 2 Subtotal to CFR 80.84(b)(1):	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Recycle \$	Other \$	without Contingency \$	Contingency \$	with Contingency \$	Staff Materials	Craft Materials	Craft Materials
Common	Total 10 CFR 80.75(a): Total 10 CFR 80.84(b)(1):			\$170,374						\$2,183,119	\$2,383,485	\$370,160	\$2,723,893			
Unit 1, Unit 2 & Common	Total 10 CFR 80.75(a): Total 10 CFR 80.84(b)(1):	\$23,267,183 \$748,487	\$17,207,421	\$12,898,137 \$178,374				\$1,282,388	\$2,282,287	\$2,183,119	\$49,447,872 \$20,148,406	\$8,679,809 \$4,370,800	\$88,118,473 \$24,611,340	\$28,926 7,804		
PERIOD 2 - POST-SHUTDOWN ACTIVITIES COSTS:																
SPENT FUEL ACTIVITIES																
2	A 90.84(b) Modify Spent Fuel Cooling System		\$634,004	\$1,108,000							\$1,788,004	\$408,000	\$2,235,004			9,900
2	A 90.84(b) Modify control room		\$882,042	\$800,000							\$1,682,042	\$382,000	\$1,714,042			9,900
2	A 90.84(b) Modify security system		\$485,758	\$825,000							\$880,758	\$235,000	\$1,215,758			7,280
2	A 90.84(b) Purchase ISFBI cables			\$88,471,000							\$88,471,000	\$17,387,800	\$105,858,800			7,280
	SUBTOTAL - SPENT FUEL ACTIVITIES		\$1,897,804	\$17,891,000							\$73,832,891	\$18,271,800	\$92,094,711			\$1,880
SPENT FUEL PERIOD DEPENDENT																
2	PD 90.84(b) Utility Staff	\$4,008,865									\$4,008,865	\$814,800	\$4,713,799	\$8,409		
2	PD 90.84(b) Security	\$1,818,274									\$1,818,274	\$242,400	\$1,889,874	\$3,531		
2	PD 90.84(b) Insurance									\$1,177,888	\$1,177,888	\$176,700	\$1,384,588			
2	PD 90.84(b) O & M Budget Items															
2	PD 90.84(b) Permits & Fees									\$807,106	\$807,106	\$121,100	\$1,028,206			
2	PD 90.84(b) Waste Transfer and Loading															
2	PD 90.84(b) Energy							\$249,084			\$249,084	\$57,400	\$306,484			
2	PD 90.84(b) Spent Fuel Storage Maintenance Supplies			\$440,472							\$440,472	\$112,100	\$552,572			
2	PD 90.84(b) Small Tools			\$18,718							\$18,718	\$4,200	\$22,918			
	SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$6,716,289		\$468,181				\$249,084	\$1,998,884	\$8,414,848	\$1,998,788	\$8,725,248	\$11,837			
DECOMMISSIONING ACTIVITIES																
2	A 60.75(c) Primary System Decom Unit 1 & 2		\$8,548,040	\$1,417,080				\$8,548,040			\$18,920,780	\$5,675,600	\$24,596,380			
2	A 60.75(c) Frame & Other Systems (PERFORMED BY UTILITY STAFF)															
2	A 60.75(c) Implement cold & dark		\$781,038	\$1,600,000							\$2,381,038	\$673,700	\$3,054,738			11,820
2	A 60.75(c) Modify V1 Containment Access		\$346,437	\$528,000							\$874,437	\$210,300	\$1,084,737			5,760
2	A 60.75(c) Modify V2 Containment Access		\$346,437	\$528,000							\$874,437	\$210,300	\$1,084,737			5,760
2	A 60.75(c) Historical Site Assessment	\$375,882									\$375,882	\$98,400	\$432,282	\$4,880		
2	A 60.75(c) Vessel and Intermediate Activation Analysis	\$108,336									\$108,336	\$18,400	\$126,736	\$840		
2	A 60.75(c) Characterization survey	\$789,888									\$789,888	\$118,400	\$908,288	\$12,880		
2	A 60.75(c) Test special equipment and training		\$838,723								\$838,723	\$214,500	\$1,053,223			13,440
	SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$1,274,208	\$10,838,872	\$4,067,080				\$8,548,040			\$18,247,887	\$7,076,800	\$25,323,187	\$18,880	\$8,488	
DECOMMISSIONING PERIOD DEPENDENT																
2	PD 60.75(c) Utility Staff	\$16,243,382									\$16,243,382	\$2,730,500	\$18,973,882	\$300,070		
2	PD 60.75(c) DGC Staff	\$11,702,745									\$11,702,745	\$1,755,400	\$13,458,145	\$187,540		
2	PD 60.75(c) Security	\$5,208,454									\$5,208,454	\$881,000	\$6,089,454	\$124,274		
2	PD 60.75(c) HP Supplies			\$788,590							\$788,590	\$185,600	\$984,190			
2	PD 60.75(c) Equipment			\$1,018,708							\$1,018,708	\$254,700	\$1,273,408			
2	PD 60.75(c) Unit 1 Insurance									\$288,242	\$288,242	\$38,800	\$327,042			
2	PD 60.75(c) Unit 2 Insurance									\$288,242	\$288,242	\$38,800	\$327,042			
2	PD 60.75(c) O & M Budget Items			\$2,080,773							\$2,080,773	\$721,400	\$2,802,173			
2	PD 60.75(c) Permits & Fees															
2	PD 60.75(c) Waste Transfer and Loading									\$2,075,053	\$2,075,053	\$311,300	\$2,386,353			
2	PD 60.75(c) Energy															
2	PD 60.75(c) Services	\$23,200,808								\$1,982,488	\$1,982,488	\$398,800	\$2,381,288			
2	PD 60.75(c) Small Tools			\$218,793							\$218,793	\$54,700	\$273,493			
	SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$56,383,384		\$4,091,893				\$1,982,488	\$2,807,638	\$68,858,264	\$18,363,498	\$76,194,864	\$82,484			
	TOTAL PERIOD 2 - POST-SHUTDOWN ACTIVITIES COSTS:	\$63,342,333	\$12,811,802	\$21,978,104				\$8,888,840	\$2,241,283	\$4,892,842	\$172,550,888	\$37,119,808	\$218,546,940	\$12,821	\$8,788	
ACTIVITY																
UNIT 1																
	Unit 1 Subtotal to CFR 80.75(a): Unit 1 Subtotal to CFR 80.84(b)(1):		\$4,818,487	\$1,239,840				\$4,483,320			\$10,338,317	\$3,848,098	\$14,186,415			\$1,760
UNIT 2																

2012 O & C Cost
 DECOR, On-Site Dry Storage, 2002, Repository and Current Accession Rate

Task	Unit	Craft	Equipment & Materials	Residuals	Transportation	Clean	Construction	Reactor	Other	Work	Support	With	Staff	Craft	Cost
Unit 2 Subtotal - 10 CFR 80.74(c) Unit 2 Subtotal - 10 CFR 80.84(b)(1)			\$4,818,487	\$1,223,648			\$4,433,320			\$18,338,317	\$3,843,958	\$13,284,367			6,760
Common															
Common Subtotal - 10 CFR 80.74(c) Common Subtotal - 10 CFR 80.84(b)(1)			\$1,274,388	\$1,270,787	\$1,288,000					\$4,871,052	\$979,408	\$1,604,442	18,404	24,900	
				\$1,871,891	\$71,861,000					\$73,832,911	\$18,771,808	\$62,061,103		19,880	
PERIOD DEPENDENT															
UNIT 1															
Unit 1 Subtotal - 10 CFR 80.74(c) Unit 1 Subtotal - 10 CFR 80.84(b)(1)															
UNIT 2															
Unit 2 Subtotal - 10 CFR 80.74(c) Unit 2 Subtotal - 10 CFR 80.84(b)(1)															
Common															
Common Subtotal - 10 CFR 80.74(c) Common Subtotal - 10 CFR 80.84(b)(1)			\$66,303,374	\$4,881,303	\$488,191			\$1,882,469	\$2,497,828	\$81,331,264	\$10,382,404	\$76,188,854	\$82,494	111,837	
			\$8,718,258					\$248,384	\$1,825,504	\$8,454,848	\$1,282,788	\$9,737,636			
Unit 1, Unit 2 & Common															
Total 10 CFR 80.74(c) Total 10 CFR 80.84(b)(1)			\$67,827,658	\$10,329,872	\$8,848,573		\$8,848,573	\$1,882,469	\$2,497,828	\$91,182,861	\$17,438,904	\$78,643,957	\$82,494	111,837	\$6,480
			\$8,718,258	\$1,871,891	\$72,438,191			\$248,384	\$1,895,004	\$89,647,438	\$19,680,404	\$101,728,038			\$3,290
PERIOD 3 VESSEL AND INTERNALS REMOVAL COSTS															
SPENT FUEL ACTIVITIES															
3 A 80.54(b)(1) Purchase SFB/ Cask					\$68,471,000					\$68,471,000	\$17,387,800	\$81,058,800			
SUBTOTAL - SPENT FUEL ACTIVITIES					\$68,471,000					\$68,471,000	\$17,387,800	\$81,058,800			
SPENT FUEL PERIOD DEPENDENT															
5 PD 50.54(b)(1) Utility Staff			\$12,695,186							\$12,695,186	\$1,948,303	\$14,643,489	218,888		
5 PD 50.54(b)(2) Security			\$6,124,120							\$6,124,120	\$788,600	\$6,912,720	184,210		
5 PD 50.54(b)(3) Insurance									\$3,734,324	\$3,734,324	\$887,100	\$4,621,424			
5 PD 50.54(b)(4) O & M Budget Item															
5 PD 50.54(b)(5) Permit & Fee									\$2,558,793	\$2,558,793	\$363,800	\$2,922,593			
5 PD 50.54(b)(6) Waste Transfer and Loading															
5 PD 50.54(b)(7) Energy								\$511,358		\$511,358	\$70,700	\$582,058			
5 PD 50.54(b)(8) Spent Fuel Storage Maintenance Supplies				\$1,421,806						\$1,421,806	\$365,500	\$1,787,306			
5 PD 50.54(b)(9) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT			\$18,119,284	\$1,421,806				\$511,358	\$6,293,118	\$28,445,368	\$4,084,303	\$32,529,671	403,098		
DECOMMISSIONING ACTIVITIES															
UNIT 1															
1 A 80.75(c) Install of reactor spending flow coordination control hardware (O&E), support structures, piping, internal work platforms and process equipment (BY UTILITY STAFF)															
1 A 80.75(c) Finalize Reactor Radiation Inventory (WITH RITS CHARACTERIZATION)															
1 A 80.75(c) Finalize Internal and Vessel Segmentation Details (WITH ACTIVATION ANALYSIS)															
1 A 80.75(c) Remove, pack, ship and bury Unit 1 Primary Loop			\$1,013,043		\$300	\$72,594		\$899,352		\$1,903,590	\$388,300	\$2,291,890		18,725	
1 A 80.75(c) Decommission, package, ship and bury Unit 1 steam generators			\$4,230,772	\$1,022,887	\$12,800	\$833,287		\$12,054,509		\$18,238,854	\$8,887,000	\$24,251,384		79,183	
1 A 80.75(c) Remove Unit 1 equipment hatch structure (BY UTILITY STAFF)															
1 A 80.75(c) Remove Unit 1 control rod drive and reactor cavity missile shields (BY UTILITY STAFF)															
1 A 80.75(c) Remove Unit 1 CRD mechanisms and control air ducts, and reactor vessel head (BY UTILITY STAFF)															
1 A 80.75(c) Remove, segment, package and ship Unit 1 vessel & vessel head (BY UTILITY STAFF)			\$674,720					\$350,040		\$824,760	\$171,800	\$996,560			
1 A 80.75(c) Prepare Unit 1 vessel head for shipment as its own component (WITH VESSEL REMOVAL)															
1 A 80.75(c) Decommission and clean up Unit 1 plant area (BY UTILITY STAFF)															
1 A 80.75(c) Prepare liquid and solid radioactive wastes (BY UTILITY STAFF)															
1 A 80.75(c) Decommission, package, ship and dispose of Unit 1 contaminated systems			\$8,008,782	\$432,000	\$58,395	\$481,288		\$8,178,162		\$18,302,067	\$5,314,900	\$23,315,967		180,371	
1 A 80.75(c) Remove, package, ship and dispose of Unit 1 clean systems			\$9,088,325	\$520,388		\$138,218		\$9,646,931		\$11,084,586	\$2,882,000	\$13,966,586		192,218	
1 A 80.75(c) Install Unit 1 water cleanup system in fuel transfer canal (BY UTILITY STAFF)															
1 A 80.75(c) Segment, package and ship Unit 1 internal as radioactive waste			\$2,881,854	\$602,630	\$81,200	\$4,574,980		\$33,431,361		\$41,182,335	\$14,280,700	\$55,463,035		47,300	
1 A 80.75(c) Decommission internal work platform and store (BY UTILITY STAFF)															
1 A 80.75(c) Install Unit 1 vessel support structure (WITH VESSEL REMOVAL)															
1 A 80.75(c) Segment and process Unit 1 reactor vessel and associated equipment as LLW			\$1,382,622	\$141,481	\$24,000	\$2,038,282		\$14,437,188		\$18,184,413	\$8,288,500	\$24,472,913		24,820	
1 A 80.75(c) Decommission reactor vessel platform and store															
1 A 80.75(c) Decommission Unit 1 reactor building			\$4,418,224	\$853,223	\$418,438	\$2,872,802		\$13,922,464		\$21,882,152	\$7,013,200	\$28,895,352		80,876	
UNIT 2															

DECON, On-Site Dry Storage, 2032 Repository and Current Acceptance Rate

Page 5 of 11
12/3/2012

2017 D.C. Cost
Worksheet 3
DECON, On-Site Dry Storage, 2032 Repository and Current Acceptance Rate

TYPE	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Package \$	Transportation \$	Clean Contract \$	Construction Contract \$	Energy \$	Other \$	Without Construction \$	Construction \$	With Construction \$	Staff Materials	Craft Materials	Craft Materials
Total 10 CFR 60.75(c):	891,746,371	840,748,714	138,385,118	7720,880	118,208,643		9144,844,880	\$1,040,807	\$7,345,593	\$336,358,416	\$68,735,309	\$418,093,716	1,308,797		
Total 10 CFR 60.64(b):	118,119,288		278,892,809					\$11,069	\$6,283,116	\$65,816,266	\$21,691,899	\$117,278,086	406,876		
Total Greenfield:		\$9,710,428	\$992,345		\$178,198	\$83,361	\$815,444			\$11,322,767	\$2,706,809	\$14,029,571		193,811	
PERIOD 4 DECONTAMINATE BALANCE OF SITE COSTS:															
SPENT FUEL PERIOD DEPENDENT															
4 PD 50.54(b): Utility Staff	\$4,778,340									\$4,778,340	\$716,500	\$5,494,840	71,576		
4 PD 50.54(b): Security	\$2,411,303									\$2,411,303	\$381,700	\$2,793,003	60,274		
4 PD 50.54(b): Insurance									\$482,870	\$482,870	\$72,400	\$555,270			
4 PD 50.54(b): O & M Budget Items									\$929,799	\$929,799	\$138,500	\$1,068,299			
4 PD 50.54(b): Permits & Fees															
4 PD 50.54(b): Waste Transfer and Loading															
4 PD 50.54(b): Energy								\$12,187		\$12,187	\$2,000	\$14,187			
4 PD 50.54(b): Special Fuel Storage Maintenance Supplies			\$282,228							\$282,228	\$40,500	\$322,728			
4 PD 50.54(b): Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$7,190,643		\$282,228					\$12,187	\$1,412,749	\$8,678,827	\$1,382,100	\$10,060,927	131,848		
DECOMMISSIONING ACTIVITIES															
4 A 50.75(c): Decon, remove, package, ship and dispose of Unit 2 contaminated systems	\$18,538,258	\$804,125	\$105,567	\$803,963		\$15,182,481				\$33,432,411	\$9,870,000	\$43,302,411			\$34,974
4 A Greenfield: Remove, package, ship and dispose of Unit 2 clean systems	\$17,827,319	\$989,404		\$395,691	\$1,614,799					\$20,804,231	\$4,519,700	\$25,323,931	395,973		
4 A 50.75(c): Decon Steam Generator Storage Building	\$80,083	\$27,038	\$409	\$8,024		\$278,060				\$367,433	\$128,300	\$495,733			1,868
4 A 50.75(c): Decon Unit 2 Reactor Building	\$4,415,224	\$553,223	\$418,439	\$2,672,602		\$13,922,404				\$21,950,102	\$7,013,200	\$28,963,302			80,876
4 A 50.75(c): Remove spent fuel storage racks	\$2,591,493	\$99,370	\$8,948	\$43,305		\$1,865,736				\$4,248,314	\$1,199,000	\$5,447,314	49,874		
4 A 50.75(c): Decon Auxiliary Building	\$1,088,599	\$695,318	\$10,980	\$150,898		\$3,011,788				\$8,903,790	\$3,008,400	\$11,912,190			\$2,624
4 A 50.75(c): Perform final radiological survey of all structures	\$1,828,680	\$34,180								\$1,862,860	\$428,000	\$2,290,860			
4 A 50.75(c): Perform final survey of the site	\$8,031,680	\$218,980								\$8,250,660	\$2,283,000	\$10,533,660			
4 A 50.75(c): Obtain NRC approval															
4 A 50.75(c): Prepare final report of dismantling program	\$49,382									\$49,382	\$7,400	\$56,782	488		
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$49,382	\$84,482,629	\$8,311,487	\$84,1783	\$3,908,883	\$1,614,798	\$27,441,488			\$101,321,084	\$18,499,708	\$119,820,792	488	496,847	\$48,831
DECOMMISSIONING PERIOD DEPENDENT															
4 PD 50.75(c): Utility Staff	\$24,754,291									\$24,754,291	\$3,713,100	\$28,467,391	391,778		
4 PD 50.75(c): OOC Staff	\$26,358,892									\$26,358,892	\$4,283,800	\$30,642,692	381,732		
4 PD 50.75(c): Security	\$4,044,893									\$4,044,893	\$698,700	\$4,743,593	142,838		
4 PD 50.75(c): HP Supplies		\$5,706,093								\$5,706,093	\$1,440,000	\$7,146,093			
4 PD 50.75(c): Equipment		\$5,042,647								\$5,042,647	\$1,280,700	\$6,323,347			
4 PD 50.75(c): Unit 1 Insurance								\$845,125		\$845,125	\$98,500	\$943,625			
4 PD 50.75(c): Unit 2 Insurance								\$845,125		\$845,125	\$98,500	\$943,625			
4 PD 50.75(c): O & M Budget Items		\$582,817								\$582,817	\$145,700	\$728,517			
4 PD 50.75(c): Permits & Fees									\$4,040,772	\$4,040,772	\$698,100	\$4,738,872			
4 PD 50.75(c): Waste Transfer and Loading	\$8,447,354									\$8,447,354	\$1,471,300	\$9,918,654			125,392
4 PD 50.75(c): Energy								\$4,040,772		\$4,040,772	\$698,100	\$4,738,872			
4 PD 50.75(c): Services	\$1,833,466									\$1,833,466	\$245,000	\$2,078,466			
4 PD 50.75(c): Small Tools			\$1,218,586							\$1,218,586	\$204,600	\$1,423,186			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$44,788,304	\$6,447,354	\$12,440,166					\$4,040,772	\$5,311,822	\$87,391,861	\$14,878,808	\$102,260,669	1,146,148		\$125,882
TOTAL PERIOD 4 DECONTAMINATE BALANCE OF SITE COSTS:	\$94,128,307	\$90,929,983	\$19,750,594	\$84,1783	\$3,949,883	\$1,614,798	\$37,441,488	\$4,197,195	\$6,724,571	\$187,691,722	\$33,378,508	\$224,060,230	1,642,036	496,847	\$176,113
ACTIVITY															
UNIT 1															
Unit 1 Subtotal 10 CFR 60.75(c):															
Unit 1 Subtotal 10 CFR 60.64(b):															
Unit 1 Subtotal Greenfield:															
UNIT 2															
Unit 2 Subtotal 10 CFR 60.75(c):	\$28,984,478	\$1,387,348	\$422,627	\$3,473,766		\$28,104,848				\$59,418,568	\$18,893,910	\$78,312,478			\$18,860
Unit 2 Subtotal 10 CFR 60.64(b):															
Unit 2 Subtotal Greenfield:	\$17,327,319	\$866,484		\$348,681	\$1,114,768					\$20,804,231	\$4,519,700	\$25,323,931		\$84,873	
Common:															
Common Subtotal 10 CFR 60.75(c):	\$49,382	\$18,709,733	\$987,896	\$18,737	\$988,337	\$8,348,636				\$28,984,368	\$7,021,299	\$35,995,667	488	\$8,874	\$3,882
Common Subtotal 10 CFR 60.64(b):															
Common Subtotal Greenfield:															
PERIOD DEPENDENT															
UNIT 1															
Unit 1 Subtotal 10 CFR 60.75(c):															
Unit 1 Subtotal 10 CFR 60.64(b):															

2012 D. C. Cook
 Schedule 3
 DEDOH, On-Site Dry Storage, 2032 Reprovision and Current Acceptance Rate

Item	Shift Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Chemical \$	Contaminant Disposal \$	Remed \$	Other \$	without Contingency \$	with Contingency \$	Slow March \$	Craft March \$	Craft March \$
UNIT 2														
Unit 2 Subtotal 10 CFR 80.74(c):														
Unit 2 Subtotal 10 CFR 80.84(b):														
Common														
Common Subtotal 10 CFR 80.74(c):	568,739,303	88,447,354	\$12,849,159					\$4,184,007	\$6,331,023	\$87,301,841	\$14,878,040	\$192,288,741	\$14,148	138,982
Common Subtotal 10 CFR 80.84(b):	\$7,190,643		\$987,223					\$13,187	\$1,412,749	\$8,978,827	\$1,583,180	\$10,261,827	131,848	
Unit 1, Unit 2 & Common														
Total 10 CFR 80.74(c):	568,836,954	843,197,894	\$14,306,188	\$84,1783	\$3,873,893		\$37,481,480	\$4,184,007	\$8,331,823	\$108,102,661	\$26,781,540	\$208,880,580	\$16,864	40,974
Total 10 CFR 80.84(b):	\$7,190,643		\$987,223					\$13,187	\$1,412,749	\$8,978,827	\$1,583,180	\$10,261,827	131,848	876,199
Total Greenfield		\$17,827,318	\$988,454		\$286,891	\$1,514,746				\$20,884,331	\$4,826,720	\$26,128,851	366,873	
PERIOD 8 - CLEAN STRUCTURE DEMOLITION COSTS:														
SPENT FUEL PERIOD DEPENDENT														
5 PD 50.54(b) Utility Staff	\$2,839,502									\$2,839,502	\$395,800	\$3,034,792	39,500	
5 PD 50.54(b) Security	\$1,301,411									\$1,301,411	\$199,700	\$1,501,111	83,080	
5 PD 50.54(b) HP Supplies			\$105,267							\$105,267	\$28,300	\$133,567	33,280	
5 PD 50.54(b) Equipment														
5 PD 50.54(b) Insurance														
5 PD 50.54(b) O & M Budget Items									\$286,674	\$286,674	\$40,000	\$306,674		
5 PD 50.54(b) Permits & Fees														
5 PD 50.54(b) Waste Transfer and Loading									\$613,363	\$613,363	\$77,000	\$690,363		
5 PD 50.54(b) Energy								\$7,281		\$7,281	\$1,100	\$8,381		
5 PD 50.54(b) Spent Fuel Storage Maintenance Supplies			\$200,005							\$200,005	\$50,000	\$250,005		
5 PD 50.54(b) Small Tools														
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$1,978,344		\$906,272					\$7,281	\$730,037	\$4,945,964	\$795,880	\$6,442,944	108,881	
DECOMMISSIONING ACTIVITIES														
5 A Greenfield Remove Unit 1 reactor building		\$1,401,598	\$958,412		\$641,175	\$5,143,736				\$5,948,821	\$871,000	\$6,819,821	24,370	
5 A Greenfield Remove Unit 2 reactor building		\$1,401,598	\$958,412		\$641,175	\$5,143,736				\$5,948,821	\$871,000	\$6,819,821	24,370	
5 A Greenfield Remove Auxiliary Building		\$12,105,883	\$4,988,267		\$1,894,741	\$9,322,988				\$27,908,849	\$8,277,000	\$36,185,849	182,482	
5 A Greenfield Remove Turbine Building		\$8,645,384	\$3,650,951		\$1,145,834	\$5,627,787				\$19,917,839	\$3,788,700	\$23,677,839	137,870	
5 A Greenfield Remove Steam Generator Storage Building		\$169,400	\$88,037		\$52,497	\$34,804				\$343,896	\$106,200	\$450,096	3,191	
5 A Greenfield Remove Electrical Transmission		\$61,963	\$2,008		\$13,844	\$8,109				\$83,924	\$27,045	\$110,969	1,899	
5 A Greenfield Remove of Unit 1 Turbine Generator		\$163,800	\$7,869		\$7,746	\$48,000				\$219,415	\$43,000	\$262,415	2,888	
5 A Greenfield Remove of Unit 1 Main Condenser		\$1,335,888	\$7,427		\$86,019	\$409,646				\$1,831,934	\$373,900	\$2,205,834	21,888	
5 A Greenfield Remove of Unit 2 Turbine Generator		\$163,800	\$7,869		\$7,746	\$48,000				\$219,415	\$43,000	\$262,415	2,888	
5 A Greenfield Remove of Unit 2 Main Condenser		\$1,335,888	\$7,427		\$86,019	\$409,646				\$1,831,934	\$373,900	\$2,205,834	21,888	
5 A Greenfield Remove of Standby Diesel Generator		\$30,412	\$6,447		\$2,324	\$13,800				\$52,983	\$16,400	\$69,383	832	
5 A Greenfield Remove Administration Building		\$800,780	\$100,762							\$901,542	\$88,800	\$990,342	4,488	
5 A Greenfield Remove Low Level Radioactive Building		\$1,107,801	\$170,898		\$136,846	\$794,963				\$2,215,608	\$404,800	\$2,620,408	18,088	
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$28,405,679	\$18,443,813			\$4,216,147	\$14,898,494				\$47,878,735	\$15,481,308	\$63,359,885	486,444	
DECOMMISSIONING PERIOD DEPENDENT														
5 PD Greenfield Utility Staff	\$1,100,733									\$1,100,733	\$166,500	\$1,267,233	19,413	
5 PD Greenfield DDC Staff	\$7,488,815									\$7,488,815	\$1,120,300	\$8,609,115	94,294	
5 PD Greenfield Security	\$511,812									\$511,812	\$78,800	\$590,612	10,640	
5 PD Greenfield HP Supplies														
5 PD Greenfield Equipment			\$2,223,437							\$2,223,437	\$968,800	\$3,192,237		
5 PD Greenfield Unit 1 Insurance										\$281,850	\$39,300	\$321,150		
5 PD Greenfield Unit 2 Insurance										\$281,850	\$39,300	\$321,150		
5 PD Greenfield O & M Budget Items			\$42,488							\$42,488	\$18,800	\$61,288		
5 PD Greenfield Permits & Fees														
5 PD Greenfield Waste Transfer and Loading		\$2,189,733								\$177,588	\$26,800	\$204,388		
5 PD Greenfield Energy								\$148,182		\$148,182	\$22,000	\$170,182		
5 PD Greenfield Services	\$3,155,871									\$3,155,871	\$473,400	\$3,629,271		
5 PD Greenfield Small Tools			\$612,105							\$612,105	\$183,000	\$795,105		
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$12,448,339	\$2,189,733	\$2,887,861					\$148,182	\$701,288	\$18,183,442	\$3,189,800	\$21,373,242	190,348	41,888
TOTAL PERIOD 8 - CLEAN STRUCTURE DEMOLITION COSTS:	\$18,216,874	\$20,637,051	\$11,644,236		\$4,216,147	\$14,898,494		\$188,463	\$1,491,332	\$66,022,141	\$18,671,108	\$107,273,281	299,428	488,483
ACTIVITY														
UNIT 1														
Unit 1 Subtotal Greenfield (g):		\$2,887,168	\$916,738		\$803,804	\$3,882,382				\$8,182,411	\$1,387,499	\$9,569,911		48,847
Unit 1 Subtotal 10 CFR 80.84(b):														

2012 D. C. Cook
Scenario 3
DECON, On-Site Dry Storage, HONR Repossibility and Current Acceptance Rule

Type	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Removal \$	Contaminated Disposal \$	Storage \$	Other \$	without Contingency \$	Contingency \$	with Contingency \$	Staff Members	Craft Members	Craft Members
UNIT 2															
Unit 2 Subtotal Greenfield (q):		\$2,867,188	\$919,734		\$632,854	\$1,082,882				\$8,182,421	\$1,387,860	\$9,570,281		48,847	
Unit 2 Subtotal 10 CFR 60.64(h):															
Common															
Common Subtotal Greenfield (q):		\$22,471,237	\$8,885,194		\$2,861,279	\$17,444,242				\$81,571,882	\$8,886,640	\$91,458,522		287,751	
Common Subtotal 10 CFR 60.64(h):															
PERIOD DEPENDENT															
UNIT 1:															
Unit 1 Subtotal Greenfield (q):															
Unit 1 Subtotal 10 CFR 60.64(h):															
UNIT 2:															
Unit 2 Subtotal Greenfield (q):															
Unit 2 Subtotal 10 CFR 60.64(h):															
Common															
Common Subtotal Greenfield (q):	\$12,546,339	\$2,194,735	\$2,847,941					\$146,192	\$791,246	\$19,191,492	\$5,190,909	\$24,382,391	109,348	41,808	
Common Subtotal 10 CFR 60.64(h):	\$3,976,544		\$506,272					\$7,381	\$780,047	\$5,962,894	\$789,900	\$6,752,794	109,951		
Unit 1, Unit 2 & Common															
Total Greenfield (q):	\$12,546,339	\$24,694,503	\$15,349,594		\$4,218,147	\$24,444,494		\$146,192	\$791,246	\$38,773,194	\$15,445,830	\$54,219,024	109,348	494,888	
Total 10 CFR 60.64(h):	\$3,976,544		\$506,272					\$7,381	\$780,047	\$7,924,884	\$789,900	\$8,714,784	109,951		
PERIOD 8 - RESTORE SITE COSTS:															
SPENT FUEL PERIOD DEPENDENT															
PD 60.64(h) Utility Staff	\$594,031									\$594,031	\$44,730	\$638,761	4,493		
PD 60.64(h) Security	\$159,396									\$159,396	\$22,630	\$182,026	8,759		
PD 60.64(h) HP Supplies			\$10,800							\$10,800	\$2,730	\$13,530	8,759		
PD 60.64(h) Insurance									\$30,117	\$30,117	\$4,500	\$34,617			
PD 60.64(h) Equipment															
PD 60.64(h) O & M Budget Items															
PD 60.64(h) Permits & Fees									\$97,881	\$97,881	\$4,730	\$102,611			
PD 60.64(h) Waste Transfer and Loading															
PD 60.64(h) Energy								\$822		\$822	\$100	\$922			
PD 60.64(h) Spent Fuel Storage Maintenance Supplies			\$22,538							\$22,538	\$1,630	\$24,168			
PD 60.64(h) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$444,396		\$33,477					\$822	\$38,939	\$679,784	\$28,889	\$708,673	11,889		
DECOMMISSIONING ACTIVITIES															
A Greenfield Backfill, grade and landscape site		\$165,109								\$165,109	\$37,800	\$202,909		1,787	
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:		\$165,109								\$165,109	\$37,800	\$202,909		1,787	
DECOMMISSIONING PERIOD DEPENDENT															
PD Greenfield Utility Staff	\$52,051									\$52,051	\$7,000	\$59,051	943		
PD Greenfield OGC Staff	\$390,828									\$390,828	\$58,000	\$448,828	4,589		
PD Greenfield Security	\$14,518									\$14,518	\$2,200	\$16,718	826		
PD Greenfield HP Supplies															
PD Greenfield Equipment			\$74,824							\$74,824	\$16,700	\$91,524			
PD Greenfield Unit 1 Insurance									\$28,572	\$28,572	\$4,400	\$32,972			
PD Greenfield Unit 2 Insurance									\$28,572	\$28,572	\$4,400	\$32,972			
PD Greenfield O & M Budget Items			\$7,038							\$7,038	\$1,600	\$8,638			
PD Greenfield Permits & Fees									\$20,054	\$20,054	\$3,000	\$23,054			
PD Greenfield Waste Transfer and Loading		\$248,430								\$248,430	\$36,700	\$285,130		4,889	
PD Greenfield Energy								\$6,053		\$6,053	\$1,000	\$7,053			
PD Greenfield Severance	\$177,796									\$177,796	\$28,700	\$206,496			
PD Greenfield Small Tools			\$6,281							\$6,281	\$2,100	\$8,381			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$626,289	\$248,430	\$81,305					\$6,053	\$76,198	\$1,088,444	\$187,400	\$1,275,844	6,284	4,889	
TOTAL PERIOD 8 - RESTORE SITE COSTS:	\$1,882,884	\$414,439	\$123,449					\$7,381	\$187,238	\$1,788,248	\$234,289	\$2,022,537	18,246	6,446	
ACTIVITY															
UNIT 1															
Unit 1 Subtotal Greenfield (q):															
Unit 1 Subtotal 10 CFR 60.64(h):															

2012 D. C. Cook
Scenario 3
DEDON, On-Site Dry Storage, 2032 Repository and Current Acceptance Rate

Type	UNIT 2	Unit 1 Subtotal Greenfield (g): Unit 1 Subtotal 10 CFR 60.54(b):	Unit 1 Subtotal Greenfield (g): Unit 1 Subtotal 10 CFR 60.54(b):	Unit 2 Subtotal Greenfield (g): Unit 2 Subtotal 10 CFR 60.54(b):	Unit 1, Unit 2 & Common Total Greenfield (g): Total 10 CFR 60.54(b):	Staff Labor	Craft Labor	Equipment & Materials	Packaging	Transportation	Clean Disposal	Contaminated Disposal	Energy	Other	Without Contingency	Contingency	With Contingency	Staff Materials	Craft Materials	Craft Materials
	UNIT 2	Unit 1 Subtotal Greenfield (g): Unit 1 Subtotal 10 CFR 60.54(b):																		
	Common	Common Subtotal Greenfield (g): Common Subtotal 10 CFR 60.54(b):																		
	PERIOD DEPENDENT																			
	UNIT 1	Unit 1 Subtotal Greenfield (g): Unit 1 Subtotal 10 CFR 60.54(b):																		
	UNIT 2	Unit 2 Subtotal Greenfield (g): Unit 2 Subtotal 10 CFR 60.54(b):																		
	Common	Common Subtotal Greenfield (g): Common Subtotal 10 CFR 60.54(b):																		
	Unit 1, Unit 2 & Common	Total Greenfield (g): Total 10 CFR 60.54(b):																		
	PERIOD 7 - DRY STORAGE COSTS:																			
	SPENT FUEL ACTIVITIES																			
	7 A 50.54(b)	Common to ship fuel to repository																		
	SUBTOTAL - SPENT FUEL ACTIVITIES																			
	SPENT FUEL PERIOD DEPENDENT																			
	7 PO 50.54(b)	Unit Staff																		
	7 PO 50.54(b)	Security																		
	7 PO 50.54(b)	Insurance																		
	7 PO 50.54(b)	O & M Budget Items																		
	7 PO 50.54(b)	Permits & Fees																		
	7 PO 50.54(b)	Vehicle Transfer and Loading																		
	7 PO 50.54(b)	Energy																		
	7 PO 50.54(b)	Equipment																		
	7 PO 50.54(b)	HP Supplies																		
	7 PO 50.54(b)	Spent Fuel Storage Maintenance Supplies																		
	7 PO 50.54(b)	Severance																		
	7 PO 50.54(b)	Small Tools																		
	SUBTOTAL - SPENT FUEL PERIOD DEPENDENT																			
	SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT																			
	TOTAL PERIOD 7 - DRY STORAGE COSTS:																			
	ACTIVITY																			
	Common	Common Subtotal 10 CFR 60.78(c): Common Subtotal 10 CFR 60.54(b):																		
	PERIOD DEPENDENT																			
	Common	Common Subtotal 10 CFR 60.78(c): Common Subtotal 10 CFR 60.54(b):																		
	Unit 1, Unit 2 & Common	Total 10 CFR 60.78(c): Total 10 CFR 60.54(b):																		
	PERIOD 8 - RFSI REMOVAL COSTS:																			
	SPENT FUEL PERIOD DEPENDENT																			
	8 PO 50.54(b)	Unit Staff																		
	8 PO 50.54(b)	DGC Staff																		
	8 PO 50.54(b)	Security																		

2012 D. G. Galt
Scenario 3
DECON, On-Site Dry Storage, 2012 Inventory and Closure Assistance Rate

Type	Off Labor \$	Off Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Up Costs \$	Contingency \$	Energy \$	Other \$	Off Labor \$	Contingency \$	Off Labor \$	Bluff Materials	Off Labor \$	Off Labor \$
PD 50.54(bb) HP Supplies			\$21,692								\$21,692	\$5,500	\$27,692	2,835	
PD 50.54(bb) Insurance									\$44,827		\$44,827	\$6,700	\$51,327		
PD 50.54(bb) Equipment			\$106,615								\$106,615	\$10,700	\$117,315		
PD 50.54(bb) O & M Budget Items			\$29,396								\$29,396	\$7,300	\$36,696		
PD 50.54(bb) Permits & Fees									\$5,527		\$5,527	\$800	\$6,327		
PD 50.54(bb) Waste Transfer and Loading															
PD 50.54(bb) Energy								\$1,241			\$1,241	\$200	\$1,441		
PD 50.54(bb) Special Fuel Storage Maintenance Supplies											\$639,367	\$65,000	\$704,367		
PD 50.54(bb) Severance	\$639,367										\$21,308	\$5,300	\$26,608		
PD 50.54(bb) Small Tools			\$21,308												
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$1,601,683		\$179,303					\$1,241	\$50,144	\$1,732,691	\$391,809	\$1,694,381	16,698		
TOTAL PERIOD 1 - BPSI REMOVAL COSTS:	\$1,601,683	\$2,100,798	\$179,303					\$1,241	\$50,144	\$3,863,347	\$748,109	\$4,611,447	36,698	22,624	
ACTIVITY															
Common															
Total 10 CFR 80.7(c):															
Common Subtotal Greenfield (g)															
Common Subtotal 50.54 (bb)		\$2,130,798								\$2,130,798	\$498,309	\$2,629,107		22,624	
PERIOD DEPENDENT															
Common															
Total 10 CFR 80.7(c):															
Common Subtotal Greenfield (g)															
Common Subtotal 50.54 (bb)	\$1,601,683		\$179,303					\$1,241	\$50,144	\$1,732,691	\$391,809	\$1,694,381	16,698		
Unit 1, Unit 2 & Common															
Total 10 CFR 80.7(c):															
Total Greenfield (g)															
Total 50.54(bb)	\$1,601,683	\$2,130,798	\$179,303					\$1,241	\$50,144	\$3,863,347	\$748,109	\$4,611,447	36,698	22,624	
TOTAL ACTIVITY COSTS:															
UNIT 1															
SUBTOTAL UNIT 1 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 8		\$27,393,348	\$3,888,688	\$58,184	\$10,823,883		\$87,844,688			\$120,484,728	\$42,891,159	\$173,388,878		6,760	431,184
SUBTOTAL UNIT 1 10 CFR 50.54(bb) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 1 GREENFIELD COSTS FOR PERIODS 1 - 8		\$12,599,482	\$1,338,137		\$793,162	\$3,622,682	\$916,444			\$19,157,907	\$6,049,609	\$25,207,516		240,864	
UNIT 2															
SUBTOTAL UNIT 2 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 8	\$61,231	\$28,801,849	\$4,327,838	\$640,827	\$10,393,679		\$94,461,285			\$149,868,303	\$47,244,688	\$197,112,991		6,760	688,757
SUBTOTAL UNIT 2 10 CFR 50.54(bb) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 2 GREENFIELD COSTS FOR PERIODS 1 - 8		\$10,794,486	\$1,788,182		\$829,626	\$6,187,360				\$28,706,653	\$9,915,600	\$38,622,253		401,621	
COMMON															
SUBTOTAL COMMON 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 8	\$6,419,483	\$17,837,783	\$2,886,308	\$30,222	\$282,843		\$4,487,631			\$28,269,286	\$8,322,900	\$36,592,186	160,190	74,834	\$6,821
SUBTOTAL COMMON 10 CFR 50.54(bb) COSTS FOR PERIODS 1 - 8	\$748,487	\$20,846,048	\$141,432,900							\$183,821,588	\$40,238,900	\$224,060,488	7,304	65,804	
SUBTOTAL COMMON GREENFIELD COSTS FOR PERIODS 1 - 8		\$22,748,441	\$8,848,963		\$2,952,184	\$17,287,483				\$41,768,177	\$9,708,200	\$51,476,377		301,209	
TOTAL PERIOD DEPENDENT COSTS															
UNIT 1															
SUBTOTAL UNIT 1 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 8	\$28,177,442		\$12,836,167					\$1,292,288	\$2,382,287	\$41,548,222	\$7,487,500	\$49,035,732	164,738		
SUBTOTAL UNIT 1 10 CFR 50.54(bb) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 1 GREENFIELD COSTS FOR PERIODS 1 - 8															
UNIT 2															
SUBTOTAL UNIT 2 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 2 10 CFR 50.54(bb) COSTS FOR PERIODS 1 - 8															
SUBTOTAL UNIT 2 GREENFIELD COSTS FOR PERIODS 1 - 8															
COMMON															
SUBTOTAL COMMON 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 8	\$28,848,896	\$14,883,047	\$23,282,815					\$11,817,283	\$16,784,864	\$28,727,495	\$48,812,100	\$35,540,595	2,896,420		289,316
SUBTOTAL COMMON 10 CFR 50.54(bb) COSTS FOR PERIODS 1 - 8	\$148,873,841		\$16,350,280					\$801,893	\$24,108,825	\$197,082,718	\$20,495,240	\$217,577,958	2,748,641		
SUBTOTAL COMMON GREENFIELD COSTS FOR PERIODS 1 - 8	\$12,881,820	\$2,448,183	\$2,897,314					\$164,746	\$786,484	\$19,282,046	\$3,270,300	\$22,552,346	138,812	46,307	
UNIT 1, UNIT 2 & COMMON															
GRAND TOTAL ACTIVITY COSTS FOR PERIODS 1-8	\$10,314,127	\$188,867,438	\$164,344,858	\$1,263,763	\$26,688,377	\$28,087,418	\$182,178,746			\$677,816,788	\$168,268,600	\$846,085,388	108,100	1,149,846	1,062,864
GRAND TOTAL PERIOD DEPENDENT COSTS FOR PERIODS 1-8	\$380,851,420	\$17,231,178	\$66,217,147					\$16,248,248	\$63,048,312	\$840,421,398	\$26,843,100	\$926,264,498	6,987,268	40,307	289,814
GRAND TOTAL	\$400,786,596	\$174,189,616	\$230,562,002	\$1,265,023	\$26,688,377	\$28,087,418	\$198,178,746	\$16,248,248	\$83,048,312	\$1,517,832,613	\$246,049,600	\$1,762,889,886	115,088	1,190,153	1,352,678
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 80.7(c):	\$28,177,442	\$27,393,348	\$19,482,837	\$58,184	\$10,823,883	\$87,844,688	\$1,292,288	\$2,382,287	\$17,843,600	\$60,128,600	\$241,881,610	\$64,735	6,760	431,184	
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 50.54(bb):															
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (g):		\$12,599,482	\$1,338,137		\$793,162	\$3,622,682	\$916,444			\$19,157,907	\$6,049,609	\$25,207,516		240,864	

2012 D.C. Desk
Scenario 3
DECON, On-Site Dry Storage, 2032 Repository and Current Acceptance Rate

Item	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	with Contingency \$	Contingency \$	with Contingency \$	Staff Materials	Craft Materials	Craft Materials
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 64.74(c):	\$61,231	\$25,091,844	\$4,387,456	\$940,477	\$10,884,679		\$44,861,986			\$149,884,203	\$47,244,884	\$183,210,845		\$,740	\$86,787
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 64.74(d):															
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (b):		\$26,794,486	\$1,786,182		\$828,638	\$4,187,366				\$23,704,843	\$6,932,809	\$34,637,653		\$86,821	
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 64.74(c):	\$216,283,215	\$32,420,766	\$30,046,133	\$30,232	\$262,463		\$8,467,831	\$11,817,283	\$15,794,644	\$321,086,781	\$66,234,400	\$277,320,181	\$,696,416	\$4,834	\$28,838
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 64.74(d):	\$144,423,047	\$20,846,049	\$167,733,380					\$881,833	\$34,128,826	\$389,104,367	\$88,322,000	\$429,426,367	\$,777,408	\$6,964	
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (b):	\$12,891,820	\$26,186,610	\$11,836,597		\$2,882,184	\$17,307,463		\$164,746	\$780,444	\$71,016,882	\$13,146,800	\$84,163,683	\$36,412	\$87,688	
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 64.74(c):	\$241,481,889	\$44,706,041	\$88,868,369	\$1,262,758	\$21,066,436		\$191,369,151	\$12,169,099	\$16,193,813	\$690,896,915	\$163,817,800	\$792,683,618	\$,161,382	\$8,364	\$1,342,788
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 64.74(d):	\$144,423,047	\$20,846,049	\$167,733,380					\$881,833	\$34,128,826	\$389,104,367	\$88,322,000	\$429,426,367	\$,777,408	\$6,964	
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (b):	\$12,891,820	\$26,186,610	\$11,836,597		\$2,882,184	\$17,307,463		\$164,746	\$780,444	\$71,016,882	\$13,146,800	\$84,163,683	\$36,412	\$87,688	
GRAND TOTAL	\$400,796,756	\$174,186,660	\$228,882,602	\$1,262,758	\$28,866,377	\$28,867,415	\$192,178,746	\$14,246,346	\$53,046,313	\$1,117,822,813	\$246,048,800	\$1,382,891,613	\$,983,368	\$1,996,231	\$1,342,788

2012 U.C. Cost
Summary 4
SAFSTOR, Permanent On-Site Dry Storage

Task	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Permitting \$	Transportation \$	Clean Channel \$	Contaminated Channel \$	Energy \$	Other \$	Subtotal without Contingency \$	Contingency \$	Total with Contingency \$	Shift Manhours	Clean Craft Manhours	Contaminated Craft Manhours
PERIOD 1 - U1 & U2 DECOMMISSIONING PLANNING COST:															
SPENT FUEL ACTIVITIES															
1 A 50.54(b) Modify spent fuel support systems										\$62,772	\$8,400	\$72,172	608		
1 A 50.54(b) Define systems modification										\$147,690	\$22,000	\$169,690	1,508		
1 A 50.54(b) Design systems modification and equipment specifications										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Prepare installation procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Prepare test procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Prepare maintenance procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Control room relocation										\$62,772	\$8,400	\$72,172	608		
1 A 50.54(b) Define control room equipment										\$176,962	\$20,000	\$203,782	1,898		
1 A 50.54(b) Design control room relocation and equipment specifications										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Prepare installation procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Prepare test procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Prepare maintenance procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Design spent fuel storage security modifications										\$25,408	\$4,400	\$33,888	288		
1 A 50.54(b) Define modification										\$102,741	\$18,400	\$118,141	1,318		
1 A 50.54(b) Design modification and equipment specifications										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Prepare installation procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Prepare test procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) Prepare maintenance procedures										\$18,349	\$2,800	\$21,149	192		
1 A 50.54(b) 10761 Post Construction										\$25,102,477	\$5,763,400	\$30,005,877	182		
SUBTOTAL - SPENT FUEL ACTIVITIES	3748,487	435,162,477								\$28,951,564	\$5,876,288	\$34,727,164	7,304		
SPENT FUEL PERIOD DEPENDENT															
1 PD 50.54(b) Utility Staff															
1 PD 50.54(b) Security															
1 PD 50.54(b) Insurance															
1 PD 50.54(b) O & M Budget Items									\$2,179,335	\$2,179,335	\$336,000	\$2,605,335			
1 PD 50.54(b) Permits & Fees															
1 PD 50.54(b) Waste Transfer and Loading															
1 PD 50.54(b) E-Waste															
1 PD 50.54(b) Spent Fuel Storage Maintenance Supplies															
1 PD 50.54(b) Small Tools										\$251,025	\$62,800	\$313,625			
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT									\$2,179,335	\$2,430,360	\$339,790	\$2,829,080			
DECOMMISSIONING ACTIVITIES															
1 A 50.75(a) Primary system decontamination															
1 A 50.75(a) Define scope										\$41,836	\$6,200	\$47,836	328		
1 A 50.75(a) Estimate resources										\$53,024	\$8,000	\$61,024	448		
1 A 50.75(a) Prepare bid specifications and RFP										\$52,889	\$7,000	\$60,788	512		
1 A 50.75(a) Qualify Contractors										\$14,104	\$2,100	\$16,204	112		
1 A 50.75(a) Evaluate Proposals										\$38,339	\$5,600	\$44,139	248		
1 A 50.75(a) Select SAFSTOR General Contractor										\$79,043	\$11,000	\$91,083	736		
1 A 50.75(a) Define scope										\$84,013	\$12,600	\$96,613	776		
1 A 50.75(a) Prepare bid specifications and RFP										\$21,846	\$3,200	\$24,846	176		
1 A 50.75(a) Qualify Contractors										\$38,339	\$5,600	\$44,139	248		
1 A 50.75(a) Evaluate Proposals										\$47,781	\$7,200	\$54,981	436		
1 A 50.75(a) U1 & U2 Site Characterization										\$63,495	\$8,000	\$71,495	496		
1 A 50.75(a) Define scope										\$21,846	\$3,200	\$24,846	176		
1 A 50.75(a) Prepare bid specifications and RFP										\$48,339	\$6,800	\$54,139	248		
1 A 50.75(a) Qualify Contractors										\$133,040	\$19,500	\$152,040	1,208		
1 A 50.75(a) Evaluate Proposals															
1 A 50.75(a) Prepare procedures															
ADMINISTRATIVE ACTIVITIES															
1 A 50.75(a) Develop staff transfer plan										\$41,832	\$6,200	\$47,732	382		
1 A 50.75(a) Develop severance and vacation policy										\$45,028	\$6,800	\$51,828	408		
1 A 50.75(a) Prepare project administrative procedures										\$208,076	\$31,400	\$240,400	2,240		
1 A 50.75(a) Develop area based decommissioning cost estimate										\$30,924	\$4,100	\$35,024	648		
1 A 50.75(a) Develop project budget and schedule controls										\$24,307	\$3,000	\$27,307	296		
1 A 50.75(a) Assemble plant drawings										\$36,216	\$5,400	\$41,516	280		
1 A 50.75(a) Define end product										\$223,854	\$33,800	\$257,454	2,440		
1 A 50.75(a) Develop technical approach and detailed project plan															
LICENSING/PERMITTING DOCUMENTATION															
1 A 50.75(a) Insurance coverage										\$48,144	\$6,900	\$55,044	376		
1 A 50.75(a) Prepare Post-Shutdown Decommissioning Activities Report										\$194,389	\$28,200	\$224,789	1,400		
1 A 50.75(a) Prepare certification of permanent cessation of operations										\$6,143	\$800	\$6,943	40		
1 A 50.75(a) Prepare certification of permanent reactor shutdown										\$6,143	\$800	\$6,943	40		
1 A 50.75(a) Prepare post-shutdown technical specification modifications										\$35,049	\$5,000	\$40,049	340		
1 A 50.75(a) Update FSAR										\$31,424	\$4,700	\$36,124	336		
1 A 50.75(a) Develop certified fuel handler program										\$36,166	\$5,400	\$41,566	336		
1 A 50.75(a) Prepare post-shutdown emergency plan										\$162,778	\$24,400	\$187,178	1,480		

2072 D. C. Cook
Scenario 4
SAFSTOR, Permanent On-Site Dry Storage

1	A 50.76(c)	Prepare post-shutdown QA plan	\$104,139			\$104,139	\$16,900	\$119,739	1,000
1	A 50.76(c)	Prepare post-shutdown security plan	\$104,139			\$104,139	\$16,900	\$119,739	1,000
1	A 50.76(c)	Prepare post-shutdown fire protection plan	\$104,139			\$104,139	\$16,900	\$119,739	1,000
1	A 50.76(c)	Prepare post-shutdown radiation protection manual	\$104,139			\$104,139	\$16,900	\$119,739	1,000
1	A 50.76(c)	Prepare and submit state and local permits	\$95,422			\$95,422	\$14,300	\$109,722	960
1	A 50.76(c)	Respond to NRC conditions on PSDAP	\$6,143			\$6,143	\$903	\$7,043	40
1	A 50.76(c)	Prepare detailed real-time loaded project schedule	\$386,157			\$386,157	\$28,400	\$294,557	2,460
1	A 50.76(c)	Perform 50.59 unreviewed safety questions	\$82,271			\$82,271	\$13,960	\$106,071	738
1	A 50.76(c)	Prepare activity specifications	\$170,077			\$170,077	\$25,500	\$195,577	16,000
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:			\$1,475,898			\$1,475,898	\$219,840	\$1,695,438	86,198
DECOMMISSIONING PERIOD DEPENDENT									
1	PD 50.76(c)	Utility Staff	\$4,421,337			\$4,421,337	\$683,200	\$5,104,537	75,444
1	PD 50.76(c)	D3C Staff	\$4,463,843			\$4,463,843	\$674,100	\$5,137,943	53,158
1	PD 50.76(c)	Security	\$691,477			\$691,477	\$102,200	\$793,677	22,881
1	PD 50.76(c)	HR Supplies		\$267,551		\$267,551	\$71,900	\$339,451	
1	PD 50.76(c)	Equipment		\$162,532		\$162,532	\$38,100	\$200,632	
1	PD 50.76(c)	Unit 1 Insurance			\$842,613	\$842,613	\$125,400	\$968,013	
1	PD 50.76(c)	Unit 2 Insurance							
1	PD 50.76(c)	O & M Budget Items		\$12,078,778		\$12,078,778	\$2,015,700	\$14,094,478	
1	PD 50.76(c)	Permits & Fees			\$1,806,577	\$1,806,577	\$225,900	\$2,032,477	
1	PD 50.76(c)	Waste Transfer and Loading							
1	PD 50.76(c)	Energy		\$4,026,190		\$4,026,190	\$603,900	\$4,630,090	
1	PD 50.76(c)	Supervisors	\$15,571,825			\$15,571,825	\$2,335,800	\$17,907,625	
1	PD 50.76(c)	Small Tools							
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT			\$25,188,883	\$12,518,871		\$4,026,190	\$2,348,100	\$44,061,812	\$7,851,188
TOTAL PERIOD 1 - U1 & U2 DECOMMISSIONING PLANNING COSTS:			\$26,383,807	\$25,102,477	\$12,768,888	\$4,026,190	\$4,627,828	\$76,818,874	\$14,647,394
ACTIVITY									
UNIT 1 - PERIOD 1 COSTS									
Unit 1 Subtotal to CFR 50.76(c):									
Unit 1 Subtotal to CFR 50.84(b):									
UNIT 2									
Unit 2 Subtotal to CFR 50.76(c):									
Unit 2 Subtotal to CFR 50.84(b):									
Common									
Total to CFR 50.76(c):			\$3,475,838			\$3,475,838	\$536,800	\$4,012,638	80,182
Total to CFR 50.84(b):			\$749,487	\$28,102,477		\$28,851,964	\$8,674,270	\$37,526,194	7,394
PERIOD DEPENDENT									
UNIT 1 - PERIOD 1 COSTS									
Unit 1 Subtotal to CFR 50.76(c):									
Unit 1 Subtotal to CFR 50.84(b):									
UNIT 2									
Unit 2 Subtotal to CFR 50.76(c):									
Unit 2 Subtotal to CFR 50.84(b):									
Common									
Total to CFR 50.76(c):				\$351,825		\$2,476,336	\$2,430,588	\$285,700	\$2,822,088
Total to CFR 50.84(b):									
Unit 1, Unit 2 & Common			\$28,844,121		\$12,518,871	\$4,026,190	\$2,348,100	\$47,637,281	\$8,392,000
Total to CFR 50.76(c):			\$749,487	\$28,102,477	\$28,851,968	\$2,476,336	\$2,348,100	\$34,582,323	\$6,587,800
Total to CFR 50.84(b):									
PERIOD 2 - POST-SHUTDOWN ACTIVITIES COSTS:									
SPENT FUEL ACTIVITIES									
2	A 50.54(b)	Modify spent fuel cooling system	\$234,804	\$1,155,000		\$1,389,804	\$438,800	\$2,228,604	8,300
2	A 50.54(b)	Modify control room	\$882,042	\$800,000		\$1,682,042	\$228,800	\$1,910,842	6,900
2	A 50.54(b)	Modify security system	\$465,796	\$325,000		\$790,796	\$238,900	\$1,029,696	7,200
2	A 50.54(b)	Purchase 10501 cables		\$115,785,000		\$115,785,000	\$28,646,300	\$144,431,300	7,280
SUBTOTAL - SPENT FUEL ACTIVITIES			\$1,582,642	\$119,275,000		\$118,044,842	\$29,653,800	\$147,698,642	33,680
SPENT FUEL PERIOD DEPENDENT									
2	PD 50.54(b)	Utility Staff	\$3,468,380			\$3,468,380	\$620,100	\$4,088,480	57,880
2	PD 50.54(b)	Security	\$1,367,810			\$1,367,810	\$205,100	\$1,572,910	36,834
2	PD 50.54(b)	Insurance			\$880,663	\$880,663	\$140,500	\$1,021,163	
2	PD 50.54(b)	O & M Budget Items							

2012 D-6 Cook
Scenario 4
SAFSTOR, Permanent On-Site Dry Storage

2	PD 50.54(bb)	Permits & Fees				\$892,936	\$892,936	\$102,400	\$786,536		
2	PD 50.54(bb)	Waste Transfer and Loading									
2	PD 50.54(bb)	Energy				\$832,582	\$832,582	\$124,000	\$697,482		
2	PD 50.54(bb)	Spent Fuel Storage Maintenance Supplies		\$378,477			\$378,477	\$94,900	\$474,377		
2	PD 50.54(bb)	Small Tools		\$18,718			\$18,718	\$4,200	\$24,918		
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT			\$4,136,987	\$194,186		\$832,582	\$1,478,619	\$7,744,375	\$1,281,346	\$8,945,073	\$4,718
DECOMMISSIONING ACTIVITIES											
2	A 50.75(c)	Primary System Decom Unit 1 & 2		\$8,548,040	\$1,417,080		\$6,088,840	\$18,828,780	\$5,175,800	\$24,100,880	
2	A 50.75(c)	Flash & Drain Systems (Performed by Utility Staff)									
2	A 50.75(c)	Decontamination & clean up Reactor Buildings (Performed by Utility Staff)									
2	A 50.75(c)	Install emission control monitors		\$30,103	\$43,780			\$13,063	\$17,990	\$91,793	450
2	A 50.75(c)	Perform quarterly inspections		\$36,522				\$36,522	\$5,800	\$47,322	360
2	A 50.75(c)	Perform semi-annual environmental surveys		\$36,522				\$36,522	\$5,800	\$47,322	360
2	A 50.75(c)	Prepare SAFSTOR reports		\$12,627				\$12,627	\$2,000	\$15,527	90
2	A 50.75(c)	Historical Site Assessment		\$375,892				\$375,892	\$56,400	\$432,292	4,800
2	A 50.75(c)	Characterization survey		\$780,088				\$780,088	\$118,400	\$898,488	12,800
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:			\$1,164,869	\$8,668,212	\$1,480,868	\$5,868,640	\$20,288,282	\$6,384,800	\$26,642,282	17,760	1,296
DECOMMISSIONING PERIOD DEPENDENT											
2	PD 50.75(p)	Utility Staff		\$15,439,888				\$15,439,888	\$2,315,800	\$17,755,688	254,328
2	PD 50.75(p)	DGC Staff		\$1,789,573				\$3,789,873	\$556,400	\$4,346,273	47,360
2	PD 50.75(p)	Security		\$2,713,153				\$2,713,153	\$407,000	\$3,120,153	105,240
2	PD 50.75(p)	VIP Supplies			\$381,304			\$381,304	\$56,500	\$437,804	
2	PD 50.75(p)	Equipment			\$285,376			\$285,376	\$71,300	\$356,676	
2	PD 50.75(c)	Unit 1 Insurance					\$225,282	\$225,282	\$33,800	\$259,082	
2	PD 50.75(c)	Unit 2 Insurance					\$225,282	\$225,282	\$33,800	\$259,082	
2	PD 50.75(c)	C & M Budget Item			\$2,441,808			\$2,441,808	\$610,500	\$3,052,308	
2	PD 50.75(c)	Permits & Fees					\$1,785,814	\$1,785,814	\$283,400	\$2,069,214	
2	PD 50.75(c)	Waste Transfer and Loading									
2	PD 50.75(c)	Energy				\$4,116,228		\$4,116,228	\$617,300	\$4,733,528	
2	PD 50.75(c)	Sewerage		\$22,920,511				\$22,920,511	\$3,438,100	\$26,358,611	
2	PD 50.75(c)	Small Tools			\$175,310			\$175,310	\$45,000	\$220,310	
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT			\$44,888,927	\$5,241,708		\$4,116,228	\$2,208,378	\$54,443,333	\$9,482,704	\$63,926,037	488,828
TOTAL PERIOD 1 - POST-SHUTDOWN ACTIVITIES COSTS:			\$48,998,883	\$10,337,704	\$123,263,864	\$8,986,840	\$4,547,791	\$7,888,997	\$20,382,878	\$45,038,808	\$547,421,478
ACTIVITY											
UNIT 1											
Unit 1 Subtotal 10 CFR 50.75(p):				\$4,273,823	\$708,548		\$4,480,328	\$8,464,888	\$2,584,400	\$13,069,288	
Unit 1 Subtotal 10 CFR 50.54(bb):											
UNIT 2											
Unit 2 Subtotal 10 CFR 50.75(p):				\$4,273,823	\$708,548		\$4,480,328	\$8,464,888	\$2,584,400	\$13,069,288	
Unit 2 Subtotal 10 CFR 50.54(bb):											
Common											
Common Subtotal - 10 CFR 50.74(c):			\$1,164,869	\$189,773	\$43,780			\$1,318,822	\$212,400	\$1,531,222	17,760
Common Subtotal - 10 CFR 50.54(bb):				\$1,871,281	\$118,278,000			\$119,848,881	\$28,882,404	\$148,731,285	31,280
PERIOD DEPENDENT											
UNIT 1											
Unit 1 Subtotal 10 CFR 50.75(p):											
Unit 1 Subtotal 10 CFR 50.54(bb):											
UNIT 2											
Unit 2 Subtotal 10 CFR 50.75(p):											
Unit 2 Subtotal 10 CFR 50.54(bb):											
Common											
Common Subtotal - 10 CFR 50.75(c):			\$44,888,927	\$5,241,708	\$5,261,739	\$4,116,228	\$2,208,378	\$64,443,333	\$9,482,704	\$73,926,037	488,828
Common Subtotal - 10 CFR 50.54(bb):			\$4,876,987		\$288,188	\$832,582	\$1,878,619	\$7,744,375	\$1,281,346	\$9,026,721	\$4,718
Unit 1, Unit 2 & Common								\$72,187,708	\$13,764,146	\$85,951,854	
Total 10 CFR 50.75(p):			\$46,034,884	\$9,689,812	\$4,732,889	\$8,986,840	\$4,116,228	\$7,470,161	\$13,878,708	\$21,348,869	1,296
Total 10 CFR 50.54(bb):			\$4,876,987	\$1,871,281	\$118,278,188		\$832,582	\$1,878,619	\$7,744,375	\$9,626,464	\$5,130
PERIOD 2 - DORMANCY WITH WET & DRY SPENT FUEL STORAGE:								\$202,202,878			
SPENT FUEL ACTIVITIES											
3	A 50.54(bb)	Purchase ISFSI casks:		\$115,785,000				\$115,785,000	\$28,882,400	\$144,667,400	7,200
SUBTOTAL - SPENT FUEL ACTIVITIES				\$115,785,000				\$115,785,000	\$28,882,400	\$144,667,400	7,200

2012 D.C. Cook
Scenario A
SAFSTOR, Permanent On-Site Dry Storage

SPENT FUEL PERIOD DEPENDENT												
3	PD 50.54(b)	Utility Staff	\$18,116,910					\$18,116,910	\$2,717,800	\$20,834,710	202,376	
3	PD 50.54(b)	Security	\$7,144,482					\$7,144,482	\$1,071,799	\$8,216,281	102,421	
3	PD 50.54(b)	Insurance				\$5,206,696		\$5,206,696	\$781,200	\$5,987,896		
3	PD 50.54(b)	HP Supplies		\$433,631				\$433,631	\$108,400	\$542,031		
3	PD 50.54(b)	Permits & Fees				\$3,887,875		\$3,887,875	\$635,200	\$4,523,075		
3	PD 50.54(b)	O & M Budget Items		\$2,696,446				\$2,696,446	\$724,100	\$3,420,546		
3	PD 50.54(b)	Waste Transfer and Loading										
3	PD 50.54(b)	Energy					\$2,812,716	\$2,812,716	\$421,000	\$3,233,716		
3	PD 50.54(b)	Spent Fuel Storage Maintenance Supplies		\$1,862,365				\$1,862,365	\$495,500	\$2,357,865		
3	PD 50.54(b)	Small Tools										
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT			\$86,943,372	\$6,912,472		\$2,812,716	\$8,774,471	\$12,162,828	\$8,855,780	\$19,018,608	484,796	
DECOMMISSIONING ACTIVITIES												
3	A 50.75(c)	Perform quarterly inspections		\$231,131				\$231,131	\$50,100	\$281,231	2,160	
3	A 50.75(c)	Perform semi-annual environmental surveys		\$231,131				\$231,131	\$50,100	\$281,231	2,160	
3	A 50.75(c)	Prepare SAFSTOR reports		\$75,780				\$75,780	\$17,400	\$93,180	676	
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:				\$538,042				\$538,042	\$117,600	\$655,642	4,996	
DECOMMISSIONING PERIOD DEPENDENT												
3	PD 50.75(c)	Utility Staff										
3	PD 50.75(c)	DGO Staff										
3	PD 50.75(c)	Security	\$1,881,308					\$1,881,308	\$253,700	\$1,945,008	84,977	
3	PD 50.75(c)	HP Supplies										
3	PD 50.75(c)	Equipment		\$126,873				\$126,873	\$31,700	\$158,573		
3	PD 50.75(c)	Unit 1 Insurance				\$1,178,878		\$1,178,878	\$178,550	\$1,357,428		
3	PD 50.75(c)	Unit 2 Insurance				\$1,178,878		\$1,178,878	\$178,550	\$1,357,428		
3	PD 50.75(c)	O & M Budget Items										
3	PD 50.75(c)	Permits & Fees				\$6,784,772		\$6,784,772	\$1,017,700	\$7,802,472		
3	PD 50.75(c)	Waste Transfer and Loading										
3	PD 50.75(c)	Energy				\$846,800		\$846,800	\$97,000	\$943,800		
3	PD 50.75(c)	Stewards	\$8,445,085					\$8,445,085	\$986,500	\$9,431,585		
3	PD 50.75(c)	Small Tools		\$10,780					\$2,700	\$13,480		
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT			\$8,138,384	\$137,654		\$648,600	\$8,138,638	\$18,089,187	\$2,722,600	\$20,811,787	84,977	
TOTAL PERIOD 3 - DORMANCY WITH WET & DRY SPENT FUEL STORAGE COSTS:			\$95,081,756	\$678,922	\$121,336,104	\$1,461,316	\$17,512,809	\$17,848,108	\$16,644,380	\$18,183,308	569,774	12,178
ACTIVITY												
UNIT 1												
Unit 1 Subtotal to CFR 50.75(c):												
Unit 1 Subtotal to CFR 50.84(b):												
UNIT 2												
Unit 2 Subtotal to CFR 50.75(c):												
Unit 2 Subtotal to CFR 50.84(b):												
Common												
Common Subtotal - to CFR 50.75(c):				\$538,042				\$538,042	\$122,600	\$660,642	4,996	
Common Subtotal - to CFR 50.84(b):					\$116,786,800			\$116,786,800	\$28,848,300	\$145,635,100	7,280	
PERIOD DEPENDENT												
UNIT 1												
Unit 1 Subtotal to CFR 50.75(c):												
Unit 1 Subtotal to CFR 50.84(b):												
UNIT 2												
Unit 2 Subtotal to CFR 50.75(c):												
Unit 2 Subtotal to CFR 50.84(b):												
Common												
Common Subtotal - to CFR 50.75(c):			\$8,138,384	\$137,654		\$648,600	\$8,138,638	\$18,089,187	\$2,722,600	\$20,811,787	84,977	
Common Subtotal - to CFR 50.84(b):			\$25,383,372	\$5,312,472		\$1,461,316	\$17,512,809	\$17,848,108	\$16,644,380	\$18,183,308	569,774	
PERIOD 4 - DORMANCY WITH DRY SPENT FUEL STORAGE:												
SPENT FUEL ACTIVITIES												
SPENT FUEL PERIOD DEPENDENT												
4	PD 50.54(b)	Utility Staff	\$88,618,276					\$88,618,276	\$13,262,700	\$101,880,976	1,327,130	
4	PD 50.54(b)	Security	\$44,710,289					\$44,710,289	\$6,705,500	\$51,415,789	1,117,500	
4	PD 50.54(b)	Insurance				\$8,065,209		\$8,065,209	\$1,343,300	\$9,408,509		
4	PD 50.54(b)	HP Supplies		\$3,015,195				\$3,015,195	\$733,800	\$3,749,000		

2012 D. C. D. C.
Example 4
SAFSTOR, Permanent On-Site Dry Storage

4	PD 50.54(b)	C & M Budget Items	\$5,780,562			\$5,780,562	\$1,447,808	\$7,228,370	
4	PD 50.54(b)	Permit & Fees			\$17,340,293	\$17,340,293	\$2,865,000	\$19,205,293	
4	PD 50.54(b)	Waste Transfer and Loading							
4	PD 50.54(b)	Energy		\$208,123		\$208,123	\$128,200	\$1,044,328	
4	PD 50.54(b)	Spent Fuel Storage Maintenance Supplies	\$9,716,408			\$9,716,408	\$1,878,100	\$8,285,308	
4	PD 50.54(b)	Small Tools							
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT			\$19,328,644	\$18,032,189	\$808,123	\$28,196,161	\$176,884,084	\$27,945,280	\$109,999,660
DECOMMISSIONING ACTIVITIES									
4	A 50.75(c)	Perform quarterly inspections	\$7,288,467			\$7,288,467	\$527,700	\$2,828,187	21,400
4	A 50.75(c)	Perform semi-annual environmental surveys	\$2,288,467			\$2,288,467	\$527,700	\$2,828,187	21,400
4	A 50.75(c)	Prepare SAFSTOR reports	\$713,353			\$713,353	\$173,000	\$556,353	5,728
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:			\$10,289,287			\$10,289,287	\$1,228,400	\$6,172,527	48,528
DECOMMISSIONING PERIOD DEPENDENT									
4	PD 50.75(c)	Utility Staff							
4	PD 50.75(c)	DGC Staff							
4	PD 50.75(c)	Security	\$17,190,007			\$17,190,007	\$2,576,803	\$19,766,810	538,794
4	PD 50.75(c)	HP Supplies							
4	PD 50.75(c)	Equipment	\$244,778			\$244,778	\$181,200	\$808,876	
4	PD 50.75(c)	Unit 1 Insurance			\$11,861,863	\$11,861,863	\$1,784,300	\$13,756,163	
4	PD 50.75(c)	Unit 2 Insurance			\$11,861,863	\$11,861,863	\$1,784,300	\$13,756,163	
4	PD 50.75(c)	C & M Budget Items							
4	PD 50.75(c)	Permit & Fees			\$62,009,379	\$62,009,379	\$9,004,400	\$80,033,779	
4	PD 50.75(c)	Waste Transfer and Loading							
4	PD 50.75(c)	Energy		\$6,572,091		\$6,572,091	\$983,800	\$7,555,891	
4	PD 50.75(c)	Severance	\$633,417			\$633,417	\$128,000	\$808,417	
4	PD 50.75(c)	Small Tools		\$197,007		\$197,007	\$26,800	\$193,807	
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT			\$18,023,945	\$781,781	\$6,572,091	\$85,382,144	\$18,478,400	\$126,771,404	\$88,794
TOTAL PERIOD 4 - DORMANCY WITH DRY SPENT FUEL STORAGE COSTS:			\$181,363,437	\$6,360,357	\$18,073,874	\$7,480,216	\$118,148,546	\$280,808,687	\$45,844,800
ACTIVITY									
UNIT 1									
Unit 1 Subtotal 10 CFR 50.74(c):									
Unit 1 Subtotal 10 CFR 50.54(b):									
UNIT 2									
Unit 2 Subtotal 10 CFR 50.74(c):									
Unit 2 Subtotal 10 CFR 50.54(b):									
Commons									
Common Subtotal - 10 CFR 50.74(c):			\$8,368,327			\$8,368,327	\$1,228,400	\$6,878,727	48,528
Common Subtotal - 10 CFR 50.54(b):									
PERIOD DEPENDENT									
UNIT 1									
Unit 1 Subtotal 10 CFR 50.74(c):									
Unit 1 Subtotal 10 CFR 50.54(b):									
UNIT 2									
Unit 2 Subtotal 10 CFR 50.74(c):									
Unit 2 Subtotal 10 CFR 50.54(b):									
Commons									
Common Subtotal - 10 CFR 50.74(c):			\$18,023,945	\$781,781	\$6,572,091	\$85,382,144	\$18,478,400	\$126,771,404	\$88,794
Common Subtotal - 10 CFR 50.54(b):			\$133,339,494	\$18,622,183	\$208,123	\$26,196,591	\$176,884,084	\$27,945,280	\$109,999,660
Unit 1, Unit 2 & Commons									
Total 10 CFR 50.74(c):			\$18,023,945	\$781,781	\$6,572,091	\$85,382,144	\$18,478,400	\$126,771,404	\$88,794
Total 10 CFR 50.54(b):			\$133,339,494	\$18,622,183	\$208,123	\$26,196,591	\$176,884,084	\$27,945,280	\$109,999,660
Check									
PERIOD 5 - DORMANCY WITH DECOMMISSIONING PLANNING COST:									
SPENT FUEL PERIOD DEPENDENT									
5	PD 50.54(b)	Utility Staff	\$5,870,204				\$8,970,004	\$1,320,560	\$9,970,564
5	PD 50.54(b)	Security	\$4,374,247				\$4,374,247	\$666,100	\$5,050,347
5	PD 50.54(b)	Insurance				\$218,120	\$878,193	\$131,400	\$1,097,593
5	PD 50.54(b)	HP Supplies							

SAFSTOR, Permanent On-Site Dry Storage

5	PO 50.5-4(a)	O & M Budget Items				\$1,696,711	\$1,696,711	\$293,000	\$1,393,711		
5	PO 50.5-4(b)	Permits & Fees									
5	PO 50.5-4(b)	Waste Transfer and Loading									
5	PO 50.5-4(b)	Energy				\$68,847	\$68,847	\$13,300	\$102,147		
5	PO 50.5-4(b)	Spent Fuel Storage/Maintenance Supplies		6957,102			\$697,102	\$164,300	\$621,402		
5	PO 50.5-4(b)	Small Tools									
SUBTOTAL - SPENT PERIOD DEPENDENT			\$13,044,880	\$667,302		\$68,847	\$2,882,047	\$18,363,046	\$2,816,890	\$18,871,646	238,181
DECOMMISSIONING ACTIVITIES											
Select Decommissioning General Contractor											
5	A 50.75(c)	Define scope	\$70,080								
5	A 50.75(c)	Prepare bid specifications and RFP	\$64,010					\$76,653	\$11,900	\$81,583	738
5	A 50.75(c)	Qualify Contractors	\$21,846					\$84,013	\$12,600	\$86,613	770
5	A 50.75(c)	Evaluate Proposals	\$30,338					\$21,846	\$3,200	\$24,846	178
5	A 50.75(c)	U1 & U2 add and draft site repointing						\$38,339	\$5,600	\$44,139	248
5	A 50.75(c)	Define scope	\$88,277								
5	A 50.75(c)	Design modification and equipment specifications	\$150,932					\$66,277	\$10,200	\$78,477	618
5	A 50.75(c)	Prepare installation procedures	\$21,274					\$160,932	\$22,600	\$179,532	1,590
5	A 50.75(c)	Prepare test procedures	\$16,346					\$21,274	\$31,900	\$244,824	2,080
5	A 50.75(c)	Modify U1 & U2 containment access						\$18,349	\$3,800	\$21,149	162
5	A 50.75(c)	Select new access location	\$30,261								
5	A 50.75(c)	Design access and equipment specifications	\$133,533					\$30,261	\$4,500	\$34,761	278
5	A 50.75(c)	U1 & U2 Site Characterization						\$133,533	\$20,000	\$153,533	1,320
5	A 50.75(c)	Define scope	\$17,784								
5	A 50.75(c)	Prepare bid specifications and RFP	\$53,488					\$47,781	\$7,200	\$54,981	408
5	A 50.75(c)	Qualify Contractors	\$21,846					\$53,488	\$9,000	\$61,488	495
5	A 50.75(c)	Evaluate Proposals	\$30,338					\$21,846	\$5,800	\$24,846	178
5	A 50.75(c)	Prepare procedures	\$133,300					\$38,139	\$5,600	\$44,139	248
5	A 50.75(c)	ADMINISTRATIVE ACTIVITIES						\$133,000	\$19,900	\$152,900	1,298
5	A 50.75(c)	Prepare project administrative procedures	\$45,028								
5	A 50.75(c)	Develop area based decommissioning cost estimate	\$269,038					\$45,028	\$6,900	\$51,928	460
5	A 50.75(c)	Develop project budget and schedule controls	\$60,824					\$269,038	\$31,400	\$294,438	2,340
5	A 50.75(c)	Assemble plant drawings	\$24,307					\$60,824	\$9,100	\$70,024	545
5	A 50.75(c)	Define end product	\$30,216					\$24,307	\$3,800	\$27,087	206
5	A 50.75(c)	Develop technical approach and detailed project plans	\$223,854					\$30,216	\$5,400	\$34,110	260
5	A 50.75(c)	LICENSING/PERMITTING DOCUMENTATION						\$223,854	\$33,600	\$267,454	2,140
5	A 50.75(c)	Prepare post-shutdown emergency plan	\$182,776								
5	A 50.75(c)	Prepare post-shutdown QA plan	\$104,138					\$182,776	\$24,400	\$187,176	1,480
5	A 50.75(c)	Prepare post-shutdown remedy plan	\$104,138					\$104,138	\$16,800	\$119,738	1,000
5	A 50.75(c)	Prepare post-shutdown the protection plan	\$104,138					\$104,138	\$16,800	\$119,738	1,000
5	A 50.75(c)	Prepare post-shutdown radiation protection manual	\$104,138					\$104,138	\$16,800	\$119,738	1,000
5	A 50.75(c)	Prepare and submit state and local permits	\$55,422								
5	A 50.75(c)	Prepare detailed resource based project schedule	\$298,157					\$55,422	\$14,200	\$100,722	960
5	A 50.75(c)	Prepare facility specifications	\$1,700,771					\$298,157	\$36,400	\$294,057	2,480
5	A 50.75(c)	Prepare detailed work procedures	\$1,800,383					\$1,700,771	\$285,100	\$1,986,871	16,090
5	A 50.75(c)	Select shipping costs and obtain permits	\$24,092					\$1,800,383	\$340,700	\$1,845,083	16,080
5	A 50.75(c)	Implement cold & dirt						\$24,092	\$3,600	\$27,692	240
5	A 50.75(c)	Modify U1 Containment Access		\$761,635	\$1,800,000			\$2,361,038	\$574,700	\$2,935,738	11,520
5	A 50.75(c)	Modify U2 Containment Access		\$346,437	\$925,000			\$971,437	\$210,800	\$1,082,237	5,780
5	A 50.75(c)	Visual and infrared activation analysis	\$100,380					\$346,437	\$52,800	\$1,052,237	5,780
5	A 50.75(c)	Characterization survey	\$769,000					\$100,380	\$16,400	\$125,780	940
5	A 50.75(c)	Test special equipment and training						\$769,000	\$116,400	\$907,400	12,580
5	A 50.75(c)	LICENSE TERMINATION PLAN						\$638,723	\$216,500	\$1,165,553	13,440
5	A 50.75(c)	General information	\$1,380								
5	A 50.75(c)	Site Characterization	\$32,667					\$1,380	\$200	\$1,080	18
5	A 50.75(c)	Identification of remaining site dismantlement activities	\$33,267					\$32,667	\$5,100	\$39,067	328
5	A 50.75(c)	Formaldehyde Plans	\$17,880					\$33,267	\$5,100	\$39,067	330
5	A 50.75(c)	Final Radiation Survey Plan	\$230,813					\$17,880	\$2,700	\$20,580	178
5	A 50.75(c)	Compliance with the radiological criteria for license termination	\$227,508					\$230,813	\$30,800	\$386,813	3,620
5	A 50.75(c)	Update decommissioning cost estimate	\$55,404					\$227,508	\$34,100	\$281,008	2,440
5	A 50.75(c)	Supplement to the environmental report	\$55,404					\$55,404	\$8,200	\$63,704	588
5	A 50.75(c)	Response to NRC questions	\$25,093					\$55,404	\$8,200	\$63,704	588
5	A 50.75(c)	Update LTP	\$51,042					\$25,093	\$3,000	\$28,093	200
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS			\$7,730,882	\$2,381,432	\$1,860,000			\$12,774,404	\$2,371,690	\$19,146,094	82,880
DECOMMISSIONING PERIOD DEPENDENT											
5	PO 50.75(a)	Utility Grant	\$26,317,410								
5	PO 50.75(a)	DGO Draft	\$3,059,721								
5	PO 50.75(a)	Security	\$1,661,640					\$26,317,410	\$4,250,000	\$33,934,010	451,028
5	PO 50.75(a)	HP Supplies						\$3,059,721	\$529,600	\$4,020,321	
5	PO 50.75(a)	Equipment						\$1,661,640	\$272,800	\$1,894,140	54,670
5	PO 50.75(a)	Unit 1 Insurance						\$263,199	\$700,000	\$1,000,199	
5	PO 50.75(a)	Unit 2 Insurance						\$2,263,865	\$566,000	\$2,879,865	
5	PO 50.75(a)	O & M Budget Items						\$1,170,205	\$175,500	\$1,345,705	
5	PO 50.75(a)	Permits & Fees						\$1,170,205	\$175,500	\$1,345,705	
5	PO 50.75(a)							\$688,525	\$141,600	\$708,125	
5	PO 50.75(a)							\$5,872,898	\$860,900	\$6,733,798	
								\$5,872,898	\$860,900	\$6,733,798	

SAFETOP, Permanent On-Site Dry Storage

4	PD 50.75(a)	Waste Transfer and Loading																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
---	-------------	----------------------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

445 STOP. Permanent On-Off Dry Storage

A 50.75(c)	Decommission Internals and platform and store (BY UTILITY STAFF)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

SAFSTOR, Permanent On-Site Dry Storage

Unit 1, Unit 2 & Common															
	Total 19 CFR 84.74(c):	199,523,684	840,728,784	119,607,072	6887,790	110,489,344	193,083,107	112,711,784	17,378,892	128,812,050	168,344,700	328,181,780	926,003	787,316	
	Total 19 CFR 84.44(b)(i):	58,549,798		3473,703				889,814	11,843,848	111,745,973	11,911,809	115,874,773	173,041		
	Total Greenfield:		19,710,438	1883,346		1178,105	1878,866			111,822,741	12,389,360	113,816,681		193,911	
PERIOD 7 DECONTAMINATE BALANCE OF SITE COSTS:															
SPENT FUEL PERIOD DEPENDENT															
7	PD 50.54(a)	Utility Staff	\$4,082,939							\$4,082,939	\$703,800	\$5,396,639	7C,276		
7	PD 50.54(b)	Security	\$2,387,561							\$2,387,561	\$306,100	\$2,722,661	55,190		
7	PD 50.54(b)	Internal							\$474,225	\$474,209	\$71,100	\$545,309			
7	PD 50.54(b)	HP Supplies													
7	PD 50.54(b)	C & M Budget Items													
7	PD 50.54(b)	Permits & Fees							9812,932	9812,932	\$130,300	\$1,045,032			
7	PD 50.54(b)	Waste Transfer and Loading													
7	PD 50.54(b)	Energy						\$40,008		\$40,008	\$7,200	\$55,388			
7	PD 50.54(b)	Spent Fuel Storage Maintenance Supplies			\$365,857					\$365,857	\$88,000	\$444,857			
7	PD 50.54(b)	Small Tools													
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT			\$7,880,299		\$365,857			\$42,898	\$1,387,141	\$8,861,086	\$1,383,188	\$10,214,188	128,466		
DECOMMISSIONING ACTIVITIES															
7	A 50.75(c)	Design, remove, package, ship and dispose of Unit 2 contaminated systems		\$18,830,283	\$404,125	\$106,907	\$800,063		\$15,182,461	\$33,432,411	\$8,007,800	\$42,440,211		334,974	
7	A 50.75(c)	Remove, package, ship and dispose of Unit 2 clean systems		\$17,827,319	\$959,654		\$285,891	\$1,514,788		\$20,604,231	\$4,546,500	\$26,150,731	356,573		
7	A 50.75(c)	Design Steam Generator Storage Building		\$80,053	\$27,869	\$409	\$6,024		\$273,080	\$387,433	\$113,800	\$501,033		1,000	
7	A 50.75(c)	Design Unit 2 Reactor Building		\$4,415,224	\$659,223	\$116,438	\$2,677,802		\$13,822,464	\$21,980,162	\$5,180,100	\$28,160,262		80,870	
7	A 50.75(c)	Remove spent fuel storage racks		\$2,881,453	\$50,370	\$6,348	\$13,305		\$1,088,758	\$4,248,314	\$1,112,700	\$5,362,014		32,024	
7	A 50.75(c)	Design Auxiliary Building		\$1,898,990	\$695,318	\$10,990	\$106,899		\$9,801,700	\$2,831,000	\$11,634,700				
7	A 50.75(c)	Perform final radiological survey of all structures		\$1,826,530	\$34,100				\$1,862,720	\$428,400	\$2,291,120				
7	A 50.75(c)	Perform final survey of the site		\$8,631,000	\$210,000				\$8,841,640	\$2,266,400	\$11,107,440				
7	A 50.75(c)	Obtain NRC approval													
7	A 50.75(c)	Prepare final report of decommissioning program	\$49,382						\$49,382	\$7,400	\$56,782	409			
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:			\$49,382	\$84,482,828	\$3,311,487	\$841,783	\$3,888,683	\$1,614,788	\$37,461,440	\$19,121,044	\$28,293,899	\$27,814,844	468	368,873	
DECOMMISSIONING PERIOD DEPENDENT															
7	PD 50.75(c)	Utility Staff	\$24,683,033							\$24,683,033	\$3,690,500	\$28,302,533	388,602		
7	PD 50.75(c)	DGIC Staff	\$27,842,248							\$27,842,248	\$4,170,300	\$32,018,548	374,807		
7	PD 50.75(c)	Security	\$3,571,497							\$3,571,497	\$555,700	\$4,087,197	194,987		
7	PD 50.75(c)	HP Supplies			\$5,780,287					\$5,780,287	\$1,442,100	\$7,200,387			
7	PD 50.75(c)	Equipment			\$4,801,093					\$4,801,093	\$1,237,800	\$6,038,893			
7	PD 50.75(c)	Unit 1 Insurance							\$633,422	\$633,422	\$95,000	\$728,422			
7	PD 50.75(c)	Unit 2 Insurance							\$633,422	\$633,422	\$98,000	\$731,422			
7	PD 50.75(c)	C & M Budget Items			\$572,245					\$572,245	\$143,100	\$715,345			
7	PD 50.75(c)	Permits & Fees							\$3,897,470	\$3,897,470	\$590,100	\$4,487,570			
7	PD 50.75(c)	Waste Transfer and Loading			\$6,390,385					\$6,390,385	\$1,462,480	\$7,783,798		123,313	
7	PD 50.75(c)	Energy						\$9,070,009		\$9,070,009	\$1,360,500	\$10,430,509			
7	PD 50.75(c)	Supervision	\$688,975							\$688,975	\$130,300	\$1,022,275			
7	PD 50.75(c)	Small Tools			\$1,215,259					\$1,215,259	\$394,100	\$1,609,359			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT			\$37,288,742	\$6,338,386	\$19,609,633			\$9,070,009	\$6,234,316	\$89,868,914	\$18,329,898	\$108,428,914	\$92,487	123,313	
TOTAL PERIOD 7 DECONTAMINATE BALANCE OF SITE COSTS:			\$44,476,946	\$90,811,824	\$18,167,877	\$841,783	\$3,308,683	\$1,614,788	\$37,461,440	\$40,118,898	\$48,421,486	\$104,873,984	\$45,898,884	1,403,499	368,873
ACTIVITY															
UNIT 1															
Unit 1 Subtotal 19 CFR 84.74(c):															
Unit 1 Subtotal Greenfield:															
UNIT 2															
Unit 2 Subtotal 19 CFR 84.74(c):															
Unit 2 Subtotal Greenfield:															
Common															
Common Subtotal 19 CFR 84.74(c):															
Common Subtotal Greenfield:															
PERIOD DEPENDENT															
UNIT 1															
Unit 1 Subtotal 19 CFR 84.74(c):															
Unit 1 Subtotal 19 CFR 84.44(b)(i):															
UNIT 2															
Unit 2 Subtotal 19 CFR 84.74(c):															
Unit 2 Subtotal 19 CFR 84.44(b)(i):															

SAFSTOR, Permethrin On-Site Dry Storage

Common													
Common Subtotal - 10 CFR 60.75(c):	\$17,266,242	\$6,336,298	\$12,929,943			\$9,079,009	\$8,234,318	\$90,000,914	\$15,329,000	\$105,828,914	902,687	122,319	
Common Subtotal - 10 CFR 60.84(d):	\$7,060,300		\$385,687			148,688	\$1,287,161	\$8,861,000	\$1,363,100	\$10,224,100	128,486		
Unit 1, Unit 2 & Common													
Total 10 CFR 60.75(c):	\$17,416,106	\$42,998,908	\$14,848,480	\$64,1763	\$2,873,003	\$37,481,480	\$9,870,000	\$8,234,318	\$17,121,730	\$17,676,400	\$201,804,528	802,863	872,845
Total 10 CFR 60.84(d):	\$7,060,300		\$205,887				249,098	\$1,287,161	\$9,881,000	\$1,363,100	\$10,224,100	128,486	
Total Greenfield:		\$17,827,310	\$980,464		\$288,691	\$1,614,788		\$4,648,880	\$28,160,731			368,873	

PERIOD 8 - CLEAN STRUCTURE DEMOLITION COSTS:

SPENT FUEL PERIOD DEPENDENT

PD 50.54(h)	Utility Staff	\$2,622,676			\$2,622,676	\$193,400	\$3,616,076	39.27%
PD 50.54(h)	Security	\$1,323,210			\$1,323,210	\$186,560	\$1,621,710	33.67%
PD 50.54(h)	Insurance				\$265,031	\$39,000	\$304,031	
PD 50.54(h)	HP Supplies		\$49,235		\$49,235	\$22,360	\$111,856	
PD 50.54(h)	C & M Budget Items							
PD 50.54(h)	Permits & Fees				\$510,230	\$76,690	\$666,730	
PD 50.54(h)	Waste Transfer and Loading							
PD 50.54(h)	Energy				\$28,676	\$4,000	\$32,676	
PD 50.54(h)	Spent Fluid Storage Maintenance Supplies		\$198,773		\$198,773	\$49,760	\$248,473	
PD 50.54(h)	Small Tools							

SUBTOTAL : SPENT FUEL PERIOD DEPENDENT

DECOMMISSIONING ACTIVITIES

7	A Greenfield	Remove Unit 1 reactor building	\$1,461,505	\$938,412	\$541,175	\$3,143,736	\$8,069,921	\$965,800	\$8,935,721	24,370
8	A Greenfield	Remove Unit 2 reactor building	\$1,491,500	\$903,472	\$581,175	\$3,143,736	\$8,069,921	\$965,800	\$8,935,721	24,370
9	A Greenfield	Remove Auxiliary Building	\$12,106,653	\$4,332,287	\$1,624,741	\$6,922,088	\$27,093,046	\$6,272,400	\$39,228,046	102,482
10	A Greenfield	Remove Turbine Building	\$6,645,258	\$3,523,051	\$1,140,834	\$6,827,787	\$19,750,500	\$19,874,339	\$137,370	
11	A Greenfield	Remove Steam Generator Storage Building	\$150,400	\$60,387	\$82,467	\$304,494	\$843,096	\$105,800	\$762,686	3,181
12	A Greenfield	Remove Electrical Transformer	\$61,805	\$2,808	\$15,944	\$81,000	\$30,900	\$320,315	1,859	
13	A Greenfield	Removal of Unit 1 Turbine Generator	\$152,820	\$7,399	\$1,746	\$45,000	\$213,248	\$43,100	\$259,345	2,087
14	A Greenfield	Removal of Unit 1 Main Condenser	\$1,353,080	\$7,427	\$165,013	\$492,046	\$1,919,254	\$374,660	\$2,293,854	21,890
15	A Greenfield	Removal of Unit 2 Turbine Generator	\$152,820	\$7,399	\$1,746	\$45,000	\$213,245	\$43,100	\$259,345	2,087
16	A Greenfield	Removal of Unit 2 Main Condenser	\$1,332,968	\$7,427	\$165,013	\$492,046	\$1,916,254	\$374,660	\$2,290,854	21,890
17	A Greenfield	Removal of Standby Diesel Generators	\$30,412	\$8,447	\$2,324	\$18,500	\$52,052	\$10,400	\$63,062	532
18	A Greenfield	Remove Administration building	\$300,700	\$100,702			\$44,200	\$495,051	4,408	
19	A Greenfield	Remove Low Level Radiactive building	\$1,107,591	\$170,895	\$136,848	\$794,643	\$2,711,593	\$404,600	\$2,816,060	18,026

SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:

DECOMMISSIONING PERIOD DEPENDENT

PO Greenfield	Utility Bill	\$1,780,173			\$1,780,173	\$399,400	\$2,024,173	27,569
PO Greenfield	DGC Roll	\$7,422,808			\$7,422,808	\$1,113,400	\$8,536,208	93,713
PO Greenfield	Security	\$752,785			\$752,785	\$112,800	\$865,608	10,204
PO Greenfield	HP Supplies		\$89,235		\$89,235	\$22,200	\$111,535	
PO Greenfield	Equipment		\$2,209,740		\$2,209,740	\$882,400	\$2,702,140	
PO Greenfield	Unit 1 Insurance			\$380,237	\$380,237	\$56,000	\$436,237	
PO Greenfield	Unit 2 Insurance			\$380,237	\$380,237	\$36,000	\$416,237	
PO Greenfield	C & M Budget Items		\$42,024		\$42,024	\$32,972	\$75,000	
PO Greenfield	Permits & Fees				\$178,472	\$216,400	\$394,872	
PO Greenfield	Waste Transfer and Loading	\$2,180,103			\$2,180,103	\$46,700	\$2,226,803	41,351
PO Greenfield	Energy			\$324,673	\$324,673	\$100,400	\$425,073	
PO Greenfield	Insurance	\$3,036,673			\$3,036,673	\$440,000	\$3,526,673	
PO Greenfield	Smart Tools	\$611,805			\$611,805	\$165,000	\$776,805	

SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT

TOTAL PERIOD B - CLEAN STRUCTURE DEMOLITION COSTS.

ACTIVITY

UNIT 1

Unit 1 Subtotal Greenfield (g):	\$2,907,100	\$018,738	\$033,834	\$1,082,682	\$0,102,421	\$1,303,300	\$0,488,921	48,847
Unit 2 Subtotal Greenfield (g):	\$2,907,100	\$018,738	\$033,834	\$0,082,682	\$0,102,421	\$1,303,300	\$0,488,921	48,847
Common Subtotal Greenfield (g)	\$22,471,037	\$0,000,104	\$0,001,878	\$17,144,848	\$0,127,180	\$0,677,300	\$0,104,018	107,761

PERIOD DEPENDENT

UNIT 1

Unit 1 Subtotal Greenfield (g):

2012 D.C. Cook
Scenario 4
SAFETOP, Permanent On-Site Dry Storage

Unit 1 Subtotal 10 CFR 50.54(b):

UNIT 2

Unit 2 Subtotal Greenfield (g):

Unit 2 Subtotal 10 CFR 50.54(b):

Common

Common Subtotal Greenfield (g):

Common Subtotal - 10 CFR 50.54(b):

Unit 1, Unit 2 & Common

Total Greenfield (g):

Total 10 CFR 50.54(b):

PERIOD 9 - RESTORE SITE COSTS:

SPENT FUEL PERIOD DEPENDENT

9	PD Greenfield	Utility Staff	\$286,001					\$286,001	\$44,700	\$342,701	4,463
9	PD Greenfield	Security	\$150,366					\$150,366	\$22,600	\$172,966	2,768
9	PD Greenfield	Insurance					\$30,117	\$30,117	\$4,620	\$34,737	440
9	PD Greenfield	HP Supplies			\$10,140			\$10,140	\$2,800	\$12,940	161
9	PD Greenfield	O & M Budget Items									
9	PD Greenfield	Permits & Fees					\$57,561	\$57,561	\$5,700	\$63,261	808
9	PD Greenfield	Waste Transfer and Loading									
9	PD Greenfield	Energy					\$3,054	\$3,054	\$500	\$3,554	45
9	PD Greenfield	Spent Fuel Storage Maintenance Supplies			\$22,000			\$22,000	\$5,000	\$27,000	340
9	PD Greenfield	Small Tools									
		SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$446,366	\$35,740		\$3,054	\$95,699	\$572,878	\$88,700	\$661,578	5,223

DECOMMISSIONING ACTIVITIES

9	A Greenfield	Backfill, grade and landscape site	\$188,100					\$188,100	\$38,100	\$226,200	1,757
		SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$188,100					\$188,100	\$38,100	\$226,200	1,757

DECOMMISSIONING PERIOD DEPENDENT

9	PD Greenfield	Utility Staff	\$112,771					\$112,771	\$16,900	\$129,671	1,598
9	PD Greenfield	O&M Staff	\$305,026					\$305,026	\$58,600	\$363,626	4,598
9	PD Greenfield	Security	\$42,240					\$42,240	\$6,300	\$48,540	610
9	PD Greenfield	HP Supplies			\$10,140			\$10,140	\$2,800	\$12,940	161
9	PD Greenfield	Equipment			\$74,626			\$74,626	\$18,700	\$93,326	1,184
9	PD Greenfield	Unit 1 Insurance					\$20,672	\$20,672	\$4,400	\$25,072	315
9	PD Greenfield	Unit 2 Insurance					\$20,672	\$20,672	\$4,400	\$25,072	315
9	PD Greenfield	O & M Budget Items			\$7,040			\$7,040	\$1,000	\$8,040	101
9	PD Greenfield	Permits & Fees					\$20,054	\$20,054	\$3,000	\$23,054	290
9	PD Greenfield	Waste Transfer and Loading			\$240,430			\$240,430	\$57,000	\$297,430	3,748
9	PD Greenfield	Energy					\$25,000	\$25,000	\$3,000	\$28,000	350
9	PD Greenfield	Severance	\$444,869					\$444,869	\$66,700	\$511,569	6,404
9	PD Greenfield	Small Tools							\$2,100	\$2,100	26
		SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$1,444,126	\$248,430	\$109,163	\$25,000	\$75,168	\$1,692,887	\$246,300	\$1,939,187	23,944

TOTAL PERIOD 9 - RESTORE SITE COSTS:

ACTIVITY

UNIT 1

Unit 1 Subtotal Greenfield (g):

UNIT 2

Unit 2 Subtotal Greenfield (g):

Common

Common Subtotal Greenfield (g):

PERIOD DEPENDENT

UNIT 1

Unit 1 Subtotal Greenfield (g):

Unit 1 Subtotal 10 CFR 50.54(b):

UNIT 2

Unit 2 Subtotal Greenfield (g):

Unit 2 Subtotal 10 CFR 50.54(b):

Common

Common Subtotal Greenfield (g):

2012 D. O. Cook
Scenario 4
BAFSTOR, Permanent On-Site Dry Storage

Common Subtotal - 10 CFR 80.54(bb)			\$448,898		\$52,729		\$3,864	\$88,788	\$872,278	\$89,100	\$881,378	0.222				
Unit 1, Unit 2 & Common																
Total Greenfield (gr)			\$980,434	\$414,538	\$100,183		\$28,860	\$73,188	\$1,870,334	\$284,400	\$1,894,834	1.204	0.486			
Total 10 CFR 80.54(bb)			\$448,898		\$52,729		\$3,864	\$88,788	\$872,278	\$89,100	\$881,378	0.222				
PERIOD 10 COSTS:																
SPENT FUEL ACTIVITIES																
SPENT FUEL PERIOD DEPENDENT																
10	PD 80.54(bb)	Utility Staff	\$1,878,146						\$1,878,145	\$296,900	\$2,275,045	29.639				
10	PD 80.54(bb)	Security	\$808,631						\$808,531	\$146,800	\$1,146,831	24.960				
10	PD 80.54(bb)	Insurance						\$200,000	\$200,000	\$20,000	\$220,000					
10	PD 80.54(bb)	O & M Budget Items			\$122,823				\$126,823	\$12,900	\$142,228					
10	PD 80.54(bb)	Permits & Fees						\$385,034	\$385,034	\$38,500	\$423,534					
10	PD 80.54(bb)	Waste Transfer and Loading														
10	PD 80.54(bb)	Storage					\$30,281		\$30,281	\$2,050	\$32,281					
10	PD 80.54(bb)	Equipment			\$18,748				\$18,748	\$2,000	\$21,748					
10	PD 80.54(bb)	HP Supplies			\$67,338				\$67,338	\$5,790	\$73,128					
10	PD 80.54(bb)	Spent Fuel Storage Maintenance Supplies			\$160,000				\$160,000	\$15,000	\$165,000					
10	PD 80.54(bb)	Small Tools														
10	PD 80.54(bb)	Severance														
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT			\$2,877,878		\$366,409		\$28,281	\$888,834	\$3,849,481	\$543,890	\$4,403,281	64.889				
TOTAL PERIOD 10 COSTS:			\$2,877,878		\$366,409		\$28,281	\$888,834	\$3,849,481	\$543,890	\$4,403,281	64.889				
ACTIVITY																
Common																
Total 80.54(bb)																
PERIOD DEPENDENT																
Common																
Total 80.54(bb)			\$2,877,878		\$366,409		\$28,281	\$888,834	\$3,849,481	\$543,890	\$4,403,281	64.889				
TOTAL ACTIVITY COSTS:																
UNIT 1																
SUBTOTAL UNIT 1 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 10			\$27,363,348	\$3,886,484	\$876,384	\$8,788,364			\$37,316,148		\$38,981,842	6.780	401.164			
SUBTOTAL UNIT 1 10 CFR 80.54(bb) COSTS FOR PERIODS 1 - 10																
SUBTOTAL UNIT 1 GREENFIELD COSTS FOR PERIODS 1 - 10			\$12,686,482	\$1,238,137		\$793,182	\$4,488,228		\$13,187,007	\$5,831,890	\$21,028,647	240.864				
UNIT 2																
SUBTOTAL UNIT 2 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 10			\$81,331	\$24,991,844	\$4,327,458	\$654,827	\$7,138,050		\$44,329,448		\$111,483,217	8.780	884.787			
SUBTOTAL UNIT 2 10 CFR 80.54(bb) COSTS FOR PERIODS 1 - 10																
SUBTOTAL UNIT 2 GREENFIELD COSTS FOR PERIODS 1 - 10			\$24,784,486	\$1,789,182			\$88,187,350		\$28,708,893	\$5,830,890	\$94,006,993	496.821				
COMMON																
SUBTOTAL COMMON 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 10			\$12,420,122	\$23,846,878	\$2,700,888	\$10,212	\$262,863	\$8,447,811	\$47,427,901	\$18,898,830	\$89,184,101	188.886	78.840			
SUBTOTAL COMMON 10 CFR 80.54(bb) COSTS FOR PERIODS 1 - 10			\$749,487						\$749,487		\$749,487					
SUBTOTAL COMMON GREENFIELD COSTS FOR PERIODS 1 - 10			\$21,748,447	\$8,848,083			\$2,962,164	\$17,207,485	\$51,788,177	\$5,786,238	\$89,824,377	48.560	281.203			
TOTAL PERIOD DEPENDENT COSTS:																
UNIT 1																
SUBTOTAL UNIT 1 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 10			\$68,731,880		\$18,341,832				\$87,073,712		\$105,361,938	889.291				
SUBTOTAL UNIT 1 10 CFR 80.54(bb) COSTS FOR PERIODS 1 - 10																
SUBTOTAL UNIT 1 GREENFIELD COSTS FOR PERIODS 1 - 10																
UNIT 2																
SUBTOTAL UNIT 2 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 10																
SUBTOTAL UNIT 2 10 CFR 80.54(bb) COSTS FOR PERIODS 1 - 10																
SUBTOTAL UNIT 2 GREENFIELD COSTS FOR PERIODS 1 - 10																
COMMON																
SUBTOTAL COMMON 10 CFR 80.7(c) COSTS FOR PERIODS 1 - 10			\$18,888,381	\$14,744,118	\$11,830,388				\$33,114,724	\$187,948,888	\$446,087,609	\$64,545,406	\$471,283,945	2,849,188	287.308	
SUBTOTAL COMMON 10 CFR 80.54(bb) COSTS FOR PERIODS 1 - 10			\$187,210,382		\$83,889,889				\$4,784,179	\$48,488,821	\$276,888,435	\$41,888,790	\$113,827,136	3,688,888		
SUBTOTAL COMMON GREENFIELD COSTS FOR PERIODS 1 - 10			\$15,953,109	\$2,434,811	\$3,879,838				\$354,832	\$778,164	\$108,837,808	\$13,884,808	\$24,222,468	147.274	48.080	
SUBTOTAL COMMON 10 CFR 80.54(bb) COSTS FOR PERIODS 1 - 10			\$691,814,814													
UNIT 1, UNIT 2 & COMMON																
GRAND TOTAL ACTIVITY COSTS FOR PERIODS 1-10			\$13,231,140	\$188,799,887	\$247,818,818	\$1,228,883	\$18,848,279	\$28,891,889	\$136,187,228	\$43,874,881	\$184,732,701	\$18,128,041	\$163,884,700	\$769,222,761	188,888	1,188,888
GRAND TOTAL PERIOD DEPENDENT COSTS FOR PERIODS 1-10			\$488,883,474	\$17,179,731	\$74,332,861									\$918,744,447	7,311,740	287,308
ANNUAL SPENT FUEL STORAGE			\$2,877,878		\$366,409				\$30,281	\$888,834	\$3,849,481	\$543,890	\$4,403,281	\$4,403,281		
GRAND TOTAL			\$881,814,814	\$188,878,623	\$331,348,677	\$1,228,883	\$18,848,279	\$28,891,889	\$136,187,228	\$48,874,881	\$189,732,701	\$18,128,041	\$168,884,700	\$774,032,142	1,188,888	1,548,888

2012 D. C. Cook
Scenario 4
648TOR Permanent On-Site Dry Storage

SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 40.71(c):	\$68,751,858	\$27,348,348	\$20,387,883	\$878,204	\$6,708,284		\$87,316,149	\$8,434,348	\$10,851,778	\$187,049,778	\$43,281,300	\$228,202,879	\$85,381	\$,780	\$31,164
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 40.84(b)(i):		\$19,549,482	\$1,335,137		\$709,183	\$4,488,228				\$18,187,867	\$3,851,800	\$22,039,667		\$40,884	
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (i):															
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 40.71(c):	\$64,221	\$26,081,846	\$4,387,636	\$884,827	\$7,195,656		\$84,383,448			\$111,663,217	\$31,104,300	\$142,807,417		\$,780	\$88,787
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 40.84(b)(i):															
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (i):		\$20,794,485	\$1,758,192		\$823,828	\$5,187,280				\$28,768,883	\$8,850,800	\$34,838,683		\$48,821	
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 40.71(c):	\$231,878,100	\$28,288,883	\$24,350,478	\$20,232	\$292,883		\$5,487,631	\$33,118,724	\$107,308,888	\$463,488,070	\$78,842,800	\$628,427,670	\$,898,188	\$9,840	\$25,192
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 40.84(b)(i):	\$198,888,858	\$26,774,880	\$267,348,883				\$4,784,179	\$48,888,821	\$532,493,288	\$107,733,800	\$440,188,888	\$,843,412	\$8,880		
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (i):	\$13,993,182	\$26,183,888	\$11,821,421		\$2,882,184	\$17,287,483		\$288,832	\$778,144	\$72,393,888	\$13,184,100	\$86,748,788	\$47,778	\$27,283	
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 40.71(c):	\$289,891,204	\$108,888,104	\$98,888,884	\$1,228,883	\$14,188,837		\$18,187,288	\$38,840,888	\$118,470,738	\$781,888,888	\$148,338,888	\$891,327,888	\$,888,447	\$1,280	\$148,888
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 40.84(b)(i):	\$188,888,858	\$26,774,288	\$267,348,883				\$4,784,179	\$48,888,821	\$532,493,288	\$107,733,800	\$440,188,888	\$,843,412	\$8,880		
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (i):	\$13,993,182	\$26,183,888	\$11,821,421		\$2,882,184	\$17,287,483		\$288,832	\$778,144	\$72,393,888	\$13,184,100	\$86,748,788	\$47,778	\$27,283	
GRAND TOTAL	\$801,814,814	\$185,878,888	\$151,248,487	\$1,228,883	\$18,848,279	\$28,883,888	\$128,187,228	\$43,874,881	\$184,732,701	\$1,444,718,888	\$288,188,888	\$1,884,827,188	\$,888,888	\$1,888,888	\$148,888

2012 D. C. Cozart

Scenario 5

DUGON, Wet Storage Modified Systems, 2032 Repository and Current DOE Acceptable Rate

Page 1 of 12
12/3/2012

2012 U. C. Cost
Scenario 5
DECON, Wet Storage, Modified Systems, 2032 Repository and Current DOE Acceptance Rate

	Type	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Decontam. \$	Contaminant Decontam. \$	Remed. \$	Other \$	Wet Storage Construction \$	Construction \$	Wet Storage Construction \$	Staff Materials	Craft Materials	Craft Materials
1	A 50.75(e)	\$223,854									\$223,854	\$33,000	\$257,854	2,440		
	LICENSING/PERMITTING DOCUMENTATION															
1	A 50.75(e)	\$46,144									\$46,144	\$6,500	\$52,644	376		
1	A 50.75(e)	\$134,889									\$134,889	\$20,300	\$155,189	1,400		
1	A 50.75(e)	\$0,143									\$0,143	\$600	\$7,043	40		
1	A 50.75(e)	\$0,143									\$0,143	\$600	\$7,043	40		
1	A 50.75(e)	\$335,249									\$335,249	\$50,300	\$385,549	3,600		
1	A 50.75(e)	\$311,424									\$311,424	\$46,700	\$358,124	3,350		
1	A 50.75(e)	\$36,168									\$36,168	\$5,400	\$41,568	336		
1	A 50.75(e)	\$162,775									\$162,775	\$24,400	\$187,175	1,480		
1	A 50.75(e)	\$104,139									\$104,139	\$15,600	\$119,739	1,000		
1	A 50.75(e)	\$104,139									\$104,139	\$15,600	\$119,739	1,000		
1	A 50.75(e)	\$104,139									\$104,139	\$15,600	\$119,739	1,000		
1	A 50.75(e)	\$95,422									\$95,422	\$14,200	\$109,622	900		
1	A 50.75(e)	\$6,143									\$6,143	\$900	\$7,043	40		
1	A 50.75(e)	\$250,151									\$250,151	\$36,400	\$286,551	2,430		
1	A 50.75(e)	\$62,271									\$62,271	\$9,200	\$71,471	736		
1	A 50.75(e)	\$1,700,771									\$1,700,771	\$255,100	\$1,955,871	18,090		
1	A 50.75(e)	\$1,604,383									\$1,604,383	\$240,700	\$1,845,083	16,060		
1	A 50.75(e)	\$24,032									\$24,032	\$3,600	\$27,632	240		
	LICENSE TERMINATION PLAN															
1	A 50.75(e)	\$1,350									\$1,350	\$200	\$1,550	16		
1	A 50.75(e)	\$33,067									\$33,067	\$5,100	\$38,167	336		
1	A 50.75(e)	\$33,067									\$33,067	\$5,100	\$38,167	336		
1	A 50.75(e)	\$17,880									\$17,880	\$2,700	\$20,580	176		
1	A 50.75(e)	\$390,813									\$390,813	\$50,800	\$441,613	3,620		
1	A 50.75(e)	\$227,508									\$227,508	\$34,100	\$261,608	2,440		
1	A 50.75(e)	\$35,404									\$35,404	\$5,300	\$40,704	390		
1	A 50.75(e)	\$35,404									\$35,404	\$5,300	\$40,704	390		
1	A 50.75(e)	\$25,693									\$25,693	\$3,800	\$29,493	290		
1	A 50.75(e)	\$51,042									\$51,042	\$7,700	\$58,742	536		
	SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$8,889,742									\$8,889,742	\$1,211,899	\$10,101,641	\$1,340		
	DECOMMISSIONING PERIOD DEPENDENT															
1	PD 50.75(e)	\$4,429,012									\$4,429,012	\$684,400	\$5,113,412	75,076		
1	PD 50.75(e)	\$4,493,843									\$4,493,843	\$674,100	\$5,167,943	66,169		
1	PD 50.75(e)	\$682,600									\$682,600	\$102,400	\$785,000	23,001		
1	PD 50.75(e)	\$287,908		\$287,908							\$287,908	\$42,900	\$330,808			
1	PD 50.75(e)	\$152,707		\$152,707							\$152,707	\$23,200	\$175,907			
1	PD 50.75(e)									\$644,076	\$644,076	\$128,800	\$772,876			
1	PD 50.75(e)															
1	PD 50.75(e)			\$12,085,435							\$12,085,435	\$3,023,800	\$15,109,235			
1	PD 50.75(e)									\$1,508,191	\$1,508,191	\$226,200	\$1,734,391			
1	PD 50.75(e)															
1	PD 50.75(e)															
1	PD 50.75(e)									\$1,785,868	\$1,785,868	\$267,800	\$2,053,668			
1	PD 50.75(e)	\$15,071,925									\$15,071,925	\$2,356,800	\$17,428,725			
1	PD 50.75(e)															
	SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$28,177,442		\$12,836,137					\$1,785,868	\$2,352,387	\$41,861,713	\$7,551,600	\$49,413,313	134,736		
	TOTAL PERIOD 1 - U1 & U2 DECOMMISSIONING PLANNING COST:	\$34,816,679		\$12,836,137					\$1,785,868	\$4,704,284	\$50,273,356	\$8,103,499	\$58,376,855	247,788		
	ACTIVITY															
	UNIT 1 - PERIOD 1 COSTS															
	Unit 1 Subtotal 10 CFR 50.75(e):															
	Unit 1 Subtotal 10 CFR 50.54(b):															
	UNIT 2															
	Unit 2 Subtotal 10 CFR 50.75(e):															
	Unit 2 Subtotal 10 CFR 50.54(b):															
	Common															
	Total 10 CFR 50.75(e):	\$8,889,742									\$8,889,742	\$1,211,899	\$10,101,641	\$1,340		
	Total 10 CFR 50.54(b):	\$749,487									\$749,487	\$112,800	\$862,287	7,712		
	PERIOD DEPENDENT															
	UNIT 1 - PERIOD 1 COSTS															
	Unit 1 Subtotal 10 CFR 50.75(e):	\$28,177,442		\$12,836,137					\$1,785,868	\$2,352,387	\$41,861,713	\$7,551,600	\$49,413,313	134,736		
	Unit 1 Subtotal 10 CFR 50.54(b):															
	UNIT 2															

2012 D. C. Cook
Scenario 5
OECON, Wet Storage, Modified Systems, 2032 Repository and Current DOE Acceptance Rate

TYPE		Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	Without Contingency \$	Contingency \$	With Contingency \$	Staff Materials	Craft Materials	Craft Materials
	Unit 2 Subtotal to CFR 80.79(c):															
	Unit 2 Subtotal to CFR 80.84(b)(i):															
	Common															
	Total 10 CFR 80.79(c):															
	Total 10 CFR 80.84(b)(i):															
	Unit 1, Unit 2 & Common															
	Total 10 CFR 80.79(c):															
	Total 10 CFR 80.84(b)(i):															
	PERIOD 2 - POST-SHUTDOWN ACTIVITIES COSTS:															
	SPENT FUEL ACTIVITIES															
2	A 50.54(b) Modify Spent Fuel Cooling System		\$634,094	\$1,098,300							\$1,732,364	\$417,800	\$2,150,164		8,900	
2	A 50.54(b) Modify control room		\$682,042	\$750,000							\$1,332,042	\$319,000	\$1,651,042		9,360	
2	A 50.54(b) Modify security system		\$455,755	\$500,000							\$955,755	\$228,000	\$1,183,755		7,280	
	SUBTOTAL - SPENT FUEL ACTIVITIES		\$1,671,891	\$2,348,300							\$4,080,161	\$964,800	\$5,044,961		25,540	
	SPENT FUEL PERIOD DEPENDENT															
2	PD 50.54(b) Utility Staff	\$4,087,734									\$4,087,734	\$613,200	\$4,700,934	65,218		
2	PD 50.54(b) Security	\$1,611,833									\$1,611,833	\$241,800	\$1,853,633	43,411		
2	PD 50.54(b) Insurance									\$1,174,602	\$1,174,602	\$170,200	\$1,344,802			
2	PD 50.54(b) O & M Budget Items															
2	PD 50.54(b) Permits & Fees									\$804,898	\$804,898	\$120,700	\$925,598			
2	PD 50.54(b) Waste Transfer and Loading															
2	PD 50.54(b) Energy								\$243,401		\$243,401	\$36,000	\$279,401			
2	PD 50.54(b) Spent Fuel Storage Maintenance Supplies			\$447,240							\$447,240	\$111,800	\$559,040			
2	PD 50.54(b) Small Tools			\$16,710							\$16,710	\$4,300	\$20,910			
	SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$6,099,867		\$463,950					\$243,401	\$1,079,859	\$8,064,478	\$1,304,400	\$9,368,878	111,629		
	DECOMMISSIONING ACTIVITIES															
2	A 50.75(c) Primary System: Decon Unit 1 & 2		\$8,545,040	\$1,417,000				\$8,962,040			\$18,029,760	\$5,980,900	\$24,010,660			
2	A 50.75(c) Flush & Drain Systems (PERFORMED BY UTILITY STAFF)															
2	A 50.75(c) Insulation sold & dump		\$761,035	\$1,000,000							\$2,261,035	\$548,900	\$2,809,935		11,800	
2	A 50.75(c) Modify UT Containment Access		\$346,437	\$800,000							\$846,437	\$203,300	\$1,049,737		5,760	
2	A 50.75(c) Modify UT Containment Access		\$346,437	\$800,000							\$846,437	\$203,300	\$1,049,737		5,760	
2	A 50.75(c) Historical Site Assessment	\$379,882									\$379,882	\$56,400	\$436,282		4,660	
2	A 50.75(c) Vessel and Interim Interim Interim	\$108,336									\$108,336	\$16,400	\$124,736		640	
2	A 50.75(c) Characterization survey	\$788,098									\$788,098	\$118,400	\$906,498		12,880	
2	A 50.75(c) Test special equipment and training		\$939,723								\$939,723	\$142,300	\$1,082,023		13,440	
	SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$1,274,908	\$10,935,872	\$3,917,889				\$8,962,040			\$28,097,897	\$7,917,988	\$36,015,885	18,468	38,480	
	DECOMMISSIONING PERIOD DEPENDENT															
2	PD 50.75(c) Utility Staff	\$18,193,241									\$18,193,241	\$2,739,000	\$20,932,241	292,745		
2	PD 50.75(c) O&M Staff	\$11,670,689									\$11,670,689	\$1,750,900	\$13,421,589	187,167		
2	PD 50.75(c) Security	\$3,197,645									\$3,197,645	\$478,900	\$3,676,545	124,932		
2	PD 50.75(c) HP Supplies			\$755,542							\$755,542	\$109,200	\$864,742			
2	PD 50.75(c) Equipment			\$1,017,840							\$1,017,840	\$154,900	\$1,172,740			
2	PD 50.75(c) Unit 1 Insurance									\$285,511	\$285,511	\$43,800	\$329,311			
2	PD 50.75(c) Unit 2 Insurance									\$285,511	\$285,511	\$43,800	\$329,311			
2	PD 50.75(c) O & M Budget Items															
2	PD 50.75(c) Permits & Fees															
2	PD 50.75(c) Waste Transfer and Loading															
2	PD 50.75(c) Energy								\$3,353,502		\$3,353,502	\$504,500	\$3,858,002			
2	PD 50.75(c) Services	\$23,300,805									\$23,300,805	\$3,460,100	\$26,760,905			
2	PD 50.75(c) Small Tools			\$218,793							\$218,793	\$34,700	\$253,493			
	SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$38,562,381		\$4,371,435					\$3,353,502	\$2,800,374	\$47,887,632	\$7,044,332	\$54,931,964	386,884		
	TOTAL PERIOD 2 - POST-SHUTDOWN ACTIVITIES COSTS:	\$43,336,156	\$12,011,963	\$11,696,768				\$8,962,040	\$3,683,962	\$4,079,935	\$104,801,988	\$18,838,888	\$123,640,788	710,912	80,440	
	ACTIVITY															
	UNIT 1															
	Unit 1 Subtotal to CFR 80.79(c):		\$4,819,487	\$1,208,840							\$10,311,317	\$3,083,780	\$13,395,097		5,760	
	Unit 1 Subtotal to CFR 80.84(b)(i):															
	UNIT 2															
	Unit 2 Subtotal to CFR 80.79(c):		\$4,819,487	\$1,208,840							\$10,311,317	\$3,083,780	\$13,395,097		5,760	

2012 D.C. Book
 Appendix C
 DECON, Unit Storage, Modified Systems, 2032 Repository and Current DOE Assistance Rate

Task	Staff Labor, \$	Craft Labor, \$	Equipment & Materials, \$	Permitting, \$	Transportation, \$	Clean Disposal, \$	Contaminated Materials, \$	Storage, \$	Other, \$	Without Certification, \$	Costs, \$	With Certification, \$	Staff Materials	Craft Materials	Craft Materials
UNIT 2 Subtotal 10 CFR 50.54(b)(5):															
Common															
Common Subtotal - 10 CFR 50.75(c):	\$1,274,385	\$1,700,787	\$1,308,085							\$4,475,062	\$850,408	\$5,428,462	14,400	24,960	
Common Subtotal - 10 CFR 50.54(b)(5):	\$1,871,891	\$2,346,309	\$2,346,309							\$4,920,191	\$944,808	\$4,984,891		28,800	
PERIOD DEPENDENT															
UNIT 1															
Unit 1 Subtotal 10 CFR 50.75(c):															
Unit 1 Subtotal 10 CFR 50.54(b)(5):															
UNIT 2															
Unit 2 Subtotal 10 CFR 50.75(c):															
Unit 2 Subtotal 10 CFR 50.54(b)(5):															
Common															
Common Subtotal - 10 CFR 50.75(c):	\$55,262,385	\$4,871,439	\$4,871,439					\$5,043,652	\$2,400,374	\$67,887,432	\$10,851,705	\$77,849,332	\$88,484		
Common Subtotal - 10 CFR 50.54(b)(5):	\$5,899,567	\$493,989	\$493,989					\$243,401	\$1,979,659	\$8,384,478	\$1,204,480	\$9,880,678	\$11,429		
Unit 1, Unit 2 & Common															
Total 10 CFR 50.75(c):	\$57,539,591	\$10,938,472	\$8,788,800				\$8,968,640	\$3,363,652	\$2,608,374	\$82,185,230	\$17,549,590	\$109,764,920	\$99,284	28,800	
Total 10 CFR 50.54(b)(5):	\$5,899,567	\$1,871,391	\$2,812,209					\$243,401	\$1,979,659	\$12,406,688	\$2,209,206	\$14,676,889	\$11,429		28,800
PERIOD 3 VESSEL AND INTERNALS REMOVAL COSTS:															
SPENT FUEL PERIOD DEPENDENT															
3 PD 50.54(b) Utility Staff	\$12,995,106									\$12,995,106	\$1,949,300	\$14,944,406	216,800		
3 PD 50.54(b) Security	\$5,124,120									\$5,124,120	\$768,800	\$5,892,920	184,010		
3 PD 50.54(b) Insurance									\$3,734,324	\$3,734,324	\$560,100	\$4,294,424			
3 PD 50.54(b) O & M Budget Items															
3 PD 50.54(b) Permits & Fees									\$2,968,793	\$2,968,793	\$369,900	\$3,338,693			
3 PD 50.54(b) Waste Transfer and Loading															
3 PD 50.54(b) Energy								\$493,169		\$493,169	\$74,300	\$567,469			
3 PD 50.54(b) Spent Fuel Storage Maintenance Supplies			\$1,421,608							\$1,421,608	\$258,800	\$1,777,308			
3 PD 50.54(b) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$18,119,226		\$1,421,608					\$493,169	\$8,263,114	\$28,323,373	\$4,601,800	\$33,426,973	409,379		
DECOMMISSIONING ACTIVITIES															
UNIT 1															
3 A 50.75(c) Install all reactor operating floor decommissioning control equipment (CCCs), support structures, rigging, internal work platforms and process equipment (BY UTILITY STAFF)															
3 A 50.75(c) Finalize Residual Radiation Inventory (WITH SITE CHARACTERIZATION)															
3 A 50.75(c) Finalize Internals and Vessel Segmentation Details (WITH ACTIVATION ANALYSIS)															
3 A 50.75(c) Remove, package, ship and bury Unit 1 Pressurizer		\$12,604		\$800	\$72,394		\$890,982			\$1,390,860	\$584,400	\$2,574,394			18,778
3 A 50.75(c) Remove, package, ship and bury Unit 1 steam generators		\$4,240,772	\$1,092,597	\$12,609	\$635,287		\$12,054,598			\$18,284,194	\$5,363,700	\$24,247,784			79,182
3 A 50.75(c) Remove Unit 1 equipment hatch closure (BY UTILITY STAFF)															
3 A 50.75(c) Remove Unit 1 control rod drive and reactor cavity (internals ahead) (BY UTILITY STAFF)															
3 A 50.75(c) Remove Unit 1 ORD mechanisms and cables, air ducts, and reactor vessel head (BY UTILITY STAFF)															
3 A 50.75(c) Remove, segment, package and bury Unit 1 vessel & vessel head reaction		\$174,720					\$353,340			\$528,060	\$171,300	\$699,360			
3 A 50.75(c) Prepare Unit 1 vessel head for shipment as a own container (WITH VESSEL REMOVAL)															
3 A 50.75(c) Decommission and clean up Unit 1 plant (BY UTILITY STAFF)															
3 A 50.75(c) Process liquid and solid radioactive wastes (BY UTILITY STAFF)															
3 A 50.75(c) Remove, package, ship and dispose of Unit 1 contaminated systems		\$5,905,792	\$432,890	\$65,985	\$431,268		\$8,175,182			\$18,002,067	\$5,298,120	\$23,300,187			180,371
3 A Greenfield Remove, package, ship and dispose of Unit 1 internal as radioactive waste		\$2,588,325	\$820,388		\$158,218	\$815,644				\$11,084,586	\$2,416,100	\$13,899,896	192,216		
3 A 50.75(c) Install Unit 1 water cleanup system in fuel transfer canal (BY UTILITY STAFF)															
3 A 50.75(c) Segment, package and ship Unit 1 internals as radioactive waste		\$2,681,864	\$802,820	\$81,000	\$4,574,890		\$33,431,081			\$41,182,335	\$14,302,700	\$55,485,035			47,360
3 A 50.75(c) Decommission Internals work platform and stairs (BY UTILITY STAFF)															
3 A 50.75(c) Install Unit 1 vessel support structure (WITH VESSEL REMOVAL)															
3 A 50.75(c) Segment and process Unit 1 reactor vessel and associated equipment as LLW		\$1,392,522	\$141,461	\$24,000	\$2,038,252		\$14,827,168			\$18,184,413	\$4,294,300	\$22,478,713			24,820
3 A 50.75(c) Decommission reactor vessel platform and stairs (BY UTILITY STAFF)															
3 A 50.75(c) Decommission Unit 1 reactor building		\$4,416,224	\$953,223	\$416,439	\$2,672,602		\$13,922,464			\$21,980,182	\$7,016,600	\$28,996,782			80,876
UNIT 2															
3 A 50.75(c) Finalize Residual Radiation Inventory (WITH SITE CHARACTERIZATION)															
3 A 50.75(c) Finalize Internals and Vessel Segmentation Details (WITH ACTIVATION ANALYSIS)															
3 A 50.75(c) Review Integrated Work Sequence and Schedule		\$51,231								\$51,231	\$7,700	\$58,931			
3 A 50.75(c) Transfer all reactor operating floor CCCs support structures, rigging, internals work platforms and process equipment to position and install (BY UTILITY STAFF)															

2012 O. C. Cook
Scenario 5
OCEAN Wet Storage, Modified Systems, 2032 Repairs and Current DOE Acceptance Rate

		Off Labor \$	Off Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Decont. \$	Contaminated Decont. \$	Form \$	Other \$	without Contingency \$	Contingency \$	with Contingency \$	Staff Months	Off Months	Off Months
3	A 50.75(c)	Remove Unit 2 equipment hatch closure (BY UTILITY STAFF)														
3	A 50.75(c)	Remove Unit 2 CRD riser and reactor cavity riser shields (BY UTILITY STAFF)														
3	A 50.75(c)	Remove Unit 2 CRD mechanisms and cables, air ducts, and reactor vessel head (BY UTILITY STAFF)														
3	A 50.75(c)	Remove, segment, package and bury Unit 2 vessel & vessel head insulation		\$174,730				\$363,040			\$634,760	\$171,300	\$466,060			
3	A 50.75(c)	Prepare Unit 2 vessel head for shipment as its own container (WITH VESSEL REMOVAL)														
3	A 50.75(c)	Decontaminate and clean up Unit 2 plant areas (BY UTILITY STAFF)														
3	A 50.75(c)	Protect field and solid radioactive wastes (BY UTILITY STAFF)														
3	A 50.75(c)	Install Unit 2 enter cleanup system in fuel transfer canal (BY UTILITY STAFF)														
3	A 50.75(c)	Segment, package and ship Unit 2 internals as radioactive waste	\$2,591,854	\$502,630	\$81,000	\$4,574,880		\$23,431,981			\$41,182,236	\$14,302,700	\$55,484,936			47,900
3	A 50.75(c)	Decontaminate internal access platforms and process as LLW (BY UTILITY STAFF)														
3	A 50.75(c)	Install Unit 2 vessel support structure (WITH VESSEL REMOVAL)														
3	A 50.75(c)	Segment and process Unit 2 reactor vessel and associated equipment as LLW	\$1,362,872	\$141,451	\$24,000	\$2,039,382		\$14,627,158			\$16,184,413	\$6,284,300	\$22,468,713			24,835
3	A 50.75(c)	Disassemble reactor vessel sitting equipment and work platform, package and process as LLW (WIT)														
3	A 50.75(c)	Disassemble, remove, package, ship and bury Unit 2 steam generators	\$4,280,772	\$1,082,687	\$12,800	\$633,257		\$12,054,598			\$16,294,044	\$5,953,700	\$22,247,744			79,163
3	A 50.75(c)	Remove, pack, ship and bury Unit 2 Pressurizer	\$1,018,043	\$600	\$72,354	\$72,354		\$989,362			\$1,090,580	\$994,400	\$2,074,980			16,775
3	A 50.75(c)	Decontaminate non-essential structures	\$136,262	\$88,543	\$10,408	\$62,726		\$121,025			\$399,222	\$108,608	\$507,722			2,242
3	A 50.75(c)	Remove non-essential structures	\$111,101	\$42,947	\$10,881	\$10,881	\$63,241				\$228,176	\$44,600	\$272,675		1,094	
	SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:	\$51,231	\$42,023,487	\$6,091,098	\$720,980	\$18,378,547	\$878,885	\$144,844,980			\$212,087,817	\$99,518,300	\$311,606,117		193,911	803,323
DECOMMISSIONING PERIOD DEPENDENT																
3	PD 50.75(c)	Utility Staff	\$30,885,935								\$39,965,935	\$5,983,400	\$45,949,335	630,880		
3	PD 50.75(c)	DOC Staff	\$44,280,951								\$44,280,951	\$6,642,100	\$50,923,051	584,608		
3	PD 50.75(c)	Security	\$5,282,289								\$5,282,289	\$798,800	\$6,081,089	184,010		
3	PD 50.75(c)	HP Supplies		\$8,005,157							\$8,005,157	\$2,001,300	\$10,006,457			
3	PD 50.75(c)	Equipment		\$4,779,381							\$4,779,381	\$1,194,800	\$5,974,181			
3	PD 50.75(c)	Unit 1 Insurance								\$844,078	\$844,078	\$128,800	\$972,878			
3	PD 50.75(c)	Unit 2 Insurance								\$844,078	\$844,078	\$128,800	\$972,878			
3	PD 50.75(c)	O & M Budget Items		\$2,077,376							\$2,077,376	\$518,300	\$2,595,676			
3	PD 50.75(c)	Permits & Fees								\$6,157,542	\$6,157,542	\$923,700	\$7,081,242			
3	PD 50.75(c)	Waste Transfer and Loading	\$8,435,653								\$8,435,653	\$1,905,600	\$10,341,253			184,323
3	PD 50.75(c)	Energy							\$10,015,988		\$10,015,988	\$1,905,600	\$11,921,588			
3	PD 50.75(c)	Services	\$2,177,265								\$2,177,265	\$338,700	\$2,515,965			
3	PD 50.75(c)	Small Tools		\$1,000,183							\$1,000,183	\$252,300	\$1,252,483			
	SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$91,767,140	\$8,451,683	\$18,870,787		\$18,378,547	\$878,885	\$144,844,980	\$10,015,988	\$7,845,983	\$133,878,521	\$22,308,600	\$156,187,121	1,389,787		194,333
	TOTAL PERIOD 3 VESSEL AND INTERNALS REMOVAL COSTS:	\$108,877,887	\$50,465,141	\$22,384,286	\$720,980	\$18,378,547	\$878,885	\$144,844,980	\$10,015,988	\$14,139,116	\$212,087,817	\$99,518,300	\$311,606,117	1,809,698	183,911	787,845
ACTIVITY																
UNIT 1																
	Unit 1 Subtotal to CFR 50.75(c):	\$22,744,887	\$2,722,866	\$591,384	\$10,623,903			\$83,460,796			\$120,148,411	\$39,826,100	\$159,974,511			431,164
	Unit 1 Subtotal to CFR 50.54(b):															
	Unit 1 Subtotal Greenfield:	\$8,891,328	\$620,386		\$159,218		\$815,644				\$11,094,888	\$2,415,100	\$13,509,988		192,216	
UNIT 2																
	Unit 2 Subtotal to CFR 50.75(c):	\$91,231	\$9,427,511	\$1,736,747	\$116,800	\$7,619,313		\$61,343,130			\$80,217,423	\$27,324,100	\$107,541,523			168,917
	Unit 2 Subtotal to CFR 50.54(b):															
	Unit 2 Subtotal Greenfield:															
Commons																
	Total to CFR 50.75(c):		\$136,382	\$68,843	\$10,408	\$62,726		\$11,046			\$399,222	\$108,600	\$507,722			2,242
	Total to CFR 50.54(b):															
	Total Greenfield:		\$111,101	\$42,947		\$10,487	\$63,241				\$228,176	\$44,600	\$272,676		1,094	
PERIOD DEPENDENT																
UNIT 1																
	Unit 1 Subtotal to CFR 50.75(c):															
	Unit 1 Subtotal to CFR 50.54(b):															
UNIT 2																
	Unit 2 Subtotal to CFR 50.75(c):															
	Unit 2 Subtotal to CFR 50.54(b):															
Commons																
	Total to CFR 50.75(c):	\$91,767,140	\$8,451,683	\$18,870,787		\$18,378,547		\$144,844,980	\$10,015,988	\$7,845,983	\$133,878,521	\$22,308,600	\$156,187,121	1,389,787		194,333
	Total to CFR 50.54(b):	\$18,119,266		\$1,421,885					\$486,188	\$6,293,116	\$28,328,373	\$4,091,800	\$32,420,173	400,878		
Unit 1, Unit 2 & Commons																
	Total to CFR 50.75(c):	\$91,767,140	\$8,451,683	\$18,870,787	\$720,980	\$18,378,547		\$144,844,980	\$10,015,988	\$7,845,983	\$133,878,521	\$22,308,600	\$156,187,121	1,389,787		194,333
	Total to CFR 50.54(b):	\$18,119,266		\$1,421,885					\$486,188	\$6,293,116	\$28,328,373	\$4,091,800	\$32,420,173	400,878		
	Total Greenfield:	\$9,718,404	\$843,545			\$170,108	\$774,885				\$11,222,781	\$2,488,900	\$13,711,681		103,911	

PERIOD 4 DECONTAMINATE BALANCE OF SITE COSTS:

2012 D. C. Cook
Scenario B
DECON. Wet Storage Modified Systems, 2032 Repository and Current DOE Acceptance Rate

Task	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	Wet Cell Containment \$	Electrolysis \$	Wet Cell Containment \$	Staff Materials	Craft Materials	Craft Materials
SPENT FUEL PERIOD DEPENDENT															
4 PD 50.54(bb) Utility Staff	\$9,132,651									\$9,132,651	\$1,309,000	\$10,002,551	152,400		
4 PD 50.54(bb) Security	\$3,601,083									\$3,601,083	\$640,200	\$4,141,283	26,896		
4 PD 50.54(bb) Insurance									\$2,024,382	\$2,024,382	\$993,700	\$3,018,082			
4 PD 50.54(bb) O & M Budget Items									\$1,798,200	\$1,798,200	\$269,700	\$2,067,900			
4 PD 50.54(bb) Permits & Fees															
4 PD 50.54(bb) Waste Transfer and Loading															
4 PD 50.54(bb) Energy								\$347,989		\$347,989	\$52,700	\$400,689			
4 PD 50.54(bb) Spent Fuel Storage Maintenance Supplies			\$600,200							\$600,200	\$240,800	\$1,240,000			
4 PD 50.54(bb) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$12,733,744		\$600,200					\$347,989	\$4,422,832	\$18,883,571	\$2,878,600	\$21,378,671	349,397		
DECOMMISSIONING ACTIVITIES															
4 A 50.75(c) Decom, remove, package, ship and dispose of Unit 2 concentrated systems		\$16,535,252	\$804,125	\$106,587	\$800,993		\$15,132,481			\$23,432,411	\$9,941,100	\$43,273,511			\$24,574
4 A 50.75(c) Removal, package, ship and dispose of Unit 2 debris systems		\$17,827,315	\$865,454		\$295,681	\$1,514,768				\$20,604,231	\$4,489,200	\$25,093,431	358,973		
4 A 50.75(c) Decom Steam Generator Storage Building		\$90,000	\$27,855	\$409	\$6,024		\$279,080			\$387,433	\$128,200	\$515,633			1,658
4 A 50.75(c) Decom Unit 2 Reactor Building		\$4,415,224	\$553,228	\$416,439	\$2,677,802		\$13,227,464			\$21,580,152	\$7,010,600	\$28,590,752			\$0,870
4 A 50.75(c) Perform final radiological survey of all structures		\$1,026,300	\$34,160							\$1,060,460	\$421,700	\$1,482,160			
4 A 50.75(c) Perform final survey of the site		\$9,031,600	\$210,980							\$9,242,580	\$2,231,100	\$11,473,680			
4 A 50.75(c) Obtain NRC approval															
4 A 50.75(c) Prepare final report of dismantling program	\$49,362									\$49,362	\$7,400	\$56,762	456		
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS	\$49,362	\$16,322,106	\$1,408,780	\$522,435	\$3,775,488	\$1,514,768	\$29,378,025			\$46,167,860	\$24,126,300	\$112,294,260	456	\$36,073	\$17,698
DECOMMISSIONING PERIOD DEPENDENT															
4 PD 50.75(c) Utility Staff	\$22,219,030									\$22,219,030	\$3,332,900	\$25,551,930	346,388		
4 PD 50.75(c) DDO Staff	\$26,073,973									\$26,073,973	\$3,811,100	\$29,885,073	391,003		
4 PD 50.75(c) Security	\$3,719,255									\$3,719,255	\$557,800	\$4,277,055	129,317		
4 PD 50.75(c) HP Outlets			\$0,422,420							\$0,422,420	\$1,365,600	\$1,788,020			
4 PD 50.75(c) Equipment			\$4,940,421							\$4,940,421	\$1,160,100	\$6,100,521			
4 PD 50.75(c) Unit 1 Insurance											\$693,194	\$693,194			
4 PD 50.75(c) Unit 2 Insurance											\$693,194	\$693,194			
4 PD 50.75(c) O & M Budget Items			\$536,801							\$536,801	\$134,000	\$670,801			
4 PD 50.75(c) Permits & Fees									\$3,719,498	\$3,719,498	\$557,300	\$4,276,798			
4 PD 50.75(c) Waste Transfer and Loading		\$5,928,348								\$5,928,348	\$1,339,400	\$7,267,748			113,482
4 PD 50.75(c) Energy								\$6,022,647		\$6,022,647	\$1,036,400	\$7,059,047			
4 PD 50.75(c) Severance	\$933,427									\$933,427	\$140,000	\$1,073,427			
4 PD 50.75(c) Small Tools			\$1,125,000							\$1,125,000	\$261,300	\$1,386,300			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT	\$32,845,856	\$1,328,348	\$11,723,239					\$6,022,647	\$4,901,842	\$62,422,312	\$13,986,000	\$86,408,322	\$25,705		\$15,482
TOTAL PERIOD 4 DECONTAMINATE BALANCE OF SITE COSTS	\$46,718,792	\$16,280,449	\$15,328,745	\$522,435	\$3,775,488	\$1,514,768	\$29,378,025	\$7,220,635	\$9,324,674	\$189,093,664	\$40,987,600	\$230,681,944	1,978,458	\$36,073	\$32,989
ACTIVITY															
UNIT 1															
Unit 1 Subtotal 10 CFR 50.75(c):															
Unit 1 Subtotal 10 CFR 50.54(bb):															
Unit 1 Subtotal Greenfield:															
UNIT 2															
Unit 2 Subtotal 10 CFR 50.75(c):															
Unit 2 Subtotal 10 CFR 50.54(bb):															
Unit 2 Subtotal Greenfield:															
Common															
Common Subtotal 10 CFR 50.75(c):															
Common Subtotal 10 CFR 50.54(bb):															
Common Subtotal Greenfield:															
PERIOD DEPENDENT															
UNIT 1															
Unit 1 Subtotal 10 CFR 50.75(c):															
Unit 1 Subtotal 10 CFR 50.54(bb):															
UNIT 2															
Unit 2 Subtotal 10 CFR 50.75(c):															
Unit 2 Subtotal 10 CFR 50.54(bb):															
Common															
Common Subtotal 10 CFR 50.75(c):															
Common Subtotal 10 CFR 50.54(bb):															
Common Subtotal Greenfield:															
PERIOD DEPENDENT															
SUBTOTAL - PERIOD DEPENDENT	\$32,945,586	\$5,928,348	\$11,723,239					\$6,022,647	\$4,901,842	\$62,422,312	\$13,986,000	\$86,408,322	\$25,705		\$15,482

20" R.O. C. Cost
Scenario 5
DECON, Wld Storage, Modified Systems, 2032 Remedial and Current DOE Acceptable Pids

Type	Common Subtotal 10 CFR 80.54(b):	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Backpack \$	Instrumentation \$	Clean Chemical \$	Contaminated Chemical \$	Excavation \$	Welding \$	Without Contamination \$	Contamination \$	With Contamination \$	Staff Measures \$	Craft Measures \$	Craft Measures \$
		\$12,733,744		\$999,206					\$347,863	\$4,422,832	\$16,501,571	\$2,873,800	\$21,378,071	\$249,387		
Unit 1, Unit 2 & Common																
Total 10 CFR 80.78(c):		\$62,884,048	\$38,433,130	\$12,369,088	\$122,438	\$3,479,738		\$26,378,018	\$6,832,647	\$4,801,882	\$148,886,041	\$33,827,190	\$163,813,141	\$37,181		\$32,980
Total 10 CFR 80.54(b):		\$12,733,744		\$999,206					\$347,863	\$4,422,832	\$16,501,571	\$2,873,800	\$21,378,071	\$249,387		
Total Greenfield			\$17,827,319	\$999,454		\$286,891	\$1,514,768				\$26,604,331	\$4,435,890	\$26,089,421		\$66,370	
PERIOD 5 - CLEAN STRUCTURE DEMOLITION COSTS:																
SPENT FUEL PERIOD DEPENDENT																
5 PD 80.54(a) Utility Staff		\$5,912,340									\$5,912,340	\$896,600	\$6,788,240	\$9,807		
5 PD 80.54(a) Security		\$2,733,591									\$2,733,591	\$323,400	\$2,478,591	\$8,007		
5 PD 80.54(a) Insurance										\$1,588,452	\$1,588,452	\$235,400	\$1,804,452			
5 PD 80.54(b) O & M Budget Items																
5 PD 80.54(b) Permits & Fees										\$1,078,402	\$1,078,402	\$181,300	\$1,236,702			
5 PD 80.54(b) Waste Transfer and Loading																
5 PD 80.54(b) Energy									\$208,107		\$208,107	\$31,300	\$226,507			
5 PD 80.54(b) Spent Fuel Storage Maintenance Supplies				\$597,552							\$597,552	\$145,400	\$748,252			
5 PD 80.54(b) Small Tools																
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT		\$9,665,891		\$597,552					\$208,107	\$2,644,454	\$11,619,454	\$1,797,200	\$13,363,804	\$15,808		
DECOMMISSIONING ACTIVITIES																
5 A Greenfield Remove Unit 1 reactor building			\$1,401,550	\$805,412		\$541,175	\$3,143,736				\$3,869,821	\$887,600	\$6,827,321			24,370
5 A Greenfield Remove Unit 2 reactor building			\$1,481,598	\$803,412		\$541,175	\$3,143,736				\$3,869,821	\$887,600	\$6,827,321			24,370
5 A Greenfield Remove Turbine Building			\$8,045,268	\$3,053,891		\$1,140,634	\$8,827,787				\$19,817,839	\$3,746,100	\$23,857,839			157,370
5 A Greenfield Remove Steam Generator Storage Building			\$198,400	\$88,097		\$52,487	\$304,904				\$643,889	\$108,800	\$752,889			3,181
5 A Greenfield Remove Steam Generator			\$81,803	\$2,908		\$13,844	\$61,300				\$178,815	\$30,430	\$210,215			1,859
5 A Greenfield Remove of Unit 1 Turbine Generator			\$152,600	\$7,898		\$7,748	\$45,300				\$213,245	\$42,800	\$258,845			2,897
5 A Greenfield Remove of Unit 1 Main Condenser			\$1,332,988	\$7,427		\$35,013	\$493,849				\$1,918,254	\$370,900	\$2,260,154			21,580
5 A Greenfield Remove of Unit 2 Turbine Generator			\$182,600	\$7,898		\$7,748	\$45,300				\$213,245	\$42,800	\$258,845			2,897
5 A Greenfield Remove of Unit 2 Main Condenser			\$1,332,988	\$7,427		\$35,013	\$493,849				\$1,918,254	\$370,900	\$2,260,154			21,580
5 A Greenfield Remove of Standby Diesel Generators			\$30,412	\$6,447		\$2,324	\$13,800				\$52,882	\$10,300	\$62,882			632
5 A Greenfield Remove Administration building			\$380,750	\$100,792							\$481,451	\$52,100	\$494,551			4,469
5 A Greenfield Remove Low Level Radioactive building			\$1,187,601	\$175,888		\$138,649	\$734,863				\$2,210,699	\$402,300	\$2,612,699			18,088
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:		\$18,288,918	\$8,410,346	\$8,410,346		\$2,614,405	\$18,187,218				\$38,611,687	\$7,147,280	\$46,738,287			282,694
DECOMMISSIONING PERIOD DEPENDENT																
5 PD Greenfield Utility Staff		\$482,682									\$482,682	\$144,800	\$1,110,762	\$15,872		
5 PD Greenfield DDO Staff		\$7,438,142									\$7,438,142	\$1,115,700	\$8,553,842	\$23,807		
5 PD Greenfield Security		\$509,810									\$509,810	\$79,300	\$588,310	\$15,872		
5 PD Greenfield HP Supplies				\$295,867							\$295,867	\$74,000	\$369,867			
5 PD Greenfield Equipment				\$2,249,402							\$2,249,402	\$682,400	\$2,931,802			
5 PD Greenfield Unit 1 Insurance										\$354,746	\$354,746	\$53,200	\$407,946			
5 PD Greenfield Unit 2 Insurance										\$354,746	\$354,746	\$53,200	\$407,946			
5 PD Greenfield O & M Budget Items				\$32,152							\$32,152	\$15,800	\$47,952			
5 PD Greenfield Permits & Fees										\$173,835	\$173,835	\$38,500	\$209,335			
5 PD Greenfield Waste Transfer and Loading			\$2,100,700								\$2,100,700	\$498,000	\$2,898,700			41,437
5 PD Greenfield Energy									\$735,408		\$735,408	\$108,800	\$841,208			
5 PD Greenfield Severance		\$9,022,504									\$9,022,504	\$452,400	\$9,474,904			
5 PD Greenfield Small Tools				\$389,784							\$389,784	\$92,400	\$482,184			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT		\$11,836,388	\$2,110,700	\$2,977,215					\$735,408	\$895,225	\$18,886,066	\$3,288,600	\$21,864,566	\$27,880	\$1,437	
TOTAL PERIOD 5 - CLEAN STRUCTURE DEMOLITION COSTS:		\$20,862,249	\$18,498,718	\$8,886,113		\$2,614,405	\$18,187,218		\$913,973	\$3,531,182	\$69,823,857	\$12,202,800	\$82,026,467	\$28,988	\$34,031	
ACTIVITY																
UNIT 1																
Unit 1 Subtotal Greenfield (g):			\$2,997,166	\$816,738		\$633,836	\$3,662,882				\$6,162,421	\$1,381,100	\$8,483,821			48,647
Unit 1 Subtotal 10 CFR 80.54(b):																
UNIT 2																
Unit 2 Subtotal Greenfield (g):			\$2,997,166	\$816,738		\$633,836	\$3,662,882				\$6,162,421	\$1,381,100	\$8,483,821			48,647
Unit 2 Subtotal 10 CFR 80.54(b):																
Common																
Common Subtotal Greenfield (g):			\$10,384,884	\$5,475,578		\$1,346,137	\$7,632,164				\$23,448,244	\$5,345,600	\$28,793,244			165,300
Common Subtotal 10 CFR 80.54(b):																
PERIOD DEPENDENT																

2042 D Q Code
 Section 5
 DECON, Wet Storage, Modified System, 2032 Reproductive and Current DOE Compliance Rate

Job	UNIT 1	UNIT 2	Common	Unit 1, Unit 2 & Common	Staff Labor	Staff Labor	Equipment & Materials	Backfill	Transportation	Clean Up	Contaminated Class	Excav	Other	without Containment	with Containment	Staff Mechan	Craft Mechan	Craft Maint	
	Unit 1 Subtotal Greenfield (g): Unit 1 Subtotal 10 CFR 80.54(b):	Unit 2 Subtotal Greenfield (g): Unit 2 Subtotal 10 CFR 80.54(b):	Common Subtotal Greenfield (g): Common Subtotal 10 CFR 80.54(b):	Unit 1, Unit 2 & Common Total Greenfield (g): Total 10 CFR 80.54(b):															
					\$11,838,358 \$8,086,891	\$2,109,700	\$2,977,215 \$697,612					\$708,466 \$208,197	\$246,328 \$2,444,854	\$18,606,808 \$11,816,404	\$3,268,800 \$1,787,200	\$21,964,668 \$15,303,604	127,890 191,408	61,437	
					\$11,838,358 \$3,085,391	\$13,469,716	\$3,487,661 \$997,652		\$2,914,406	\$15,187,319		\$708,466 \$208,197	\$246,328 \$2,444,854	\$18,606,808 \$11,816,404	\$3,268,800 \$1,787,200	\$21,964,668 \$15,303,604	127,890 191,408	304,891	
PERIOD 8 - RESTORE SITE COSTS:																			
SPENT FUEL PERIOD DEPENDENT																			
5	PD 50.04(b)	Utility Staff			\$645,091									\$645,091	\$88,900	\$742,991	10,238		
6	PD 50.54(b)	Security			\$236,307									\$236,307	\$35,900	\$272,207	2,338		
6	PD 50.54(b)	Insurance										\$171,907		\$171,907	\$25,700	\$197,607			
6	PD 50.54(b)	O & M Budget Items																	
6	PD 50.54(b)	Permits & Fees										\$17,518		\$17,518	\$17,600	\$135,118			
6	PD 50.54(b)	Waste Transfer and Loading																	
6	PD 50.54(b)	Energy										\$22,742		\$22,742	\$3,400	\$26,142			
6	PD 50.54(b)	Spent Fuel Storage Maintenance Supplies					\$66,300							\$66,300	\$18,900	\$85,200			
6	PD 50.54(b)	Small Tools																	
					\$881,427		\$66,300					\$22,742	\$28,628	\$1,258,404	\$188,200	\$1,465,804	16,800		
DECOMMISSIONING ACTIVITIES																			
6	A Greenfield	Backfill, grade and landscape site			\$166,108									\$166,108	\$37,600	\$203,708	1,787		
					\$166,108									\$166,108	\$37,600	\$203,708	1,787		
DECOMMISSIONING PERIOD DEPENDENT																			
5	PD Greenfield	Utility Staff			\$34,637									\$34,637	\$5,200	\$40,137	804		
6	PD Greenfield	DGC Staff			\$376,711									\$376,711	\$58,500	\$435,211	4,627		
6	PD Greenfield	Security			\$13,988									\$13,988	\$2,100	\$16,088	804		
6	PD Greenfield	HF Supplies					\$22,223							\$22,223	\$3,800	\$26,023			
6	PD Greenfield	Equipment					\$75,222							\$75,222	\$18,800	\$94,022			
6	PD Greenfield	Unit 1 Insurance										\$36,705		\$36,705	\$5,800	\$42,505			
6	PD Greenfield	Unit 2 Insurance										\$36,705		\$36,705	\$5,800	\$42,505			
6	PD Greenfield	O & M Budget Items					\$6,792							\$6,792	\$1,700	\$8,492			
6	PD Greenfield	Permits & Fees										\$19,324		\$19,324	\$2,900	\$22,224			
6	PD Greenfield	Waste Transfer and Loading					\$236,306							\$236,306	\$34,100	\$270,406	4,570		
6	PD Greenfield	Energy										\$77,692		\$77,692	\$11,600	\$89,292			
6	PD Greenfield	Severance			\$177,796									\$177,796	\$28,700	\$206,496			
6	PD Greenfield	Small Tools					\$4,110							\$4,110	\$2,000	\$6,110			
					\$945,452		\$236,306	\$112,348				\$77,692	\$48,644	\$1,124,129	\$184,900	\$1,307,956	5,735	4,628	
TOTAL PERIOD 8 - RESTORE SITE COSTS:																			
					\$1,464,859		\$460,608	\$177,848				\$99,434	\$208,882	\$2,440,533	\$401,800	\$2,842,333	22,534	6,295	
ACTIVITY																			
UNIT 1																			
	Unit 1 Subtotal Greenfield (g): Unit 1 Subtotal 10 CFR 80.54(b):																		
UNIT 2																			
	Unit 2 Subtotal Greenfield (g): Unit 2 Subtotal 10 CFR 80.54(b):																		
Common																			
	Common Subtotal Greenfield (g): Common Subtotal 10 CFR 80.54(b):					\$166,108								\$166,108	\$37,600	\$203,708	1,787		
PERIOD DEPENDENT																			
UNIT 1																			
	Unit 1 Subtotal Greenfield (g): Unit 1 Subtotal 10 CFR 80.54(b):																		

2012 D. C. Buck
Scenario B
DECON, Wet Storage, Modified System, 2012 Regulatory and Costing DOL Acceptance Rate

Task	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Permitting \$	Translocation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	Wet Cell Containment \$	Decontamination \$	With Containment \$	Staff Manhours	Craft Manhours	Craft Manhours
UNIT 2															
Unit 2 Subtotal Greenfield (g):															
Unit 2 Subtotal 19 CFR 60.54(b):															
Common															
Common Subtotal Greenfield (g)	\$801,432	\$239,396	\$112,549					\$77,682	\$80,856	\$1,128,116	\$196,809	\$1,527,526	6,738	4,628	
Common Subtotal 19 CFR 60.54(b):	\$801,432		\$68,300					\$21,742	\$259,025	\$1,385,474	\$165,209	\$1,483,694	16,609		
Unit 1, Unit 2 & Common															
Total Greenfield (g):	\$801,432	\$405,493	\$112,549					\$77,682	\$99,616	\$1,294,250	\$259,500	\$1,531,535	6,738	4,265	
Total 19 CFR 60.54(b):	\$801,432		\$68,300					\$21,742	\$289,019	\$1,385,474	\$165,209	\$1,483,694	16,609		
PERIOD 7 - DRY STORAGE COSTS:															
SPENT FUEL ACTIVITIES															
7 A.50.54(b) Continue to ship fuel to repository															
SUBTOTAL - SPENT FUEL ACTIVITIES															
SPENT FUEL PERIOD DEPENDENT															
7 PD 60.54(b) Utility Staff	\$69,741,231									\$69,741,231	\$10,481,200	\$80,202,431	1,107,714		
7 PD 60.54(b) Security	\$26,403,026									\$26,403,026	\$3,810,500	\$29,213,526	684,178		
7 PD 60.54(b) Insurance									\$26,082,131	\$2,688,230	\$28,770,361				
7 PD 60.54(b) O & M Budget Items			\$2,025,680						\$2,025,680	\$202,600	\$2,228,280				
7 PD 60.54(b) Permits & Fees									\$12,855,314	\$1,268,500	\$13,853,814				
7 PD 60.54(b) Waste Transfer and Loading															
7 PD 60.54(b) Energy								\$10,083,722		\$10,083,722	\$1,006,400	\$11,109,122			
7 PD 60.54(b) Equipment			\$1,152,691							\$1,152,691	\$115,300	\$1,267,991			
7 PD 60.54(b) HP Supplies			\$1,500,191							\$1,500,191	\$150,000	\$1,748,191			
7 PD 60.54(b) Spent Fuel Storage Maintenance Supplies			\$7,048,653							\$7,048,653	\$704,800	\$7,753,453			
7 PD 60.54(b) Small Tools															
SUBTOTAL - SPENT FUEL PERIOD DEPENDENT															
	\$95,144,257		\$11,617,216					\$10,083,722	\$38,567,446	\$166,622,640	\$20,419,800	\$177,042,240	1,791,598		
DECOMMISSIONING ACTIVITIES															
7 A.60.75(b) Planning for PAB Decon and Demolition (Occurs in last six months of Period 7)															
SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:															
DECOMMISSIONING PERIOD DEPENDENT															
7 PD 60.75(b) Decon Staff	\$1,123,481									\$1,123,481	\$198,500	\$1,321,981	14,040		
7 PD 60.75(b) Seawall	\$88,506									\$88,506	\$13,300	\$101,806			
SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT															
	\$1,211,987									\$1,211,987	\$211,800	\$1,394,169	14,040		
TOTAL PERIOD 7 - DRY STORAGE COSTS:															
	\$96,356,244		\$11,617,216					\$10,083,722	\$38,567,446	\$167,834,640	\$20,631,600	\$178,436,240	1,805,638		
ACTIVITY															
Common															
Common Subtotal 19 CFR 60.75(c):															
Common Subtotal 19 CFR 60.54(b):															
PERIOD DEPENDENT															
Common															
Common Subtotal 19 CFR 60.75(c):	\$1,211,987									\$1,211,987	\$198,500	\$1,394,169	14,040		
Common Subtotal 19 CFR 60.54(b):	\$88,506									\$88,506	\$13,300	\$101,806			
Unit 1, Unit 2 & Common															
Total 19 CFR 60.75(c):	\$1,211,987									\$1,211,987	\$198,500	\$1,394,169	14,040		
Total 19 CFR 60.54(b):	\$88,506									\$88,506	\$13,300	\$101,806			
PERIOD 8 - AUXILIARY BUILDING REMOVAL COSTS:															
SPENT FUEL PERIOD DEPENDENT															
8 PD 60.54(b) Utility Staff	\$1,010,101									\$1,010,101	\$242,400	\$1,252,501	27,164		
8 PD 60.54(b) Security	\$984,205									\$984,205	\$147,000	\$1,131,205	34,801		
8 PD 60.54(b) Insurance									\$197,131	\$197,131	\$238,000	\$238,000			
8 PD 60.54(b) O & M Budget Items															
8 PD 60.54(b) Permits & Fees									\$302,105	\$302,105	\$75,000	\$677,205			

2012 D. G. Cook
Scenario 5
DECON, Wet Storage, Modified Systems, 2032 Repository and Current DOE Acceptance Rate

			Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	without Contingency \$	Contingency \$	with Contingency \$	Staff Manhours	Craft Manhours	Craft Manhours
8	PD 50.54(b)	Waste Transfer and Loading								\$425		\$425	\$100	\$525			
8	PD 50.54(b)	Energy										\$147,848	\$37,000	\$184,848			
8	PD 50.54(b)	Spent Fuel Storage Maintenance Supplies			\$147,848												
8	PD 50.54(b)	Small Tools															
	SUBTOTAL - SPENT FUEL PERIOD DEPENDENT		\$2,800,308		\$147,848					\$425	\$700,236	\$3,448,878	\$332,200	\$3,981,078	61,706		
	DECOMMISSIONING ACTIVITIES																
8	A 50.75(c)	Remove Spent fuel storage racks		\$2,591,493	\$50,370	\$0,348	\$43,305		\$1,856,799			\$4,249,314	\$1,194,300	\$5,443,614			40,874
8	A 50.75(c)	Decon Auxiliary Building		\$1,598,938	\$655,318	\$10,980	\$150,898		\$8,517,898			\$6,933,790	\$3,008,300	\$11,910,080			32,024
8	A Greenfield	Remove Auxiliary Building		\$12,100,593	\$4,932,267		\$1,004,741	\$9,322,088				\$27,865,048	\$5,249,500	\$33,215,148	102,462		
8	A 50.75(c)	Final Survey		\$1,146,024	\$28,412							\$1,171,436	\$265,300	\$1,436,736			
	SUBTOTAL - DECOMMISSIONING ACTIVITY COSTS:			\$17,413,087	\$4,663,368	\$18,328	\$1,788,946	\$9,322,088	\$8,673,486			\$42,399,189	\$9,716,400	\$52,095,689	192,462		81,897
	DECOMMISSIONING PERIOD DEPENDENT																
8	PD 50.75(c)	Utility Staff	\$2,593,931									\$2,593,931	\$448,100	\$3,443,031	48,690		
8	PD 50.75(c)	DGC Staff	\$6,114,297									\$6,114,297	\$917,100	\$7,031,397	82,005		
8	PD 50.75(c)	Security	\$1,175,885									\$1,175,885	\$178,400	\$1,352,285	36,902		
8	PD 50.75(c)	HP Supplies			\$1,091,640							\$1,091,640	\$272,900	\$1,364,540			
8	PD 50.75(c)	Equipment			\$1,536,442							\$1,536,442	\$363,900	\$1,919,342			
8	PD 50.75(c)	Unit 1 Insurance									\$263,316	\$263,316	\$39,500	\$302,816			
8	PD 50.75(c)	Unit 2 Insurance									\$263,316	\$263,316	\$39,500	\$302,816			
8	PD 50.75(c)	O & M Budget Items			\$127,468							\$127,468	\$31,900	\$159,368			
8	PD 50.75(c)	Permits & Fees															
8	PD 50.75(c)	Waste Transfer and Loading		\$1,315,798								\$1,315,798	\$297,300	\$1,613,098			25,631
8	PD 50.75(c)	Energy								\$523,845		\$523,845	\$78,500	\$602,145			
8	PD 50.75(c)	Severance															
8	PD 50.75(c)	Small Tools			\$374,576							\$374,576	\$93,800	\$468,176			
	SUBTOTAL - DECOMMISSIONING PERIOD DEPENDENT		\$10,284,114	\$1,315,798	\$3,129,124					\$523,845	\$626,633	\$15,775,303	\$2,779,709	\$18,699,003	187,897		25,631
	TOTAL PERIOD 6 - AUXILIARY BUILDING REMOVAL COSTS:		\$12,884,480	\$18,728,783	\$8,840,339	\$18,328	\$1,798,946	\$9,322,088	\$8,673,486	\$824,089	\$1,226,868	\$61,618,305	\$13,027,309	\$74,645,688	219,363	192,462	107,828
	ACTIVITY Common																
	Total 10 CFR 50.75(c):			\$5,306,484	\$731,889	\$18,328	\$194,204		\$8,073,486			\$14,324,940	\$4,468,900	\$18,796,440			61,897
	Common Subtotal Greenfield (g)			\$12,106,553	\$4,832,287		\$1,804,741	\$9,322,088				\$27,865,048	\$5,249,500	\$33,215,148	192,462		
	Common Subtotal 50.54 (bb)																
	PERIOD DEPENDENT Common																
	Total 10 CFR 50.75(c):		\$10,284,114	\$1,315,798	\$3,129,124					\$523,845	\$626,633	\$15,775,303	\$2,779,709	\$18,699,003	187,897		25,631
	Common Subtotal Greenfield (g)																
	Common Subtotal 50.54 (bb)		\$2,800,308		\$147,848					\$425	\$700,236	\$3,448,878	\$332,200	\$3,981,078	61,706		
	Unit 1, Unit 2 & Common																
	Total 10 CFR 50.75(c):		\$10,284,114	\$6,822,240	\$3,960,225	\$18,328	\$194,204		\$8,073,486	\$523,845	\$626,633	\$30,103,843	\$7,246,900	\$37,349,443	187,897		107,528
	Total Greenfield (g):			\$12,106,553	\$4,832,287		\$1,804,741	\$9,322,088				\$27,865,048	\$5,249,500	\$33,215,148	192,462		
	Total 50.54(bb)		\$2,800,308		\$147,848					\$425	\$700,236	\$3,448,878	\$332,200	\$3,981,078	61,706		
	PERIOD 9 COSTS:																
	SPENT FUEL ACTIVITIES																
9	A 50.54(bb)	Continue to ship fuel to repository															
	SPENT FUEL PERIOD DEPENDENT																
9	PD 50.54(bb)	Utility Staff	\$30,567,729									\$30,567,729	\$5,935,200	\$36,502,929	592,561		
9	PD 50.54(bb)	Security	\$19,982,958									\$19,982,958	\$2,894,400	\$22,857,358	498,999		
9	PD 50.54(bb)	Insurance									\$3,998,467	\$3,998,467	\$599,800	\$4,598,267			
9	PD 50.54(bb)	O & M Budget Items			\$2,585,478							\$2,585,478	\$298,500	\$2,883,978			
9	PD 50.54(bb)	Permits & Fees									\$7,897,727	\$7,897,727	\$789,800	\$8,687,527			
9	PD 50.54(bb)	Waste Transfer and Loading															
9	PD 50.54(bb)	Energy								\$101,139		\$101,139	\$10,100	\$111,239			
9	PD 50.54(bb)	Equipment			\$394,789							\$394,789	\$39,500	\$434,289			
9	PD 50.54(bb)	HP Supplies			\$1,346,273							\$1,346,273	\$134,600	\$1,480,873			
9	PD 50.54(bb)	Spent Fuel Storage Maintenance Supplies			\$2,998,850							\$2,998,850	\$299,200	\$3,298,050			
9	PD 50.54(bb)	Small Tools															
9	PD 50.54(bb)	Severance	\$1,011,212									\$1,011,212	\$191,700	\$1,192,912			
	SUBTOTAL - SPENT FUEL PERIOD DEPENDENT		\$60,841,909		\$7,325,379					\$101,139	\$11,895,193	\$79,868,611	\$10,893,600	\$90,662,111	1,091,560		

2012 D. C. Cook
Scenario 5
DECOR, Wet Storage, Modified Systems, 2032 Repository and Current DOE Acceptance Rate

Year		Staff Labor \$	Cost Labor \$	Equipment & Materials \$	Process \$	Transportation \$	Clean Disposal \$	Contaminated Process \$	Energy \$	Other \$	without Contingency \$	with Contingency \$	Staff Maintenance \$	Cost Maintenance \$	Cost Maintenance \$
	TOTAL PERIOD 9 COSTS:	\$80,541,803		\$7,328,370					\$101,130	\$11,086,193	\$78,044,811	\$10,993,900	\$90,488,115	1,201,380	
	ACTIVITY														
	Common														
	Total \$0.54(b)														
	PERIOD DEPENDENT														
	Common														
	Total \$0.54(b)	\$80,541,803		\$7,328,370					\$101,130	\$11,086,193	\$78,044,811	\$10,993,900	\$90,488,115	1,201,380	
PERIOD 10 COSTS:															
	SPENT FUEL ACTIVITIES														
10	A 50.54(b)														
	Remove casks, casklets and storage pads		\$500,765								\$528,768	\$119,700	\$648,468	5,625	
	SUBTOTAL - SPENT FUEL ACTIVITIES		\$500,765								\$528,768	\$119,700	\$648,468	5,625	
	SPENT FUEL PERIOD DEPENDENT														
10	PD 50.54(b)														
	Utility Staff	\$288,011									\$288,011	\$44,400	\$340,411	4,727	
10	PD 50.54(b)										\$454,344	\$68,200	\$522,544	5,169	
10	PD 50.54(b)										\$118,142	\$17,700	\$135,842	2,836	
10	PD 50.54(b)									\$89,255	\$99,255	\$13,400	\$102,655		
10	PD 50.54(b)														
10	PD 50.54(b)										\$5,527	\$800	\$6,327		
10	PD 50.54(b)									\$5,627	\$187,452	\$42,400	\$239,552		
10	PD 50.54(b)		\$187,452								\$1,150	\$200	\$1,350		3,545
10	PD 50.54(b)								\$1,150		\$108,616	\$28,700	\$133,316		
10	PD 50.54(b)			\$108,616							\$50,251	\$12,600	\$62,851		
10	PD 50.54(b)			\$50,251											
10	PD 50.54(b)														
10	PD 50.54(b)										\$7,172	\$1,800	\$8,972		
10	PD 50.54(b)										\$433,387	\$55,000	\$488,387		
	SUBTOTAL - SPENT FUEL PERIOD DEPENDENT	\$1,591,845	\$187,452	\$184,048					\$1,160	\$94,781	\$1,940,324	\$323,200	\$2,272,524	12,782	3,545
	TOTAL PERIOD 10 COSTS:	\$1,591,845	\$717,210	\$184,048					\$1,160	\$94,781	\$2,479,880	\$442,900	\$2,821,880	12,782	3,545
	ACTIVITY														
	Common														
	Total \$0.54(b)		\$528,768								\$528,768	\$119,700	\$648,468	5,625	
	PERIOD DEPENDENT														
	Common														
	Total \$0.54(b)	\$1,591,845	\$187,452	\$184,048					\$1,160	\$94,781	\$1,940,324	\$323,200	\$2,272,524	12,782	3,545
TOTAL ACTIVITY COSTS:															
UNIT 1															
	SUBTOTAL UNIT 1 10 CFR 60.75(C) COSTS FOR PERIODS 1 - 10		\$27,368,348	\$3,031,500	\$891,804	\$10,823,301					\$130,455,728	\$42,688,855	\$173,119,578	5,780	431,164
	SUBTOTAL UNIT 1 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 10														
	SUBTOTAL UNIT 1 GREENFIELD COSTS FOR PERIODS 1 - 10		\$12,446,482	\$1,336,137		\$783,152	\$4,498,228				\$19,197,607	\$3,798,200	\$22,995,207	240,864	
UNIT 2															
	SUBTOTAL UNIT 2 10 CFR 60.75(C) COSTS FOR PERIODS 1 - 10	\$41,281	\$55,041,646	\$4,202,635	\$440,827	\$10,493,379					\$145,341,305	\$47,304,586	\$193,186,553	5,780	648,797
	SUBTOTAL UNIT 2 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 10														
	SUBTOTAL UNIT 2 GREENFIELD COSTS FOR PERIODS 1 - 10		\$20,794,486	\$1,764,182		\$829,025	\$5,187,350				\$28,708,853	\$8,894,300	\$34,572,853	405,821	
COMMON															
	SUBTOTAL COMMON 10 CFR 60.75(C) COSTS FOR PERIODS 1 - 10	\$8,413,488	\$18,883,777	\$2,081,728	\$30,232	\$162,963					\$39,438,723	\$8,627,200	\$48,065,922	100,180	24,960
	SUBTOTAL COMMON 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 10	\$749,467	\$2,291,817	\$2,348,309							\$8,289,444	\$1,187,309	\$9,476,744	7,712	31,028
	SUBTOTAL COMMON GREENFIELD COSTS FOR PERIODS 1 - 10		\$12,748,447	\$8,848,093		\$2,893,184	\$17,297,453				\$51,786,177	\$9,714,305	\$61,482,877	361,203	
TOTAL PERIOD DEPENDENT COSTS															
UNIT 1															
	SUBTOTAL UNIT 1 10 CFR 60.75(C) COSTS FOR PERIODS 1 - 10		\$26,177,442	\$12,636,137					\$1,765,868	\$2,382,267	\$41,841,713	\$7,421,800	\$49,263,513	144,735	
	SUBTOTAL UNIT 1 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 10														
	SUBTOTAL UNIT 1 GREENFIELD COSTS FOR PERIODS 1 - 10														
UNIT 2															
	SUBTOTAL UNIT 2 10 CFR 60.75(C) COSTS FOR PERIODS 1 - 10														
	SUBTOTAL UNIT 2 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 10														
	SUBTOTAL UNIT 2 GREENFIELD COSTS FOR PERIODS 1 - 10														
COMMON															
	SUBTOTAL COMMON 10 CFR 60.75(C) COSTS FOR PERIODS 1 - 10	\$21,241,344	\$15,875,786	\$36,335,373					\$26,822,811	\$19,874,882	\$300,288,138	\$49,884,200	\$350,172,338	2,988,514	205,425
	SUBTOTAL COMMON 10 CFR 60.54(b) COSTS FOR PERIODS 1 - 10	\$208,288,342	\$187,462	\$23,882,383					\$11,813,636	\$88,870,983	\$308,842,888	\$42,846,306	\$351,689,194	3,878,390	3,846

2012 D. C. Cook
Scenario 5
DECON, Wet Storage, Modified Systems, 2032 Repository and Current DOE Acceptance Rate

Task	Staff Labor \$	Craft Labor \$	Equipment & Materials \$	Packaging \$	Transportation \$	Clean Disposal \$	Contaminated Disposal \$	Energy \$	Other \$	Wet Storage \$	Wet Storage \$	Wet Storage \$	Wet Storage \$	Staff Months	Craft Months	Craft Months
SUBTOTAL COMMON GREENFIELD COSTS FOR PERIODS 1-10	\$12,438,749	\$2,430,090	\$2,069,884					\$782,688	\$993,186	\$18,825,191	\$3,467,300	\$22,285,481		132,786	46,965	
UNIT 1, UNIT 2 & COMMON														7,262,833		
GRAND TOTAL ACTIVITY COSTS FOR PERIODS 1-10:	\$16,214,127	\$159,368,948	\$28,124,867	\$1,262,752	\$26,868,377	\$26,303,059	\$191,363,101	\$34,908,078	\$88,081,286	\$420,810,013	\$19,977,506	\$840,782,933		107,868	1,076,782	1,102,728
GRAND TOTAL PERIOD DEPENDENT COSTS FOR PERIODS 1-10:	\$495,417,167	\$18,297,328	\$74,223,078							\$971,927,931	\$103,896,809	\$776,584,931		7,154,824	43,849	308,841
GRAND TOTAL	\$495,631,244	\$157,882,385	\$99,309,894	\$1,262,752	\$26,868,377	\$26,303,059	\$191,363,101	\$34,908,078	\$88,081,286	\$1,092,737,943	\$123,829,806	\$1,316,267,763		7,262,833	1,121,787	1,411,798
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.76(c):	\$26,177,442	\$27,388,346	\$16,467,637	\$891,684	\$10,823,893		\$87,844,088	\$1,786,888	\$2,362,287	\$172,311,441	\$50,191,388	\$222,852,781		164,733	\$,700	431,164
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.54(b):																
SUBTOTAL UNIT 1 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (g):		\$12,886,492	\$1,339,197		\$793,182	\$4,486,228				\$16,197,007	\$3,796,308	\$22,883,207		240,804		
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.76(c):	\$61,231	\$36,091,846	\$4,302,836	\$840,627	\$10,893,879		\$94,981,348			\$146,941,365	\$47,208,658	\$195,160,855		\$,700	685,787	
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.54(b):																
SUBTOTAL UNIT 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (h):		\$20,794,486	\$1,783,192		\$929,828	\$3,197,380				\$28,706,853	\$8,888,308	\$34,872,383		408,421		
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.76(c):	\$26,182,943	\$34,363,685	\$36,178,793	\$30,232	\$262,963		\$8,407,431	\$20,826,811	\$18,674,842	\$338,827,880	\$98,338,400	\$899,183,260		3,088,210	24,968	381,232
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.54(b):	\$206,037,839	\$2,396,100	\$26,568,803					\$11,813,838	\$48,878,863	\$316,182,332	\$44,047,209	\$369,209,532		3,886,102	31,625	3,646
SUBTOTAL COMMON DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (g):	\$12,836,789	\$28,178,642	\$11,837,947		\$2,842,144	\$17,207,450		\$782,688	\$483,186	\$71,891,368	\$13,183,600	\$84,776,188		132,786	407,168	
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.76(c):	\$26,182,943	\$36,733,786	\$36,847,085	\$1,262,752	\$21,880,438		\$101,363,101	\$22,812,679	\$18,227,149	\$665,080,864	\$188,738,308	\$814,816,904		3,243,946	36,480	1,408,163
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR 10 CFR 60.54(b):	\$206,037,839	\$2,396,100	\$26,568,803					\$11,813,838	\$48,878,863	\$316,182,332	\$44,047,209	\$369,209,532		3,886,102	31,625	3,646
TOTAL UNIT 1 & 2 DECON PROGRAM FINANCIAL PLANNING COST FOR GREENFIELD (g):	\$12,836,789	\$28,178,642	\$11,837,947		\$2,842,144	\$17,207,450		\$782,688	\$483,186	\$71,891,368	\$13,183,600	\$84,776,188		132,786	1,053,862	
GRAND TOTAL	\$495,631,244	\$157,882,385	\$99,309,894	\$1,262,752	\$26,868,377	\$26,303,059	\$191,363,101	\$34,908,078	\$88,081,286	\$1,092,737,943	\$123,829,806	\$1,316,267,763		7,262,833	1,121,787	1,411,798

APPENDIX C

CASH FLOW TABLES

2017 D. C. Cook
Scenario 1
DECON and Permanent On-Site Dry Storage

Scenario 1.-Yearly costs:

UNIT 1

Year	Labor	Material & Equipment	Packaging Transportation & Disposal	Energy	Other	Contingency	Total
2034	\$1,461,800	\$727,800	\$0	\$75,000	\$136,600	\$433,000	\$2,834,200
2035	\$7,968,600	\$3,967,700	\$0	\$409,000	\$744,500	\$2,360,300	\$15,450,100
2036	\$7,968,600	\$3,967,700	\$0	\$409,000	\$744,500	\$2,360,300	\$15,450,100
2037	\$7,889,100	\$3,902,500	\$107,400	\$399,300	\$726,700	\$2,377,100	\$15,402,100
2038	\$4,788,000	\$1,232,000	\$5,201,500	\$0	\$0	\$3,344,400	\$14,565,900
2039	\$10,238,200	\$1,026,500	\$30,273,500	\$0	\$0	\$13,336,600	\$54,874,900
2040	\$10,238,200	\$1,026,500	\$30,273,500	\$0	\$0	\$13,336,600	\$54,874,900
2041	\$10,238,200	\$1,026,500	\$30,273,500	\$0	\$0	\$13,336,600	\$54,874,900
2042	\$1,354,500	\$135,800	\$4,005,100	\$0	\$0	\$1,764,400	\$7,259,800
2043	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2044	\$1,007,700	\$278,100	\$1,466,000	\$0	\$0	\$472,100	\$3,223,900
2045	\$1,959,400	\$540,700	\$2,850,500	\$0	\$0	\$918,000	\$6,268,600
2046	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	\$65,112,300	\$17,831,800	\$104,451,300	\$1,292,300	\$2,352,300	\$54,039,400	\$245,079,400
Rounding Allowance:							\$17
							\$245,079,417
Annual Storage:	\$0	\$0	\$0	\$0	\$0	\$0	\$0

UNIT 2

Year	Labor	Material & Equipment	Packaging Transportation & Disposal	Energy	Other	Contingency	Total
2034	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2035	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2036	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2037	\$110,700	\$29,600	\$107,400	\$0	\$0	\$73,200	\$320,900
2038	\$4,590,600	\$1,219,000	\$4,971,500	\$0	\$0	\$3,216,800	\$13,997,900
2039	\$3,000,100	\$549,700	\$21,838,900	\$0	\$0	\$8,657,000	\$34,045,700
2040	\$3,000,100	\$549,700	\$21,838,900	\$0	\$0	\$8,657,000	\$34,045,700
2041	\$3,000,100	\$549,700	\$21,838,900	\$0	\$0	\$8,657,000	\$34,045,700
2042	\$14,332,000	\$907,700	\$15,433,500	\$0	\$0	\$8,853,700	\$39,526,900
2043	\$16,059,700	\$962,300	\$14,456,900	\$0	\$0	\$8,883,700	\$40,362,600
2044	\$9,794,800	\$804,600	\$9,876,100	\$0	\$0	\$5,332,800	\$25,808,300
2045	\$1,959,400	\$540,700	\$2,850,500	\$0	\$0	\$918,000	\$6,268,600
2046	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	\$55,847,500	\$6,113,000	\$112,712,600	\$0	\$0	\$53,249,200	\$227,922,300
Rounding Allowance:							(\$95)
							\$227,922,205
Annual Storage:	\$0	\$0	\$0	\$0	\$0	\$0	\$0

Common

Year	Labor	Material & Equipment	Packaging Transportation & Disposal	Energy	Other	Contingency	Total
2034	\$1,970,600	\$14,800	\$0	\$0	\$125,700	\$433,300	\$2,545,200
2035	\$10,742,500	\$79,400	\$0	\$0	\$691,000	\$2,361,900	\$13,874,800
2036	\$10,742,500	\$79,400	\$0	\$0	\$691,000	\$2,361,900	\$13,874,800
2037	\$12,084,300	\$3,077,400	\$0	\$53,700	\$784,500	\$3,326,200	\$19,326,100
2038	\$66,140,200	\$123,373,000	\$2,300	\$2,241,900	\$4,604,600	\$42,057,500	\$238,419,400
2039	\$37,508,100	\$42,154,300	\$85,000	\$1,947,900	\$4,475,000	\$17,367,000	\$103,537,300
2040	\$37,508,100	\$42,154,300	\$85,000	\$1,947,900	\$4,475,000	\$17,367,000	\$103,537,300
2041	\$37,508,100	\$42,154,300	\$85,000	\$1,947,900	\$4,475,000	\$17,367,000	\$103,537,300
2042	\$36,646,100	\$10,746,700	\$3,089,400	\$1,766,500	\$3,015,200	\$10,706,100	\$65,970,000
2043	\$36,514,600	\$5,958,100	\$3,547,400	\$1,788,900	\$2,792,600	\$9,690,600	\$60,242,200
2044	\$33,865,600	\$7,338,400	\$8,766,000	\$1,004,600	\$2,031,100	\$9,943,700	\$62,955,400
2045	\$28,295,500	\$8,027,900	\$13,270,500	\$109,300	\$1,111,000	\$9,302,000	\$60,116,200
2046	\$337,000	\$25,500	\$0	\$1,600	\$34,600	\$69,100	\$467,800
	\$349,865,200	\$285,183,300	\$28,930,600	\$12,760,100	\$29,307,300	\$142,359,300	\$848,403,800
Rounding Allowance:							(\$233)
							\$848,403,567
Annual Storage:	\$2,977,700	\$366,400	\$0	\$6,300	\$585,000	\$542,400	\$4,477,800
	\$470,823,000	\$309,128,100	\$246,094,500	\$14,052,400	\$31,659,600	\$249,647,900	\$1,321,405,189
Annual Storage:	\$2,977,700	\$366,400	\$0	\$6,300	\$585,000	\$542,400	\$4,477,800

2012 D. C. Cook
Scenario 2
DECON, Off-Site Permanent Dry Storage

Scenario 2 - Yearly costs:

UNIT 1

Year	Labor	Material & Equipment	Packaging		Energy	Other	Contingency	Total
			Transportation & Disposal					
2034	\$1,461,800	\$727,800	\$0		\$75,000	\$136,600	\$433,000	\$2,834,200
2035	\$7,968,600	\$3,967,700	\$0		\$409,000	\$744,500	\$2,360,300	\$15,450,100
2036	\$7,968,600	\$3,967,700	\$0		\$409,000	\$744,500	\$2,360,300	\$15,450,100
2037	\$7,889,100	\$3,902,500	\$107,400		\$399,300	\$726,700	\$2,376,700	\$15,401,700
2038	\$4,788,000	\$1,232,000	\$5,201,500		\$0	\$0	\$3,327,200	\$14,548,700
2039	\$10,238,200	\$1,026,500	\$30,273,600		\$0	\$0	\$13,358,700	\$54,897,000
2040	\$10,238,200	\$1,026,500	\$30,273,600		\$0	\$0	\$13,358,700	\$54,897,000
2041	\$10,238,200	\$1,026,500	\$30,273,600		\$0	\$0	\$13,358,700	\$54,897,000
2042	\$1,354,500	\$135,800	\$4,005,100		\$0	\$0	\$1,767,300	\$7,262,700
2043	\$0	\$0	\$0		\$0	\$0	\$0	\$0
2044	\$1,007,700	\$278,100	\$1,466,000		\$0	\$0	\$468,700	\$3,220,500
2045	\$1,959,400	\$540,700	\$2,850,500		\$0	\$0	\$911,200	\$6,261,800
2046	\$0	\$0	\$0		\$0	\$0	\$0	\$0
	\$65,112,300	\$17,831,800	\$104,451,300		\$1,292,300	\$2,352,300	\$54,080,800	\$245,120,800

Rounding Allowance: \$17

\$245,120,817

UNIT 2

Year	Labor	Material & Equipment	Packaging		Energy	Other	Contingency	Total
			Transportation & Disposal					
2034	\$0	\$0	\$0		\$0	\$0	\$0	\$0
2035	\$0	\$0	\$0		\$0	\$0	\$0	\$0
2036	\$0	\$0	\$0		\$0	\$0	\$0	\$0
2037	\$110,700	\$29,600	\$107,400		\$0	\$0	\$72,700	\$320,400
2038	\$4,590,600	\$1,219,000	\$4,971,500		\$0	\$0	\$3,198,400	\$13,979,500
2039	\$3,000,100	\$549,700	\$21,838,900		\$0	\$0	\$8,636,400	\$34,025,100
2040	\$3,000,100	\$549,700	\$21,838,900		\$0	\$0	\$8,636,400	\$34,025,100
2041	\$3,000,100	\$549,700	\$21,838,900		\$0	\$0	\$8,636,400	\$34,025,100
2042	\$14,332,000	\$907,700	\$15,433,500		\$0	\$0	\$8,797,800	\$39,471,000
2043	\$16,059,700	\$962,300	\$14,456,900		\$0	\$0	\$8,822,500	\$40,301,400
2044	\$9,794,800	\$804,600	\$9,376,100		\$0	\$0	\$5,295,800	\$25,271,300
2045	\$1,959,400	\$540,700	\$2,850,500		\$0	\$0	\$911,200	\$6,261,800
2046	\$0	\$0	\$0		\$0	\$0	\$0	\$0
	\$55,847,500	\$6,113,000	\$112,712,600		\$0	\$0	\$53,007,600	\$227,680,700

Rounding Allowance: (\$95)

\$227,680,605

Common

Year	Labor	Material & Equipment	Packaging		Energy	Other	Contingency	Total
			Transportation & Disposal					
2034	\$513,200	\$0	\$0		\$0	\$2,528,700	\$456,300	\$3,498,200
2035	\$2,797,600	\$0	\$0		\$0	\$13,784,700	\$2,487,300	\$19,069,600
2036	\$2,797,600	\$0	\$0		\$0	\$13,784,700	\$2,487,300	\$19,069,600
2037	\$4,329,100	\$226,100	\$0		\$53,700	\$14,303,800	\$2,865,600	\$21,778,300
2038	\$66,140,200	\$9,361,200	\$2,300		\$2,239,700	\$35,793,800	\$18,221,100	\$131,758,300
2039	\$37,508,100	\$5,508,400	\$85,000		\$1,945,800	\$45,237,700	\$14,310,300	\$104,595,300
2040	\$37,508,100	\$5,508,400	\$85,000		\$1,945,800	\$45,237,700	\$14,310,300	\$104,595,300
2041	\$37,508,100	\$5,508,400	\$85,000		\$1,945,800	\$45,237,700	\$14,310,300	\$104,595,300
2042	\$36,013,900	\$5,972,000	\$3,089,400		\$1,823,800	\$23,667,000	\$12,494,000	\$83,060,100
2043	\$35,786,100	\$6,042,700	\$3,547,400		\$1,805,200	\$20,378,200	\$12,217,100	\$79,776,700
2044	\$32,616,700	\$7,281,000	\$8,766,000		\$1,038,100	\$14,647,000	\$11,568,700	\$75,717,500
2045	\$26,286,500	\$7,799,700	\$13,270,500		\$103,100	\$7,267,800	\$9,809,600	\$64,537,200
2046	\$244,400	\$18,600	\$0		\$1,400	\$223,100	\$81,400	\$568,900
	\$320,049,600	\$53,226,500	\$28,930,600		\$12,902,400	\$281,891,900	\$115,619,300	\$812,620,300

Rounding Allowance: (\$175)

\$812,620,125

Annual Storage:	\$0	\$0	\$0	\$0	\$6,004,500	\$600,400	\$6,604,900	
	\$441,009,400	\$77,171,300	\$248,094,500	\$14,194,700	\$284,244,200	\$222,707,700	\$1,285,421,548	

2012 D. C. Cook
Scenario 3
DECON, On-Site Dry Storage, Modified Systems, 2032 Repository and Current Acceptance Rate

Scenario 3 - Yearly costs:

UNIT 1

Year	Labor	Material & Equipment	Packaging Transportation & Disposal	Energy	Other	Contingency	Total
2034	\$1,461,800	\$727,800	\$0	\$75,000	\$136,600	\$433,000	\$2,834,200
2035	\$7,968,600	\$3,967,700	\$0	\$409,000	\$744,500	\$2,360,300	\$15,450,100
2036	\$7,968,600	\$3,967,700	\$0	\$409,000	\$744,500	\$2,360,300	\$15,450,100
2037	\$7,889,100	\$3,902,500	\$107,400	\$399,300	\$726,700	\$2,377,000	\$15,402,000
2038	\$4,788,000	\$1,232,000	\$5,201,500	\$0	\$0	\$3,340,100	\$14,561,600
2039	\$10,238,200	\$1,026,500	\$30,273,600	\$0	\$0	\$13,386,400	\$54,924,700
2040	\$10,238,200	\$1,026,500	\$30,273,600	\$0	\$0	\$13,386,400	\$54,924,700
2041	\$10,238,200	\$1,026,500	\$30,273,600	\$0	\$0	\$13,386,400	\$54,924,700
2042	\$1,354,500	\$135,800	\$4,005,100	\$0	\$0	\$1,771,000	\$7,266,400
2043	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2044	\$1,007,700	\$278,100	\$1,466,000	\$0	\$0	\$471,400	\$3,223,200
2045	\$1,959,400	\$540,700	\$2,850,500	\$0	\$0	\$916,500	\$6,267,100
2046	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2047	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2048	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2049	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2050	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2051	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2052	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2053	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2054	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2055	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2056	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2057	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2058	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2059	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2060	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2061	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2062	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2063	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2064	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2065	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2066	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2067	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2068	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2069	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2070	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2071	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2072	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2073	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2074	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2075	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2076	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2077	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2078	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2079	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2080	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2081	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2082	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	\$65,112,300	\$17,831,800	\$104,451,300	\$1,292,300	\$2,352,300	\$54,188,300	\$245,228,800

Rounding Allowance: (\$283)

\$245,228,517

2012 D. C. Cook
Scenario 3
DECON, On-Site Dry Storage, Modified Systems, 2032 Repository and Current Acceptance Rate

UNIT 2

Year	Labor	Material & Equipment	Packaging Transportation & Disposal	Energy	Other	Contingency	Total
2034	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2035	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2036	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2037	\$110,700	\$29,600	\$107,400	\$0	\$0	\$73,000	\$320,700
2038	\$4,590,600	\$1,219,000	\$4,971,500	\$0	\$0	\$3,210,800	\$13,991,900
2039	\$3,000,100	\$549,700	\$21,838,900	\$0	\$0	\$8,644,400	\$34,033,100
2040	\$3,000,100	\$549,700	\$21,838,900	\$0	\$0	\$8,644,400	\$34,033,100
2041	\$3,000,100	\$549,700	\$21,838,900	\$0	\$0	\$8,644,400	\$34,033,100
2042	\$14,332,000	\$907,700	\$15,433,500	\$0	\$0	\$8,836,500	\$39,509,700
2043	\$16,059,700	\$962,300	\$14,456,900	\$0	\$0	\$8,865,800	\$40,344,700
2044	\$9,794,800	\$804,600	\$9,376,100	\$0	\$0	\$5,322,300	\$25,297,800
2045	\$1,959,400	\$540,700	\$2,850,500	\$0	\$0	\$916,500	\$6,267,100
2046	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2047	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2048	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2049	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2050	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2051	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2052	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2053	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2054	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2055	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2056	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2057	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2058	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2059	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2060	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2061	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2062	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2063	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2064	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2065	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2066	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2067	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2068	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2069	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2070	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2071	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2072	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2073	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2074	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2075	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2076	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2077	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2078	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2079	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2080	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2081	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2082	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	\$55,847,500	\$6,113,000	\$112,712,600	\$0	\$0	\$53,158,100	\$227,831,200

Rounding Allowance: (\$95)

\$227,831,105

DECON, On-Site Dry Storage, Modified Systems, 2032 Repository and Current Acceptance Rate

Common

Year	Labor	Material & Equipment	Packaging		Energy	Other	Contingency	Total
			Transportation & Disposal					
2034	\$1,502,400	\$9,900	\$0		\$0	\$126,700	\$324,200	\$1,963,200
2035	\$8,189,900	\$53,900	\$0		\$0	\$691,000	\$1,767,300	\$10,702,100
2036	\$8,189,900	\$53,900	\$0		\$0	\$691,000	\$1,767,300	\$10,702,100
2037	\$9,592,600	\$1,943,000	\$0		\$53,700	\$784,500	\$2,468,300	\$14,842,100
2038	\$66,140,200	\$77,767,600	\$2,300		\$2,241,000	\$4,604,600	\$30,653,800	\$181,409,500
2039	\$37,508,100	\$27,495,900	\$85,000		\$1,947,100	\$4,475,000	\$13,700,300	\$85,211,400
2040	\$37,508,100	\$27,495,900	\$85,000		\$1,947,100	\$4,475,000	\$13,700,300	\$85,211,400
2041	\$37,508,100	\$27,495,900	\$85,000		\$1,947,100	\$4,475,000	\$13,700,300	\$85,211,400
2042	\$36,646,100	\$8,664,500	\$3,089,400		\$1,765,700	\$3,015,200	\$10,177,900	\$63,358,800
2043	\$36,514,600	\$5,793,300	\$3,547,400		\$1,738,100	\$2,792,600	\$9,640,800	\$60,026,800
2044	\$33,865,600	\$7,248,200	\$8,766,000		\$1,003,800	\$2,031,100	\$9,916,500	\$62,831,200
2045	\$28,189,700	\$8,027,900	\$13,270,500		\$108,500	\$1,111,000	\$9,274,100	\$59,981,700
2046	\$3,198,100	\$380,500	\$0		\$6,800	\$601,400	\$590,900	\$4,777,700
2047	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2048	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2049	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2050	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2051	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2052	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2053	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2054	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2055	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2056	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2057	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2058	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2059	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2060	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2061	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2062	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2063	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2064	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2065	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2066	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2067	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2068	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2069	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2070	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2071	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2072	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2073	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2074	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2075	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2076	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2077	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2078	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2079	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2080	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2081	\$2,981,300	\$366,400	\$0		\$5,500	\$585,000	\$542,900	\$4,481,100
2082	\$5,124,100	\$362,600	\$0		\$4,000	\$342,800	\$1,019,700	\$6,853,200
	\$454,023,000	\$205,617,000	\$28,930,600		\$12,955,400	\$50,691,900	\$137,703,200	\$889,921,100
Rounding Allowance:								\$891
								\$889,921,991
	\$574,982,800	\$229,561,800	\$246,094,600		\$14,247,700	\$53,044,200	\$245,050,100	\$1,362,981,613

2012 D. C. Cook
Scenario 4
SAFSTOR: Permanent On-Site Dry Storage

Scenario 4 - Yearly costs:

UNIT 1							
Year	Labor	Material & Equipment	Packaging Transportation & Disposal	Energy	Other	Contingency	Total
2034	\$1,420,100	\$706,400	\$0	\$227,200	\$132,500	\$443,600	\$2,929,800
2035	\$7,979,700	\$3,969,100	\$0	\$1,276,500	\$744,500	\$2,492,400	\$16,462,200
2036	\$7,979,700	\$3,969,100	\$0	\$1,276,500	\$744,500	\$2,492,400	\$16,462,200
2037	\$7,910,100	\$3,894,400	\$126,900	\$1,246,000	\$726,700	\$2,506,000	\$16,410,100
2038	\$4,152,000	\$688,500	\$4,356,400	\$0	\$0	\$2,512,200	\$11,709,100
2039	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2040	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2041	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2042	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2043	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2044	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2045	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2046	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2047	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2048	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2049	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2050	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2051	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2052	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2053	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2054	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2055	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2056	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2057	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2058	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2059	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2060	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2061	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2062	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2063	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2064	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2065	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2066	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2067	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2068	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2069	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2070	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2071	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2072	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2073	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2074	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2075	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2076	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2077	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2078	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2079	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2080	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2081	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2082	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2083	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2084	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2085	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2086	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2087	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2088	\$7,734,700	\$991,700	\$0	\$318,900	\$1,873,500	\$1,743,300	\$12,662,100
2089	\$7,740,700	\$992,400	\$0	\$319,200	\$1,875,000	\$1,744,600	\$12,671,900
2090	\$7,740,700	\$992,400	\$0	\$319,200	\$1,875,000	\$1,744,600	\$12,671,900
2091	\$7,740,700	\$992,400	\$0	\$319,200	\$1,875,000	\$1,744,600	\$12,671,900
2092	\$9,307,000	\$1,015,200	\$12,002,300	\$121,700	\$715,200	\$5,890,700	\$29,047,100
2093	\$10,264,900	\$1,029,200	\$19,403,800	\$0	\$0	\$8,447,500	\$39,145,400
2094	\$10,264,900	\$1,029,200	\$19,403,800	\$0	\$0	\$8,447,500	\$39,145,400
2095	\$5,469,100	\$548,400	\$10,338,400	\$0	\$0	\$4,500,800	\$20,856,700
2096	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2097	\$215,300	\$58,400	\$313,200	\$0	\$0	\$100,400	\$688,300
2098	\$2,239,100	\$617,800	\$3,257,400	\$0	\$0	\$1,044,000	\$7,158,300
2099	<u>\$512,800</u>	<u>\$141,500</u>	<u>\$745,900</u>	<u>\$0</u>	<u>\$0</u>	<u>\$239,100</u>	<u>\$1,639,300</u>
	\$98,666,500	\$21,637,100	\$69,948,100	\$5,424,400	\$10,561,900	\$46,093,700	\$252,331,700

Rounding Allowance: (\$515)

\$252,331,185

2012 D: C. Cook
Scenario 4
SAFSTOR, Permanent On-Site Dry Storage

UNIT 2

Year	Labor	Material & Equipment	Packaging Transportation & Disposal	Energy	Other	Contingency	Total
2034	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2035	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2036	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2037	\$121,000	\$20,100	\$126,900	\$0	\$0	\$73,200	\$341,200
2038	\$4,152,000	\$688,500	\$4,356,400	\$0	\$0	\$2,512,200	\$11,709,100
2039	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2040	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2041	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2042	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2043	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2044	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2045	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2046	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2047	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2048	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2049	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2050	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2051	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2052	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2053	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2054	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2055	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2056	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2057	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2058	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2059	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2060	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2061	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2062	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2063	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2064	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2065	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2066	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2067	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2068	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2069	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2070	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2071	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2072	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2073	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2074	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2075	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2076	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2077	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2078	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2079	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2080	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2081	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2082	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2083	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2084	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2085	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2086	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2087	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2088	\$79,000	\$119,800	\$0	\$0	\$0	\$48,100	\$246,900
2089	\$79,100	\$119,800	\$0	\$0	\$0	\$48,100	\$247,000
2090	\$79,100	\$119,800	\$0	\$0	\$0	\$48,100	\$247,000
2091	\$79,100	\$119,800	\$0	\$0	\$0	\$48,100	\$247,000
2092	\$1,890,700	\$386,600	\$6,771,400	\$0	\$0	\$2,599,500	\$11,648,200
2093	\$3,008,000	\$551,100	\$10,947,200	\$0	\$0	\$4,172,800	\$18,679,100
2094	\$3,008,000	\$551,100	\$10,947,200	\$0	\$0	\$4,172,800	\$18,679,100
2095	\$9,244,400	\$751,500	\$12,711,700	\$0	\$0	\$6,111,800	\$28,819,400
2096	\$16,356,400	\$980,100	\$14,724,000	\$0	\$0	\$8,323,100	\$40,383,600
2097	\$14,999,000	\$945,200	\$13,621,400	\$0	\$0	\$7,623,200	\$37,188,800
2098	\$2,239,100	\$617,800	\$3,257,400	\$0	\$0	\$1,044,000	\$7,158,300
2099	<u>\$512,800</u>	<u>\$141,500</u>	<u>\$745,900</u>	<u>\$0</u>	<u>\$0</u>	<u>\$239,100</u>	<u>\$1,639,300</u>
	\$55,847,700	\$6,112,700	\$78,209,500	\$0	\$0	\$37,064,100	\$177,234,000

Rounding Allowance: \$70

\$177,234,070

2012 D. C. Cook
Scenario 4
SAFSTOR, Permanent On-Site Dry Storage

Common							
Year	Labor	Material & Equipment	Packaging	Energy	Other	Contingency	Total
			Transportation & Disposal				
2034	\$1,654,800	\$14,200	\$0	\$0	\$123,000	\$382,900	\$2,174,900
2035	\$9,298,200	\$79,600	\$0	\$0	\$691,000	\$2,151,700	\$12,220,500
2036	\$9,298,200	\$79,600	\$0	\$0	\$691,000	\$2,151,700	\$12,220,500
2037	\$10,566,900	\$3,531,100	\$0	\$140,100	\$784,500	\$3,228,900	\$18,251,500
2038	\$52,553,100	\$123,493,400	\$0	\$4,949,500	\$4,510,300	\$40,315,700	\$225,822,000
2039	\$7,703,800	\$27,520,100	\$0	\$785,300	\$4,066,200	\$8,773,100	\$48,848,500
2040	\$7,703,800	\$27,520,100	\$0	\$785,300	\$4,066,200	\$8,773,100	\$48,848,500
2041	\$7,703,800	\$27,520,100	\$0	\$785,300	\$4,066,200	\$8,773,100	\$48,848,500
2042	\$7,703,800	\$27,520,100	\$0	\$785,300	\$4,066,200	\$8,773,100	\$48,848,500
2043	\$4,444,500	\$6,466,300	\$0	\$306,000	\$2,821,000	\$2,761,900	\$16,799,700
2044	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2045	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2046	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2047	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2048	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2049	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2050	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2051	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2052	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2053	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2054	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2055	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2056	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2057	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2058	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2059	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2060	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2061	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2062	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2063	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2064	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2065	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2066	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2067	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2068	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2069	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2070	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2071	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2072	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2073	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2074	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2075	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2076	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2077	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2078	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2079	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2080	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2081	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2082	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2083	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2084	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2085	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2086	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2087	\$3,499,700	\$363,500	\$0	\$167,100	\$2,460,000	\$1,019,400	\$7,509,700
2088	\$5,129,400	\$515,100	\$0	\$20,400	\$586,500	\$1,020,000	\$7,271,400
2089	\$5,130,700	\$515,200	\$0	\$20,300	\$585,000	\$1,020,000	\$7,271,200
2090	\$5,130,700	\$515,200	\$0	\$20,300	\$585,000	\$1,020,000	\$7,271,200
2091	\$5,130,700	\$515,200	\$0	\$20,300	\$585,000	\$1,020,000	\$7,271,200
2092	\$23,217,700	\$3,251,300	\$52,700	\$2,515,400	\$2,032,900	\$5,136,800	\$36,206,800
2093	\$34,371,600	\$4,938,500	\$85,200	\$4,054,000	\$1,925,800	\$7,675,600	\$54,050,700
2094	\$34,371,600	\$4,938,500	\$85,200	\$4,054,000	\$1,925,800	\$7,675,600	\$54,050,700
2095	\$35,358,800	\$5,359,100	\$1,733,400	\$3,956,700	\$2,863,600	\$8,671,100	\$57,942,700
2096	\$36,484,500	\$5,838,700	\$3,613,000	\$3,845,600	\$2,792,600	\$9,806,500	\$62,380,900
2097	\$35,995,300	\$6,152,800	\$4,723,700	\$3,501,300	\$2,630,900	\$9,865,600	\$62,869,600
2098	\$31,397,100	\$9,105,300	\$15,164,600	\$265,300	\$1,111,000	\$10,421,500	\$67,464,800
2099	<u>\$9,043,300</u>	<u>\$2,218,000</u>	<u>\$3,472,700</u>	<u>\$89,800</u>	<u>\$421,700</u>	<u>\$2,760,000</u>	<u>\$18,005,500</u>
	\$533,379,100	\$303,601,500	\$28,930,500	\$38,252,600	\$154,171,400	\$197,031,500	\$1,255,366,600
Rounding Allowance:							(\$4,656)
							\$1,255,361,944
Annual Cost:	\$687,893,300	\$331,351,300	\$177,088,100	\$43,677,000	\$164,733,300	\$280,189,300	\$1,684,927,198
	\$2,977,676	\$388,409	\$0	\$20,281	\$588,034	\$543,800	\$4,493,201

2012 D. C. Cook
Scenario 5
DECON, Wet Storage, Modified Systems, 2032 Repository and Current DOE Acceptance Rate

Scenario 5 - Yearly costs:

UNIT 1

Year	Labor	Material & Equipment	Packaging, Transportation & Disposal	Energy	Other	Contingency	Total
2034	\$1,461,800	\$727,800	\$0	\$103,700	\$136,600	\$437,300	\$2,867,200
2035	\$7,968,600	\$3,967,700	\$0	\$565,200	\$744,500	\$2,383,700	\$15,629,700
2036	\$7,968,600	\$3,967,700	\$0	\$565,200	\$744,500	\$2,383,700	\$15,629,700
2037	\$7,889,400	\$3,902,000	\$107,700	\$551,700	\$726,700	\$2,399,700	\$15,577,200
2038	\$4,815,700	\$1,210,300	\$5,284,100	\$0	\$0	\$3,360,200	\$14,670,300
2039	\$10,238,200	\$1,026,500	\$30,273,600	\$0	\$0	\$13,306,000	\$54,844,300
2040	\$10,238,200	\$1,026,500	\$30,273,600	\$0	\$0	\$13,306,000	\$54,844,300
2041	\$10,238,200	\$1,026,500	\$30,273,600	\$0	\$0	\$13,306,000	\$54,844,300
2042	\$1,326,400	\$133,000	\$3,922,200	\$0	\$0	\$1,723,900	\$7,105,500
2043	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2044	\$1,452,400	\$400,800	\$2,112,900	\$0	\$0	\$676,000	\$4,642,100
2045	\$1,514,800	\$418,000	\$2,203,600	\$0	\$0	\$705,100	\$4,841,500
2046	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2047	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2048	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2049	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2050	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2051	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2052	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2053	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2054	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2055	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2056	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2057	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2058	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2059	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2060	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2061	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2062	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2063	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2064	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2065	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2066	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2067	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2068	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2069	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2070	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2071	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2072	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2073	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2074	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2075	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2076	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2077	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2078	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2079	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2080	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2081	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2082	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	\$65,112,300	\$17,806,800	\$104,451,300	\$1,785,800	\$2,352,300	\$53,987,600	\$245,496,100

Rounding Allowance: (\$101)

\$245,495,999

2012 D. C. Cook
Scenario 5
DECON, Wet Storage, Modified Systems, 2032 Repository and Current DOE Acceptance Rate

UNIT 2

Year	Labor	Material & Equipment	Packaging Transportation & Disposal	Energy	Other	Contingency	Total
2034	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2035	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2036	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2037	\$111,000	\$29,000	\$107,700	\$0	\$0	\$72,900	\$320,600
2038	\$4,598,500	\$1,196,000	\$5,031,000	\$0	\$0	\$3,220,400	\$14,045,900
2039	\$3,000,100	\$549,700	\$21,838,900	\$0	\$0	\$8,648,100	\$34,036,800
2040	\$3,000,100	\$549,700	\$21,838,900	\$0	\$0	\$8,648,100	\$34,036,800
2041	\$3,000,100	\$549,700	\$21,838,900	\$0	\$0	\$8,648,100	\$34,036,800
2042	\$15,591,500	\$982,200	\$16,515,000	\$0	\$0	\$9,484,700	\$42,573,400
2043	\$17,465,700	\$1,046,500	\$15,722,500	\$0	\$0	\$9,609,200	\$43,843,900
2044	\$7,565,700	\$767,100	\$7,616,000	\$0	\$0	\$4,039,400	\$19,988,200
2045	\$1,514,800	\$418,000	\$2,203,600	\$0	\$0	\$705,100	\$4,841,500
2046	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2047	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2048	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2049	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2050	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2051	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2052	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2053	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2054	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2055	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2056	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2057	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2058	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2059	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2060	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2061	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2062	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2063	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2064	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2065	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2066	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2067	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2068	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2069	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2070	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2071	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2072	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2073	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2074	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2075	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2076	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2077	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2078	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2079	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2080	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2081	\$0	\$0	\$0	\$0	\$0	\$0	\$0
2082	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	\$55,847,500	\$6,087,900	\$112,712,500	\$0	\$0	\$53,076,000	\$227,723,900

Rounding Allowance: (\$95)

\$227,723,805

2012 D. C. Cook
Scenario 5
DECON, Wet Storage, Modified Systems, 2032 Repository and Current DOE Acceptance Rate

Common

Year	Packaging Transportation & Disposal						Total
	Labor	Material & Equipment	Disposal	Energy	Other	Contingency	
2034	\$513,200	\$0	\$0	\$0	\$126,700	\$96,000	\$735,900
2035	\$2,797,600	\$0	\$0	\$0	\$691,000	\$523,300	\$4,011,900
2036	\$2,797,600	\$0	\$0	\$0	\$691,000	\$523,300	\$4,011,900
2037	\$4,330,900	\$220,600	\$0	\$86,600	\$784,500	\$841,600	\$6,264,200
2038	\$66,134,300	\$9,128,400	\$2,500	\$3,620,100	\$4,604,200	\$13,692,700	\$97,182,200
2039	\$37,508,100	\$5,508,400	\$85,000	\$3,327,100	\$4,475,000	\$8,404,200	\$59,307,800
2040	\$37,508,100	\$5,508,400	\$85,000	\$3,327,100	\$4,475,000	\$8,404,200	\$59,307,800
2041	\$37,508,100	\$5,508,400	\$85,000	\$3,327,100	\$4,475,000	\$8,404,200	\$59,307,800
2042	\$37,473,700	\$5,811,700	\$120,600	\$3,281,200	\$4,235,100	\$8,792,200	\$59,714,500
2043	\$37,468,600	\$5,856,900	\$125,900	\$3,274,400	\$4,199,400	\$8,849,900	\$59,775,100
2044	\$29,051,100	\$5,695,500	\$4,532,000	\$1,593,300	\$3,198,300	\$7,718,700	\$51,788,900
2045	\$19,600,200	\$4,113,300	\$4,680,800	\$680,300	\$2,635,700	\$5,483,900	\$37,194,200
2046	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2047	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2048	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2049	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2050	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2051	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2052	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2053	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2054	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2055	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2056	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2057	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2058	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2059	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2060	\$6,151,600	\$754,400	\$0	\$644,400	\$2,526,100	\$1,315,200	\$11,391,700
2061	\$19,457,400	\$5,023,100	\$10,006,100	\$586,600	\$1,868,300	\$7,424,400	\$44,365,900
2062	\$16,747,700	\$4,477,700	\$9,207,700	\$253,800	\$896,600	\$6,533,100	\$38,116,600
2063	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2064	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2065	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2066	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2067	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2068	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2069	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2070	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2071	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2072	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2073	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2074	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2075	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2076	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2077	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2078	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2079	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2080	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2081	\$3,028,300	\$366,400	\$0	\$5,100	\$585,000	\$549,900	\$4,534,700
2082	<u>\$3,626,300</u>	<u>\$334,300</u>	<u>\$0</u>	<u>\$3,500</u>	<u>\$366,600</u>	<u>\$698,400</u>	<u>\$5,029,100</u>
	\$502,334,600	\$75,464,300	\$28,930,600	\$33,124,000	\$86,728,900	\$116,566,200	\$843,148,600

Rounding Allowance: (\$640)

\$843,147,960

\$623,294,400	\$99,359,000	\$248,094,400	\$34,909,800	\$89,081,200	\$223,629,800	\$1,316,367,763
---------------	--------------	---------------	--------------	--------------	---------------	-----------------