



**UNITED STATES
NUCLEAR REGULATORY COMMISSION**
REGION II
245 PEACHTREE CENTER AVENUE NE, SUITE 1200
ATLANTA, GEORGIA 30303-1257

January 10, 2013

Mr. Tom E. Tynan
Vice President
Southern Nuclear Operating Company, Inc.
Vogtle Electric Generating Plant
7821 River Road
Waynesboro, GA 30830

**SUBJECT: VOGTLE ELECTRIC GENERATING PLANT UNIT 2 – NOTIFICATION OF
INSPECTION AND REQUEST FOR INFORMATION**

Dear Tynan:

From March 18 – March 29, 2013, the Nuclear Regulatory Commission (NRC) will perform the baseline inservice inspection (ISI) at the Vogtle Electric Generating Plant , Unit 2, in accordance with NRC Inspection Procedure 71111.08. Experience has shown that this inspection is resource intensive both for the NRC inspectors and your staff. In order to minimize the impact to your on-site resources and to ensure a productive inspection, we have enclosed a request for documents needed for this inspection. These documents have been divided into two groups. The first group (Section A of the enclosure) identifies information to be provided prior to the inspection to ensure that the inspectors are adequately prepared. The second group (Section B of the enclosure) identifies the information the inspectors will need upon arrival at the site. It is important that all of these documents are up to date and complete in order to minimize the number of additional documents requested during the preparation and/or the on-site portions of the inspection.

We have discussed the schedule for these inspection activities with your staff and understand that our regulatory contact for this inspection will be Mr. Mark Hickox of your organization. Our inspection dates are subject to change based on your updated schedule of outage activities. If there are any questions about this inspection or the material requested, please contact the lead inspector, Michael Coursey at (404) 997-4671 (Michael.Coursey@nrc.gov).

In accordance with 10 CFR 2.390 of the NRC's "Rules of Practice," a copy of this letter, and its Enclosure, will be available electronically for public inspection in the NRC Public Document Room or from the Publicly Available Records (PARS) component of NRC's document system,

T. Tynan

2

ADAMS. ADAMS is accessible from the NRC Web site at [http://www.nrc.gov/ reading-rm/adams.html](http://www.nrc.gov/reading-rm/adams.html) (the Public Electronic Reading Room).

Sincerely,

/RA/

Steven J. Vias, Chief
Engineering Branch 3
Division of Reactor Safety

Docket No.: 50-425
License No.: NPF-81

Enclosure:
Inservice Inspection Document Request

cc: (See page 3)

ADAMS. ADAMS is accessible from the NRC Web site at [http://www.nrc.gov/ reading-rm/adams.html](http://www.nrc.gov/reading-rm/adams.html) (the Public Electronic Reading Room).

Sincerely,

/RA/

Steven J. Vias, Chief
Engineering Branch 3
Division of Reactor Safety

Docket No.: 50-425
License No.: NPF-81

Enclosure:
Inservice Inspection Document Request

cc: (See page 3)

PUBLICLY AVAILABLE NON-PUBLICLY AVAILABLE SENSITIVE NON-SENSITIVE
ADAMS: Yes ACCESSION NUMBER: _____ SUNSI REVIEW COMPLETE FORM 665 ATTACHED

OFFICE	RII:DRS	RII:DRS	RII:DRS	RII:DRS			
SIGNATURE	RA	RA	RA	RA			
NAME	COURSEY	CARRION	LAKE	VIAS			
DATE	1/8/2013	1/8/2013	1/9/2013	1/10/2013	1/ /2013	1/ /2013	1/ /2013
E-MAIL COPY?	YES NO	YES NO	YES NO	YES NO	YES NO	YES NO	YES NO

OFFICIAL RECORD COPY DOCUMENT NAME: S:\DRS\ENG BRANCH 3\INSPECTIONS\WORKING DOCUMENTS\SI REQUEST FOR INFORMATION LETTERS\2013\VOGTLE U2 ISI SGISI RFI 2013002 MSC RC.DOCX

cc:

C. Russ Dedrickson
Fleet Support Supervisor
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

S. Kuczynski
Chairman, President and CEO
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

Todd L. Youngblood
Vice President
Fleet Oversight
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

W. L. Bargeron
Plant Manager
Vogtle Electric Generating Plant
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

D. G. Bost
Chief Nuclear Officer
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

N. J. Stringfellow
Licensing Manager
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

Paula Marino
Vice President
Engineering
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

T. A. Lynch
Vice President
Joseph M. Farley Nuclear Plant
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

Dennis R. Madison
Vice President
Edwin I. Hatch Nuclear Plant
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

Leigh Perry
SVP & General Counsel-Ops & SNC
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

M. J. Ajluni
Nuclear Licensing Director
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

B. D. McKinney, Jr.
Regulatory Response Manager
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

D. W. Daughhetee
Licensing Engineer
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

Bradley J. Adams
Vice President
Fleet Operations Support
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

T. D. Honeycutt
Regulatory Response Supervisor
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

L. P. Hill
Licensing Supervisor
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

L. L. Crumpton
Administrative Assistant, Sr.
Southern Nuclear Operating Company, Inc.
Electronic Mail Distribution

Hickox, T. Mark
Vogtle Electric Generating Plant
Electronic Mail Distribution

(cc cont'd – See page 4)

(cc cont'd)

Mark Rauckhorst
Site Vice President
Vogtle Units 3 and 4
Southern Nuclear Operating Company
Electronic Mail Distribution

S. C. Swanson
Site Support Manager
Vogtle Electric Generating Plant
Electronic Mail Distribution

Senior Resident Inspector
U.S. Nuclear Regulatory Commission
Vogtle Electric Generating Plant
7821 River Road
Waynesboro, GA 30830

Arthur H. Domby, Esq.
Troutman Sanders
Electronic Mail Distribution

Jerry Ranalli
Municipal Electric Authority of Georgia
Power
Electronic Mail Distribution

Sandra Threatt, Manager
Nuclear Response and Emergency
Environmental Surveillance
Bureau of Land and Waste Management
Department of Health and Environmental
Control
Electronic Mail Distribution

Division of Radiological Health
TN Dept. of Environment & Conservation
401 Church Street
Nashville, TN 37243-1532

Richard Haynes
Director, Division of Waste Management
Bureau of Land and Waste Management
S.C. Department of Health and
Environmental Control
2600 Bull Street
Columbia, SC 29201

Lee Foley
Manager of Contracts Generation
Oglethorpe Power Corporation
Electronic Mail Distribution

Mark Williams
Commissioner
Georgia Department of Natural Resources
Electronic Mail Distribution

Chuck Mueller
Manager
Policy and Radiation Program
Georgia Department of Natural Resources
Electronic Mail Distribution

Cynthia A. Sanders
Radioactive Materials Program Manager
Environmental Protection Division
Georgia Department of Natural Resources
Electronic Mail Distribution

James C. Hardeman
Environmental Radiation Program Manager
Environmental Protection Division
Georgia Department of Natural Resources
Electronic Mail Distribution

Mr. Steven M. Jackson
Senior Engineer - Power Supply
Municipal Electric Authority of Georgia
Electronic Mail Distribution

Reece McAlister
Executive Secretary
Georgia Public Service Commission
Electronic Mail Distribution

Office of the Attorney General
40 Capitol Square, SW
Atlanta, GA 30334

Office of the County Commissioner
Burke County Commission
Electronic Mail Distribution

(cc cont'd – See page 5)

(cc cont'd)
Director
Consumers' Utility Counsel Division
Governor's Office of Consumer Affairs
2 M. L. King, Jr. Drive
Plaza Level East; Suite 356
Atlanta, GA 30334-4600

Amy Whaley
Resident Manager
Electronic Mail Distribution

Letter to Tom E. Tynan from Stephen J. Vias dated January 10, 2013.

SUBJECT: VOGTLE ELECTRIC GENERATING PLANT UNIT 2 – NOTIFICATION OF
INSPECTION AND REQUEST FOR INFORMATION

Distribution:

RIDSNRRDIRS

PUBLIC

RidsNrrPMVogtle Resource

INSERVICE INSPECTION DOCUMENT REQUEST

Inspection Dates: March 18 – March 29, 2013

Inspection Procedures: IP 71111.08, "Inservice Inspection (ISI) Activities"

Inspectors: Michael Coursey, Reactor Inspector (ISI, Lead Inspector)
Robert Carrion, Senior Reactor Inspector (Steam Generators)

A. Information Requested for the In-Office Preparation Week

The following information should be sent to the Region II office in hard copy or electronic format (CD or SharePoint preferred), in care of Michael Coursey by March 4, 2013, to facilitate the selection of specific items that will be reviewed during the on-site inspection weeks. The inspector will select specific items from the information requested below and then request, from your staff, additional documents needed during the on-site inspection week (Section B of this Enclosure). We ask that the specific items selected from the lists be available, and ready for review, on the first day of inspection. *Please provide requested documentation electronically if possible. If requested documents are large and only hard copy formats are available, please inform the inspectors, and provide subject documentation during the first day of the on-site inspection. If you have any questions regarding this information request, please call the inspector as soon as possible.

A.1 ISI / Welding Programs and Schedule Information

a) A detailed schedule (including preliminary dates) of:

- i) Nondestructive examinations (NDEs) planned for Class 1 and 2 systems and containment, performed as part of your ASME Section XI, Risk-Informed (if applicable), and augmented ISI Programs during the upcoming outage.

Please include a status summary of the NDE inspection activities versus the required inspection period percentages for this Interval by category per American Society for Mechanical Engineers (ASME) Section XI, IWX-2400. (Do not provide separately if other documentation requested contains this information.)

- ii) Reactor pressure vessel head (RPVH) examinations planned for the upcoming outage.
- iii) Examinations planned for Alloy 82/182/600 components that are required by Code Case N770-01. (If applicable)
- iv) Examinations planned as part of your Boric Acid Corrosion Control

Enclosure

Program. (Mode 3 walkdowns, bolted connection walkdowns, etc.)

- v) Welding activities to be completed during the upcoming outage for ASME Class 1, 2, or 3 structures, systems, or components (SSCs).
- b) A copy of ASME Section XI Code Relief Requests and associated NRC Safety Evaluations applicable to the examinations identified above.
- c) A list of NDE reports, (ultrasonic, radiography, magnetic particle, and dye penetrant) that have identified surface or volumetric indications, which were analytically evaluated and accepted for continued service on Code Class 1, 2, and 3 systems since the beginning of the last refueling outage. This should include the previous Section XI pressure test(s) conducted during start up, and any evaluations associated with the results of the pressure tests.
- d) A list, with a brief description (e.g., system, material, pipe size, weld number, and NDE performed), of the welds in Code Class 1, 2, and 3 systems that have been fabricated due to component repair/replacement activities since the beginning of the last refueling outage, or are planned to be fabricated during this refueling outage. Also, please indicate which of those welds are risk-significant.
- e) If reactor vessel shell weld examinations required by the ASME Code are scheduled to occur during the upcoming outage, provide a detailed description of the welds to be examined, and the extent of the planned examination. Please also provide reference numbers for applicable procedures that will be used to conduct these examinations.
- f) A copy of any 10 CFR Part 21 reports applicable to your SSCs, within the scope of Section XI of the ASME Code, that have been identified since the beginning of the last refueling outage.
- g) A list of any temporary non-code repairs in service (e.g., pinhole leaks).
- h) Copies of the most recent self assessments for the ISI, Welding, and Alloy 600 Programs.

A.2 Reactor Pressure Vessel Head (RPVH)

- a) Please provide the detailed scope of the planned NDE of the reactor vessel head which identifies the types of NDE methods to be used on each specific part of the vessel head to meet the augmented inspection requirements of 10CFR50.55a(g)(6)(ii)(D). Also, include examination scope expansion criteria and planned expansion sample sizes if relevant indications are identified. (If applicable)
- b) Please provide a list of the standards and/or requirements that will be used to evaluate indications identified during NDE of the reactor vessel head (e.g., the specific industry or procedural standards that will be used to evaluate potential leakage and/or flaw indications).

- c) Also, include in the list the NDE reports with identified surface or volumetric indications in the RPVH penetration nozzles that have been analytically evaluated and accepted for continued service. The list of NDE reports should include a brief description of the SSC where the recordable indication was identified.

A.3 Boric Acid Corrosion Control Program (BACCP)

- a) Please provide a copy of the procedures that govern the scope, equipment, and implementation of the inspections required to identify boric acid leakage, and the procedures for boric acid leakage/corrosion evaluation.
- b) Please provide a list of leaks (including code class of the components) that have been identified since the last refueling outage and associated corrective action documentation. If during the last cycle, the Unit was shutdown, please provide documentation of containment walkdown inspections performed as part of the BACCP.
- c) Please provide a copy of the most recent self-assessment performed for the BACCP.

A.4 Steam Generator (SG) Inspections

- a) Please provide a detailed schedule of:
 - i) SG tube inspection, data analyses, and repair activities for the upcoming outage. (If occurring)
 - ii) SG secondary side inspection activities for the upcoming outage. (If occurring)
- b) Please provide a copy of your SG ISI Inspection Program and Plan. Please include a copy of the Operational Assessment from last outage, and a copy of the following documents as they become available:
 - i) Degradation Assessment
 - ii) Condition Monitoring Assessment
- c) If you are planning to modify your Standard Technical Specifications (STS) as such that they are consistent with TSTF-449, please provide copies of your correspondence with the NRC regarding deviations from the STS.
- d) Please provide a copy of SG history documentation given to vendors performing eddy current (ET) testing of the SGs during the upcoming outage.

- e) Please provide a copy of SG Eddy Current Data Analyst Guidelines, and Site Validated Eddy Current Technique. Additionally, please provide a copy of EPRI Appendix H Eddy Current Technique Qualification Records.
- f) Please identify, and quantify, any SG tube leakage experienced during the previous operating cycle. Also, provide documentation identifying which SG was leaking and corrective actions completed, or planned for this condition. (If applicable)
- g) Please provide past history of the condition and issues pertaining to the secondary side of the steam generators (including items such as loose parts, fouling, top of tube sheet condition, and crud removal amounts, etc)
- h) Please provide copies of your most recent self-assessments of the SG monitoring, loose parts monitoring, and secondary side water chemistry control programs.
- i) Please also indicate where the primary, secondary, and resolution analyses are scheduled to take place.
- j) Please provide a summary of the scope of the SG ISI examinations, including examination methods such as Bobbin, Rotating Pancake, or Plus Points, and the percentage of tubes to be examined. **Do not provide these documents separately if already included in other information requested.*

A.5 Additional information related to all ISI activities

- a) Please provide a list with a brief description of ISI-, BACCP-, and SG ISI- related issues (e.g., condition reports) entered into your corrective action program since the beginning of the last refueling outage (for Unit 2). For example, a list based upon data base searches using key words related to piping or SG tube degradation such as: ISI, ASME Code, Section XI, NDE, cracks, wear, thinning, leakage, rust, corrosion, boric acid, or errors in piping/SG tube examinations.
- b) Please provide names and phone numbers for the following program leads:
 - ISI (Examination, planning)
 - Containment Exams
 - Alloy 600/MRP-139
 - RPVH Exams
 - Snubbers and Supports
 - Repair and Replacement Program
 - Licensing
 - Site Welding
 - Boric Acid Corrosion Control Program
 - SG Inspection Activities (site lead and vendor contact)

B. Information to be provided on-site to the inspector at the entrance meeting (March 18, 2013):

B.1 ISI / Welding Programs and Schedule Information

- a) Updated schedules for ISI/NDE activities, planned welding activities, and schedule showing contingency repair plans, if available.
- b) For ASME Class 1, 2, and 3 welds selected by the inspector from the lists provided from Section A of this Enclosure, please provide copies of the following documentation for each subject weld:
 - i) Weld data sheet (traveler)
 - ii) Weld configuration and system location
 - iii) Applicable Code Edition and Addenda for weldment
 - iv) Applicable Code Edition and Addenda for Welding Procedures
 - v) Applicable Weld Procedures (WPS) used to fabricate the welds
 - vi) Copies of procedure qualification records (PQRs) supporting the WPS from B.1.b.v
 - vii) Copies of mechanical test reports identified in the PQRs above
 - viii) Copies of the nonconformance reports for the selected welds (If Applicable)
 - ix) Radiographs of the selected welds and access to equipment to allow viewing radiographs (If RT was performed)
 - x) Copies of the preservice examination records for the selected welds
 - xi) Copies of welder performance qualifications records applicable to WPS, including documentation that welder maintained proficiency in the applicable welding processes specified in the WPS (At least six months prior to date subject work)
 - xii) Copies of NDE personnel qualifications (VT, PT, UT, RT) (As applicable)
- c) For the ISI related corrective action issues selected by the inspector from Section A of this Enclosure, please provide a copy of the corrective actions and supporting documentation.
- d) For the NDE reports with relevant indications on Code Class 1, 2, and 3 systems selected by the inspector from Section A above, please provide a copy of the examination records, examiner qualification records, and associated corrective action documents.
- e) Please provide a copy of (or ready access to) most current revision of the ISI Program Manual and Plan for the current Interval.
- f) For the NDEs selected by the inspector from section A of this Enclosure, please provide a copy of the NDE procedures used to perform the examinations (including calibration and flaw characterization/sizing procedures). For ultrasonic examination procedures qualified in accordance with ASME Code, Section XI,

Appendix VIII, please provide documentation supporting the procedure qualification (e.g., the EPRI performance demonstration qualification summary sheets). Also, please include documentation of the specific equipment to be used (e.g., ultrasonic unit, cables, and transducers including serial numbers) and NDE personnel qualification records.

B.2 Reactor Pressure Vessel Head

- a) Please provide the NDE personnel qualification records for the examiners who will perform examinations of the RPVH.
- b) Please provide drawings showing the following: (If a visual examination is planned for the upcoming refueling outage)
 - i) RPVH and CRDM nozzle configurations
 - ii) RPVH insulation configuration

The drawings listed above should include fabrication drawings for the nozzle attachment welds, as applicable.

- c) Please provide a copy of NDE reports from the last RPVH examination.
- d) Please provide a copy of evaluation or calculation demonstrating that the scope of the visual examination of the upper head will meet the 95% minimum coverage required by ASME Code Case N-729-1 (If a visual examination is planned for the upcoming refueling outage).
- e) Please provide a copy of the procedures that will be used to identify the source of any boric acid deposits identified on the RPVH. If no explicit procedures exist which govern this activity, provide a description of the process to be followed including personnel responsibilities and expectations.
- f) Please provide a copy of the updated calculation of effective degradation years (EDY) and re-inspection years (RIY) for the RPVH crack initiation and propagation susceptibility parameters.
- g) Please provide a copy of the vendor qualification report(s) that demonstrates the detection capability of the NDE equipment used for the RPVH examinations. Also, please identify any changes in equipment configurations used for the RPVH examinations that differ from that used in the vendor qualification or demonstration report(s).

B.3 Boric Acid Corrosion Control Program

- a) Please provide boric acid walkdown inspection results, an updated list of boric acid leaks identified during the current outage, associated corrective action documentation, and overall status of planned boric acid inspections.

- b) Please provide any engineering evaluations completed for boric acid leaks identified since the end of the last refueling outage. Please include a status of corrective actions to repair and/or clean these boric acid leaks. Please specify which known leaks, if any, have remained in service, or will remain in service, as active leaks.
- c) In accordance with NRC inspection procedure 71111.08, the inspector would like to conduct an independent boric acid walkdown of the Reactor Building early in the inspection week. Please have knowledgeable BACCP staff available to accompany the inspector during the walkdown.

B.4 Steam Generator Inspections

- a) Please provide copies of the Examination Technique Specification Sheets (ETSS) and associated justification for any revisions.
- b) Please provide a copy of the guidance to be followed if a loose part or foreign material is identified in the steam generators (SGs).
- c) Please provide a copy of the ET procedures used to perform the SG ISI (specifically calibration and flaw characterization/sizing procedures, etc.). Also, include documentation for the specific equipment to be used.
- d) Please provide copies of your responses to NRC and industry operating experience communications such as; Generic Letters, Information Notices, etc. (As applicable to SG inspections.) **Do not provide these documents separately if already included in other information requested such as the degradation assessment.*
- e) Please provide a list of corrective action documents generated by the vendor and/or site with respect to SG inspection activities.

B.5 Codes and Standards

- a) Please provide ready access to: (i.e., copies provided to the inspector to use for the duration of the inspection at the on-site inspection location, or room number and location where available)
 - i) Applicable editions of the ASME Code (Sections V, IX, and XI) for the inservice inspection program and the repair/replacement program.
 - ii) EPRI and industry standards referenced in the procedures used to perform the SG tube eddy current examination.

Inspector Contact Information:

Michael Coursey (Lead ISI Inspector)
Reactor Inspector
404-997-4671
Michael.Coursey@nrc.gov

Mailing Address:

US NRC Region 2
Attn: Michael Coursey
245 Peachtree Center Avenue, Suite 1200
Atlanta, GA 30303

Robert Carrion (SGISI Inspector)
Senior Reactor Inspector
(404) 997-4522
Robert.Carrion@nrc.gov

Mailing Address:

US NRC Region 2
Attn: Robert Carrion
245 Peachtree Center Avenue, Suite 1200
Atlanta, GA 30303