

2.6 HVAC Systems

2.6.1 Main Control Room Air Conditioning System

Design Description

1.0 System Description

The main control room air conditioning system (CRACS) supplies air to the control room envelope (CRE) area which includes the main control room (MCR) and associated rooms.

The CRACS controls the CRE area temperature and air change rate for personnel comfort, personnel safety, and equipment protection during normal plant operation. The CRACS provides cooling, heating, and ventilation for the CRE area to remove equipment heat, and heat generated from other sources. The CRACS also provides heat to maintain a minimum temperature in the CRE area. The CRACS provides a minimal air change rate for the CRE area and controls building pressurization to reduce spreading of contamination.

The CRACS maintains habitability of the CRE area in case of radioactive or toxic gas contamination of the environment. The CRACS also maintains a positive pressure in the CRE area to prevent infiltration of contaminated outside air. The CRACS operates in recirculation mode with fresh air makeup.

The CRACS provides the following safety-related functions:

- Maintains ambient temperature conditions inside the CRE area.
- Provides carbon filtration of outside air and recirculated air from within the CRE area.
- Maintains a positive pressure in the CRE area relative to the adjacent areas to prevent unfiltered in-leakage, upon receipt of a containment isolation signal (CIS) or high radiation alarm signal in the air intake ducts.

2.0 Arrangement

- 2.1 The functional arrangement of the CRACS is as described in the Design Description of Section 2.6.1, Tables 2.6.1-1—Main Control Room Air Conditioning System Equipment Mechanical Design and 2.6.1-2—Main Control Room Air Conditioning System Equipment I&C and Electrical Design, and as shown on Figures 2.6.1-1— Control Room Air Intake and CREF (Iodine Filtration) Train Subsystem Functional Arrangement, 2.6.1-2—Control Room Air Conditioning and Recirculation Air Handling Subsystem Functional Arrangement, and 2.6.1-3—CRE Air Supply and Recirculation Subsystem Functional Arrangement.
- 2.2 Deleted.

EPR	U.S. EPR FINAL SAFETY ANALYSIS REPORT
2.3	Physical separation exists between the CRACS fresh air intake, iodine filtration, and recirculation and air conditioning trains as listed in Table 2.6.1-1.
3.0	Mechanical Design Features
3.1	Deleted.
3.2	Class 1E dampers listed in Table 2.6.1-2 will function to change position as listed in Table 2.6.1-1 under normal operating conditions.
3.3	Equipment identified as Seismic Category I in Table 2.6.1-1 can withstand seismic design basis loads without a loss of the function listed in Table 2.6.1-1.
3.4	Equipment listed in Table 2.6.1-1 as ASME AG-1 Code are designed in accordance with ASME AG-1 Code requirements.
3.5	Equipment listed in Table 2.6.1-1 as ASME AG-1 Code are fabricated in accordance with ASME AG-1 Code requirements, including welding requirements.
3.6	Equipment listed in Table 2.6.1-1 as ASME AG-1 Code are installed, inspected, and tested in accordance with ASME AG-1 Code requirements.
4.0	I&C Design Features, Displays, and Controls
4.1	Displays listed in Table 2.6.1-2 are indicated on the PICS operator workstations in the main control room (MCR) and the remote shutdown station (RSS).
4.2	Controls on the PICS operator workstations in the MCR and the RSS perform the function listed in Table 2.6.1-2.
4.3	Equipment listed as being controlled by a priority and actuator control system (PACS) module in Table 2.6.1-2 responds to the state requested and provides drive monitoring signals back to the PACS module. The PACS module will protect the equipment by terminating the output command upon the equipment reaching the requested state.
5.0	Electrical Power Design Features
5.1	Equipment designated as Class 1E in Table 2.6.1-2 are powered from the Class 1E division as listed in Table 2.6.1-2 in a normal or alternate feed condition.
5.2	Deleted.
6.0	Equipment and System Performance
6.1	The CRACS maintains a positive pressure in the CRE area relative to the outside environment and adjacent areas, while operating in a design basis accident alignment.
6.2	Upon receipt of a containment isolation signal (CIS), the iodine filtration train will start automatically, outside air supply to the CRE area is diverted through the iodine filtration train, a minimum recirculation flowrate is established from the CRE area to

I

I

I

the iodine filtration train, and a positive pressure is maintained in the CRE area relative to the adjacent areas.

- 6.3 Deleted.
- 6.4 The CRE area ventilation unfiltered air in-leakage is minimized in order to maintain the MCR habitability.
- 6.5 The CRACS provides cooling to maintain the design temperatures in the CRE area, while operating in a design basis accident alignment.
- 6.6 The CREF heaters protect the carbon adsorber from high humidity during operation of the CREF unit.
- 6.7 Upon receipt of a high radiation alarm signal in the air intake ducts, the iodine filtration train will start automatically, the outside air supply to the CRE area is diverted through the iodine filtration train, a minimum CRE recirculation flowrate is established from the CRE area to the iodine filtration train, and a positive pressure is maintained in the CRE area relative to the adjacent areas.

Inspections, Tests, Analyses, and Acceptance Criteria

Table 2.6.1-3 lists the CRACS ITAAC.

Table 2.6.1-1—CRACS Equipment Mechanical Design Sheet 1 of 5

Description	Tag Number ⁽¹⁾	Location	ASME AG-1 Code	Function	Seismic Category					
	Fresh Air Intake Trains 30SAB01 and 30SAB04									
Motor Operated Dampers	30SAB01AA002 30SAB04AA002 30SAB11AA001 30SAB11AA003 30SAB11AA004 30SAB14AA001 30SAB14AA003 30SAB14AA004	Safeguard Building 2 Safeguard Building 3	Yes	Open	I					
Electric Heaters	30SAB01AH001 30SAB04AH001	Safeguard Building 2 Safeguard Building 3	Yes	On / Off (based on ambient conditions)	Ι					
Motor Operated Dampers	30SAB01AA003 30SAB04AA003 30SAB01AA004 30SAB04AA004	Safeguard Building 2 Safeguard Building 3	Yes	Close	Ι					
Prefilters	30SAB01AT001 30SAB04AT001	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι					
Manual Dampers	30SAB01AA006 30SAB04AA006	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι					
Motor Operated Dampers	30SAB01AA012 30SAB04AA012	Safeguard Building 2 Safeguard Building 3	Yes	Open	Ι					

Table 2.6.1-1—CRACS Equipment Mechanical Design Sheet 2 of 5

Description	Tag Number ⁽¹⁾	Location	ASME AG-1 Code	Function	Seismic Category
		lodine Filtration 30SAB11 and 30			
Motor Operated Dampers (Recirculation from CRE)	30SAB11AA004 30SAB14AA004	Safeguard Building 2 Safeguard Building 3	Yes	Open	Ι
Motor Operated Dampers	30SAB11AA001 30SAB14AA001	Safeguard Building 2 Safeguard Building 3	Yes	Open	Ι
Electric Heaters	30SAB11AH001 30SAB14AH001	Safeguard Building 2 Safeguard Building 3	Yes	On / Off (based on ambient conditions)	Ι
Prefilters	30SAB11AT001 30SAB14AT001	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι
Upstream HEPA Filters	30SAB11AT002 30SAB14AT002	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι
Carbon Adsorbers	30SAB11AT003 30SAB14AT003	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι
Downstream HEPA Filters	30SAB11AT004 30SAB14AT004	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι
Motor Operated Damper	30SAB11AA003 30SAB14AA003	Safeguard Building 2 Safeguard Building 3	Yes	Open	Ι
Supply Air Fans	30SAB11AN001 30SAB14AN001	Safeguard Building 2 Safeguard Building 3	Yes	Run	Ι
Back draft Dampers	30SAB11AA002 30SAB14AA002	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι

Table 2.6.1-1—CRACS Equipment Mechanical Design Sheet 3 of 5

Description	Tag Number ⁽¹⁾	Location	ASME AG-1 Code	Function	Seismic Category			
Recirculation and Air Conditioning Trains 30SAB01 and 30SAB04								
Manual Dampers (recirculation from CRE)	30SAB01AA009 30SAB04AA009	Safeguard Building 2 Safeguard Building 3	Yes	N/A	I			
Manual Dampers (recirculation from CRE)	30SAB01AA010 30SAB04AA010	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι			
Air Cooling Coils	30SAB01AC001 30SAB04AC001	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι			
Moisture Separators	30SAB01AT004 30SAB04AT004	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι			
Supply Air Fans	30SAB01AN001 30SAB04AN001	Safeguard Building 2 Safeguard Building 3	Yes	Run	Ι			
HEPA Filters	30SAB01AT005 30SAB04AT005	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι			
Back draft Dampers	30SAB01AA011 30SAB04AA011	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι			
	Red	circulation and Air Cor 30SAB02 and 30						
Manual Dampers (recirculation from CRE)	30SAB02AA009 30SAB03AA009	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι			
Manual Dampers (recirculation from CRE)	30SAB02AA010 30SAB03AA010	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι			
Air Cooling Coils	30SAB02AC001 30SAB03AC001	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι			
Moisture Separators	30SAB02AT004 30SAB03AT004	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι			

Table 2.6.1-1—CRACS Equipment Mechanical Design Sheet 4 of 5

Description	Tag Number ⁽¹⁾	Location	ASME AG-1 Code	Function	Seismic Category
Supply Air Fans	30SAB02AN001 30SAB03AN001	Safeguard Building 2 Safeguard Building 3	Yes	Stop	Ι
HEPA Filters	30SAB02AT005 30SAB03AT005	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι
Backdraft Dampers	30SAB02AA011 30SAB03AA011	Safeguard Building 2 Safeguard Building 3	Yes	N/A	Ι
		Kitchen and Sanitar 30SAB45	y Exhaust		
Motor Operated Damper	30SAB45AA003	Safeguard Building 2	Yes	Close	Ι
Silencer	30SAB45BS001	Safeguard Building 2	Yes	N/A	Ι
Manual damper	30SAB45AA005	Safeguard Building 2	Yes	N/A	Ι
Exhaust fan	30SAB45AN001	Safeguard Building 2	Yes	Stop	Ι
Motor Operated Damper	30SAB45AA004	Safeguard Building 2	Yes	Close	Ι
Backdraft damper	30SAB45AA006	Safeguard Building 2	Yes	N/A	Ι
		MCR Air Sup 30SAB32			
Manual Dampers	30SAB32AA001 30SAB32AA002 30SAB32AA003 30SAB32AA006 30SAB32AA013 30SAB32AA015 30SAB32AA017	Safeguard Building 2	Yes	N/A	I



Table 2.6.1-1—CRACS Equipment Mechanical Design
Sheet 5 of 5

Description	Tag Number ⁽¹⁾	Location	ASME AG-1 Code	Function	Seismic Category
Heaters	30SAB32AH001 30SAB32AH002 30SAB32AH003 30SAB32AH004 30SAB32AH005 30SAB32AH006 30SAB32AH006	Safeguard Building 2	Yes	On / Off (based on ambient conditions)	Ι
		MCR Air Exha 30SAB42	lust		
Motor Operated Dampers	30SAB42AA001 30SAB42AA002	Safeguard Building 2	Yes	Open	Ι
Manual Dampers	30SAB42AA006 30SAB42AA009 30SAB42AA011 30SAB42AA012 30SAB42AA014 30SAB42AA016	Safeguard Building 2	Yes	N/A	Ι

1. Equipment tag numbers are provided for information only and are not part of the certified design.

Table 2.6.1-2—CRACS Equipment I&C and Electrical Design Sheet 1 of 5

Description	Tag Number ⁽¹⁾	Location	IEEE Class 1E ⁽²⁾	PACS	MCR / RSS Displays	MCR / RSS Controls
	U	Fresh Air Intake 30SAB01	Train			
Motor Operated Damper	30SAB01AA002	Safeguard Building 2	Division 4 ^N Division 3 ^A	Yes	Position / Position	Open-Close / Open-Close
Electric Heater	30SAB01AH001	Safeguard Building 2	Division 1 ^N	Yes	On-Off / On-Off	Start-Stop / Start-Stop
Motor Operated Damper	30SAB01AA003	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	Position / Position	Open-Close / Open-Close
Motor Operated Damper	30SAB01AA012	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	Position / Position	Open-Close / Open-Close
Motor Operated Damper	30SAB01AA004	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	Position / Position	Open-Close / Open-Close
	-	Fresh Air Intake 30SAB04	Train			
Motor Operated Damper	30SAB04AA002	Safeguard Building 3	Division 1 ^N Division 2 ^A	Yes	Position / Position	Open-Close / Open-Close
Electric Heater	30SAB04AH001	Safeguard Building 3	Division 4 ^N	Yes	On-Off / On-Off	Start-Stop / Start-Stop
Motor Operated Damper	30SAB04AA003	Safeguard Building 2	Division 4 ^N Division 3 ^A	Yes	Position / Position	Open-Close / Open-Close
Motor Operated Damper	30SAB04AA012	Safeguard Building 3	Division 4 ^N Division 3 ^A	Yes	Position / Position	Open-Close / Open-Close

Table 2.6.1-2—CRACS Equipment I&C and Electrical Design Sheet 2 of 5

Description	Tag Number ⁽¹⁾	Location	IEEE Class 1E ⁽²⁾	PACS	MCR / RSS Displays	MCR / RSS Controls
Motor Operated Damper	30SAB04AA004	Safeguard Building 3	Division 4 ^N Division 3 ^A	Yes	Position / Position	Open-Close / Open-Close
		Iodine Filtration 30SAB11	Train			
Motor Operated Damper (Recirculation from CRE)	30SAB11AA004	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	Position / Position	Open-Close / Open-Close
Motor Operated Damper	30SAB11AA001	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	Position / Position	Open-Close / Open-Close
Electric Heater	30SAB11AH001	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	On-Off / On-Off	Start-Stop / Start-Stop
Motor Operated Damper	30SAB11AA003	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	Position / Position	Open-Close / Open-Close
Supply Air Fan	30SAB11AN001	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	On-Off / On-Off	Run-Stop / Run-Stop
		Iodine Filtration 30SAB14	Train			
Motor Operated Damper (Recirculation from CRE)	30SAB14AA004	Safeguard Building 3	Division 4 ^N Division 3 ^A	Yes	Position / Position	Open-Close / Open-Close
Motor Operated Damper	30SAB14AA001	Safeguard Building 3	Division 4 ^N Division 3 ^A	Yes	Position / Position	Open-Close / Open-Close
Electric Heater	30SAB14AH001	Safeguard Building 3	Division 4 ^N Division 3 ^A	Yes	On-Off / On-Off	Start-Stop / Start-Stop

Table 2.6.1-2—CRACS Equipment I&C and Electrical Design
Sheet 3 of 5

Description	Tag Number ⁽¹⁾	Location	IEEE Class 1E ⁽²⁾	PACS	MCR / RSS Displays	MCR / RSS Controls
Motor Operated Damper	30SAB14AA003	Safeguard Building 2	Division 4 ^N Division 3 ^A	Yes	Position / Position	Open-Close / Open-Close
Supply Air Fan	30SAB14AN001	Safeguard Building 3	Division 4 ^N Division 3 ^A	Yes	On-Off / On-Off	Run-Stop / Run-Stop
	Rec	irculation and Air Con 30SAB01	ditioning Trai	n		
Supply Air Fan	30SAB01AN001	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	On-Off / On-Off	Run-Stop / Run-Stop
	Rec	irculation and Air Con 30SAB02	ditioning Trai	n	<u> </u>	
Supply Air Fan	30SAB02AN001	Safeguard Building 2	Division 2 ^N	Yes	On-Off / On-Off	Run-Stop / Run-Stop
	Rec	irculation and Air Con 30SAB03	ditioning Trai	n	· · · ·	
Supply Air Fan	30SAB03AN001	Safeguard Building 3	Division 3 ^N	Yes	On-Off / On-Off	Run-Stop / Run-Stop
	Rec	irculation and Air Con 30SAB04	ditioning Trai	n	<u> </u>	
Supply Air Fan	30SAB04AN001	Safeguard Building 3	Division 4 ^N Division 3 ^A	Yes	On-Off / On-Off	Run-Stop / Run-Stop
	1	Kitchen and Sanitary 30SAB45	/ Exhaust		1 1	
Motor Operated Damper	30SAB45AA003	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	Position / Position	Open-Close / Open-Close

Table 2.6.1-2—CRACS Equipment I&C and Electrical Design Sheet 4 of 5

Description	Tag Number ⁽¹⁾	Location	IEEE Class 1E ⁽²⁾	PACS	MCR / RSS Displays	MCR / RSS Controls
Motor Operated Damper	30SAB45AA004	Safeguard Building 2	Division 4 ^N Division 3 ^A	Yes	Position / Position	Open-Close / Open-Close
		MCR Air Exha 30SAB42				
Motor Operated Damper	30SAB42AA001	Safeguard Building 2	Division 1 ^N Division 2 ^A	Yes	Position / Position	Open-Close / Open-Close
Motor Operated Damper	30SAB42AA002	Safeguard Building 2	Division 4 ^N Division 3 ^A	Yes	Position / Position	Open-Close / Open-Close
	L	Instruments	5		1	
Differential Pressure across 30SAB11 Iodine Train Filters	30SAB11CP001	Safeguard Building 2	N/A	N/A	Press / Press	N/A
Differential Pressure across 30SAB14 Iodine Train Filters	30SAB14CP001	Safeguard Building 3	N/A	N/A	Press / Press	N/A
Differential Pressure between Main Control Room and Adjacent Rooms	30SAB32CP001 30SAB32CP002 30SAB32CP003	Safeguard Building 2	N/A	N/A	Press / Press	N/A
Iodine Filtration Train Flow	30SAB11CF001 30SAB14CF001	Safeguard Building 2 Safeguard Building 3	N/A	N/A	Flow / Flow	N/A
Protective Switch-off Temperature for Electric Heaters	30SAB01CT002 30SAB04CT002	Safeguard Building 2 Safeguard Building 3	N/A	N/A	Temp / Temp	N/A
Temperature Downstream of Electric Heaters	30SAB01CT003/004 30SAB04CT003/004	Safeguard Building 2 Safeguard Building 3	N/A	N/A	Temp / Temp	N/A
Main Control Room Temperature	30SAB32CT002 30SAB32CT003	Safeguard Building 2	N/A	N/A	Temp / Temp	N/A



Table 2.6.1-2—CRACS Equipment I&C and Electrical Design Sheet 5 of 5

Description	Tag Number ⁽¹⁾	Location	IEEE Class 1E ⁽²⁾	PACS	MCR / RSS Displays	MCR / RSS Controls
Temperature Downstream of Iodine Train Heaters	30SAB11CT002 30SAB14CT002	Safeguard Building 2 Safeguard Building 3	N/A	N/A	Temp / Temp	N/A
Temperature Upstream of Iodine Train Heaters	30SAB11CT001 30SAB14CT001	Safeguard Building 2 Safeguard Building 3	N/A	N/A	Temp / Temp	N/A
Temperature Upstream of Electric Heaters	30SAB01CT001 30SAB04CT001	Safeguard Building 2 Safeguard Building 3	N/A	N/A	Temp / Temp	N/A
Temperature Downstream of Carbon Adsorber	30SAB11CT003 30SAB14CT003	Safeguard Building 2 Safeguard Building 3	N/A	N/A	Temp / Temp	N/A
Conditioning Trains Air Flow	30SAB01/02CF001 30SAB03/04CF001	Safeguard Building 2 Safeguard Building 3	N/A	N/A	Flow / Flow	N/A

1. Equipment tag numbers are provided for information only and are not part of the certified design.

2. ^N denotes division the equipment is normally powered from, while ^A denotes division the equipment is powered from when alternate feed is implemented.

Table 2.6.1-3—Main Control Room Air Conditioning System ITAAC
Sheet 1 of 8

	Commitment Wording	Inspections, Tests, Analyses	Acceptance Criteria
2.1	The functional arrangement of the CRACS is as described in the Design Description of Section 2.6.1, Tables 2.6.1-1 and 2.6.1-2, and as shown on Figures 2.6.1-1, 2.6.1-2, and 2.6.1-3.	An inspection of the as-built CRACS functional arrangement will be performed.	The CRACS conforms to the functional arrangement as described in the Design Description of Section 2.6.1, Tables 2.6.1-1 and 2.6.1-2, and as shown on Figures 2.6.1-1, 2.6.1-2, and 2.6.1-3.
2.2	Deleted.	Deleted.	Deleted.
2.3	Physical separation exists between the CRACS fresh air intake, iodine filtration, and recirculation and air conditioning trains as listed in Table 2.6.1-1.	An inspection will be performed to verify that the as-built CRACS fresh air intake, iodine filtration, and recirculation and air conditioning trains are located in separate rooms of Safeguard Buildings 2 and 3.	 The CRACS fresh air intake train 30SAB01, iodine filtration train 30SAB11, and recirculation and air conditioning train 30SAB01 as listed in Table 2.6.1-1 are located in room 2UJK31034 of Safeguard Building 2. The CRACS fresh air intake train 30SAB04, iodine filtration train 30SAB14, and recirculation and air conditioning train 30SAB04 as listed in Table 2.6.1-1 are located in room 2UJK31034 of Safeguard Building 3. The CRACS recirculation and air conditioning train 30SAB02 as listed in Table 2.6.1-1 is located in room 2UJK31035 of Safeguard Building 2. The CRACS recirculation and air conditioning train 30SAB02 as listed in Table 2.6.1-1 is located in room 2UJK31035 of Safeguard Building 2. The CRACS recirculation and air conditioning train 30SAB03 as listed in Table 2.6.1-1 is located in room 2UJK31035 of Safeguard Building 3.
3.1	Deleted.	Deleted.	Deleted.

	Commitment Wording	Inspections, Tests, Analyses	Acceptance Criteria
3.2	Class 1E dampers listed in Table 2.6.1-2 will function to change position as listed in Table 2.6.1-1 under normal operating conditions.	Tests will be performed to verify the ability of Class 1E dampers to change position under normal operating conditions.	Class 1E dampers listed in Table 2.6.1-2 change position as listed in Table 2.6.1-1 under normal operating conditions.
3.3	Equipment identified as Seismic Category I in Table 2.6.1-1 can withstand seismic design basis loads without a loss of the function listed in Table 2.6.1-1.	 a. Type tests, analyses, or a combination of type tests and analyses will be performed on the equipment identified as Seismic Category I in Table 2.6.1-1 using analytical assumptions, or under conditions, which bound the Seismic Category I design requirements. b. An inspection will be performed of the as-built equipment identified as Seismic Category I in Table 2.6.1-1 to verify that the equipment, including anchorage, are installed per the approved design requirements. 	 a. Test/analysis reports conclude that the equipment identified as Seismic Category I in Table 2.6.1-1 can withstand seismic design basis loads without a loss of the function listed in Table 2.6.1-1 including the time required to perform the listed function. b. Inspection reports conclude that the equipment identified as Seismic Category I in Table 2.6.1-1, including anchorage, are installed per the approved design requirements.
3.4	Equipment listed in Table 2.6.1-1 as ASME AG-1 Code are designed in accordance with ASME AG-1 Code requirements.	An analysis will be performed of ASME AG-1 Code Design Verification Reports.	ASME AG-1 Code Design Verification Reports (AA-4400) conclude that the design of equipment listed as ASME AG-1 Code in Table 2.6.1-1 complies with ASME AG-1 Code requirements.
3.5	Equipment listed in Table 2.6.1-1 as ASME AG-1 Code are fabricated in accordance with ASME AG-1 Code requirements, including welding requirements.	An inspection of the as-built fabrication activities and documentation for ASME AG- 1 Code equipment will be conducted.	A report concludes that ASME AG-1 Code equipment listed in Table 2.6.1-1 are fabricated in accordance with ASME AG-1 Code requirements.

Table 2.6.1-3—Main Control Room Air Conditioning System ITAAC
Sheet 2 of 8



-	Increations Tests					
	Commitment Wording Inspections, Tests, Analyses		Acceptance Criteria			
3.6	Equipment listed in Table 2.6.1-1 as ASME AG-1 Code are installed, inspected, and tested in accordance with ASME AG-1 Code requirements.	An inspection of the as-built construction activities and documentation for ASME AG-1 Code equipment will be conducted.	A report concludes that ASME AG-1 Code equipment listed in Table 2.6.1-1 are installed, inspected, and tested in accordance with ASME AG-1 Code requirements.			
4.1	Displays listed in Table 2.6.1-2 are indicated on the PICS operator workstations in the MCR and the RSS.	a. Tests will be performed to verify that the displays listed in Table 2.6.1-2 are indicated on the PICS operator workstations in the MCR by using test input signals to PICS.	a. Displays listed in Table 2.6.1-2 are indicated on the PICS operator workstations in the MCR.			
		b. Tests will be performed to verify that the displays listed in Table 2.6.1-2 are indicated on the PICS operator workstations in the RSS by using test input signals inputs to PICS.	b. Displays listed in Table 2.6.1-2 are indicated on the PICS operator workstations in the RSS.			
4.2	Controls on the PICS operator workstations in the MCR and the RSS perform the function listed in Table 2.6.1-2.	a. Tests will be performed using controls on the PICS operator workstations in the MCR.	a. Controls on the PICS operator workstations in the MCR perform the function listed in Table 2.6.1-2.			
		b. Tests will be performed using controls on the PICS operator workstations in the RSS.	b. Controls on the PICS operator workstations in the RSS perform the function listed in Table 2.6.1-2.			
4.3	Equipment listed as being controlled by a PACS module in Table 2.6.1-2 responds to the state requested and provides drive monitoring signals back to the PACS module. The PACS module will protect the equipment by terminating the output command upon the equipment reaching the requested state.	A test will be performed using test input signals to verify equipment controlled by a PACS module responds to the state requested and provides drive monitoring signals back to the PACS module.	Equipment listed as being controlled by a PACS module in Table 2.6.1-2 responds to the state requested and provides drive monitoring signals back to the PACS module. The PACS module will protect the equipment by terminating the output command upon the equipment reaching the requested state.			

Table 2.6.1-3—Main Control Room Air Conditioning System ITAAC
Sheet 3 of 8



	Commitment Wording	Inspections, Tests, Analyses	Acceptance Criteria	
5.1	Equipment designated as Class 1E in Table 2.6.1-2 are powered from the Class 1E division as listed in Table 2.6.1-2 in a normal or alternate feed condition.	a. Testing will be performed by providing a test input signal in each normally aligned division.	a. The test input signal provided in the normally aligned division is present at the respective Class 1E equipment identified in Table 2.6.1-2.	
		 b. Testing will be performed by providing a test input signal in each division with the alternate feed aligned to the divisional pair. 	b. The test input signal provided in each division with the alternate feed aligned to the divisional pair is present at the respective Class 1E equipment identified in Table 2.6.1-2.	
5.2	Deleted.	Deleted.	Deleted.	
6.1	The CRACS maintains a positive pressure in the CRE area relative to the outside environment and adjacent areas, while operating in a design basis accident alignment.	A test will be performed using test input signals to verify that the CRACS maintains a positive pressure in the CRE area relative to the outside environment and adjacent areas, while operating in a design basis accident alignment.		

Table 2.6.1-3—Main Control Room Air Conditioning System ITAAC Sheet 4 of 8

	Commitment Wording	Inspections, Tests, Analyses	Acceptance Criteria
6.2	Upon receipt of a containment isolation signal, the iodine filtration train will start automatically, outside air supply to the CRE area is diverted through the iodine filtration train, a minimum recirculation flowrate is established from the CRE area to the iodine filtration train and a positive pressure is maintained in the CRE area relative to the adjacent areas.	a. A test will be performed to verify, upon receipt of a containment isolation test input signal, that the iodine filtration train will start automatically; and the outside air supply to the CRE area is diverted through the iodine filtration train. A test will be performed separately for each iodine filtration train using test input signals.	a. Upon receipt of a containment isolation test input signal from the PACS module, the iodine filtration trains start automatically within 60 seconds and the outside air supply to the CRE area is diverted through the iodine filtration train.
		b. A test will be performed to verify that upon receipt of a containment isolation test input signal, a minimum recirculation flowrate is established from the CRE area to the iodine filtration train. A test will be performed separately for each iodine filtration train using test input signals.	b. Upon receipt of a containment isolation test input signal from the PACS module, a recirculation flowrate of greater than or equal to 3000 scfm is established from the CRE area to the iodine filtration train.
		c. A test will be performed using test input signals to verify that upon receipt of a containment isolation test input signal, the CRACS maintains a positive pressure in the CRE area relative to the adjacent areas.	c. Upon receipt of a containment isolation test input signal from the PACS module, the CRACS maintains a pressure of greater than or equal to 0.125 inches water gauge in the CRE area relative to the adjacent areas.
6.3	Deleted.	Deleted.	Deleted.
6.4	The CRE area ventilation unfiltered air in-leakage is minimized in order to maintain the MCR habitability.	A test will be performed to measure the unfiltered air in-leakage inside the CRE area boundary.	The unfiltered air in-leakage inside the CRE area boundary is less than or equal to 40 scfm.

Table 2.6.1-3—Main Control Room Air Conditioning System ITAAC Sheet 5 of 8



	Commitment Wording	Inspections, Tests, Analyses	Acceptance Criteria
6.5	The CRACS provides cooling to maintain the design temperatures in the CRE area, while operating in a design basis accident alignment.	a. Tests and analysis will be performed to verify the CRACS provides cooling to maintain design temperatures in the CRE area, while operating in a design basis accident alignment.	a. Each CRACS cooling coil is capable of providing design cooling capacity, while operating in a design basis accident alignment.
		b. A test of the CRACS fans will be performed to verify that the design air flow is greater than the approved design requirement.	 b. Each CRACS fan is capable of meeting the design air flow requirements, while operating in a design basis accident alignment.
6.6	The CREF heaters protect the carbon adsorber from high humidity during operation of the CREF unit.	Tests and analysis of the CREF heaters will be performed to verify the CREF heaters protect the carbon adsorber from high humidity during operation of the CREF unit.	The CREF heaters are capable of protecting the carbon adsorber from high humidity during operation of the CREF unit.

Table 2.6.1-3—Main Control Room Air Conditioning System ITAACSheet 6 of 8

	Commitment Wording	Inspections, Tests, Analyses		Acceptance Criteria
6.7	Upon receipt of a high radiation alarm signal in the air intake duct, the iodine filtration train will start automatically, the outside air supply to the CRE area is diverted through the iodine filtration train, a minimum CRE recirculation flowrate is established from the CRE area to the iodine filtration train, and a positive pressure is maintained in the CRE area relative to the adjacent areas.	A test will be performed to verify, upon receipt of high radiation alarm test input signal in the air intake duct, that the iodine filtration train will start automatically; and the outside air supply to the CRE area is diverted through the iodine filtration train. A test will be performed separately for each iodine filtration train using test input signals.		A separate test for each iodine filtration train confirms, upon receipt of high radiation alarm test input signal from the PACS module, that the iodine filtration train will start automatically within 60 seconds after receipt of a test input signal from the PACS module, and the outside air supply is diverted through the iodine filtration train.
		A test will be performed to verify, upon receipt of high radiation alarm test input signal in the air intake duct, that a minimum CRE recirculation flowrate for each iodine filtration train is achieved. A test will be performed separately for each iodine filtration train using test input signals.	Ь.	A separate test for each iodine filtration train confirms, upon receipt of high radiation alarm test input signal from the PACS module, that a CRE recirculation flowrate of greater than or equal to 3,000 scfm is established from the CRE area to the iodine filtration train.
		A test will be performed using test input signals to verify, upon receipt of high radiation alarm test input signal in the air intake duct, that a positive pressure is maintained in the CRE area relative to the adjacent areas. A test will be performed separately for each iodine filtration train using test input signals.	C.	A separate test for each iodine filtration train confirms, upon receipt of high radiation alarm test input signal from the PACS module, that a positive pressure of greater than or equal to 0.125 inches water gauge is maintained in the CRE area relative to the adjacent areas.

Table 2.6.1-3—Main Control Room Air Conditioning System ITAAC Sheet 7 of 8



	Commitment Wording	Inspections, Tests, Analyses	Acceptance Criteria
6.8	The CRACS provides heating to maintain design temperatures in the CRE area, while operating in a design basis accident alignment.	1 ×	Each CRACS air inlet heater is capable of providing design heating capacity to maintain design temperatures in the CRE area, while operating in a design basis accident alignment.

Table 2.6.1-3—Main Control Room Air Conditioning System ITAACSheet 8 of 8