

RO Admin Job Performance Measure "C"

Facility: **Vogle**

Task No: V-LO-TA-63004

Task Title: Determine Tagging Requirements

JPM No: V-NRC-JP-NMP-AD-003-HL17

K/A Reference: G2.2.13 RO 4.1 SRO 4.3

Examinee: _____ NRC Examiner: _____

Facility Evaluator: _____ Date: _____

Method of testing:

Simulated Performance _____ Actual Performance _____

Classroom _____ Simulator _____ Plant _____

Read to the examinee:

I will explain the initial conditions, which steps to simulate or discuss, and provide initiating cues. When you complete the task successfully, the objective for this job performance measure will be satisfied.

Initial Conditions: Unit 1 is at 100% Power. A planned outage for Containment Spray Pump (CSP) Train "A" is required to replace the pump seals.

All electrical components and associated handswitches requiring Tagout for the CSP "A" work are tagged under another referenced Tagout.

All pump motor cooling water required for Tagout for the CSP "A" work are tagged under another referenced Tagout.

Initiating Cue: Determine the appropriate boundary points and required positions of components to isolate the fluid boundary and drain CSP "A", 1-1206-P6-001.

Task Standard: Boundary points for isolation and drains for CSP "A" are determined.

Required Materials: Provide following references to candidate
NMP-AD-003, "Equipment Clearance and Tagging" Ver. 14.0
NMP-AD-003-002 "Tagout Standards" Ver. 7.0
P&ID 1X4DB131 Ver. 35.0
Provide to candidate if requested.
1X4DR003 Ver. 1.0 Fill and Vent Diagram For Containment
Spray System

General References: none

Time Critical Task: No

Validation Time: 45 minutes

Performance Information

Critical steps denoted with an asterisk

References NMP-AD-003, NMP-AD-003-002, and P&ID 1X4DB131.

Standard: Candidate uses references.

Comment:

Determines the following components and positions are required to isolate and drain fluid boundary for CSP A.

Standard:

- Candidate correctly identifies the listed points to tag out CSP as listed below.
- **The ones in BOLD are the critical points.**
- The description should describe valve function.
- The description listed is expected description.
- The lineup description is listed in parentheses.
- The additional drains may be added but are not required.

Component Number	Description	Required Position
1-HV-9001A	CSP A Pump Discharge Isolation Valve (CNMT SPRAY ISO)	CLOSED
1-HV-9017A	CSP A RWST Suction Isolation Valve (CNMT SPRAY PUMP A RWST SUCT ISO VLV)	CLOSED
1-HV-9003A	CSP A CNMT Sump Suction Isolation Valve (CNMT SPRAY PUMP A CNMT SUMP SUCT ORC)	CLOSED
1-1206-U4-115	1HV-9003A Bypass Line Isolation Valve (CNMT SPRAY PUMP TRAIN A SUMP SUPPLY HV 9003A BYP)	CLOSED
1-1206-U4-006	CSP A RWST Test line Isolation Valve (CNMT SPRAY PUMP TRAIN A TEST FLOWPATH ISOLATION)	CLOSED
1-1206-U4-034	CSP A Discharge to Eductor Isolation Valve (CNMT SPRAY SPRAY ADD TK DISCH ISO TO EDUCTOR 1)	CLOSED
1-1206-U4-109	CSP A Pump Casing Drain Valve (CNMT SPRAY PUMP TRAIN A DISCHARGE CASING DRAIN)	OPEN
1-1206-U4-112	CSP A Pump Casing Drain Valve (CNMT SPRAY PUMP TRAIN A SUCTION CASING DRAIN)	OPEN
1-1206-U4-108	CSP A Pump Casing Vent Valve (CNMT SPRAY PUMP TRAIN A CASE VENT)	UNFLANGE/OPEN or UNCAP/OPEN
1-1206-X4-108	CSP A Header Vent Valve (CNMT SPRAY HEADER TRAIN A VENT)	UNCAP/OPEN
1-1206-U4-002	CSP A Suction Drain Valve (CNMT SPRAY PUMP TRAIN A SUCTION FLOOR DRAIN ISO)	OPEN
1-1206-X4-005	CSP A RWST Supply Drain Valve (CNMT SPRAY PUMP TRAIN A RWST SUPPLY DRN TO FLOOR)	OPEN
1-1206-X4-009	CSP A Suction Vent Valve (CNMT SPRAY PUMP TRAIN A SUCTION PRESS TEST ROOT)	OPEN

1-1206-X4-026	CSP A Discharge Drain Valve (CNMT SPRAY PUMP TRAIN A DISCHARGE LINE DRAIN)	UNCAP/OPEN
1-1206-X4-013	CSP A Discharge to Eductor Drain Valve (CNMT SPRAY PUMP TRAIN A DISCHARGE TO EDUCTOR DRN)	OPEN
1-1206-X4-035	CSP A Header Drain Valve (CNMT SPRAY HEADER TRAIN A DRAIN)	OPEN
1-1206-U4-011	CSP A Discharge Flush Conn Isolation (CNMT SPRAY PUMP TRAIN A DISCH FLUSH CONN ISO)	UNFLANGE/OPEN or CLOSED

Comment:

Terminating cue: Candidate informs SS of completion of the identified points to Tagout Containment Spray Pump A or returns the cue sheet.

Verification of Completion

Job Performance Measure No. V-NRC-JP-NMP-AD-003-HL17

Examinee's Name:

Examiner's Name:

Date Performed:

Number of Attempts:

Time to Complete:

Question Documentation:

Question: _____

Response: _____

Result: Satisfactory/Unsatisfactory

Examiner's signature and date: _____

