

ULNRC-05976  
Enclosure 2

**2011 Decommissioning Cost Analysis for the Callaway Energy Center**

**DECOMMISSIONING COST ANALYSIS**  
**for the**  
**CALLAWAY ENERGY CENTER**



*prepared for*




**Ameren Missouri**

*prepared by*

**TLG Services, Inc.**  
**Bridgewater, Connecticut**

**August 2011**

APPROVALS

Project Manager	 _____ William A. Cloutier, Jr.	<u>08/30/2011</u> Date
Project Engineer	 _____ Thomas J. Garrett	<u>08/30/2011</u> Date
Technical Manager	 _____ Francis W. Seymore	<u>8/30/11</u> Date

## TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
EXECUTIVE SUMMARY .....	vii-xvi
1. INTRODUCTION .....	1-1
1.1 Objectives of Study .....	1-1
1.2 Site Description.....	1-1
1.3 Regulatory Guidance .....	1-2
1.3.1 Nuclear Waste Policy Act.....	1-4
1.3.2 Low-Level Radioactive Waste Acts .....	1-5
1.3.3 Radiological Criteria for License Termination.....	1-7
2. DECOMMISSIONING ALTERNATIVES .....	2-1
2.1 DECON.....	2-1
2.1.1 Period 1 - Preparations .....	2-2
2.1.2 Period 2 - Decommissioning Operations.....	2-4
2.1.3 Period 3 - Site Restoration .....	2-7
2.2 SAFSTOR .....	2-8
2.2.1 Period 1 - Preparations .....	2-8
2.2.2 Period 2 - Dormancy.....	2-9
2.2.3 Periods 3 and 4 - Delayed Decommissioning.....	2-10
2.2.4 Period 5 - Site Restoration .....	2-11
3. COST ESTIMATE.....	3-1
3.1 Basis of Estimate .....	3-1
3.2 Methodology .....	3-1
3.3 Financial Components of the Cost Model .....	3-3
3.3.1 Contingency .....	3-3
3.3.2 Financial Risk.....	3-5
3.4 Site-Specific Considerations.....	3-6
3.4.1 Spent Fuel Management.....	3-6
3.4.2 Reactor Vessel and Internal Components .....	3-7
3.4.3 Primary System Components.....	3-8
3.4.4 Retired Components.....	3-10
3.4.5 Main Turbine and Condenser.....	3-10
3.4.6 Transportation Methods .....	3-10
3.4.7 Low-Level Radioactive Waste Disposal.....	3-11
3.4.8 Site Conditions Following Decommissioning .....	3-12

**TABLE OF CONTENTS**  
(continued)

<b><u>SECTION</u></b>	<b><u>PAGE</u></b>
3.5 Assumptions.....	3-13
3.5.1 Estimating Basis .....	3-13
3.5.2 Labor Costs .....	3-13
3.5.3 Design Conditions.....	3-14
3.5.4 General.....	3-14
3.6 Cost Estimate Summary .....	3-16
4. SCHEDULE ESTIMATE .....	4-1
4.1 Schedule Estimate Assumptions .....	4-1
4.2 Project Schedule.....	4-2
5. RADIOACTIVE WASTES .....	5-1
6. RESULTS .....	6-1
7. REFERENCES .....	7-1

**TABLES**

DECON Cost Summary, Decommissioning Cost Elements.....	xv
SAFSTOR Cost Summary, Decommissioning Cost Elements .....	xvi
3.1 DECON Alternative, Schedule of Total Annual Expenditures.....	3-18
3.1a DECON Alternative, Schedule of License Termination Expenditures .....	3-19
3.1b DECON Alternative, Schedule of Spent Fuel Management Expenditures.	3-20
3.1c DECON Alternative, Schedule of Site Restoration Expenditures.....	3-21
3.2 SAFSTOR Alternative, Schedule of Total Annual Expenditures .....	3-22
3.2a SAFSTOR Alternative, Schedule of License Termination Expenditures ....	3-24
3.2b SAFSTOR Alternative, Schd. of Spent Fuel Management Expenditures ...	3-26
3.2c SAFSTOR Alternative, Schedule of Site Restoration Expenditures .....	3-27

**TABLE OF CONTENTS**  
(continued)

**SECTION** **PAGE**

**TABLES**

5.1	DECON Alternative, Decommissioning Waste Summary .....	5-3
5.2	SAFSTOR Alternative, Decommissioning Waste Summary.....	5-4
6.1	DECON Alternative, Decommissioning Cost Elements.....	6-4
6.2	SAFSTOR Alternative, Decommissioning Cost Elements .....	6-5

**FIGURES**

4.1	Activity Schedule .....	4-3
4.2	Decommissioning Timelines .....	4-4

**APPENDICES**

A.	Unit Cost Factor Development.....	A-1
B.	Unit Cost Factor Listing.....	B-1
C.	Detailed Cost Analysis, DECON.....	C-1
D.	Detailed Cost Analysis, SAFSTOR .....	D-1

**REVISION LOG**

<b>No.</b>	<b>CRA No.</b>	<b>Date</b>	<b>Item Revised</b>	<b>Reason for Revision</b>
0		08-30-11		Original Issue

## **EXECUTIVE SUMMARY**

This report presents estimates of the cost to decommission the Callaway Energy Center (Callaway) for the selected decommissioning scenarios following the scheduled cessation of plant operations. The analysis relies upon site-specific, technical information from an evaluation prepared in 2008,<sup>[1]</sup> updated to reflect current assumptions pertaining to the disposition of the nuclear unit and relevant industry experience in undertaking such projects. The current estimates are designed to provide Ameren Missouri with sufficient information to assess its financial obligations, as they pertain to the eventual decommissioning of the nuclear unit. It is not a detailed engineering study, but a financial analysis prepared in advance of the detailed engineering that will be required to carry out the decommissioning.

The currently projected cost to decommission the station, assuming the DECON alternative, is estimated at \$754.5 million, as reported in 2011 dollars. An estimate for the SAFSTOR alternative is also provided.

The estimates are based on numerous fundamental assumptions that consider current regulations, low-level radioactive waste disposal options, spent fuel management requirements, site restoration practices, and project contingencies. The estimates incorporate a minimum cooling period of approximately five and one-half years for the spent fuel that resides in the storage pool when operations cease. During this period, it is assumed the spent fuel will be transferred to an Independent Spent Fuel Storage Installation (ISFSI) located on the Callaway site.

### Alternatives and Regulations

The ultimate objective of the decommissioning process is to reduce the inventory of contaminated and activated material so that the license can be terminated. The Nuclear Regulatory Commission (NRC or Commission) provided initial decommissioning requirements in its rule adopted on June 27, 1988.<sup>[2]</sup> In this rule, the NRC set forth financial criteria for decommissioning licensed nuclear power facilities. The regulations addressed planning needs, timing, funding methods, and environmental review requirements for decommissioning. The rule also defined three decommissioning alternatives as being acceptable to the NRC: DECON, SAFSTOR, and ENTOMB.

---

<sup>1</sup> "Decommissioning Cost Analysis for the Callaway Plant," Document No. A22-1599-002, Rev. 0, TLG Services, Inc., August 2008

<sup>2</sup> U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72 "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018 et seq.), June 27, 1988



DECON is defined as "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations."<sup>[3]</sup>

SAFSTOR is defined as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use."<sup>[4]</sup> Decommissioning is to be completed within 60 years, although longer time periods will be considered when necessary to protect public health and safety.

ENTOMB is defined as "the alternative in which radioactive contaminants are encased in a structurally long-lived material, such as concrete; the entombed structure is appropriately maintained and continued surveillance is carried out until the radioactive material decays to a level permitting unrestricted release of the property."<sup>[5]</sup> As with the SAFSTOR alternative, decommissioning is currently required to be completed within 60 years.

The 60-year restriction has limited the practicality for the ENTOMB alternative at commercial reactors that generate significant amounts of long-lived radioactive material. In 1997, the Commission directed its staff to re-evaluate this alternative and identify the technical requirements and regulatory actions that would be necessary for entombment to become a viable option. The resulting evaluation provided several recommendations; however, rulemaking has been deferred pending the completion of additional research studies, for example, on engineered barriers.

In 1996, the NRC published revisions to the general requirements for decommissioning nuclear power plants to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process.<sup>[6]</sup> The amendments allow for greater public participation

---

<sup>3</sup> Ibid. Page FR24022, Column 3

<sup>4</sup> Ibid.

<sup>5</sup> Ibid. Page FR24023, Column 2

<sup>6</sup> U.S. Code of Federal Regulations, Title 10, Parts 2, 50, and 51, "Decommissioning of Nuclear Power Reactors," Nuclear Regulatory Commission, Federal Register Volume 61, (p 39278 et seq.), July 29, 1996

and better define the transition process from operations to decommissioning. Regulatory Guide 1.184,<sup>[7]</sup> issued in July 2000, further described the methods and procedures acceptable to the NRC staff for implementing the requirements of the 1996 revised rule relating to the initial activities and major phases of the decommissioning process. The costs and schedules presented in this analysis follow the general guidance and processes described in the amended regulations. The format and content of the estimates is also consistent with the recommendations of Regulatory Guide 1.202,<sup>[8]</sup> issued in February 2005.

### Methodology

The methodology used to develop the estimates described within this document follows the basic approach originally presented in the cost estimating guidelines<sup>[9]</sup> developed by the Atomic Industrial Forum (now Nuclear Energy Institute). This reference describes a unit factor method for determining decommissioning activity costs. The unit factors used in this analysis incorporate site-specific costs and the latest available information on worker productivity in decommissioning.

An activity duration critical path is used to determine the total decommissioning program schedule. The schedule is relied upon in calculating the carrying costs, which include program management, administration, field engineering, equipment rental, and support services, such as quality control and security.

### Contingency

Consistent with cost estimating practice, contingencies are applied to the decontamination and dismantling costs developed as "specific provision for unforeseeable elements of cost within the defined project scope, particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur."<sup>[10]</sup> The cost elements in the estimates are based on ideal conditions; therefore, the types of unforeseeable events that are almost certain to occur in decommissioning, based on industry experience, are addressed through a percentage contingency applied on a line-item basis. This contingency factor is a nearly universal element in all large-scale construction and demolition projects. It should be noted that contingency, as used in

---

<sup>7</sup> "Decommissioning of Nuclear Power Reactors," Regulatory Guide 1.184, Nuclear Regulatory Commission, July 2000

<sup>8</sup> "Standard Format and Content of Decommissioning Cost Estimates of Decommissioning Cost Estimates for Nuclear Power Reactors," Regulatory Guide 1.202, U.S. Nuclear Regulatory Commission, February 2005

<sup>9</sup> T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986

<sup>10</sup> Project and Cost Engineers' Handbook, Second Edition, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York, p. 239

this analysis, does not account for price escalation and inflation in the cost of decommissioning over the remaining operating life of the station.

Contingency funds are expected to be fully expended throughout the program. As such, inclusion of contingency is necessary to provide assurance that sufficient funding will be available to accomplish the intended tasks.

### Low-Level Radioactive Waste Disposal

The contaminated and activated material generated in the decontamination and dismantling of a commercial nuclear reactor is classified as low-level (radioactive) waste, although not all of the material is suitable for “shallow-land” disposal. With the passage of the “Low-Level Radioactive Waste Policy Act” in 1980,<sup>[11]</sup> and its Amendments of 1985,<sup>[12]</sup> the states became ultimately responsible for the disposition of low-level radioactive waste generated within their own borders. With the exception of Texas (which has issued a license to Waste Control Specialists for the construction of a new facility in Andrews, Texas), no new compact facilities have been successfully sited, licensed, and constructed.

The disposal facility in Barnwell, South Carolina is currently closed to generators outside the Atlantic Compact (comprising the states of Connecticut, New Jersey and South Carolina). The commercial disposal facility on the Hanford Nuclear Reservation near Richland, Washington accepts low-level radioactive waste from the Northwest (Alaska, Hawaii, Idaho, Montana, Oregon, Utah, Washington and Wyoming) and Rocky Mountain (Colorado, Nevada, and New Mexico) Compact states. This leaves EnergySolutions’ disposal facility in Clive, Utah as the only available option for the disposal of the majority of the low-level radioactive waste generated in decommissioning.

For the purpose of this analysis, Ameren Missouri’s Utilities Service Alliance agreement with EnergySolutions is used as the basis for estimating the disposal cost for the majority of the radioactive waste (Class A <sup>[13]</sup>). EnergySolutions does not have a license to dispose of the more highly radioactive waste (Classes B and C), for example, generated in the dismantling of the reactor vessel. As a proxy, the disposal cost for this material is based upon the last published rate schedule for non-compact waste for the Barnwell facility.

The dismantling of the components residing closest to the reactor core generates radioactive waste considered unsuitable for shallow-land disposal (i.e., low-level

---

<sup>11</sup> “Low-Level Radioactive Waste Policy Act of 1980,” Public Law 96-573, 1980

<sup>12</sup> “Low-Level Radioactive Waste Policy Amendments Act of 1985,” Public Law 99-240, 1986

<sup>13</sup> U.S. Code of Federal Regulations, Title 10, Part 61, “Licensing Requirements for Land Disposal of Radioactive Waste”

radioactive waste with concentrations of radionuclides that exceed the limits established by the NRC for Class C radioactive waste (Greater-than-Class C or GTCC)). The Low-Level Radioactive Waste Policy Amendments Act of 1985 assigned the federal government the responsibility for the disposal of this material. The Act also stated that the beneficiaries of the activities resulting in the generation of such radioactive waste bear all reasonable costs of disposing of such waste. However, to date, the federal government has not identified a cost for disposing of GTCC or a schedule for acceptance.

For purposes of this study, GTCC is packaged in the same canisters used for spent fuel. The GTCC material is assumed to be stored at the ISFSI along with the spent fuel in the DECON scenario. It is shipped directly to a DOE facility as it is generated in the SAFSTOR scenario since it is assumed that the transfer of the spent fuel has been completed prior to the start of the deferred decontamination and dismantling activities.

A significant portion of the waste material generated during decommissioning may only be potentially contaminated by radioactive materials. This waste can be analyzed on site or shipped off site to licensed facilities for further analysis, for processing and/or for conditioning/recovery. Reduction in the volume of low-level radioactive waste requiring disposal in a licensed low-level radioactive waste disposal facility can be accomplished through a variety of methods, including analyses and surveys or decontamination to eliminate the portion of waste that does not require disposal as radioactive waste, compaction, incineration or metal melt. The estimates for Callaway reflect the savings from waste recovery/volume reduction.

### High-Level Radioactive Waste Management

Congress passed the “Nuclear Waste Policy Act”<sup>[14]</sup> (NWPA) in 1982, assigning the federal government’s long-standing responsibility for disposal of the spent nuclear fuel created by the commercial nuclear generating plants to the DOE. The NWPA provided that DOE would enter into contracts with utilities in which DOE would promise to take the utilities’ spent fuel and high-level radioactive waste and utilities would pay the cost of the disposition services for that material. NWPA, along with the individual contracts with the utilities, specified that the DOE was to begin accepting spent fuel by January 31, 1998.

Since the original legislation, the DOE has announced several delays in the program schedule. By January 1998, the DOE had failed to accept any spent fuel or high level waste, as required by the NWPA and utility contracts. Delays continue and, as a

---

<sup>14</sup> “Nuclear Waste Policy Act of 1982 and Amendments,” DOE’s Office of Civilian Radioactive Management, 1982

result, generators have initiated legal action against the DOE in an attempt to obtain compensation for DOE's breach of contract.

In June 2011, Ameren Missouri and the DOE reached an agreement on a settlement. The terms include payment to Ameren Missouri for spent fuel storage and related costs through 2010, and thereafter, annual payment of such costs after they are incurred.

At shutdown, the spent fuel pool is expected to contain freshly discharged assemblies (from the most recent refueling cycles) as well as the final reactor core. Over the following five and one-half years the assemblies are packaged into multipurpose canisters for transfer to the ISFSI. It is assumed that this period provides the necessary cooling for the final core to meet the dry storage system's requirements for decay heat.

The NRC requires that licensees establish a program to manage and provide funding for the management of all irradiated fuel at the reactor site until title of the fuel is transferred to the Secretary of Energy, pursuant to 10 CFR Part 50.54(bb).<sup>[15]</sup> The post-shutdown costs incurred to satisfy this requirement include the isolation and continued operation of the spent fuel pool and the ISFSI during the five and one-half years following the cessation of plant operations.

Costs are also included within the decommissioning estimates for offloading the pool. Cost for the dry storage system, ISFSI construction and/or expansion, and ISFSI operations until such time that the transfer of fuel to the DOE can be completed, are expected to be fully reimbursable and therefore not addressed in this study. The eventual decommissioning of the ISFSI is also not included.

Relocation of the spent fuel from the pool to the ISFSI will allow Ameren Missouri to proceed with decommissioning (or safe-storage preparations) in the shortest time possible.

### Site Restoration

Prompt dismantling of site structures (once the facilities are decontaminated) is clearly the most appropriate and cost-effective option. It is unreasonable to anticipate that these structures would be repaired and preserved after the radiological contamination is removed. The cost to dismantle site structures with a work force already mobilized on site is more efficient than if the process is deferred. Site facilities quickly degrade without maintenance, adding additional expense and

---

<sup>15</sup> U.S. Code of Federal Regulations, Title 10, Part 50, "Domestic Licensing of Production and Utilization Facilities," Subpart 54 (bb), "Conditions of Licenses"

creating potential hazards to the public and the demolition work force. Consequently, this study assumes that site structures are removed to a nominal depth of three feet below the local grade level wherever possible. The site is then to be graded and stabilized.

### Summary

The costs to decommission Callaway assume the removal of all contaminated and activated plant components and structural materials such that the owner may then have unrestricted use of the site with no further requirements for an operating license. Low-level radioactive waste, other than GTCC waste, is sent to a commercial processor for treatment/conditioning or to a controlled disposal facility.

Decommissioning is accomplished within the 60-year period required by current NRC regulations. Regardless of the timing of the decommissioning activities, the estimates assume the eventual removal of all the contaminated and activated plant components and structural materials, such that the facility operator may then have unrestricted use of the site with no further requirement for an operating license.

The decommissioning scenarios are described in Section 2. The assumptions are presented in Section 3, along with schedules of annual expenditures. The major cost contributors are identified in Section 6, with detailed activity costs, waste volumes, and associated manpower requirements delineated in Appendices C and D. The major cost components are also identified in the cost summary provided at the end of this section.

The cost elements in the estimates are assigned to one of three subcategories: NRC License Termination, Spent Fuel Management, and Site Restoration. The subcategory “NRC License Termination” is used to accumulate costs that are consistent with “decommissioning” as defined by the NRC in its financial assurance regulations (i.e., 10 CFR Part 50.75). The cost reported for this subcategory is generally sufficient to terminate the unit’s operating license, recognizing that there may be some additional cost impact from spent fuel management.

The “Spent Fuel Management” subcategory contains costs associated with the transfer of the spent fuel to the ISFSI as well as the operation of the spent fuel pool until such time that the transfer is complete.

“Site Restoration” is used to capture costs associated with the dismantling and demolition of buildings and facilities demonstrated to be free from contamination. This includes structures never exposed to radioactive materials, as well as those facilities that have been decontaminated to appropriate levels. Structures are removed to a depth of three feet and backfilled to conform to local grade.

It should be noted that the costs assigned to these subcategories are allocations. Delegation of cost elements is for the purposes of comparison (e.g., with NRC financial guidelines) or to permit specific financial treatment (e.g., Asset Retirement Obligation determinations). In reality, there can be considerable interaction between the activities in the three subcategories. For example, an owner may decide to remove non-contaminated structures early in the project to improve access to highly contaminated facilities or plant components. In these instances, the non-contaminated removal costs could be reassigned from Site Restoration to an NRC License Termination support activity. However, in general, the allocations represent a reasonable accounting of those costs that can be expected to be incurred for the specific subcomponents of the total estimated program cost, if executed as described.

As noted within this document, the estimates were developed and costs are presented in 2011 dollars. As such, the estimates do not reflect the escalation of costs (due to inflationary and market forces) over the remaining operating life of the reactor or during the decommissioning period.

**DECON COST SUMMARY**  
**DECOMMISSIONING COST ELEMENTS**  
(thousands of 2011 dollars)

Cost Element	Cost
Decontamination	18,215
Removal	161,612
Packaging	24,658
Transportation	13,787
Waste Disposal	65,642
Off-site Waste Processing	25,465
Program Management <sup>[1]</sup>	272,613
Security	44,414
Corporate Allocations	40,691
Spent Fuel Pool Isolation	11,822
Spent Fuel Management - Direct Costs <sup>[2]</sup>	33,726
Insurance and Regulatory Fees	11,565
Energy	4,901
Characterization and Licensing Surveys	15,843
Property Taxes	2,595
Miscellaneous Equipment	6,948
<b>Total <sup>[3]</sup></b>	<b>754,498</b>

Cost Element	Cost
License Termination	617,324
Spent Fuel Management	33,726
Site Restoration	103,448
<b>Total <sup>[3]</sup></b>	<b>754,498</b>

<sup>[1]</sup> Includes engineering costs

<sup>[2]</sup> Direct costs only. Excludes program management costs (staffing) but includes costs for spent fuel loading/ spent fuel pool O&M and Emergency Planning fees

<sup>[3]</sup> Columns may not add due to rounding



**SAFSTOR COST SUMMARY  
DECOMMISSIONING COST ELEMENTS**  
(thousands of 2011 dollars)

Cost Element	Cost
Decontamination	16,286
Removal	162,821
Packaging	18,857
Transportation	10,639
Waste Disposal	47,737
Off-site Waste Processing	27,479
Program Management <sup>[1]</sup>	364,227
Security	156,821
Corporate Allocations	55,341
Spent Fuel Pool Isolation	11,822
Spent Fuel Management <sup>[2]</sup>	33,726
Insurance and Regulatory Fees	53,557
Energy	10,144
Characterization and Licensing Surveys	17,246
Property Taxes	18,943
Miscellaneous Equipment	20,738
<b>Total <sup>[3]</sup></b>	<b>1,026,384</b>

Cost Element	Cost
License Termination	849,173
Spent Fuel Management <sup>[4]</sup>	73,749
Site Restoration	103,462
<b>Total <sup>[3]</sup></b>	<b>1,026,384</b>

- <sup>[1]</sup> Includes engineering costs
- <sup>[2]</sup> Direct costs only. Excludes program management costs (staffing) but includes costs for spent fuel loading/spent fuel pool O&M and Emergency Planning fees
- <sup>[3]</sup> Columns may not add due to rounding
- <sup>[4]</sup> Includes percentage of Period 2a (dormancy) plant operating costs until spent fuel pool is emptied, in addition to the direct costs.

## **1. INTRODUCTION**

This report presents estimates of the costs to decommission the Callaway Energy Center (Callaway) following a scheduled cessation of plant operations. The analysis relies upon site-specific, technical information from an earlier evaluation prepared in 2008,<sup>[1]\*</sup> updated to reflect current assumptions pertaining to the disposition of the nuclear unit and relevant industry experience in undertaking such projects. The supporting analysis was designed to provide Ameren Missouri with sufficient information to assess its financial obligations, as they pertain to the eventual decommissioning of the nuclear station. It is not a detailed engineering document, but a financial analysis prepared in advance of the detailed engineering that will be required to carry out the decommissioning.

### **1.1 OBJECTIVES OF STUDY**

The objectives of this study were to prepare comprehensive estimates of the costs to decommission Callaway, to provide a sequence or schedule for the associated activities, and to develop waste stream projections from the decontamination and dismantling activities.

An operating license was issued for Callaway in 1984 for a 40 year operating period. Ameren Missouri has informed the NRC of their intent to submit a license renewal application in the fourth quarter of 2011 (for an additional 20 years of operation). However, for the purposes of this study, the final shutdown date (license expiration) is projected to be October of 2024, based upon the current (40 year) license. This date was used as input to scheduling the decommissioning activities.

### **1.2 SITE DESCRIPTION**

The nuclear unit is located in Callaway County, Missouri, approximately 80 miles west of the St. Louis metropolitan area. The nearest population center is Jefferson City, 25 miles west-southwest of the plant site. The station is an 1,171 MWe (net design electrical rating) pressurized water reactor with supporting facilities.

Westinghouse Electric Company designed the nuclear steam supply system (NSSS). The NSSS consists of a pressurized water reactor with four independent primary coolant loops, each of which contains a reactor coolant pump and a steam generator. An electrically heated pressurizer and

---

\* References provided in Section 7 of the document

connecting piping complete the system. The NSSS is rated at a thermal power level of 3,579 MWt (3,565 MWt reactor core plus 14 MWt for reactor coolant pumps), with a corresponding turbine-generator gross output of 1284 MWe. The system is housed within a containment structure, a pre-stressed, post-tensioned concrete structure with cylindrical wall, a hemispherical dome, and a flat foundation slab. The wall and dome form a pre-stressed post-tensioned system. The inside surface of the structure is covered with a carbon steel liner, providing a leak tight membrane.

A power conversion system converts heat produced in the reactor to electrical energy. This system converts the thermal energy of the steam into mechanical shaft power and then into electrical energy. The turbine-generator is a tandem-compound, six-flow, four element, 1800-rpm unit. The unit consists of one high pressure and three low-pressure turbine elements driving a directly coupled generator. The turbine is operated in a closed feedwater cycle that condenses the steam; the feedwater is returned to the steam generators. Heat rejected in the main condensers is removed by the circulating water system.

The circulating water system supplies cooling water to the main condenser, condensing the steam exhausted from the turbine. Cooling for the condenser circulating water system is supplied by a large natural draft cooling tower. Makeup water for the cooling tower is drawn from the Missouri River.

### **1.3 REGULATORY GUIDANCE**

The Nuclear Regulatory Commission (NRC or Commission) provided initial decommissioning requirements in its rule "General Requirements for Decommissioning Nuclear Facilities," issued in June 1988.<sup>[2]</sup> This rule set forth financial criteria for decommissioning licensed nuclear power facilities. The regulation addressed decommissioning planning needs, timing, funding methods, and environmental review requirements. The intent of the rule was to ensure that decommissioning would be accomplished in a safe and timely manner and that adequate funds would be available for this purpose. Subsequent to the rule, the NRC issued Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors,"<sup>[3]</sup> which provided additional guidance to the licensees of nuclear facilities on the financial methods acceptable to the NRC staff for complying with the requirements of the rule. The regulatory guide addressed the funding requirements and provided guidance on the content and form of the financial assurance mechanisms indicated in the rule.

The rule defined three decommissioning alternatives as being acceptable to the NRC: DECON, SAFSTOR, and ENTOMB. The DECON alternative assumes

that any contaminated or activated portion of the plant's systems, structures and facilities are removed or decontaminated to levels that permit the site to be released for unrestricted use shortly after the cessation of plant operations. The rule also placed limits on the time allowed to complete the decommissioning process. For SAFSTOR, the process is restricted in overall duration to 60 years, unless it can be shown that a longer duration is necessary to protect public health and safety. The guidelines for ENTOMB are similar, providing the NRC with both sufficient leverage and flexibility to ensure that these deferred options are only used in situations where it is reasonable and consistent with the definition of decommissioning. At the conclusion of a 60-year dormancy period (or longer for ENTOMB if the NRC approves such a case), the site would still require significant remediation to meet the unrestricted release limits for license termination.

The ENTOMB alternative has not been viewed as a viable option for power reactors due to the significant time required to isolate the long-lived radionuclides for decay to permissible levels. However, with rulemaking permitting the controlled release of a site,<sup>[4]</sup> the NRC has re-evaluated this alternative. The resulting feasibility study, based upon an assessment by Pacific Northwest National Laboratory, concluded that the method did have conditional merit for some, if not most reactors. However, the staff also found that additional rulemaking would be needed before this option could be treated as a generic alternative. The NRC had considered rulemaking to alter the 60-year time for completing decommissioning and to clarify the use of engineered barriers for reactor entombments.<sup>[5]</sup>

The NRC's staff has recommended that rulemaking be deferred, based upon several factors, e.g., no licensee has committed to pursuing the entombment option, and the NRC's current priorities, at least until after the additional research studies are complete. The Commission concurred with the staff's recommendation.

In 1996, the NRC published revisions to the general requirements for decommissioning nuclear power plants.<sup>[6]</sup> When the decommissioning regulations were adopted in 1988, it was assumed that the majority of licensees would decommission at the end of the facility's operating licensed life. Since that time, several licensees permanently and prematurely ceased operations. Exemptions from certain operating requirements were required once the reactor was defueled to facilitate the decommissioning. Each case was handled individually, without clearly defined generic requirements. The NRC amended the decommissioning regulations in 1996 to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process. The amendments allow for greater

public participation and better define the transition process from operations to decommissioning.

Under the revised regulations, licensees will submit written certification to the NRC within 30 days after the decision to cease operations. Certification will also be required once the fuel is permanently removed from the reactor vessel. Submittal of these notices will entitle the licensee to a fee reduction and eliminate the obligation to follow certain requirements needed only during operation of the reactor. Within two years of submitting notice of permanent cessation of operations, the licensee is required to submit a Post-Shutdown Decommissioning Activities Report (PSDAR) to the NRC. The PSDAR describes the planned decommissioning activities, the associated sequence and schedule, and an estimate of expected costs. Prior to completing decommissioning, the licensee is required to submit an application to the NRC to terminate the license, which will include a license termination plan (LTP).

### 1.3.1 Nuclear Waste Policy Act

Congress passed the “Nuclear Waste Policy Act”<sup>[7]</sup> (NWPA) in 1982, assigning the federal government’s long-standing responsibility for disposal of the spent nuclear fuel created by the commercial nuclear generating plants to the U.S. Department of Energy (DOE). The NWPA provided that DOE would enter into contracts with utilities in which DOE would promise to take the utilities’ spent fuel and high-level radioactive waste and utilities would pay the cost of the disposition services for that material. NWPA, along with the individual contracts with the utilities, specified that the DOE was to begin accepting spent fuel by January 31, 1998.

Since the original legislation, the DOE has announced several delays in the program schedule. By January 1998, the DOE had failed to accept any spent fuel or high level waste, as required by the NWPA and utility contracts. Delays continue and, as a result, generators have initiated legal action against the DOE in an attempt to obtain compensation for DOE’s breach of contract.

In June 2011, Ameren Missouri and the DOE reached an agreement. The terms include payment to Ameren Missouri for spent fuel storage and related costs through 2010, and thereafter, annual payment of such costs after they are incurred.

At shutdown, the spent fuel pool is expected to contain freshly discharged assemblies (from the most recent refueling cycles) as well as the final

reactor core. Over the following five and one-half years the assemblies are packaged into multipurpose canisters for transfer to the Independent Spent Fuel Storage Installation (ISFSI). It is assumed that this period provides the necessary cooling for the final core to meet the dry storage system's requirements for decay heat.

The NRC requires that licensees establish a program to manage and provide funding for the management of all irradiated fuel at the reactor site until title of the fuel is transferred to the Secretary of Energy, pursuant to 10 CFR Part 50.54(bb).<sup>[8]</sup> The post-shutdown costs incurred to satisfy this requirement include the isolation and continued operation of the spent fuel pool and the ISFSI during the five and one-half years following the cessation of plant operations.

Costs are also included within the decommissioning estimates for offloading the pool. Cost for the dry storage system, ISFSI construction and/or expansion, and ISFSI operations until such time that the transfer of fuel to the DOE can be completed, are expected to be fully reimbursable and therefore not addressed in this study. The eventual decommissioning of the ISFSI is also not included.

Relocation of the spent fuel from the pool to the ISFSI will allow Ameren Missouri to proceed with decommissioning (or safe-storage preparations) in the shortest time possible.

### 1.3.2 Low-Level Radioactive Waste Acts

The contaminated and activated material generated in the decontamination and dismantling of a commercial nuclear reactor is classified as low-level (radioactive) waste, although not all of the material is suitable for "shallow-land" disposal. With the passage of the "Low-Level Radioactive Waste Policy Act" in 1980,<sup>[9]</sup> and its Amendments of 1985,<sup>[10]</sup> the states became ultimately responsible for the disposition of low-level radioactive waste generated within their own borders.

The disposal facility in Barnwell, South Carolina is currently closed to generators outside the Atlantic Compact (comprising the states of Connecticut, New Jersey and South Carolina). The commercial disposal facility on the Hanford Nuclear Reservation near Richland, Washington accepts low-level radioactive waste from the Northwest (Alaska, Hawaii, Idaho, Montana, Oregon, Utah, Washington and Wyoming) and Rocky Mountain (Colorado, Nevada, and New Mexico) Compact states. This

leaves EnergySolutions' disposal facility in Clive, Utah as the only available option for the disposal of the majority of the low-level radioactive waste generated in decommissioning.

For the purpose of this analysis, Ameren Missouri's Utilities Service Alliance agreement with EnergySolutions is used as the basis for estimating the disposal cost for the majority of the radioactive waste (Class A<sup>[11]</sup>). EnergySolutions does not have a license to dispose of the more highly radioactive waste (Class B and C), for example, generated in the dismantling of the reactor vessel. As a proxy, the disposal cost for this material is based upon the last published rate schedule for non-compact waste for the Barnwell facility.

The dismantling of the components residing closest to the reactor core generates radioactive waste considered unsuitable for shallow land disposal (i.e., low-level radioactive waste with concentrations of radionuclides that exceed the limits established by the NRC for Class C radioactive waste (Greater-than-Class C or GTCC)). The Low-Level Radioactive Waste Policy Amendments Act of 1985 assigned the federal government the responsibility for the disposal of this material. The Act also stated that the beneficiaries of the activities resulting in the generation of such radioactive waste bear all reasonable costs of disposing of such waste. However, to date, the federal government has not identified a cost for disposing of GTCC or a schedule for acceptance.

For purposes of this study, GTCC is packaged in the same canisters used for spent fuel. The GTCC material is assumed to be stored at the ISFSI along with the spent fuel in the DECON scenario. It is shipped directly to a DOE facility as it is generated in the SAFSTOR scenario since it is assumed that the transfer of the spent fuel has been completed prior to the start of the deferred decontamination and dismantling activities.

A significant portion of the waste material generated during decommissioning may only be potentially contaminated by radioactive materials. This waste can be analyzed on site or shipped off site to licensed facilities for further analysis, for processing and/or for conditioning/recovery. Reduction in the volume of low-level radioactive waste requiring disposal in a licensed low-level radioactive waste disposal facility can be accomplished through a variety of methods, including analyses and surveys or decontamination to eliminate the portion of waste that does not require disposal as radioactive waste, compaction, incineration or metal melt. The estimates for Callaway reflect the savings from waste recovery/volume reduction.

### 1.3.3 Radiological Criteria for License Termination

In 1997, the NRC published Subpart E, “Radiological Criteria for License Termination,”<sup>[12]</sup> amending 10 CFR Part 20. This subpart provides radiological criteria for releasing a facility for unrestricted use. The regulation states that the site can be released for unrestricted use if radioactivity levels are such that the average member of a critical group would not receive a Total Effective Dose Equivalent (TEDE) in excess of 25 millirem per year, and provided that residual radioactivity has been reduced to levels that are As Low As Reasonably Achievable (ALARA). The decommissioning estimates assume that the Callaway site will be remediated to a residual level consistent with the NRC-prescribed level.

It should be noted that the NRC and the Environmental Protection Agency (EPA) differ on the amount of residual radioactivity considered acceptable in site remediation. The EPA has two limits that apply to radioactive materials. An EPA limit of 15 millirem per year is derived from criteria established by the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA or Superfund).<sup>[13]</sup> An additional and separate limit of 4 millirem per year, as defined in 40 CFR §141.16, is applied to drinking water.<sup>[14]</sup>

On October 9, 2002, the NRC signed an agreement with the EPA on the radiological decommissioning and decontamination of NRC-licensed sites. The Memorandum of Understanding (MOU)<sup>[15]</sup> provides that EPA will defer exercise of authority under CERCLA for the majority of facilities decommissioned under NRC authority. The MOU also includes provisions for NRC and EPA consultation for certain sites when, at the time of license termination, (1) groundwater contamination exceeds EPA-permitted levels; (2) NRC contemplates restricted release of the site; and/or (3) residual radioactive soil concentrations exceed levels defined in the MOU.

The MOU does not impose any new requirements on NRC licensees and should reduce the involvement of the EPA with NRC licensees who are decommissioning. Most sites are expected to meet the NRC criteria for unrestricted use, and the NRC believes that only a few sites will have groundwater or soil contamination in excess of the levels specified in the MOU that trigger consultation with the EPA. However, if there are other hazardous materials on the site, the EPA may be involved in the cleanup. As such, the possibility of dual regulation remains for certain licensees. The present study does not include any costs for this occurrence.



## **2. DECOMMISSIONING ALTERNATIVES**

Detailed cost estimates were developed to decommission the Callaway nuclear unit for the approved decommissioning alternatives: DECON and SAFSTOR. Although the alternatives differ with respect to technique, process, cost, and schedule, they attain the same result: the ultimate release of the site for unrestricted use.

The following sections describe the basic activities associated with each alternative. Although detailed procedures for each activity identified are not provided, and the actual sequence of work may vary, the activity descriptions provide a basis not only for estimating but also for the expected scope of work, i.e., engineering and planning at the time of decommissioning.

The conceptual approach that the NRC has described in its regulations divides decommissioning into three phases. The initial phase commences with the effective date of permanent cessation of operations and involves the transition of both plant and licensee from reactor operations (i.e., power production) to facility de-activation and closure. During the first phase, notification is to be provided to the NRC certifying the permanent cessation of operations and the removal of fuel from the reactor vessel. The licensee is then prohibited from reactor operation.

The second phase encompasses activities during the storage period or during major decommissioning activities, or a combination of the two. The third phase pertains to the activities involved in license termination. The decommissioning estimates developed for Callaway are also divided into phases or periods; however, demarcation of the phases is based upon major milestones within the project or significant changes in the projected expenditures.

### **2.1 DECON**

The DECON alternative, as defined by the NRC, is "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations." This study does not address the cost to dispose of the spent fuel residing at the site; such costs are funded through a surcharge on electrical generation. The study also assumes that the costs incurred with the interim on-site storage of the fuel, pending shipment by the DOE to an off-site disposal facility, are fully reimbursable.

### 2.1.1 Period 1 - Preparations

In anticipation of the cessation of plant operations, detailed preparations are undertaken to provide a smooth transition from plant operations to site decommissioning. Through implementation of a staffing transition plan, the organization required to manage the intended decommissioning activities is assembled from available plant staff and outside resources. Preparations include the planning for permanent defueling of the reactor, revision of technical specifications applicable to the operating conditions and requirements, a characterization of the facility and major components, and the development of the PSDAR.

#### Engineering and Planning

The PSDAR, required within two years of the notice to cease operations, provides a description of the licensee's planned decommissioning activities, a timetable, and the associated financial requirements of the intended decommissioning program. Upon receipt of the PSDAR, the NRC will make the document available to the public for comment in a local hearing to be held in the vicinity of the reactor site. Ninety days following submittal and NRC receipt of the PSDAR, the licensee may begin to perform major decommissioning activities under a modified 10 CFR §50.59 procedure, i.e., without specific NRC approval. Major activities are defined as any activity that results in permanent removal of major radioactive components, permanently modifies the structure of the containment, or results in dismantling components (for shipment) containing GTCC, as defined by 10 CFR §61. Major components are further defined as comprising the reactor vessel and internals, large bore reactor coolant system piping, and other large components that are radioactive. The NRC includes the following additional criteria for use of the §50.59 process in decommissioning. The proposed activity must not:

- foreclose release of the site for possible unrestricted use,
- significantly increase decommissioning costs,
- cause any significant environmental impact, or
- violate the terms of the licensee's existing license.

Existing operational technical specifications are reviewed and modified to reflect plant conditions and the safety concerns associated with permanent cessation of operations. The environmental impact associated with the planned decommissioning activities is also considered.

Typically, a licensee will not be allowed to proceed if the consequences of a particular decommissioning activity are greater than that bounded by previously evaluated environmental assessments or impact statements. In this instance, the licensee would have to submit a license amendment for the specific activity and update the environmental report.

The decommissioning program outlined in the PSDAR will be designed to accomplish the required tasks within the ALARA guidelines (as defined in 10 CFR §20) for protection of personnel from exposure to radiation hazards. It will also address the continued protection of the health and safety of the public and the environment during the dismantling activity. Consequently, with the development of the PSDAR, activity specifications, cost-benefit and safety analyses, work packages and procedures, would be assembled to support the proposed decontamination and dismantling activities.

#### Site Preparations

Following final plant shutdown, and in preparation for actual decommissioning activities, the following activities are initiated:

- Characterization of the site and surrounding environs. This includes radiation surveys of work areas, major components (including the reactor vessel and its internals), internal piping, and primary shield cores.
- Isolation of the spent fuel storage pool and fuel handling systems, such that decommissioning operations can commence on the balance of the plant. The pool will remain operational for approximately five and one-half years following the cessation of operations before the inventory resident at shutdown can be transferred to the ISFSI.
- Specification of transport and disposal requirements for activated materials and/or hazardous materials, including shielding and waste stabilization.
- Development of procedures for occupational exposure control, control and release of liquid and gaseous effluent, processing of radwaste (including dry-active waste, resins, filter media, metallic and non-metallic components generated in decommissioning), site security and emergency programs, and industrial safety.

### 2.1.2 Period 2 - Decommissioning Operations

This period includes the physical decommissioning activities associated with the removal and disposal of contaminated and activated components and structures, including the successful termination of the 10 CFR §50 operating license. Significant decommissioning activities in this phase include:

- Construction of temporary facilities and/or modification of existing facilities to support dismantling activities. This may include a centralized processing area to facilitate equipment removal and component preparations for off-site disposal.
- Reconfiguration and modification of site structures and facilities as needed to support decommissioning operations. This may include the upgrading of roads (on- and off-site) to facilitate hauling and transport. Modifications may be required to the containment structure to facilitate access of large/heavy equipment. Modifications may also be required to the refueling area of the building to support the segmentation of the reactor vessel internals and component extraction.
- Design and fabrication of temporary and permanent shielding to support removal and transportation activities, construction of contamination control envelopes, and the procurement of specialty tooling.
- Procurement (lease or purchase) of shipping canisters, cask liners, and industrial packages for the disposition of low-level radioactive waste.
- Decontamination of components and piping systems as required to control (minimize) worker exposure.
- Removal of piping and components no longer essential to support decommissioning operations.
- Removal of control rod drive housings and the head service structure from the reactor vessel head. Segmentation of the vessel closure head.
- Removal and segmentation of the upper internals assemblies. Segmentation will maximize the loading of the shielded transport casks, i.e., by weight and activity. The operations are conducted under water using remotely operated tooling and contamination controls.

- Disassembly and segmentation of the remaining reactor internals, including the core shroud and lower core support assembly. Some material is expected to exceed Class C disposal requirements. As such, the segments will be packaged in modified fuel storage canisters for geologic disposal.
- Segmentation of the reactor vessel. A shielded platform is installed for segmentation as cutting operations are performed in-air using remotely operated equipment within a contamination control envelope. The water level is maintained just below the cut to minimize the working area dose rates. Segments are transferred in-air to containers that are stored under water, for example, in an isolated area of the refueling canal.
- Removal of the activated portions of the concrete biological shield and accessible contaminated concrete surfaces. If dictated by the steam generator and pressurizer removal scenarios, those portions of the associated cubicles necessary for access and component extraction are removed.
- Removal of the steam generators and pressurizer for material recovery and controlled disposal. The generators will be moved to an on-site processing center, the steam domes removed and the internal components segregated for recycling. The lower shell and tube bundle will be packaged for direct disposal. These components can serve as their own burial containers provided that all penetrations are properly sealed and the internal contaminants are stabilized, e.g., with grout. Steel shielding will be added, as necessary, to those external areas of the package to meet transportation limits and regulations. The pressurizer is disposed of intact.

At least two years prior to the anticipated date of license termination, an LTP is required. Submitted as a supplement to the Final Safety Analysis Report (FSAR) or its equivalent, the plan must include: a site characterization, description of the remaining dismantling activities, plans for site remediation, procedures for the final radiation survey, designation of the end use of the site, an updated cost estimate to complete the decommissioning, and any associated environmental concerns. The NRC will notice the receipt of the plan, make the plan available for public comment, and schedule a local hearing. LTP approval will be subject to any conditions and limitations as deemed appropriate by the Commission. The licensee may then commence with the final remediation of site facilities and services, including:

- Removal of remaining plant systems and associated components as they become nonessential to the decommissioning program or worker health and safety (e.g., waste collection and treatment systems, electrical power and ventilation systems).
- Removal of the steel liners from refueling canal, disposing of the activated and contaminated sections as radioactive waste. Removal of any activated/ contaminated concrete.
- Surveys of the decontaminated areas of the containment structure.
- Remediation and removal of the contaminated equipment and material from the fuel building and any other contaminated facility. Radiation and contamination controls will be utilized until residual levels indicate that the structures and equipment can be released for unrestricted access and conventional demolition. This activity may necessitate the dismantling and disposition of most of the systems and components (both clean and contaminated) located within these buildings. This activity facilitates surface decontamination and subsequent verification surveys required prior to obtaining release for demolition.
- Routing of material removed in the decontamination and dismantling to a central processing area. Material certified to be free of contamination is released for unrestricted disposition, e.g., as scrap, recycle, or general disposal. Contaminated material is characterized and segregated for additional off-site processing (disassembly, chemical cleaning, volume reduction, and waste treatment), and/or packaged for controlled disposal at a low-level radioactive waste disposal facility.

Incorporated into the LTP is the Final Survey Plan. This plan identifies the radiological surveys to be performed once the decontamination activities are completed and is developed using the guidance provided in the “Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM).”<sup>[16]</sup> This document incorporates the statistical approaches to survey design and data interpretation used by the EPA. It also identifies state-of-the-art, commercially available instrumentation and procedures for conducting radiological surveys. Use of this guidance ensures that the surveys are conducted in a manner that provides a high degree of confidence that applicable NRC criteria are satisfied. Once the survey is complete, the results are provided to the NRC in a format that can be verified. The NRC then reviews and evaluates the information, performs an independent confirmation of radiological site conditions, and makes a determination on final termination of the license.

The NRC will terminate the operating license if it determines that site remediation has been performed in accordance with the LTP, and that the terminal radiation survey and associated documentation demonstrate that the facility is suitable for release.

### 2.1.3 Period 3 - Site Restoration

Following completion of decommissioning operations, site restoration activities will begin. Efficient removal of the contaminated materials and verification that residual radionuclide concentrations are below the NRC limits will result in substantial damage to many of the structures. Although performed in a controlled, safe manner, blasting, coring, drilling, scarification (surface removal), and the other decontamination activities will substantially degrade power block structures including the reactor, fuel handling, and radioactive waste buildings. Under certain circumstances, verifying that subsurface radionuclide concentrations meet NRC site release requirements will require removal of grade slabs and lower floors, potentially weakening footings and structural supports. This removal activity will be necessary for those facilities and plant areas where historical records, when available, indicate the potential for radionuclides having been present in the soil, where system failures have been recorded, or where it is required to confirm that subsurface process and drain lines were not breached over the operating life of the station.

Prompt dismantling of site structures is clearly the most appropriate and cost-effective option. It is unreasonable to anticipate that these structures would be repaired and preserved after the radiological contamination is removed. The cost to dismantle site structures with a work force already mobilized on site is more efficient than if the process were deferred. Site facilities quickly degrade without maintenance, adding additional expense and creating potential hazards to the public as well as to future workers. Abandonment creates a breeding ground for vermin infestation as well as other biological hazards.

This cost study presumes that non-essential structures and site facilities are dismantled as a continuation of the decommissioning activity. Foundations and exterior walls are removed to a nominal depth of three feet below grade. The three-foot depth allows for the placement of gravel for drainage, as well as topsoil, so that vegetation can be established for erosion control. Site areas affected by the dismantling activities are restored and the plant area graded as required to prevent ponding and inhibit the refloating of subsurface materials.

Non-contaminated concrete rubble produced by demolition activities is processed to remove reinforcing steel and miscellaneous embedments. The processed material is then used on site to backfill foundation voids. Excess non-contaminated materials are trucked to an off-site area for disposal as construction debris.

## **2.2 SAFSTOR**

The NRC defines SAFSTOR as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use." The facility is left intact (during the dormancy period), with structures maintained in a sound condition. Systems that are not required to support the spent fuel pool or site surveillance and security are drained, de-energized, and secured. Minimal cleaning/removal of loose contamination and/or fixation and sealing of remaining contamination is performed. Access to contaminated areas is secured to provide controlled access for inspection and maintenance.

The engineering and planning requirements are similar to those for the DECON alternative, although a shorter time period is expected for these activities due to the more limited work scope. Site preparations are also similar to those for the DECON alternative. However, with the exception of the required radiation surveys and site characterizations, the mobilization and preparation of site facilities is less extensive.

### **2.2.1 Period 1 - Preparations**

Preparations for long-term storage include the planning for permanent defueling of the reactor, revision of technical specifications appropriate to the operating conditions and requirements, a characterization of the facility and major components, and the development of the PSDAR.

The process of placing the plant in safe-storage includes, but is not limited to, the following activities:

- Isolation of the spent fuel storage services and fuel handling systems so that safe-storage operations may commence on the balance of the plant. This activity may be carried out by plant personnel in accordance with existing operating technical specifications. Activities are scheduled around the fuel handling systems to the greatest extent possible.



- Transfer of the spent fuel from the storage pool to the ISFSI following the minimum required cooling period.
- Draining and de-energizing of the non-contaminated systems not required to support continued site operations or maintenance.
- Disposing of contaminated filter elements and resin beds not required for processing wastes from layup activities for future operations.
- Draining of the reactor vessel, with the internals left in place and the vessel head secured.
- Draining and de-energizing non-essential, contaminated systems with decontamination as required for future maintenance and inspection.
- Preparing lighting and alarm systems whose continued use is required; de-energizing portions of fire protection, electric power, and HVAC systems whose continued use is not required.
- Cleaning of the loose surface contamination from building access pathways.
- Performing an interim radiation survey of plant, posting warning signs where appropriate.
- Erecting physical barriers and/or securing all access to radioactive or contaminated areas, except as required for inspection and maintenance.
- Installing security and surveillance monitoring equipment and relocating security fence around secured structures, as required.

### 2.2.2 Period 2 - Dormancy

The second phase identified by the NRC in its rule addresses licensed activities during a storage period and is applicable to the dormancy phases of the deferred decommissioning alternatives. Dormancy activities include a 24-hour security force, preventive and corrective maintenance on security systems, area lighting, general building maintenance, heating and ventilation of buildings, routine radiological inspections of contaminated structures, maintenance of structural integrity, and a site environmental and radiation monitoring program. Resident maintenance personnel perform equipment maintenance, inspection activities, routine services to maintain safe conditions, adequate lighting, heating, and ventilation, and periodic preventive maintenance on essential site services.

An environmental surveillance program is carried out during the dormancy period to ensure that releases of radioactive material to the environment are prevented and/or detected and controlled. Appropriate emergency procedures are established and initiated for potential releases that exceed prescribed limits. The environmental surveillance program constitutes an abbreviated version of the program in effect during normal plant operations.

Security during the dormancy period is conducted primarily to prevent unauthorized entry and to protect the public from the consequences of its own actions. The security fence, sensors, alarms, and other surveillance equipment provide security. Fire and radiation alarms are also monitored and maintained.

Consistent with the DECON scenario, the spent fuel storage pool is emptied within five and one-half years of the cessation of operations. The pool is secured for storage and decommissioned along with the power block structures in Period 4.

After an optional period of storage (such that license termination is accomplished within 60 years of final shutdown), it is required that the licensee submit an application to terminate the license, along with an LTP (described in Section 2.1.2), thereby initiating the third phase.

### 2.2.3 Periods 3 and 4 - Delayed Decommissioning

Prior to the commencement of decommissioning operations, preparations are undertaken to reactivate site services and prepare for decommissioning. Preparations include engineering and planning, a detailed site characterization, and the assembly of a decommissioning management organization. Final planning for activities and the writing of activity specifications and detailed procedures are also initiated at this time.

Much of the work in developing a termination plan is relevant to the development of the detailed engineering plans and procedures. The activities associated with this phase and the follow-on decontamination and dismantling processes are detailed in Sections 2.1.1 and 2.1.2. The primary difference between the sequences anticipated for the DECON and this deferred scenario is the absence, in the latter, of any constraint on the availability of the fuel storage facilities for decommissioning.

Variations in the length of the dormancy period are expected to have little effect upon the quantities of radioactive wastes generated from system and structure removal operations. Given the levels of radioactivity and spectrum of radionuclides expected from forty years of plant operation, no plant process system identified as being contaminated upon final shutdown will become releasable due to the decay period alone, i.e., there is no significant reduction in the waste generated from the decommissioning activities. However, due to the lower activity levels, a greater percentage of the waste volume can be designated for off-site processing and recovery.

The delay in decommissioning also yields lower working area radiation levels. As such, the estimate for this delayed scenario incorporates reduced ALARA controls for the SAFSTOR's lower occupational exposure potential.

Although the initial radiation levels due to  $^{60}\text{Co}$  will decrease during the dormancy period, the internal components of the reactor vessel will still exhibit sufficiently high radiation dose rates to require remote sectioning under water due to the presence of long-lived radionuclides such as  $^{94}\text{Nb}$ ,  $^{59}\text{Ni}$ , and  $^{63}\text{Ni}$ . Therefore, the dismantling procedures described for the DECON alternative would still be employed during this scenario. Portions of the biological shield will still be radioactive due to the presence of activated trace elements with long half-lives ( $^{152}\text{Eu}$  and  $^{154}\text{Eu}$ ). Decontamination will require controlled removal and disposal. It is assumed that radioactive corrosion products on inner surfaces of piping and components will not have decayed to levels that will permit unrestricted use or allow conventional removal. These systems and components will be surveyed as they are removed and disposed of in accordance with the existing radioactive release criteria.

#### 2.2.4 Period 5 - Site Restoration

Following completion of decommissioning operations, site-restoration activities can begin. Dismantling, as a continuation of the decommissioning process, is clearly the most appropriate and cost-effective option, as described in Section 2.1.3. The basis for the dismantling cost in this scenario is consistent with that described for DECON, presuming the removal of structures and site facilities to a nominal depth of three feet below grade and the limited restoration of the site.

### **3. COST ESTIMATE**

The cost estimates prepared for decommissioning Callaway consider the unique features of the site, including the NSSS, power generation systems, support services, site buildings, and ancillary facilities. The basis of the estimates, including the sources of information relied upon, the estimating methodology employed, site-specific considerations, and other pertinent assumptions, is described in this section.

#### **3.1 BASIS OF ESTIMATE**

The estimates were developed using the site-specific, technical information from the 2008 analysis. This information was reviewed for the current analysis and updated as deemed appropriate. The site-specific considerations and assumptions used in the previous evaluation were also revisited. Modifications were incorporated where new information was available or experience from previously completed decommissioning programs provided viable alternatives or improved processes.

#### **3.2 METHODOLOGY**

The methodology used to develop the estimates follows the basic approach originally presented in the AIF/NESP-036 study report, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates,"<sup>[17]</sup> and the DOE "Decommissioning Handbook."<sup>[18]</sup> These documents present a unit factor method for estimating decommissioning activity costs, which simplifies the estimating calculations. Unit factors for concrete removal (\$/cubic yard), steel removal (\$/ton), and cutting costs (\$/inch) are developed using local labor rates. The activity-dependent costs are estimated with the item quantities (cubic yards and tons), developed from plant drawings and inventory documents. Removal rates and material costs for the conventional disposition of components and structures rely upon information available in the industry publication, "Building Construction Cost Data," published by R.S. Means.<sup>[19]</sup>

The unit factor method provides a demonstrable basis for establishing reliable cost estimates. The detail provided in the unit factors, including activity duration, labor costs (by craft), and equipment and consumable costs, ensures that essential elements have not been omitted. Appendix A presents the detailed development of a typical unit factor. Appendix B provides the values contained within one set of factors developed for this analysis.

This analysis reflects lessons learned from TLG's involvement in the Shippingport Station Decommissioning Project, completed in 1989, as well as the decommissioning of the Cintichem reactor, hot cells, and associated facilities, completed in 1997. In addition, the planning and engineering for the Pathfinder, Shoreham, Rancho Seco, Trojan, Yankee Rowe, Big Rock Point, Maine Yankee, Humboldt Bay-3, Oyster Creek, Connecticut Yankee, and San Onofre-1 nuclear units have provided additional insight into the process, the regulatory aspects, and the technical challenges of decommissioning commercial nuclear units.

### Work Difficulty Factors

TLG has historically applied work difficulty adjustment factors (WDFs) to account for the inefficiencies in working in a power plant environment. WDFs are assigned to each unique set of unit factors, commensurate with the inefficiencies associated with working in confined, hazardous environments. The ranges used for the WDFs are as follows:

- Access Factor 10% to 20%
- Respiratory Protection Factor 10% to 50%
- Radiation/ALARA Factor 10% to 37%
- Protective Clothing Factor 10% to 30%
- Work Break Factor 8.33%

The factors and their associated range of values were developed in conjunction with the AIF/NESP-036 study. The application of the factors is discussed in more detail in that publication.

### Scheduling Program Durations

The unit factors, adjusted by the WDFs as described above, are applied against the inventory of materials to be removed in the radiological controlled areas. The resulting man-hours, or crew-hours, are used in the development of the decommissioning program schedule, using resource loading and event sequencing considerations. The scheduling of conventional removal and dismantling activities is based upon productivity information available from the "Building Construction Cost Data" publication.

An activity duration critical path is used to determine the total decommissioning program schedule. The schedule is relied upon in calculating the carrying costs, which include program management, administration, field

engineering, equipment rental, and support services such as quality control and security. This systematic approach for assembling decommissioning estimates ensures a high degree of confidence in the reliability of the resulting costs.

### **3.3 FINANCIAL COMPONENTS OF THE COST MODEL**

TLG's proprietary decommissioning cost model, DECCER, produces a number of distinct cost elements. These direct expenditures, however, do not comprise the total cost to accomplish the project goal, i.e., license termination and site restoration.

Inherent in any cost estimate that does not rely on historical data is the inability to specify the precise source of costs imposed by factors such as tool breakage, accidents, illnesses, weather delays, and labor stoppages. In the DECCER cost model, contingency fulfills this role. Contingency is added to each line item to account for costs that are difficult or impossible to develop analytically. Such costs are historically inevitable over the duration of a job of this magnitude; therefore, this cost analysis includes funds to cover these types of expenses.

#### **3.3.1 Contingency**

The activity- and period-dependent costs are combined to develop the total decommissioning cost. A contingency is then applied on a line-item basis, using one or more of the contingency types listed in the AIF/NESP-036 study. "Contingencies" are defined in the American Association of Cost Engineers "Project and Cost Engineers' Handbook"<sup>[20]</sup> as "specific provision for unforeseeable elements of cost within the defined project scope; particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur." The cost elements in this analysis are based upon ideal conditions and maximum efficiency; therefore, consistent with industry practice, contingency is included. In the AIF/NESP-036 study, the types of unforeseeable events that are likely to occur in decommissioning are discussed and guidelines are provided for percentage contingency in each category. It should be noted that contingency, as used in this analysis, does not account for price escalation and inflation in the cost of decommissioning over the remaining operating life of the station.

Contingency funds are an integral part of the total cost to complete the decommissioning process. Exclusion of this component puts at risk a

successful completion of the intended tasks and, potentially, subsequent related activities. For this study, TLG examined the major activity-related problems (decontamination, segmentation, equipment handling, packaging, transport, and waste disposal) that necessitate a contingency. Individual activity contingencies ranged from 10% to 75%, depending on the degree of difficulty judged to be appropriate from TLG's actual decommissioning experience. The contingency values used in this study are as follows:

• Decontamination	50%
• Contaminated Component Removal	25%
• Contaminated Component Packaging	10%
• Contaminated Component Transport	15%
• Low-Level Radioactive Waste Disposal	25%
• Reactor Segmentation	75%
• NSSS Component Removal	25%
• Reactor Waste Packaging	25%
• Reactor Waste Transport	25%
• Reactor Vessel Component Disposal	50%
• GTCC Disposal	15%
• Non-Radioactive Component Removal	15%
• Heavy Equipment and Tooling	15%
• Supplies	25%
• Engineering	15%
• Energy	15%
• Characterization and Termination Surveys	30%
• Construction	15%
• Taxes and Fees	10%
• Insurance	10%
• Staffing	15%

The contingency values are applied to the appropriate components of the estimates on a line item basis. A composite value is then reported at the end of each detailed estimate (as provided in Appendix C and D). For example, the composite contingency value reported for the DECON alternative in Appendix C is approximately 18.0%.

### 3.3.2 Financial Risk

In addition to the routine uncertainties addressed by contingency, another cost element that is sometimes necessary to consider when bounding decommissioning costs relates to uncertainty, or risk. Examples can include changes in work scope, pricing, job performance, and other variations that could conceivably, but not necessarily, occur. Consideration is sometimes necessary to generate a level of confidence in the estimate, within a range of probabilities. TLG considers these types of costs under the broad term “financial risk.” Included within the category of financial risk are:

- Transition activities and costs: ancillary expenses associated with eliminating 50% to 80% of the site labor force shortly after the cessation of plant operations, added cost for worker separation packages throughout the decommissioning program, national or company-mandated retraining, and retention incentives for key personnel.
- Delays in approval of the decommissioning plan due to intervention, public participation in local community meetings, legal challenges, and national and local hearings.
- Changes in the project work scope from the baseline estimate, involving the discovery of unexpected levels of contaminants, contamination in places not previously expected, contaminated soil previously undiscovered (either radioactive or hazardous material contamination), variations in plant inventory or configuration not indicated by the as-built drawings.
- Regulatory changes, for example, affecting worker health and safety, site release criteria, waste transportation, and disposal.
- Policy decisions altering national commitments (e.g., in the ability to accommodate certain waste forms for disposition), or in the timetable for such, for example, the start and rate of acceptance of spent fuel by the DOE.
- Pricing changes for basic inputs such as labor, energy, materials, and disposal. Items subject to widespread price competition (such as materials) may not show significant variation; however, others such as waste disposal could exhibit large pricing uncertainties, particularly in markets where limited access to services is available.

It has been TLG’s experience that the results of a risk analysis, when compared with the base case estimate for decommissioning, indicate



that the chances of the base decommissioning estimate's being too high is a low probability, and the chances that the estimate is too low is a higher probability. This is mostly due to the pricing uncertainty for low-level radioactive waste burial, and to a lesser extent due to schedule increases from changes in plant conditions and to pricing variations in the cost of labor (both craft and staff). This cost study, however, does not add any additional costs to the estimate for financial risk, since there is insufficient historical data from which to project future liabilities. Consequently, the areas of uncertainty or risk are revisited periodically and addressed through repeated revisions or updates of the base estimates.

### **3.4 SITE-SPECIFIC CONSIDERATIONS**

There are a number of site-specific considerations that affect the method for dismantling and removal of equipment from the site and the degree of restoration required. The cost impact of the considerations identified below is included in this cost study.

#### **3.4.1 Spent Fuel Management**

The cost to dispose the spent fuel generated from plant operations is not reflected within the estimates to decommission Callaway. Ultimate disposition of the spent fuel is within the province of the DOE's Waste Management System, as defined by the Nuclear Waste Policy Act. As such, the disposal cost is financed by a 1 mill/kWhr surcharge paid into the DOE's waste fund during operations. However, the NRC requires licensees to establish a program to manage and provide funding for the management of all irradiated fuel at the reactor until title of the fuel is transferred to the Secretary of Energy. This funding requirement is fulfilled through inclusion of certain high-level waste cost elements within the estimates, as described below.

For estimating purposes, Ameren Missouri has assumed that all spent fuel will be relocated to an ISFSI on the Callaway site within five and one-half years after shutdown. This will allow Ameren Missouri to proceed with decommissioning (or safe-storage) operations in the shortest time possible.

It is assumed that the five and one-half years provides the necessary cooling period for the final core to meet storage requirements for decay heat. Once the pool is emptied, the spent fuel storage and handling

facilities are available for decommissioning. Operation and maintenance costs for the spent fuel pool are included within the estimate.

#### Canister Loading and Transfer

A cost of \$240,000 is used for the labor to load/transport the spent fuel from the pool to the ISFSI. The capital cost for the dry storage system is not included.

#### Operations and Maintenance

An annual cost of approximately \$764,000 is used for operation and maintenance of the spent fuel pool. Pool operations are expected to continue approximately five and one-half years after the cessation of operations. An annual cost of approximately \$90,000 is used for operation and maintenance of the ISFSI during decommissioning.

#### GTCC

The dismantling of the reactor internals will generate radioactive waste considered unsuitable for shallow land disposal, i.e., low-level radioactive waste with concentrations of radionuclides that exceed the limits established by the Commission for Class C radioactive waste (GTCC). The Low-Level Radioactive Waste Policy Amendments Act of 1985 assigned the federal government the responsibility for the disposal of this material. The Act also stated that the beneficiaries of the activities resulting in the generation of such radioactive waste bear all reasonable costs of disposing of such waste. However, to date, the federal government has not identified a cost for disposing of GTCC or a schedule for acceptance.

For purposes of this study, GTCC is packaged in the same canisters used to transport spent fuel. The GTCC is assumed to be disposed of as it is generated during reactor vessel segmentation operations.

### 3.4.2 Reactor Vessel and Internal Components

The reactor pressure vessel and internal components are segmented for disposal in shielded, reusable transportation casks. Segmentation is performed in the refueling canal, where a turntable and remote cutter are installed. The vessel is segmented in place, using a mast-mounted cutter supported off the lower head and directed from a shielded work platform installed overhead in the reactor cavity. Transportation cask

specifications and transportation regulations dictate the segmentation and packaging methodology.

Intact disposal of reactor vessel shells has been successfully demonstrated at several of the sites currently being decommissioned. Access to navigable waterways has allowed these large packages to be transported to the Barnwell, South Carolina and Hanford, Washington disposal sites with minimal overland travel. Intact disposal of the reactor vessel and internal components can provide savings in cost and worker exposure by eliminating the complex segmentation requirements, isolation of the GTCC material, and transport/storage of the resulting waste packages. Portland General Electric (PGE) was able to dispose of the Trojan reactor as an intact package (including the internals). However, its location on the Columbia River simplified the transportation analysis since:

- the reactor package could be secured to the transport vehicle for the entire journey, i.e., the package was not lifted during transport,
- there were no man-made or natural terrain features between the plant site and the disposal location that could produce a large drop, and
- transport speeds were very low, limited by the overland transport vehicle and the river barge.

As a member of the Northwest Compact, PGE had a site available for disposal of the package - the US Ecology facility in Washington State. The characteristics of this arid site proved favorable in demonstrating compliance with land disposal regulations.

It is not known whether this option will be available when the Callaway unit ceases operation. Future viability of this option will depend upon the ultimate location of the disposal site, as well as the disposal site licensee's ability to accept highly radioactive packages and effectively isolate them from the environment. Consequently, the study assumes the reactor vessel will require segmentation, as a bounding condition.

### 3.4.3 Primary System Components

In the DECON scenario, the reactor coolant system components are assumed to be decontaminated using chemical agents prior to the start of dismantling operations. This type of decontamination can be expected

to have a significant ALARA impact, since in this scenario the removal work is done within the first few years of shutdown. A decontamination factor (average reduction) of 10 is assumed for the process. In the SAFSTOR scenario, radionuclide decay is expected to provide the same benefit and, therefore, a chemical decontamination is not included.

The following discussion deals with the removal and disposition of the steam generators, but the techniques involved are also applicable to other large components, such as heat exchangers, component coolers, and the pressurizer. The steam generators' size and weight, as well as their location within the reactor building, will ultimately determine the removal strategy.

A trolley crane is set up for the removal of the generators. It can also be used to move portions of the steam generator cubicle walls and floor slabs from the reactor building to a location where they can be decontaminated and transported to the material handling area. Interferences within the work area, such as grating, piping, and other components are removed to create sufficient laydown space for processing these large components.

The generators are rigged for removal, disconnected from the surrounding piping and supports, and maneuvered into the open area where they are lowered onto a dolly. Each generator is rotated into the horizontal position for extraction from the containment and placed onto a multi-wheeled vehicle for transport to an on-site processing and storage area.

The generators are disassembled on-site with the steam dome and lightly contaminated subassemblies designated for off-site recycling. The more highly contaminated tube sheet and tube bundle are packaged for direct disposal. The interior volume is filled with low-density cellular concrete for stabilization of the internal contamination.

Reactor coolant piping is cut from the reactor vessel once the water level in the vessel (used for personnel shielding during dismantling and cutting operations in and around the vessel) is dropped below the nozzle zone. The piping is boxed and transported by shielded van. The reactor coolant pumps and motors are lifted out intact, packaged, and transported for processing and/or disposal.

#### 3.4.4 Retired Components

The estimates include the cost to dispose of the retired steam generators expected to be in storage at the site upon the cessation of plant operations. The components are size-reduced to facilitate transportation.

#### 3.4.5 Main Turbine and Condenser

The main turbine is dismantled using conventional maintenance procedures. The turbine rotors and shafts are removed to a laydown area. The lower turbine casings are removed from their anchors by controlled demolition. The main condensers are also disassembled and moved to a laydown area. Material is then prepared for transportation to an off-site recycling facility where it is surveyed and designated for either decontamination or volume reduction, conventional disposal, or controlled disposal. Components are packaged and readied for transport in accordance with the intended disposition.

#### 3.4.6 Transportation Methods

Contaminated piping, components, and structural material other than the highly activated reactor vessel and internal components will qualify as LSA-I, II or III or Surface Contaminated Object, SCO-I or II, as described in Title 49.<sup>[21]</sup> The contaminated material will be packaged in Industrial Packages (IP-1, IP-2, or IP-3, as defined in subpart 173.411) for transport unless demonstrated to qualify as their own shipping containers. The reactor vessel and internal components are expected to be transported in accordance with Part 71, as Type B. It is conceivable that the reactor, due to its limited specific activity, could qualify as LSA II or III. However, the high radiation levels on the outer surface would require that additional shielding be incorporated within the packaging so as to attenuate the dose to levels acceptable for transport.

Any fuel cladding failure that occurred during the lifetime of the plant is assumed to have released fission products at sufficiently low levels that the buildup of quantities of long-lived isotopes (e.g., <sup>137</sup>Cs, <sup>90</sup>Sr, or transuranics) has been prevented from reaching levels exceeding those that permit the major reactor components to be shipped under current transportation regulations and disposal requirements.

Transport of the highly activated metal, produced in the segmentation of the reactor vessel and internal components, will be by shielded truck cask. Cask shipments may exceed 95,000 pounds, including vessel

segment(s), supplementary shielding, cask tie-downs, and tractor-trailer. The maximum level of activity per shipment assumed permissible was based upon the license limits of the available shielded transport casks. The segmentation scheme for the vessel and internal segments is designed to meet these limits.

The transport of large intact components (e.g., large heat exchangers and other oversized components) will be by a combination of truck, rail, and/or multi-wheeled transporter.

Transportation costs for material requiring controlled disposal are based upon the mileage to the EnergySolutions facility in Clive, Utah. Transportation costs for off-site waste processing are based upon the mileage to Oak Ridge, Tennessee. Truck transport costs are estimated using published tariffs from Tri-State Motor Transit.<sup>[22]</sup>

#### 3.4.7 Low-Level Radioactive Waste Disposal

To the greatest extent practical, metallic material generated in the decontamination and dismantling processes is processed to reduce the total cost of controlled disposal. Material meeting the regulatory and/or site release criterion, is released as scrap, requiring no further cost consideration. Conditioning (preparing the material to meet the waste acceptance criteria of the disposal site) and recovery of the waste stream is performed off site at a licensed processing center. Any material leaving the site is subject to a survey and release charge, at a minimum.

The mass of radioactive waste generated during the various decommissioning activities at the site is shown on a line-item basis in the detailed Appendices C and D, and summarized in Section 5. The quantified waste summaries shown in these tables are consistent with 10 CFR Part 61 classifications. Commercially available steel containers are presumed to be used for the disposal of piping, small components, and concrete. Larger components can serve as their own containers, with proper closure of all openings, access ways, and penetrations. The volumes are calculated based on the exterior package dimensions for containerized material or a specific calculation for components serving as their own waste containers.

The more highly activated reactor components will be shipped in reusable, shielded truck casks with disposable liners. In calculating disposal costs, the burial fees are applied against the liner volume, as well as the special handling requirements of the payload. Packaging

efficiencies are lower for the highly activated materials (greater than Type A quantity waste), where high concentrations of gamma-emitting radionuclides limit the capacity of the shipping canisters.

Disposal fees are based upon estimated charges, with surcharges added for the highly activated components, for example, generated in the segmentation of the reactor vessel. The cost to dispose of the majority of the material generated from the decontamination and dismantling activities is based upon the current cost for disposal at *EnergySolutions* facility in Clive, Utah. Disposal costs for the higher activity waste (Class B and C) were based upon the last published rate schedule for non-compact waste for the Barnwell facility (as a proxy).

#### 3.4.8 Site Conditions Following Decommissioning

The NRC will terminate the site license when it determines that site remediation has been performed in accordance with the license termination plan, and that the terminal radiation survey and associated documentation demonstrate that the facility is suitable for release. The NRC's involvement in the decommissioning process will end at this point. Local building codes and state environmental regulations will dictate the next step in the decommissioning process, as well as the owner's own future plans for the site.

The estimates presented herein include the dismantling of the major structures to just below ground level, backfilling and the collapsing of below grade voids, and regrading such that the site upon which the power block and supplemental structures are located is transformed into a "grassy plain."

The existing electrical switchyard and access roads will remain in support of the electrical transmission and distribution system. Site restoration does not include the remediation of the water treatment plant's settling basins, if required.

Sludge removed from the sewage treatment plant lagoon was assumed to contain low levels of contamination that would require controlled disposal. As such, 3,600 cubic feet of material from the lagoon was designated for disposition at *EnergySolutions'* facility.

The existing and replacement cooling tower discharge pipes will be left in place and flow filled with suitable material to prevent the pipes from collapsing. The intake line will also be filled.

The estimates do not assume the remediation of any significant volume of contaminated soil. This assumption may be affected by continued plant operations and/or future regulatory actions, such as the development of site-specific release criteria.

### **3.5 ASSUMPTIONS**

The following are the major assumptions made in the development of the estimates for decommissioning the site.

#### **3.5.1 Estimating Basis**

The study follows the principles of ALARA through the use of work duration adjustment factors. These factors address the impact of activities such as radiological protection instruction, mock-up training, and the use of respiratory protection and protective clothing. The factors lengthen a task's duration, increasing costs and lengthening the overall schedule. ALARA planning is considered in the costs for engineering and planning, and in the development of activity specifications and detailed procedures. Changes to worker exposure limits may impact the decommissioning cost and project schedule.

#### **3.5.2 Labor Costs**

The craft labor required to decontaminate and dismantle the nuclear unit is acquired through standard site contracting practices. The current cost of labor at the site is used as an estimating basis.

Ameren Missouri, as the operator, will continue to provide site operations support, including decommissioning program management, licensing, radiological protection, and site security. A Decommissioning Operations Contractor (DOC) will provide the supervisory staff needed to oversee the labor subcontractors, consultants, and specialty contractors needed to perform the work required for the decontamination and dismantling effort. The DOC will also provide the engineering services needed to develop activity specifications, detailed procedures, detailed activation analyses, and support field activities such as structural modifications.

Personnel costs are based upon average salary information provided by Ameren Missouri. Overhead costs are included for site and corporate support, reduced commensurate with the staffing of the project.



Security, while reduced from operating levels, is maintained throughout the decommissioning for access control, material control, and to safeguard the spent fuel.

### 3.5.3 Design Conditions

Any fuel cladding failure that occurred during the lifetime of the plant is assumed to have released fission products at sufficiently low levels that the buildup of quantities of long-lived isotopes (e.g., <sup>137</sup>Cs, <sup>90</sup>Sr, or transuranics) has been prevented from reaching levels exceeding those that permit the major NSSS components to be shipped under current transportation regulations and disposal requirements.

The curie contents of the vessel and internals at final shutdown are derived from those listed in NUREG/CR-3474.<sup>[23]</sup> Actual estimates are derived from the curie/gram values contained therein and adjusted for the different mass of the Callaway components, projected operating life, and different periods of decay. Additional short-lived isotopes were derived from CR-0130<sup>[24]</sup> and CR-0672,<sup>[25]</sup> and benchmarked to the long-lived values from CR-3474.

The control elements are disposed of along with the spent fuel, i.e., there is no additional cost provided for their disposal.

Activation of the containment building structure is confined to the biological shield. More extensive activation (at very low levels) of the interior structures within containment has been detected at several reactors and the owners have elected to dispose of the affected material at a controlled facility rather than reuse the material as fill on site or send it to a landfill. The ultimate disposition of the material removed from the containment building will depend upon the site release criteria selected, as well as the designated end use for the site.

### 3.5.4 General

#### Transition Activities

Existing warehouses are cleared of non-essential material and remain for use by Ameren Missouri and its subcontractors. The plant's operating staff performs the following activities at no additional cost or credit to the project during the transition period:

- Drain and collect fuel oils, lubricating oils, and transformer oils for recycle and/or sale.
- Drain and collect acids, caustics, and other chemical stores for recycle and/or sale.
- Process operating waste inventories, i.e., the estimates do not address the disposition of any legacy wastes; the disposal of operating wastes during this initial period is not considered a decommissioning expense.

### Scrap and Salvage

The existing plant equipment is considered obsolete and suitable for scrap as deadweight quantities only. Ameren Missouri will make economically reasonable efforts to salvage equipment following final plant shutdown. However, dismantling techniques assumed by TLG for equipment in this analysis are not consistent with removal techniques required for salvage (resale) of equipment. Experience has indicated that some buyers wanted equipment stripped down to very specific requirements before they would consider purchase. This required expensive rework after the equipment had been removed from its installed location. Since placing a salvage value on this machinery and equipment would be speculative, and the value would be small in comparison to the overall decommissioning expenses, this analysis does not attempt to quantify the value that an owner may realize based upon those efforts.

It is assumed, for purposes of this analysis, that any value received from the sale of scrap generated in the dismantling process would be more than offset by the on-site processing costs. The dismantling techniques assumed in the decommissioning estimates do not include the additional cost for size reduction and preparation to meet “furnace ready” conditions. For example, the recovery of copper from electrical cabling may require the removal and disposition of any contaminated insulation, an added expense. With a volatile market, the potential profit margin in scrap recovery is highly speculative, regardless of the ability to free release this material. This assumption is an implicit recognition of scrap value in the disposal of clean metallic waste at no additional cost to the project.

Furniture, tools, mobile equipment such as forklifts, trucks, bulldozers, and other property is removed at no cost or credit to the

decommissioning project. Disposition may include relocation to other facilities. Spare parts are also made available for alternative use.

### Energy

For estimating purposes, the plant is assumed to be de-energized, with the exception of those facilities associated with spent fuel storage. Replacement power costs are used to calculate the cost of energy consumed during decommissioning for tooling, lighting, ventilation, and essential services.

### Insurance

Costs for continuing coverage (nuclear liability and property insurance) following cessation of plant operations and during decommissioning are included and based upon current operating premiums. Reductions in premiums, throughout the decommissioning process, are based upon the guidance and the limits for coverage defined in the NRC's proposed rulemaking "Financial Protection Requirements for Permanently Shutdown Nuclear Power Reactors."<sup>[26]</sup> The NRC's financial protection requirements are based on various reactor (and spent fuel) configurations.

### Taxes

Property tax payments are included for the land only and will continue through the decommissioning project.

### Site Modifications

The perimeter fence and in-plant security barriers will be moved, as appropriate, to conform to the Site Security Plan in force during the various stages of the project.

## **3.6 COST ESTIMATE SUMMARY**

Schedules of expenditures are provided in Tables 3.1 and 3.2. The tables delineate the cost contributors by year of expenditures as well as cost contributor (e.g., labor, materials, and waste disposal).

The cost elements are also assigned to one of three subcategories: "License Termination," "Spent Fuel Management," and "Site Restoration." The subcategory "License Termination" is used to accumulate costs that are

consistent with “decommissioning” as defined by the NRC in its financial assurance regulations (i.e., 10 CFR §50.75). The cost reported for this subcategory is generally sufficient to terminate the unit’s operating license, recognizing that there may be some additional cost impact from spent fuel management. These costs are identified in Tables 3.1a and 3.2a.

The “Spent Fuel Management” subcategory contains costs associated with the five and one-half years of post-shutdown pool operations and the transfer of the fuel from the pool to the ISFSI. These costs are identified in Tables 3.1b and 3.2b.

“Site Restoration” is used to capture costs associated with the dismantling and demolition of buildings and facilities demonstrated to be free from contamination. This includes structures never exposed to radioactive materials, as well as those facilities that have been decontaminated to appropriate levels. Structures are removed to a depth of three feet and backfilled to conform to local grade. These costs are identified in Tables 3.1c and 3.2c.

As discussed in Section 3.4.1, while designated for disposal at the geologic repository along with the spent fuel, GTCC waste is still classified as low-level radioactive waste and, as such, included as a “License Termination” expense.

Decommissioning costs are reported in 2011 dollars. Costs are not inflated, escalated, or discounted over the period of expenditure (or projected lifetime of the plant). The schedules are based upon the detailed activity costs reported in Appendices C and D, along with the timeline presented in Section 4.

**TABLE 3.1**  
**DECON ALTERNATIVE**  
**SCHEDULE OF TOTAL ANNUAL EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other <sup>[1]</sup>	Total <sup>[2]</sup>
2024	11,577	978	171	7	1,965	14,699
2025	58,992	7,323	1,003	1,575	15,120	84,013
2026	68,700	25,346	1,052	25,055	29,700	149,853
2027	67,008	26,210	767	29,080	24,429	147,494
2028	58,156	10,262	626	7,944	10,104	87,092
2029	57,997	10,234	624	7,922	10,076	86,854
2030	44,042	6,998	413	6,611	7,058	65,122
2031	32,625	8,686	143	19	3,369	44,842
2032	30,644	26,753	83	0	3,681	61,162
2033	6,698	5,848	18	0	805	13,369
<b>Total</b>	<b>436,438</b>	<b>128,637</b>	<b>4,901</b>	<b>78,214</b>	<b>106,307</b>	<b>754,498</b>

<sup>[1]</sup> Includes property taxes, insurance, fees, surveys, and GTCC disposal

<sup>[2]</sup> Columns may not add due to rounding

**TABLE 3.1a**  
**DECON ALTERNATIVE**  
**SCHEDULE OF LICENSE TERMINATION EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2024	11,240	340	171	7	1,458	13,217
2025	57,149	4,265	1,003	1,575	12,653	76,646
2026	65,441	22,302	1,052	25,055	27,550	141,399
2027	63,309	23,019	767	29,080	22,380	138,556
2028	53,411	6,604	626	7,944	7,841	76,426
2029	53,265	6,586	624	7,922	7,820	76,217
2030	42,642	5,919	413	6,611	6,390	61,975
2031	24,040	1,157	119	19	3,281	28,616
2032	140	0	0	0	3,366	3,506
2033	31	0	0	0	736	766
<b>Total</b>	<b>370,666</b>	<b>70,191</b>	<b>4,776</b>	<b>78,214</b>	<b>93,476</b>	<b>617,324</b>

**TABLE 3.1b**  
**DECON ALTERNATIVE**  
**SCHEDULE OF SPENT FUEL MANAGEMENT EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2024	213	638	0	0	507	1,358
2025	1,019	3,058	0	0	2,467	6,543
2026	999	2,997	0	0	2,128	6,124
2027	1,013	3,038	0	0	1,984	6,035
2028	993	2,979	0	0	1,990	5,962
2029	990	2,971	0	0	1,984	5,946
2030	293	879	0	0	587	1,759
2031	0	0	0	0	0	0
2032	0	0	0	0	0	0
2033	0	0	0	0	0	0
<b>Total</b>	<b>5,520</b>	<b>16,560</b>	<b>0</b>	<b>0</b>	<b>11,646</b>	<b>33,726</b>

**TABLE 3.1c**  
**DECON ALTERNATIVE**  
**SCHEDULE OF SITE RESTORATION EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2024	125	0	0	0	0	125
2025	824	0	0	0	0	824
2026	2,261	48	0	0	22	2,330
2027	2,686	153	0	0	65	2,904
2028	3,751	679	0	0	273	4,703
2029	3,741	677	0	0	272	4,691
2030	1,107	200	0	0	81	1,388
2031	8,585	7,529	23	0	89	16,226
2032	30,505	26,753	83	0	315	57,656
2033	6,668	5,848	18	0	69	12,602
<b>Total</b>	<b>60,252</b>	<b>41,886</b>	<b>125</b>	<b>0</b>	<b>1,185</b>	<b>103,448</b>



**TABLE 3.2**  
**SAFSTOR ALTERNATIVE**  
**SCHEDULE OF TOTAL ANNUAL EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other <sup>[1]</sup>	Total <sup>[2]</sup>
2024	9,543	879	171	7	1,843	12,444
2025	48,860	7,091	832	447	9,451	66,682
2026	23,651	5,167	365	629	18,659	48,472
2027	13,317	3,369	166	13	4,330	21,196
2028	13,353	3,378	167	13	4,342	21,254
2029	13,317	3,369	166	13	4,330	21,196
2030	6,299	1,203	108	8	2,255	9,874
2031	3,350	293	83	6	1,383	5,116
2032	3,360	294	83	6	1,387	5,130
2033	3,350	293	83	6	1,383	5,116
2034	3,350	293	83	6	1,383	5,116
2035	3,350	293	83	6	1,383	5,116
2036	3,360	294	83	6	1,387	5,130
2037	3,350	293	83	6	1,383	5,116
2038	3,350	293	83	6	1,383	5,116
2039	3,350	293	83	6	1,383	5,116
2040	3,360	294	83	6	1,387	5,130
2041	3,350	293	83	6	1,383	5,116
2042	3,350	293	83	6	1,383	5,116
2043	3,350	293	83	6	1,383	5,116
2044	3,360	294	83	6	1,387	5,130
2045	3,350	293	83	6	1,383	5,116
2046	3,350	293	83	6	1,383	5,116
2047	3,350	293	83	6	1,383	5,116
2048	3,360	294	83	6	1,387	5,130
2049	3,350	293	83	6	1,383	5,116
2050	3,350	293	83	6	1,383	5,116
2051	3,350	293	83	6	1,383	5,116
2052	3,360	294	83	6	1,387	5,130
2053	3,350	293	83	6	1,383	5,116
2054	3,350	293	83	6	1,383	5,116
2055	3,350	293	83	6	1,383	5,116
2056	3,360	294	83	6	1,387	5,130

**TABLE 3.2 (continued)**  
**SAFSTOR ALTERNATIVE**  
**SCHEDULE OF TOTAL ANNUAL EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other <sup>[1]</sup>	Total <sup>[2]</sup>
2057	3,350	293	83	6	1,383	5,116
2058	3,350	293	83	6	1,383	5,116
2059	3,350	293	83	6	1,383	5,116
2060	3,360	294	83	6	1,387	5,130
2061	3,350	293	83	6	1,383	5,116
2062	3,350	293	83	6	1,383	5,116
2063	3,350	293	83	6	1,383	5,116
2064	3,360	294	83	6	1,387	5,130
2065	3,350	293	83	6	1,383	5,116
2066	3,350	293	83	6	1,383	5,116
2067	3,350	293	83	6	1,383	5,116
2068	3,360	294	83	6	1,387	5,130
2069	3,350	293	83	6	1,383	5,116
2070	3,350	293	83	6	1,383	5,116
2071	3,350	293	83	6	1,383	5,116
2072	3,360	294	83	6	1,387	5,130
2073	3,350	293	83	6	1,383	5,116
2074	3,350	293	83	6	1,383	5,116
2075	3,350	293	83	6	1,383	5,116
2076	3,360	294	83	6	1,387	5,130
2077	3,350	293	83	6	1,383	5,116
2078	27,456	1,188	444	18	2,894	31,999
2079	43,085	5,077	832	34	4,135	53,163
2080	60,287	28,908	794	34,110	27,083	151,182
2081	50,850	11,050	657	12,469	10,971	85,998
2082	48,476	6,552	624	6,987	6,905	69,544
2083	48,476	6,552	624	6,987	6,905	69,544
2084	33,183	6,970	169	308	3,483	44,112
2085	30,561	26,679	83	0	3,605	60,929
2086	9,126	7,967	25	0	1,077	18,195
<b>Total</b>	<b>637,419</b>	<b>139,174</b>	<b>10,144</b>	<b>62,323</b>	<b>177,324</b>	<b>1,026,384</b>

<sup>[1]</sup> Includes property taxes, insurance, fees, surveys, and GTCC disposal

<sup>[2]</sup> Columns may not add due to rounding

**TABLE 3.2a**  
**SAFSTOR ALTERNATIVE**  
**SCHEDULE OF LICENSE TERMINATION EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2024	9,331	241	171	7	1,336	11,086
2025	47,813	3,949	832	447	6,984	60,026
2026	16,334	2,117	307	629	15,872	35,259
2027	3,351	419	83	13	1,407	5,273
2028	3,360	420	83	13	1,410	5,288
2029	3,351	419	83	13	1,407	5,273
2030	3,350	330	83	8	1,390	5,162
2031	3,350	293	83	6	1,383	5,116
2032	3,360	294	83	6	1,387	5,130
2033	3,350	293	83	6	1,383	5,116
2034	3,350	293	83	6	1,383	5,116
2035	3,350	293	83	6	1,383	5,116
2036	3,360	294	83	6	1,387	5,130
2037	3,350	293	83	6	1,383	5,116
2038	3,350	293	83	6	1,383	5,116
2039	3,350	293	83	6	1,383	5,116
2040	3,360	294	83	6	1,387	5,130
2041	3,350	293	83	6	1,383	5,116
2042	3,350	293	83	6	1,383	5,116
2043	3,350	293	83	6	1,383	5,116
2044	3,360	294	83	6	1,387	5,130
2045	3,350	293	83	6	1,383	5,116
2046	3,350	293	83	6	1,383	5,116
2047	3,350	293	83	6	1,383	5,116
2048	3,360	294	83	6	1,387	5,130
2049	3,350	293	83	6	1,383	5,116
2050	3,350	293	83	6	1,383	5,116
2051	3,350	293	83	6	1,383	5,116
2052	3,360	294	83	6	1,387	5,130
2053	3,350	293	83	6	1,383	5,116
2054	3,350	293	83	6	1,383	5,116
2055	3,350	293	83	6	1,383	5,116
2056	3,360	294	83	6	1,387	5,130

**TABLE 3.2a (continued)**  
**SAFSTOR ALTERNATIVE**  
**SCHEDULE OF LICENSE TERMINATION EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2057	3,350	293	83	6	1,383	5,116
2058	3,350	293	83	6	1,383	5,116
2059	3,350	293	83	6	1,383	5,116
2060	3,360	294	83	6	1,387	5,130
2061	3,350	293	83	6	1,383	5,116
2062	3,350	293	83	6	1,383	5,116
2063	3,350	293	83	6	1,383	5,116
2064	3,360	294	83	6	1,387	5,130
2065	3,350	293	83	6	1,383	5,116
2066	3,350	293	83	6	1,383	5,116
2067	3,350	293	83	6	1,383	5,116
2068	3,360	294	83	6	1,387	5,130
2069	3,350	293	83	6	1,383	5,116
2070	3,350	293	83	6	1,383	5,116
2071	3,350	293	83	6	1,383	5,116
2072	3,360	294	83	6	1,387	5,130
2073	3,350	293	83	6	1,383	5,116
2074	3,350	293	83	6	1,383	5,116
2075	3,350	293	83	6	1,383	5,116
2076	3,360	294	83	6	1,387	5,130
2077	3,350	293	83	6	1,383	5,116
2078	26,844	1,188	444	18	2,894	31,387
2079	42,237	5,077	832	34	4,135	52,315
2080	57,000	28,826	794	34,110	27,053	147,782
2081	47,617	10,568	657	12,469	10,778	82,089
2082	45,269	5,971	624	6,987	6,671	65,522
2083	45,269	5,971	624	6,987	6,671	65,522
2084	26,800	1,464	152	308	3,408	32,132
2085	139	0	0	0	3,291	3,430
2086	42	0	0	0	983	1,024
<b>Total</b>	<b>535,683</b>	<b>80,735</b>	<b>9,686</b>	<b>62,323</b>	<b>160,746</b>	<b>849,173</b>

**TABLE 3.2b**  
**SAFSTOR ALTERNATIVE**  
**SCHEDULE OF SPENT FUEL MANAGEMENT EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2024	213	638	0	0	507	1,358
2025	1,047	3,142	0	0	2,467	6,656
2026	7,317	3,050	58	0	2,787	13,212
2027	9,966	2,950	83	0	2,924	15,923
2028	9,993	2,958	83	0	2,932	15,966
2029	9,966	2,950	83	0	2,924	15,923
2030	2,949	873	25	0	865	4,711
2031-86	0	0	0	0	0	0
<b>Total</b>	<b>41,451</b>	<b>16,560</b>	<b>333</b>	<b>0</b>	<b>15,405</b>	<b>73,749</b>

**TABLE 3.2c**  
**SAFSTOR ALTERNATIVE**  
**SCHEDULE OF SITE RESTORATION EXPENDITURES**  
(thousands, 2011 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2024-77	0	0	0	0	0	0
2078	539	0	0	0	0	539
2079	873	0	0	0	0	873
2080	3,144	77	0	0	28	3,250
2081	3,304	466	0	0	186	3,956
2082	3,293	596	0	0	240	4,129
2083	3,293	596	0	0	240	4,129
2084	6,332	5,497	17	0	70	11,917
2085	30,421	26,679	83	0	314	57,498
2086	9,085	7,967	25	0	94	17,171
<b>Total</b>	<b>60,285</b>	<b>41,879</b>	<b>125</b>	<b>0</b>	<b>1,173</b>	<b>103,462</b>

## **4. SCHEDULE ESTIMATE**

The schedules for the decommissioning scenarios considered in this study follow the sequences presented in the AIF/NESP-036 study, with minor changes to reflect recent experience and site-specific constraints. In addition, the scheduling has been revised to reflect the spent fuel management plan described in Section 3.4.1.

A schedule or sequence of activities for the DECON alternative is presented in Figure 4.1. The scheduling sequence assumes that fuel is removed from the spent fuel pool within five and one-half years. The key activities listed in the schedule do not reflect a one-to-one correspondence with those activities in the cost tables, but reflect dividing some activities for clarity and combining others for convenience. The schedule was prepared using the "Microsoft Project Professional 2010" computer software.<sup>[27]</sup>

### **4.1 SCHEDULE ESTIMATE ASSUMPTIONS**

The schedule reflects the results of a precedence network developed for the site decommissioning activities, i.e., a PERT (Program Evaluation and Review Technique) Software Package. The work activity durations used in the precedence network reflect the actual man-hour estimates from the cost table, adjusted by stretching certain activities over their slack range and shifting the start and end dates of others. The following assumptions were made in the development of the decommissioning schedule:

- The fuel building is isolated until such time that all spent fuel has been transferred from the spent fuel pool to the DOE. Decontamination and dismantling of the storage pool is initiated once the transfer of spent fuel is complete (DECON option).
- All work (except vessel and internals removal) is performed during an 8-hour workday, 5 days per week, with no overtime. There are eleven paid holidays per year.
- Reactor and internals removal activities are performed by using separate crews for different activities working on different shifts, with a corresponding backshift charge for the second shift.
- Multiple crews work parallel activities to the maximum extent possible, consistent with optimum efficiency, adequate access for cutting, removal and laydown space, and with the stringent safety measures necessary during demolition of heavy components and structures.

- For plant systems removal, the systems with the longest removal durations in areas on the critical path are considered to determine the duration of the activity.


## **4.2 PROJECT SCHEDULE**

The period-dependent costs presented in the detailed cost tables are based upon the durations developed in the schedules for decommissioning. Durations are established between several milestones in each project period; these durations are used to establish a critical path for the entire project. In turn, the critical path duration for each period is used as the basis for determining the period-dependent costs. A second critical path is shown for the spent fuel storage period, which determines the release of the Fuel Building for final decontamination.

Project timelines are provided in Figures 4.2 and 4.3 with milestone dates based on a 2024 shutdown date. The fuel pool is emptied approximately five and one-half years after shutdown. Deferred decommissioning in the SAFSTOR scenarios is assumed to commence so that the operating license is terminated within a 60-year period from the cessation of plant operations.




**FIGURE 4.1  
ACTIVITY SCHEDULE**



- Legend:
1. Red text and/or shaded scheduling bars indicate critical path activities
  2. Shaded scheduling bars associated with major decommissioning periods, e.g., Period 1a, indicate overall duration of that period
  3. Blue text and/or diamond symbols indicate major milestones

**FIGURE 4.2**  
**DECOMMISSIONING TIMELINES**  
(not to scale)



## **5. RADIOACTIVE WASTES**

The objectives of the decommissioning process are the removal of all radioactive material from the site that would restrict its future use and the termination of the NRC license. This currently requires the remediation of all radioactive material at the site in excess of applicable legal limits. Under the Atomic Energy Act,<sup>[28]</sup> the NRC is responsible for protecting the public from sources of ionizing radiation. Title 10 of the Code of Federal Regulations delineates the production, utilization, and disposal of radioactive materials and processes. In particular, Part 71 defines radioactive material as it pertains to transportation and Part 61 specifies its disposition.

Most of the materials being transported for controlled burial are categorized as Low Specific Activity (LSA) or Surface Contaminated Object (SCO) materials containing Type A quantities, as defined in 49 CFR Parts 173-178. Shipping containers are required to be Industrial Packages (IP-1, IP-2 or IP-3, as defined in 10 CFR §173.411). For this study, commercially available steel containers are presumed to be used for the disposal of piping, small components, and concrete. Larger components can serve as their own containers, with proper closure of all openings, access ways, and penetrations.

The volumes of radioactive waste generated during the various decommissioning activities at the site are shown on a line-item basis in Appendices C and D, and summarized in Tables 5.1 and 5.2. The quantified waste volume summaries shown in these tables are consistent with Part 61 classifications. The volumes are calculated based on the exterior dimensions for containerized material and on the displaced volume of components serving as their own waste containers.

The reactor vessel and internals are categorized as large quantity shipments and, accordingly, will be shipped in reusable, shielded truck casks with disposable liners. In calculating disposal costs, the burial fees are applied against the liner volume, as well as the special handling requirements of the payload. Packaging efficiencies are lower for the highly activated materials (greater than Type A quantity waste), where high concentrations of gamma-emitting radionuclides limit the capacity of the shipping canisters.

No process system containing/handling radioactive substances at shutdown is presumed to meet material release criteria by decay alone (i.e., systems radioactive at shutdown will still be radioactive over the time period during which the decommissioning is accomplished, due to the presence of long-lived radionuclides).

While the dose rates decrease with time, radionuclides such as  $^{137}\text{Cs}$  will still control the disposition requirements.

The waste material produced in the decontamination and dismantling of the nuclear units is primarily generated during Period 2 of DECON and Period 4 of SAFSTOR. Material that is considered potentially contaminated when removed from the radiological controlled area is sent to processing facilities in Tennessee for conditioning and disposal. Heavily contaminated components and activated materials are routed for controlled disposal. The disposal volumes reported in the tables reflect the savings resulting from reprocessing and recycling.

For purposes of constructing the estimates, the cost for disposal at the *EnergySolutions* facility was used as a proxy for future disposal facilities. Separate rates were used for containerized waste and large components, including the steam generators and reactor coolant pump motors. Demolition debris including miscellaneous steel, scaffolding, and concrete was disposed of at a bulk rate. The decommissioning waste stream also included resins and dry active waste.

Since *EnergySolutions* is not currently able to receive the more highly radioactive components generated in the decontamination and dismantling of the reactor, disposal costs for the Class B and C material were based upon the last published rate schedule for non-compact waste for the Barnwell facility (as a proxy). Additional surcharges were included for activity, dose rate, and/or handling added as appropriate for the particular package.

A small quantity of material generated during the decommissioning will not be considered suitable for near-surface disposal, and is assumed to be disposed of in a geologic repository, in a manner similar to that envisioned for spent fuel disposal. Such material, known as Greater-Than-Class-C or GTCC material, is estimated to require six spent fuel storage canisters (or the equivalent) to dispose of the most radioactive portions of the reactor vessel internals. The volume and weight reported in Tables 5.1 and 5.2 represent the packaged weight and volume of the spent fuel storage canisters.

**TABLE 5.1  
DECON ALTERNATIVE  
DECOMMISSIONING WASTE SUMMARY**

Waste	Cost Basis	Class <sup>[1]</sup>	Waste Volume (cubic feet)	Mass (pounds)
Low-Level Radioactive Waste (near-surface disposal)	EnergySolutions	A	146,443	12,358,063
	Barnwell	B	1,690	191,293
	Barnwell	C	459	48,448
Greater than Class C (geologic repository)	Spent Fuel Equivalent	GTCC	2,142	422,146
Processed/Conditioned (off-site recycling center)	Recycling Vendors	A	281,077	10,863,740
Totals <sup>[2]</sup>			431,812	23,883,690

<sup>[1]</sup> Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

<sup>[2]</sup> Columns may not add due to rounding.

**TABLE 5.2**  
**SAFSTOR ALTERNATIVE**  
**DECOMMISSIONING WASTE SUMMARY**

Waste	Cost Basis	Class <sup>[1]</sup>	Waste Volume (cubic feet)	Mass (pounds)
Low-Level Radioactive Waste (near-surface disposal)	EnergySolutions	A	123,652	9,946,932
	Barnwell	B	376	49,054
	Barnwell	C	470	47,758
Greater than Class C (geologic repository)	Spent Fuel Equivalent	GTCC	2,142	422,146
Processed/Conditioned (off-site recycling center)	Recycling Vendors	A	301,556	11,730,720
Totals <sup>[2]</sup>			428,196	22,196,610

<sup>[1]</sup> Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

<sup>[2]</sup> Columns may not add due to rounding.

## **6. RESULTS**

The analysis to estimate the costs to decommission Callaway relied upon the site-specific, technical information developed for a previous analysis prepared in 2008. While not an engineering study, the estimates provide the plant owner with sufficient information to assess its financial obligations, as they pertain to the eventual decommissioning of the nuclear station.

The estimates described in this report are based on numerous fundamental assumptions, including regulatory requirements, project contingencies, low-level radioactive waste disposal practices, high-level radioactive waste management options, and site restoration requirements. The decommissioning scenarios assume continued operation of the station's spent fuel pool for a minimum of five and one-half years following the cessation of operations for continued cooling of the assemblies. Once sufficiently cooled, the assemblies will be moved to the ISFSI for interim storage and to await transfer to a DOE facility (e.g., geologic repository).

The cost projected to promptly decommission (DECON) Callaway is estimated to be \$754.5 million. The majority of this cost (approximately 81.8%) is associated with the physical decontamination and dismantling of the nuclear unit so that the operating license can be terminated. Another 4.5% is associated with the management, interim storage, and eventual transfer of the spent fuel. The remaining 13.7% is for the demolition of the designated structures and limited restoration of the site.

The cost projected for deferred decommissioning (SAFSTOR) is estimated to be \$1,026.4 million. The majority of this cost (approximately 82.7%) is associated with placing the unit in storage, ongoing caretaking of the unit during dormancy, and the eventual physical decontamination and dismantling of the nuclear unit so that the operating license can be terminated. Another 7.2% is associated with the management, interim storage, and eventual transfer of the spent fuel. The remaining 10.1% is for the demolition of the designated structures and limited restoration of the site.

The primary cost contributors, identified in Tables 6.1 and 6.2, are either labor-related or associated with the management and disposition of the radioactive waste. Program management is the largest single contributor to the overall cost. The magnitude of the expense is a function of both the size of the organization required to manage the decommissioning, as well as the duration of the program. It is assumed, for purposes of this analysis, that Ameren Missouri will oversee the decommissioning program, using a DOC to manage the decommissioning labor force and the associated subcontractors. The size and composition of the management

organization varies with the decommissioning phase and associated site activities. However, once the operating license is terminated, the staff is substantially reduced for the conventional demolition and restoration of the site (for the DECON alternative).

As described in this report, the spent fuel pool will remain operational for a minimum of five and one-half years following the cessation of operations. The pool will be isolated and an independent spent fuel island created. This will allow decommissioning operations to proceed in and around the pool area. Over the five and one-half year period, the spent fuel will be packaged into multi-purpose canisters and transferred to the ISFSI. The ISFSI will continue to operate until such time that the transfer of spent fuel to a DOE facility is complete.

The cost for waste disposal includes only those costs associated with the controlled disposition of the low-level radioactive waste generated from decontamination and dismantling activities, including plant equipment and components, structural material, filters, resins and dry-active waste. As described in Section 5, disposition of the low-level radioactive material required controlled disposal is at the EnergySolutions' facility. Highly activated components, requiring additional isolation from the environment (GTCC), are packaged for geologic disposal. The cost of geologic disposal is based upon a cost equivalent for spent fuel.

A significant portion of the metallic waste is designated for additional processing and treatment at an off-site facility. Processing reduces the volume of material requiring controlled disposal through such techniques and processes as survey and sorting, decontamination, and volume reduction. The material that cannot be unconditionally released is packaged for controlled disposal at one of the currently operating facilities. The cost identified in the summary tables for processing is all-inclusive, incorporating the ultimate disposition of the material.

Removal costs reflect the labor-intensive nature of the decommissioning process, as well as the management controls required to ensure a safe and successful program. Decontamination and packaging costs also have a large labor component that is based upon prevailing union wages. Non-radiological demolition is a natural extension of the decommissioning process. The methods employed in decontamination and dismantling are generally destructive and indiscriminate in inflicting collateral damage. With a work force mobilized to support decommissioning operations, non-radiological demolition can be an integrated activity and a logical expansion of the work being performed in the process of terminating the operating license. Prompt demolition reduces future liabilities and can be more cost effective than deferral, due to the deterioration of the facilities (and therefore the working conditions) with time.



The reported cost for transport includes the tariffs and surcharges associated with moving large components and/or overweight shielded casks overland, as well as the general expense, e.g., labor and fuel, of transporting material to the destinations identified in this report. For purposes of this analysis, material is primarily moved overland by truck.

Decontamination is used to reduce the plant's radiation fields and minimize worker exposure. Slightly contaminated material or material located within a contaminated area is sent to an off-site processing center, i.e., this analysis does not assume that contaminated plant components and equipment can be decontaminated for uncontrolled release in-situ. Centralized processing centers have proven to be a more economical means of handling the large volumes of material produced in the dismantling of a nuclear unit.

License termination survey costs are associated with the labor intensive and complex activity of verifying that contamination has been removed from the site to the levels specified by the regulating agency. This process involves a systematic survey of all remaining plant surface areas and surrounding environs, sampling, isotopic analysis, and documentation of the findings. The status of any plant components and materials not removed in the decommissioning process will also require confirmation and will add to the expense of surveying the facilities alone.

The remaining costs include allocations for heavy equipment and temporary services, as well as for other expenses such as regulatory fees and the premiums for nuclear insurance. While site operating costs are greatly reduced following the final cessation of plant operations, certain administrative functions do need to be maintained either at a basic functional or regulatory level.

**TABLE 6.1**  
**DECON ALTERNATIVE**  
**DECOMMISSIONING COST ELEMENTS**  
(thousands of 2011 dollars)

Cost Element	Total	Percentage
Decontamination	18,215	2.4
Removal	161,612	21.4
Packaging	24,658	3.3
Transportation	13,787	1.8
Waste Disposal	65,642	8.7
Off-site Waste Processing	25,465	3.4
Program Management <sup>[1]</sup>	272,613	36.1
Security	44,414	5.9
Corporate Allocations	40,691	5.4
Spent Fuel Pool Isolation	11,822	1.6
Spent Fuel Management <sup>[2]</sup>	33,726	4.5
Insurance and Regulatory Fees	11,565	1.5
Energy	4,901	0.6
Characterization and Licensing Surveys	15,843	2.1
Property Taxes	2,595	0.3
Miscellaneous Equipment	6,948	0.9
<b>Total <sup>[3]</sup></b>	<b>754,498</b>	<b>100</b>

Cost Element	Total	Percentage
License Termination	617,324	81.8
Spent Fuel Management	33,726	4.5
Site Restoration	103,448	13.7
<b>Total <sup>[3]</sup></b>	<b>754,498</b>	<b>100.0</b>

<sup>[1]</sup> Includes engineering costs

<sup>[2]</sup> Direct costs only. Excludes program management costs (staffing) but includes costs for spent fuel loading/spent fuel pool O&M and Emergency Planning fees

<sup>[3]</sup> Columns may not add due to rounding

**TABLE 6.2**  
**SAFSTOR ALTERNATIVE**  
**DECOMMISSIONING COST ELEMENTS**  
(thousands of 2011 dollars)

Cost Element	Total	Percentage
Decontamination	16,286	1.6
Removal	162,821	15.9
Packaging	18,857	1.8
Transportation	10,639	1.0
Waste Disposal	47,737	4.7
Off-site Waste Processing	27,479	2.7
Program Management <sup>[1]</sup>	364,227	35.5
Security	156,821	15.3
Corporate Allocations	55,341	5.4
Spent Fuel Pool Isolation	11,822	1.2
Spent Fuel Management <sup>[2]</sup>	33,726	3.3
Insurance and Regulatory Fees	53,557	5.2
Energy	10,144	1.0
Characterization and Licensing Surveys	17,246	1.7
Property Taxes	18,943	1.8
Miscellaneous Equipment	20,738	2.0
<b>Total <sup>[3]</sup></b>	<b>1,026,384</b>	<b>100.0</b>

Cost Element	Total	Percentage
License Termination	849,173	82.73
Spent Fuel Management <sup>[4]</sup>	73,749	7.19
Site Restoration	103,462	10.08
<b>Total <sup>[3]</sup></b>	<b>1,026,384</b>	<b>100.0</b>

<sup>[1]</sup> Includes engineering costs

<sup>[2]</sup> Direct costs only. Excludes program management costs (staffing) but includes costs for spent fuel loading/spent fuel pool O&M and Emergency Planning fees

<sup>[3]</sup> Columns may not add due to rounding

<sup>[4]</sup> Includes percentage of Period 2a (dormancy) plant operating costs until spent fuel pool is emptied, in addition to the direct costs.

## **7. REFERENCES**

1. “Decommissioning Cost Analysis for the Callaway Plant,” Document No. A22-1599-002, Rev. 0, TLG Services, Inc., August 2008
2. U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72, "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018 et seq.), June 27, 1988
3. U.S. Nuclear Regulatory Commission, Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors," October 2003
4. U.S. Code of Federal Regulations, Title 10, Part 20, Subpart E, “Radiological Criteria for License Termination”
5. U.S. Code of Federal Regulations, Title 10, Parts 20 and 50, “Entombment Options for Power Reactors,” Advanced Notice of Proposed Rulemaking, Federal Register Volume 66, Number 200, October 16, 2001
6. U.S. Code of Federal Regulations, Title 10, Parts 2, 50 and 51, "Decommissioning of Nuclear Power Reactors," Nuclear Regulatory Commission, Federal Register Volume 61 (p 39278 et seq.), July 29, 1996.
7. “Nuclear Waste Policy Act of 1982 and Amendments,” U.S. Department of Energy’s Office of Civilian Radioactive Management, 1982
8. U.S. Code of Federal Regulations, Title 10, Part 50, “Domestic Licensing of Production and Utilization Facilities,” Subpart 54 (bb), “Conditions of Licenses”
9. “Low Level Radioactive Waste Policy Act,” Public Law 96-573, 1980
10. “Low-Level Radioactive Waste Policy Amendments Act of 1985,” Public Law 99-240, 1986
11. Waste is classified in accordance with U.S. Code of Federal Regulations, Title 10, Part 61.55
12. U.S. Code of Federal Regulations, Title 10, Part 20, Subpart E, “Radiological Criteria for License Termination,” Federal Register, Volume 62, Number 139 (p 39058 et seq.), July 21, 1997

## **7. REFERENCES**

(continued)

13. "Establishment of Cleanup Levels for CERCLA Sites with Radioactive Contamination," EPA Memorandum OSWER No. 9200.4-18, August 22, 1997.
14. U.S. Code of Federal Regulations, Title 40, Part 141.16, "Maximum contaminant levels for beta particle and photon radioactivity from man-made radionuclides in community water systems"
15. "Memorandum of Understanding Between the Environmental Protection Agency and the Nuclear Regulatory Commission: Consultation and Finality on Decommissioning and Decontamination of Contaminated Sites," OSWER 9295.8-06a, October 9, 2002
16. "Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM)," NUREG/CR-1575, Rev. 1, EPA 402-R-97-016, Rev. 1, August 2000
17. T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986
18. W.J. Manion and T.S. LaGuardia, "Decommissioning Handbook," U.S. Department of Energy, DOE/EV/10128-1, November 1980
19. "Building Construction Cost Data 2011," Robert Snow Means Company, Inc., Kingston, Massachusetts
20. Project and Cost Engineers' Handbook, Second Edition, p. 239, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York, 1984
21. U.S. Department of Transportation, Title 49 of the Code of Federal Regulations, "Transportation," Parts 173 through 178
22. Tri-State Motor Transit Company, published tariffs, Interstate Commerce Commission (ICC), Docket No. MC-427719 Rules Tariff, March 2004, Radioactive Materials Tariff, February 2011
23. J.C. Evans et al., "Long-Lived Activation Products in Reactor Materials" NUREG/CR-3474, Pacific Northwest Laboratory for the Nuclear Regulatory Commission, August 1984

## **7. REFERENCES**

(continued)

24. R.I. Smith, G.J. Konzek, W.E. Kennedy, Jr., "Technology, Safety and Costs of Decommissioning a Reference Pressurized Water Reactor Power Station," NUREG/CR-0130 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission, June 1978
25. H.D. Oak, et al., "Technology, Safety and Costs of Decommissioning a Reference Boiling Water Reactor Power Station," NUREG/CR-0672 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission, June 1980
26. "Financial Protection Requirements for Permanently Shutdown Nuclear Power Reactors," 10 CFR Parts 50 and 140, Federal Register Notice, Vol. 62, No. 210, October 30, 1997
27. "Microsoft Project Professional 2011," Microsoft Corporation, Redmond, WA.
28. "Atomic Energy Act of 1954," (68 Stat. 919)

**APPENDIX A**  
**UNIT COST FACTOR DEVELOPMENT**

**APPENDIX A**  
**UNIT COST FACTOR DEVELOPMENT**

Example: Unit Factor for Removal of Contaminated Heat Exchanger < 3,000 lbs.

**1. SCOPE**

Heat exchangers weighing < 3,000 lbs. will be removed in one piece using a crane or small hoist. They will be disconnected from the inlet and outlet piping. The heat exchanger will be sent to the waste processing area.

**2. CALCULATIONS**

Act ID	Activity Description	Activity Duration (minutes)	Critical Duration (minutes)*
a	Remove insulation	60	(b)
b	Mount pipe cutters	60	60
c	Install contamination controls	20	(b)
d	Disconnect inlet and outlet lines	60	60
e	Cap openings	20	(d)
f	Rig for removal	30	30
g	Unbolt from mounts	30	30
h	Remove contamination controls	15	15
i	Remove, wrap, send to waste processing area	<u>60</u>	<u>60</u>
Totals (Activity/Critical)		355	255

Duration adjustment(s):

+ Respiratory protection adjustment (50% of critical duration) 128

+ Radiation/ALARA adjustment (37% of critical duration) 95

Adjusted work duration 478

+ Protective clothing adjustment (30% of adjusted duration) 143

Productive work duration 621

+ Work break adjustment (8.33 % of productive duration) 52

Total work duration (minutes) 673

**\*\*\* Total duration = 11.217 hr \*\*\***

\* alpha designators indicate activities that can be performed in parallel



**APPENDIX A  
(continued)**

**3. LABOR REQUIRED**

Crew	Number	Duration (hours)	Rate (\$/hr)	Cost
Laborers	3.00	11.217	\$40.00	\$1,346.04
Craftsmen	2.00	11.217	\$55.71	\$1,249.80
Foreman	1.00	11.217	\$60.00	\$673.02
General Foreman	0.25	11.217	\$61.00	\$171.06
Fire Watch	0.05	11.217	\$40.00	\$22.43
Health Physics Technician	1.00	11.217	\$44.00	\$493.55
Total Labor Cost				\$3,955.90

**4. EQUIPMENT & CONSUMABLES COSTS**

Equipment Costs	none
Consumables/Materials Costs	
<ul style="list-style-type: none"> <li>• Universal Polypropylene Sorbent 50 @ \$0.56/sq ft <sup>[1]</sup></li> <li>• Tarpaulin, oil resistant, fire retardant 50 @ \$0.41/sq ft <sup>[2]</sup></li> <li>• Gas torch consumables 1 @ \$10.71 x 1 /hr <sup>[3]</sup></li> </ul>	<p>\$28.00</p> <p>\$20.50</p> <p>\$10.71</p>
Subtotal cost of equipment and materials	\$59.21
Overhead & profit on equipment and materials @ 15.30 %	\$8.43
Total costs, equipment & material	\$67.64

**TOTAL COST:**

<b>Removal of contaminated heat exchanger &lt;3000 pounds:</b>	<b>\$4,023.54</b>
Total labor cost:	\$3,955.90
Total equipment/material costs:	\$67.64
Total craft labor man-hours required per unit:	81.88

## **5. NOTES AND REFERENCES**

- Work difficulty factors were developed in conjunction with the Atomic Industrial Forum's (now NEI) program to standardize nuclear decommissioning cost estimates and are delineated in Volume 1, Chapter 5 of the "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.
- References for equipment & consumables costs:
  1. [www.mcmaster.com](http://www.mcmaster.com) online catalog, McMaster Carr Spill Control (7193T88)
  2. R.S. Means (2011) Division 01 56, Section 13.60-0600, page 20
  3. R.S. Means (2011) Division 01 54 33, Section 40-6360, page 664
- Material and consumable costs were adjusted using the regional indices for Columbia, Missouri.

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(DECON: Power Block Structures Only)**

## APPENDIX B

### UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Removal of clean instrument and sampling tubing, \$/linear foot	0.45
Removal of clean pipe 0.25 to 2 inches diameter, \$/linear foot	4.75
Removal of clean pipe >2 to 4 inches diameter, \$/linear foot	6.84
Removal of clean pipe >4 to 8 inches diameter, \$/linear foot	13.53
Removal of clean pipe >8 to 14 inches diameter, \$/linear foot	25.94
Removal of clean pipe >14 to 20 inches diameter, \$/linear foot	33.68
Removal of clean pipe >20 to 36 inches diameter, \$/linear foot	49.57
Removal of clean pipe >36 inches diameter, \$/linear foot	58.91
Removal of clean valve >2 to 4 inches	89.78
Removal of clean valve >4 to 8 inches	135.30
Removal of clean valve >8 to 14 inches	259.42
Removal of clean valve >14 to 20 inches	336.83
Removal of clean valve >20 to 36 inches	495.70
Removal of clean valve >36 inches	589.14
Removal of clean pipe hanger for small bore piping	29.39
Removal of clean pipe hanger for large bore piping	105.22
Removal of clean pump, <300 pound	227.25
Removal of clean pump, 300-1000 pound	635.91
Removal of clean pump, 1000-10,000 pound	2,512.51
Removal of clean pump, >10,000 pound	4,855.69
Removal of clean pump motor, 300-1000 pound	267.30
Removal of clean pump motor, 1000-10,000 pound	1,046.19
Removal of clean pump motor, >10,000 pound	2,353.92
Removal of clean heat exchanger <3000 pound	1,349.70
Removal of clean heat exchanger >3000 pound	3,392.76
Removal of clean feedwater heater/deaerator	9,560.36
Removal of clean moisture separator/reheater	19,650.32
Removal of clean tank, <300 gallons	292.44
Removal of clean tank, 300-3000 gallon	923.97
Removal of clean tank, >3000 gallons, \$/square foot surface area	7.79

## APPENDIX B

### UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Removal of clean electrical equipment, <300 pound	124.28
Removal of clean electrical equipment, 300-1000 pound	435.19
Removal of clean electrical equipment, 1000-10,000 pound	870.37
Removal of clean electrical equipment, >10,000 pound	2,080.03
Removal of clean electrical transformer < 30 tons	1,444.55
Removal of clean electrical transformer > 30 tons	4,160.05
Removal of clean standby diesel generator, <100 kW	1,475.49
Removal of clean standby diesel generator, 100 kW to 1 MW	3,293.38
Removal of clean standby diesel generator, >1 MW	6,817.96
Removal of clean electrical cable tray, \$/linear foot	11.60
Removal of clean electrical conduit, \$/linear foot	5.07
Removal of clean mechanical equipment, <300 pound	124.28
Removal of clean mechanical equipment, 300-1000 pound	435.19
Removal of clean mechanical equipment, 1000-10,000 pound	870.37
Removal of clean mechanical equipment, >10,000 pound	2,080.03
Removal of clean HVAC equipment, <300 pound	150.28
Removal of clean HVAC equipment, 300-1000 pound	522.91
Removal of clean HVAC equipment, 1000-10,000 pound	1,042.15
Removal of clean HVAC equipment, >10,000 pound	2,080.03
Removal of clean HVAC ductwork, \$/pound	0.48
Removal of contaminated instrument and sampling tubing, \$/linear foot	1.39
Removal of contaminated pipe 0.25 to 2 inches diameter, \$/linear foot	20.32
Removal of contaminated pipe >2 to 4 inches diameter, \$/linear foot	34.39
Removal of contaminated pipe >4 to 8 inches diameter, \$/linear foot	54.67
Removal of contaminated pipe >8 to 14 inches diameter, \$/linear foot	106.28
Removal of contaminated pipe >14 to 20 inches diameter, \$/linear foot	127.23
Removal of contaminated pipe >20 to 36 inches diameter, \$/linear foot	175.31
Removal of contaminated pipe >36 inches diameter, \$/linear foot	206.84
Removal of contaminated valve >2 to 4 inches	410.69
Removal of contaminated valve >4 to 8 inches	492.85

## APPENDIX B

### UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Removal of contaminated valve >8 to 14 inches	1,007.40
Removal of contaminated valve >14 to 20 inches	1,277.34
Removal of contaminated valve >20 to 36 inches	1,697.70
Removal of contaminated valve >36 inches	2,013.05
Removal of contaminated pipe hanger for small bore piping	132.03
Removal of contaminated pipe hanger for large bore piping	439.82
Removal of contaminated pump, <300 pound	879.29
Removal of contaminated pump, 300-1000 pound	2,048.94
Removal of contaminated pump, 1000-10,000 pound	6,654.59
Removal of contaminated pump, >10,000 pound	16,203.50
Removal of contaminated pump motor, 300-1000 pound	884.33
Removal of contaminated pump motor, 1000-10,000 pound	2,722.12
Removal of contaminated pump motor, >10,000 pound	6,111.62
Removal of contaminated heat exchanger <3000 pound	4,023.54
Removal of contaminated heat exchanger >3000 pound	11,690.42
Removal of contaminated tank, <300 gallons	1,465.84
Removal of contaminated tank, >300 gallons, \$/square foot	28.52
Removal of contaminated electrical equipment, <300 pound	678.28
Removal of contaminated electrical equipment, 300-1000 pound	1,666.80
Removal of contaminated electrical equipment, 1000-10,000 pound	3,211.02
Removal of contaminated electrical equipment, >10,000 pound	6,344.12
Removal of contaminated electrical cable tray, \$/linear foot	32.70
Removal of contaminated electrical conduit, \$/linear foot	16.33
Removal of contaminated mechanical equipment, <300 pound	754.34
Removal of contaminated mechanical equipment, 300-1000 pound	1,839.92
Removal of contaminated mechanical equipment, 1000-10,000 pound	3,538.68
Removal of contaminated mechanical equipment, >10,000 pound	6,344.12
Removal of contaminated HVAC equipment, <300 pound	754.34
Removal of contaminated HVAC equipment, 300-1000 pound	1,839.92
Removal of contaminated HVAC equipment, 1000-10,000 pound	3,538.68

## APPENDIX B

### UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Removal of contaminated HVAC equipment, >10,000 pound	6,344.12
Removal of contaminated HVAC ductwork, \$/pound	1.98
Removal/plasma arc cut of contaminated thin metal components, \$/linear in.	3.65
Additional decontamination of surface by washing, \$/square foot	7.55
Additional decontamination of surfaces by hydrolasing, \$/square foot	33.34
Decontamination rig hook up and flush, \$/ 250 foot length	6,342.48
Chemical flush of components/systems, \$/gallon	17.41
Removal of clean standard reinforced concrete, \$/cubic yard	134.03
Removal of grade slab concrete, \$/cubic yard	175.15
Removal of clean concrete floors, \$/cubic yard	345.59
Removal of sections of clean concrete floors, \$/cubic yard	1,032.77
Removal of clean heavily rein concrete w/#9 rebar, \$/cubic yard	228.56
Removal of contaminated heavily rein concrete w/#9 rebar, \$/cubic yard	2,006.85
Removal of clean heavily rein concrete w/#18 rebar, \$/cubic yard	288.92
Removal of contaminated heavily rein concrete w/#18 rebar, \$/cubic yard	2,653.13
Removal heavily rein concrete w/#18 rebar & steel embedments, \$/cubic yard	441.58
Removal of below-grade suspended floors, \$/cubic yard	345.59
Removal of clean monolithic concrete structures, \$/cubic yard	855.56
Removal of contaminated monolithic concrete structures, \$/cubic yard	1,995.44
Removal of clean foundation concrete, \$/cubic yard	671.85
Removal of contaminated foundation concrete, \$/cubic yard	1,859.02
Explosive demolition of bulk concrete, \$/cubic yard	29.60
Removal of clean hollow masonry block wall, \$/cubic yard	90.64
Removal of contaminated hollow masonry block wall, \$/cubic yard	297.33
Removal of clean solid masonry block wall, \$/cubic yard	90.64
Removal of contaminated solid masonry block wall, \$/cubic yard	297.33
Backfill of below-grade voids, \$/cubic yard	31.19
Removal of subterranean tunnels/voids, \$/linear foot	107.71
Placement of concrete for below-grade voids, \$/cubic yard	126.91
Excavation of clean material, \$/cubic yard	3.19

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Excavation of contaminated material, \$/cubic yard	39.88
Removal of clean concrete rubble (tipping fee included), \$/cubic yard	22.91
Removal of contaminated concrete rubble, \$/cubic yard	24.11
Removal of building by volume, \$/cubic foot	0.29
Removal of clean building metal siding, \$/square foot	1.08
Removal of contaminated building metal siding, \$/square foot	3.71
Removal of standard asphalt roofing, \$/square foot	2.11
Removal of transite panels, \$/square foot	2.04
Scarifying contaminated concrete surfaces (drill & spall), \$/square foot	12.08
Scabbling contaminated concrete floors, \$/square foot	7.27
Scabbling contaminated concrete walls, \$/square foot	19.08
Scabbling contaminated ceilings, \$/square foot	65.35
Scabbling structural steel, \$/square foot	5.97
Removal of clean overhead crane/monorail < 10 ton capacity	614.39
Removal of contaminated overhead crane/monorail < 10 ton capacity	1,701.23
Removal of clean overhead crane/monorail >10-50 ton capacity	1,474.56
Removal of contaminated overhead crane/monorail >10-50 ton capacity	4,082.25
Removal of polar crane > 50 ton capacity	6,188.09
Removal of gantry crane > 50 ton capacity	26,000.33
Removal of structural steel, \$/pound	0.20
Removal of clean steel floor grating, \$/square foot	4.43
Removal of contaminated steel floor grating, \$/square foot	12.63
Removal of clean free standing steel liner, \$/square foot	11.68
Removal of contaminated free standing steel liner, \$/square foot	33.34
Removal of clean concrete-anchored steel liner, \$/square foot	5.84
Removal of contaminated concrete-anchored steel liner, \$/square foot	38.83
Placement of scaffolding in clean areas, \$/square foot	16.80
Placement of scaffolding in contaminated areas, \$/square foot	26.01
Landscaping with topsoil, \$/acre	28,266.82
Cost of CPC B-88 LSA box & preparation for use	2,113.50



**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Cost of CPC B-25 LSA box & preparation for use	1,933.79
Cost of CPC B-12V 12 gauge LSA box & preparation for use	1,569.88
Cost of CPC B-144 LSA box & preparation for use	10,784.62
Cost of LSA drum & preparation for use	194.44
Cost of cask liner for CNSI 8 120A cask (resins)	7,742.32
Cost of cask liner for CNSI 8 120A cask (filters)	8,101.54
Decontamination of surfaces with vacuuming, \$/square foot	0.75

**APPENDIX C**  
**DETAILED COST ANALYSIS**  
**DECON**

Table C  
Callaway Energy Center  
DECON Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Contingency	Total Contingency	Total Costs	Lic. Term. Costs	NIC Management Costs	Spent Fuel Reservoir Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A			Class B			Burial / Processed Wt. Lbs.	Utility and Contractor Mammals
																Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet		
<b>PERIOD 1a - Shutdown through Transition</b>																							
Period 1a Direct Decommissioning Activities																							
1a.1.1	Prepare preliminary decommissioning cost	-	-	-	-	-	-	152	23	174	174	-	-	-	-	-	-	-	-	-	-	-	1,300
1a.1.2	Notification of Cession of Operations	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1a.1.3	Remove fuel & equipment from site	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1a.1.4	Notification of Permit Deregulation	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1a.1.5	Deactivate plant systems & process waste	-	-	-	-	-	-	233	35	268	268	-	-	-	-	-	-	-	-	-	-	-	2,000
1a.1.6	Prepare and submit PSDAR	-	-	-	-	-	-	537	81	617	617	-	-	-	-	-	-	-	-	-	-	-	4,600
1a.1.7	Review plant dwgs. & specs.	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1a.1.8	Perform detailed rad survey	-	-	-	-	-	-	117	18	134	134	-	-	-	-	-	-	-	-	-	-	-	1,000
1a.1.9	Estimate by-product inventory	-	-	-	-	-	-	18	5	23	23	-	-	-	-	-	-	-	-	-	-	-	1,000
1a.1.10	Final rad description	-	-	-	-	-	-	152	23	174	174	-	-	-	-	-	-	-	-	-	-	-	1,300
1a.1.11	Develop site safety	-	-	-	-	-	-	875	131	1,007	1,007	-	-	-	-	-	-	-	-	-	-	-	7,500
1a.1.12	Define major work sequence	-	-	-	-	-	-	362	54	416	416	-	-	-	-	-	-	-	-	-	-	-	3,100
1a.1.13	Perform SER and EA	-	-	-	-	-	-	584	88	671	671	-	-	-	-	-	-	-	-	-	-	-	5,000
1a.1.14	Perform Site-Specific Cost Study	-	-	-	-	-	-	478	72	550	550	-	-	-	-	-	-	-	-	-	-	-	4,096
1a.1.15	Prepare/submit License Termination Plan	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1a.1.16	Receive NRC approval of termination plan	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Activity Specifications																							
1a.1.17.1	Plant & temporary facilities	-	-	-	-	-	-	574	86	660	594	-	-	-	-	-	-	-	-	-	-	-	4,920
1a.1.17.2	Plant systems	-	-	-	-	-	-	486	73	559	503	-	-	-	-	-	-	-	-	-	-	-	4,167
1a.1.17.3	SSSS Decommissionation Flush	-	-	-	-	-	-	58	9	67	67	-	-	-	-	-	-	-	-	-	-	-	500
1a.1.17.4	Reactor internals	-	-	-	-	-	-	829	124	953	853	-	-	-	-	-	-	-	-	-	-	-	7,100
1a.1.17.5	Biological shield	-	-	-	-	-	-	141	9	150	141	-	-	-	-	-	-	-	-	-	-	-	500
1a.1.17.6	Biological shield	-	-	-	-	-	-	58	9	67	67	-	-	-	-	-	-	-	-	-	-	-	500
1a.1.17.7	Steam generators	-	-	-	-	-	-	364	55	419	419	-	-	-	-	-	-	-	-	-	-	-	3,120
1a.1.17.8	Reinforced concrete	-	-	-	-	-	-	187	28	215	107	-	-	-	-	-	-	-	-	-	-	-	1,600
1a.1.17.9	Main Turbine	-	-	-	-	-	-	47	7	54	-	-	-	-	-	-	-	-	-	-	-	-	400
1a.1.17.10	Main Condensers	-	-	-	-	-	-	354	85	439	269	-	-	-	-	-	-	-	-	-	-	-	3,120
1a.1.17.11	Plant structures & buildings	-	-	-	-	-	-	305	16	321	305	-	-	-	-	-	-	-	-	-	-	-	800
1a.1.17.12	Off-site waste	-	-	-	-	-	-	105	16	121	60	-	-	-	-	-	-	-	-	-	-	-	600
1a.1.17.13	Facility & site cleanup	-	-	-	-	-	-	4,415	662	5,077	4,471	-	-	-	-	-	-	-	-	-	-	-	37,827
1a.1.17	Total	-	-	-	-	-	-	4,415	662	5,077	4,471	-	-	-	-	-	-	-	-	-	-	-	37,827
Planning & Site Preparations																							
1a.1.18	Prepare dismantling sequence	-	-	-	-	-	-	280	42	322	322	-	-	-	-	-	-	-	-	-	-	-	2,400
1a.1.19	Plant prep. & temp. access	-	-	-	-	-	-	2,800	40	3,240	3,240	-	-	-	-	-	-	-	-	-	-	-	1,400
1a.1.20	Site preparation	-	-	-	-	-	-	2,200	330	2,530	2,530	-	-	-	-	-	-	-	-	-	-	-	1,400
1a.1.21	Rigging/Cont. Cont. Erection/cooling/etc.	-	-	-	-	-	-	144	22	165	165	-	-	-	-	-	-	-	-	-	-	-	1,230
1a.1.22	Procure casks/liners & containers	-	-	-	-	-	-	13,608	2,041	15,650	15,043	-	-	-	-	-	-	-	-	-	-	-	73,753
1a.1	Subtotal Period 1a Activity Costs	-	-	-	-	-	-	13,608	2,041	15,650	15,043	-	-	-	-	-	-	-	-	-	-	-	73,753
Period 1a Colateral Costs																							
1a.3.1	Spent Fuel Capital and Transfer	-	-	-	-	-	-	3,690	540	4,140	-	-	-	-	-	-	-	-	-	-	-	-	-
1a.3	Subtotal Period 1a Colateral Costs	-	-	-	-	-	-	3,690	540	4,140	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 1a Period-Dependent Costs																							
1a.4.1	Insurance	-	-	-	-	-	-	1,589	159	1,747	1,747	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.2	Property taxes	-	-	-	-	-	-	280	28	308	308	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.3	Health physics supplies	-	-	-	-	-	-	-	113	967	967	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.4	Heavy equipment rental	-	-	-	-	-	-	466	35	502	502	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.5	Dismantling of DAW	-	-	-	-	-	-	28	53	81	81	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.6	Plant energy budget	-	-	-	-	-	-	724	109	832	832	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.7	NRC Fees	-	-	-	-	-	-	769	77	846	846	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.8	Emergency Planning Fees	-	-	-	-	-	-	1,351	135	1,486	1,486	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.9	INPO Fees	-	-	-	-	-	-	289	43	332	332	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.10	Spent Fuel Post O&M	-	-	-	-	-	-	763	114	878	878	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.11	Spent Fuel On-site Storage Costs	-	-	-	-	-	-	3,510	35	3,545	3,545	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.12	Construction Allowance	-	-	-	-	-	-	33	33	66	66	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.13	Security Staff Cost	-	-	-	-	-	-	6,892	1,034	7,926	7,926	-	-	-	-	-	-	-	-	-	-	-	-
1a.4.14	Utility Staff Cost	-	-	-	-	-	-	28,091	4,214	32,305	32,305	-	-	-	-	-	-	-	-	-	-	-	-
1a.4	Subtotal Period 1a Period-Dependent Costs	-	-	-	-	-	-	890	13	903	903	-	-	-	-	-	-	-	-	-	-	-	-
1a.0	TOTAL PERIOD 1a COST	-	-	-	-	-	-	61,555	9,046	71,555	64,322	-	-	-	-	-	-	-	-	-	-	-	654,624

Table C  
Callaway Energy Center  
DECON Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	Lic. Term. Costs	NRC Management Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A			Class B			Burial / Processed Wt. Lbs.	Craft Mammals	Utility and Contractor Mammals
																Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet			
PERIOD 1b - Decommissioning Preparations																								
Period 1b Direct Decommissioning Activities																								
Detailed Work Procedures																								
Bb.1.1	SSS Decontamination	-	-	-	-	-	-	552	83	635	-	572	-	-	-	-	-	-	-	-	-	-	4,533	
Bb.1.1.1	SSS Decontamination	-	-	-	-	-	-	117	18	134	-	134	-	-	-	-	-	-	-	-	-	-	1,000	
Bb.1.1.2	SSS Decontamination Flush	-	-	-	-	-	-	292	44	336	-	336	-	-	-	-	-	-	-	-	-	-	2,500	
Bb.1.1.3	Reactor internals	-	-	-	-	-	-	158	24	181	-	181	-	-	-	-	-	-	-	-	-	-	1,350	
Bb.1.1.4	Remaining buildings	-	-	-	-	-	-	117	18	134	-	134	-	-	-	-	-	-	-	-	-	-	1,000	
Bb.1.1.5	CRD cooling assembly	-	-	-	-	-	-	117	18	134	-	134	-	-	-	-	-	-	-	-	-	-	1,000	
Bb.1.1.6	CRD housings & ICI tubes	-	-	-	-	-	-	117	18	134	-	134	-	-	-	-	-	-	-	-	-	-	1,000	
Bb.1.1.7	Incore instrumentation	-	-	-	-	-	-	140	21	161	-	161	-	-	-	-	-	-	-	-	-	-	1,000	
Bb.1.1.8	Incore shield	-	-	-	-	-	-	53	8	60	-	60	-	-	-	-	-	-	-	-	-	-	450	
Bb.1.1.9	Facility abatement	-	-	-	-	-	-	140	21	161	-	161	-	-	-	-	-	-	-	-	-	-	1,200	
Bb.1.1.10	Miss-site shields	-	-	-	-	-	-	537	81	617	-	617	-	-	-	-	-	-	-	-	-	-	4,600	
Bb.1.1.11	Biological shield	-	-	-	-	-	-	117	18	134	-	134	-	-	-	-	-	-	-	-	-	-	1,000	
Bb.1.1.12	Steam generators	-	-	-	-	-	-	182	27	209	-	209	-	-	-	-	-	-	-	-	-	-	1,500	
Bb.1.1.13	Reinforced concrete	-	-	-	-	-	-	319	48	366	-	366	-	-	-	-	-	-	-	-	-	-	2,700	
Bb.1.1.14	Main Turbine	-	-	-	-	-	-	319	48	366	-	366	-	-	-	-	-	-	-	-	-	-	2,700	
Bb.1.1.15	Steam generators	-	-	-	-	-	-	319	48	366	-	366	-	-	-	-	-	-	-	-	-	-	2,700	
Bb.1.1.16	Auxiliary building	-	-	-	-	-	-	582	83	665	-	665	-	-	-	-	-	-	-	-	-	-	33,243	
Bb.1.1.17	Reactor building	-	-	-	-	-	-	582	83	665	-	665	-	-	-	-	-	-	-	-	-	-	33,243	
Bb.1.1	Total	600	-	-	-	-	-	3,880	582	4,462	-	4,462	-	-	-	-	-	-	-	-	-	-	1,067	
Bb.1.2	Decom primary loop	600	-	-	-	-	-	-	882	5,362	-	5,362	-	-	-	-	-	-	-	-	-	-	1,067	
Bb.1	Subtotal Period 1b Activity Costs	600	-	-	-	-	-	3,880	882	5,362	-	5,362	-	-	-	-	-	-	-	-	-	-	1,067	
Period 1b Additional Costs																								
Bb.2.1	Spent fuel pool isolation	-	-	-	-	-	-	10,280	1,542	11,822	-	11,822	-	-	-	-	-	-	-	-	-	-	-	
Bb.2.2	Site Characterization	-	-	-	-	-	-	2,551	765	3,316	-	3,316	-	-	-	-	-	-	-	-	-	-	19,100	
Bb.2	Subtotal Period 1b Additional Costs	-	-	-	-	-	-	12,830	2,307	15,137	-	15,137	-	-	-	-	-	-	-	-	-	-	7,852	
Period 1b Collateral Costs																								
Bb.3	Collateral Costs	872	-	-	-	-	-	-	131	1,003	-	1,003	-	-	-	-	-	-	-	-	-	-	-	
Bb.3.1	DOC staff relocation expenses	-	-	-	-	-	-	1,080	162	1,242	-	1,242	-	-	-	-	-	-	-	-	-	-	-	
Bb.3.2	DOC staff relocation expenses	-	-	-	-	-	-	99	59	291	-	291	-	-	-	-	-	-	-	-	-	-	55	
Bb.3.3	Process decommissioning water waste	45	-	-	18	-	-	-	772	3,987	-	3,987	-	-	-	-	-	-	-	-	-	-	16,989	
Bb.3.4	Process decommissioning chemical flush waste	2	-	-	49	-	-	-	0	2	-	2	-	-	-	-	-	-	-	-	-	-	83,917	
Bb.3.5	Small tool allowance	-	-	-	-	-	-	-	165	1,265	-	1,265	-	-	-	-	-	-	-	-	-	-	147	
Bb.3.6	Pipe cutting equipment	-	-	-	-	-	-	-	255	1,725	-	1,725	-	-	-	-	-	-	-	-	-	-	-	
Bb.3.7	Spec. rig	1,500	-	-	-	-	-	1,680	255	1,935	-	1,935	-	-	-	-	-	-	-	-	-	-	-	
Bb.3.8	Spec. rig	-	-	-	-	-	-	1,680	255	1,935	-	1,935	-	-	-	-	-	-	-	-	-	-	-	
Bb.3.9	Spec. rig	-	-	-	-	-	-	1,680	255	1,935	-	1,935	-	-	-	-	-	-	-	-	-	-	-	
Bb.3	Subtotal Period 1b Collateral Costs	2,419	1,102	-	67	313	-	3,020	1,757	11,447	-	11,447	-	-	-	-	-	-	-	-	-	-	203	
Period 1b Period-Dependent Costs																								
Bb.4.1	Decom supplies	27	-	-	-	-	-	-	7	34	-	34	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.2	Insurance	-	-	-	-	-	-	801	80	881	-	881	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.3	Property taxes	-	-	-	-	-	-	141	64	205	-	205	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.4	Heavy equipment	-	-	-	-	-	-	257	64	321	-	321	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.5	Heavy equipment rental	-	-	-	-	-	-	220	33	253	-	253	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.6	Disposal of DAW generated	-	-	-	1	-	-	-	5	31	-	31	-	-	-	-	-	-	-	-	-	-	12	
Bb.4.7	Plant energy budget	-	-	-	-	-	-	790	109	839	-	839	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.8	NRC Fees	-	-	-	-	-	-	388	39	426	-	426	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.9	Emergency Planning Fees	-	-	-	-	-	-	681	68	749	-	749	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.10	Emergency Planning Fees	-	-	-	-	-	-	388	39	426	-	426	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.11	Emergency Planning Fees	-	-	-	-	-	-	681	68	749	-	749	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.12	Corporate Allocations	-	-	-	-	-	-	324	32	356	-	356	-	-	-	-	-	-	-	-	-	-	-	
Bb.4.13	Security Staff Cost	-	-	-	-	-	-	3,474	521	3,995	-	3,995	-	-	-	-	-	-	-	-	-	-	79,383	
Bb.4.14	DOC Staff Cost	-	-	-	-	-	-	5,700	863	6,563	-	6,563	-	-	-	-	-	-	-	-	-	-	64,137	
Bb.4.15	Utility Staff Cost	-	-	-	-	-	-	14,237	2,136	16,373	-	16,373	-	-	-	-	-	-	-	-	-	-	214,491	
Bb.4	Subtotal Period 1b Period-Dependent Costs	27	476	-	8	1	-	17	29,872	4,327	34,728	33,485	1,243	-	-	-	-	-	-	-	-	-	12	
Bb.0	TOTAL PERIOD 1b COST	3,045	1,578	-	75	314	-	3,037	49,342	9,283	66,675	62,660	3,175	839	-	-	-	-	-	-	-	-	399,106	
PERIOD 1 TOTALS																								
Subtotal Period 1b Activity Costs		3,045	2,468	-	88	317	-	3,065	110,897	18,329	138,210	126,982	9,782	1,446	-	-	-	-	-	-	-	-	20,401	
Subtotal Period 1b Additional Costs		-	-	-	-	-	-	12,830	2,307	15,137	-	15,137	-	-	-	-	-	-	-	-	-	-	7,852	
Subtotal Period 1b Collateral Costs		2,419	1,102	-	67	313	-	3,020	1,757	11,447	-	11,447	-	-	-	-	-	-	-	-	-	-	203	
Subtotal Period 1b Period-Dependent Costs		27	476	-	8	1	-	17	29,872	4,327	34,728	33,485	1,243	-	-	-	-	-	-	-	-	-	12	
TOTAL PERIOD 1b COST		3,045	2,468	-	88	317	-	3,065	110,897	18,329	138,210	126,982	9,782	1,446	-	-	-	-	-	-	-	-	20,401	

Table C  
Callaway Energy Center  
DECON Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	OFF-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	LIC. Term. Costs	NRC Management Costs	Spent Fuel Management Costs	Site Remediation Costs	Processed Volume Cu. Feet	Class A		Class B		Burial/Processed Wt. Lbs.	Craft Mammals	Utility and Contractor Mammals
																Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet			
<b>PERIOD 2a - Large Component Removal</b>																						
Period 2a Direct Decommissioning Activities																						
Nuclear Steam Supply System Removal																						
2a.1.1.1	Minor Component Removal	176	188	95	97	-	963	229	1,032	1,032	-	-	-	-	-	-	1,997	-	-	146,300	6,838	-
2a.1.1.2	Reactor Relief Tank	30	25	7	8	-	94	47	211	211	-	-	-	-	-	-	328	-	-	36,305	1,088	-
2a.1.1.3	Reactor Coolant Pumps & Motors	90	94	79	188	-	889	327	1,669	1,669	-	-	-	-	-	-	3,886	-	-	816,140	4,188	100
2a.1.1.4	Pressurizer	44	56	3,067	1,45	2,549	6,084	4,027	23,635	23,635	-	-	-	-	40,262	-	3,739	-	-	267,383	2,470	1,875
2a.1.1.5	Steam Generators	373	4,385	2,252	2,497	2,549	5,918	2,462	15,678	15,678	-	-	-	-	40,262	-	22,546	-	-	3,370,150	23,233	3,500
2a.1.1.6	Retired Steam Generator Units	149	83	237	47	823	223	921	321	321	-	-	-	-	-	-	3,881	-	-	10,800	2,250	-
2a.1.1.7	CRDMs/ICIS/Service Structure Removal	116	3,259	9,360	1,371	-	9,360	1,631	12,455	12,455	-	-	-	-	-	-	1,377	903	469	80,025	4,285	1,316
2a.1.1.8	Reactor Vessel	83	6,218	2,113	838	-	10,743	6,530	18,144	18,144	-	-	-	-	-	-	8,735	-	-	954,909	29,600	1,316
2a.1.1.9	Reactor Vessel	1,061	14,888	17,879	7,661	5,098	35,627	25,152	107,900	107,900	-	-	-	-	80,623	-	68,436	903	459	9,968,791	112,983	10,357
2a.1.1	Totals	-	501	420	85	795	508	441	2,810	2,810	-	-	-	-	4,921	-	2,740	-	-	626,627	9,888	-
2a.1.2	Main Turbine/Generator	-	1,469	220	69	700	531	622	3,852	3,852	-	-	-	-	7,701	-	2,412	-	-	631,964	27,762	-
2a.1.3	Main Condensers	-	502	457	-	-	-	135	1,037	1,037	-	-	-	-	-	-	-	-	-	-	10,575	-
2a.1.4.1	Reactor	-	457	-	-	-	-	69	525	525	-	-	-	-	-	-	-	-	-	-	5,551	-
2a.1.4.2	Auxiliary	-	1	0	1	-	-	0	1	1	-	-	-	-	-	-	-	-	-	-	16	-
2a.1.4.3	Hot Machine Shop	-	96	-	4	-	-	169	169	169	-	-	-	-	-	-	-	-	-	-	1,108	-
2a.1.4.4	Refuse	-	292	-	33	-	-	33	325	325	-	-	-	-	-	-	-	-	-	-	2,250	-
2a.1.4.5	Building	-	1,675	-	-	-	-	251	1,826	1,826	-	-	-	-	-	-	-	-	-	-	13,645	-
2a.1.4	Totals	-	705	11	26	626	47	275	1,644	1,644	-	-	-	-	7,629	-	211	-	-	309,812	13,471	-
2a.1.5.1	100 Aux Bldg Non-System Specific	-	115	5	5	39	39	47	258	258	-	-	-	-	310	-	-	-	-	37,227	2,280	-
2a.1.5.2	100 Auxiliary Bldg Non-System Specific	-	270	-	7	177	177	40	310	310	-	-	-	-	305	-	-	-	-	87,550	9,833	-
2a.1.5.3	AB - Main Steam	-	295	3	3	-	-	46	305	305	-	-	-	-	-	-	-	-	-	-	5,641	-
2a.1.5.4	AC - Main Turbine	-	293	-	-	-	-	44	337	337	-	-	-	-	-	-	-	-	-	-	6,144	-
2a.1.5.5	AD - Condensate	-	202	-	-	-	-	30	232	232	-	-	-	-	-	-	-	-	-	-	4,271	-
2a.1.5.6	AE - Feedwater	-	249	-	-	-	-	37	286	286	-	-	-	-	-	-	-	-	-	-	5,352	-
2a.1.5.7	AF - Feedwater Heater Extraction	-	92	-	-	-	-	14	105	105	-	-	-	-	-	-	-	-	-	-	1,944	-
2a.1.5.8	AG - Condensate Demineralizer	-	40	-	-	-	-	6	35	35	-	-	-	-	-	-	-	-	-	-	868	-
2a.1.5.9	AH - Auxiliary Feedwater	-	121	-	-	-	-	9	26	26	-	-	-	-	-	-	-	-	-	-	1,344	-
2a.1.5.10	AI - Auxiliary Feedwater	-	40	-	-	-	-	6	35	35	-	-	-	-	-	-	-	-	-	-	868	-
2a.1.5.11	AJ - Auxiliary Feedwater	-	40	-	-	-	-	6	35	35	-	-	-	-	-	-	-	-	-	-	868	-
2a.1.5.12	AK - Steam Generator Blowdown - RCA	-	380	6	14	337	337	148	885	885	-	-	-	-	-	-	147	-	-	48,384	2,392	-
2a.1.5.13	AL - Steam Generator Blowdown - RCA	-	343	17	26	452	452	181	1,107	1,107	-	-	-	-	-	-	433	-	-	166,857	7,095	-
2a.1.5.14	AN - Borated Refueling Water Storage	-	21	-	-	-	-	3	24	24	-	-	-	-	-	-	-	-	-	257,752	6,935	-
2a.1.5.15	AO - Steam Seal	-	60	-	-	-	-	9	69	69	-	-	-	-	-	-	-	-	-	-	45	-
2a.1.5.16	AP - Main Turbine Lube Oil	-	10	-	-	-	-	1	11	11	-	-	-	-	-	-	-	-	-	-	1,207	-
2a.1.5.17	AQ - Generator Hydrogen Seal & CO2	-	10	-	-	-	-	1	11	11	-	-	-	-	-	-	-	-	-	-	1,207	-
2a.1.5.18	AR - Generator Hydrogen Seal	-	16	-	-	-	-	2	16	16	-	-	-	-	-	-	-	-	-	-	287	-
2a.1.5.19	AS - Strator Cooling Water	-	12	-	-	-	-	2	14	14	-	-	-	-	-	-	-	-	-	-	211	-
2a.1.5.20	AT - Lube Oil Storage Xftr & Purification	-	39	-	-	-	-	6	44	44	-	-	-	-	-	-	-	-	-	-	812	-
2a.1.5.21	AG - Condenser Air Removal	-	61	-	-	-	-	5	36	36	-	-	-	-	-	-	-	-	-	-	697	-
2a.1.5.22	CH - Main Turbine Control Oil	-	349	-	-	-	-	9	70	70	-	-	-	-	-	-	-	-	-	-	1,219	-
2a.1.5.23	DA - Circulating Water	-	52	-	-	-	-	9	68	68	-	-	-	-	-	-	-	-	-	-	7,692	-
2a.1.5.24	DB - Cooling Tower Blowdown & Blowdown	-	52	-	-	-	-	9	68	68	-	-	-	-	-	-	-	-	-	-	7,692	-
2a.1.5.25	DD - Cooling Tower Blowdown & Blowdown	-	52	-	-	-	-	9	68	68	-	-	-	-	-	-	-	-	-	-	7,692	-
2a.1.5.26	DE - Cooling Tower Blowdown & Blowdown	-	52	-	-	-	-	9	68	68	-	-	-	-	-	-	-	-	-	-	7,692	-
2a.1.5.27	DF - Residual Heat Removal	-	290	5	12	292	292	116	706	706	-	-	-	-	-	-	-	-	-	-	1,084	-
2a.1.5.28	EG - Residual Heat Removal	-	401	44	39	225	398	244	1,352	1,352	-	-	-	-	-	-	-	-	-	-	4,931	-
2a.1.5.29	EH - High Pressure Coolant Injection	-	340	14	13	208	208	131	712	712	-	-	-	-	-	-	-	-	-	-	265,217	8,021
2a.1.5.30	EE - Containment Spray	-	223	5	10	148	148	95	581	581	-	-	-	-	-	-	-	-	-	-	6,626	-
2a.1.5.31	EF - Accumulator Safety Injection	-	177	8	9	131	131	47	1,599	1,599	-	-	-	-	-	-	-	-	-	-	4,134	-
2a.1.5.32	FG - Auxiliary Steam Generator	-	98	-	-	-	-	15	112	112	-	-	-	-	-	-	-	-	-	-	82,910	3,475
2a.1.5.33	FH - Auxiliary Steam Generator	-	84	1	3	67	67	32	187	187	-	-	-	-	-	-	-	-	-	-	2,106	-
2a.1.5.34	FI - Auxiliary Turbines	-	63	-	-	-	-	9	73	73	-	-	-	-	-	-	-	-	-	-	33,148	1,537
2a.1.5.35	FJ - Auxiliary Steam Chemical Addition	-	180	-	-	-	-	1	6	6	-	-	-	-	-	-	-	-	-	-	1,320	-
2a.1.5.36	GK - Turbine Building HVAC	-	78	3	4	54	54	27	207	207	-	-	-	-	-	-	-	-	-	-	1,05	-
2a.1.5.37	GL - Containment Hydrogen Control	-	314	-	-	213	213	416	1,513	1,513	-	-	-	-	-	-	-	-	-	-	33,357	1,398
2a.1.5.38	HE - Boron Recycle	-	580	31	26	213	213	416	1,513	1,513	-	-	-	-	-	-	-	-	-	-	16,649	-

Table C  
Callaway Energy Center  
DECON Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	Lic. Term. Costs	NRC Management Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A			Class B			Class C			Burial/Processed Wt. Lbs.	Craft Mammals	Utility and Contractor Manhours					
																Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet				Cu. Feet	Cu. Feet			
Disposal of Plant Systems (continued)																																
2a.1.5.39	HF - Secondary Liquid Waste	697	1,008	70	61	507	528	-	825	3,696	3,696	3,696	-	-	6,186	2,619	-	-	-	-	-	-	-	-	-	-	454,900	31,872	-			
2a.1.5.40	JA - Auxiliary Oil & Transfer	-	32	-	-	-	-	5	37	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	690	-	-			
2a.1.5.41	KS - Bulk Chemical Storage	-	92	10	22	529	-	-	107	700	760	-	-	-	6,449	-	-	-	-	-	-	-	-	-	-	-	261,800	1,825	-			
2a.1.5.42	LE - Oil Waste	-	181	-	-	-	-	27	208	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3,865	-	-			
2a.1.5.43	OB - Waste RCA	-	44	-	8	185	-	-	113	863	510	-	-	-	2,256	-	-	-	-	-	-	-	-	-	-	-	91,628	-	-			
2a.1.5.44	TR - Waste RCA	-	75	-	-	-	-	-	113	863	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	14,405	-	-			
2a.1.5.44	TR - Waste RCA - Non-System Specific	1,077	8,657	242	291	4,264	1,495	-	3,437	19,464	15,471	-	-	-	3,993	7,167	-	-	-	-	-	-	-	-	-	-	2,687,951	192,092	-			
2a.1.6	Scaffolding in support of decommissioning	-	1,600	28	6	112	18	-	425	2,189	2,189	-	-	-	1,233	82	-	-	-	-	-	-	-	-	-	-	62,415	36,741	-			
2a.1	Subtotal Period 2a Activity Costs	2,139	25,730	15,790	8,113	10,989	38,259	533	30,328	137,841	133,348	-	-	-	3,993	146,354	80,857	903	459	2,142	13,897,350	398,120	-	-	-	-	-	-	10,357			
Period 2a Catalytic Costs																																
2a.3.1	Process decommissioning water waste	198	-	82	313	-	443	-	265	1,300	1,300	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2a.3.2	Process decommissioning chemical flush waste	1	-	25	127	-	254	-	85	492	492	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2a.3.3	Small tool allowance	-	348	-	-	-	-	5,520	828	6,348	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2a.3.4	Spent Fuel Capital and Transfer	-	-	-	-	-	-	62	6	68	68	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2a.3.5	On-site survey and release of 90.37 tons clean metallic waste	-	-	-	-	-	697	5,362	1,237	8,659	2,221	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2a.3	Subtotal Period 2a Catalytic Costs	199	348	107	440	-	697	5,362	1,237	8,659	2,221	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
Period 2a Period-Dependent Costs																																
2a.4.1	Decom supplies	83	-	-	-	-	-	21	104	104	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2a.4.2	Insurance	-	-	-	-	-	-	916	916	1,008	1,008	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.3	Property taxes	-	-	-	-	-	-	437	44	481	433	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.4	Health physics supplies	-	2,389	-	-	-	-	600	2,989	2,989	48	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.5	Transportation	-	2,964	-	-	-	-	85	3,049	3,049	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.6	Disposal of DAW generated	-	-	127	22	-	275	-	85	609	609	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.7	Plant energy budget	-	-	-	-	-	-	1,074	1,120	1,232	1,232	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2a.4.8	NRC Fees	-	-	-	-	-	-	1,425	142	1,567	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.9	Emergency Planning Fees	-	-	-	-	-	-	303	35	348	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.10	Spent Fuel Pool O&M	-	-	-	-	-	-	1,192	179	1,371	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.11	Spent Fuel Pool O&M	-	-	-	-	-	-	303	35	348	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.12	Spent Fuel Pool O&M	-	-	-	-	-	-	1,192	179	1,371	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.13	Spent Fuel Pool O&M	-	-	-	-	-	-	303	35	348	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.14	Corporate Allocations	-	-	-	-	-	-	11,970	1,197	13,167	13,167	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.15	Security Staff Cost	-	-	-	-	-	-	9,273	1,391	10,664	10,664	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4.16	DOC Staff Cost	-	-	-	-	-	-	21,806	3,271	25,077	25,077	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.4	Subtotal Period 2a Period-Dependent Costs	83	5,363	127	22	-	275	80,901	12,492	99,263	96,117	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2a.0	TOTAL PERIOD 2a COST	2,420	34,441	19,924	8,575	10,989	39,211	87,017	44,057	245,714	232,186	-	-	-	4,081	146,354	88,428	903	459	2,142	14,135,470	398,637	-	-	-	-	-	-	-	-		
PERIOD 2b - Site Decontamination																																
Period 2b Direct Decommissioning Activities																																
Disposal of Plant Systems																																
2b.1.1.1	200 Reactor Bldg Non-System Specific	-	93	3	3	22	31	-	35	187	187	-	-	-	369	139	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.2	200 Reactor Bldg Non-System Specific	-	583	7	16	391	-	-	298	1,205	1,205	-	-	-	4,768	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.3	300 Control Bldg Non-System Specific	-	181	3	7	175	-	-	73	440	440	-	-	-	2,139	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.4	300 Control Bldg Non-System Specific	-	1,382	-	-	-	-	-	207	1,689	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.5	700 Radwaste Bldg Non-System Specific	-	1,163	19	43	1,041	-	-	455	2,721	2,721	-	-	-	12,684	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.6	700 Radwaste Bldg Non-System Specific	-	1,986	9	9	58	82	-	78	421	421	-	-	-	705	372	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.7	700 Radwaste Bldg Non-System Specific	-	133	-	-	-	-	-	176	315	315	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.8	700 Radwaste Bldg Non-System Specific	-	43	-	-	-	-	-	14	83	83	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.9	AP - Condensate Storage & Transfer	-	89	0	26	-	-	-	13	103	103	-	-	-	314	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.10	BB - Reactor Coolant System	-	345	33	27	149	277	-	185	1,016	1,016	-	-	-	1,812	1,437	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.11	BG - Chemical & Volume Control	767	984	93	78	405	813	-	915	4,055	4,055	-	-	-	4,431	3,705	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.12	BL - Reactor Makeup Water	-	312	20	17	158	140	-	141	788	788	-	-	-	1,928	720	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.13	DE - Intake & Water Treatment	-	121	-	-	-	-	18	140	140	140	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.14	DF - Intake & Water Treatment	-	146	-	-	-	-	25	148	148	148	-	-	-	11,923	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.15	EA - Service Water RCA	-	46	2	4	102	-	-	28	182	182	-	-	-	1,248	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.16	EA - Service Water RCA	-	59	-	-	-	-	9	68	68	68	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2b.1.1.17	EB - Closed Cooling Water	-	337	-	-	-	-	51	388																							

**Table C**  
**Callaway Energy Center**  
**DECON Decommissioning Cost Estimate**  
(thousands of 2011 dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	NIC Lic. Term. Costs	Spent Fuel Management Costs	Site Remediation Costs	Processed Volume Cu. Feet	Class A			Class B			Class C			Burial / Processed Wt. lbs.	Craft Mammals	Utility and Contractor Mammals						
															Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet				Cu. Feet	Cu. Feet				
Disposal of Plant Systems (continued)																																
2b.1.1.22	GA - Plant Heating RCA		99		1	2	52		33	187	187			638													25,924		1,705			
2b.1.1.23	GB - Central Chilled Water		83		0	15	15		12	96	96			96														1,803				
2b.1.1.24	GB - Central Chilled Water RCA		27		0	1	1		9	52	52			187														7,591		452		
2b.1.1.25	GD - Essential Steam Wtr. Pumphouse HVAC		19		0	3	3		22	53	53			22														89,509		427		
2b.1.1.26	GH - Backbuilding HVAC		185		3	7	197		45	693	693			2,624														104,709		5,454		
2b.1.1.27	GH - Backbuilding HVAC		185		5	10	199		89	496	496			2,423															3,959			
2b.1.1.28	GK - Control Building HVAC		175		0	0	0		26	201	201			201															8,450			
2b.1.1.29	GL - Auxiliary Building HVAC		457		11	20	415		190	1,132	1,132			5,064															3,401.76		695	
2b.1.1.30	GM - Diesel Generator Building HVAC		30		0	0	0		5	35	35			7,387														23,570		790		
2b.1.1.31	GN - Containment Cooling		510		21	33	604		252	1,526	1,526			1,580															89,988		2,237	
2b.1.1.32	GP - Containment Ingrand Leak Rate Test		40		1	2	48		17	108	108			1,948															400.250		30,882	
2b.1.1.33	GP - Containment Ingrand Leak Rate Test		40		1	2	48		17	108	108			1,948															180,557		7,433	
2b.1.1.34	GT - Containment Purging HVAC		119		6	9	128		63	384	384			881															2,890		1,289	
2b.1.1.35	HA - Gaseous Radwaste	761	366		19	18	110		158	898	898			2,782															32,538		2,330	
2b.1.1.36	HB - Liquid Radwaste		888		64	53	456		798	3,472	3,472			5,560															402		8,376	
2b.1.1.37	HC - Solid Radwaste		381		29	26	173		189	1,044	1,044			1,114															179,151		7,064	
2b.1.1.38	HD - Decontamination		105		5	6	81		28	214	214			983															10,059		5,837	
2b.1.1.39	JE - Emergency Fuel Oil		62		0	0	0		9	72	72			661															38,924		374	
2b.1.1.40	KA - Compressed Air		132		0	0	0		49	246	246			65															1,226		1,226	
2b.1.1.41	KA - Compressed Air RCA		132		0	0	0		49	246	246			65															98,813		4,481	
2b.1.1.42	KB - Breathing Air		24		1	3	66		4	28	28			801															516		516	
2b.1.1.43	KB - Breathing Air RCA		24		1	3	66		4	28	28			801															402		8,376	
2b.1.1.44	KC - Fire Protection		382		0	0	0		6	32	32			71															2,874		2,874	
2b.1.1.45	KC - Fire Protection RCA		382		0	0	0		6	32	32			71															179,151		7,064	
2b.1.1.46	KD - Domestic Water		177		0	0	0		27	204	204			247															10,059		5,837	
2b.1.1.47	KE - Roof Drains RCA		15		0	1	30		20	127	127			661															38,924		374	
2b.1.1.48	KE - Roof Handling & Storage Error vsl		19		3	4	54		26	127	127			661															1,226		1,226	
2b.1.1.49	KH - Service Gas (CO2 N2 H2 & O2)		56		0	0	0		8	65	65			2,433															98,813		4,481	
2b.1.1.50	KH - Service Gas (CO2 N2 H2 & O2) RCA		56		0	0	0		8	65	65			2,433															6,749		6,749	
2b.1.1.51	KJ - Standby Diesel Engine		330		0	0	0		50	380	380			380															51,684		1,811	
2b.1.1.52	LA - Sanitary Drains		45		0	0	0		7	52	52			52															86,858		2,694	
2b.1.1.53	LA - Sanitary Drains RCA		45		0	0	0		7	52	52			52															33,900		3,498	
2b.1.1.54	LB - Roof Drains		69		2	4	104		4	264	264			1,273															51,684		1,811	
2b.1.1.55	LB - Roof Drains RCA		69		2	4	104		4	264	264			1,273															86,858		2,694	
2b.1.1.56	LD - Chemical & Detergent Waste		123		3	7	175		64	397	397			2,139															33,900		3,498	
2b.1.1.57	LF - Floor & Equipment Drains		1520		4	4	41		80	353	353			3,739															42,123		2,771	
2b.1.1.58	RM - Process Sampling & Analysis		138		98	84	307		684	3,637	3,637			661															28,947		1,618	
2b.1.1.59	SI - Nuclear Sampling		80		5	4	35		34	187	187			298															5,815		5,815	
2b.1.1.60	UB - Services Stores - Site Security Bldg		51		0	0	0		27	208	208			31															5,318.678		321,572	
2b.1.1.61	UB - Services Stores - Non-System Specific		33		0	0	0		119	358	358			31															1,656.632		81,719	
2b.1.1	Totals	1,594	15,162		515	597	8,054		6,352	35,723	30,282			5,141															78,019		45,526	
2b.1.2	Scaffolding in support of decommissioning		2,000		35	8	140		531	2,736	2,736			1,541															3,600		3,600	
Decontamination of Site Buildings																																
2b.1.3.1	Reactor	1,054	1,102		33	170	692		1,979	5,107	5,107			5,995															979,803		44,361	
2b.1.3.2	Reactor	465	375		1	72	169		517	2,924	2,924			2,058															417,673		14,324	
2b.1.3.3	Communication Corridor - Contaminated		15		0	2	1		11	39	39			17															8,854		395	
2b.1.3.4	Hot Machine Shop		18		0	2	1		14	54	54			103															8,892		597	
2b.1.3.5	RAM Storage Building		45		16	4	2		30	109	109			19															19,136		1,162	
2b.1.3.6	Radioactive and Personnel Tunnel		6		0	1	3		7	30	30			84															5,022		334	
2b.1.3.7	Radwaste		354		181	7	41		267	1,028	1,028			66															28,861.0		9,997	
2b.1.3.8	Radwaste Drum Storage		40		0	0	0		19	110	110			66															22,242		4,388	
2b.1.3.9	Steam Generator Replacement Bldgs		238		0	0	0		119	358	358			31															1,656.632		81,719	
2b.1.3	Totals	2,637	1,725		55	302	738		2,273	9,179</																						

Table C  
Callaway Energy Center  
DECON Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A			Class B			Class C			Burial / Processed Wt. Lbs.	Craft Mammals	Utility and Contractor Mammals							
															Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet										
Period 2b Collateral Costs (continued)																																	
2b.3.4	Decommissioning Equipment Disposition	-	-	138	34	545	87	8,400	123	928	928	-	-	6,000	397	-	-	-	-	-	-	-	-	-	-	-	-	-					
2b.3.5	Spent Fuel Capital and Transfer	-	-	-	-	-	-	303	30	334	334	9,660	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-					
2b.3.6	On-site survey and release of 207.3 tons clean metallic waste	-	-	-	-	-	-	303	30	334	334	9,660	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-					
2b.3	Subtotal Period 2b Collateral Costs	171	429	292	721	545	1,303	8,703	1,985	14,150	4,990	9,660	-	6,000	2,845	-	-	-	-	-	-	-	-	-	-	-	-	-	555				
Period 2b Period-Dependent Costs																																	
2b.4.1	Decom supplies	1,190	-	-	-	-	-	1,431	297	1,487	1,487	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
2b.4.2	Insurance	-	-	-	-	-	-	1,431	143	1,574	1,574	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
2b.4.3	Property taxes	-	-	-	-	-	-	682	68	751	751	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
2b.4.4	Health physics supplies	-	3,495	-	-	-	-	889	4,294	4,294	4,294	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
2b.4.5	Heavy equipment rental	-	4,590	-	-	-	-	689	5,279	5,279	5,279	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
2b.4.6	Responsibility of DAW generated	-	-	-	25	-	305	184	1,824	1,824	1,824	-	-	-	6,547	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
2b.4.7	Plant energy budget	-	-	-	-	-	-	1,324	175	1,924	1,924	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4.8	NRC Fees	-	-	-	-	-	-	1,749	175	1,924	1,924	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4.9	Emergency Planning Fees	-	-	-	-	-	-	2,225	222	2,447	2,447	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4.10	Spent Fuel Pool O&M	-	-	-	-	-	-	1,861	279	2,140	2,140	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4.11	Liquid Radwaste Processing Equipment/Services	-	-	-	-	-	-	473	71	543	543	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4.12	ISFSI Operating Costs	-	-	-	-	-	-	33	33	66	66	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4.13	ISFSI Construction	-	-	-	-	-	-	10,178	11,387	21,565	21,565	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4.14	Specialty Staff Cost	-	-	-	-	-	-	14,479	2,172	16,651	16,651	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4.15	DOC Staff Cost	-	-	-	-	-	-	32,819	4,923	37,742	37,742	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4.16	Utility Staff Cost	-	-	-	-	-	-	46,864	7,030	53,893	53,893	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
2b.4	Subtotal Period 2b Period-Dependent Costs	1,190	8,025	141	25	-	305	114,475	18,288	142,448	137,611	4,838	-	-	6,547	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	214		
2b.0	TOTAL PERIOD 2b COST	5,391	32,245	1,115	2,542	9,478	6,735	123,647	30,429	211,780	185,545	14,498	11,437	114,720	45,973	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	8,025,761	552,194	1,382,043
PERIOD 2d - Decontamination Following Wet Fuel Storage																																	
Period 2d Direct Decommissioning Activities																																	
2d.1.1	Remove spent fuel racks	838	83	310	87	-	1,154	-	772	3,244	3,244	-	-	-	5,241	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Disposal of Plant Systems																																	
2d.1.1.2	600 Fuel Bldg Non-Specific Systems RCA	-	317	5	11	293	-	-	121	716	716	-	-	3,200	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1.1.2.1	600 Fuel Bldg Non-System Specific	-	49	2	2	2	-	-	20	107	107	-	-	170	90	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1.1.2.2	EC - Fuel Pool Cooling & Cleanup	-	412	22	22	213	180	-	186	1,035	1,035	-	-	2,692	818	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1.1.2.3	GA - Plant Heating Fuel Building	-	23	1	1	4	7	-	8	44	44	-	-	50	31	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1.1.2.4	GG - Fuel Building HVAC	-	252	8	15	306	26	-	118	724	724	-	-	3,729	116	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1.1.2.5	GG - Fuel Building HVAC	-	122	2	4	102	-	-	47	277	277	-	-	1,239	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1.1.2.6	KC - Fire Protection Fuel Building	-	175	39	55	92	252	-	459	2,963	2,963	-	-	10,391	1,096	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1.1.2	Totals	-	1,175	39	55	92	252	-	459	2,963	2,963	-	-	10,391	1,096	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Decommissioning of Site Buildings																																	
2d.1.3.1	Fuel Building	785	851	9	28	222	67	-	660	2,621	2,621	-	-	2,705	1,041	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1.3	Totals	785	851	9	28	222	67	-	660	2,621	2,621	-	-	2,705	1,041	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1.4	Scaffolding in support of decommissioning	-	400	7	2	28	4	-	106	547	547	-	-	308	20	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
2d.1	Subtotal Period 2d Activity Costs	1,623	2,509	395	171	1,151	1,458	-	2,038	9,315	9,315	-	-	14,004	7,359	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Period 2d Additional Costs																																	
2d.2.1	License Termination Survey Program Management	-	-	-	-	-	-	1,366	410	1,776	1,776	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.2	Subtotal Period 2d Additional Costs	-	-	-	-	-	-	1,366	410	1,776	1,776	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 2d Collateral Costs																																	
2d.3.1	Plant decommissioning water waste	90	-	39	148	-	209	-	124	610	610	-	-	-	601	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.3.3	Small tool allowance	-	68	-	-	-	-	-	10	78	78	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.3.4	Decommissioning Equipment Disposition	-	-	138	34	545	87	-	123	928	928	-	-	6,000	397	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.3	Subtotal Period 2d Collateral Costs	90	68	177	183	545	297	-	256	1,616	1,616	-	-	6,000	998	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Period 2d Period-Dependent Costs																																	
2d.4.1	Decom supplies	172	-	-	-	-	-	301	63	315	315	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.4.2	Insurance	-	-	-	-	-	-	301	39	430	430	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.4.3	Property taxes	-	-	-	-	-	-	186	19	205	205	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.4.4	Health physics supplies	-	547	-	-	-	-	889	4,294	4,294	4,294	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.4.5	Heavy equipment rental	-	1,253	-	-	-	-	689	5,279	5,279	5,279	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.4.6	Responsibility of DAW generated	-	-	-	8	-	97	-	188	1,441	1,441	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.4.7	Plant energy budget	-	-	-	-	-	-	193	29	222	222	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2d.4.8	NRC Fees	-	-	-	-	-	-	478	4																								



Table C  
Callaway Energy Center  
DECON Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	Lic. Term. Costs	NRC Management Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A		Class B		Class C		Burial / Processed Wt. Lbs.	Craft Mammals	Utility and Contractor Mammals	
																Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet	Cu. Feet					
Period 2d Period-Dependent Costs (continued)																									
2d.4.9	Liquid Radiowaste Processing Equipment/Services	-	-	-	-	-	-	258	39	297	-	297	-	-	-	-	-	-	-	-	-	-	-	-	
2d.4.10	Corporate Allocations	-	-	-	-	-	-	1,890	189	2,079	-	2,079	-	-	-	-	-	-	-	-	-	-	-	-	
2d.4.11	Security Staff Cost	-	-	-	-	-	-	1,171	176	1,347	-	1,347	-	-	-	-	-	-	-	-	-	-	-	20,829	
2d.4.12	DOC Staff Cost	-	-	-	-	-	-	6,114	922	7,036	-	7,036	-	-	-	-	-	-	-	-	-	-	-	68,429	
2d.4.13	Utility Staff Cost	-	-	-	-	-	-	1,216	186	1,402	-	1,402	-	-	-	-	-	-	-	-	-	-	-	21,179	
2d.4	Subtotal Period 2d Period-Dependent Costs	172	1,800	45	8	-	97	19,885	3,233	25,240	-	25,240	-	-	-	2,081	-	-	-	-	-	41,624	68	221,177	
2d.0	TOTAL PERIOD 2d COST	1,885	4,377	587	362	1,697	1,851	21,250	5,837	37,946	-	37,946	-	-	20,004	10,438	-	-	-	-	-	1,578,117	65,032	233,357	
PERIOD 2f - License Termination																									
Period 2f Direct Decommissioning Activities																									
2f.1.1	ORISE confirmatory survey	-	-	-	-	-	-	154	46	200	-	200	-	-	-	-	-	-	-	-	-	-	-	-	
2f.1.2	Terminate license	-	-	-	-	-	-	154	46	200	-	200	-	-	-	-	-	-	-	-	-	-	-	-	
2f.1	Subtotal Period 2f Activity Costs	-	-	-	-	-	-	308	92	400	-	400	-	-	-	-	-	-	-	-	-	-	-	-	
Period 2f Additional Costs																									
2f.2.1	License Termination-Survey	-	-	-	-	-	-	7,808	2,342	10,150	-	10,150	-	-	-	-	-	-	-	-	-	-	-	-	
2f.2	Subtotal Period 2f Additional Costs	-	-	-	-	-	-	7,808	2,342	10,150	-	10,150	-	-	-	-	-	-	-	-	-	-	-	-	
2f.3.1	DOC staff relocation expenses	-	-	-	-	-	-	1,080	162	1,242	-	1,242	-	-	-	-	-	-	-	-	-	-	-	-	
2f.3	Subtotal Period 2f Collateral Costs	-	-	-	-	-	-	1,080	162	1,242	-	1,242	-	-	-	-	-	-	-	-	-	-	-	-	
Period 2f Period-Dependent Costs																									
2f.4.1	Property taxes	-	-	-	-	-	-	212	21	233	-	233	-	-	-	-	-	-	-	-	-	-	-	-	
2f.4.2	Health physics supplies	-	-	-	-	-	-	165	165	330	-	330	-	-	-	-	-	-	-	-	-	-	-	-	
2f.4.3	Disposal of DAW generated	-	-	-	8	-	-	109	16	125	-	125	-	-	-	353	-	-	-	-	-	7,050	11	-	
2f.4.4	Plant energy budget	-	-	-	-	-	-	58	58	116	-	116	-	-	-	-	-	-	-	-	-	-	-	-	
2f.4.5	NRC Fees	-	-	-	-	-	-	1,480	144	1,624	-	1,624	-	-	-	-	-	-	-	-	-	-	-	-	
2f.4.6	Corporate Allocations	-	-	-	-	-	-	5,171	776	5,947	-	5,947	-	-	-	-	-	-	-	-	-	-	-	-	
2f.4.7	Security Staff Cost	-	-	-	-	-	-	5,739	861	6,600	-	6,600	-	-	-	-	-	-	-	-	-	-	-	57,666	
2f.4.8	DOC Staff Cost	-	-	-	-	-	-	14,583	2,246	17,815	-	17,815	-	-	-	-	-	-	-	-	-	-	-	74,914	
2f.4.9	Utility Staff Cost	-	-	-	-	-	-	16	16	32	-	32	-	-	-	-	-	-	-	-	-	-	-	156,137	
2f.4	Subtotal Period 2f Period-Dependent Costs	-	-	-	-	-	-	16,224	4,796	21,020	-	21,020	-	-	-	353	-	-	-	-	-	7,050	11	162,377	
2f.0	TOTAL PERIOD 2f COST	-	-	-	-	-	-	23,624	85,219	52,447	-	485,084	23,944	15,518	281,077	1,651,191	-	-	-	-	-	7,050	149,350	162,377	
PERIOD 2 TOTALS		9,897	71,723	20,733	11,480	22,144	47,813	255,537	85,219	52,447	-	485,084	23,944	15,518	281,077	1,651,191	-	-	-	-	7,050	149,350	162,377		
PERIOD 3b - Site Restoration																									
Period 3b Direct Decommissioning Activities																									
3b.1.1.1	Demolition of Remaining Site Buildings	-	5,121	-	-	-	-	-	768	5,889	-	5,889	-	5,889	-	-	-	-	-	-	-	-	-	-	
3b.1.1.2	Auxiliary	-	4,111	-	-	-	-	-	617	4,728	-	4,728	-	4,728	-	-	-	-	-	-	-	-	-	-	
3b.1.1.3	Auxiliary Boiler	-	38	-	-	-	-	-	6	43	-	43	-	43	-	-	-	-	-	-	-	-	-	619	
3b.1.1.4	Barge Facility	-	1,561	-	-	-	-	-	234	1,795	-	1,795	-	1,795	-	-	-	-	-	-	-	-	-	18,771	
3b.1.1.5	Circulating & Service Water Pumphouse	-	314	-	-	-	-	-	47	361	-	361	-	361	-	-	-	-	-	-	-	-	-	4,345	
3b.1.1.6	Communication Corridor - Clean	-	1,324	-	-	-	-	-	199	1,523	-	1,523	-	1,523	-	-	-	-	-	-	-	-	-	17,215	
3b.1.1.7	Communication Corridor - Contaminated	-	894	-	-	-	-	-	9	894	-	894	-	894	-	-	-	-	-	-	-	-	-	13,472	
3b.1.1.8	Diesel Generator	-	486	-	-	-	-	-	73	559	-	559	-	559	-	-	-	-	-	-	-	-	-	5,492	
3b.1.1.9	Essential Service Water Pumphouse	-	299	-	-	-	-	-	45	343	-	343	-	343	-	-	-	-	-	-	-	-	-	3,938	
3b.1.1.10	Fire Water Pumphouse	-	28	-	-	-	-	-	4	32	-	32	-	32	-	-	-	-	-	-	-	-	-	382	
3b.1.1.11	Hot Machine Shop	-	24	-	-	-	-	-	4	27	-	27	-	27	-	-	-	-	-	-	-	-	-	417	
3b.1.1.12	Intake	-	369	-	-	-	-	-	55	424	-	424	-	424	-	-	-	-	-	-	-	-	-	4,221	
3b.1.1.13	Intake Structures	-	2,372	-	-	-	-	-	56	2,428	-	2,428	-	2,428	-	-	-	-	-	-	-	-	-	-	2,421
3b.1.1.14	Miscellaneous Site Foundations	-	372	-	-	-	-	-	5	377	-	377	-	377	-	-	-	-	-	-	-	-	-	5,483	
3b.1.1.15	Outage Maintenance	-	185	-	-	-	-	-	28	213	-	213	-	213	-	-	-	-	-	-	-	-	-	3,190	
3b.1.1.16	RAM Storage Building	-	69	-	-	-	-	-	10	79	-	79	-	79	-	-	-	-	-	-	-	-	-	1,081	
3b.1.1.17	RAM Storage Building	-	28	-	-	-	-	-	4	33	-	33	-	33	-	-	-	-	-	-	-	-	-	386	
3b.1.1.18	Radiactive and Personnel Tunnel	-	1,851	-	-	-	-	-	275	2,126	-	2,126	-	2,126	-	-	-	-	-	-	-	-	-	-	21,798
3b.1.1.19	Radiowaste	-	272	-	-	-	-	-	41	313	-	313	-	313	-	-	-	-	-	-	-	-	-	-	
3b.1.1.20	Radiowaste Drum Storage	-	2,224	-	-	-	-	-	354	2,578	-	2,578	-	2,578	-	-	-	-	-	-	-	-	-	-	
3b.1.1.21	Security Additions	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3,840	

Table C  
Callaway Energy Center  
DECON Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	OFF-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Lic. Term. Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes			Burial / Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours	
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet				
Demolition of Remaining Site Buildings (continued)																					
3b.1.1.22	Service	-	502	-	-	-	-	75	75	577	-	-	577	-	-	-	-	-	6,045	-	-
3b.1.1.23	Sludge Pump Station & Lagoon	-	25	-	-	-	-	-	4	29	-	-	29	-	-	-	-	-	313	-	-
3b.1.1.24	Steam Generator Replacement Bldgs	-	1,187	-	-	-	-	178	1,865	1,865	-	-	1,865	-	-	-	-	-	15,693	-	-
3b.1.1.25	Turbine Building	-	3,698	-	-	-	-	547	4,195	4,195	-	-	4,195	-	-	-	-	-	55,694	-	-
3b.1.1.26	UHS Cooling Tower	-	1,638	-	-	-	-	148	1,786	1,786	-	-	1,786	-	-	-	-	-	10,688	-	-
3b.1.1.27	UHS Cooling Tower	-	638	-	-	-	-	86	724	724	-	-	724	-	-	-	-	-	6,683	-	-
3b.1.1.28	Water Treatment Plant	-	-	-	-	-	-	0	1	1	-	-	1	-	-	-	-	-	9	-	-
3b.1.1.29	Fuel Building	-	2,035	-	-	-	-	305	2,340	2,340	-	-	2,340	-	-	-	-	-	22,590	-	-
3b.1.1	Totals	-	31,051	-	-	-	-	4,658	35,708	35,708	-	-	35,708	-	-	-	-	-	382,179	-	-
Site Closeout Activities																					
3b.1.2	Final Site	-	9,290	-	-	-	-	1,998	10,718	10,718	-	-	10,718	-	-	-	-	-	17,988	-	-
3b.1.3	Grads & package site	-	124	-	-	-	-	19	142	142	-	-	142	-	-	-	-	-	592	-	-
3b.1	Final report to NRC	-	-	-	-	-	-	182	209	209	-	-	209	-	-	-	-	-	-	-	-
3b.1	Subtotal Period 3b Activity Costs	-	40,494	-	-	-	-	182	46,778	46,778	-	-	46,778	-	-	-	-	-	400,700	-	-
Period 3b Additional Costs																					
3b.2.1	Concrete Crushing	-	1,226	-	-	-	-	185	1,419	1,419	-	-	1,419	-	-	-	-	-	5,830	-	-
3b.2.2	Concrete Discharge & Intake Pipe Flow Fill	-	3,779	-	-	-	-	557	4,346	4,346	-	-	4,346	-	-	-	-	-	15,588	-	-
3b.2.3	Cooling Tower Demolition	-	3,846	-	-	-	-	577	4,423	4,423	-	-	4,423	-	-	-	-	-	20,492	-	-
3b.2	Subtotal Period 3b Additional Costs	-	13,070	-	-	-	-	9	15,040	15,040	-	-	15,040	-	-	-	-	-	51,840	-	-
Period 3b Collateral Costs																					
3b.3.1	Small tool allowance	-	410	-	-	-	-	62	472	472	-	-	472	-	-	-	-	-	-	-	-
3b.3	Subtotal Period 3b Collateral Costs	-	410	-	-	-	-	62	472	472	-	-	472	-	-	-	-	-	-	-	-
Period 3b Period-Dependent Costs																					
3b.4.1	Insurance	-	-	-	-	-	-	-	42	463	-	-	463	-	-	-	-	-	-	-	-
3b.4.2	Property taxes	-	-	-	-	-	-	689	4,697	4,697	-	-	4,697	-	-	-	-	-	-	-	-
3b.4.3	Heavy equipment rental	-	4,058	-	-	-	-	46	4,504	4,504	-	-	4,504	-	-	-	-	-	-	-	-
3b.4.4	Plant energy budget	-	-	-	-	-	-	300	2,302	2,302	-	-	2,302	-	-	-	-	-	-	-	-
3b.4.5	Safety Staff Cost	-	-	-	-	-	-	1,501	11,507	11,507	-	-	11,507	-	-	-	-	-	-	-	-
3b.4.6	DOC Staff Cost	-	-	-	-	-	-	697	5,340	5,340	-	-	5,340	-	-	-	-	-	-	-	-
3b.4.7	Utility Staff Cost	-	-	-	-	-	-	3,624	29,453	29,453	-	-	29,453	-	-	-	-	-	-	-	-
3b.4.8	Subtotal Period 3b Period-Dependent Costs	-	4,058	-	-	-	-	21,771	11,749	91,742	-	-	86,484	-	-	-	-	-	452,540	-	-
3b.0	TOTAL PERIOD 3b COST	-	58,032	-	-	-	-	21,961	11,749	91,742	-	-	86,484	-	-	-	-	-	452,540	-	-
3b.0	TOTAL PERIOD 3b COST	-	58,032	-	-	-	-	21,961	11,749	91,742	-	-	86,484	-	-	-	-	-	452,540	-	-
PERIOD 3 TOTALS		12,942	132,224	20,821	11,797	221,144	50,878	388,396	115,237	754,498	617,324	35,726	103,448	281,077	2,142	1,690	1,690	23,885,690	1,638,154	3,963,950	
TOTAL COST TO DECOMMISSION		12,942	132,224	20,821	11,797	221,144	50,878	388,396	115,237	754,498	617,324	35,726	103,448	281,077	2,142	1,690	1,690	23,885,690	1,638,154	3,963,950	

TOTAL COST TO DECOMMISSION WITH 18.04% CONTINGENCY:	\$754,498 thousands of 2011 dollars
TOTAL NRC LICENSE TERMINATION COST IS 81.82% OR:	\$617,324 thousands of 2011 dollars
SPENT FUEL MANAGEMENT COST IS 4.47% OR:	\$33,726 thousands of 2011 dollars
NON-NUCLEAR DEMOLITION COST IS 13.71% OR:	\$103,448 thousands of 2011 dollars
TOTAL LOW-LEVEL RADIOACTIVE WASTE VOLUME BURIED (EXCLUDING GTCCO):	148,593 cubic feet
TOTAL GREATER THAN CLASS C RADWASTE VOLUME GENERATED:	2,142 cubic feet
TOTAL SCRAP METAL REMOVED:	71,335 tons
TOTAL CRAFT LABOR REQUIREMENTS:	1,638,154 man-hours

End Notes:  
n/a - indicates that this activity not charged as decommissioning expense.  
a - indicates that this activity performed by decommissioning staff.  
0 - indicates that this value is less than 0.5 but is non-zero.  
a cell containing "-" indicates a zero value

**APPENDIX D**  
**DETAILED COST ANALYSIS**  
**SAFSTOR**

Table D  
Callaway Energy Center  
SAFSTOR Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Direct Cost	Removal Cost	Repackaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	Liab. Costs	NRC Lic. Costs	Spent Fuel Management Costs	Site Remediation Costs	Processed Material Costs	Class A Waste Costs	Burial Volumes Class A	Burial Volumes Class C	CRWC Costs	Burial/Prep. Costs	Class B Waste Costs	Class C Waste Costs	Utility and Other Costs	
<b>PERIOD 1a - Shutdown through Transition</b>																								
Period 1a Direct Decommissioning Activities																								
Ia.1.1	SAFSTOR site characterization survey	-	-	-	-	-	-	317	104	451	451	451	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.2	Prepare preliminary decommissioning cost	-	-	-	-	-	-	152	23	174	174	174	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.3	Notification of Cessation of Operations	-	-	-	-	-	-	-	-	n/a	n/a	-	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.4	Remove fuel & source material	-	-	-	-	-	-	-	-	a	a	-	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.5	Notification of Permanent Dismantling	-	-	-	-	-	-	-	-	a	a	-	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.6	Deactivate plant systems & process waste	-	-	-	-	-	-	533	95	628	628	628	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.7	Prepare final signed PSDAR	-	-	-	-	-	-	152	23	174	174	174	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.8	Remove plant equipment	-	-	-	-	-	-	-	-	595	595	595	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.9	Perform detailed rad survey	-	-	-	-	-	-	-	-	174	174	174	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.10	Estimate by-product inventory	-	-	-	-	-	-	-	-	134	134	134	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.11	End product description	-	-	-	-	-	-	-	-	18	18	18	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.12	Detailed by-product inventory	-	-	-	-	-	-	-	-	175	175	175	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.13	Define by-product waste sequence	-	-	-	-	-	-	-	-	134	134	134	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.14	Perform SWR, EIS	-	-	-	-	-	-	322	44	366	366	366	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.15	Perform Site-Specific Cost Study	-	-	-	-	-	-	584	88	672	672	672	-	-	-	-	-	-	-	-	-	-	-	-
Activity Specifications																								
Ia.1.16.1	Prepare plant and facilities for SAFSTOR	-	-	-	-	-	-	574	86	660	660	660	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.16.2	Plant systems	-	-	-	-	-	-	86	72	60	60	60	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.16.3	Plant buildings and buildings	-	-	-	-	-	-	328	35	363	363	363	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.16.4	Waste management	-	-	-	-	-	-	233	35	268	268	268	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.16.5	Facility and site dormancy	-	-	-	-	-	-	233	35	268	268	268	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.16.6	Total	-	-	-	-	-	-	1,892	284	2,176	2,176	2,176	-	-	-	-	-	-	-	-	-	-	-	-
Detailed Work Procedures																								
Ia.1.17.1	Plant systems	-	-	-	-	-	-	138	91	150	150	150	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.17.2	Facility, equipment & dormancy	-	-	-	-	-	-	140	21	161	161	161	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.17.3	Total	-	-	-	-	-	-	278	42	320	320	320	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.18	Procure vacuum drying system	-	-	-	-	-	-	12	2	13	13	13	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.19	Drain/de-energize non-cont. systems	-	-	-	-	-	-	-	-	a	a	-	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.20	Drain and dry NSSS	-	-	-	-	-	-	-	-	a	a	-	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.21	Drain/de-energize contaminated systems	-	-	-	-	-	-	-	-	a	a	-	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1.22	Decontaminate contaminated systems	-	-	-	-	-	-	-	-	a	a	-	-	-	-	-	-	-	-	-	-	-	-	-
Ia.1	Subtotal Period 1a Activity Costs	-	-	-	-	-	-	4,535	732	5,268	5,268	5,268	-	-	-	-	-	-	-	-	-	-	-	-
Period 1a Collateral Costs																								
Ia.3.1	Spent Fuel Capital and Transfer	-	-	-	-	-	-	-	-	4,140	4,140	4,140	-	-	-	-	-	-	-	-	-	-	-	-
Ia.3	Subtotal Period 1a Collateral Costs	-	-	-	-	-	-	3,600	540	4,140	4,140	4,140	-	-	-	-	-	-	-	-	-	-	-	-
Period 1a Period-Dependent Costs																								
Ia.4.1	Insurance	-	-	-	-	-	-	1,589	159	1,747	1,747	1,747	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.2	Property taxes	-	-	-	-	-	-	280	28	308	308	308	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.3	Health physics supplies	-	-	-	-	-	-	454	113	567	567	567	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.4	Health physics training	-	-	-	-	-	-	436	106	542	542	542	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.5	Disposal of DAW generated	-	-	-	-	-	-	28	9	37	37	37	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.6	Plant energy budget	-	-	-	-	-	-	724	109	832	832	832	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.7	NRC Fees	-	-	-	-	-	-	769	77	846	846	846	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.8	Emergency Planning Fees	-	-	-	-	-	-	1,351	135	1,486	1,486	1,486	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.9	INPO Fees	-	-	-	-	-	-	289	43	332	332	332	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.10	INPO Fuel Pool O&M	-	-	-	-	-	-	743	114	857	857	857	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.11	RESPI Operator Costs	-	-	-	-	-	-	89	13	102	102	102	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.12	Corporate Allocations	-	-	-	-	-	-	2,970	297	3,267	3,267	3,267	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.13	Security Staff Cost	-	-	-	-	-	-	6,892	1,084	7,976	7,976	7,976	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4.14	Utility Staff Cost	-	-	-	-	-	-	28,091	4,214	32,305	32,305	32,305	-	-	-	-	-	-	-	-	-	-	-	-
Ia.4	Subtotal Period 1a Period-Dependent Costs	-	-	-	-	-	-	43,807	6,411	51,151	51,151	51,151	-	-	-	-	-	-	-	-	-	-	-	-
Ia.0	TOTAL PERIOD 1a COST	-	-	-	-	-	-	51,943	7,683	60,559	60,559	60,559	-	-	-	-	-	-	-	-	-	-	-	-

Table D  
Callaway Energy Center  
SAFSTOR Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Direct Cost	Removal Cost	Prepackaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	NRC Lic. Costs	Spent Fuel Management Costs	Site Remediation Costs	Processed Class A Cu. Feet	Burial Volumes Class A Cu. Feet	Burial Volumes C Cu. Feet	CWC Cu. Feet	Burial/Processed Wt. Lbs.	Conf. Manhours	Utility and Other Manhours
<b>PERIOD 1b - SAFSTOR Limited DECON Activities</b>																				
Period 1b Direct Decommissioning Activities																				
Decommissioning of Site Buildings																				
1b.1.1.1	Roaster	1,235	-	-	-	-	-	-	618	1,853	1,853	-	-	-	-	-	-	-	-	-
1b.1.1.2	Auxiliary	626	-	-	-	-	-	-	313	940	940	-	-	-	-	-	-	-	-	24,102
1b.1.1.3	Communication Corridor - Contaminated	14	-	-	-	-	-	-	7	21	21	-	-	-	-	-	-	-	-	12,027
1b.1.1.4	Fuel Building	774	-	-	-	-	-	-	387	1,161	1,161	-	-	-	-	-	-	-	-	276
1b.1.1.5	Hot Machine Shop	17	-	-	-	-	-	-	9	26	26	-	-	-	-	-	-	-	-	14,371
1b.1.1.6	Hot Storage Building	45	-	-	-	-	-	-	2	47	47	-	-	-	-	-	-	-	-	334
1b.1.1.7	Radwaste and Personnel Tunnel	303	-	-	-	-	-	-	2	305	305	-	-	-	-	-	-	-	-	95
1b.1.1.8	Radwaste	34	-	-	-	-	-	-	17	51	51	-	-	-	-	-	-	-	-	9
1b.1.1.9	Radwaste Drum Storage	3,051	-	-	-	-	-	-	1,525	4,576	4,576	-	-	-	-	-	-	-	-	5,964
1b.1.1	Totals	3,051	-	-	-	-	-	-	1,525	4,576	4,576	-	-	-	-	-	-	-	-	59,211
1b.1	Subtotal Period 1b Activity Costs	872	-	-	-	-	-	-	131	1,003	1,003	-	-	-	-	-	-	-	-	64,942
Period 1b Collateral Costs																				
1b.3.1	Decon equipment	171	-	-	-	-	-	-	8	179	179	-	-	-	-	-	-	-	-	-
1b.3.2	Process decommissioning water waste	50	-	-	-	-	-	-	144	1,104	1,104	-	-	-	-	-	-	-	-	211
1b.3.3	Small tool allowance	1,044	-	-	-	-	-	-	569	3,278	2,174	-	-	-	-	-	-	-	-	211
1b.3	Subtotal Period 1b Collateral Costs	1,108	-	-	-	-	-	-	277	1,385	1,385	-	-	-	-	-	-	-	-	-
Period 1b Period-Dependent Costs																				
1b.4.1	Decon supplies	-	-	-	-	-	-	-	40	400	440	-	-	-	-	-	-	-	-	-
1b.4.2	Insurance	-	-	-	-	-	-	-	7	78	78	-	-	-	-	-	-	-	-	-
1b.4.3	Property taxes	-	-	-	-	-	-	-	67	67	67	-	-	-	-	-	-	-	-	-
1b.4.4	Health physics supplies	-	-	-	-	-	-	-	16	126	126	-	-	-	-	-	-	-	-	-
1b.4.5	Health physics equipment	-	-	-	-	-	-	-	34	63	63	-	-	-	-	-	-	-	-	-
1b.4.6	Disposal of DAW generated	-	-	-	3	-	-	-	11	63	63	-	-	-	-	-	-	-	-	24
1b.4.7	Plant energy budget	-	-	-	-	-	-	-	27	210	210	-	-	-	-	-	-	-	-	-
1b.4.8	NRC Fees	-	-	-	-	-	-	-	194	213	213	-	-	-	-	-	-	-	-	-
1b.4.9	Emergency Planning Fees	-	-	-	-	-	-	-	34	375	375	-	-	-	-	-	-	-	-	-
1b.4.10	Spent Fuel Pool O&M	-	-	-	-	-	-	-	12	221	221	-	-	-	-	-	-	-	-	-
1b.4.11	ISPS O&M	-	-	-	-	-	-	-	23	23	23	-	-	-	-	-	-	-	-	-
1b.4.12	Corporate Allocations	-	-	-	-	-	-	-	1,080	1,088	1,188	-	-	-	-	-	-	-	-	-
1b.4.13	Security Staff Cost	-	-	-	-	-	-	-	1,737	261	1,998	-	-	-	-	-	-	-	-	39,691
1b.4.14	Utility Staff Cost	-	-	-	-	-	-	-	7,081	1,062	8,143	-	-	-	-	-	-	-	-	106,720
1b.4	Subtotal Period 1b Period-Dependent Costs	1,108	474	16	3	-	-	34	11,300	13,866	14,921	622	-	-	-	-	-	-	-	146,411
1b.0	TOTAL PERIOD 1b COST	5,203	524	86	270	-	411	12,260	4,021	22,774	21,049	1,726	-	-	-	-	-	-	-	59,446
<b>PERIOD 1c - Preparations for SAFSTOR Dormancy</b>																				
Period 1c Direct Decommissioning Activities																				
1c.1.1	Prepare support equipment for storage	-	497	-	-	-	-	-	65	503	503	-	-	-	-	-	-	-	-	3,090
1c.1.2	Install containment pressure equal lines	-	39	-	-	-	-	-	6	45	45	-	-	-	-	-	-	-	-	700
1c.1.3	Interim survey prior to dormancy	-	-	-	-	-	-	-	733	953	953	-	-	-	-	-	-	-	-	15,678
1c.1.4	Secure building accesses	-	-	-	-	-	-	-	a	78	78	-	-	-	-	-	-	-	-	-
1c.1.5	Prepare & submit interim report	-	-	-	-	-	-	-	68	10	78	-	-	-	-	-	-	-	-	583
1c.1	Subtotal Period 1c Activity Costs	-	476	-	-	-	-	-	301	1,579	1,579	-	-	-	-	-	-	-	-	19,378
Period 1c Additional Costs																				
1c.2.1	Spent Fuel Isolation	-	-	-	-	-	-	-	10,280	11,822	11,822	-	-	-	-	-	-	-	-	-
1c.2	Subtotal Period 1c Additional Costs	-	-	-	-	-	-	-	10,280	11,822	11,822	-	-	-	-	-	-	-	-	-
Period 1c Collateral Costs																				
1c.3.1	Process decommissioning water waste	187	-	-	292	-	-	-	248	1,216	1,216	-	-	-	-	-	-	-	-	231
1c.3.2	Small tool allowance	-	4	-	-	-	-	-	1	4	4	-	-	-	-	-	-	-	-	-
1c.3.4	Spent Fuel Capital and Transfer	-	-	-	-	-	-	-	960	144	1,104	-	-	-	-	-	-	-	-	-
1c.3	Subtotal Period 1c Collateral Costs	187	4	-	292	-	-	-	383	2,324	2,220	-	-	-	-	-	-	-	-	231
Period 1c Period-Dependent Costs																				
1c.4.1	Decon equipment	-	-	-	-	-	-	-	40	440	440	-	-	-	-	-	-	-	-	-
1c.4.2	Property taxes	-	-	-	-	-	-	-	7	78	78	-	-	-	-	-	-	-	-	-

Table D  
Callaway Energy Center  
SAFSTOR Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Direct Cost	Renewal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	Site Remediation Costs	Processed Class A	Burial Volumes	CRWC	Burial/Placed	Utility and		
												Cu. Feet	Cu. Feet	Cu. Feet	Wt. Lbs.	Cu. Ft. Manhours		
Period 1c: Period-Dependent Costs (continued)																		
1c4.3	Health physics supplies	-	197	-	-	-	-	-	49	246	-	-	-	-	-	-	-	
1c4.4	Heavy equipment rental	-	110	-	-	-	-	-	16	126	-	-	-	-	-	-	-	
1c4.5	Disposal of DAW generated	-	-	3	-	-	7	-	182	195	-	-	-	-	-	-	5	
1c4.6	Emergency budget	-	-	-	-	-	-	-	19	213	-	-	-	-	-	-	-	
1c4.7	NRC Fees	-	-	-	-	-	-	-	34	375	-	-	-	-	-	-	-	
1c4.8	Emergency Planning Fees	-	-	-	-	-	-	-	29	221	-	-	-	-	-	-	-	
1c4.9	Spent Fuel Pool O&M	-	-	-	-	-	3	-	26	26	-	-	-	-	-	-	-	
1c4.10	ISFSI Operating Costs	-	-	-	-	-	34	-	1,584	1,618	-	-	-	-	-	-	-	
1c4.11	Corporate Allocations	-	-	-	-	-	1,440	-	1,440	1,440	-	-	-	-	-	-	-	
1c4.12	Utility Staff Cost	-	-	-	-	-	1,062	-	1,062	1,062	-	-	-	-	-	-	99,591	
1c4.13	Subtotal Period 1c: Period-Dependent Costs	-	307	3	1	-	7	11,660	1,695	13,673	622	-	-	-	3,073	146,411	108,720	
1c0	TOTAL PERIOD 1c COST	187	786	80	293	-	420	23,701	3,381	29,397	1,726	-	-	-	74,073	19,614	146,995	
PERIOD 1 TOTALS		5,390	2,200	178	565	-	859	87,904	15,634	112,731	10,058	-	-	-	165,832	79,080	910,108	
PERIOD 2a- SAFSTOR Dormancy with Wet Spent Fuel Storage																		
Period 2a: Direct Decommissioning Activities																		
2a.1.1	Quarterly Inspection	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2a.1.2	Semi-annual environmental survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2a.1.3	Health physics supplies	-	-	-	-	-	-	-	44	335	-	-	-	-	-	-	-	-
2a.1.4	Bituminous roof replacement	-	-	-	-	-	-	291	135	675	-	-	-	-	-	-	-	-
2a.1.5	Maintenance supplies	-	-	-	-	-	-	831	179	1,069	-	-	-	-	-	-	-	-
2a.1	Subtotal Period 2a: Activity Costs	-	-	-	-	-	-	13,680	2,032	15,712	-	-	-	-	-	-	-	-
2a.3.1	Spent Fuel Canister and Transfer	-	-	-	-	-	-	13,680	2,032	15,712	15,726	-	-	-	-	-	-	-
2a.3	Subtotal Period 2a: Collateral Costs	-	-	-	-	-	-	13,680	2,032	15,732	15,732	-	-	-	-	-	-	-
Period 2a: Period-Dependent Costs																		
2a.4.1	Insurance	-	-	-	-	-	-	2,347	235	2,582	-	-	-	-	-	-	-	-
2a.4.2	Property taxes	-	-	-	-	-	-	1,119	112	1,231	-	-	-	-	-	-	-	-
2a.4.3	Health physics supplies	-	-	-	-	-	-	43	152	195	-	-	-	-	-	-	-	-
2a.4.4	Disposal of DAW generated	-	-	20	-	-	43	-	87	666	-	-	-	-	920	-	30	
2a.4.5	Plant energy budget	-	-	-	-	-	-	579	88	970	-	-	-	-	-	-	-	
2a.4.6	NRC Fees	-	-	-	-	-	-	881	365	4,014	-	-	-	-	-	-	-	
2a.4.7	Emergency Planning Fees	-	-	-	-	-	-	3,650	365	4,014	-	-	-	-	-	-	-	
2a.4.8	Spent Fuel Pool O&M	-	-	-	-	-	-	458	3,510	3,510	-	-	-	-	-	-	-	
2a.4.9	ISFSI Operating Costs	-	-	-	-	-	-	458	44	411	-	-	-	-	-	-	-	
2a.4.10	Corporate Allocations	-	-	-	-	-	-	20,638	3,095	23,733	-	-	-	-	-	-	-	
2a.4.11	Security Staff Cost	-	-	-	-	-	-	22,072	3,311	25,383	-	-	-	-	-	-	-	
2a.4.12	Utility Staff Cost	-	-	-	-	-	-	58,835	8,414	68,042	-	-	-	-	18,406	30	773,800	
2a.4	Subtotal Period 2a: Period-Dependent Costs	-	728	20	3	-	43	73,346	10,644	84,784	63,091	-	-	-	18,406	30	773,800	
2a.0	TOTAL PERIOD 2a COST	-	728	20	3	-	43	73,346	10,644	84,784	63,091	-	-	-	18,406	30	773,800	
PERIOD 2c- SAFSTOR Dormancy without Spent Fuel Storage																		
Period 2c: Direct Decommissioning Activities																		
2c.1.1	Quarterly Inspection	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.1.2	Semi-annual environmental survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.1.3	Health physics supplies	-	-	-	-	-	-	-	527	4,039	-	-	-	-	-	-	-	-
2c.1.4	Bituminous roof replacement	-	-	-	-	-	-	3,512	1,627	8,137	-	-	-	-	-	-	-	-
2c.1.5	Maintenance supplies	-	-	-	-	-	-	10,622	2,154	12,176	-	-	-	-	-	-	-	-
2c.1	Subtotal Period 2c: Activity Costs	-	-	-	-	-	-	10,622	2,154	12,176	-	-	-	-	-	-	-	-
Period 2c: Period-Dependent Costs																		
2c.4.1	Insurance	-	-	-	-	-	-	24,584	2,469	27,054	-	-	-	-	-	-	-	-
2c.4.2	Property taxes	-	-	-	-	-	-	13,562	1,001	14,563	-	-	-	-	-	-	-	-
2c.4.3	Health physics supplies	-	-	-	-	-	-	1,001	5,007	5,007	-	-	-	-	-	-	-	-
2c.4.4	Disposal of DAW generated	-	-	105	18	-	229	-	71	423	-	-	-	-	98,237	160	-	
2c.4.5	Plant energy budget	-	-	-	-	-	-	3,493	524	4,017	-	-	-	-	-	-	-	
2c.4.6	NRC Fees	-	-	-	-	-	-	9,635	963	10,598	-	-	-	-	-	-	-	
2c.4.7	Corporate Allocations	-	-	-	-	-	-	12,109	1,215	13,365	-	-	-	-	-	-	-	
2c.4.8	Utility Staff Cost	-	-	-	-	-	-	15,726	1,695	17,421	-	-	-	-	-	-	-	
2c.4.9	Utility Staff Cost	-	-	-	-	-	-	53,420	8,013	61,433	-	-	-	-	-	-	-	

**Table D**  
**Callaway Energy Center**  
**SAFSTOR Decommissioning Cost Estimate**  
(thousands of 2011 dollars)

Activity Index	Activity Description	Direct Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	NRC Lic. m. Costs	Spent Fuel Management Costs	Site Remediation Costs	Processed Cu. Feet	Burial Volumes		Burial/Proc. Wt. Lbs.	Ccu/Ft Manhours	Utility and Support Manhours
															Cu. Feet	Cu. Feet			
2c.4	Subtotal Period 2c. Period-Dependent Costs	-	4,006	105	18	-	229	201,982	28,387	234,677	234,677	-	-	-	-	-	98,237	160	2,390,336
2c.0	TOTAL PERIOD 2c. COST	-	4,006	105	18	-	229	211,983	30,511	246,853	246,853	-	-	-	-	-	98,237	160	2,390,336
<b>PERIOD 2 TOTALS</b>		-	4,734	125	22	-	272	283,229	41,155	331,637	331,637	63,691	-	-	-	-	116,613	190	3,164,136
<b>PERIOD 3a - Reactivate Site Following SAFSTOR Dormancy</b>																			
Period 3a. Direct Decommissioning Activities																			
3a.1.1	Prepare preliminary decommissioning cost	-	-	-	-	-	-	152	23	174	174	-	-	-	-	-	-	-	1,300
3a.1.2	Obtain plant drawings & specs.	-	-	-	-	-	-	537	81	617	617	-	-	-	-	-	-	-	4,600
3a.1.3	Perform site survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3a.1.4	End product description	-	-	-	-	-	-	117	18	134	134	-	-	-	-	-	-	-	1,000
3a.1.5	Detailed by-product inventory	-	-	-	-	-	-	162	23	174	174	-	-	-	-	-	-	-	1,300
3a.1.6	Define major work sequence	-	-	-	-	-	-	875	131	1,007	1,007	-	-	-	-	-	-	-	7,500
3a.1.7	Perform SER and EA	-	-	-	-	-	-	382	54	416	416	-	-	-	-	-	-	-	3,100
3a.1.8	Perform Site-Specific Cost Study	-	-	-	-	-	-	584	89	673	673	-	-	-	-	-	-	-	5,000
3a.1.9	Prepare Decommissioning Plan	-	-	-	-	-	-	478	72	550	550	-	-	-	-	-	-	-	4,086
3a.1.10	Receive NRC approval of termination plan	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Activity Specifications																			
3a.1.1.1	Re-activate plant & temporary facilities	-	-	-	-	-	-	800	129	989	989	-	-	-	-	-	-	-	7,370
3a.1.1.2	Plant start-up	-	-	-	-	-	-	886	124	1,010	1,010	-	-	-	-	-	-	-	4,700
3a.1.1.3	Reactor internals	-	-	-	-	-	-	829	114	953	953	-	-	-	-	-	-	-	7,100
3a.1.1.4	Biological shield	-	-	-	-	-	-	759	9	872	872	-	-	-	-	-	-	-	6,500
3a.1.1.5	Biological shield	-	-	-	-	-	-	58	9	67	67	-	-	-	-	-	-	-	500
3a.1.1.6	Steam generators	-	-	-	-	-	-	364	55	419	419	-	-	-	-	-	-	-	3,120
3a.1.1.7	Reinforced concrete	-	-	-	-	-	-	187	28	215	215	-	-	-	-	-	-	-	1,000
3a.1.1.8	Reactor pressure vessel	-	-	-	-	-	-	47	7	54	54	-	-	-	-	-	-	-	400
3a.1.1.9	Main Condensers	-	-	-	-	-	-	47	7	54	54	-	-	-	-	-	-	-	400
3a.1.1.10	Plant structures & buildings	-	-	-	-	-	-	364	55	419	419	-	-	-	-	-	-	-	3,120
3a.1.1.11	Waste management	-	-	-	-	-	-	537	81	617	617	-	-	-	-	-	-	-	4,600
3a.1.1.12	Facility & site closure	-	-	-	-	-	-	105	16	121	121	-	-	-	-	-	-	-	900
3a.1.1.1	Total	-	-	-	-	-	-	4,643	696	5,339	4,700	-	-	-	-	-	-	-	38,777
Planning & Site Preparations																			
3a.1.1.2	Prepare dismantling sequence	-	-	-	-	-	-	280	42	322	322	-	-	-	-	-	-	-	2,400
3a.1.1.3	Plant prep. & temp. svcs	-	-	-	-	-	-	2,800	420	3,220	3,220	-	-	-	-	-	-	-	-
3a.1.1.4	Design water clean-up system	-	-	-	-	-	-	163	25	188	188	-	-	-	-	-	-	-	1,400
3a.1.1.5	Rigging/Cont. Cntrl Envelop/boiling/etc.	-	-	-	-	-	-	2,200	330	2,530	2,530	-	-	-	-	-	-	-	-
3a.1.1.6	Secure caskloaders & containers	-	-	-	-	-	-	144	22	166	166	-	-	-	-	-	-	-	1,250
3a.1	Subtotal Period 3a. Activity Costs	-	-	-	-	-	-	13,486	2,023	15,369	14,860	-	-	-	-	-	-	-	72,763
Period 3a. Period-Dependent Costs																			
3a.4.1	Insurance	-	-	-	-	-	-	260	26	286	286	-	-	-	-	-	-	-	-
3a.4.2	Property taxes	-	-	-	-	-	-	14	14	155	155	-	-	-	-	-	-	-	-
3a.4.3	Health physics supplies	-	-	-	-	-	-	200	50	250	250	-	-	-	-	-	-	-	-
3a.4.4	Site cleanup materials	-	-	-	-	-	-	420	54	474	474	-	-	-	-	-	-	-	-
3a.4.5	Disposal of DAW generated	-	-	-	1	-	-	22	22	23	23	-	-	-	-	-	-	-	8
3a.4.6	Plant energy budget	-	-	-	-	-	-	305	55	420	420	-	-	-	-	-	-	-	-
3a.4.7	NRC Fees	-	-	-	-	-	-	137	14	151	151	-	-	-	-	-	-	-	-
3a.4.8	Corporate Allocations	-	-	-	-	-	-	1,530	153	1,683	1,683	-	-	-	-	-	-	-	-
3a.4.9	Security Staff Cost	-	-	-	-	-	-	1,935	239	1,835	1,835	-	-	-	-	-	-	-	-
3a.4.10	Utility Staff Cost	-	-	-	-	-	-	1,875	187	1,688	1,688	-	-	-	-	-	-	-	-
3a.4	Subtotal Period 3a. Period-Dependent Costs	-	-	-	6	-	-	12,829	1,908	15,175	15,175	-	-	-	-	-	-	-	8
3a.0	TOTAL PERIOD 3a. COST	-	-	-	1	-	12	26,315	3,931	30,684	30,684	-	-	-	-	-	5,186	8	235,937
<b>PERIOD 3b - Decommissioning Preparations</b>																			
Period 3b. Direct Decommissioning Activities																			
Detailed Work Procedures																			
3b.1.1.1	Plant system	-	-	-	-	-	-	552	83	635	635	-	-	-	-	-	-	-	4,733
3b.1.1.2	Reactor internals	-	-	-	-	-	-	292	44	336	336	-	-	-	-	-	-	-	2,500
3b.1.1.3	Remaining buildings	-	-	-	-	-	-	158	24	181	181	-	-	-	-	-	-	-	1,300
3b.1.1.4	Overhead assembly	-	-	-	-	-	-	117	17	134	134	-	-	-	-	-	-	-	1,000
3b.1.1.5	CRD housings & ICI tubes	-	-	-	-	-	-	117	18	134	134	-	-	-	-	-	-	-	1,000

Table D  
Callaway Energy Center  
SAFSTOR Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Direct Cost	Removal Cost	Repackaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	Site Remediation Costs	Processed Class A	Burial Volumes	Burial/Prepacked	Utility and Members	
												Cu. Feet	Cu. Feet	Wt. Lbs.		
Detailed Work Procedures (continued)																
3b.1.1.6	Incore instrumentation	-	-	-	-	-	-	117	18	134	-	-	-	-	-	1,000
3b.1.1.7	Reactor vessel	-	-	-	-	-	-	424	64	487	-	-	-	-	-	3,650
3b.1.1.8	Quality closet	-	-	-	-	-	-	140	21	161	-	-	-	-	-	1,200
3b.1.1.9	Material storage	-	-	-	-	-	-	140	21	161	81	-	-	-	-	1,200
3b.1.1.10	Biological shield	-	-	-	-	-	-	140	21	161	-	-	-	-	-	1,200
3b.1.1.11	Steam generators	-	-	-	-	-	-	537	81	617	-	-	-	-	-	4,600
3b.1.1.12	Reinforced concrete	-	-	-	-	-	-	117	18	134	67	-	-	-	-	1,000
3b.1.1.13	Main Turbine	-	-	-	-	-	-	182	27	209	209	-	-	-	-	1,560
3b.1.1.14	Main Condensers	-	-	-	-	-	-	82	12	94	209	-	-	-	-	1,560
3b.1.1.15	Secondary building	-	-	-	-	-	-	319	48	366	37	-	-	-	-	2,730
3b.1.1.16	Reactor building	-	-	-	-	-	-	319	48	366	37	-	-	-	-	2,730
3b.1.1	Total	-	-	-	-	-	-	3,763	565	4,328	839	-	-	-	-	32,243
3b.1	Subtotal Period 3b Activity Costs	-	-	-	-	-	-	3,763	565	4,328	839	-	-	-	-	32,243
Period 3b: Additional Costs																
3b.2	Site Characterization	-	-	-	-	-	-	2,551	705	3,256	-	-	-	-	-	19,100
3b.2	Subtotal Period 3b: Additional Costs	-	-	-	-	-	-	2,551	705	3,256	-	-	-	-	-	19,100
Period 3b: Collateral Costs																
3b.3.1	Decon equipment	872	-	-	-	-	-	-	131	1,003	-	-	-	-	-	-
3b.3.2	DOC staff relocation expenses	-	-	-	-	-	-	-	162	1,242	-	-	-	-	-	-
3b.3.3	Pipe-cutting equipment	-	1,100	-	-	-	-	-	165	1,265	-	-	-	-	-	-
3b.3	Subtotal Period 3b: Collateral Costs	872	1,100	-	-	-	-	1,080	458	3,510	-	-	-	-	-	-
Period 3b: Period-Dependent Costs																
3b.4.1	Decon supplies	53	-	-	-	-	-	-	13	67	67	-	-	-	-	-
3b.4.2	Insurance	-	-	-	-	-	-	-	59	645	645	-	-	-	-	-
3b.4.3	Property taxes	-	-	-	-	-	-	-	28	308	308	-	-	-	-	-
3b.4.4	Health physics supplies	-	407	-	-	-	-	-	165	572	572	-	-	-	-	-
3b.4.5	Health physics equipment	-	438	-	-	-	-	-	165	603	603	-	-	-	-	-
3b.4.6	Disposal of DAW generated	-	-	-	2	-	-	-	8	50	50	-	-	11,636	19	-
3b.4.7	Plant energy budget	-	-	-	-	-	-	724	109	832	832	-	-	-	-	-
3b.4.8	NRC Fees	-	-	-	-	-	-	272	27	299	299	-	-	-	-	-
3b.4.9	Corporate Allocations	-	-	-	-	-	-	2,610	261	2,871	2,871	-	-	-	-	65,179
3b.4.10	DOC Staff Cost	-	-	-	-	-	-	10,435	1,043	11,478	11,478	-	-	-	-	116,800
3b.4.11	DOC Staff Cost	-	-	-	-	-	-	10,435	1,043	11,478	11,478	-	-	-	-	116,800
3b.4.12	Utility Staff Cost	-	-	-	-	-	-	17,468	2,019	20,077	20,077	-	-	-	-	258,629
3b.4.12	Utility Staff Cost	-	-	-	-	-	-	17,468	2,019	20,077	20,077	-	-	-	-	258,629
3b.4.12	Subtotal Period 3b: Period-Dependent Costs	53	873	12	2	-	-	35,530	5,338	41,837	41,837	-	-	11,636	19	440,697
3b.0	TOTAL PERIOD 3b: COST	926	1,973	12	2	-	-	42,924	7,126	52,990	52,151	-	-	11,636	19	480,702
PERIOD 3 TOTALS		926	2,263	18	3	-	-	69,239	11,056	83,675	82,196	-	-	16,822	19,127	716,639
PERIOD 4a - Large Component Removal																
Period 4a: Direct Decommissioning Activities																
4a.1.1.1	Reactor Coolant Pump Removal	36	171	25	14	130	182	-	130	689	689	-	-	-	-	3,957
4a.1.1.2	Reactor Coolant Pump	6	23	7	4	37	47	-	27	151	151	-	-	-	-	694
4a.1.1.3	Pressurizer Relief Tank	20	83	48	175	889	284	-	326	1,926	1,926	-	-	-	-	8,161,140
4a.1.1.4	Pressurizer	9	56	413	140	2,179	2,497	-	326	21,944	21,944	-	-	-	-	240,915
4a.1.1.5	Steam Generators	77	4,985	2,179	2,497	2,649	5,018	-	326	21,944	21,944	-	-	-	-	3,340,305
4a.1.1.6	Steam Generators	31	1,933	2,179	2,497	2,649	5,018	-	326	21,944	21,944	-	-	-	-	20,308
4a.1.1.7	CRDMs/ICHS/Generator Uchis	81	2,933	2,179	2,497	2,649	5,018	-	326	21,944	21,944	-	-	-	-	2,250
4a.1.1.8	Reactor Vessel Internals	50	2,655	7,310	671	766	189	-	1,007	681	681	-	-	-	-	3,340,305
4a.1.1.9	Vessel & Internals (GTCC Disposal)	-	-	-	-	-	-	3,778	195	5,952	20,641	-	-	-	-	2,250
4a.1.1.10	Reactor Vessel	-	5,663	1,350	280	-	10,743	-	1,611	12,355	12,355	-	-	-	-	965
4a.1.1.10	Reactor Vessel	-	5,663	1,350	280	-	10,743	-	1,611	12,355	12,355	-	-	-	-	965
4a.1.1	Totals	229	13,747	13,743	6,313	5,321	30,571	391	20,304	90,619	90,619	-	-	2,142	19	83,850
Removal of Major Equipment																
4a.1.2	Main Turbine/Generator	-	442	284	37	837	-	-	270	1,871	1,871	-	-	-	-	8,721
4a.1.3	Main Condensers	-	1,263	174	31	737	-	-	448	2,653	2,653	-	-	-	-	24,802
Crewing Costs from Clean Building Demolition																
4a.1.4.1	Reactor	-	902	-	-	-	-	-	135	1,037	-	-	-	-	-	10,375
4a.1.4.2	Secondary Building	-	229	-	-	-	-	-	83	253	-	-	-	-	-	2,395
4a.1.4.3	Fuel Building	-	229	-	-	-	-	-	83	253	-	-	-	-	-	2,395



Table D  
Callaway Energy Center  
SAFSTOR Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Direct Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	Site Remediation Costs	Processed Class A	Burial Volumes Class A	Class C	Class D	Burial/Processed Wt. Lbs.	Cu. Feet	Cu. Feet	Cu. Feet	Utility and Other Members	
4a.1.4.4	Hot Machine Shop	1							0	1										16	
4a.1.4.5	Radiation	95							14	109										1,108	
4a.1.4	Totals	1,675							251	1,926										19,646	
4a.1.5.1	100 Aux. Bldg Non-System Specific RCA		705	11	26	626			275	1,644						3,093,812				13,471	
4a.1.5.2	100 Auxiliary Bldg Non-System Specific		104	2	3	68	5		38	219						35,461				2,030	
4a.1.5.3	AB - Main Steam		270						48	315						87,550				5,833	
4a.1.5.4	AB - Main Steam RCA		79	3	7	177			48	315						87,550				1,515	
4a.1.5.5	AC - Main Turbine		203						44	337						6,141				6,141	
4a.1.5.6	AD - Condenser		202						30	232						4,271				4,271	
4a.1.5.7	AE - Feedwater		249						37	286						5,352				852	
4a.1.5.8	AF - Feedwater Heater Extraction		42						14	105						1,944				1,944	
4a.1.5.9	AK - Condensate Demineralizer		40						6	46						852				852	
4a.1.5.10	AL - Auxiliary Feedwater		169						42	252						46,993				2,138	
4a.1.5.11	AQ - Condensate & Feedwater Chem Addn		10						11	11						166,857				7,066	
4a.1.5.12	AR - Steam Generator Blowdown - RCA		389						148	885						254,024				6,161	
4a.1.5.13	BM - Steam Generator Blowdown - RCA		307						158	1,069						6,255				465	
4a.1.5.14	BN - Bormed Reducing Water Storage		21						3	24										2,107	
4a.1.5.15	CA - Steam Seal		69						9	69										198	
4a.1.5.16	CB - Main Turbine Lubcs Oil		10						1	11										198	
4a.1.5.17	CC - Generator Hydrogen Seal & CO2		10						1	11										198	
4a.1.5.18	CD - Steam Generator Blowdown - RCA		12						2	14										241	
4a.1.5.19	CE - Steam Cooling Water		39						6	44										812	
4a.1.5.20	CF - Lubcs Oil Storage Xfer & Pfrication		61						5	36										657	
4a.1.5.21	CG - Condenser Air Removal		349						52	401										1,219	
4a.1.5.22	CH - Main Turbine Control Oil		82						8	69										7,302	
4a.1.5.23	DA - Circulating Water		289	5	12	292			116	706						144,376				1,080	
4a.1.5.24	DB - Cooling Water Storage & Blowdown		362	26	30	368	192		201	1,179						256,270				4,951	
4a.1.5.25	DD - Cooling Water Chemical Control SSS		309	3	8	182			106	697						89,903				7,137	
4a.1.5.26	DE - Cooling Water Chemical Control SSS		223	5	10	248			95	381						122,874				4,134	
4a.1.5.27	EJ - Residual Heat Removal		194	3	7	163			66	470						80,762				3,12	
4a.1.5.28	EM - High Pressure Coolant Injection		94						15	112										2106	
4a.1.5.29	EN - Containment Spray		84	1	3	67			32	187						33,148				1,537	
4a.1.5.30	FA - Auxiliary Steam Generator		63						9	73										1,320	
4a.1.5.31	FB - Auxiliary Steam RCA		179						1	6										105	
4a.1.5.32	FC - Auxiliary Turbines		467						207	207										3,957	
4a.1.5.33	FD - Auxiliary Steam Chemical Addition		913						284	1,213						32,539				3,957	
4a.1.5.34	FE - Auxiliary Steam HVAC		467	1	3	66			52	168						191,035				8,962	
4a.1.5.35	FF - Turbine Building HVAC		913	20	22	284	131		187	1,121						443,537				17,817	
4a.1.5.36	GG - Gas		32						409	2,365											690
4a.1.5.37	HH - Boron Recycle		92	10	22	529			107	760						261,890				1,825	
4a.1.5.38	HF - Secondary Liquid Waste		81						27	298						3,885				3,885	
4a.1.5.39	HG - Secondary Liquid Waste		731						113	863						91,628				15,405	
4a.1.5.40	JA - Auxiliary Oil & Transfer		8,362	153	249	4,890	500		2,677	16,921						2,648,658				166,857	
4a.1.5.41	KB - Bulk Chemical Storage								392	2,023										33,634	
4a.1.5.42	LC - Oil Waste								24,342	116,013										470	
4a.1.5.43	LD - Oil Waste								112	18										62,415	
4a.1.5.44	LE - Oil Waste								392	2,023										62,415	
4a.1.5	Totals	229	25,587	14,382	6,636	11,597	31,179	391	24,342	116,013						13,206,740				8,009	
4a.1.6	Scaffolding in support of decommissioning																				
4a.1	Subtotal Period in Activity Costs																				
4a.3.1	Collateral Costs																				
4a.3.3	Small tool allowance		5		19		27		12	68											
4a.3.4	On-site survey and release of 60.87 tons clean metallic waste		285					62	43	328										15	
4a.3	Subtotal Period in Collateral Costs		285		19		27	62	61	464											
4a.4	Period 4a Period-Dependent Costs																				
4a.4.1	Decom supplies		63						16	78											
4a.4.2	Insurance							691	69	760											
4a.4.3	Property taxes							330	33	363											
4a.4.4	Health physics supplies		1,945						486	2,431											
4a.4.5	Health physics equipment		2,236						362	2,598											
4a.4.6	Disposal of DAW generated			100	17		217		67	401										152	

**Table D**  
**Callaway Energy Center**  
**SAFSTOR Decommissioning Cost Estimate**  
(thousands of 2011 dollars)

Activity Index	Activity Description	Direct Cost	Removal Cost	Prepacking Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	Total Lic. Costs	Site Remediation Costs	Spent Fuel Management Costs	Processed Class A	Burial Volumes	Class A	Class C	Burial/Prepacked Wt. Lbs.	Conf. Manhours	Utility and Other Manhours	
<b>Period 4a - Period-Dependent Costs (continued)</b>																					
4a.4.7	Plant energy budget	-	-	-	-	-	-	810	122	932	-	-	-	-	-	-	-	-	-	-	
4a.4.8	NRG Fees	-	-	-	-	-	-	845	85	930	-	-	-	-	-	-	-	-	-	-	
4a.4.9	Liquid Radwaste Processing Equipment/Services	-	-	-	-	-	-	807	68	875	-	-	-	-	-	-	-	-	-	-	
4a.4.10	Specialized Staff	-	-	-	-	-	-	3,728	559	4,288	-	-	-	-	-	-	-	-	-	76,786	
4a.4.11	DOC Staff Cost	-	-	-	-	-	-	14,731	2,210	16,941	-	-	-	-	-	-	-	-	-	169,543	
4a.4.12	Utility Staff Cost	-	-	-	-	-	-	20,691	3,104	23,794	-	-	-	-	-	-	-	-	-	307,143	
4a.4.13	Subtotal Period 4a Period-Dependent Costs	63	4,181	100	17	-	217	51,103	8,095	63,716	-	-	-	-	-	-	-	-	-	558,471	
4a.4	TOTAL PERIOD 4a COST	296	31,423	14,487	6,672	11,597	31,423	51,556	32,439	180,193	-	4,082	-	156,147	75,349	376	470	2,142	13,306,500	337,676	861,481
<b>PERIOD 4b - Site Decontamination</b>																					
<b>Period 4b Direct Decommissioning Activities</b>																					
4b.1.1	Remove spent fuel racks	700	83	310	87	-	1,154	-	733	3,127	3,127	-	-	-	-	-	-	-	-	-	1,925
<b>Disposal of Plant Systems</b>																					
4b.1.2.1	200 Reactor Bldg Non-System Specific	-	84	1	2	41	3	-	28	160	160	-	-	502	14	-	-	-	-	-	1,569
4b.1.2.2	200 Reactor Bldg Non-System Specific RCA	-	583	7	16	391	-	-	208	1,205	1,205	-	-	4,768	-	-	-	-	-	-	10,425
4b.1.2.3	300 Control Bldg Non-System Specific	-	181	3	7	175	-	-	73	440	440	-	-	2,139	-	-	-	-	-	-	3,413
4b.1.2.4	300 Control Bldg Non-System Specific Ch	-	1,382	-	-	-	-	-	207	1,589	-	1,589	-	-	-	-	-	-	-	-	29,076
4b.1.2.5	600 Fuel Bldg Non-System Specific RCA	-	317	-	-	263	-	-	121	716	716	-	-	3,280	-	-	-	-	-	-	128,374
4b.1.2.6	600 Fuel Bldg Non-System Specific RCA	-	1,163	-	-	1,041	-	-	455	2,721	2,721	-	-	12,684	9	-	-	-	-	-	5,859
4b.1.2.7	700 Radwaste Bldg Non-System Specific	-	1,163	19	43	1,041	-	-	455	2,721	2,721	-	-	12,684	-	-	-	-	-	-	21,919
4b.1.2.8	700 Radwaste Bldg Non-System Specific RCA	-	168	3	5	109	8	-	23	176	176	-	-	1,329	38	-	-	-	-	-	3,252
4b.1.2.9	AN - Demineralized Wtr Storage & Xtr	-	153	-	-	26	-	-	14	83	83	-	-	314	-	-	-	-	-	-	3,283
4b.1.2.10	AN - Demineralized Wtr Storage & Xtr RCA	-	89	-	-	219	189	-	103	103	103	-	-	9,586	-	-	-	-	-	-	740
4b.1.2.11	AP - Condensate Storage & Transfer	-	316	23	53	672	617	-	446	2,547	2,547	-	-	8,192	605	-	-	-	-	-	1,794
4b.1.2.12	AP - Condensate Storage & Transfer RCA	-	893	47	68	672	617	-	446	2,547	2,547	-	-	8,192	1,954	-	-	-	-	-	17,230
4b.1.2.13	BL - Reactor Makeup Water	-	283	12	14	207	69	-	122	708	708	-	-	2,529	330	-	-	-	-	-	5,490
4b.1.2.14	BL - Reactor Makeup Water RCA	-	18	-	-	-	-	-	18	140	140	-	-	-	-	-	-	-	-	-	2,517
4b.1.2.15	DE - Intake & Water Treatment	-	253	18	41	978	-	-	218	1,508	1,508	-	-	11,923	-	-	-	-	-	-	5,014
4b.1.2.16	DE - Intake & Water Treatment RCA	-	146	-	-	102	-	-	22	168	168	-	-	1,248	-	-	-	-	-	-	3,115
4b.1.2.17	EA - Service Water	-	68	-	-	58	182	-	49	68	68	-	-	4,119	-	-	-	-	-	-	1,409
4b.1.2.18	EA - Service Water RCA	-	59	-	-	49	68	-	147	878	878	-	-	6,288	-	-	-	-	-	-	1,285
4b.1.2.19	EB - Chilled Water	-	374	6	14	338	-	-	51	388	388	-	-	3,888	-	-	-	-	-	-	7,163
4b.1.2.20	EC - Fuel Pool Cooling & Cleanup	-	337	-	-	437	-	-	120	786	786	-	-	5,326	-	-	-	-	-	-	7,244
4b.1.2.21	EF - Essential Service Water	-	203	8	18	437	-	-	37	285	285	-	-	285	-	-	-	-	-	-	3,862
4b.1.2.22	EF - Essential Service Water RCA	-	247	-	-	-	-	-	102	102	102	-	-	-	-	-	-	-	-	-	5,335
4b.1.2.23	EG - Component Cooling Water RCA	-	68	-	-	52	-	-	7	37	37	-	-	638	-	-	-	-	-	-	1,912
4b.1.2.24	GA - Plant Heating	-	21	0	0	9	-	-	107	107	107	-	-	1,400	-	-	-	-	-	-	4,351
4b.1.2.25	GA - Plant Heating Fuel Building	-	83	-	-	9	-	-	12	96	96	-	-	107	-	-	-	-	-	-	1,803
4b.1.2.26	GB - Central Chilled Water	-	27	0	1	15	-	-	3	22	22	-	-	187	-	-	-	-	-	-	482
4b.1.2.27	GB - Central Chilled Water RCA	-	19	-	-	67	-	-	36	353	353	-	-	2,094	-	-	-	-	-	-	2,026
4b.1.2.28	GD - Essential Serv Wtr Pumphouse HVAC	-	327	3	7	334	-	-	16	350	350	-	-	3,004	-	-	-	-	-	-	3,004
4b.1.2.29	GD - Essential Serv Wtr Pumphouse HVAC RCA	-	207	-	-	210	-	-	201	201	201	-	-	2,561	-	-	-	-	-	-	3,959
4b.1.2.30	GF - Miscellaneous Building HVAC	-	167	4	9	210	-	-	25	201	201	-	-	5,381	-	-	-	-	-	-	7,364
4b.1.2.31	GH - Radwaste Building HVAC	-	175	-	-	210	-	-	35	1,054	1,054	-	-	8,264	-	-	-	-	-	-	8,405
4b.1.2.32	GH - Radwaste Building HVAC RCA	-	413	8	18	441	-	-	5	35	35	-	-	8,264	-	-	-	-	-	-	8,405
4b.1.2.33	GK - Control Building HVAC	-	30	-	-	22	-	-	19	136	136	-	-	1,163	-	-	-	-	-	-	330
4b.1.2.34	GL - Auxiliary Building HVAC	-	461	12	28	678	-	-	55	353	353	-	-	2,185	-	-	-	-	-	-	4,407
4b.1.2.35	GM - Diesel Generator Building HVAC	-	18	-	-	94	-	-	19	136	136	-	-	1,163	-	-	-	-	-	-	330
4b.1.2.36	GN - Containment Upgrade HVAC	-	108	3	7	179	-	-	55	353	353	-	-	2,185	-	-	-	-	-	-	4,407
4b.1.2.37	GO - Containment Upgrade HVAC RCA	-	334	5	13	303	-	-	131	786	786	-	-	3,699	-	-	-	-	-	-	1,973
4b.1.2.38	GP - Containment Purge HVAC	-	807	40	43	604	239	-	363	2,097	2,097	-	-	7,362	1,131	-	-	-	-	-	6,286
4b.1.2.39	GT - Containment Purge HVAC RCA	-	346	19	21	245	-	-	142	938	938	-	-	2,985	654	-	-	-	-	-	15,491
4b.1.2.40	HA - Gaseous Radwaste	-	5	-	-	81	-	-	44	258	258	-	-	383	132	-	-	-	-	-	6,644
4b.1.2.41	HB - Liquid Radwaste	-	183	-	-	222	-	-	29	222	222	-	-	72	-	-	-	-	-	-	1,283
4b.1.2.42	HC - Solid Radwaste	-	132	1	3	66	-	-	43	246	246	-	-	801	-	-	-	-	-	-	4,187
4b.1.2.43	HD - Decontamination	-	24	-	-	102	-	-	4	28	28	-	-	71	-	-	-	-	-	-	2,339
4b.1.2.44	HE - Compressed Air	-	183	-	-	222	-	-	29	222	222	-	-	72	-	-	-	-	-	-	4,187
4b.1.2.45	KA - Compressed Air	-	132	1	3	66	-	-	43	246	246	-	-	801	-	-	-	-	-	-	2,339
4b.1.2.46	KB - Breathing Air	-	24	-	-	102	-	-	4	28	28	-	-	71	-	-	-	-	-	-	516
4b.1.2.47	KB - Breathing Air RCA	-	20	0	0	6	-	-	32	32	32	-	-	2874	-	-	-	-	-	-	402
4b.1.2.48	KC - Fire Protection RCA	-	382	7	15	362	-	-	37	439	439	-	-	4,411	-	-	-	-	-	-	8,376
4b.1.2.49	KD - Fire Protection RCA	-	122	2	4	102	-	-	17	102	102	-	-	1,239	-	-	-	-	-	-	1,701
4b.1.2.51	KC - Fire Protection Fuel Building	-	122	2	4	102	-	-	17	102	102	-	-	1,239	-	-	-	-	-	-	2,115

Table D  
Callaway Energy Center  
SAFSTOR Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Decon Cost	Renewal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Contingency	Total Contingency	Total Costs	Site Remediation Costs	Processed Class A - Cu. Feet	Burial Volumes - Cu. Feet	Class C - Cu. Feet	Burial/Prepacked - Wt. Lbs.	Cu. Feet	Members	Utility and Other Members
Disposal of Plant Systems (continued)																		
4b1.2.62	KD - Domestic Water	-	177	-	-	1	20	-	27	204	-	-	-	-	-	-	-	-
4b1.2.63	KD - Domestic Water	-	27	0	-	1	72	-	10	58	-	247	-	-	-	-	-	-
4b1.2.64	KE - Fuel Handling & Storage Reactor vessel	-	17	1	3	-	72	-	16	109	-	882	-	-	-	-	-	-
4b1.2.65	KH - Service Gas (CO2, N2, H2 & O2) RCA	-	269	4	-	8	200	-	96	568	-	2,433	-	-	-	-	-	-
4b1.2.67	KJ - Standby Diesel Engine	-	330	-	-	-	-	-	50	380	-	-	-	-	-	-	-	-
4b1.2.68	LA - Sanitary Drains	-	45	-	-	-	104	-	7	52	-	-	-	-	-	-	-	-
4b1.2.69	LA - Sanitary Drains	-	109	2	4	-	175	-	44	264	-	1,273	-	-	-	-	-	-
4b1.2.69	LB - Roof Drains	-	60	-	-	-	175	-	9	68	-	2,159	-	-	-	-	-	-
4b1.2.69	LC - Roof Drains	-	112	-	-	-	105	-	58	210	-	707	-	-	-	-	-	-
4b1.2.69	LD - Chemical & Decontamination Waste	-	112	-	-	-	105	-	58	210	-	707	-	-	-	-	-	-
4b1.2.69	LE - Floor & Equipment Drains	-	1380	67	68	-	566	-	594	3,254	-	6,660	-	-	-	-	-	-
4b1.2.69	LF - Floor & Equipment Drains	-	123	1	3	-	81	-	44	253	-	6,660	-	-	-	-	-	-
4b1.2.65	SJ - Nuclear Sampling	-	181	-	-	-	56	-	27	298	-	677	-	-	-	-	-	-
4b1.2.66	UB - Services Stores Site Security Bldg and Non-System Specific	-	15,629	367	-	-	10,324	-	5,535	34,139	-	125,856	-	-	-	-	-	-
4b1.2	Totals	-	2,900	42	9	168	27	-	588	3,034	-	1,849	-	-	-	-	-	-
4b1.3	Scarfolding in support of decommissioning	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Decontamination of Site Buildings																		
4b1.4.1	Reactor	1,125	911	31	157	-	492	-	1,166	4,894	-	5,995	-	-	-	-	-	-
4b1.4.2	Communication	201	201	0	4	-	129	-	48	1,068	-	2,078	-	-	-	-	-	-
4b1.4.3	Communication Corridor - Contaminated	13	3	0	1	-	2	-	8	29	-	42	-	-	-	-	-	-
4b1.4.4	Fuel Building	700	721	8	18	-	222	-	578	2,988	-	2,705	-	-	-	-	-	-
4b1.4.4	Hot Machine Shop	16	6	0	1	-	3	-	10	36	-	51	-	-	-	-	-	-
4b1.4.4	RAM Storage Building	40	8	0	2	-	2	-	24	82	-	19	-	-	-	-	-	-
4b1.4.7	Radiosactive and Personnel Tunnel	5	5	0	1	-	17	-	4	17	-	17	-	-	-	-	-	-
4b1.4.9	Richards Drum Storage	315	162	0	22	-	69	-	175	844	-	844	-	-	-	-	-	-
4b1.4.10	Steam Generator Replacement Bldgs	35	10	0	2	-	5	-	23	88	-	66	-	-	-	-	-	-
4b1.4.10	Totals	213	1987	54	246	-	960	-	106	319	-	11,704	-	-	-	-	-	-
4b1.4	Totals	3,046	1,987	773	963	-	11,463	-	2,528	10,169	-	13,241	-	-	-	-	-	-
4b1	Subtotal Period 4b Activity Costs	3,806	19,899	773	963	-	11,463	-	9,404	50,410	-	45,269	-	-	-	-	-	-
Period 4b Additional Costs																		
4b2.1	License Termination Survey Program Management	-	-	-	-	-	-	-	410	1,776	-	-	-	-	-	-	-	-
4b2.2	Sanitary Treatment Lagoons LLW	-	5	75	781	-	207	-	178	1,247	-	-	-	-	-	-	-	-
4b2.3	Cooling Tower Asbestos Panel Removal	-	-	-	109	-	-	-	821	6,296	-	-	-	-	-	-	-	-
4b2	Subtotal Period 4b Additional Costs	-	4,983	75	890	-	207	-	1,834	1,409	-	3,600	-	-	-	-	-	-
Period 4b Collateral Costs																		
4b3.1	Process decommissioning water waste	13	-	14	53	-	74	-	34	187	-	-	-	-	-	-	-	-
4b3.3	Small tool allowance	-	444	-	-	-	-	-	67	510	-	-	-	-	-	-	-	-
4b3.4	Decommissioning Equipment Disposition	-	-	138	34	-	87	-	123	928	-	6,000	-	-	-	-	-	-
4b3.5	On-site survey and release of 297.3 tons clean metallic waste	-	-	152	87	-	162	-	30	334	-	-	-	-	-	-	-	-
4b3	Subtotal Period 4b Collateral Costs	13	444	152	87	-	162	-	303	1,959	-	6,000	-	-	-	-	-	-
Period 4b Period-Dependent Costs																		
4b4.1	Decon supplies	1,246	-	-	-	-	-	-	311	1,557	-	-	-	-	-	-	-	-
4b4.2	Insurance	-	-	-	-	-	-	-	167	1,836	-	-	-	-	-	-	-	-
4b4.3	Property taxes	-	-	-	-	-	-	-	80	875	-	-	-	-	-	-	-	-
4b4.4	Health physics supplies	-	3,981	-	-	-	-	-	895	4,476	-	-	-	-	-	-	-	-
4b4.5	Energy services contract	-	5,354	-	-	-	-	-	867	6,477	-	-	-	-	-	-	-	-
4b4.6	Decon LLW generated	-	-	146	25	-	316	-	97	1,884	-	-	-	-	-	-	-	-
4b4.7	Plant energy budget	-	-	-	-	-	-	-	232	1,775	-	-	-	-	-	-	-	-
4b4.8	NRC Fees	-	-	-	-	-	-	-	204	2,244	-	-	-	-	-	-	-	-
4b4.9	Liquid Radwaste Processing Equipment/Services	-	-	-	-	-	-	-	165	1,267	-	-	-	-	-	-	-	-
4b4.10	Corporate Allocations	-	-	-	-	-	-	-	963	10,690	-	-	-	-	-	-	-	-
4b4.11	Decommissioning Staff Cost	-	-	-	-	-	-	-	30,889	30,889	-	-	-	-	-	-	-	-
4b4.12	Decommissioning Staff Cost	-	-	-	-	-	-	-	4,292	4,292	-	-	-	-	-	-	-	-
4b4.13	Utility Staff Cost	-	-	-	-	-	-	-	71,097	54,485	-	-	-	-	-	-	-	-
4b4	Subtotal Period 4b Period-Dependent Costs	1,246	8,934	146	25	-	316	-	107,841	136,084	-	6,780	-	-	-	-	-	-
4b0	TOTAL PERIOD 4b COST	5,065	34,180	1,145	1,505	-	11,398	-	28,643	197,772	-	145,409	-	-	-	-	-	-
4b0	TOTAL PERIOD 4b COST	5,065	34,180	1,145	1,505	-	11,398	-	28,643	197,772	-	145,409	-	-	-	-	-	-
4b0	TOTAL PERIOD 4b COST	5,065	34,180	1,145	1,505	-	11,398	-	28,643	197,772	-	145,409	-	-	-	-	-	-

Table D  
Callaway Energy Center  
SAFSTOR Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Direct Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Costs	Spent Fuel Management Costs	Site Remediation Costs	Processed Class A	Burial Volumes		CWC	Burial/Pre-Used Wt., Lbs.	Cnfg. Manhours	Utility and Contractor Manhours
															Cu. Feet	Cu. Feet				
<b>PERIOD 4f - License Termination</b>																				
Period of Direct Decommissioning Activities																				
4f.1.1	ORISE confirmatory survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4f.1.2	Subtotal Period of Activity Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4f.1	Subtotal Period of Activity Costs	-	-	-	-	-	-	154	46	200	200	-	-	-	-	-	-	-	-	-
Period of Additional Costs																				
4f.2.1	License Termination Survey	-	-	-	-	-	-	7,808	2,342	10,150	10,150	-	-	-	-	-	-	-	-	-
4f.2	Subtotal Period of Additional Costs	-	-	-	-	-	-	7,808	2,342	10,150	10,150	-	-	-	-	-	-	-	-	149,339
4f.2	Subtotal Period of Additional Costs	-	-	-	-	-	-	7,808	2,342	10,150	10,150	-	-	-	-	-	-	-	-	149,339
Period of Collateral Costs																				
4f.3.1	DOC staff relocation expenses	-	-	-	-	-	-	1,080	162	1,242	1,242	-	-	-	-	-	-	-	-	-
4f.3	Subtotal Period of Collateral Costs	-	-	-	-	-	-	1,080	162	1,242	1,242	-	-	-	-	-	-	-	-	-
Period of Period-Dependent Costs																				
4f.4.1	Insurance	-	-	-	-	-	-	212	21	233	233	-	-	-	-	-	-	-	-	-
4f.4.2	Health physics supplies	-	-	-	-	-	-	165	5	170	170	-	-	-	-	-	-	-	-	-
4f.4.3	Health physics supplies	661	-	-	-	-	16	109	16	126	126	-	-	-	-	-	-	-	-	-
4f.4.4	Disposal of DAW generated	-	-	8	1	-	-	582	58	640	640	-	-	-	-	-	-	-	-	11
4f.4.5	Plant energy budget	-	-	-	-	-	-	1,409	144	1,554	1,554	-	-	-	-	-	-	-	-	-
4f.4.6	Plant energy budget	-	-	-	-	-	-	1,409	144	1,554	1,554	-	-	-	-	-	-	-	-	-
4f.4.7	Corporate Allocations	-	-	-	-	-	-	1,409	144	1,554	1,554	-	-	-	-	-	-	-	-	-
4f.4.8	Supplies	-	-	-	-	-	-	1,409	144	1,554	1,554	-	-	-	-	-	-	-	-	-
4f.4.9	DOC Staff Cost	-	-	-	-	-	-	5,171	776	5,946	5,946	-	-	-	-	-	-	-	-	18,996
4f.4.10	Utility Staff Cost	-	-	-	-	-	-	5,739	861	6,600	6,600	-	-	-	-	-	-	-	-	57,566
4f.4	Subtotal Period of Period-Dependent Costs	661	-	8	1	-	16	14,259	2,197	17,143	17,143	-	-	-	-	-	-	-	-	74,914
4f.4	Subtotal Period of Period-Dependent Costs	661	-	8	1	-	16	14,259	2,197	17,143	17,143	-	-	-	-	-	-	-	-	151,406
4f.0	TOTAL PERIOD 4f COST	-	661	8	1	-	16	23,300	4,748	28,734	28,734	-	-	-	-	-	-	-	-	157,646
4f.0	TOTAL PERIOD 4f COST	5,361	66,263	15,640	8,578	23,895	36,297	184,834	65,830	406,688	391,199	-	15,499	301,556	113,219	376	470	21,887,310	1,041,205	2,014,278
<b>PERIOD 4 TOTALS</b>																				
<b>PERIOD 5b - Site Restoration</b>																				
Period 5b Direct Decommissioning Activities																				
Demolition of Remaining Site Buildings																				
5b.1.1.1	Reactor	-	5,121	-	-	-	-	-	768	5,889	-	-	5,889	-	-	-	-	-	-	60,047
5b.1.1.2	Auxiliary	-	4,111	-	-	-	-	-	617	4,728	-	-	4,728	-	-	-	-	-	-	49,968
5b.1.1.3	Auxiliary Boiler	-	38	-	-	-	-	-	6	43	-	-	43	-	-	-	-	-	-	619
5b.1.1.4	Badge Facility	-	1,661	-	-	-	-	-	234	1,795	-	-	1,795	-	-	-	-	-	-	18,771
5b.1.1.5	Circulating & Service Water Pumphouse	-	314	-	-	-	-	-	147	361	-	-	361	-	-	-	-	-	-	4,345
5b.1.1.6	Communication Corridor - Contaminated	-	1,354	-	-	-	-	-	169	1,524	-	-	1,524	-	-	-	-	-	-	17,625
5b.1.1.7	Communication Corridor - Contaminated	-	57	-	-	-	-	-	9	66	-	-	66	-	-	-	-	-	-	674
5b.1.1.8	Cooling Tower Basement	-	894	-	-	-	-	-	134	1,028	-	-	1,028	-	-	-	-	-	-	13,472
5b.1.1.9	Disposal Generator	-	486	-	-	-	-	-	73	559	-	-	559	-	-	-	-	-	-	5,492
5b.1.1.10	Essential Service Water Pumphouse	-	289	-	-	-	-	-	45	343	-	-	343	-	-	-	-	-	-	3,938
5b.1.1.11	Fire Water Pumphouse	-	28	-	-	-	-	-	36	64	-	-	64	-	-	-	-	-	-	382
5b.1.1.12	Hot Machine Shop	-	2,076	-	-	-	-	-	36	2,112	-	-	2,112	-	-	-	-	-	-	22,382
5b.1.1.13	Hot Machine Shop	-	24	-	-	-	-	-	4	27	-	-	27	-	-	-	-	-	-	417
5b.1.1.14	Intake	-	369	-	-	-	-	-	55	424	-	-	424	-	-	-	-	-	-	4,224
5b.1.1.15	Misc. Structures	-	2,357	-	-	-	-	-	353	2,710	-	-	2,710	-	-	-	-	-	-	27,821
5b.1.1.16	Miscellaneous Site Foundations	-	372	-	-	-	-	-	56	428	-	-	428	-	-	-	-	-	-	5,483
5b.1.1.17	Outage Maintenance	-	185	-	-	-	-	-	28	213	-	-	213	-	-	-	-	-	-	3,190
5b.1.1.18	Storage Building	-	28	-	-	-	-	-	4	32	-	-	32	-	-	-	-	-	-	386
5b.1.1.19	Storage Building	-	28	-	-	-	-	-	4	32	-	-	32	-	-	-	-	-	-	386
5b.1.1.20	Radwaste and Personnel Tunnel	-	28	-	-	-	-	-	4	32	-	-	32	-	-	-	-	-	-	386
5b.1.1.21	Radwaste Drum Storage	-	1,831	-	-	-	-	-	275	2,106	-	-	2,106	-	-	-	-	-	-	21,798
5b.1.1.22	Security Additions	-	272	-	-	-	-	-	41	313	-	-	313	-	-	-	-	-	-	3,840
5b.1.1.23	Service	-	2,224	-	-	-	-	-	334	2,557	-	-	2,557	-	-	-	-	-	-	20,577
5b.1.1.24	Sludge Pump Station & Lagoon	-	502	-	-	-	-	-	75	577	-	-	577	-	-	-	-	-	-	6,045
5b.1.1.25	Storage Building	-	28	-	-	-	-	-	4	32	-	-	32	-	-	-	-	-	-	386
5b.1.1.26	Turbine Pedestal	-	3,648	-	-	-	-	-	178	3,826	-	-	3,826	-	-	-	-	-	-	45,694
5b.1.1.27	Turbine Pedestal	-	1,063	-	-	-	-	-	547	4,195	-	-	4,195	-	-	-	-	-	-	55,694
5b.1.1.28	U.H.S. Cooling Tower	-	638	-	-	-	-	-	96	734	-	-	734	-	-	-	-	-	-	10,928
5b.1.1.29	Water Treatment Plant	-	1	-	-	-	-	-	0	1	-	-	1	-	-	-	-	-	-	6,681
5b.1.1	Totals	-	31,051	-	-	-	-	-	4,658	35,708	-	-	35,708	-	-	-	-	-	-	392,179

Table D  
Callaway Energy Center  
SAFSTOR Decommissioning Cost Estimate  
(thousands of 2011 dollars)

Activity Index	Activity Description	Direct Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NIC Lic. Costs	Spent Fuel Management Costs	Site Remediation Costs	Processed Class A	Burial Volumes		Burial/Prep. Wt., Lbs.	Ccu/Ft. Members	Utility and Other Members	
															Cu. Feet	Cu. Feet				
5b.1.2	Site Closeout Activities	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
5b.1.3	Backfill Site	-	9,320	-	-	-	-	-	1,388	10,718	-	-	10,718	-	-	-	-	-	17,028	
5b.1.4	Grade & landscape site	-	124	-	-	-	-	-	19	142	-	-	142	-	-	-	-	-	592	
5b.1	Final report to NIC	-	-	-	-	-	-	-	27	269	-	-	269	-	-	-	-	-	1,560	
5b.2.1	Subtotal Period 5b Activity Costs	-	40,494	-	-	-	-	182	6,101	46,778	209	-	46,568	-	-	-	-	-	4,007,700	
5b.2	Period 5b Additional Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
5b.2.1	Concrete Crushing	-	1,226	-	-	-	-	9	185	1,419	-	-	1,419	-	-	-	-	-	5,830	
5b.2.2	Mine Area Backfill	-	4,219	-	-	-	-	-	633	4,852	-	-	4,852	-	-	-	-	-	15,960	
5b.2.3	Cooling Tower Discharge & Intake Pipe Flow Fill	-	3,779	-	-	-	-	-	567	4,346	-	-	4,346	-	-	-	-	-	9,388	
5b.2.4	Cooling Tower Foundation	-	1,878	-	-	-	-	-	1,878	3,756	-	-	3,756	-	-	-	-	-	12,002	
5b.2	Subtotal Period 5b Additional Costs	-	13,070	-	-	-	-	9	1,962	15,040	-	-	15,040	-	-	-	-	-	51,840	
5b.3	Period 5b Collateral Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
5b.3.1	Small tool allowance	-	410	-	-	-	-	-	62	472	-	-	472	-	-	-	-	-	-	
5b.3	Subtotal Period 5b Collateral Costs	-	410	-	-	-	-	-	62	472	-	-	472	-	-	-	-	-	-	
5b.4	Period 5b Period-Dependent Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
5b.4.1	Insurance	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
5b.4.2	Property taxes	-	-	-	-	-	-	421	42	463	-	-	463	-	-	-	-	-	-	
5b.4.3	Heavy equipment rental	-	4,068	-	-	-	-	109	609	4,677	-	-	4,677	-	-	-	-	-	-	
5b.4.4	Plant energy budget	-	-	-	-	-	-	16	16	125	-	-	125	-	-	-	-	-	-	
5b.4.5	Corporate Allocations	-	-	-	-	-	-	4,000	400	4,500	-	-	4,500	-	-	-	-	-	-	
5b.4.6	Site Office Cost	-	-	-	-	-	-	300	300	2,500	-	-	2,500	-	-	-	-	-	37,646	
5b.4.7	DOC Staff Cost	-	-	-	-	-	-	10,066	1,501	11,567	-	-	11,567	-	-	-	-	-	106,663	
5b.4.8	Utility Staff Cost	-	-	-	-	-	-	4,643	697	5,340	-	-	5,340	-	-	-	-	-	61,174	
5b.4	Subtotal Period 5b Period-Dependent Costs	-	4,068	-	-	-	-	21,681	3,615	29,354	4,650	-	24,404	-	-	-	-	-	205,483	
5b.0	TOTAL PERIOD 5b COST	-	58,032	-	-	-	-	21,871	11,740	91,643	5,159	-	86,484	-	-	-	-	-	452,540	
PERIOD 5 TOTALS		-	58,032	-	-	-	-	21,871	11,740	91,643	5,159	-	86,484	-	-	-	-	-	452,540	
TOTAL COST TO DECOMMISSION		11,676	138,622	15,982	9,168	23,895	37,468	649,178	145,416	1,026,384	849,173	73,749	109,462	301,556	123,852	376	2,142	22,196,610	1,892,143	7,012,263

TOTAL COST TO DECOMMISSION WITH 16.5% CONTINGENCY:	\$1,026,384	thousands of 2011 dollars
TOTAL NRC LICENSE TERMINATION COST IS 82.73% OR:	\$849,173	thousands of 2011 dollars
SPENT FUEL MANAGEMENT COST IS 7.19% OR:	\$73,749	thousands of 2011 dollars
NON-NUCLEAR DEMOLITION COST IS 10.08% OR:	\$105,462	thousands of 2011 dollars
TOTAL LOW-LEVEL RADIOACTIVE WASTE BURIED (EXCLUDING GTCCO):	124,497	cubic feet
TOTAL GREATER THAN CLASS C WASTE VOLUME GENERATED	2,142	cubic feet
TOTAL SCRAP METAL REMOVED:	71,007	tons
TOTAL CRAFT LABOR REQUIREMENTS:	1,592,143	man-hours

End Notes:  
nil - indicates that this activity not charged as decommissioning expense.  
- indicates that this activity is not a cost item.  
0 - indicates that this value is less than 0.5 but is non-zero.  
a cell containing "-" indicates a zero value