

**TRM UPDATE INSTRUCTIONS**

Manual Holder REGIONAL LIBRARY

TRM Copy # 14 NRC REGION III

TRM Rev. # N/A

Responsible Licensing Engineer/Specialist Tony Browning

This update is to correct a typographical error in the current TRM (Ref. AR01859645).  
This update becomes effective on the following date: 3/29/13

Please update your TRM manual as indicated below:

Pg 4.0-36 REMOVE

Pg 4.0-36 INSERT

---

**NOTICE OF RECEIPT OF TECHNICAL REQUIREMENTS MANUAL UPDATE**

This acknowledges receipt of this TRM update. Please sign and return this form, along with the sheets removed from the TRM, to the responsible Licensing Engineer/Specialist within 10 days of the effective date of this TRM update.

TRM Copy # 14 NRC REGION III

TRM Revision # N/A

Signature \_\_\_\_\_ DATE \_\_\_\_\_

*ADD  
URL*

DAEC  
 Technical Requirements Manual  
 Chapter 4.0 (Technical Specification Surveillance Frequency Control Program)  
 Table 4.0-8 (Electrical Systems)

TS SR #	Subject	TS SSC/Function	STP #	Frequency	SR Frequency Note?	AR#
3.8.1.1	Verify Breaker Alignment & Power Availability	Offsite AC Sources	3.8.1-01	7 Days	No	
3.8.1.2	Verify Start (Slow) - Output Voltage & Frequency	EDGs	3.8.1-04 3.8.1-05 3.8.1-06	31 Days	No	
3.8.1.3	60 Minute Load Test	EDGs	3.8.1-04 3.8.1-05 3.8.1-06	31 Days	Yes	
3.8.1.4	Verify Day Tank Volume	EDGs	3.8.1-04 3.8.1-05 3.8.1-06	31 Days	No	
3.8.1.5	Day Tank Presence of Water Check	EDGs	3.8.1-08 3.8.1-09	31 Days	No	
3.8.1.6	Fuel Oil Transfer Operational Test	EDGs	3.8.1-04 3.8.1-05 3.8.1-06	31 Days	No	
3.8.1.7	Timed (Fast) Start – Voltage & Frequency Check	EDGs	3.8.1-06	184 Days	No	
3.8.1.8	Verify Slow Transfer Between Start-up & Stand-by Transformers	Offsite AC Sources	3.8.1-07	24 Months	Yes	
3.8.1.9	Load Reject Test	EDGs	3.8.1-07	24 Months	Yes	
3.8.1.10	Verify Automatic Trip Bypass	EDGs	3.8.1-07	24 Months	Yes	
3.8.1.11	Verify Manual Control for Transferring Loads to Offsite Power	EDGs	3.8.1-07	24 Months	Yes	
3.8.1.12	Verify Load Sequence Separation	EDGs	3.8.1-07	24 Months	Yes	