

TABLE 4.3-1 (Continued)

TABLE NOTATION

- * - With reactor trip breakers in the closed position and the CEA drive system capable of CEA withdrawal.
- (1) - Each startup or when required with the reactor trip breakers closed and the CEA drive system capable of rod withdrawal, if not performed in the previous 7 days.
- (2) - Heat balance only (CHANNEL FUNCTIONAL TEST not included), above 15% of RATED THERMAL POWER; adjust the Linear Power Level signals and the CPC addressable constant multipliers to make the CPC delta T power and CPC nuclear power calculations agree with the calorimetric calculation if absolute difference is greater than 2%. During PHYSICS TESTS, these daily calibrations may be suspended provided these calibrations are performed upon reaching each major test power plateau and prior to proceeding to the next major test power plateau.
- (3) - Above 15% of RATED THERMAL POWER, verify that the linear power subchannel gains of the excore detectors are consistent with the values used to establish the shape annealing matrix elements in the Core Protection Calculators.
- (4) - Neutron detectors may be excluded from CHANNEL CALIBRATION.
- (5) - After each fuel loading and prior to exceeding 70% of RATED THERMAL POWER, the incore detectors shall be used to determine the shape annealing matrix elements and the Core Protection Calculators shall use these elements.
- (6) - This CHANNEL FUNCTIONAL TEST shall include the injection of simulated process signals into the channel as close to the sensors as practicable to verify OPERABILITY including alarm and/or trip functions.
- (7) - Above 70% of RATED THERMAL POWER, verify that the total RCS flow rate as indicated by each CPC is less than or equal to the actual RCS total flow rate determined by either using the reactor coolant pump differential pressure instrumentation (conservatively compensated for measurement uncertainties) or by calorimetric calculations (conservatively compensated for measurement uncertainties) and if necessary, adjust the CPC addressable constant flow coefficients such that each CPC indicated flow is less than or equal to the actual flow rate. The flow measurement uncertainty may be included in the BERR1 term in the CPC and is equal to or greater than 4%.
- (8) - Above 70% of RATED THERMAL POWER, verify that the total RCS flow rate as indicated by each CPC is less than or equal to the actual RCS total flow rate determined by calorimetric calculations (conservatively compensated for measurement uncertainties).
- (9) - Above 55% of RATED THERMAL POWER.
- (10) - Deleted.
- (11) - The monthly CHANNEL FUNCTIONAL TEST shall include verification that the correct values of addressable constants are installed in each OPERABLE CPC per Specification 2.2.2.
- (12) - At least once per 18 months and following maintenance or adjustment of the reactor trip breakers, the CHANNEL FUNCTIONAL TEST shall include independent verification of the undervoltage and shunt trips.

8911070187 891102
PDR ADDOCK 05000361
PDC

ATTACHMENT B

Change Note (2) of Table 4.3-1 as follows:

- (2) - Heat Balance only (CHANNEL FUNCTIONAL TEST not included), above 15% of RATED THERMAL POWER; adjust ~~compare the indicated Linear Power Level, signals and the CPC addressable constant multipliers to make the CPC delta T power, and the CPC nuclear power calculations agree with the calorimetric calculation and if absolute difference is greater than 2% any are less than the calorimetric calculation by more than 1.0% of RATED THERMAL POWER, adjust the indication to be within -1.0% or greater than the calorimetric calculation.~~ During PHYSICS TESTS, these daily calibrations may be suspended provided these calibrations are performed upon reaching each major test power plateau and prior to proceeding to the next major test power plateau.

ATTACHMENT C

TABLE 4.3-1 (Continued)

TABLE NOTATION

- * - With reactor trip breakers in the closed position and the CEA drive system capable of CEA withdrawal.
- (1) - Each startup or when required with the reactor trip breakers closed and the CEA drive system capable of rod withdrawal, if not performed in the previous 7 days.
- (2) - Heat balance only (CHANNEL FUNCTIONAL TEST not included), above 15% of RATED THERMAL POWER; adjust the Linear Power Level signals and the CPC addressable constant multipliers to make the CPC delta T power and CPC nuclear power calculations agree with the calorimetric calculation if absolute difference is greater than 2%. During PHYSICS TESTS, these daily calibrations may be suspended provided these calibrations are performed upon reaching each major test power plateau and prior to proceeding to the next major test power plateau.
- (3) - Above 15% of RATED THERMAL POWER, verify that the linear power subchannel gains of the excore detectors are consistent with the values used to establish the shape annealing matrix elements in the Core Protection Calculators.
- (4) - Neutron detectors may be excluded from CHANNEL CALIBRATION.
- (5) - After each fuel loading and prior to exceeding 70% of RATED THERMAL POWER, the incore detectors shall be used to determine the shape annealing matrix elements and the Core Protection Calculators shall use these elements.
- (6) - This CHANNEL FUNCTIONAL TEST shall include the injection of simulated process signals into the channel as close to the sensors as practicable to verify OPERABILITY including alarm and/or trip functions.
- (7) - Above 70% of RATED THERMAL POWER, verify that the total RCS flow rate as indicated by each CPC is less than or equal to the actual RCS total flow rate determined by either using the reactor coolant pump differential pressure instrumentation (conservatively compensated for measurement uncertainties) or by calorimetric calculations (conservatively compensated for measurement uncertainties) and if necessary, adjust the CPC addressable constant flow coefficients such that each CPC indicated flow is less than or equal to the actual flow rate. The flow measurement uncertainty may be included in the BERRI term in the CPC and is equal to or greater than 4%.
- (8) - Above 70% of RATED THERMAL POWER, verify that the total RCS flow rate as indicated by each CPC is less than or equal to the actual RCS total flow rate determined by calorimetric calculations (conservatively compensated for measurement uncertainties).
- (9) - Above 55% of RATED THERMAL POWER.
- (10) - Deleted.
- (11) - The monthly CHANNEL FUNCTIONAL TEST shall include verification that the correct values of addressable constants are installed in each OPERABLE CPC per Specification 2.2.2.
- (12) - At least once per 18 months and following maintenance or adjustment of the reactor trip breakers, the CHANNEL FUNCTIONAL TEST shall include independent verification of the undervoltage and shunt trips.

ATTACHMENT D

Change Note (2) of Table 4.3-1 as follows:

- (2) - Heat Balance only (CHANNEL FUNCTIONAL TEST not included), above 15% of RATED THERMAL POWER; adjust ~~compare the indicated Linear Power Level, signals and the CPC addressable constant multipliers to make the CPC delta T power, and the CPC nuclear power calculations agree with the calorimetric calculation and if absolute difference is greater than 2% any are less than the calorimetric calculation by more than 1.0% of RATED THERMAL POWER, adjust the indication to be within -1.0% or greater than the calorimetric calculation.~~ During PHYSICS TESTS, these daily calibrations may be suspended provided these calibrations are performed upon reaching each major test power plateau and prior to proceeding to the next major test power plateau.