Enclosure 2

NUCLEAR GENERATION SITE UNITS 2 AND 3 COMPLETE REVISION EFFECTIVE DATE <u>AUG 2 D 19</u>84 EMERGENCY OPERATING PROCEDURE SO23-3-5.27 REVISION 6 PAGE 1 OF 12

EARTHQUAKE

TABLE OF CONTENTS

SECTI	ON		PAGE
1.0	SYMPTOMS		2
2.0	AUTOMATIC ACTIONS	SITE FILE COPY	2
3.0	IMMEDIATE OPERATOR ACTIONS	JIL HLL VOIT	2
4.0	SUBSEQUENT OPERATOR ACTIONS	RECEIVED	2
5.0	ATTACHMENT	AUG 201984	7
6.0	REFERENCE(S)	CDM SITE	7
7.0	RECORDS		7

QA PROGRAM AFFECTING

0097g

8501250213 850123 PDR ADDCK 05000361 F PDR

EMERGENCY OPERATING PROCEDURE SO23-3-5.27 REVISION 6 PAGE 2 OF 12

#### EARTHQUAKE

- 1.0 SYMPTOMS
  - 1.1 Alarms
    - 1.1.1 Seismic Recording System Activation
    - 1.1.2 Operating Basis Earthquake Acceleration
  - 1.2 Indications

1.2.1 Ground motion that is readily felt and may cause observable effects to plant processes, structures and operating equipment.

#### 2.0 AUTOMATIC ACTIONS

2.1 Initiations of seismic recording and indicating instrumentation and seismic annunciators

2.2 Possible seismic reactor trip (0.48g ground motion)

- 2.3 Possible turbine trip due to high vibration
- 2.4 Possible storage tank Hi/Lo level alarm, feedwater heater Hi/Lo level alarms, or sump high level alarms

### 3.0 IMMEDIATE OPERATOR ACTIONS

- 3.1 If reactor trip has occurred, carry out all immediate operator actions per S023-3-5.1, "Emergency Plant Shutdown".
- 3.2 Use the public address system to notify onsite personnel concerning the nature of the emergency.

CAUTION ====== Do not place system in "MANUAL" unless misoperation in "AUTOMATIC" is apparent. Systems placed in "MANUAL" must be checked frequently to ensure proper operation.

### 4.0 SUBSEQUENT OPERATOR ACTIONS

4.1 Verify all immediate operator actions have been initiated as follows:

EMERGENCY OPERATING PROCEDURE SO23-3-5.27 REVISION 6 PAGE 3 OF 12

#### 4.0 SUBSEQUENT OPERATOR ACTIONS (Continued) \*INITIALS 4.1.1 With a reactor trip verify all immediate and subsequent operator actions per SO23-3-5.1, "Emergency Plant Shutdown", are being performed concurrently with the steps in this instruction. 4.1.2 Notify onsite personnel, on the public address system, concerning the nature of this emergency. 4.1.3 With valid initiation of the "Seismic Recording System Activation" alarm 61C21, as indicated by an illuminated amber alarm on the Seismic Instrumentation Panel, or if notified by Unit 1 that Seismic Instrumentation has been activated, complete Section 4.3. With a valid "Operating Basis Earthquake 4.1.4 Acceleration" (OBE) alarm, 61C22, or red alarm light on the Seismic Instrumentation Panel indicating a 0.33g ground motion, complete Section 4.4. 4.2 The Shift Superintendent shall notify the Plant Superintendent or designee and Shift Technical Advisor and discuss the situation. 4.2.1 Within 15 minutes an assessment of the plant status and safety shall be made and the event classified per SO23-VIII-1, "Recognition and Classification of Emergency." 4.2.2 If an emergency is declared (Unusual, Alert, Site Emergency or General Emergency), then use the Emergency Procedures to implement the SONGS 1, 2 and 3 Emergency Plan. 4.2.3 Notify the NRC via the Red Phone within one hour, per S023-0-25, "Telephone Notification of NRC for Significant Events."

4.2.3.1 If possible, discuss the contents of the notification with the Plant Superintendent or designee prior to the notification.

\* The initial column is an operator aid and is intended to be used as follows:

Initial each completed action. Do not write NA; leave blank items that are not applicable. Proceed through the instruction, performing all applicable steps, frequently rechecking those steps passed over to ensure action is taken when applicable.

#### EMERGENCY OPERATING PROCEDURE S023-3-5:27 REVISION 6 PAGE 4 OF 12

Resident/Time

CC&C/TIme

#### 4.0 SUBSEQUENT OPERATOR ACTION (Continued)

INITIALS

4.2.3.2 Record the names of the persons involved with the notification and time.

NRC \_\_\_\_\_\_\_ Bethesda Time Region V/Time

4.2.3.3 Notify the Systems Operating Supervisor concerning the nature of the emergency.

Plant Supt/Time

- 4.2.3.4 Notify Emergency Preparedness concerning the nature of the emergency.
- 4.2.3.5 Notify Station Engineering that an analysis of the seismic recording and indicating instrumentation is to be performed to determine exact magnitude of the earthquake.
- 4.2.3.6 The Emergency Coordinator (Shift Superintendent, until properly relieved by a designated alternate) should ensure the emergency classification is evaluated for revision as more definite information is obtained concerning the magnitude of the earthquake.
- 4.3 Following a seismic event greater than or equal to .05g perform the following:
  - 4.3.1 Within 2 hours, per T.S. 4.3.3.7.4.a, each zone shown in Tech. Spec. Table 3.3-11 (Attachment 1) shall be inspected for fires. Log completion of inspection and results in Control Operator's and Shift Superintendent's log book.
    - NOTE: <u>If</u> the Seismic Event renders any portion of the fire detection inoperable, <u>then</u> a fire watch must be established within (1) one hour.
  - 4.3.2 Within 72 hours, an engineering evaluation shall be performed to verify the <u>OPERABILITY</u> of the fire detection system in each zone in Tech. Spec. Table 3.3-11. (Attachment 1)
  - 4.3.3 Perform SO23-3-3.37, "RCS Water Inventory Balance."

. .

EMERGENCY OPERATING PROCEDURE SO23-3-5.27 REVISION 6 PAGE 5 OF 12

4.0	SUBSEQUENT OPER	RATOR ACTION (	Continued)	INITIALS
	4.3.4	Verify there i normal into th	s no increase in flow above ne containment sump.	
	4.3.5	Exercise the c SO23-3-3.5, "C	ontrol rods as outlined in EA Operability".	
	4.3.6	pumps per SO23	ine test of auxiliary feedwater 3-3-3.16, "Auxiliary Feedwater peration Test".	
	4.3.7	Perform a rout Generators per Monthly Test.'	tine monthly test of both Diesel r SO23-3-3.23, "Diesel Generator "	
	4.3.8	and power ava	trical supply breaker alignment ilability Check-Off Sheet per , "Weekly Electrical Bus	
	4.3.9	A physical in plant paying following sys	spection shall be made of the particular attention to the tems:	
	4.3.	9.1 Safety I	njection System, including the RWST.	<u></u>
	4.3.	of the C	System, including the part VCS that is located within tor auxiliary building.	
	4.3.	.9.3 Inspect the foll	Fuel Handling Building for owing:	
		4.3.9.3.1	Proper water level in the spent fuel pool.	
		4.3.9.3.2	Leakage of the spent fuel pool liner.	
		4.3.9.3.3	Leakage at the sumps of the spent fuel transfer tube.	
	4.3		nt Cooling Water for leakage.	
	4.3	.9.5 Boric a associa	cid storage tank and ted piping for leaks.	
	4.3	9.6 Contain piping	ment electrical and penetrations.	
	4.3	includi	ment Spray System ng the NaOH chemical e tank.	

PAGE 6 OF 12 **REVISION 6** 

EMERGENCY OPERATING PROCEDURE \$023-3-5.27

#### 4.0 SUBSEQUENT OPERATOR ACTION (Continued) INITIALS 4.3.9.8 Atmospheric Steam Dump System air supply and back-up nitrogen supply to both atmospheric dump valves. 4.3.9.9 Station Fire Main and Fire Fighting systems 4.3.9.9.1 If fire system is ruptured, relocate Seismic Tankers to Seismic Stand pipes and connect to Fire Main per SO23-XIII-60 "Post Earthquake Fire Water System Operation." 4.3.10 Have Instrumentation and Control reset the seismic recording and indicating instrumentation. Refer to Technical Specification 3-4.3.3, "Monitoring Instrumentation", Specification 3.3.3.3, "Seismic Instrumentation". With each seismic event, complete S023-0-20, 4.3.11

- "Cumulative Equipment Inoperability and Design Cycles".
- 4.4 For "Operating Basis Earthquake", (greater than 0.33g ground motion) perform the following:
  - 4.4.1 If in Modes 1 or 2, commence a unit shutdown to cold shutdown conditions per SO23-5-1.4, "Plant Shutdown from Minimum Load to Hot Standby" performing applicable steps concurrently with the steps in this instruction.
  - 4.4.2 If in Modes 3 or 4, commence cooldown to Cold shutdown conditions per SO23-5-1.5, "Plant Shutdown - Hot Standby to Cold Shutdown" performing applicable steps concurrently with the steps in this instruction.
  - 4.4.3 Perform the inspections in steps 4.3.1 through 4.3.11.
  - 4.4.4 The unit shall not be returned to service following an "OBE" until an evaluation has been made by the On-Site Review Committee.
  - 4.4.5 Any observed damage to the plant shall be documented in the Control Operator's and Shift Superintendent's Log Books so that it can be related to the intensity of the earthquake.

EMERGENCY OPERATING PROCEDURE S023-3-5.27 REVISION 6 PAGE 7 OF 12

#### SUBSEQUENT OPERATOR ACTION (Continued) 4.0 INITIALS 4.4.6 Have Engineering conduct a piping penetration leakrate test on all penetrations except those that are required to place the plant in cold shutdown. 4.4.7 Have Instrumentation and Control perform Station Procedure S023-II-1.1, "Reactor Protection System Testing - 31 day Interval", ESFAS Section. 4.4.8 Have Instrumentation and Control perform S023-II-5, "Nuclear Instrumentation Calibration Wide Range Log Linear Power Safety Channels". 4.4.9 Make a thorough inspection of the RCS, including the control rod housings, the steam generators, the RCP's, the pressurizer, and all associated piping. 4.4.10 Perform S023-3-3.8, "Safety Injection Monthly Tests". 4.4.11 Perform SO23-3-3.11, "Containment Spray Monthly and Refueling Tests". 4.4.12 Obtain a RCS sample and analyze for total activity. 4.4.13 Obtain an incore thermocouple map and have Engineering evaluate. 4.4.14 Obtain an incore flux map and have Engineering evaluate. 4.4.15 Have Instrumentation and Control reset the seismic recording and indicating instrumentation. Refer to Technical Specification 3.3.3.3, "Seismic Instrumentation". 4.4.16 Record date and time this procedure was terminated and unit affected. Date Time Unit 5.0 ATTACHMENT 5.1 Attachment 1, "Fire Zone Check Sheet" (Tech. Spec. Table 3.3-11) 6.0 REFERENCE(S) 6.1 None 7.0 RECORDS REQUIRED 7.1 File per SO23-0-11, "Trip/Transient Review."

M.BARR:0097g

EMERGENCY OPERATING PROCEDURE SO23-3-5.27 REVISION 6 PAGE 8 OF 12 ATTACHMENT 1

FIRE ZONE CHECK SHEET (Tech Spec Table 3.3-11)

TIME OF SEISMIC EVENT: TIME CHECK SHEET COMPLETED: COMPLETION VERIFIED BY:

(S.R.O.)

ZONE	INSTRUMENT LOCATION	CHECKED BY:
1	<u>Containment</u> Cable Tray Areas Elev. 63'3" Cable Tray Areas Elev. 45' Cable Tray Areas Elev. 30'	
	Combustible Oil Area Two steam generator rooms	
	Charcoal Filter Area, Elev 45'	
2	Penetration Elev. 63'6"	
4	New Fuel Storage Area and Spent Fuel Pool Areas Spent Fuel Pool New Fuel Pool	
5	<u>Control Building Elev 70'</u> Cable Riser Gallery Rm 423 Cable Riser Gallery Rm 449	
6	Control Building Elev 70' Radiation Chemical Lab Rm 421 Radiation Chemical Lab Rm 420	
7	<u>Radwaste Elev 63'6"</u> Chemical Storage Area Rm 503 Radwaste Control Panel Rm 513 Storage Area Rm 523 Hot Machine Shop	

. 🎝

### EMERGENCY OPERATING PROCEDURE SO23-3-5.27 REVISION 6 PAGE 9 OF 12 ATTACHMENT 1

ZONE	FIRE ZONE CHECK SHEET (Tech Spec Table 3.3-11) INSTRUMENT LOCATION	CHECKED BY:
ZUNE	INSTRUMENT EUCATION	UNECKED DT.
8	<u>Radwaste Elev 63'6"</u> Waste Decay Tank Rms 511A	
9	<u>Fuel Handling Building Elev 45'</u> Emgy. A.C. Unit Rm 309-Train A Emgy. A.C. Unit Rm 301-Train B	
10	Penetration Elev. 45'	
11	S.E.B. Roof and Main Steam Relief Valves	
12	<u>Control Building Elev 50'</u> Cable Riser Gallery Rm 305 Cable Riser Gallery Rm 315	
13A	Control Building Elev 30 <sup>ª</sup> Emgy. HVAC Unit Rm 309A	
13B	Control Building Elev 50' Emgy. HVAC Unit Rm 309B	
14	<u>Radwaste Elev 24'</u> Boric Acid Makeup Tank Rm 204B Boric Acid Makeup Tank Rm 204A	
15	<u>Control Building Elev 50'</u> ESF Switchgear Rm 308A ESF Switchgear Rm 308B	
16	Radwaste Elev 37' & 50' Ion Exchangers	
17	<u>Diesel Generator Building</u> Train A Train B	
18	Diesel Fuel Oil Storage Tank Underground Vaults	·
20	Condensate Storage Tank T-121	<u> </u>
21	Nuclear Storage Tank T-104	- <u></u>
22	Auxiliary Feedwater Pump Room	
23	Fuel Handling Bldg Elev 30' Spent Fuel Pools Heat Exchange Room 209	· · · · · · · · · · · · · · · · · · ·
28	Penetration Elev. 30'	

• .

ATTACHMENT 1

PAGE 2 OF 5

# EMERGENCY OPERATING PROCEDURE S023-3-5.27 REVISION 6 PAGE 10 OF 12 ATTACHMENT 1

ZONE	FIRE ZONE CHECK SHEET (Tech Spec Table 3.3-11) INSTRUMENT LOCATION	CHECKED BY:
29	<u>Control Building Elev. 30'</u> Cable Riser Gallery Rm 236 Cable Riser Gallery Rm 224	
30	Electrical Tunnel Elev. 30'6"	
31	Control Building Elev. 30'	
32A	<u>Control Building Elev. 30'</u> Fan Room 219 & Corridor 221	
32B	Control Building Elev. 30' Fan Room Rm 233 and Corridor Rm 234	
34	<u>Radwaste Elev. 9' and 24'</u> Secondary Radwaste Tank Rms 126A,B, and 127 A & B	· 
35	Radwaste Elev. 9' and 24' Spent Resin Tank Rms 125A, B	,
36	Fuel Handling Building Elev. 17'6" Spent Fuel Pool Pump Rm 107	
37	<u>Radwaste Elev. 24'</u> Letdown Heat Exchanger Rms 209A,B	
38	<u>Radwaste Elev. 24'</u> Letdown Control Valve Rms 218A,B	-
39 🌋	Radwaste Elev. 24' Filter Crvd Tank Rm 216	
40	Radwaste Elev. 9' and 24' Primary Radwaste Tank Rms 211A,D	
41	Control Building Elev. 9' Cable Spreading Rm 111A Cable Spreading Rm 111B	
42	Control Building Elev. 9' Cable Riser Gallery Rm 110 Cable Riser Gallery Rm 112	
43	Control Building Elev. 9' Emgy. Chiller Rm 115 Emgy. Chiller Rm 117	

÷

EMERGENCY OPERATING PROCEDURE S023-3-5.27 REVISION 6 PAGE 11 OF 12 ATTACHMENT 1

ZONE	FIRE ZONE CHECK SHEET (Tech Spec Table 3.3-11) INSTRUMENT LOCATION	CHECKED BY:
44	Intake Structure Pump Rm. T2-106 Pump Rm. T3-106	
45	Penetration Area Elev. 9' & 15' Piping Penetration Area 15'	
48	Safety Equipment Building Elev. 9' CCW HX and Piping Rm 022-025	
50	<u>Radwaste Elev. 9'</u> Charging Pump Rms 106A-F	
51	<u>Radwaste Elev. 9'</u> Boric Acid Makeup Tank Rms 105A-D	
53	<u>Electrical Tunnel Elev. 9'6", 11'6". (-) 2'6</u> "	
54	Safety Equipment Bldg Elev. 15'6" and 8' Shutdown HX Rms 003, 004, 016, 018	
55	<u>Safety Equipment Bldg Elev. 8'</u> Chemical Storage Tank Rm 019	
56	<u>Safety Equipment Bldg Elev. 8'</u> Component Cooling Water Surge Tank Rms 020, 021	
57	<u>Safety Equipment Bldg Elev. 15'6"</u> Pump Rm 005	
58	<u>Radwaste Elev. 37'</u> Reactor Trip System Rms 308A-D, 309-A-C	
59	<u>Safety Equipment Bldg Elev. 15'6"</u> Pump Rm 001	·
60	<u>Safety Equipment Bldg Elev. 15'6"</u> Pump Rm 015	
61	<u>Safety Equipment Bldg Elev. 15'6"</u> Component Cooling Water Pump Rms 006, 007, 008	
62	Radwaste Elev. 50' Volume Control Valve Rooms	
63	<u>Control Building Elev. 50'</u> Corridor	
64	<u>Control Building Elev. 50'</u> Vital Power Distribution Rms 310A-H	
	ATTACHMENT 1	PAGE 4 OF 5

t

EMERGENCY OPERATING PROCEDURE SO23-3-5.27 REVISION 6 PAGE 12 OF 12 ATTACHMENT 1

(Tech Spec Table 3.3-11) INSTRUMENT LOCATION	CHECKED BY:
Control Building Elev. 50 <sup>4</sup> Battery Rms 306B-J	
Control Building Elev. 50' Evacuation Rm 311	
<u>Radwaste Elev. 63'6"</u> Cable Riser Gallery Rm 506A Cable Riser Gallery Rm 506B	
Penetration 9' - 63'6" Cable Riser Shaft	
<u>Safety Equipment Bldg Elev. 5'3"</u> Salt Water Cooling Piping Rm 010	
<u>Radwaste Elev. 24'</u> Duct Shaft Rms 222A,B	
<u>Control Building Elev. 70'</u> Corridor 442	
Refueling Water Storage Tank T-005	
Refueling Water Storage Tank T-006	
<u>Control Building Elev. 9'</u> Corridor Rm 105	
<u>Control Building Elev. 50'</u> ESF Switchgear Rm 302A ESF Switchgear Rm 302B	
<u>Radwaste Elev. 37' and 50'</u> Duct Shaft Rms	
Radwaste Elev. 63'6" Duct Shaft Rms 527A,B	
Salt Water Cooling Tunnel	
<u>Safety Equipment Bldg Elev. 8'</u> HVAC Rm 017	
	Control Building Elev. 50' Battery Rms 306B-J Control Building Elev. 50' Evacuation Rm 311 Radwaste Elev. 63'6" Cable Riser Gallery Rm 506A Cable Riser Gallery Rm 506B Penetration 9' - 63'6" Cable Riser Shaft Safety Equipment Bldg Elev. 5'3" Salt Water Cooling Piping Rm 010 Radwaste Elev. 24' Duct Shaft Rms 222A,B Control Building Elev. 70' Corridor 442 Refueling Water Storage Tank T-005 Refueling Water Storage Tank T-006 Control Building Elev. 9' Corridor Rm 105 Control Building Elev. 50' ESF Switchgear Rm 302A ESF Switchgear Rm 302B Radwaste Elev. 37' and 50' Duct Shaft Rms Radwaste Elev. 63'6" Duct Shaft Rms Salt Water Cooling Tunnel Safety Equipment Bldg Elev. 8'

Date

Time

-----

ATTACHMENT 1

Unit