

PARTIAL PLAN
(NOT TO SCALE)



ISOMETRIC VIEW
(TYPICAL FOR PT-425X1 & PT-425X2)





FRONT EVEVATION
(TYPICAL FOR PRESS. INSTR. CAB. # 1 & 3)

NOTES:

1. DIMENSIONAL TOLERANCES SHALL BE ± 1/4" UNLESS OTHERWISE NOTED.
2. ALLOW A MINIMUM OF 6" TOP CLEARANCE FOR INSTRUMENT COVER REMOVAL.
3. ALL WELDING SHALL BE WITH E70XX ELECTRODES & SHALL BE PER APPLICABLE SECTION OF SCE SPEC # 82-6220.
4. BILL OF MATERIAL ITEM NO'S. USED IN THIS DWG. ARE IN JOB SECTION C103 OF M-31771.

PARTS LIST

PART NO.	DESCRIPTION	QTY.	MATERIAL	REMARKS
1	PRESSURE TRANSMITTER	2	FOXBORO MODEL EIIGM-I5A(E)2	SEE B/M # M-31639
2	INSTRUMENT VALVE	2	GLOBE TYPE, STN. STL., 3/8-INCH	SEE B/M # M-31771
3	TUBING CONNECTOR	4	3/8" TUBE × 1/2" MALE NPT, STN. STL.	
4	3/8" TUBING	30FT.	STAINLESS STEEL, 0.065 MIN. WALL THICKNESS	
5	STEEL CHANNEL	2	MC3X7.1X 14 IN. LONG, A36 CARBON STL.	
6	3/8" TUBING CAP	2	STAINLESS STEEL TYPE 316	
7	3/8" UNION TEE	2	STAINLESS STEEL TYPE 316	
8	STEEL PLATE	2	4" × 6" × 1/4" THK., A36 CARBON STL.	
9	3/8" TUBING TEE	2	STAINLESS STEEL, SOCKET WELD	
10	STEEL PLATE	2	4" × 21" × 1/4" THK, A36 CARBON STL.	

TI APERTURE CARD

SONGS 1
SAFETY RELATED
R.O.F. MITIGATING SYSTEM

8601030147

Rev. No.	Revisions	Date	Approved	O.K.	O.K.	Ck'd.	Made	J.O. No.
1	INCORP CCN#1. EFF. DATE: IMMEDIATELY	4-6-79					AL	GJ 7539
0	ISSUED FOR CONSTRUCTION	3-31-78					AL	GJ 7419

Reference Drawings: 5154617 SYS. LOGIC/SIGNAL FLOW DIAG.; M- Drawing List Sheet

Location SAN ONOFRE NUCLEAR GEN. STA.

REACTOR OVERPRESSURIZATION SYSTEM PT-425X1 & PT-425X2 INSTALLATION DETAIL

Southern California Edison Company

5131370-1

Southern California Edison Company
26X