

BECHTEL PROJECT NO.: 25161				MACTEC PROJECT NO.: 6468-09-2473				COUNTY: Louisa, VA				GEOLOGIST: R. Clark						
SITE DESCRIPTION: North Anna 3 Project Supplement 2								DRILLER: F. Cox/R. Hall				FLUID LEVEL (ft)						
BORING NO.: M-21				DRILL METHOD: Mud Rotary/Rock Core				DRILL MACHINE: CME-55 Track (RAL)				0 HR.		10.5				
GROUND ELEV.: 303.9 ft (NAVD88)				NORTHING: 3,909,811 US ft (NAD83)				EASTING: 11,686,270 US ft (NAD83)				24 HR.		29.5				
TOTAL DEPTH: 151.8 ft		SAMPLE METHODS: ASTM D 1586-08a; 2488-09a; 2113-08; 6032-08						ROD TYPE: AWJ		HAMMER (ID): 140-lb. Auto (MEC-21)								
DATE STARTED: 9/22/09		COMPLETED: 9/24/09		HOLE DIA.: 4"		CASING DEPTH: 63.8 ft		CORE SIZE: HQ3		BITS USED: 3-7/8" Tri-Cone								
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT						SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION					
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100								
303.9					Ground Surface								303.9	0.0				
															No sampling from 0.0 to 11.1 feet due to soft dig utility clearance by Dominion Personnel			
292.8	11.1	5	9	6							SS-1		292.8	11.1				
290.3	13.6	10	15	18							SS-2							
287.7	16.2	7	11	16							SS-3				RESIDUAL SOIL: Silty SAND (SM), light gray (10YR 7/2), medium dense, moist, fine to coarse grained sand, angular quartz fragments, relict rock fabric			
285.5	18.4	18	24	23							SS-4				13.6 ft: Pale yellow (2.5Y 7/4), dense 16.2 ft: Medium dense 18.4 ft: Dense			
280.5	23.4	16	25	37							SS-5				23.4 ft: Very dense			
275.6	28.3	37	63/0.3								SS-6		275.6	27.5	WEATHERED ROCK: Severely weathered BIOTITE QUARTZ GNEISS (Sampled as Silty SAND (SM), brownish yellow (10YR 6/6), very dense, moist, fine to coarse grained sand, angular quartz rock fragments)			
270.4	33.5	9	10	8							SS-7		272.9	31.0	RESIDUAL SOIL: Silty SAND (SM), light yellowish brown (10YR 6/4), medium dense, moist, fine grained sand, some mica, relict rock fabric			
265.4	38.5	7	9	15							SS-8				38.5 ft: Wet			
260.4	43.5	8	32	27							SS-9				43.5 ft: Very dense, fine to medium grained sand			
255.4	48.5	50/0.2									SS-10		257.9	46.0	WEATHERED ROCK: Severely weathered BIOTITE QUARTZ GNEISS (Sampled as Silty SAND (SM), light yellowish brown (2.5Y 6/4), very dense, wet, fine to coarse grained sand, angular quartz rock fragments)			
250.4	53.5	50/0.3									SS-11							
245.4	58.5	30	50/0.3								SS-12							
240.4	63.5	50/0.3									SS-13		240.1	63.8	HARD ROCK: Gray to dark gray, with orange staining, moderately severely to moderately weathered, close fracturing, soft to medium hard, BIOTITE QUARTZ GNEISS			
													234.6	69.3	WEATHERED ROCK: Brown, reddish brown, and dark gray, severely weathered, close fracturing, very soft to soft, BIOTITE QUARTZ GNEISS and BIOTITE GNEISS			

NORTH ANNA 3 BORE NORTH ANNA 3 PROJECT.GPJ NORTH ANNA 3.GDT 12/3/09



SHEET 2 OF 3

BECHTEL PROJECT NO.: 25161			MACTEC PROJECT NO.: 6468-09-2473			COUNTY: Louisa, VA			GEOLOGIST: R. Clark		
SITE DESCRIPTION: North Anna 3 Project Supplement 2						DRILLER: F. Cox/R. Hall			FLUID LEVEL (ft)		
BORING NO.: M-21			DRILL METHOD: Mud Rotary/Rock Core			DRILL MACHINE: CME-55 Track (RAL)			0 HR. 10.5		
GROUND ELEV.: 303.9 ft (NAVD88)			NORTHING: 3,909,811 US ft (NAD83)			EASTING: 11,686,270 US ft (NAD83)			24 HR. 29.5		
TOTAL DEPTH: 151.8 ft			SAMPLE METHODS: ASTM D 1586-08a; 2488-09a; 2113-08; 6032-08			ROD TYPE: AWJ			HAMMER (ID):140-lb. Auto (MEC-21)		
DATE STARTED: 9/22/09			COMPLETED: 9/24/09			HOLE DIA.: 4"			CASING DEPTH: 63.8 ft		
						CORE SIZE: HQ3			BITS USED: 3-7/8" Tri-Cone		

ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT						SAMP. NO.	LOG MOI	SOIL AND ROCK DESCRIPTION
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100			
229.1					Continued from previous page								
													227.1 HARD ROCK: Black to light gray, with brown staining, moderately weathered, close fracturing, medium hard, BIOTITE GNEISS 76.8
													224.1 WEATHERED ROCK: Light gray, severely weathered, close fracturing, soft, BIOTITE QUARTZ GNEISS 79.8
													223.1 HARD ROCK: Light gray, moderately weathered, close fracturing, moderately hard to hard, BIOTITE QUARTZ GNEISS 80.8
													221.4 HARD ROCK: Dark and light gray to black, moderately severe to slightly weathered, close fracturing, soft to hard, BIOTITE GNEISS with hornblende 82.5
													212.1 HARD ROCK: Gray to dark gray, slightly weathered to fresh, moderately close to wide fracturing, hard to very hard, BIOTITE GNEISS to QUARTZ BIOTITE GNEISS 91.8

NORTH ANNA 3 BORE NORTH ANNA 3 PROJECT.GPJ NORTH ANNA 3.GDT 12/3/09

BECHTEL PROJECT NO.: 25161						MACTEC PROJECT NO.: 6468-09-2473								COUNTY: Louisa, VA						GEOLOGIST: R. Clark															
SITE DESCRIPTION: North Anna 3 Project Supplement 2																		DRILLER: F. Cox/R. Hall						FLUID LEVEL (ft)											
BORING NO.: M-21						DRILL METHOD: Mud Rotary/Rock Core						DRILL MACHINE: CME-55 Track (RAL)						0 HR. 10.5																	
GROUND ELEV.: 303.9 ft (NAVD88)						NORTHING: 3,909,811 US ft (NAD83)						EASTING: 11,686,270 US ft (NAD83)						24 HR. 29.5																	
TOTAL DEPTH: 151.8 ft						SAMPLE METHODS: ASTM D 1586-08a; 2488-09a; 2113-08; 6032-08						ROD TYPE: AWJ						HAMMER (ID): 140-lb. Auto (MEC-21)																	
DATE STARTED: 9/22/09						COMPLETED: 9/24/09						HOLE DIA.: 4"						CASING DEPTH: 63.8 ft						CORE SIZE: HQ3						BITS USED: 3-7/8" Tri-Cone					
ELEV.	DEPTH	BLOW COUNT			BLOWS PER FOOT						SAMP.		L O G	SOIL AND ROCK DESCRIPTION																					
(ft)	(ft)	0.5ft	0.5ft	0.5ft	0	20	40	60	80	100	NO.															MOI									
154.3					Continued from previous page																														
																																			
														152.1 Boring and coring terminated at 151.8 feet. Boring closed by tremie method with cement-bentonite grout. 151.8																					

NORTH ANNA 3 BORE NORTH ANNA 3 PROJECT.GPJ NORTH ANNA 3.GDT 12/3/09



SHEET 1 OF 2

BECHTEL PROJECT NO.: 25161			MACTEC PROJECT NO.: 6468-09-2473			COUNTY: Louisa, VA		GEOLOGIST: R. Clark		
SITE DESCRIPTION: North Anna 3 Project Supplement 2						DRILLER: F. Cox/R. Hall			FLUID LEVEL (ft) 0 HR. 10.5 24 HR. 29.5	
BORING NO.: M-21			DRILL METHOD: Mud Rotary/Rock Core			DRILL MACHINE: CME-55 Track (RAL)				
GROUND ELEV.: 303.9 ft		(NAVD88)	NORTHING: 3,909,811 US ft (NAD83)			EASTING: 11,686,270 US ft (NAD83)				
TOTAL DEPTH: 151.8 ft		SAMPLE METHODS: ASTM D 1586-08a; 2488-09a; 2113-08; 6032-08						HAMMER (ID): 140-lb. Auto (MEC-21)		
DATE STARTED: 9/22/09		COMPLETED: 9/24/09		CASING DEPTH: 63.8 ft		CORE BARREL TYPE: Wireline HQ3 Triple Tube, series 6 & 10 bits				

ELEV. (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		L O G	DESCRIPTION AND REMARKS
				REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %		
										Begin Coring @ 63.8 ft
240.1	63.8	3.0	5:34 3:21	(2.0) 67%	(1.1) 37%	RUN 1	(4.5) 82%	(3.2) 58%	240.1	HARD ROCK: Gray to dark gray, with orange staining, moderately severely to moderately weathered, close fracturing, soft to medium hard, BIOTITE QUARTZ GNEISS
237.1	66.8		2:49							
		4.0	1:38 3:37 3:55	(2.5) 63%	(2.1) 53%	RUN 2				(4 joints at 45°, tight; foliation at 45°)
233.1	70.8		2:42				(2.4) 32%	(0.0) 0%	234.6	WEATHERED ROCK: Brown, reddish brown, and dark gray, severely weathered, close fracturing, very soft to soft, BIOTITE QUARTZ GNEISS and BIOTITE GNEISS
232.1	71.8	1.0	3:24	(0.0) 0%	(0.0) 0%	RUN 3				
230.1	73.8	2.0	2:28 2:41	(0.5) 25%	(0.0) 0%	RUN 4				
		5.0	2:27 2:33	(1.9) 38%	(0.0) 0%	RUN 5				(3 joints at 0-10°, tight with trace iron staining; 5 joints at 45°, tight with trace iron staining; foliation at 45°)
227.1	76.8		2:11	(2.5) 63%	(0.7) 18%	RUN 6	(1.7) 57%	(0.7) 23%	227.1	HARD ROCK: Black to light gray, with brown staining, moderately weathered, close fracturing, medium hard, BIOTITE GNEISS
225.1	78.8	4.0	2:33 2:28	(0.8) 80%	(0.0) 0%				224.1	(3 joints at 30°, tight; 1 joint at 80°, tight with quartz vein; foliation at 30°)
223.1	80.8		3:05 3:14	(1.0) 100%	(0.0) 0%	RUN 7			223.1	WEATHERED ROCK: Light gray, severely weathered, close fracturing, soft, BIOTITE QUARTZ GNEISS
222.1	81.8	1.0	3:59	(2.5) 96%	(1.3) 50%	RUN 8	(1.7) 100%	(0.7) 41%	221.4	HARD ROCK: Light gray, moderately weathered, close fracturing, moderately hard to hard, BIOTITE QUARTZ GNEISS
	84.4	2.6	5:15 2:27	(5.0) 100%	(2.8) 56%	RUN 9	(9.1) 98%	(4.9) 53%		(4 joints at 0-10°, tight; 2 joints at 45-55°, tight with trace iron staining)
		2.4	2:45/0.6 5:14 6:58	(5.0) 100%	(2.8) 56%	RUN 10				HARD ROCK: Dark and light gray to black, moderately severe to slightly weathered, close fracturing, soft to hard, BIOTITE GNEISS with hornblende
		5.0	3:25 3:33 4:34 2:54 5:18	(5.0) 100%	(2.8) 56%				212.1	(2 joints at 60°, tight; foliation at 60°)
212.1	91.8						(59.9) 100%	(57.3) 96%		(5 joints at 0-10°, tight)
		5.0	5:53 3:23 3:42 3:37 3:11	(5.0) 100%	(3.1) 62%	RUN 11				(5 joints at 50°, tight; foliation at 50°)
207.1	96.8									HARD ROCK: Gray to dark gray, slightly weathered to fresh, moderately close to wide fracturing, hard to very hard, BIOTITE GNEISS to QUARTZ BIOTITE GNEISS
		5.0	5:46 5:48 5:00 3:02 4:50	(5.0) 100%	(4.5) 90%	RUN 12				(7 joints at 30-45°, tight with iron staining)
202.1	101.8									(4 joints at 50-60°, tight with trace chlorite; 2 quartz veins at 60° with trace calcite, chlorite, magnetite, and pyrite)
		5.0	2:25 2:33 2:46 2:49 3:09	(5.0) 100%	(5.0) 100%	RUN 13				(3 joints at 45°, tight with trace hornblende and iron staining; foliation at 45°)
197.1	106.8									
		5.0	2:43 2:08 2:11 3:42 1:57	(5.0) 100%	(5.0) 100%	RUN 14				(2 joints at 40°, tight; 1 joint at 60°, tight)
192.1	111.8									
		5.0	2:38 2:17 2:02 2:08 2:12	(5.0) 100%	(5.0) 100%	RUN 15				(1 joint at 30°, tight)
187.1	116.8									
		5.0	3:49 2:42 2:12 2:30 2:42	(5.0) 100%	(4.8) 96%	RUN 16				(3 joints at 30°, tight; 1 quartz vein at 70° with trace pyrite)
182.1	121.8									
		5.0	2:27 2:33 2:35 2:42 2:48	(5.0) 100%	(5.0) 100%	RUN 17				(2 joints at 25°, tight; 1 joint at 45°, tight; trace pyrite)
177.1	126.8									
		5.0	2:40 2:38 2:48 2:55 2:59	(4.9) 98%	(4.9) 98%	RUN 18				(3 joints at 50°, tight; foliation at 50°)
172.1	131.8									
		5.0	2:10 2:09 2:02 1:53 1:48	(5.0) 100%	(5.0) 100%	RUN 19				(1 joint at 45°, tight)
167.1	136.8									
		5.0	2:51 2:25	(5.0) 100%	(5.0) 100%	RUN 20				(No joints)

NORTH ANNA 3 CORE NORTH ANNA 3 PROJECT.GPJ NORTH ANNA 3.GDT 12/3/09




SHEET 2 OF 2

BECHTEL PROJECT NO.: 25161			MACTEC PROJECT NO.: 6468-09-2473			COUNTY: Louisa, VA			GEOLOGIST: R. Clark		
SITE DESCRIPTION: North Anna 3 Project Supplement 2						DRILLER: F. Cox/R. Hall			FLUID LEVEL (ft)		
BORING NO.: M-21			DRILL METHOD: Mud Rotary/Rock Core			DRILL MACHINE: CME-55 Track (RAL)			0 HR. 10.5		
GROUND ELEV.: 303.9 ft (NAVD88)			NORTHING: 3,909,811 US ft (NAD83)			EASTING: 11,686,270 US ft (NAD83)			24 HR. 29.5		
TOTAL DEPTH: 151.8 ft			SAMPLE METHODS: ASTM D 1586-08a; 2488-09a; 2113-08; 6032-08						HAMMER (ID): 140-lb. Auto (MEC-21)		
DATE STARTED: 9/22/09			COMPLETED: 9/24/09			CASING DEPTH: 63.8 ft			CORE BARREL TYPE: Wireline HQ3 Triple Tube, series 6 & 10 bits		

ELEV. (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		L O G	DESCRIPTION AND REMARKS
				REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %		
										Continued from previous page
162.1	141.8		2:31 1:54 1:48	100%	100%					 HARD ROCK: Gray to dark gray, slightly weathered to fresh, moderately close to wide fracturing, hard to very hard, BIOTITE GNEISS to QUARTZ BIOTITE GNEISS (<i>continued</i>) (1 joint at 55°, tight; foliation at 55°; trace pyrite) (No joints; trace pyrite and hornblende)
		5.0	2:03 2:26 2:06 2:46 2:05	(5.0) 100%	(5.0) 100%	RUN 21				
157.1	146.8									
		5.0	2:08 2:33 2:25 2:11 2:04	(5.0) 100%	(5.0) 100%	RUN 22				
152.1	151.8									152.1 151.8
Boring and coring terminated at 151.8 feet.										
Boring closed by tremie method with cement-bentonite grout.										


NORTH ANNA 3 CORE NORTH ANNA 3 PROJECT.GPJ NORTH ANNA 3.GDT 12/3/09




M-21 - Box 1




M-21 - Box 2




M-21 - Box 3




M-21 - Box 4



M-21 - Box 5



M-21 - Box 6



M-21 - Box 7



GEOTECHNICAL BORING LOG

Prepared By JJJ Date 12/16/09Checked By MM Date 12/16/09

SHEET 1 OF 3

BECHTEL PROJECT NO.: 25161				MACTEC PROJECT NO.: 6468-09-2473				COUNTY: Louisa, VA				GEOLOGIST: C. Baldwin				
SITE DESCRIPTION: North Anna 3 Project Supplement 2								DRILLER: P. Pitts/J. Tucker				FLUID LEVEL (ft) 0 HR. NA 24 HR. 34.0				
BORING NO.: M-27				DRILL METHOD: Mud Rotary/Rock Core				DRILL MACHINE: CME-55 Trailer (RAL)								
GROUND ELEV.: 330.2 ft (NAVD88)				NORTHING: 3,909,426 US ft (NAD83)				EASTING: 11,685,938 US ft (NAD83)								
TOTAL DEPTH: 151.4 ft		SAMPLE METHODS: ASTM D 1586-08a; 2488-09a; 2113-08; 6032-08						ROD TYPE: AWJ		HAMMER (ID): 140-lb. Auto (MEC-425)						
DATE STARTED: 9/15/09		COMPLETED: 9/21/09		HOLE DIA.: 3"		CASING DEPTH: 114.6 ft		CORE SIZE: NQ3		BITS USED: 2-7/8" Tri-Cone						
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100						
330.2					Ground Surface								330.2	0.0		
														No sampling from 0.0 to 9.0 feet due to soft dig utility clearance by Dominion Personnel		
321.2	9.0												321.2	9.0		
318.5	11.7	5	4	7	11						SS-1			RESIDUAL SOIL: Silty SAND (SM), reddish yellow (7.5YR 6/6), medium dense, moist, fine to coarse grained sand, little mica, relict rock fabric 11.7 ft: Very pale brown (10YR 7/3), fine to medium grained sand		
316.4	13.8	5	5	6	11						SS-2					
		5	4	7	11						SS-3					
311.4	18.8													18.8 ft: Light yellowish brown (10YR 6/4), fine to coarse grained sand		
		7	8	8	16						SS-4					
306.4	23.8	8	11	11										23.8 ft: Very pale brown (10YR 7/3)		
					22						SS-5					
301.4	28.8	10	15	19										28.8 ft: Pale brown (10YR 6/3), dense, fine to medium grained sand		
					34						SS-6					
296.5	33.7	12	15	15										33.7 ft: Brownish yellow (10YR 6/6), medium dense, fine to coarse grained sand		
					30						SS-7					
291.5	38.7	19	21	25										38.7 ft: Dense		
					46						SS-8					
286.5	43.7	22	41	35										43.7 ft: Very pale brown (10YR 7/3), very dense		
					76						SS-9					
281.5	48.7	16	26	31										48.7 ft: Light yellowish brown (10YR 6/4)		
					57						SS-10					
276.5	53.7	17	21	50										273.2 57.0		
					71						SS-11					
271.5	58.7	42	58/0.4											WEATHERED ROCK: Severely weathered BIOTITE QUARTZ GNEISS (Sampled as Silty SAND (SM), light yellowish brown (10YR 6/4), very dense, moist, fine to coarse grained sand, little mica)		
					100/0.9						SS-12					
266.5	63.7	37	63/0.4											63.7 ft: Yellowish brown (10YR 5/6)		
					100/0.9						SS-13					
261.5	68.7	50/0.2														
					50/0.2						SS-14					
256.5	73.7	50/0.2														
					50/0.2						SS-15					

NORTH ANNA 3 BORE NORTH ANNA 3 PROJECT.GPJ NORTH ANNA 3.GDT 12/4/09



SHEET 2 OF 3

BECHTEL PROJECT NO.: 25161				MACTEC PROJECT NO.: 6468-09-2473				COUNTY: Louisa, VA				GEOLOGIST: C. Baldwin			
SITE DESCRIPTION: North Anna 3 Project Supplement 2								DRILLER: P. Pitts/J. Tucker				FLUID LEVEL (ft)			
BORING NO.: M-27				DRILL METHOD: Mud Rotary/Rock Core				DRILL MACHINE: CME-55 Trailer (RAL)				0 HR.		NA	
GROUND ELEV.: 330.2 ft (NAVD88)				NORTHING: 3,909,426 US ft (NAD83)				EASTING: 11,685,938 US ft (NAD83)				24 HR.		34.0	
TOTAL DEPTH: 151.4 ft		SAMPLE METHODS: ASTM D 1586-08a; 2488-09a; 2113-08; 6032-08						ROD TYPE: AWJ		HAMMER (ID): 140-lb. Auto (MEC-425)					
DATE STARTED: 9/15/09		COMPLETED: 9/21/09		HOLE DIA.: 3"		CASING DEPTH: 114.6 ft		CORE SIZE: NQ3		BITS USED: 2-7/8" Tri-Cone					
ELEV.	DEPTH	BLOW COUNT			BLOWS PER FOOT					SAMP.	LOG	SOIL AND ROCK DESCRIPTION			
(ft)	(ft)	0.5ft	0.5ft	0.5ft	0	20	40	60	80	100					NO.
255.4					Continued from previous page										
251.5	78.7													WEATHERED ROCK: Severely weathered BIOTITE QUARTZ GNEISS (Sampled as Silty SAND (SM), light yellowish brown (10YR 6/4), very dense, moist, fine to coarse grained sand, little mica) (continued)	
		50/0.1									50/0.1	SS-16			
243.8	86.4													86.4 ft: Pale Yellow (2.5YR 7/3)	
		50/0.2									50/0.2	SS-17			
239.4	90.8														
		50/0.3									50/0.3	SS-18			
234.4	95.8													95.8 ft: Very pale brown (10YR 7/4)	
		50/0.2									50/0.2	SS-19			
229.4	100.8														
		41	59/0.5								100/1.0	SS-20			
224.4	105.8														
		50/0.1									50/0.1	SS-21			
219.4	110.8														
		50/0.1									50/0.1	SS-22			
214.4	115.8													115.0 ft: Hard Drilling/Bit Chatter; SPT Refusal with no penetration at 115.8 ft	
		100/0.0									100/0.0	SS-23			
														HARD ROCK: Gray and white to light gray, with orange staining, moderately severely to moderately weathered, very close to close fracturing, medium hard to moderately hard, BIOTITE QUARTZ GNEISS	
														HARD ROCK: Gray and white with trace orange staining, moderately to slightly weathered, very close to moderately close fracturing, moderately hard to hard, BIOTITE QUARTZ GNEISS	
														HARD ROCK: Gray and white with trace orange staining, moderately to very slightly weathered, close to moderately close fracturing, moderately hard to hard, BIOTITE QUARTZ GNEISS	
											</				

NORTH ANNA 3 BORE NORTH ANNA 3 PROJECT.GPJ NORTH ANNA 3.GDT 12/4/09



SHEET 3 OF 3

BECHTEL PROJECT NO.: 25161		MACTEC PROJECT NO.: 6468-09-2473		COUNTY: Louisa, VA		GEOLOGIST: C. Baldwin	
SITE DESCRIPTION: North Anna 3 Project Supplement 2				DRILLER: P. Pitts/J. Tucker		FLUID LEVEL (ft)	
BORING NO.: M-27		DRILL METHOD: Mud Rotary/Rock Core		DRILL MACHINE: CME-55 Trailer (RAL)		0 HR. NA	
GROUND ELEV.: 330.2 ft (NAVD88)		NORTHING: 3,909,426 US ft (NAD83)		EASTING: 11,685,938 US ft (NAD83)		24 HR. 34.0	
TOTAL DEPTH: 151.4 ft		SAMPLE METHODS: ASTM D 1586-08a; 2488-09a; 2113-08; 6032-08		ROD TYPE: AWJ		HAMMER (ID):140-lb. Auto (MEC-425)	
DATE STARTED: 9/15/09		COMPLETED: 9/21/09		HOLE DIA.: 3"		CASING DEPTH: 114.6 ft	
				CORE SIZE: NQ3		BITS USED: 2-7/8" Tri-Cone	

ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT						SAMP. NO.	LOG MOI	SOIL AND ROCK DESCRIPTION
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100			
180.6					Continued from previous page								
													178.8
													151.4
													Boring and coring terminated at 151.4 feet.
													Boring closed by tremie method with cement-bentonite grout.
													24 hour water level measured on 9/21/2009 prior to drilling. Borehole was at a depth of 146.4 feet.

NORTH ANNA 3 BORE NORTH ANNA 3 PROJECT.GPJ NORTH ANNA 3.GDT 12/4/09




SHEET 1 OF 1


BECHTEL PROJECT NO.: 25161	MACTEC PROJECT NO.: 6468-09-2473	COUNTY: Louisa, VA	GEOLOGIST: C. Baldwin
SITE DESCRIPTION: North Anna 3 Project Supplement 2		DRILLER: P. Pitts/J. Tucker	FLUID LEVEL (ft)
BORING NO.: M-27	DRILL METHOD: Mud Rotary/Rock Core	DRILL MACHINE: CME-55 Trailer (RAL)	0 HR. NA
GROUND ELEV.: 330.2 ft (NAVD88)	NORTHING: 3,909,426 US ft (NAD83)	EASTING: 11,685,938 US ft (NAD83)	24 HR. 34.0
TOTAL DEPTH: 151.4 ft	SAMPLE METHODS: ASTM D 1586-08a; 2488-09a; 2113-08; 6032-08		HAMMER (ID): 140-lb. Auto (MEC-425)
DATE STARTED: 9/15/09	COMPLETED: 9/21/09	CASING DEPTH: 114.6 ft	CORE BARREL TYPE: Wireline NQ3 Triple Tube, series 6 bit

ELEV. (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		L O G	DESCRIPTION AND REMARKS	
				REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %			
										Begin Coring @ 78.8 ft	
251.4 248.6	78.8 81.6	2.8	3:57 3:08 2:03/0.8	(0.0) 0%	(0.0) 0%	RUN 1	(0.0) 0%	(0.0) 0%		WEATHERED ROCK: Severely weathered BIOTITE QUARTZ GNEISS (Sampled as Silty SAND (SM), light yellowish brown (10YR 6/4), very dense, moist, fine to coarse grained sand, little mica) (continued) (No Recovery) (No Recovery)	
		4.8	4:40 4:10 2:42 2:30 2:46/0.8	(0.0) 0%	(0.0) 0%	RUN 2				86.4 ft: Pale Yellow (2.5YR 7/3)	
243.8	86.4		N=50/0.2			SS-17					
			N=50/0.3			SS-18					
			N=50/0.2			SS-19					95.8 ft: Very pale brown (10YR 7/4)
			N=100/1.0			SS-20					
			N=50/0.1			SS-21					
			N=50/0.1			SS-22					
											115.0 ft: Hard Drilling/Bit Chatter; SPT Refusal with no penetration at 115.8 ft
214.4 213.8	115.8 116.4	0.6 5.0	N=100/0.0 1:40/0.6	(0.6) 100%	(0.6) 100%	RUN 3 RUN 4	(3.5) 63%	(2.5) 45%			HARD ROCK: Gray and white to light gray, with orange staining, moderately severely to moderately weathered, very close to close fracturing, medium hard to moderately hard, BIOTITE QUARTZ GNEISS (5 joints at 0°, tight; 3 joints at 30°, tight)
			2:38 1:26 3:47 1:20 2:26	(2.9) 58%	(1.9) 38%						
208.8	121.4	5.0	3:20 4:54 1:25 2:13 3:30	(5.0) 100%	(4.8) 96%	RUN 5	(13.4) 89%	(12.7) 85%			HARD ROCK: Gray and white with trace orange staining, moderately to slightly weathered, very close to moderately close fracturing, moderately hard to hard, BIOTITE QUARTZ GNEISS (1 joint at 30°, tight; 3 joints at 50°, tight) (1 joint at 20°, tight; 1 joint at 60°, tight)
203.8	126.4	5.0	3:05 3:24 3:14 2:36 2:35	(5.0) 100%	(4.8) 96%	RUN 6					(2 joints at 0°, tight to open; 2 joints at 10-20°, tight)
198.8	131.4	5.0	2:41 3:50 2:00 2:20 2:18	(3.4) 68%	(3.1) 62%	RUN 7					
193.8	136.4	5.0	2:44 2:34 3:15 3:19 3:55	(5.0) 100%	(4.0) 80%	RUN 8	(15.0) 100%	(14.0) 93%			HARD ROCK: Gray and white with trace orange staining, moderately to very slightly weathered, close to moderately close fracturing, moderately hard to hard, BIOTITE QUARTZ GNEISS (9 joints at 40°, tight; 1 joint at 60°, tight) (1 joint at 20°, open)
188.8	141.4	5.0	4:27 4:45 2:08 4:00 3:00	(5.0) 100%	(5.0) 100%	RUN 9					(2 joints at 20-30°, tight)
183.8	146.4	5.0	3:35 4:18 4:45 6:20 5:50	(5.0) 100%	(5.0) 100%	RUN 10					
178.8	151.4										Boring and coring terminated at 151.4 feet. Boring closed by tremie method with cement-bentonite grout.

NORTH ANNA 3 CORE NORTH ANNA 3 PROJECT.GPJ NORTH ANNA 3.GDT 12/4/09



M-27 - Box 1



M-27 - Box 2