

APR 1 1977

Docket No.: ~~50-372~~ ✓
50-261

Carolina Power & Light Company
ATTN: Mr. J. A. Jones
Senior Vice President
336 Fayetteville Street
Raleigh, North Carolina 27602

Gentlemen:

RE: H. B. ROBINSON UNIT NO. 2

DISTRIBUTION:
Docket File
NRC PDR
L PDR
ORB#4 Rdg
TJCarter
RReid
RIngram
GZwetzig
GZech
Attorney, OELD
OI&E (3)
DEisenhut
TBAbernathy
JRBuchanan
ACRS (16)
Gray File

A pressure transient recently occurred at an operating PWR facility when a reactor coolant pump (RCP) was started while in a water-solid condition. At the time, the temperature of the steam generator in that loop was greater than the reactor coolant system (RCS) temperature and a pressure transient from about 400 psig to about 800 psig resulted.

In our January 10, 1977 letter we stated that all PWR licensees should include provisions to prevent RCP starts while in a water-solid condition. The purpose of such provisions is to prevent pressure transients due to temperature differentials within the RCS. We also stated that should it become necessary to start a RCP while water-solid, appropriate steps are to be taken to determine and minimize the temperature profile. Such action was not taken prior to the recently reported event.

Based on this recent pressure transient and our review of PWR submittals describing RCP operating procedures, we are concerned that the significance of this event may not be fully realized.

We, therefore, now request that you implement procedures to prevent RCP starts (or "jogs") while in a water-solid condition when the steam generator temperature is greater than RCS temperature. In the event that a RCP start while water-solid cannot be avoided we request that your plant operating procedures include non-optional pre-requisite steps to ensure that the RCS temperature profile is determined and if that profile is excessive, that appropriate measures are specified to achieve an acceptable profile prior to starting a RCP.



We further request that these procedures be implemented immediately, and that they remain in effect until we have received and approved an analysis justifying any deviations from these provisions. You are requested to advise us within 15 days of receipt of this letter that you have implemented the provisions discussed above.

In addition, it is strongly recommended that you immediately conduct a critical review of your procedures to ensure that they are fully responsive to all of the positions stated in our letter of January 10, 1977 and compatible with the pertinent results of your RCS pressure response analysis.

Sincerely,

Original signed by

FWT

Robert W. Reid, Chief
Operating Reactors Branch #4
Division of Operating Reactors

cc: See next page

M.B. Floyd

OFFICE	ORB#4:DOR	ORB#1:DOR	C-ORB#4:DOR		
SURNAME	GZwetzig	GZech	RReid		
DATE	4/1/77	4/1/77	4/1/77		

Carolina Power & Light Company

cc: G. F. Trowbridge, Esq.
Shaw, Pittman, Potts & Trowbridge
1800 M Street, N. W.
Washington, D. C. 20036

Hartsville Memorial Library
Home and Fifth Avenue
Hartsville, South Carolina 29550