

West Valley Melter Package NRC Special Authorization Second Pre-Application Briefing

Presenters: SRNL: Jeff England, Charles McKeel, Ed Ketusky CHBWV: Todd Pieczynski Ameriphysics: Chris Brandjes

August 19, 2014

Rev. 0, 08/14/2014


safety & performance & cleanup & closure

www.energy.gov/EM

OFFICE OF ENVIRONMENTAL MANAGEMENT Content Description

- The West Valley Melter (Melter) is comprised of a stainless steel outer housing with an exterior structural steel frame
- The interior of the Melter is lined with refractory materials
- The maximum envelope dimensions of the Melter is 10'-9¾" wide x 11'-10" long x 10'-5 ½" high
- The Melter weight is 107,500 pounds
- The Melter was built to ASTM standards and procured under the West Valley NQA-1 program

West Valley Melter Configuration



PREDECISIONAL DRAFT

OFFICE OF ENVIRONMENTAL

ANAGEMENT

Content Radiological Description

- The Melter contains 3,554 curies (decay corrected to September 2, 2014), including the surface contaminants
- The external contaminated Melter surfaces were coated with three layers of Bartlett's PBSTM contamination fixative
 - o Surface contaminants were fixed on the equipment surface
 - A fraction of the radioactive surface content is assumed to have leached in the LDCC external to the Melter
- The internal contamination associated with the Melter is contained within a borosilicate glass
 - Radioactive content characterization was derived using analytical data from glass samples from specific sources associated with the heel and spout. Quantification of the radioactivity within the Melter refractory was completed using an average of analytical slurry samples obtained throughout Melter processing
 - A fraction of the radioactive glass content is assumed to have leached into the LDCC contained within the Melter

PREDECISIONAL DRAFT

OFFICE OF



Activity Breakdown by Source Term					
Source Term	Total Act (Ci)	Fissile Mass (g)	A2s	Decay Heat (W)	% of Total Activity
Exterior Contamination (decay corrected)	1.436E+01	6.569E-01	2.136E+00	4.054E-02	0.404%
Melter Spout (decay corrected)	1.793E+03	1.899E+01	8.244E+01	4.551E+00	50.445%
Refractory (decay corrected)	6.300E+02	3.268E+01	6.713E+01	1.768E+00	17.725%
Melter Heel (decay corrected)	1.117E+03	2.923E+01	6.315E+01	2.834E+00	31.426%
Totals	3.554E+03	8.156E+01	2.149E+02	9.194E+00	100.000%

Activity Associated to Primary Isotopes						
	Exterior Surface	Spout	Refractory	Heel		Totals
	Act (Ci)	Act (Ci)	Act (Ci)	Act (Ci)	Act (Ci)	% of Total Act
Cs-137	5.062E+00	8.566E+02	2.132E+02	5.419E+02	1.617E+03	45.487%
Ba-137m	4.778E+00	8.086E+02	2.012E+02	5.116E+02	1.526E+03	42.938%
Sr-90	2.213E+00	6.332E+01	1.068E+02	3.120E+01	2.035E+02	5.726%
Y-90	2.213E+00	6.333E+01	1.068E+02	3.121E+01	2.036E+02	5.727%
Total Activity of Primary Isotopes						99.878%
Remaining Activity						0.122%

MELTER SOURCE TERM

The radioactivity associated to the Melter is contained within four separate Source Terms

• Heel

OFFICE OF

- o Contained within the lower body of the Melter
- Consists of the remaining vitrified glass from processing of flushing materials from the Melter Feed Hold Tank and Concentrator Feed Make-Up Tank
- Consists of 300 kg of vitrified glass
- Characterized using glass shard samples taken from evacuated canister material
- Radiological Characterization Summary:

Total Activity	1.117E+03 Ci
Fissile Mass	2.923E+01 grams
A ₂ Contribution	6.315E+01 A ₂ s
Percent of Total Activity	31.426%

MELTER SOURCE TERM (Continued)

• Spout

OFFICE OF

- Consists of vitrified glass material from Batch 75, Canister 266 that clogged the West Discharge Port during vitrification processing
- Consists of 99 kg of vitrified glass
- Characterized using shard samples of Canister 266 waste for Cs-137 and Sr-90 and scaling in remaining isotopes using Heel isotopic distribution
- Radiological Characterization Summary:

 Total Activity 	1.793E+03 Ci
Fissile Mass	1.899E+01 grams
 A₂ Contribution 	8.244E+01 A ₂ s
 Percent of Total Activity 	50.445%

MELTER SOURCE TERM (Continued)

Refractory

OFFICE OF

- Contained within the body of the Melter surrounding the Melter cavity
- Consists of vitrified glass contained within the cracks, crevices and interstitial spacing between and within the pieces of refractory brick
- Conservative estimate of 1% of the total volume of refractory brick was used as the volume of vitrified glass
- Total volume of vitrified glass contained within the refractory brick is 0.927 ft³ (68.3 kg)
- Characterized using the average geometric mean concentrations for all of the samples taken from Batch 6 through 77 and applied to the mass of vitrified glass
- Radiological Characterization Summary:

Total Activity	6.300E+02 Ci
Fissile Mass	3.268E+01 grams
A ₂ Contribution	6.713E+01 A ₂ s
Percent of Total Activity	17.725%

PREDECISIONAL DRAFT

8

MELTER SOURCE TERM (Continued)

• Melter Exterior Contamination

OFFICE OF

- Consists of the removable activity associated to the exterior surface of the melter
- Characterized using smear data samples
 - Applied highest reported result to entire surface are of the Melter
 - Applied a 10% Wiping Efficiency
- Total Surface Area of Melter is 80,950 in²
- Activity concentration associated to exterior Melter is 27.50 uCi/cm²
- Radiological Characterization Summary:

•	Total Activity	1.436E+01 Ci
•	Fissile Mass	6.569E-01 grams
•	A ₂ Contribution	2.136E+00 A ₂ s
•	Percent of Total Activity	0.404%

PREDECISIONAL DRAFT


ENVIRONMENTAL West Valley Melter Package Description

- The West Valley Melter Package (WVMP) is a rectangular shaped package made from SA-516, Grade 70 carbon steel
- The package is 15'-9" long x 12'-6" wide x 12'-6" high
- It has a side cover recessed into the package with 32 1¹/₂" diameter bolts
- It was sealed with a neoprene rubber gasket
- It will be reinforced with an impact limiter over the bolted side cover (adding approximately 10" to the length of the package)

ENVIRONMENTAL Package Materials of Construction and Criteria

- ASTM SA-516 Grade 70 Carbon Steel for the Package top, bottom, sides, end cover and temporary attachments
- ASTM A36 Carbon Steel for the shock absorbers
- Package side cover bolts are ASTM A193-B7
- American Welding Society (AWS) D1.1
 - e.g., Weld electrodes per Structural Welding Code Steel
- American Institute of Steel Construction (AISC) for shipment of radioactive material under 49CFR173
- The impact limiter will be 10 CFR 71 compliant

Packaging Configuration (Cutaway Section)



MELTER DOT PACKAGE CONFIGURATION

PREDECISIONAL DRAFT

Not-to-scale Rev. 0, 08/14/2014

safety * performance * cleanup * closure

OFFICE OF


ENVIRONMENTAL MANAGEMENT

PACKaging Weight and Design Criteria

- The weight of the empty package is approximately 212,000 lbs.
- Content weight is 107,500 lbs.
- The impact limiter will meet 10 CFR 71 criteria and will weigh approximately 7,000 lbs.
- The total weight of the WVMP, including the radioactive contents, low-density cellular concrete (LDCC) and the package, is approximately 389,000 lbs.

West Valley Melter Package


Impact Limiter for Hypothetical Accident Condition (HAC)



2"x9" plates 6"x10" Tube Steel Foam Fill 2" dia Pins

Proposed


PREDECISIONAL DRAFT



PREDECISIONAL DRAFT

OFFICE OF ENVIRONMENTAL MANAGEMENT Reinforcement of Impact Limiters


Impact Limiter



PREDECISIONAL DRAFT

Reinforcement of Impact Limiters

Impact Limiter



PREDECISIONAL DRAFT

Rev. 0, 08/14/2014

safety & performance & cleanup & closure

OFFICE OF

ENVIRONMENTAL MANAGEMENT

Ongoing Structural Analyses

• NCT/HAC Drop Analyses Orientations

- Door Side Down (Maximize Content Inertial Effect)
- CG over Corner (Maximize Fish-Mouth Opening at Door)
- CG over any Edge (Combined Effect of Above two)
- Back Side Down Drops (no Added Impact Limiter)

PREDECISIONAL DRAFT

OFFICE OF

ENVIRONMENTAL

Ongoing Structural Analyses

- Existing Data for Glass Performance in Drops
 - Battelle Northwest Laboratory (BNWL) Drop Tests of Bare Canisters
 - 10 foot, 30 foot, 68 foot and 213 foot drops
 - BNWL-1903 UC-70

OFFICE OF

- Tests were performed to establish impact behavior and production of airborne particles
- Glass mixture for test was 75% frit, 25% calcine
- No canister breach at 30 foot drops
- Some canisters breached at 68 ft and 213 ft, "very little, if any, glass escaped"
- G-values were 1,000G to 3,600G for 30 foot drops
 - Glass Breakage Fraction was 0.029
- 30 foot drop analysis shows Melter with ~50G and stress is less than yield

PREDECISIONAL DRAFT

safety * performance * cleanup * closure

Ongoing Structural Assessment

• 10 Foot Corner Drop Confirmatory FEA


• SRNL Evaluation shows 23G

OFFICE OF

- Indicates Full Utilization of Absorber Occurs Prior to Absorbing Energy Demand of the 10' Drop
 - Due to 382,000 lbs. Model Weight
 - Causes Spike in Bolt Demands In latter stage of impact
 - Additional Drop Height Invokes Disproportionately Higher Demands in bolts
- Bolts Do Not Break, but at tensile strain limit (ignores Thread Failure)
 - Thread Failure Still In Question, cannot credit full bolt tensile strains, since shear failure in non-ductile

ENVIRONMENTAL Ongoing Confirmatory Structural Assessment

• 10 Foot Corner Drop Confirmatory FEA



Kinetic Energy History During Impact

Energy Plot matches the 2004 analysis, once weight diff is accounted.


PREDECISIONAL DRAFT

OFFICE OF

ENVIRONMENTAL Ongoing Confirmatory Structural Assessment

• 30 Foot Drop, CG Over Door Side Edge


- Impact = 68G Load
 - 0.035 sec total Duration, High G based on 0.02 sec
- Concrete Stress Nominally < 1000 psi, by Localized Regions above compression stress limits, ~10% damaged
- About 75% of Bolts Fail in Tension (Content Inertial Loads, Deformed Absorber)
- Door Deflection, < 1 inch. Door Lateral Gaps Tighten at Impact Points, Unchanged elsewhere



• 30 Foot Drop, CG Over Bottom Edge, Deformed Shape

PREDECISIONAL DRAFT

ENVIRONMENTAL Ongoing Confirmatory Structural Assessment




• 30 Foot Drop, CG Over Bottom Edge, Kinetic Energy History

PREDECISIONAL DRAFT

Ongoing Confirmatory Structural Assessment

- 30 Foot Drop, CG Over Edge, Door Deflections
 - 10 inch at Perimeter, ~36G
 - Additional 1.5 inch at Door Center
 - Door Gap Change ~1 inch



PREDECISIONAL DRAFT

Rev. 0, 08/14/2014


OFFICE OF

ENVIRONMENTAL

GEMENT


MANAGEMENTAL Ongoing Confirmatory Structural Assessment

- 30 Foot Drop, CG Over Edge, Bolt Loads
 - Most Bolts Still Fail
 - Failure Due to Inertial Loads from Contents



ENVIRONMENTAL Ongoing Confirmatory Structural Assessment

- 30 Foot Drop, CG Over Edge, LDCC
 - Localized LDCC Crush
 - 10% by Volume above 1000 psi Threshold in Impact Zone




Ongoing Confirmatory Structural Assessment

• 30 Foot Drop, Door Side Down

• Impact = 91G Load

OFFICE OF


- o 0.022 sec total impact duration, High G based on 0.015 sec
- Concrete Stress Nominally at 850 psi (107,500 lbs*91G/surf area)
 - FEA shows sparse locations above 1000 psi (less than 5%)
- Added Hardware Acts to Compress Door Into Container
 - No indicated bolt failures, no tension of many bolts
- Side Door Bending < 1 inch (Center to Edge)
- Total Crush of Absorbers = 6.6 inch (~50G)
 - ~70% compression of tube steel
- Melter Stress/Deflection Insignificant
 - Less than 1/10 inch differential, mostly on bottom
 - Stress < Yield



• 30 Foot Drop, Door Side Down, Deformed Shape

PREDECISIONAL DRAFT

Ongoing Confirmatory Structural Assessment



30 Foot Drop, Door Side Down, Kinetic Energy History

PREDECISIONAL DRAFT


Rev. 0, 08/14/2014

OFFICE OF

ENVIRONMENTAL

ENVIRONMENTAL Ongoing Confirmatory Structural Assessment

- 30 Foot Drop, Door Side Down, Deflections
 - 6.6 inch at Perimeter, ~54G
 - Additional 0.8 inch at Door Center
 - Essentially No Change in Door Gap




PREDECISIONAL DRAFT

OFFICE OF

MANAGEMENT Ongoing Confirmatory Structural Assessment

- 30 Foot Drop, Door Side Down, Bolts Loads
 - Bolts Remain Intact for Side Drop
 - Some Bolts see No Tension
 - Confirms no Door Gap Change




Rev. 0, 08/14/2014

OFFICE OF


MANAGEMENTAL Ongoing Confirmatory Structural Assessment

- 30 Foot Drop, Door Side Down, LDCC
 - Less than 5% Volume above 1000 psi in Impact Zone
 - FEA Results inline with G-value Based Stress Prediction



ENVIRONMENTAL Ongoing Confirmatory Structural Assessment

- 30 Foot Drop, Door Side Down, Contents
 - Melter Behaves as Rigid Unit
 - Differential Deflection < 1/10 inch, Elastic Only Behavior





Leak Rate Requirements per 10 CFR 71.51 for Type B packages specifies:

- "Normal Conditions of Transport," no loss or dispersal of radioactive contents as demonstrated to a sensitivity of 1E-06 A₂ per hour
- "Hypothetical Accident Conditions," no escape of other radioactive material exceeding a total amount A₂ in 1 week

PREDECISIONAL DRAFT

OFFICE OF ENVIRONMENTAL MANAGEMENT

Containment

Calculated HAC Releases

A ₂ s Released from Glass	A ₂ s
Spout Glass	2.5E-05
Melter Heel Glass	1.9E-05
Refractory Glass	2.0E-05
A ₂ s Released from LDCC	
LDCC content leached from Bartlett's	2.9E-06
LDCC content leached from Glass	7.9E-07
Nondispersed LDCC (sand)	9.3E-02
TOTAL	9.3E-02

Note: Some radioactive content conservatively double counted

HAC release less than 1A₂ in one week

PREDECISIONAL DRAFT

OFFICE OF ENVIRONMENTAL MANAGEMENT

Containment

Calculated NCT Releases

A ₂ s Released from Glass	A ₂ s
Spout Glass	8.3E-09
Melter Heel Glass	6.3E-09
Refractory Glass	6.7E-09
A ₂ s Released from LDCC	
LDCC content leached from Bartlett's	2.9E-07
LDCC content leached from Glass	1.6E-07
TOTAL	4.7E-07

Note: Some radioactive content conservatively double counted

NCT release less than 1E-06 A₂ per hour

Containment

STRATEGY:

OFFICE OF

- LaCrosse Special Authorization used as model for containment
- Containment system is the container made from SA-516, Grade 70 carbon steel in conjunction with LDCC external to melter
- Dispersible content includes glass internal to melter and LDCC both internal and external to melter
 - Glass is a low-dispersible waste form inside the melter
 - Internal to the melter, a fraction of radioactive glass content is assumed to have leached into LDCC
 - O Exterior surface contamination was fixed with 3 layers of Bartlett's PBS[™] with a fraction assumed to leach into LDCC external to the melter

Containment

RELEASE CALCULATIONS:

Releases calculated based on modified form of the DOE Handbook 3010-94, *Five Factor Formula for Airborne Releases*

Source Term = Material at Risk x Leak Path Factor x Damage Ratio x Respirable Fraction x Airborne Release Fraction

Material at Risk (MAR)

OFFICE OF

ENVIRONMENTAL

- \circ Glass from Heel, Spout, and Refractory content expressed in terms of A₂s
- LDCC with an assumed 25% of radionuclides leached from glass and Bartlett's PBS[™] expressed in terms of A₂s

Leak Path Factor (LPF)

• The LPF, based on handbook criteria, is 0.1 to escape melter, with an additional 0.1 to escape the combined LDCC external to melter and container

Note: Airborne Release Fractions used for contained LDCC already accounted for in LPF

PREDECISIONAL DRAFT

safety * performance * cleanup * closure

Containment

RELEASE FACTORS:

Damage Ratio (DR)

OFFICE OF

ENVIRONMENTAL

- Glass value based on previous testing of mechanical properties (i.e., broken glass fraction for NCT equals 0.01 vs 0.1 at HAC (Ref. BNWL-1903)
- LDCC values based on structural analysis (fraction of LDCC impacted) with additional conservatism applied (HAC external DR = 10%, internal LDCC DR = 1%; NCT external DR = 5%, internal = 1 %)

Respirable Fraction (RF)

• Value = 1: to calculate total A_2 s released (i.e., not limited to calculating only inhalation potential)



RELEASE FACTORS (continued):

Airborne Release Fraction (ARF)

- For the ARF, sub 20 micron inventory value used based on previous testing of mechanical properties
 - NCT fraction of 1E-06 vs. HAC fraction of 3E-04 (Ref. BNWL-1903)
- LDCC values based on testing on contained and uncontained pulverized fly-ash
 - NCT values of 1E-05 contained vs. HAC values of 5E-05 contained and 7.5E-03 uncontained (Ref. IAEA/INIS RN:37121627)

OFFICE OF

ENVIRONMENTAL



RELEASE FACTORS (continued):

Non-Release Fraction Differences between NCT and HAC

- Release for NCT includes only dispersible solids (since structural analyses shows negligible impact to WVMP under NCT)
- Modification to source term equation from DOE Handbook 3010-90 for HAC to include the contribution of "released sands" (i.e., other than airborne)