

Palo Verde / NRC Meeting Risk Informed Completion Times

February 17, 2015

DRAFT



Introductions

Bryan Thiele
Department Leader
Nuclear Engineering

DRAFT



Agenda

- Introduction Bryan Thiele
- Palo Verde Overview Tom Romay
- License Amendment Thomas Weber
- PRA Summary Everett DePue
- Implementation Plan Tom Romay
- Path Forward and Closing Comments Bryan Thiele

DRAFT



Desired Meeting Outcomes

- Summarize PVNGS design with focus on unique features
- Discuss license amendment content and variances from TSTF 505
- Provide overview of PRA models
- Discuss implementation plan
- Describe path forward

DRAFT



Palo Verde Design Overview

Tom Romay
Shift Manager
Senior Reactor Operator

DRAFT




Palo Verde Design Features

- Three identical, separate Units, minimal shared SSCs
- No pressurizer PORVs
- Low leakage RCP seals on loss of seal cooling
- Four channels of class instrumentation (two trains w/2 channels each)
- Four AC vital buses and DC buses
- Demonstrated capability to feed SG with no AC/DC power

DRAFT



RICT Timeline



DRAFT



License Amendment Request

Thomas Weber
Department Leader
Nuclear Regulatory Affairs

DRAFT



PVNGS LAR Content

- Based on TSTF 505-A & NEI 06-09-A
 - Scope includes components modeled in PRA
 - 25 LCOs
 - Mode 1 and 2 only
 - New TS Section 5.5 Program
 - Variances from TSTF 505 addressed in LAR and include:
 - RICT added to two LCOs not in TSTF 505
 - Miscellaneous variances described in LAR

DRAFT



TS 3.4.12, Pressurizer Vents

- NOT in TSTF 505 or NUREG 1432
- In PV Safety Analysis
- Modeled in PRA
- RICT added to Two Required Actions
 - Note added to preclude voluntary entry with with all pressurizer vent paths inoperable

DRAFT

TS 3.7.3, MFIVs

- Not in TSTF 505 but is in NUREG 1432
- LAR adds restoration action
- MFIVs modeled in PRA
- RICT added to Two Required Actions
 - Note added to preclude voluntary entry with both MFIVs in same flow path INOP

DRAFT



Miscellaneous Variances

- TS 3.7.2, MSIVs
 - Did not add RICT for some restoration conditions

- TS 3.7.4, ADV
 - Added note to preclude voluntary entry with all ADVs INOP

- TS 3.7.9, UHS
 - Added restoration condition
 - Added note to preclude voluntary entry

- TS 3.8.7, Inverters
 - Revised note since PVNGS Design has two inverters per train supporting 4 channels of vital instruments

DRAFT



Summary

- TSTF 439 in progress
- Minimizing other LARs at PVNGS that have changes to TSTF 505 LCOs
- Communicating with other Utilities
- Participating in Industry Committees
- Monitoring TSTF 505 RAIs

DRAFT



PRA Models

Everett DePue
Senior Engineer
PRA Lead for TSTF-505

DRAFT



Summary of PRA Models

- PRA models developed and peer reviewed
 - Internal events
 - Internal flood
 - Internal fire
 - Seismic
- RG 1.200 Rev. 2 hazards screened and peer reviewed
- Total CDF/LERF meet RG1.174 Rev. 2 limits
- Internal events and internal flood risk very low
- CDF/LERF dominated by internal fire and seismic hazards

DRAFT



Internal Events PRA

- Peer review by CEOG conducted in 1999
- Self-assessment performed against entire RA-Sa-2009 in 2015
- RA-Sa-2009 Supporting Requirements met to Capability Category II except:
 - Some sub-elements of SY-C1, SY-C2 System Notebook Documentation need completion
 - To be completed prior to RICT Program implementation

DRAFT



Internal Flood PRA

- Industry Peer Review conducted in 2010
- All ASME/ANS PRA requirements met to Capability Category II after peer review findings addressed

DRAFT



Internal Fire PRA

- PVNGS is not NFPA-805 plant,
 - Complies with methods in NUREG/CR-6850
- Industry Peer Review conducted in 2012
- Follow-up Industry Peer Review conducted in 2014 - addressed 2012 findings
- All ASME/ANS requirements met to Capability Category II after peer review findings addressed

DRAFT



Seismic PRA

- Industry peer review conducted in 2013
- All ASME/ANS requirements met to Capability Category II after peer review findings addressed except
 - SPR B7 Complementary Success Logic
 - Meets CC II for ASME/ANS RA-Sb-2013

DRAFT



Plant-Specific Modeling

- RICT CRMP model will be either:
 - Real time risk model as currently used for existing Technical Specification CRMP
 - OR
 - Pre-solved solutions (STP approach)

DRAFT



Plant Modifications

- PRA models rely on installation of modifications or taking compensatory measures
- RICT Program will not be implemented until modifications complete or compensatory measures in place
- FLEX strategies not yet reflected in the PRA models – conservatism

DRAFT



Implementation Plan

Tom Romay
Shift Manager
Senior Reactor Operator

DRAFT



Implementation Plan

- Engineering coordinate RICT implementation
- Cross organization team supporting implementation
- RICT implemented in Modes 1 and 2 only
- CRMP tool PRA Models will include Internal Events, Internal Flooding, Fire, and Seismic
- Procedure changes, training, and qualifications will support RICT CRMP capability
 - Extensive use of industry participation & benchmarking to develop program, procedures, training

DRAFT

Procedures

- Revise 40DP-9RS01, Operations Department Online Nuclear Risk Management Mode 1 and 2, to include RICT, RMAT, and RMA determinations
- New RICT Program Procedure

DRAFT



Training

- Licensed Operators
 - Hands-on training on RICT calculations
 - Classroom training to address how RICT impacts Station Operations
- Station Management
 - Affected managers trained on process, expectations, limitations
- Engineering, Work Management

DRAFT



Communications

- Industry peers via TSTF-505 task force
- Site-wide Articles at Station
 - While submittal under review
 - Once submittal is approved
- Leader Alignment Meetings
- Department All Hands Meetings

DRAFT



Credited Modifications

- DC ammeter circuits
- Non-class 1E DC motor circuits
- Replace RCP control cables with fire rated cables
- Install new permanently staged Steam Generator (SG) makeup pump that utilizes FLEX connections
- Breaker coordination on risk significant non-class 1E motor control centers/panels

DRAFT

Path Forward and Closing Comments

Bryan Thiele
Department Leader
Nuclear Engineering

DRAFT



Path Forward

- Address Fire PRA peer review comments
- Submit LAR in June
- Finalize scope and install modifications
- Complete procedures, software and training in parallel with NRC review
- Implement in late 2016

DRAFT





We SAFELY and efficiently generate electricity for the long term

DRAFT

