



UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D.C. 20555-0001

March 26, 2015

Mr. Peter M. Orphanos  
Site Vice President  
Nine Mile Point Nuclear Station  
348 Lake Road  
Oswego, NY 13126

SUBJECT: NINE MILE POINT NUCLEAR STATION, UNIT 1 - INTERIM STAFF  
EVALUATION RELATING TO OVERALL INTEGRATED PLAN IN  
RESPONSE TO PHASE 1 OF ORDER EA-13-109 (SEVERE ACCIDENT  
CAPABLE HARDENED VENTS) (TAC NO. MF4481)

Dear Mr. Orphanos:

By letter dated June 6, 2013, the U.S. Nuclear Regulatory Commission (NRC) issued Order EA-13-109, "Order to Modify Licenses with Regard to Reliable Hardened Containment Vents Capable of Operation Under Severe Accident Conditions" (Agencywide Documents Access and Management System (ADAMS) Accession No. ML13143A334). By letter dated June 27, 2014 (ADAMS Accession No. ML14184B340), Exelon Generation Company, LLC. (Exelon) submitted its Overall Integrated Plan (OIP) for Nine Mile Point Nuclear Station, Unit 2 (NMP1) in response to Phase 1 of Order EA-13-109. By letter dated December 16, 2014 (ADAMS Accession No. ML14356A192), Exelon submitted its first six-month status report for NMP1 in response to Order EA-13-109. Any changes to the compliance method described in the OIP will be reviewed as part of the ongoing audit process.

Exelon's OIP for NMP1 appears consistent with the guidance found in Nuclear Energy Institute 13-02, Revision 0, endorsed, in part, by the NRC's Japan Lessons-Learned Project Directorate (JLD) Interim Staff Guidance (ISG) JLD-ISG-2013-02, as an acceptable means for implementing the requirements of Phase 1 of Order EA-13-109. This conclusion is based on satisfactory resolution of the open items detailed in the enclosed Interim Staff Evaluation. This evaluation only addressed consistency with the guidance. Any plant modifications performed will need to be conducted in accordance with plant engineering change processes and consistent with the licensing basis.

P. Orphanos

- 2 -

If you have any questions, please contact Charles H. Norton, Project Manager, at 301-415-7818 or at [Charles.Norton@nrc.gov](mailto:Charles.Norton@nrc.gov).

Sincerely,

A handwritten signature in black ink that reads "Mandy K. Halter". The signature is written in a cursive, flowing style.

Mandy K. Halter, Acting Chief  
Orders Management Branch  
Japan Lessons-Learned Division  
Office of Nuclear Reactor Regulation

Docket No. 50-220

Enclosure:  
Interim Staff Evaluation

cc w/encl: Distribution via Listserv



UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D.C. 20555-0001

INTERIM STAFF EVALUATION  
BY THE OFFICE OF NUCLEAR REACTOR REGULATION  
RELATED TO ORDER EA-13-109 PHASE 1, MODIFYING LICENSES  
WITH REGARD TO RELIABLE HARDENED  
CONTAINMENT VENTS CAPABLE OF OPERATION UNDER  
SEVERE ACCIDENT CONDITIONS  
EXELON GENERATION COMPANY, LLC  
NINE MILE POINT NUCLEAR STATION, UNIT 1  
DOCKET NO. 50-220

1.0 INTRODUCTION

By letter dated June 6, 2013, the U.S. Nuclear Regulatory Commission (NRC, or Commission) issued Order EA-13-109, "Order Modifying Licenses with Regard to Reliable Hardened Containment Vents Capable of Operation under Severe Accident Conditions" [Reference 1]. The order requires licensees to implement its requirements in two phases. In Phase 1, licensees of boiling-water reactors (BWRs) with Mark I and Mark II containments shall design and install a venting system that provides venting capability from the wetwell during severe accident conditions. In Phase 2, licensees of BWRs with Mark I and Mark II containments shall design and install a venting system that provides venting capability from the drywell under severe accident conditions, or, alternatively, those licensees shall develop and implement a reliable containment venting strategy that makes it unlikely that a licensee would need to vent from the containment drywell during severe accident conditions.<sup>1</sup>

The purpose of the staff's review, as documented in this interim staff evaluation (ISE) is to provide an interim evaluation of the Overall Integrated Plan (OIP) for Phase 1 of Order EA-13-109. Phase 1 of Order EA-13-109 requires that BWRs with Mark I and Mark II containments design and install a severe accident capable hardened containment vent system (HCVS) that

---

<sup>1</sup> This ISE only addresses the licensee's plans for implementing Phase 1 of Order EA-13-109. While the licensee's OIP makes reference to Phase 2 issues, those issues are not being considered in this evaluation. Issues related to Phase 2 of Order EA-13-109 will be considered in a separate interim staff evaluation at a later date.

Enclosure

provides venting capability from the wetwell during severe accident conditions, using a vent path from the containment wetwell to remove decay heat, vent the containment atmosphere (including steam, hydrogen, carbon monoxide, non-condensable gases, aerosols, and fission products), and control containment pressure within acceptable limits. The HCVS shall be designed for those accident conditions (before and after core damage) for which containment venting is relied upon to reduce the probability of containment failure, including accident sequences that result in the loss of active containment heat removal capability or extended loss of alternating current (ac) power (ELAP).

By letter dated June 27, 2014 [Reference 2], Exelon Generation Company, LLC (Exelon, the licensee) provided the OIP for Nine Mile Point Nuclear Station, Unit 1 (NMP1) for compliance with Phase 1 of Order EA-13-109. The OIP describes the licensee's currently proposed modifications to systems, structures, and components, new and revised guidance, and strategies that it intends to implement in order to comply with the requirements Phase 1 of Order EA-13-109.

## 2.0 REGULATORY EVALUATION

Following the events at the Fukushima Dai-ichi nuclear power plant on March 11, 2011, the NRC established a senior-level agency task force referred to as the Near-Term Task Force (NTTF). The NTTF was tasked with conducting a systematic and methodical review of the NRC regulations and processes and determining if the agency should make improvements to these programs in light of the events at Fukushima Dai-ichi. As a result of this review, the NTTF developed a set of recommendations, documented in SECY-11-0093, "Near-Term Report and Recommendations for Agency Actions Following the Events in Japan," dated July 12, 2011 [Reference 3]. These recommendations were enhanced by the NRC staff following interactions with stakeholders. Documentation of the NRC staff's efforts is contained in the Commission's Staff Requirements Memorandum (SRM) SECY-11-0124, "Recommended Actions to be Taken without Delay from the Near-Term Task Force Report," dated September 9, 2011 [Reference 4] and SECY-11-0137, "Prioritization of Recommended Actions to be Taken in Response to Fukushima Lessons Learned," dated October 3, 2011 [Reference 5].

As directed by the Commission's SRM for SECY-11-0093 [Reference 6], the NRC staff reviewed the NTTF recommendations within the context of the NRC's existing regulatory framework and considered the various regulatory vehicles available to the NRC to implement the recommendations. SECY-11-0124 and SECY-11-0137 established the NRC staff's prioritization of the recommendations based upon the potential safety enhancements.

On February 17, 2012, the NRC staff provided SECY-12-0025, "Proposed Orders and Requests for Information in Response to Lessons Learned from Japan's March 11, 2011, Great Tohoku Earthquake and Tsunami" [Reference 7], to the Commission, including the proposed order to implement the installation of a reliable HCVS for Mark I and Mark II containments. As directed by SRM-SECY-12-0025 [Reference 8], the NRC staff issued Order EA-12-050, "Order Modifying Licenses with Regard to Reliable Hardened Containment Vents" [Reference 9], which requires licensees to install a reliable HCVS for Mark I and Mark II containments.

While developing the requirements for Order EA-12-050, the NRC acknowledged that questions remained about maintaining containment integrity and limiting the release of radioactive

materials if the venting systems were used during severe accident conditions. The NRC staff presented options to address these issues for Commission consideration in SECY-12-0157, "Consideration of Additional Requirements for Containment Venting Systems for Boiling Water Reactors with Mark I and Mark II Containments" [Reference 10]. In the SRM for SECY-12-0157 [Reference 11], the Commission directed the staff to issue a modification to Order EA-12-050, requiring licensees with Mark I and Mark II containments to "upgrade or replace the reliable hardened vents required by Order EA-12-050 with a containment venting system designed and installed to remain functional during severe accident conditions." The NRC staff held a series of public meetings following issuance of SRM SECY-12-0157 to engage stakeholders on revising the order. Accordingly, by letter dated June 6, 2013, the NRC issued Order EA-13-109, "Order Modifying Licenses with Regard to Reliable Hardened Containment Vents Capable of Performing under Severe Accident Conditions."

Order EA-13-109, Attachment 2 requires that BWRs with Mark I and Mark II containments shall have a reliable, severe accident capable HCVS. This requirement shall be implemented in two phases. In Phase 1, licensees of BWRs with Mark I and Mark II containments shall design and install a venting system that provides venting capability from the wetwell during severe accident conditions. Severe accident conditions include the elevated temperatures, pressures, radiation levels, and combustible gas concentrations, such as hydrogen and carbon monoxide, associated with accidents involving extensive core damage, including accidents involving a breach of the reactor vessel by molten core debris. In Phase 2, licensees of BWRs with Mark I and Mark II containments shall design and install a venting system that provides venting capability from the drywell under severe accident conditions, or, alternatively, those licensees shall develop and implement a reliable containment venting strategy that makes it unlikely that a licensee would need to vent from the containment drywell during severe accident conditions.

On November 12, 2013, the Nuclear Energy Institute (NEI) issued NEI 13-02, "Industry Guidance for Compliance with Order EA-13-109," Revision 0 [Reference 12] to provide guidance to assist nuclear power reactor licensees with the identification of measures needed to comply with the requirements of Phase 1 of the HCVS order. On November 14, 2013, the NRC staff issued Japan Lessons-Learned Project Directorate (JLD) interim staff guidance (ISG) JLD-ISG-2013-02, "Compliance with Order EA-13-109, 'Order Modifying Licenses with Regard to Reliable Hardened Containment Vents Capable of Performing under Severe Accident Conditions'" [Reference 13], endorsing, in part, NEI 13-02, Revision 0, as an acceptable means of meeting the requirements of Phase 1 of Order EA-13-109, and published a notice of its availability in the *Federal Register* (FR) [78 FR 70356]. Licensees are free to propose alternate methods for complying with the requirements of Phase 1 of Order EA-13-109.

By letter dated May, 27, 2014 [Reference 14], the NRC notified all BWR Mark I and Mark II Licensees that the staff will be conducting audits of the implementation of Order EA-13-109. This letter described the audit process to be used by the staff in its review of the information contained in licensee's submittals in response to Phase 1 of Order EA-13-109.

### 3.0 TECHNICAL EVALUATION

NMP1 is a General Electric BWR with a Mark I primary containment system. NMP1 is on a common site with Nine Mile Point Nuclear Station, Unit 2 (NMP2). To implement Phase I (HCVS) of Order EA-13-109, Exelon plans to use an existing penetration for the containment

vent and purge system up to the first containment isolation valve. New pipe will direct the HCVS effluent up through the reactor building roof in the northeast corner to a discharge point approximately 3 feet above the highest point on the reactor building roof. A newly installed control valve in the vent path will be used to control containment pressure during a beyond-design-basis external event (BDBEE) or severe accident.

### 3.1 GENERAL INTEGRATED PLAN ELEMENTS AND ASSUMPTIONS

#### 3.1.1 Evaluation of Extreme External Hazards

Extreme external hazards for NMP1 were evaluated in the NMP1 OIP in response to Order EA-12-049 (Mitigation Strategies) [Reference 15]. In the NMP1 ISE relating to Mitigation Strategies [Reference 16], NRC staff documented an analysis of Exelon's extreme external hazards evaluation. The following extreme external hazards screen in: Seismic, External Flooding, Tornado, Extreme Cold Temperature, Extreme High Temperature, and Ice/Snow. The following extreme external hazard screens out: Straight Wind. Based on NMP1 not excluding any external hazard from consideration, the NRC staff determined that Exelon appears to have identified the appropriate external hazards for consideration in the design of HCVS.

#### 3.1.2 Assumptions

On page 4 of the NMP1 OIP, Exelon adopted a set of generic assumptions associated with Order EA-13-109 Phase 1 actions.

The staff reviewed the NMP1 plant-specific HCVS related assumptions stated below:

- NMP1-1 EA-12-049 (FLEX) actions to restore power are sufficient to ensure continuous operation of non-dedicated containment instrumentation identified on page 15 of the OIP.
- NMP1-2 Modifications that allow a FLEX generator to be connected to a 600 volt safety related bus are assumed to have been installed such that a FLEX generator can be credited for HCVS operation beyond the initial 24 hour sustained operational period.

The staff determined that these plant specific assumptions for NMP1 do not appear to deviate from the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable method to implement the requirements of Order EA-13-109.

#### 3.1.3 Compliance Timeline and Deviations

Page 4 of the OIP states the following:

Compliance will be attained for Nine Mile Point Unit 1 (NMP1) with no known deviations to the guidelines in JLD-ISG-2013-02 and NEI 13-02 for each phase as follows:

- Phase 1 (wetwell): by the startup from the second refueling outage that begins after June 30, 2014, or June 30, 2018, whichever comes first. Currently scheduled for 2nd quarter 2017.
- Phase 2: by the startup from first refueling outage that begins after June 30, 2017, or June 30, 2019, whichever comes first. Currently scheduled for 2nd quarter 2019.

If deviations are identified at a later date, then the deviations will be communicated in a future 6 month update following identification.

NMP1's implementation schedule appears to be in accordance with the requirements of the order without deviation. Regarding other deviations, neither Exelon nor the NRC staff identified any at this time. Therefore, the staff concludes that it appears NMP1 will attain compliance with Phase 1 of Order EA-13-109 with no known deviations from the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 an acceptable means for implementing applicable requirements of Order EA-13-109.

#### Summary, Section 3.1:

The licensee's described approach to General Integrated Plan Elements and Assumptions, if implemented as described in Section 3.1, and assuming acceptable resolution of any open items identified here or as a result of licensee alterations to their proposed plans, appears to be consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109.

### 3.2 BOUNDARY CONDITIONS FOR WETWELL VENT

#### 3.2.1 Sequence of Events (SOE)

Order EA-13-109, Sections 1.1.1, 1.1.2, and 1.1.3, state that:

- 1.1.1 The HCVS shall be designed to minimize the reliance on operator actions.
- 1.1.2 The HCVS shall be designed to minimize plant operators' exposure to occupational hazards, such as extreme heat stress, while operating the HCVS system.
- 1.1.3 The HCVS shall also be designed to account for radiological conditions that would impede personnel actions needed for event response.

Page 7 of the OIP states the following:

The operation of the HCVS will be designed to minimize the reliance on operator action in response to hazards listed in Part 1 [of the OIP]. Immediate operator actions will be completed by trained plant personnel and will include the

capability for remote-manual initiation from the HCVS control station. A list of the remote manual actions performed by plant personnel to open the HCVS vent path can be found in the following table (2-1 [of the OIP]). A HCVS Extended Loss of AC Power (ELAP) Failure Evaluation table, which shows alternate actions that can be performed, is included in Attachment 4 [of the OIP].

NRC staff reviewed the Remote Manual Actions (Table 2-1 of the OIP) and concluded that these actions appear to consider minimizing the reliance on operator actions. The actions appear consistent with the types of actions described in the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. NRC staff reviewed the Wetwell HCVS Failure Evaluation Table (Attachment 4 of the OIP) and determined the actions described appear to adequately address all the failure modes listed in the guidance provided by NEI 13-02, which include: loss of normal ac power, long term loss of batteries, loss of normal pneumatic supply, loss of alternate pneumatic supply, and solenoid operated valve failure.

The staff reviewed the three cases contained in the SOE timeline [Attachment 2 of the OIP] and determined that the three cases appropriately bound the conditions for which the HCVS is required. These cases include: successful FLEX implementation with no failure of the isolation condensers (ICs); late failure of ICs leading to core damage; and failure of the ICs at the start of the event. The timelines accurately reflect the progression of events, as described in the NMP1 FLEX OIP [Reference 17], SECY-12-0157 [Reference 10], and State-of-the-Art Reactor Consequence Analyses (SOARCA) [Reference 18].

The NRC staff reviewed the licensee discussion of time constraints on page 8 of the OIP and confirmed that the time constraints identified appear to be appropriately derived from the time lines developed in Attachment 2 of the OIP, consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. The time constraints establish when the HCVS must be initiated and when supplemental compressed gas for motive power and supplemental electrical power (FLEX) must be supplied. The licensee identified the need to ensure the HCVS batteries as sized correctly and incorporated into the FLEX diesel generator (DG) loading calculation.

The NRC staff reviewed the discussion of radiological and temperature constraints on page 9 of the OIP and determined that Exelon considers radiological and temperature conditions at the locations identified to date where manual actions are necessary to operate HCVS. Specific evaluations of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and equipment outside the MCR are not available at this time; therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.

Open Item: Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.



### 3.2.2 Vent Characteristics

#### 3.2.2.1 Vent Size and Basis

Order EA-13-109, Section 1.2.1 states that:

- 1.2.1 The HCVS shall have the capacity to vent the steam/energy equivalent of one (1) percent of licensed/rated thermal power (unless a lower value is justified by analyses), and be able to restore and then maintain containment pressure below the primary containment design pressure and the primary containment pressure limit.

Page 11 of the OIP states the following:

The HCVS wetwell path is designed for venting steam/energy at a minimum capacity of 1% of 1850 MW [Megawatt] thermal power at pressure of 35 psig (Open Item #2 [in the OIP]). This pressure is the lower of the containment design pressure (62 psig) and the PCPL [primary containment pressure limit] value (35 psig). The preliminary size of the wetwell vent piping for the HCVS is  $\geq 10$  inches in diameter which provides adequate capacity to meet or exceed the Order criteria.

The NMP1 OIP describes installation of a new vent sized to meet or exceed 1 percent or greater current licensed thermal power. The licensee has identified an open item to perform a final vent path calculation for the HCVS piping confirming 1 percent minimum capacity. In addition to the licensee identified open item, an analysis that demonstrates that the suppression pool and the HCVS together are able to absorb and reject decay heat, such that following a reactor shutdown from full power containment pressure is restored and then maintained below the primary containment design pressure and the primary containment pressure limit is not available at this time; therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit analyses demonstrating that HCVS has the capacity to vent the steam/energy equivalent of one percent of licensed/rated thermal power (unless a lower value is justified), and that the suppression pool and the HCVS together are able to absorb and reject decay heat, such that following a reactor shutdown from full power containment pressure is restored and then maintained below the primary containment design pressure and the primary containment pressure limit.

#### 3.2.2.2 Vent Capacity

Order EA-13-109, Section 1.2.1 states that:

- 1.2.1 The HCVS shall have the capacity to vent the steam/energy equivalent of one (1) percent of licensed/rated thermal power (unless a lower value is justified by analyses), and be able to restore and then maintain containment pressure below the primary containment design pressure and the primary containment pressure limit.

Page 11 of the OIP states the following:

The 1% value at NMP1 assumes that the Torus has sufficient capacity to absorb the decay heat generated for a minimum of 3 hours without allowing containment pressure to exceed 43 psig (PCPL) after which point decay heat is less than or equal to 1%. The vent would then be able to prevent containment pressure from increasing above the PCPL. The duration of Torus decay heat absorption capability has been confirmed (Reference 30 [of the OIP]).

The NMP1 OIP assumes that until decay heat is less than or equal to 1 percent, the torus must absorb the decay heat generated and prevent containment pressure from increasing above the containment design pressure until the 1 percent containment vent is able to restore and maintain primary containment pressure below the primary containment design pressure and the primary containment pressure limit. Design analysis confirming the suppression pool has the capacity to absorb the decay heat generated until the decay heat rate within HCVS capacity is not available at this time; therefore the staff has not completed its review.

Open Item: Make available for NRC staff audit analyses demonstrating that HCVS has the capacity to vent the steam/energy equivalent of one percent of licensed/rated thermal power (unless a lower value is justified), and that the suppression pool and the HCVS together are able to absorb and reject decay heat, such that following a reactor shutdown from full power containment pressure is restored and then maintained below the primary containment design pressure and the primary containment pressure limit.

### 3.2.2.3 Vent Path and Discharge

Order EA-13-109, Sections 1.1.4 and 1.2.2 state that:

- 1.1.4 The HCVS controls and indications shall be accessible and functional under a range of plant conditions, including severe accident conditions, extended loss of AC power, and inadequate containment cooling.
- 1.2.2 The HCVS shall discharge the effluent to a release point above main plant structures.

Page 11 of the OIP states the following:

The HCVS vent path at NMP1 utilizes the existing penetration piping for the Containment Vent and Purge System from the Torus up to the first Primary Containment Isolation Valve, VLV-201-16. The torus (wetwell) vent piping tees off from the existing penetration piping described above. The dedicated HCVS piping then continues up through the Reactor Building and exits the Reactor Building roof in the northeast corner to a discharge point approximately 3' above the highest point of the Reactor Building roof or any nearby structure.

A new air-operated HCVS control valve will be provided in this piping, which will serve as both the primary method to control HCVS flow, therefore controlling containment pressure, and as a secondary containment isolation valve, as required by the design basis. The NMP1 vent path is completely separate from the Nine Mile Point Unit 2 (NMP2) vent path.

The NMP1 OIP describes the routing and discharge point of the HCVS that appear consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Design details not available at this time include: the seismic and tornado missile final design criteria for the HCVS stack, descriptions of the environmental and radiological effects on HCVS controls and indications, and documentation of an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment; therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit the seismic and tornado missile final design criteria for the HCVS stack.

Open Item: Make available for NRC staff audit the descriptions of local conditions (temperature, radiation and humidity) anticipated during ELAP and severe accident for the components (valves, instrumentation, sensors, transmitters, indicators, electronics, control devices, and etc.) required for HCVS venting including confirmation that the components are capable of performing their functions during ELAP and severe accident conditions.

Open Item: Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.

#### 3.2.2.4 Power and Pneumatic Supply Sources

Order EA-13-109, Sections 1.2.5 and 1.2.6 state that:

1.2.5 The HCVS shall, in addition to meeting the requirements of 1.2.4, be capable of manual operation (e.g., reach-rod with hand wheel or manual operation of pneumatic supply valves from a shielded location), which is accessible to plant operators during sustained operations.

1.2.6 The HCVS shall be capable of operating with dedicated and permanently installed equipment for at least 24 hours following the loss of normal power or loss of normal pneumatic supplies to air operated components during an extended loss of ac power.

Page 12 of the OIP states the following:

All electrical power required for operation of HCVS components will be provided by dedicated HCVS batteries with a minimum capacity capable of providing power for 24 hours without recharging. A preliminary sizing evaluation has been completed. A final confirmatory evaluation will be completed as part of the detailed design process when selection of electrical components is finalized (Ref Open Item #1 [of the OIP]). A battery charger is provided that requires a 240 VAC supply. This will be provided by a dedicated 600 VAC to 120/240 VAC transformer, which will be powered from a 600 VAC bus that will be re-powered by a diesel generator as part of the FLEX response. In addition, a connection point that utilizes standard electrical connections will be provided for a portable generator for sustained operation of the HCVS.

For the first 24 hours following the event, the motive supply for the AOVs will be dedicated nitrogen gas bottles that will be permanently installed and available. These bottles will be sized such that they can provide motive force for 12 cycles (open/close) of vent path operation (2 Primary Containment Isolation Valves (PCIVs) and 1 Pressure Control Valve (PCV)). A preliminary sizing evaluation has been completed. A final evaluation will be completed as part of the detailed design process when selection of the system AOVs is finalized (Open Item #3 [of the OIP]).

...Supplemental motive force (e.g., additional nitrogen gas bottles, air compressor), portable generators, and enough fuel for an additional 48 hours of operation will be stored on site in an area that is reasonably protected from assumed hazards consistent with the requirements of NEI 12-06. Pre-engineered quick disconnects will be provided to connect the supplemental motive force supply.

1. The HCVS flow path valves are air-operated valves (AOV) that are air-to-open and spring-to-shut. Opening the valves requires energizing a DC [direct current] powered solenoid operated valve (SOV) and providing motive air/gas. A backup means of operation is also available that does not require energizing or repositioning the SOV.
2. An assessment of temperature and radiological conditions will be performed to ensure operating personnel can safely access and operate controls at the ROS [remote operating station] based on time constraints listed in Attachment 2. (Open Item #4 [of the OIP])...
3. ...All permanently installed HCVS equipment, including any connections required to supplement the HCVS operation during an ELAP (electric power, N<sub>2</sub>/air) will be located in areas reasonably protected from the hazards listed in Part 1 of this report [the OIP].
4. All valves required to open the flow path will be designed for remote manual operation following an ELAP, such that the primary means of valve

manipulation does not rely on use of a handwheel, reach-rod, or similar means requiring close proximity to the valve (HCVS-FAQ [frequently asked question]-03, Reference 14 [of the OIP]). Any supplemental connections will be pre-engineered to minimize man-power resources and address environmental concerns. Required portable equipment will be reasonably protected from screened in hazards listed in Part 1 of this OIP.

5. Access to the locations described above will not require temporary ladders or scaffolding.

The NMP1 OIP contains system feature descriptions that appear to make the system reliable consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. The licensee identifies the need to perform the final sizing evaluation for HCVS pneumatic supply. Other design details not available at this time include the final sizing for HCVS battery/battery charger including documentation of incorporating HCVS electrical sources into the FLEX DG loading calculations and documentation of an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment; therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit documentation of the HCVS nitrogen pneumatic system design including sizing and location.

Open Item: Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.

Open Item: Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.

#### 3.2.2.5 Location of Control Panels

Order EA-13-109, Sections 1.1.1, 1.1.2, 1.1.3, 1.1.4, 1.2.4, and 1.2.5 state that:

- 1.1.1 The HCVS shall be designed to minimize the reliance on operator actions
- 1.1.2 The HCVS shall be designed to minimize plant operators' exposure to occupational hazards, such as extreme heat stress, while operating the HCVS system
- 1.1.3 The HCVS shall also be designed to account for radiological conditions that would impede personnel actions needed for event response
- 1.1.4 The HCVS controls and indications shall be accessible and functional under a range of plant conditions, including severe accident conditions, extended loss of AC power, and inadequate containment cooling.

- 1.2.4 The HCVS shall be designed to be manually operated during sustained operations from a control panel located in the main control room or a remote but readily accessible location.
- 1.2.5 The HCVS shall, in addition to meeting the requirements of 1.2.4, be capable of manual operation (e.g., reach-rod with hand wheel or manual operation of pneumatic supply valves from a shielded location), which is accessible to plant operators during sustained operations.

Page 13 of the OIP states the following:

The HCVS design allows for initiation, operation, and monitoring of the HCVS from either the MCR [main control room] or the ROS. The MCR location is protected from adverse natural phenomena and is the normal control point for HCVS operation and Plant Emergency Response actions.

The ROS will be located on the north wall west in the Turbine Building. This location is protected from adverse natural phenomena, is readily accessible, well ventilated and is shielded from the HCVS piping by the Reactor Building. The NMP1 Turbine Building was designed to seismic loads in accordance with the building code and is considered seismically robust.

The NMP1 OIP describes HCVS control locations that appear to be consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Specific design details not available at this time include: documentation demonstrating adequate communication between remote HCVS operation locations and HCVS operational decision makers, evaluations of the environmental and radiological effects on HCVS controls and indications and an evaluation of environmental and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment; therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit documentation that demonstrates adequate communication between the remote HCVS operation locations and HCVS decision makers during ELAP and severe accident conditions.

Open Item: Make available for NRC staff audit the descriptions of local conditions (temperature, radiation and humidity) anticipated during ELAP and severe accident for the components (valves, instrumentation, sensors, transmitters, indicators, electronics, control devices, and etc.) required for HCVS venting including confirmation that the components are capable of performing their functions during ELAP and severe accident conditions.

Open Item: Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.

### 3.2.2.6 Hydrogen

Order EA-13-109, Sections 1.2.10, 1.2.11, and 1.2.12 state that:

- 1.2.10 The HCVS shall be designed to withstand and remain functional during severe accident conditions, including containment pressure, temperature, and radiation while venting steam, hydrogen, and other non-condensable gases and aerosols. The design is not required to exceed the current capability of the limiting containment components.
- 1.2.11 The HCVS shall be designed and operated to ensure the flammability limits of gases passing through the system are not reached; otherwise, the system shall be designed to withstand dynamic loading resulting from hydrogen deflagration and detonation.
- 1.2.12 The HCVS shall be designed to minimize the potential for hydrogen gas migration and ingress into the reactor building or other buildings.

Page 13 of the OIP states the following:

As is required by EA-13-109, Section 1.2.11, the HCVS must be designed such that it is able to either provide assurance that a combustible mixture of gas is not credible or it must be able to accommodate the dynamic loading resulting from a combustible gas detonation. Piping upstream of the HCVS control valve will be protected by preventing the mix of oxygen with flammable gases. Several methods are available to protect piping downstream of the HCVS control valve. Methods being considered include installation of a purge system, installation of a flow-check valve near the end of the piping, designing the piping and HCVS control valve for gas detonation loading or utilize other design principles to preclude detonation. Final determination of the method to be used for the HCVS control valve and downstream piping is Open Item #5 [in the OIP]. NMP1 intends to follow the guidance in HCVS-WP-03, Hydrogen/CO Control Measures (Reference 23 [of the OIP]).

A description of the final design of the HCVS to address hydrogen detonation and deflagration (licensee identified) and a description of the strategies for hydrogen control that minimizes the potential for hydrogen gas migration and ingress into the reactor building or other buildings are not available at this time; therefore, the staff has not completed its review.

Open Item: Provide a description of the final design of the HCVS to address hydrogen detonation and deflagration.

Open Item: Provide a description of the strategies for hydrogen control that minimizes the potential for hydrogen gas migration and ingress into the reactor building or other buildings.

### 3.2.2.7 Unintended Cross Flow of Vented Fluids

Order EA-13-109, Sections 1.2.3 and 1.2.12 state that:

- 1.2.3 The HCVS shall include design features to minimize unintended cross flow of vented fluids within a unit and between units on the site.
- 1.2.12 The HCVS shall be designed to minimize the potential for hydrogen gas migration and ingress into the reactor building or other buildings.

Page 13 of the OIP states the following:

The HCVS for NMP1 is fully independent of NMP2 with separate discharge points. Therefore, the capacity at each unit is independent of the status of the other unit's HCVS. The only interfacing system with the NMP1 HCVS is the short section of primary containment penetration piping upstream of the Containment Vent and Purge System inboard PCIV. This valve is normally closed, except during infrequent vent and purge operations, and fails closed upon loss of electrical power, instrument air and upon a containment isolation signal. This valve is leak tight and tested in accordance with the 10CFR50 Appendix J program. This valve is safety related and fully qualified in accordance with the Environmental Qualification (EQ) Program for NMP1. There are no additional interface systems for the proposed HCVS for the NMP1 wetwell vent.

The NMP1 OIP describes design features to minimize unintended cross flow of vented fluids that appear consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109.

### 3.2.2.8 Prevention of Inadvertent Actuation

Order EA-13-109, Section 1.2.7 states that:

- 1.2.7 The HCVS shall include means to prevent inadvertent actuation.

Page 13 of the OIP states the following:

EOPs [emergency operating procedure] /Emergency Response Guidelines provide clear guidance that the HCVS is not to be used to defeat containment integrity during any design basis transients and accidents. In addition, the HCVS is designed to provide features that prevent inadvertent HCVS flow path actuation due to a design error, equipment malfunction, or operator error. These design features include two normally closed/fail closed, in-series PCIVs that are air-to-open and spring-to-shut. A DC SOV must be energized to allow the motive air to open the valve. Although the same DC and motive air source will be used for each valve, separate control circuits including key-locked switches will be used for the two redundant valves to address single point vulnerabilities that may cause the flow path to inadvertently open. Power to the DC SOVs will be



maintained de-energized and the key-lock switch will be required to be actuated to power the solenoids. Manual valves on the pneumatic supply from the nitrogen tanks will be locked in their normal position to maintain the valve closed.

The NMP1 OIP provides a description of methods to prevent inadvertent HCVS initiation that includes: key lock switches, valves in series that are air-to-open spring-to-shut and procedural guidance. This appears to be consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109.

### 3.2.2.9 Component Qualifications

Order EA-13-109, Section 2.1 states that:

- 2.1 The HCVS vent path up to and including the second containment isolation barrier shall be designed consistent with the design basis of the plant. Items in this path include piping, piping supports, containment isolation valves, containment isolation valve actuators and containment isolation valve position indication components.

Page 14 of the OIP states the following:

The HCVS components downstream of the second containment isolation valve are located in seismically designed and constructed structures, including the ROS, pneumatic supply station, HCVS batteries, and HCVS battery charger.

HCVS components that directly interface with the primary containment pressure boundary and the HCVS control valve will be classified as safety-related in accordance with the design basis for NMP1. Likewise, any electrical or controls component which interfaces with Class I E power sources will be classified as safety related up to applicable isolation devices (e.g., fuses, breakers), as their failure could adversely impact containment isolation and/or a safety-related power source. All safety-related components will be seismically and environmentally qualified in accordance with the design basis of the plant. Additional functionality evaluations for severe accident/boundary conditions specified in NEI 13-02 will be performed.

Interfacing HCVS components will be classified as augmented quality.

Qualification includes consideration of environmental conditions specified in NEI 13-02. HCVS components will be evaluated to ensure functionality following a design basis earthquake. Components that interface with the HCVS will be routed in seismically qualified structures or the structure will be analyzed for seismic ruggedness to ensure that any potential failure would not adversely impact the function of the HCVS or other safety related structures or components.

Instrumentation and controls components will also be evaluated for

environmental conditions postulated for a severe accident, although these evaluations will not be considered part of the site Environmental Qualification (EQ) program.

HCVS instrumentation performance (e.g., accuracy and precision) need not exceed that of similar plant installed equipment. Radiation monitoring equipment accuracy will be sufficient to confirm flow of radionuclides through the HCVS.

The HCVS instruments, including valve position indication, process instrumentation, radiation monitoring, and support system monitoring, will be qualified by using one or more of the three methods described in the ISG, which includes:

1. Purchase of instruments and supporting components with known operating principles from manufacturers with commercial quality assurance programs (e.g., ISO9001) where the procurement specifications include the applicable seismic requirements, design requirements, and applicable testing.
2. Demonstration of seismic reliability via methods that predict performance described in IEEE [Institute of Electrical and Electronics Engineers] 344-2004 (Reference 28 [of the OIP]).
3. Demonstration that instrumentation is substantially similar to the design of instrumentation previously qualified.

Instrument	Qualification Method*
HCVS process Temperature	ISO9001/IEEE 344-2004 / Demonstration
HCVS process Pressure	ISO9001/IEEE 344-2004 / Demonstration
HCVS process Radiation Monitor	ISO9001/IEEE 344-2004 / Demonstration
HCVS process Valve Position	ISO9001/IEEE 344-2004 / Demonstration
HCVS Pneumatic Supply Pressure	ISO9001/IEEE 344-2004 / Demonstration
HCVS Electrical Power Supply Availability	ISO9001/IEEE 344-2004 / Demonstration

\*The specific qualification method(s) used for each required HCVS instrument will be reported in future 6 month status reports

The NMP1 OIP describes component qualification methods that appear to be consistent with the design-basis of the plant and the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. The licensee identified the need to complete an evaluation for environmental and seismic qualifications of HCVS components [Attachment 7 of the OIP]. Documentation of an evaluation verifying the existing containment isolation valves, relied upon for the HCVS, will open under ELAP and severe accident conditions is not available at this time; therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit documentation of seismic qualification evaluation of HCVS components.

Open Item: Make available for NRC staff audit the descriptions of local conditions (temperature, radiation and humidity) anticipated during ELAP and severe accident for the components (valves, instrumentation, sensors, transmitters, indicators, electronics, control devices, and etc.) required for HCVS venting including confirmation that the components are capable of performing their functions during ELAP and severe accident conditions.

### 3.2.2.10 Monitoring of HCVS

Order EA-13-109, Sections 1.1.4, 1.2.8, and 1.2.9, state that:

- 1.1.4 The HCVS controls and indications shall be accessible and functional under a range of plant conditions, including severe accident conditions, extended loss of AC power, and inadequate containment cooling.
- 1.2.8 The HCVS shall include means to monitor the status of the vent system (e.g., valve position indication) from control panel required by 1.2.4. The monitoring system shall be designed for sustained operation during an extended loss of AC power.
- 1.2.9 The HCVS shall include a means to monitor the effluent discharge for radioactivity that may be released from operation of the HCVS. The monitoring system shall provide indication from the control panel required by 1.2.4 and shall be designed for sustained operation during an extended loss of AC power.

Page 15 of the OIP states the following:

The NMP1 wetwell HCVS will be capable of being manually operated during sustained operations from a control panel located in the MCR and will meet the requirements of Order element 1.2.4. The MCR is a readily accessible location with no further evaluation required. MCR dose associated with HCVS operation conforms to GDC [General Design Criteria] 19/Alternate Source Term (AST) for radiation shielding considerations (HCVS-FAQ-01, Reference 12 [of the OIP]). Additionally, to meet the intent for a secondary control location of section 1.2.5 of the Order, a readily accessible ROS will also be incorporated into the HCVS design as described in NEI 13-02 section 4.2.2.1.2.1. The controls at the ROS location will be accessible and functional under a range of plant conditions, including severe accident conditions with due consideration to source term and dose impact on operator exposure, extended loss of AC power (ELAP), and inadequate containment cooling.

The wetwell HCVS will include indications for HCVS valve position, vent pipe pressure, temperature, and effluent radiation levels to aid operator verification of HCVS function. Other important information on the status of supporting systems, such as power source status and pneumatic supply pressure, will also be included in the design and located to support HCVS operation. This instrumentation will be powered from the dedicated HCVS batteries, which

provide a minimum of 24-hour supply.

Other instrumentation that supports HCVS function will be provided nearby in the MCR. This includes existing containment pressure and wetwell level indication. This instrumentation is not required to validate HCVS function and is therefore not powered from the dedicated HCVS batteries. However, these instruments are expected to be available since the FLEX DG that supports HCVS battery charger function after 24 hours also supplies the station battery charger for these instruments and will be installed prior to depletion of the station batteries (Reference 1 [of the OIP]).

The HCVS instruments, including valve position indication, process instrumentation, radiation monitoring, and support system monitoring, will be qualified as previously described.

The NMP1 OIP provides a description of HCVS monitoring and control that appears to be consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Design details not available at this time include: descriptions of all instrumentation and controls (existing and planned) including qualification methods, evaluations of the environmental and radiological effects on HCVS controls and indications, and an evaluation of environmental and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment; therefore, the staff has not completed its review.

- Open Item: Make available for NRC staff audit descriptions of all instrumentation and controls (existing and planned) necessary to implement this order including qualification methods.
- Open Item: Make available for NRC staff audit the descriptions of local conditions (temperature, radiation and humidity) anticipated during ELAP and severe accident for the components (valves, instrumentation, sensors, transmitters, indicators, electronics, control devices, and etc.) required for HCVS venting including confirmation that the components are capable of performing their functions during ELAP and severe accident conditions.
- Open Item: Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.

### 3.2.2.11 Component Reliable and Rugged Performance

Order EA-13-109, Section 2.2 states that:

- 2.2 All other HCVS components shall be designed for reliable and rugged performance that is capable of ensuring HCVS functionality following a seismic event. These items include electrical power supply, valve actuator pneumatic supply and instrumentation (local and remote) components.

Page 16 of the OIP states the following:

The HCVS vent path components that directly interface with the containment pressure boundary and the HCVS control valve and downstream piping will be classified as safety-related in accordance with the design basis for the plant. In addition, any electrical or controls component which interfaces with Class 1 E power sources will be classified as safety related, as their failure could adversely impact containment isolation and/or a safety related power source. All safety-related components will be seismically qualified in accordance with the NMPI design basis. All other HCVS components, including piping and supports, electrical power supply, valve actuator pneumatic supply, and instrumentation (local and remote) will be designed for reliable and rugged operational performance that is capable of ensuring HCVS functionality following a design basis earthquake as required per Section 2.2 of EA-13-109.

For the HCVS instruments that are required after a potential seismic event, the following methods will be used to verify that the design and installation is reliable / rugged and therefore capable of ensuring HCVS functionality following a seismic event. Applicable instruments are rated by the manufacturer (or otherwise tested) for seismic impact at levels commensurate with those of postulated severe accident event conditions in the area of instrument component use using one or more of the following methods:

- demonstration of seismic motion consistent with that of existing design basis loads at the installed location.
- substantial history of operational reliability in environments with significant vibration with a design envelope inclusive of the effects of seismic motion imparted to the instruments proposed at the location.
- adequacy of seismic design and installation is demonstrated based on the guidance in Sections 7, 8, 9, and 10 of IEEE Standard 344-2004, *IEEE Recommended Practice for Seismic Qualification of Class 1E Equipment for Nuclear Power Generating Stations* (Reference 28 [of the OIP]), or a substantially similar industrial standard.
- demonstration that proposed devices are substantially similar in design to models that have been previously tested for seismic effects in excess of the plant design basis at the location where the instrument is to be installed (g-levels and frequency ranges)

- seismic qualification using seismic motion consistent with that of existing design basis loading at the installation location.

HCVS components are located in the Reactor Building and Turbine Building. The Reactor Building and Control Building are safety-related, seismic class 1 structures. The Turbine Building is seismically designed in accordance with the plant design basis and will be evaluated for the external hazards, that screen in for the plant as defined in guidance NEI 12-06 endorsed by JLD-ISG-12-01 for Order EA-12-049.

The instrumentation/power supplies/cables/connections (components) will be qualified for temperature, pressure, radiation level, and total integrated radiation dose up to 7 days for the Effluent Vent Pipe and HCVS ROS location. The qualification for the equipment by the supplier will be validated by NMP for the specific location at NMP1 to ensure that the bounding conditions envelope the specific plant conditions.

Conduit design will be in accordance with Seismic Class 1 criteria. Both existing and new barriers (if required) will be used to provide a level of protection from missiles when equipment is located outside of seismically qualified structures.

Augmented quality requirements will be applied to the components installed in response to this Order unless higher quality requirements apply.

The NMP1 OIP provides descriptions for component reliable and rugged performance that appear to be consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109.

### 3.2.3 Beyond-Design-Basis External Event Venting

#### 3.2.3.1 First 24-Hour Coping

Order EA-13-109, Section 1.2.6 states that:

- 1.2.6 The HCVS shall be capable of operating with dedicated and permanently installed equipment for at least 24 hours following the loss of normal power or loss of normal pneumatic supplies to air operated components during an extended loss of AC power.

Page 18 Of the OIP states the following:

The operation of the HCVS will be designed to minimize reliance on operator actions for response to an ELAP and severe accident events. Immediate operator actions will be completed by qualified plant personnel from either the MCR or the HCVS ROS using remote-manual actions. The operator actions required to open a vent path are as described in Table 2-1. Remote-manual is defined in this report as a non-automatic power operation of a component and does not require the operator to be at or in close proximity to the component. No other operator actions are required to initiate venting.

The HCVS will be designed to allow initiation, control, and monitoring of venting from the MCR and will be able to be operated from an installed ROS as part of the response to this Order. Both locations minimize plant operators' exposure to adverse temperature and radiological conditions and are protected from hazards assumed in Part 1 of this report [the OIP].

Permanently installed electrical power and motive air/gas capability will be available to support operation and monitoring of the HCVS for 24 hours. Power will be provided by installed batteries for up to 24 hours before generators will be required to be functional.

*System control:*

- i. Active: The HCVS PCIVs and HCVS control valve are operated in accordance with EOPs/SAPs [severe accident procedures] to control containment pressure. The HCVS is designed for a minimum of 12 open/close cycles of the vent path under ELAP conditions over the first 24 hours. Controlled venting will be permitted in the revised EOPs.
- ii. Passive: Inadvertent actuation protection is provided by use of key-locked switches for both the HCVS power supply actuation and valve operation. The normal state of the system is de-energized and isolated.

The NMP1 OIP describes a first 24 hour BDBEE coping strategy that appears to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Design details not available at this time include the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation and the final nitrogen pneumatic system design including sizing and location; therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.

Open Item: Make available for NRC staff audit documentation of the HCVS nitrogen pneumatic system design including sizing and location.

### 3.2.3.2 Greater Than 24-Hour Coping

Order EA-13-109, Section 1.2.4 states that:

1.2.4 The HCVS shall be designed to be manually operated during sustained operations from a control panel located in the main control room or a remote but readily accessible location.

Page 18 of the OIP states the following:

Actions required to extend venting beyond 24 hours include replenishment of pneumatic supplies and replenishment of electrical supply.

The pneumatic supply station will be installed in the Turbine Building and will include a nitrogen bottle station with additional connections for extra nitrogen bottles and/or connection of a portable air compressor. Connections will utilize pre-engineered quick disconnect fittings. The location of the pneumatic supply station will be evaluated for reasonable protection per Part 1 of this OIP and modified as required for compliance. Actions to replenish the pneumatic supplies include replacement of nitrogen bottles or installation and refueling of a portable air compressor. Sufficient nitrogen bottles will be staged to support operations for an additional 48 hours beyond the initial 24 hour coping period following the ELAP event.

The HCVS batteries and battery charger will also be installed in the Turbine Building. This will include battery capacity sufficient for 24 hour operation. The normal power supply to the HCVS controls and instruments will be provided by the #12 Station Battery Bus, which in turn is re-powered by a 600 VAC diesel generator connected to the #12 Station Battery Charger as part of the FLEX response. A design change to install portable generator connections to this bus is being completed in support of EA-12-049 (Reference 1 [of the OIP]). In the event that power is not restored to the bus, a local 240 VAC connection to the UPS [uninterrupted power supply] will allow the UPS to receive power from a small portable generator. Actions to replenish the electrical supply include refueling the DG or connecting and refueling a small portable generator.

The NMP1 OIP describes a greater than 24 hour BDBEE coping strategy that appears to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Design details not available at this time include the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation and the final nitrogen pneumatic system design including sizing and location; therefore, the staff has not completed its review.



Open Item: Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.

Open Item: Make available for NRC staff audit documentation of the HCVS nitrogen pneumatic system design including sizing and location.

### 3.2.4 Severe Accident Event Venting

#### 3.2.4.1 First 24 Hour Coping

Order EA-13-109, Section 1.2.6 states that:

- 1.2.6 The HCVS shall be capable of operating with dedicated and permanently installed equipment for at least 24 hours following the loss of normal power or loss of normal pneumatic supplies to air operated components during an extended loss of AC power.

Page 21 of the OIP states the following:

The operation of the HCVS will be designed to minimize reliance on operator actions for response to an ELAP and severe accident events. Progression of the ELAP into a severe accident assumes that the FLEX strategies identified in the response to Order EA-12-049 have not been effective. Immediate operator actions will be completed by operators from either the MCR or the HCVS ROS using remote-manual actions. The operator actions required to open a vent path are as described in Table 2-1 [of the OIP]. Remote-manual is defined in this plan as a non-automatic power operation of a component and does not require the operator to be at or in close proximity to the component. No other operator actions are required to initiate venting under primary procedural protocol.

The HCVS will be designed to allow initiation, control, and monitoring of venting from the MCR and will be able to be operated from an installed ROS as part of the response to this Order. Both locations minimize plant operators' exposure to adverse temperature and radiological conditions and are protected from hazards assumed in Part 1 of this report. A preliminary evaluation of travel pathways for dose and temperature concerns has been completed and travel paths identified. A final evaluation of environmental conditions will be completed as part of detailed design for confirmation.

...Permanently installed electrical power and motive air/gas capability will be available to support operation and monitoring of the HCVS for 24 hours. Power will be provided by installed batteries for up to 24 hours before generators will be required to be functional.

*System control:*

- i. Active: The HCVS PCIVs and HCVS control valve are operated in accordance with EOPs/SOPs to control containment pressure. The HCVS is designed for a minimum of 12 open/close cycles of the vent path under ELAP conditions over the first 24 hours following an ELAP. Controlled venting will be permitted in the revised EOPs. The configuration of the new pneumatic supplies allows the HCVS system controls to override the containment isolation circuit on the PCIVs needed to vent containment.
- ii. Passive: Inadvertent actuation protection is provided by use of key-locked switches for both the HCVS power supply actuation and valve operation. The normal state of the system is de-energized and closed.

The NMP1 OIP describes a first 24 hour severe accident coping strategy that appears to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Design details not available at this time include: the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation, the final nitrogen pneumatic system design including sizing and location, and an evaluation of environmental and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment (licensee identified); therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.

Open Item: Make available for NRC staff audit documentation of the HCVS nitrogen pneumatic system design including sizing and location.

Open Item: Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.

#### 3.2.4.2 Greater Than 24 Hour Coping

Order EA-13-109, Section 1.2.4 states that:

- 1.2.4 The HCVS shall be designed to be manually operated during sustained operations from a control panel located in the main control room or a remote but readily accessible location.
- 1.2.8 The HCVS shall include means to monitor the status of the vent system (e.g., valve position indication) from control panel required by 1.2.4. The monitoring system shall be designed for sustained operation during an extended loss of AC power.

Page 22 of the OIP states the following:

Actions required to extend venting beyond 24 hours include replenishment of pneumatic supplies and replenishment of electrical supply.

The pneumatic supply station will be installed in the Turbine Building and will include a nitrogen bottle station with additional connections for extra nitrogen bottles or connection of a portable air compressor. Connections will utilize pre-engineered quick disconnect fittings. The location of the pneumatic supply station will be evaluated for reasonable protection per Part 1 of this OIP and modified as required for compliance. Actions to replenish the pneumatic supplies include replacement of nitrogen bottles or installation and refueling of a portable air compressor. Sufficient nitrogen bottles will be staged to support operations for an additional 48 hours beyond the initial 24 hour coping period following the ELAP event.

The HCVS batteries and battery charger will also be installed in the Turbine Building. The UPS will include battery capacity sufficient for 24 hour operation. The normal power supply to the HCVS controls and instruments will be provided by the #12 Station Battery Bus, which in turn is re-powered by a 600 VAC diesel generator connected to the #12 Station Battery Charger as part of the FLEX response. A design change to install portable generator connections to this bus is being completed in support of EA-12-049 (Reference 1 [of the OIP]). In the event that power is not restored to the bus, a local 240 VAC connection to the UPS will allow the UPS to receive power from a small portable generator. Actions to replenish the electrical supply include refueling the DG or connecting and refueling a small portable generator.

Both the pneumatic supply station and the HCVS batteries/battery charger are located in the Turbine Building north wall west. The Turbine Building is outside of the secondary containment boundary. The HCVS piping will exit the Reactor Building in the northeast corner of the Reactor Building. Therefore, the Reactor Building provides shielding for the Turbine Building. A preliminary evaluation of radiological and temperature concerns was completed. A final evaluation will be completed when the location of the ROS is finalized.

The NMP1 OIP describes greater than 24 hour severe accident coping strategy that appears to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Specific details not available at this time include: the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation, the final nitrogen pneumatic system design including sizing and location, and an evaluation of environmental and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment (licensee identified); therefore, the staff has not completed its review.

- Open Item: Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.
- Open Item: Make available for NRC staff audit documentation of the HCVS nitrogen pneumatic system design including sizing and location.
- Open Item: Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.

### 3.2.5 Support Equipment Functions

#### 3.2.5.1 BDBEE

Order EA-13-109, Sections 1.2.8 and 1.2.9 state that:

- 1.2.8 The HCVS shall include means to monitor the status of the vent system (e.g., valve position indication) from control panel required by 1.2.4. The monitoring system shall be designed for sustained operation during an extended loss of AC power.
- 1.2.9 The HCVS shall include a means to monitor the effluent discharge for radioactivity that may be released from operation of the HCVS. The monitoring system shall provide indication from the control panel required by 1.2.4 and shall be designed for sustained operation during an extended loss of AC power.

Page 24 of the OIP states the following:

Venting will require support from the HCVS batteries, battery charger, and pneumatic supply station being installed. These provide a minimum of 24 hour operation on installed supplies and provide connection points for additional pneumatic supplies (nitrogen bottles or compressor) and electrical supplies (portable generator)[.]

Containment integrity is initially maintained by permanently installed equipment. All containment venting functions will be performed from the MCR or ROS.

The pneumatic supply station will be installed in the Turbine Building and will include a nitrogen bottle station with additional connections for extra nitrogen bottles or connection of a portable air compressor. Connections will utilize pre-engineered quick disconnect fittings. The location of the pneumatic supply station will be evaluated for reasonable protection per Part 1 of this OIP and modified as required for compliance. Actions to replenish the pneumatic supplies include replacement of nitrogen bottles or installation and refueling of a portable air compressor. Sufficient nitrogen bottles will be staged to support operations for an additional 48 hours beyond the initial 24 hour coping period following the ELAP event.

The HCVS batteries and battery charger will also be installed in the Turbine Building. The UPS will include battery capacity sufficient for 24 hour operation. The normal power supply to the HCVS controls and instruments will be provided by the #12 Station Battery Bus, which in turn is re-powered by a 600 VAC diesel generator connected to the # 12 Station Battery Charger as part of the FLEX response. A design change to install portable generator connections to this bus is being completed in support of EA- 12-049 (Reference 1 [of the OIP]). In the event that power is not restored to the bus, a local 240 VAC connection will allow the battery charger to receive power from a small portable generator. Actions to replenish the electrical supply include refueling the DG or connecting and refueling a small portable generator.

The NMP1 OIP describes BDBEE supporting equipment functions that appear to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Design details not available at this time include the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation and the final nitrogen pneumatic system design including sizing and location; therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.

Open Item: Make available for NRC staff audit documentation of the HCVS nitrogen pneumatic system design including sizing and location.

### 3.2.5.2 Severe Accident Venting

Order EA-13-109, Sections 1.2.8 and 1.2.9 state that:

1.2.8 The HCVS shall include means to monitor the status of the vent system (e.g., valve position indication) from control panel required by 1.2.4. The monitoring system shall be designed for sustained operation during an extended loss of AC power.

1.2.9 The HCVS shall include a means to monitor the effluent discharge for radioactivity that may be released from operation of the HCVS. The monitoring system shall provide indication from the control panel required by 1.2.4 and shall be designed for sustained operation during an extended loss of AC power.

Page 24 of the OIP states the following:

The same support functions that are used in the BDBEE scenario would be used for severe accident venting.

The NMP1 OIP describes support equipment functions for severe accident venting that appear

to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Design details not available at this time include: the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation, the final nitrogen pneumatic system design including sizing and location, and an evaluation of environmental and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment (licensee identified); therefore, the staff has not completed its review.

- Open Item: Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.
- Open Item: Make available for NRC staff audit documentation of the HCVS nitrogen pneumatic system design including sizing and location.
- Open Item: Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.

### 3.2.6 Venting Portable Equipment Deployment

Order EA-13-109, Section 3.1 states that:

- 3.1 The licensee shall develop, implement, and maintain procedures necessary for the safe operation of the HCVS. Procedures shall be established for system operations when normal and backup power is available, and during an extended loss of AC power.

Page 26 of the OIP states the following:

Venting actions using portable equipment include the following:

- Replacement and replenishment of pneumatic supply sources. This includes the option of replacing nitrogen bottles or connecting a portable air compressor. Equipment sufficient for an additional 48 hours of vent operation beyond the 24-hour installed supply would be pre-staged in the FLEX storage building. Installation of the HCVS includes installation of a pneumatic supply header that includes pneumatic regulators and utilizes standard pneumatic connections.
- Establishing temporary power to repower the battery charger. Option 1 is to connect the FLEX DG to Station Battery Charger # 12, which provides power to Station Battery Bus # 12 that in turn powers the HCVS equipment and battery charger. Option 1 would be completed as part of the FLEX response strategy and occurs to the south and inside the NMP1 Turbine Building. Option 2, to be taken if the FLEX DG cannot be connected to the Station Battery Charger #12, is to connect a small portable generator (approximately 2kW) to the HCVS battery charger. Option 2 would be taken locally at the battery charger. Either of these actions will also require the generators to be refueled. A one

line diagram of the electrical system to be installed is included in Attachment 3 [of the OIP].

The NMP1 OIP describes venting portable equipment deployment functions that appear to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. Design details not available at this time include: the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation, the final nitrogen pneumatic system design including sizing and location, and an evaluation of environmental and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment; therefore, the staff has not completed its review.

Open Item: Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.

Open Item: Make available for NRC staff audit documentation of the HCVS nitrogen pneumatic system design including sizing and location.

Open Item: Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.

#### Summary, Section 3.2:

The licensee's approach to Boundary Conditions for Wetwell Vent, if implemented as described in Section 3.2, and assuming acceptable resolution of any open items identified here or as a result of licensee alterations to their proposed plans, appears to be consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109.

### 3.3 BOUNDARY CONDITIONS FOR DRY WELL VENT

#### Summary, Section 3.3:

Dry Well Vent will be evaluated during Phase 2 of Order EA-13-109. The ISG for Phase 2 will be provided by April 30, 2015. Licensees will submit an updated OIP to address Phase 2 of Order EA-13-109 by December 31, 2015.

### 3.4 PROGRAMMATIC CONTROLS, TRAINING, DRILLS AND MAINTENANCE

#### 3.4.1 Programmatic Controls

Order EA-13-109, Sections 3.1 and 3.2 state that:

- 3.1 The licensee shall develop, implement, and maintain procedures necessary for the safe operation of the HCVS. Procedures shall be established for system operations when normal and backup power is

available, and during an extended loss of AC power.

- 3.2 The licensee shall train appropriate personnel in the use of the HCVS. The training curricula shall include system operations when normal and backup power is available, and during an extended loss of AC power.

Page 29 of the OIP states the following:

Program Controls:

The HCVS venting actions will include:

- Site procedures and programs are being developed in accordance with NEI 13-02 to address use and storage of portable equipment relative to the Severe Accident defined in NRC Order EA-13-109 and the hazards applicable to the site per Part 1 of this OIP.
- Routes for transporting portable equipment from storage location(s) to deployment areas will be developed as the response details are identified and finalized. The identified paths and deployment areas will be accessible when the HCVS system is required to be functional including during Severe Accidents.

Procedures:

Procedures will be established for system operations when normal and backup power is available, and during ELAP conditions.

NMP1 will utilize the industry developed guidance from the Owners Groups, EPRI [Electric Power Research Institute], and NEI Task team to develop/enhance site specific procedures or guidelines to address the criteria in NEI 13-02. These procedures and/or guidelines will support existing symptom based command and control strategies in the current EOPs and will contain the following details:

- appropriate conditions and criteria for use of the HCVS
- when and how to place the HCVS in operation
- the location of system components
- instrumentation available
- normal and backup power supplies
- directions for sustained operation (Reference 9 [of the OIP]), including the storage and location of portable equipment
- location of the remote control HCVS operating station (panel)
- training on operating the portable equipment
- testing of portable equipment



Nine Mile Point will establish provisions for out-of-service requirements of the HCVS and compensatory measures. The following provisions will be documented in the HCVS Program Document:

The provisions for out-of-service requirements for HCVS are applicable in Modes 1, 2 and 3

- If for up to 90 consecutive days, the primary or alternate means of HCVS operation are nonfunctional, no compensatory actions are necessary.
- If for up to 30 days, the primary and alternate means of HCVS operation are non-functional, no compensatory actions are necessary.
- If the out of service times exceed 30 or 90 days as described above, the following actions will be performed:
  - The condition will be entered into the corrective action system,
  - The HCVS availability will be restored in a manner consistent with plant procedures,
  - A cause assessment will be performed to prevent future unavailability for similar causes.
  - Actions will be initiated to implement appropriate compensatory actions

The NMP1 OIP describes programmatic controls that appear to be consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. NRC staff determined that procedure development appears to be in accordance with existing industry protocols. The provisions for out-of-service requirements appear to reflect consideration of the probability of an ELAP requiring severe accident venting and the consequences of a failure to vent under such conditions.

#### 3.4.2 Training

Order EA-13-109, Section 3.1 states that:

- 3.1 The licensee shall train appropriate personnel in the use of the HCVS. The training curricula shall include system operations when normal and backup power is available, and during an extended loss of AC power.

Page 30 of the OIP states the following:

The Systematic Approach to Training (SAT) will be used to identify the population to be trained and to determine both the initial and continuing elements of the required training. As determined by the SAT process, the training will consider system operations when normal and backup power is available, and during ELAP conditions. Required training will be completed prior to placing the HCVS in service.

The NMP1 OIP describes HCVS training requirements that appear to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109. The systematic approach to training process has been accepted by the NRC as appropriate for developing training for nuclear plant personnel.

### 3.4.3 Drills

Order EA-13-109, Section 3.1 states that:

- 3.1 The licensee shall develop, implement, and maintain procedures necessary for the safe operation of the HCVS. Procedures shall be established for system operations when normal and backup power is available, and during an extended loss of AC power.

Page 30 of the OIP states the following:

The site will utilize the guidance provided in NEI 13-06 and 14-01 (References 10 and 11 [of the OIP] for guidance related to drills, tabletops, or exercises for HCVS operation. In addition, the site will integrate these requirements with compliance to any rulemaking resulting from the NTTF Recommendations 8 and 9.

The NMP1 OIP describes an approach to drills that appears to be in accordance with NEI 13-06, "Enhancements to Emergency Response Capabilities for Beyond Design Basis Accidents and Events" and NEI 14-01, "Emergency Response Procedures and Guidelines for Extreme Events and Severe Accidents." This approach appears to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109.

### 3.4.4 Maintenance

Order EA-13-109, Section 1.2.13, states that:

- 1.2.13 The HCVS shall include features and provisions for the operation, testing, inspection and maintenance adequate to ensure that reliable function and capability are maintained.

Page 31 of the OIP states the following:

The site will utilize the standard EPRI industry PM process (similar to the Preventive Maintenance Basis Database) for establishing the maintenance calibration and testing actions for HCVS components. The control program will include maintenance guidance, testing procedures and frequencies established based on type of equipment and considerations made within the EPRI guidelines.

Site procedures and programs are being developed in accordance with NEI 13-02 to address use and storage of portable equipment relative to the Severe

Accident defined in NRC Order EA-13-109 and the hazards applicable to the site per Part 1 of this OIP. Attachment 1[of the OIP] defines the applicable maintenance and preventive maintenance requirements for HCVS portable equipment.

NMPI will implement the following operation, testing and inspection requirements for the HCVS to ensure reliable operation of the system.

**Table 4-1: Testing and Inspection Requirements**

<b>Description</b>	<b>Frequency</b>
Cycle the HCVS valves and the interfacing system valves not used to maintain containment integrity during operations.	Once per operating cycle
Perform visual inspections and a walk down of HCVS components	Once per operating cycle
Test and calibrate the HCVS radiation monitors.	Once per operating cycle
Leak test the HCVS.	(1) Prior to first declaring the system functional; (2) Once every three operating cycles thereafter; and (3) Post-maintenance test after restoration of any breach of system boundary within the buildings
Validate the HCVS operating procedures by conducting an open/close test of the HCVS control logic from its control panel and ensuring that all interfacing system valves move to their proper (intended) positions.	Once per every other operating cycle

The NMP1 OIP describes an approach to maintenance that appears to be in accordance with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109.

#### Summary, Section 3.4:

The licensee's approach to Programmatic Controls Training, Drills and Maintenance, if implemented as described in Section 3.4, and assuming acceptable resolution of any open items identified here or as a result of licensee alterations to their proposed plans, appears to be consistent with the guidance found in NEI 13-02, endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing applicable requirements of Order EA-13-109.

#### 4.0 OPEN ITEMS

This section contains a summary of the open items identified to date as part of the technical evaluation. Open items, whether NRC or licensee identified, are topics for which there is

insufficient information to fully resolve the issue, for which the NRC staff requires clarification to ensure the issue is on a path to resolution, or for which the actions to resolve the issue are not yet complete. The intent behind designating an issue as an open item is to highlight items that the staff intends to review further. The NRC staff has reviewed the licensee OIP for consistency with NRC policy and technical accuracy. NRC and licensee identified open items have been identified in Section 3.0 and are listed in the table below.

List of Open items

Open Item	Action	Comment
1.	Make available for NRC staff audit the seismic and tornado missile final design criteria for the HCVS stack.	Section 3.2.2.3
2.	Make available for NRC staff audit analyses demonstrating that HCVS has the capacity to vent the steam/energy equivalent of one (1) percent of licensed/rated thermal power (unless a lower value is justified) and that the suppression pool and the HCVS together are able to absorb and reject decay heat, such that following a reactor shutdown from full power containment pressure is restored and then maintained below the primary containment design pressure and the primary containment pressure limit.	Section 3.2.2.1 Section 3.2.2.2
3.	Provide a description of the final design of the HCVS to address hydrogen detonation and deflagration.	Section 3.2.2.6
4.	Make available for NRC staff audit documentation that demonstrates adequate communication between the remote HCVS operation locations and HCVS decision makers during ELAP and severe accident conditions.	Section 3.2.2.5
5.	Provide a description of the strategies for hydrogen control that minimizes the potential for hydrogen gas migration and ingress into the reactor building or other buildings.	Section 3.2.2.6
6.	Make available for NRC staff audit an evaluation of temperature and radiological conditions to ensure that operating personnel can safely access and operate controls and support equipment.	Section 3.2.1 Section 3.2.2.3 Section 3.2.2.4 Section 3.2.2.5 Section 3.2.2.10 Section 3.2.4.1 Section 3.2.4.2 Section 3.2.5.2 Section 3.2.6
7.	Make available for NRC staff audit the final sizing evaluation for HCVS batteries/battery charger including incorporation into FLEX DG loading calculation.	Section 3.2.1 Section 3.2.2.4 Section 3.2.3.1 Section 3.2.3.2 Section 3.2.4.1 Section 3.2.4.2 Section 3.2.5.1 Section 3.2.5.2 Section 3.2.6

8.	Make available for NRC staff audit documentation of the HCVS nitrogen pneumatic system design including sizing and location.	Section 3.2.2.4 Section 3.2.3.1 Section 3.2.3.2 Section 3.2.4.1 Section 3.2.4.2 Section 3.2.5.1 Section 3.2.5.2 Section 3.2.6
9.	Make available for NRC staff audit documentation of a seismic qualification evaluation of HCVS components.	Section 3.2.2.9
10.	Make available for NRC staff audit descriptions of all instrumentation and controls (existing and planned) necessary to implement this order including qualification methods.	Section 3.2.2.10
11.	Make available for NRC staff audit the descriptions of local conditions (temperature, radiation and humidity) anticipated during ELAP and severe accident for the components (valves, instrumentation, sensors, transmitters, indicators, electronics, control devices, and etc.) required for HCVS venting including confirmation that the components are capable of performing their functions during ELAP and severe accident conditions.	Section 3.2.2.3 Section 3.2.2.5 Section 3.2.2.9 Section 3.2.2.10

5.0 SUMMARY

As required by Order EA-13-109, the licensee has provided an OIP for designing and installing Phase 1 of a severe accident capable HCVS that provides venting capability from the wetwell during severe accident conditions, using a vent path from the containment wetwell to remove decay heat, vent the containment atmosphere (including steam, hydrogen, carbon monoxide, non-condensable gases, aerosols, and fission products), and control containment pressure within acceptable limits. The OIP describes a HCVS wetwell vent designed for those accident conditions (before and after core damage) for which containment venting is relied upon to reduce the probability of containment failure, including accident sequences that result in the loss of active containment heat removal capability or ELAP.

The NRC staff finds that the licensee's OIP for Phase 1 of Order EA-13-109 describes: plan elements and assumptions; boundary conditions; provisions for programmatic controls, training, drills and maintenance; and an implementation schedule that appear consistent with the guidance found in NEI 13-02 endorsed, in part, by JLD-ISG-2013-02 as an acceptable means for implementing phase 1 requirements of Order EA-13-109, subject to acceptable closure of the above open items.

## 6.0 REFERENCES

1. Order EA-13-109, "Order Modifying Licenses with Regard to Reliable Hardened Containment Vents Capable of Operation Under Severe Accident Conditions," June 6, 2013 (Agencywide Documents Access and Management System (ADAMS) Accession No. ML13143A321).
2. Letter from Exelon to NRC, "Nine Mile Point Units 1 and 2- Overall Integrated Plan Per Order EA-13-109 Modifying Licenses with Regard to Reliable Hardened Containment Vents Capable of Operation Under Severe Accident Conditions," dated June 27, 2014 (ADAMS Accession No. ML14184B340).
3. SECY-11-0093, "The Near-Term Task Force Review of Insights from the Fukushima Dai-ichi", (ADAMS Accession No. ML111861807).
4. SRM-SECY-11-0124, "Recommended Actions to be taken Without Delay From The Near-Term Task Force Report", (ADAMS Accession No. ML112911571).
5. SRM-SECY-11-0137, "Prioritization of Recommended Actions to be Taken in Response to Fukushima Lessons Learned", (ADAMS Accession No. ML113490055).
6. SRM-SECY-11-0093, "Staff Requirements – SECY-11-0093 – Near-Term Report and Recommendations for Agency Actions following the Events in Japan," August 19, 2011 (ADAMS Accession No. ML112310021)
7. SECY-12-0025, "Proposed Orders and Requests for Information in Response to Lessons Learned from Japan's March 11, 2011, Great Tohoku Earthquake and Tsunami," February 17, 2012 (ADAMS Accession No. ML12039A103)
8. SRM-SECY-12-0025, "Staff Requirements – SECY-12-0025 - Proposed Orders and Requests for Information in Response to Lessons Learned from Japan's March 11, 2011, Great Tohoku Earthquake and Tsunami," March 9, 2012 (ADAMS Accession No. ML120690347)
9. Order EA-12-050, "Order Modifying Licenses with Regard to Reliable Hardened Containment Vents," March 9, 2012 (ADAMS Accession No. ML12054A694)
10. SECY-12-0157, Consideration of Additional Requirements for Containment Venting Systems for Boiling Water Reactors with Mark I and Mark II Containments, November 26, 2012 (ADAMS Accession No. ML12325A704)
11. SRM-SECY-12-0157, "Staff Requirements - SECY-12-0157, "Consideration Of Additional Requirements For Containment Venting Systems For Boiling Water Reactors With Mark I And Mark II Containments", March 19, 2013 (ADAMS Accession No. ML13078A017).

12. NEI 13-02, "Industry Guidance for Compliance with Order EA-13-109," Revision 0, November 12, 2013 (ADAMS Accession No. ML13316A853)
13. JLD-ISG-2013-02, "Compliance with Order EA-13-109, 'Severe Accident Reliable Hardened Containment Vents,'" November 14, 2013 (ADAMS Accession No. ML13304B836)
14. Nuclear Regulatory Commission Audits Of Licensee Responses To Phase 1 of Order EA-13-109 to Modify Licenses With Regard To Reliable Hardened Containment Vents Capable Of Operation Under Severe Accident Conditions (ADAMS Accession No. ML14126A545)
15. Order EA-12-049, "Order to Modify Licenses with Regard to Requirements for Mitigation Strategies for Beyond-Design-Basis External Events," March 12, 2012 (ADAMS Accession No. ML12054A735).
16. Nine Mile Point Nuclear Station, Units 1 and 2 - Interim Staff Evaluation Relating to Overall Integrated Plan in Response to Order EA-12-049 (Mitigation Strategies) (ADAMS Accession No. ML13225A584).
17. Letter from CENG to NRC, Calvert Cliffs, Units 1 & 2, Nine Mile Point, Units 1 & 2, R.E. Gina, Overall Integrated Plan for Mitigation Strategies for Beyond-Design-Basis External Events, dated February 28, 2013 (ADAMS Accession No. ML13066A171).
18. NUREG-1935, State-of-the-Art Reactor Consequence Analyses (SOARCA) Report (ADAMS Accession No. ML12332A058).

Principal Contributors:        Bruce Heida  
   Brian Lee  
   Brett Titus  
   Jerome Bettle  
   Nageswara Karipineni  
   Khoi Nguyen  
   Steve Wyman  
   Charles Norton

Date: March 26, 2015

P. Orphanos

- 2 -

If you have any questions, please contact Charles H. Norton, Project Manager, at 301-415-7818 or at [Charles.Norton@nrc.gov](mailto:Charles.Norton@nrc.gov).

Sincerely,

**/RA/**

Mandy K. Halter, Acting Chief  
Orders Management Branch  
Japan Lessons-Learned Division  
Office of Nuclear Reactor Regulation

Docket No. 50-220

Enclosure:  
Interim Staff Evaluation

cc w/encl: Distribution via Listserv

DISTRIBUTION

PUBLIC  
JOMB R/F  
RidsNrrDoriLpl1-1  
RidsNrrPMNineMilePoint  
RidsNrrLASLent  
RidsAcrsAcnw\_MailCTR

RidsOGCMailCenter  
RidsRgn1MailCenter  
JPaige  
CNorton  
WReckley  
MHalter

**ADAMS Accession No: ML15069A671**

**\*via email**

OFFICE	NRR/JLD/JOMB/PM	NRR/JLD/LA	NRR/DORL/LPL1-1/PM	NRR/JLD/JOMB/PM
NAME	CNorton	SLent	BVaidya	JPaige
DATE	03/101/15	03/11/15	03/23/15	03/23/15
OFFICE	NRR/JLD/JCBB/BC	NRR/JLD/JOMB/BC (A)		
NAME	SBailey	MHalter		
DATE	03/13/15	03/26/15		

**OFFICIAL RECORD COPY**