



GPU Nuclear, Inc.  
Three Mile Island  
Nuclear Station  
Route 441 South  
Post Office Box 480  
Middletown, PA 17057-0480  
Tel 717-948-8461

March 27, 2015  
TMI-15-036

10 CFR 50.75  
10 CFR 50.82

ATTN: Document Control Desk  
U.S. Nuclear Regulatory Commission  
Washington, D.C. 20555-0001

SUBJECT:  
Three Mile Island Nuclear Station, Unit 2  
Docket No. 50-320, License No. DPR-73  
Decommissioning Funding Status Report for the Three Mile Island Nuclear  
Station, Unit 2

Pursuant to 10 CFR 50.75 and 10 CFR 50.82, GPU Nuclear, Inc. is hereby submitting three (3) reports to the Nuclear Regulatory Commission (NRC) for Three Mile Island Nuclear Station, Unit 2 for the year ending December 31, 2014. Attachment 1 provides a decommissioning funding status report based on the Nuclear Regulatory Commission (NRC) formula described in 10 CFR 50.75(c). Attachment 2 provides a decommissioning funding status report based upon a site-specific decommissioning cost estimate. Attachment 3 contains a financial assurance status report as required by 10 CFR 50.82(a)(8)(v).

Enclosure A provides a copy of the *Decommissioning Cost Analysis for Three Mile Island Unit 2*, December 2014. Enclosure B provides a copy of the *Escalation Analysis for Three Mile Island Unit 2 2013 Site-Specific Decommissioning Cost Estimate*, February 2015.

There are no regulatory commitments contained in this letter. If there are any questions or if additional information is required, please contact Mr. Thomas A. Lentz, Manager - FirstEnergy Nuclear Operating Company Fleet Licensing, at (330) 315-6810.

Sincerely,

A handwritten signature in black ink, appearing to read 'Gregory H. Halnon', written over a horizontal line.

Gregory H. Halnon  
Director, Fleet Regulatory Affairs

Three Mile Island Nuclear Station, Unit 2

TMI-15-036

Page 2

Attachments:

1. Three Mile Island Nuclear Station, Unit 2 Decommissioning Funding Status Report – NRC Formula
2. Three Mile Island Nuclear Station, Unit 2 Decommissioning Funding Status Report – Site-Specific Decommissioning Cost Estimate
3. Three Mile Island Nuclear Station, Unit 2 Financial Assurance Status Report

Enclosures:

- A. *Decommissioning Cost Analysis for Three Mile Island Unit 2, December 2014*
- B. *Escalation Analysis for Three Mile Island Unit 2 2013 Site-Specific Decommissioning Cost Estimate, February 2015*

cc: NRC Region I Administrator  
NRC Project Manager  
NRC Resident Inspector

Attachment 1  
TMI-15-036

Three Mile Island Nuclear Station, Unit 2 Decommissioning Funding  
Status Report – NRC Formula  
Page 1 of 3

This report reflects the FirstEnergy Corp. subsidiary ownership interests in the Three Mile Island Nuclear Station, Unit 2 as of December 31, 2014.

1. The minimum decommissioning fund estimate, pursuant to 10 CFR 50.75(b) and (c) (see Schedule 1):

Metropolitan Edison Company	\$252,161,563
Pennsylvania Electric Company	126,080,782
Jersey Central Power & Light Company	<u>126,080,782</u>
FirstEnergy Corp. Consolidated	<u>\$504,323,126</u>

2. The amount accumulated in external trust funds as of December 31, 2014:

	After Tax
Metropolitan Edison Company	\$338,038,657
Pennsylvania Electric Company	182,710,464
Jersey Central Power & Light Company	<u>211,780,107</u>
FirstEnergy Corp. Consolidated	<u>\$732,529,228</u>

3. There are no longer any funds to be collected from the ratepayers.
4. The assumptions used regarding escalation in decommissioning cost, rates of earnings on decommissioning funds, and rates of other factors used in funding projections:

Consolidated Ownership Interest in Unit	100%
Estimated Net Investment Rate	2.00%
Year of Site Restoration Completion	2053
Year of Three Mile Island Nuclear Station, Unit 1 Operating License Expiration	2034

An additional assumption is that the decommissioning activities for Three Mile Island Nuclear Station, Unit 2 will commence after the shutdown of Three Mile Island Nuclear Station, Unit 1. Three Mile Island Nuclear Station, Unit 2 transitions from a Post-Defueling Monitored Storage status to decommissioning in 2040.

5. There are no contracts upon which the owners/licensees are relying pursuant to 10 CFR 50.75(e)(1)(v).
6. There are no modifications to the licensee's current method of providing financial assurance since the last submitted report.

7. There were no amendments to the trust agreements for the above-mentioned owners of Three Mile Island Nuclear Station, Unit 2.
8. Mathematical rounding was performed during the development of the supporting calculations.



**Schedule 1**  
**FIRSTENERGY CORP.**  
Calculation of Minimum Financial Assurance Amount  
December 31, 2014  
**THREE MILE ISLAND NUCLEAR STATION, UNIT 2**

**Pennsylvania Regions**

Labor (L) = Northeast  
Energy (E) = National  
Waste Burial (B) = Generic

**For PWR Unit**

	Adjustment Factor	Ratio	Escalation Factor <sup>1</sup>
L =	2.661	0.65	1.73
E =	2.222	0.13	0.289
B =	13.885	0.22	3.055

PWR Escalation Factor = 5.074

Base Amount for PWR between 1200 MWt and 3400 MWt =  $(\$75 + 0.0088P)$  million  
(P = power level in megawatts thermal = 2772)

$(\$75 + 0.0088(2772))$  million = \$99,393,600

Escalated Amount for unit<sup>1</sup> =  
99,393,600 x 5.074 = **\$504,323,126**

<u>Owner/Licensee<sup>1</sup></u>	<u>Ownership</u>	
Pennsylvania Electric Company	25%	\$126,080,782
Jersey Central Power & Light Company	25%	\$126,080,782
Metropolitan Edison Company	<u>50%</u>	<u>\$252,161,563</u>
FirstEnergy Corp. Consolidated	100%	<u><b>\$504,323,126</b></u>

Note 1: Mathematical rounding was performed during the development of the supporting calculations.

Attachment 2  
TMI-15-036

Three Mile Island Nuclear Station, Unit 2 Decommissioning Funding  
Status Report – Site-Specific Decommissioning Cost Estimate  
Page 1 of 4

1. Decommissioning funds estimated to be required pursuant to 10 CFR 50.75(b) and (c) are based upon a site-specific decommissioning cost study, *Decommissioning Cost Analysis for Three Mile Island Unit 2*, dated December 2014, and escalated to 2014 dollars:

Radiological	\$1,180,928,000
Non-Radiological	<u>40,560,000</u>
FirstEnergy Corp. Consolidated	<u>\$1,221,488,000</u>

2. The amount accumulated in external trust funds as of December 31, 2014:

	After Tax
Metropolitan Edison Company	\$338,038,657
Pennsylvania Electric Company	182,710,464
Jersey Central Power & Light Company	<u>211,780,107</u>
FirstEnergy Corp. Consolidated	<u>\$732,529,228</u>

3. There are no longer any funds to be collected from the ratepayers.
4. The assumptions used regarding escalation in decommissioning cost, rates of earnings on decommissioning funds, and rates of other factors used in funding projections:

Consolidated Ownership Interest in Unit	100%
Estimated Rate of Escalation in Decommissioning Costs	2.77%
Estimated After-Tax Rate of Return	2.00%
Year of Site Restoration Completion	2053
Year of Three Mile Island Nuclear Station, Unit 1 end of license	2034

An additional assumption is that the decommissioning activities for Three Mile Island Nuclear Station, Unit 2 will commence after the shutdown of Three Mile Island Nuclear Station, Unit 1. Three Mile Island Nuclear Station, Unit 2 transitions from a Post-Defueling Monitored Storage status to decommissioning in 2040.

5. There are no contracts upon which the owners/licensees are relying pursuant to 10 CFR 50.75(e)(1)(v).
6. There are no modifications to the licensee's current method of providing financial assurance since the last submitted report.

7. There were no amendments to the trust agreements for the above-mentioned owners of Three Mile Island Nuclear Station, Unit 2.

8. Site-Specific Cost Analysis Assumptions

10 CFR 50.75(e)(1)(i), states, in part, that:

A licensee that has prepaid funds based on a site-specific estimate under 50.75(b)(1) of this section may take credit for projected earnings on the prepaid decommissioning trust funds, using up to a 2 percent annual real rate of return from the time of future funds' collection through the projected decommissioning period, provided that the site-specific estimate is based on a period of safe storage that is specifically described in the estimate.

In accordance with Regulatory Guide 1.159, Revision 2, a facility specific analysis may be used to demonstrate the adequacy of decommissioning funds, provided that:

NRC-required cost estimate for decommissioning costs, as defined in 10 CFR 50.2, is equal to or greater than the amount stated in the formulas in 10 CFR 50.75(c)(1) and (2).

The site-specific radiological decommissioning cost estimate is \$1,180,928,000 which is greater than the 10 CFR 50.75(c) cost estimate of \$504,323,126. The analysis assumes a 2 percent yearly rate of return. The analysis also assumes a period of safe storage. The cash flows were contained in a decommissioning cost estimate that was prepared for Three Mile Island Nuclear Station, Unit 2. The cash flow analysis assumes the yearly expenses are incurred at the beginning of year.

Schedule 1 provides the site-specific analysis. The analysis values are in 2014 dollars. The analysis includes both the radiological and site restoration costs.

9. Mathematical rounding was performed during the development of the supporting calculations.

10. References:

A. *Decommissioning Cost Analysis for Three Mile Island Unit 2*, December 2014

B. *Escalation Analysis for Three Mile Island Unit 2 2013 Site-Specific Decommissioning Cost Estimate*, February 2015

Schedule 1

**FIRSTENERGY CORP.**  
Funding Analysis  
December 31, 2014  
**THREE MILE ISLAND NUCLEAR STATION, UNIT 2**

After-Tax

Estimated Net Investment Rate	2.00%
Estimated Escalation Rate	-
Estimated After-Tax Rate of Return	<u>2.00%</u>

Qualified Trust Balance on December 31, 2014	\$732,529,228
Non-Qualified Trust Balance on December 31, 2014	-
Total	\$732,529,228

Year	Beginning Balance	Deposits	Earnings	Withdrawal <sup>1</sup>	Ending Balance
2015	732,529,228	-	14,463,385	(9,360,000) <sup>2</sup>	737,632,613
2016	737,632,613	-	14,690,092	(3,128,000)	749,194,705
2017	749,194,705	-	14,921,494	(3,120,000)	760,996,199
2018	760,996,199	-	15,157,524	(3,120,000)	773,033,723
2019	773,033,723	-	15,398,274	(3,120,000)	785,311,997
2020	785,311,997	-	15,643,680	(3,128,000)	797,827,677
2021	797,827,677	-	15,894,154	(3,120,000)	810,601,831
2022	810,601,831	-	16,149,637	(3,120,000)	823,631,467
2023	823,631,467	-	16,410,229	(3,120,000)	836,921,697
2024	836,921,697	-	16,675,874	(3,128,000)	850,469,571
2025	850,469,571	-	16,946,991	(3,120,000)	864,296,562
2026	864,296,562	-	17,223,531	(3,120,000)	878,400,093
2027	878,400,093	-	17,505,602	(3,120,000)	892,785,695
2028	892,785,695	-	17,793,154	(3,128,000)	907,450,849
2029	907,450,849	-	18,086,617	(3,120,000)	922,417,466
2030	922,417,466	-	18,385,949	(3,120,000)	937,683,415
2031	937,683,415	-	18,691,268	(3,120,000)	953,254,684
2032	953,254,684	-	19,002,534	(3,128,000)	969,129,217
2033	969,129,217	-	19,320,184	(3,120,000)	985,329,402
2034	985,329,402	-	19,644,188	(3,120,000)	1,001,853,590
2035	1,001,853,590	-	19,974,672	(3,120,000)	1,018,708,262
2036	1,018,708,262	-	20,311,605	(3,128,000)	1,035,891,867
2037	1,035,891,867	-	20,655,437	(3,120,000)	1,053,427,304

Schedule 1 (Continued)

Year	Beginning Balance	Deposits	Earnings	Withdrawal <sup>1</sup>	Ending Balance
2038	1,053,427,304	-	21,006,146	(3,120,000)	1,071,313,450
2039	1,071,313,450	-	21,363,869	(3,120,000)	1,089,557,319
2040	1,089,557,319	-	20,693,006	(54,907,000)	1,055,343,326
2041	1,055,343,326	-	19,291,187	(90,784,000)	983,850,512
2042	983,850,512	-	17,396,970	(114,002,000)	887,245,482
2043	887,245,482	-	15,464,870	(114,002,000)	788,708,352
2044	788,708,352	-	13,487,887	(114,314,000)	687,882,239
2045	687,882,239	-	11,477,605	(114,002,000)	585,357,844
2046	585,357,844	-	9,695,777	(100,569,000)	494,484,621
2047	494,484,621	-	8,387,952	(75,087,000)	427,785,573
2048	427,785,573	-	7,049,871	(75,292,000)	359,543,445
2049	359,543,445	-	5,689,129	(75,087,000)	290,145,574
2050	290,145,574	-	4,301,171	(75,087,000)	219,359,745
2051	219,359,745	-	2,934,615	(72,629,000)	149,665,360
2052	149,665,360	-	2,348,847	(32,223,000)	119,791,207
2053	119,791,207	-	1,811,724	(29,205,000)	92,397,931
			TOTAL	(1,221,478,000)	

Notes:

1. Withdrawal are assumed to be made at the beginning of the period.
2. The *Decommissioning Cost Analysis for Three Mile Island Unit 2*, December 2014, had withdrawals for the years 2013 and 2014. Those withdrawals were included in the 2015 period.

Attachment 3  
TMI-15-036

Three Mile Island Nuclear Station, Unit 2 Financial Assurance Status Report  
Page 1 of 1

1. Formal decommissioning has not started at the Three Mile Island Nuclear Station, Unit 2. A special disbursement of decommissioning trust funds occurred in 2005 for \$416,400.00. Notification of this use of decommissioning funds was made to the NRC by letter dated February 1, 2005 (Accession No. ML050380143). No funds were spent on decommissioning activities in 2014.
2. Decommissioning funds estimated to be required are based upon a site-specific decommissioning cost study, *Decommissioning Cost Analysis for Three Mile Island Unit 2*, dated December 2014, and escalated to 2014 dollars:

Radiological	\$1,180,928,000
Non-Radiological	<u>40,560,000</u>
FirstEnergy Corp. Consolidated	<u>\$1,221,488,000</u>

3. The amount accumulated in external trust funds as of December 31, 2014:

	After Tax
Metropolitan Edison Company	\$338,038,657
Pennsylvania Electric Company	182,710,464
Jersey Central Power & Light Company	<u>211,780,107</u>
FirstEnergy Corp. Consolidated	<u>\$732,529,228</u>

4. There are no longer any funds to be collected from the ratepayers.
5. There are no modifications to the licensee's current method of providing financial assurance since the last submitted report.
6. There were no amendments to the trust agreements for the above-mentioned owners of Three Mile Island Nuclear Station, Unit 2.
7. Mathematical rounding was performed during the development of the supporting calculations.
8. References:

A. *Decommissioning Cost Analysis for Three Mile Island Unit 2*, December 2014

B. *Escalation Analysis for Three Mile Island Unit 2 2013 Site-Specific Decommissioning Cost Estimate*, February 2015


Enclosure A  
TMI-15-036

*Decommissioning Cost Analysis for Three Mile Island Unit 2,*  
December 2014  
(123 pages follow)

**DECOMMISSIONING COST ANALYSIS**

**for**

**THREE MILE ISLAND UNIT 2**



*prepared for*

**FirstEnergy Corporation**

*prepared by*

**TLG Services, Inc.  
Bridgewater, Connecticut**

**December 2014**



APPROVALS

Project Manager

  
Francis W. Seymore

12/11/14  
Date

Project Engineer

  
Mark S. Houghton

12/11/14  
Date

Technical Manager

  
William A. Cloutier, Jr.

12/11/2014  
Date

## TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
EXECUTIVE SUMMARY .....	vii-xviii
1. INTRODUCTION .....	1-1
1.1 Objectives of Study .....	1-1
1.2 Site Description.....	1-2
1.3 Regulatory Guidance .....	1-4
1.3.1 Nuclear Waste Policy Act.....	1-5
1.3.2 Low-Level Radioactive Waste Acts .....	1-7
1.3.3 Radiological Criteria for License Termination.....	1-9
2. DECOMMISSIONING ALTERNATIVES .....	2-1
2.1 DECON.....	2-2
2.1.1 Period 2 - Dormancy.....	2-2
2.1.2 Period 3 - Preparations .....	2-3
2.1.3 Period 4 - Decommissioning Operations.....	2-5
2.1.4 Period 5 - Site Restoration.....	2-8
2.2 SAFSTOR and Delayed DECON.....	2-9
3. COST ESTIMATE.....	3-1
3.1 Basis of Estimate .....	3-1
3.2 Methodology .....	3-1
3.3 Impact of Decommissioning Multiple Reactor Units .....	3-3
3.4 Financial Components of the Cost Model .....	3-4
3.4.1 Contingency .....	3-4
3.4.2 Financial Risk.....	3-7
3.5 Site-Specific Considerations.....	3-8
3.5.1 Spent Fuel Management.....	3-8
3.5.2 Reactor Vessel and Internal Components .....	3-9
3.5.3 Steam Generators.....	3-10
3.5.4 Other Primary System Components.....	3-11
3.5.5 Other Systems Known to Contain High Levels of Radioactivity.....	3-12
3.5.6 Reactor Building Structures Decontamination.....	3-13
3.5.7 Demolition of Other Contaminated Structures .....	3-14
3.5.8 Main Turbine and Condenser.....	3-14

**TABLE OF CONTENTS**  
(continued)

<b><u>SECTION</u></b>	<b><u>PAGE</u></b>
3.5.9 Transportation Methods .....	3-14
3.5.10 Low-Level Radioactive Waste Disposal .....	3-15
3.5.11 Additional Decommissioning Facilities .....	3-16
3.5.12 Remediation of Soil and Underground Piping .....	3-17
3.5.13 Site Conditions Following Decommissioning .....	3-17
3.6 Assumptions .....	3-17
3.6.1 Estimating Basis .....	3-17
3.6.2 Labor Costs .....	3-18
3.6.3 Design Conditions.....	3-18
3.6.4 General.....	3-19
3.7 Cost Estimate Summary .....	3-20
4. SCHEDULE ESTIMATE .....	4-1
4.1 Schedule Estimate Assumptions .....	4-1
4.2 Project Schedule.....	4-2
5. RADIOACTIVE WASTES .....	5-1
6. RESULTS .....	6-1
7. REFERENCES .....	7-1

TABLE OF CONTENTS  
(continued)

SECTION PAGE

TABLES

	Summary of Decommissioning Cost Elements, DECON .....	xvi
	Summary of Decommissioning Cost Elements, Delayed DECON .....	xvii
	Summary of Decommissioning Cost Elements, SAFSTOR.....	xviii
1.1	Inventory of Spent Fuel, Auxiliary and Fuel Handling Buildings .....	1-10
1.2	Inventory of Spent Fuel, Reactor Building .....	1-12
1.3	Inventory of Spent Fuel, Reactor Coolant System .....	1-13
3.1	Schedule of Total Annual Expenditures, DECON.....	3-21
3.2	Schedule of Total Annual Expenditures, Delayed DECON .....	3-23
3.3	Schedule of Total Annual Expenditures, SAFSTOR .....	3-25
5.1	Decommissioning Waste Summary, DECON .....	5-5
5.2	Decommissioning Waste Summary, Delayed DECON.....	5-6
5.3	Decommissioning Waste Summary, SAFSTOR.....	5-7
6.1	Summary of Decommissioning Cost Elements, DECON .....	6-3
6.2	Summary of Decommissioning Cost Elements, Delayed DECON .....	6-4
6.3	Summary of Decommissioning Cost Elements, SAFSTOR.....	6-5

FIGURES

4.1	Activity Schedule .....	4-3
4.2	Decommissioning Timeline, DECON .....	4-4
4.3	Decommissioning Timeline, Delayed DECON.....	4-5
4.4	Decommissioning Timeline, SAFSTOR .....	4-6
5.1	TMI-2 Waste Streams Summary.....	5-3
5.2	Decommissioning Waste Destinations (Radiological) .....	5-4

APPENDICES

A.	Unit Cost Factor Development.....	A-1
B.	Unit Cost Factor Listing.....	B-1
C.	Detailed Cost Analysis, DECON.....	C-1
D.	Detailed Cost Analysis, Delayed DECON .....	D-1
E.	Detailed Cost Analysis, SAFSTOR .....	E-1

**REVISION LOG**

No.	CRA No.	Date	Item Revised	Reason for Revision
0		12-11-14		Original Issue

## EXECUTIVE SUMMARY

This report presents estimates of the cost to decommission the Three Mile Island, Unit 2 nuclear unit (TMI-2) for the selected decommissioning scenarios following the scheduled cessation of plant operations at the adjacent Unit 1 reactor. This analysis relies upon site-specific, technical information, originally developed in an evaluation for the GPU Nuclear Corporation in 1995-96,<sup>[1]</sup> and last updated in 2008 for FirstEnergy.<sup>[2]</sup> The analysis has been further updated to reflect current assumptions pertaining to the disposition of the nuclear unit and relevant industry experience in undertaking such projects. The updated estimates are designed to provide the FirstEnergy Corporation with sufficient information to assess its financial obligations, as they pertain to the eventual decommissioning of the nuclear unit.

The decommissioning of TMI-2 is a continuation of the decontamination efforts started in the 1980s, following its accident. The ultimate goal of the decommissioning is to remove the radioactive material from the site that would preclude its release for unrestricted use.

The estimates are based on numerous fundamental assumptions, including regulatory requirements, project contingencies, radioactive waste disposal options, and site remediation requirements. The estimates also include the dismantling of non-essential structures and limited restoration of the site.

### Alternatives and Regulations

The Nuclear Regulatory Commission (NRC or Commission) provided initial decommissioning requirements in its rule adopted on June 27, 1988.<sup>[3]</sup> In this rule, the NRC set forth financial criteria for decommissioning licensed nuclear power facilities. The regulations addressed planning needs, timing, funding methods, and environmental review requirements for decommissioning. The rule also defined three decommissioning alternatives as being acceptable to the NRC: DECON, SAFSTOR, and ENTOMB.

---

<sup>1</sup> "Decommissioning Cost Estimate for the Three Mile Island, Unit 2," Document No. G01-1196-003, TLG Services, Inc., February 1996.

<sup>2</sup> "Decommissioning Cost Estimate for Three Mile Island Unit 2," Document No. F07-1601-002, TLG Services, Inc., January 2009.

<sup>3</sup> U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72 "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018 et seq.), June 27, 1988.

DECON is defined as "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations."<sup>[4]</sup>

SAFSTOR is defined as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use."<sup>[5]</sup> Decommissioning is to be completed within 60 years, although longer time periods will be considered when necessary to protect public health and safety.

ENTOMB is defined as "the alternative in which radioactive contaminants are encased in a structurally long-lived material, such as concrete; the entombed structure is appropriately maintained and continued surveillance is carried out until the radioactive material decays to a level permitting unrestricted release of the property."<sup>[6]</sup> As with the SAFSTOR alternative, decommissioning is currently required to be completed within 60 years.

The 60-year restriction has limited the practicality of the ENTOMB alternative at commercial reactors that generate significant amounts of long-lived radioactive material. In 1997, the Commission directed its staff to re-evaluate this alternative and identify the technical requirements and regulatory actions that would be necessary for entombment to become a viable option. The resulting evaluation provided several recommendations, however, rulemaking has been deferred pending the completion of additional research studies, e.g., on engineered barriers.

In 1996, the NRC published revisions to the general requirements for decommissioning nuclear power plants to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process.<sup>[7]</sup> The amendments allow for greater public participation and better define the transition process from operations to decommissioning. Regulatory Guide 1.184, issued in July 2000, further described the methods and procedures acceptable to the NRC staff for implementing the requirements of the 1996 revised rule relating to the initial activities and major phases of the decommissioning

---

<sup>4</sup> Ibid. Page FR24022, Column 3.

<sup>5</sup> Ibid

<sup>6</sup> Ibid. Page FR24023, Column 2.

<sup>7</sup> U.S. Code of Federal Regulations, Title 10, Parts 2, 50, and 51, "Decommissioning of Nuclear Power Reactors," Nuclear Regulatory Commission, Federal Register Volume 61, (p 39278 et seq.), July 29, 1996.

process. The costs and schedules presented in this analysis follow the general guidance and processes described in the amended regulations.

### Decommissioning Scenarios

Three decommissioning scenarios were evaluated for the nuclear unit. The two delayed dismantling scenarios, Delayed DECON and SAFSTOR, include some consideration of the decommissioning activities planned at the adjacent Unit 1. The scenarios selected are representative of alternatives available to the owner and are defined as follows:

1. DECON: The adjacent TMI-1 is promptly decommissioned upon the scheduled cessation of operations in 2034. TMI-2 transitions from a Post-Defueling Monitored Storage status to decommissioning in 2040. The decommissioning program for TMI-2 runs independently from the TMI-1 decommissioning effort; license termination of Unit 2 occurs in 2053, approximately 10 years after Unit 1 completes its decommissioning program (exclusive of the on-site ISFSI operations for Unit 1 fuel).
2. Delayed DECON: One of the decommissioning alternatives for Unit 1 is to defer decommissioning until the spent fuel has been removed from the site.<sup>[8]</sup> This scenario assumes that the decontamination and dismantling activities at TMI-2 are synchronized with the adjacent unit such that the licenses for both units are terminated concurrently.
3. SAFSTOR: In the second scenario, TMI-1 is placed into long-term storage. TMI-2 remains in storage until such time that decommissioning activities can be coordinated with Unit 1. As with the first scenario, termination of the licenses is coordinated.

The scenarios consider that Exelon Generation has extended the operating license at the adjacent Unit 1 to 2034. The scenarios are also based upon the premise that decommissioning work at Unit 2 would not begin prior to final shutdown of Unit 1 in 2034, consistent with the agreement between Exelon and FirstEnergy.

### Methodology

The methodology used to develop the estimates described within this document follows the basic approach originally presented in the cost estimating guidelines <sup>[9]</sup> developed by the Atomic Industrial Forum (now Nuclear Energy Institute). This reference

---

<sup>8</sup> Timelines for the Unit 1 decommissioning scenarios are included in Section 4 of this report.

<sup>9</sup> T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.



describes a unit factor method for determining decommissioning activity costs. The unit factors used in this analysis incorporate site-specific costs and the latest available information on worker productivity in decommissioning.

An activity duration critical path is used to determine the total decommissioning program schedule. The schedule is relied upon in calculating the carrying costs, which include program management, administration, field engineering, equipment rental, and support services such as quality control and security. This systematic approach for assembling decommissioning estimates ensures a high degree of confidence in the reliability of the resulting cost estimate.

### Contingency

Consistent with cost estimating practice, contingencies are applied to the decontamination and dismantling costs developed as "specific provision for unforeseeable elements of cost within the defined project scope, particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur."<sup>[10]</sup> The cost elements in the estimates are based on ideal conditions; therefore, the types of unforeseeable events that are almost certain to occur in decommissioning, based on industry experience, are addressed through a percentage contingency applied on a line-item basis. This contingency factor is a nearly universal element in all large-scale construction and demolition projects. It should be noted that contingency, as used in this analysis, does not account for price escalation and inflation in the cost of decommissioning over the time intervals identified for each scenario.

The use and role of contingency within decommissioning estimates is not a safety factor issue. Safety factors provide additional security and address situations that may never occur. Contingency funds, by contrast, are expected to be fully expended throughout the program. Inclusion of contingency is necessary to provide assurance that sufficient funding will be available to accomplish the intended tasks.

### Low-Level Radioactive Waste Disposal

The contaminated and activated material generated in the decontamination and dismantling of a commercial nuclear reactor is generally classified as low-level radioactive waste, although not all of the material is suitable for shallow-land disposal. With the passage of the "Low-Level Radioactive Waste Disposal Act" in 1980 and its

---

<sup>10</sup> Project and Cost Engineers' Handbook, Second Edition, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York, p. 239.

Amendments of 1985,<sup>[11]</sup> the states became ultimately responsible for the disposition of low-level radioactive waste generated within their own borders. It was expected that groups of states would combine together to jointly deal with their radioactive wastes; these organizations are referred to as waste disposal compacts.

Few approved facilities for the disposal of LLW are currently available. Construction of the newest facility, in Texas, is now complete and the facility was declared operational by the operator, Waste Control Specialists (WCS), in November 2011. The facility will be able to accept limited quantities of non-Compact waste; however, at this time the cost for non-Compact generators is being negotiated on an individual basis.

All options and services currently available to FirstEnergy for disposition of the various waste streams produced by the decommissioning process were considered. The majority of the low-level radioactive waste designated for direct disposal (Class A<sup>[12]</sup>) can be sent to EnergySolutions' facility in Clive, Utah. Therefore, disposal costs for Class A waste were based upon FirstEnergy's agreement with EnergySolutions. This facility is not licensed to receive the higher activity portion (Classes B and C) of the decommissioning waste stream.

The Texas facility is licensed to receive the higher activity waste forms (Classes B and C). As such, for this analysis, disposal costs for the Class B and C waste were based upon the preliminary and indicative information on the cost for such from WCS.

Waste exceeding Class C limits (limited to material closest to the reactor core, or material contaminated with spent fuel debris from the March 1979 accident) is generally not suitable for shallow-land disposal (i.e., low-level radioactive waste with concentrations of radionuclides that exceed the limits established by the NRC for Class C radioactive waste, referred to as Greater Than Class C (GTCC)). The Low-Level Radioactive Waste Policy Amendments Act of 1985 assigned the federal government the responsibility for the disposal of this material. The Act also stated that the beneficiaries of the activities resulting in the generation of such radioactive waste bear all reasonable costs of disposing of such waste. However, to date, the federal government has not identified a cost for disposing of GTCC or a schedule for acceptance.

---

<sup>11</sup> "Low-Level Radioactive Waste Policy Amendments Act of 1985," Public Law 99-240, January 15, 1986

<sup>12</sup> Waste is classified in accordance with U.S. Code of Federal Regulations, Title 10, Part 61.55

For purposes of this analysis, this material is packaged in the same multipurpose canisters used for spent fuel storage/transport (e.g., at TMI-1) and designated for geologic disposal. The GTCC is shipped directly to a disposal facility as it is generated.

A significant portion of the metallic waste generated during decommissioning may only be potentially contaminated by radioactive materials. This waste can be surveyed on site or shipped off site to licensed facilities for further analysis, for processing and/or for conditioning/recovery. Reduction in the volume of low-level radioactive waste requiring disposal in a licensed low-level radioactive waste disposal facility can be accomplished through a variety of methods, including analyses and surveys or decontamination to eliminate the portion of waste that does not require disposal as radioactive waste, compaction, incineration or metal melt. The estimates reflect the savings from waste recovery/volume reduction.

Material removed during decommissioning that is free of contamination will be designated for conventional disposal or reuse / recovery.

#### Fuel-Bearing Waste Management

There will be some wastes generated in the decommissioning of TMI-2 that are not suitable for shallow land burial and therefore cannot be shipped for disposal to EnergySolutions. This material, primarily associated with systems and structures contaminated with fuel debris, requires greater isolation from the environment. For estimating purposes, a geologic waste repository, or some interim storage facility, is assumed to be available for the disposal of this material.

Congress passed the "Nuclear Waste Policy Act" (NWPA) in 1982, assigning the federal government's long-standing responsibility for disposal of the spent nuclear fuel created by the commercial nuclear generating plants to the DOE. The DOE was to begin accepting spent fuel by January 31, 1998; however, to date no progress in the removal of spent fuel from commercial generating sites has been made.

Today, the country is at an impasse on high-level waste disposal, even with the License Application for a geologic repository submitted by the DOE to the NRC in 2008. The current administration has cut the budget for the repository program while promising to "conduct a comprehensive review of policies for managing the back end of the nuclear fuel cycle ... and make recommendations for a new plan."<sup>[13]</sup> Towards this goal, the administration appointed a Blue Ribbon Commission on America's Nuclear Future (Blue Ribbon Commission) to make recommendations for a new plan for nuclear waste disposal. The Blue Ribbon Commission's charter

---

<sup>13</sup> Blue Ribbon Commission on America's Nuclear Future Charter,  
<http://cybercemetery.unt.edu/archive/brc/20120620215336/http://brc.gov/index.php?q=page/charter>

includes a requirement that it consider “[o]ptions for safe storage of used nuclear fuel while final disposition pathways are selected and deployed.”<sup>[14]</sup>

On January 26, 2012, the Blue Ribbon Commission issued its “Report to the Secretary of Energy” containing a number of recommendations on nuclear waste disposal. Two of the recommendations that may impact decommissioning planning are:

- “[T]he United States [should] establish a program that leads to the timely development of one or more consolidated storage facilities”<sup>[15]</sup>
- “[T]he United States should undertake an integrated nuclear waste management program that leads to the timely development of one or more permanent deep geological facilities for the safe disposal of spent fuel and high-level nuclear waste.”<sup>[16]</sup>

In January 2013, the DOE issued the “Strategy for the Management and Disposal of Used Nuclear Fuel and High-Level Radioactive Waste,” in response to the recommendations made by the Blue Ribbon Commission and as “a framework for moving toward a sustainable program to deploy an integrated system capable of transporting, storing, and disposing of used nuclear fuel...”<sup>[17]</sup>

“With the appropriate authorizations from Congress, the Administration currently plans to implement a program over the next 10 years that:

- Sites, designs and licenses, constructs and begins operations of a pilot interim storage facility by 2021 with an initial focus on accepting used nuclear fuel from shut-down reactor sites;
- Advances toward the siting and licensing of a larger interim storage facility to be available by 2025 that will have sufficient capacity to provide flexibility in the waste management system and allows for acceptance of enough used nuclear fuel to reduce expected government liabilities; and

---

<sup>14</sup> *Ibid.*

<sup>15</sup> “Blue Ribbon Commission on America’s Nuclear Future, Report to the Secretary of Energy,” [http://www.brc.gov/sites/default/files/documents/brc\\_finalreport\\_jan2012.pdf](http://www.brc.gov/sites/default/files/documents/brc_finalreport_jan2012.pdf), p. 32, January 2012

<sup>16</sup> *Ibid.*, p.27

<sup>17</sup> “Strategy for the Management and Disposal of Used Nuclear Fuel and High-Level Radioactive Waste,” U.S. DOE, January 11, 2013

- Makes demonstrable progress on the siting and characterization of repository sites to facilitate the availability of a geologic repository by 2048.”<sup>[18]</sup>

Completion of the decommissioning process is dependent upon the DOE’s ability to remove spent fuel from the site in a timely manner. DOE’s repository program had assumed that spent fuel allocations would be accepted for disposal from the nation’s commercial nuclear plants, with limited exceptions, in the order (the “queue”) in which it was discharged from the reactor.<sup>[19]</sup>

The estimates for TMI-2 assume the timely removal of waste designated for geologic disposal, without the need for interim on site storage (once containerized).

### Site Restoration

The efficient removal of the contaminated materials at the site may result in damage to many of the site structures. Blasting, coring, drilling, and the other decontamination activities will substantially damage power block structures, potentially weakening the footings and structural supports. Prompt demolition once the license is terminated is clearly the most appropriate and cost-effective option. It is unreasonable to anticipate that these structures would be repaired and preserved after the radiological contamination is removed. The cost to dismantle site structures with a work force already mobilized is more efficient and less costly than if the process were deferred. Experience at shutdown generating stations has shown that plant facilities quickly degrade without maintenance, adding additional expense and creating potential hazards to the public and the demolition work force. Consequently, this analysis assumes that non-essential site structures within the restricted access area are removed. The site is then backfilled, graded and stabilized.

### Summary

The costs to decommission TMI-2 are evaluated for three decommissioning scenarios. Regardless of the timing of the decommissioning activities, the estimates assume the eventual removal of all the contaminated and neutron-activated plant components and

---

<sup>18</sup> Ibid., p.2

<sup>19</sup> U.S. Code of Federal Regulations, Title 10, Part 961.11, Article IV – Responsibilities of the Parties, B. DOE Responsibilities, 5.(a) ... DOE shall issue an annual acceptance priority ranking for receipt of SNF and/or HLW at the DOE repository. This priority ranking shall be based on the age of SNF and/or HLW as calculated from the date of discharge of such materials from the civilian nuclear power reactor. The oldest fuel or waste will have the highest priority for acceptance ...”

structural materials, such that the facility operator may then have unrestricted use of the site with no further requirement for an license.

The scenarios analyzed for the purpose of generating the estimates are described in Section 2. The assumptions are presented in Section 3, along with schedules of annual expenditures. The major cost contributors are identified in Section 6, with detailed activity costs, waste volumes, and associated manpower requirements delineated in Appendices C, D, and E. Cost summaries for the various scenarios are provided at the end of this section for the major cost components.

**DECON COST SUMMARY**  
**DECOMMISSIONING COST ELEMENTS**  
(thousands of 2013 dollars)

Cost Element	Total
Decontamination	35,403
Removal	189,064
Packaging	28,008
Transportation	26,427
Waste Disposal	276,112
Off-site Waste Processing	11,053
Program Management <sup>[1]</sup>	484,509
Security	55,590
Insurance and Regulatory Fees	15,766
Energy	18,061
Characterization and Licensing Surveys	10,844
Property Taxes	0
Miscellaneous Equipment	23,851
Site O&M	4,968
PDMS Monitoring	8,908
Total <sup>[2]</sup>	1,188,564

Cost Element	
NRC License Termination	1,149,098
Site Restoration	39,467
Total <sup>[2]</sup>	1,188,564

<sup>[1]</sup> Includes engineering costs

<sup>[2]</sup> Columns may not add due to rounding

**DELAYED DECON COST SUMMARY  
DECOMMISSIONING COST ELEMENTS**  
(thousands of 2013 dollars)

Cost Element	Total <sup>[1]</sup>
Decontamination	35,321
Removal	190,858
Packaging	28,007
Transportation	26,310
Waste Disposal	276,022
Off-site Waste Processing	11,053
Program Management <sup>[2]</sup>	472,755
Security	46,850
Insurance and Regulatory Fees	21,899
Energy	19,459
Characterization and Licensing Surveys	10,844
Property Taxes	0
Miscellaneous Equipment	26,259
Site O&M	4,968
PDMS Monitoring	6,949
Total <sup>[3]</sup>	1,177,554

Cost Element	
License Termination	1,139,536
Site Restoration	38,018
Total <sup>[3]</sup>	1,177,554

<sup>[1]</sup> Includes dormancy costs following TMI-1 shutdown in 2034

<sup>[2]</sup> Includes engineering costs

<sup>[3]</sup> Columns may not add due to rounding



**SAFSTOR COST SUMMARY  
DECOMMISSIONING COST ELEMENTS**  
(thousands of 2013 dollars)

Cost Element	Total <sup>[1]</sup>
Decontamination	35,286
Removal	196,595
Packaging	28,065
Transportation	26,298
Waste Disposal	275,884
Off-site Waste Processing	11,206
Program Management <sup>[2]</sup>	482,930
Security	56,699
Insurance and Regulatory Fees	41,497
Energy	28,227
Characterization and Licensing Surveys	10,844
Property Taxes	0
Miscellaneous Equipment	33,617
Site O&M	4,968
PDMS Monitoring	6,949
Total <sup>[3]</sup>	1,239,065

Cost Element	
License Termination	1,201,047
Site Restoration	38,018
Total <sup>[3]</sup>	1,239,065

<sup>[1]</sup> Includes dormancy costs following TMI-1 shutdown in 2034

<sup>[2]</sup> Includes engineering costs

<sup>[3]</sup> Columns may not add due to rounding

## **1. INTRODUCTION**

This report presents estimates of the cost to decommission the Three Mile Island Unit 2 nuclear unit (TMI-2) for the scenarios described in Section 2. This analysis relies upon site-specific, technical information, originally developed in an evaluation for the GPU Nuclear Corporation in 1995-96 <sup>[1]\*</sup>, and last updated in 2008 for FirstEnergy Corporation.<sup>[2]</sup> The analysis is designed to provide the FirstEnergy Corporation with sufficient information to assess its financial obligations, as they pertain to the eventual decommissioning of the nuclear unit. It is not a detailed engineering document, but a financial analysis prepared in advance of the detailed engineering that will be required to carry out the decommissioning.

### **1.1 OBJECTIVES OF STUDY**

The objective of this study was to prepare estimates of the cost, schedule, and waste volumes generated to decommission TMI-2, including all areas affected by the March 1979 accident.

Three decommissioning scenarios were evaluated for TMI-2. In the delayed scenarios (Delayed DECON and SAFSTOR) decommissioning activities are coordinated to some extent with the adjacent operating unit (TMI-1 or Unit 1). The scenarios consider that Exelon Generation has extended the operating license for Unit 1 to 2034. The three scenarios are also based upon the premise that decommissioning work at Unit 2 would not begin prior to final shutdown of Unit 1 in 2034, consistent with the agreement between Exelon and FirstEnergy.

**DECON** The adjacent TMI-1 is promptly decommissioned upon the scheduled cessation of operations in 2034. TMI-2 transitions from a Post-Defueling Monitored Storage status to decommissioning in 2040. The decommissioning program for TMI-2 runs independent from the TMI-1 decommissioning effort; license termination of Unit 2 occurs in 2053, approximately 10 years after Unit 1 completes its decommissioning program (exclusive of the on-site ISFSI operations for Unit 1 fuel).

**Delayed DECON** Decommissioning of TMI-2 commences upon the removal of TMI-1's spent fuel from the site in 2051. The decommissioning program for TMI-2 runs concurrently with the TMI-1 decommissioning effort and concludes with the termination of both licenses.

---

\* Annotated references for citations in Sections 1-6 are provided in Section 7.

SAFSTOR TMI-1 is placed into safe-storage with decommissioning deferred 60 years. TMI-2 remains in storage with decommissioning deferred until it can be sequenced with TMI-1. The decommissioning program for TMI-2 runs concurrently with the TMI-1 decommissioning effort and concludes with the termination of both licenses.

## **1.2 SITE DESCRIPTION**

TMI-2 is located on the northern-most section of Three Mile Island near the east shore of the Susquehanna River in Dauphin County, Pennsylvania. The station is comprised of two pressurized water reactors. This study specifically addresses the decommissioning requirements for Unit 2, although the timing of each scenario is dependent upon the associated activities at the adjacent unit.

The nuclear steam supply system (NSSS) consists of a pressurized water reactor rated at a core thermal power level of 2772 MWth with a corresponding turbine-generator gross output of 959 MWe. The NSSS consists of the reactor with two independent primary coolant loops, each containing two reactor coolant pumps and a steam generator. An electrically heated pressurizer and connecting piping complete the system. The system is housed within a steel-lined, post-tensioned concrete structure (reactor building) in the shape of a right, vertical cylinder with a hemispherical dome and a flat, reinforced concrete basemat. A welded steel liner plate, anchored to the inside face of the reactor building, serves as a leak-tight membrane.

Heat produced in the reactor was converted to electrical energy by the turbine generator system. This system converted the thermal energy of the steam into mechanical shaft power and then into electrical energy. The turbine-generator is a tandem-compound design, consisting of one double-flow, high pressure turbine and two double-flow, low-pressure turbines driving a directly coupled generator at 1800 rpm. The turbine operated in a closed feedwater cycle where steam was condensed, feedwater heated, and ultimately returned to the steam generators. Heat rejected in the main condensers was removed by the condenser circulating and river water systems.

The condenser circulating water was cooled in two hyperbolic natural draft cooling towers located to the east of the station. The towers provided the heat sink required for removal of waste heat in the power plant's thermal cycle. Cooling tower blowdown was discharged to the Susquehanna River.

TMI-2's operating license was issued on February 8, 1978, with commercial operation declared on December 30, 1978. On March 28, 1979, the unit

experienced an accident initiated by interruption of secondary feedwater flow. The steam generator boiled dry, resulting in the reduction of primary-to-secondary heat exchange. This caused an increase in the primary coolant temperature, creating a surge into the pressurizer, and an increase in system pressure. The pilot operated relief valve (PORV) opened to relieve the pressure, but failed to close when the pressure decreased. The reactor coolant pumps were turned off and a core heat-up began as the water level decreased to uncover the top of the core. The melting temperature of the zircaloy fuel cladding was exceeded, resulting in relocation of the molten zircaloy and some liquefied fuel to the lower core regions, solidifying near the coolant interface. Based on the end-state core and core support assembly configuration and supporting analysis of the degraded core heat-up, it is believed that as the crust failed, molten core material migrated to the lower internals. The majority of the molten material flowed down through the region of the southeastern assemblies and into the core bypass region. A portion of the molten core material flowed around the bypass region and migrated down into the lower internals and lower head region. Limited damage to the core support assembly occurred as the core material flowed to the lower plenum. It is estimated that about 17 - 20 tons of material relocated to the lower internals and lower head region. Several in-core instrument guide tubes were melted but overall vessel integrity was maintained throughout the accident.

As a result of this accident, small quantities of core debris and fission products were transported through the RCS and the reactor building as a result of the coolant flow through the PORV and the makeup and purification system (MU&P) during the accident. In addition, a small quantity of core debris was transported to the auxiliary and fuel handling buildings (AFHB) via the MU&P. Further spread of the debris also occurred as part of the post-accident water processing cleanup activities.

GPU Nuclear conducted a substantial program to defuel the reactor vessel and decontaminate the facility. As a result, TMI-2 has been placed in a safe, inherently stable condition suitable for long-term management, and any threat to the public health and safety has been eliminated. Fuel and core material removed in the defueling has been shipped off site. The current long-term management condition is termed Post-Defueling Monitored Storage (PDMS). The costs for maintaining TMI-2 in this state from 2013 until the shutdown of Unit 1 in 2034 (PDMS is continued until 2040 for the DECON scenario) is included in the cost estimates in this analysis.

Substantial contaminated areas still exist on site, as well as trace quantities of spent nuclear fuel (SNF). Several cubicles in the auxiliary and fuel handling buildings remain locked, and the basement of the reactor building has been

uninhabitable since the accident. The quantity of fuel remaining at TMI-2 is a small fraction of the initial fuel load; approximately 99% was successfully removed in the defueling. Additionally large quantities of radioactive fission products were released into various systems and structures. Most of this radioactivity was removed as part of the waste processing activities during the TMI-2 Clean-up Program which concluded with entry into Post-Defueling Monitored Storage in December 1993. Significant quantities of radioactive fission products were removed from the reactor coolant system in preparation for the PDMS. However, the remaining 1% of the fuel and the remaining fission products pose unique problems in completing the decommissioning of TMI-2. A summary of the quantity and suspected location of the remaining fuel debris is provided in Tables 1.1 through 1.3.

### **1.3 REGULATORY GUIDANCE**

The Nuclear Regulatory Commission (NRC or Commission) provided initial decommissioning requirements in its rule "General Requirements for Decommissioning Nuclear Facilities," issued in June 1988 [3]. This rule set forth financial criteria for decommissioning licensed nuclear power facilities. The regulation addressed decommissioning planning needs, timing, funding methods, and environmental review requirements. The intent of the rule was to ensure that decommissioning would be accomplished in a safe and timely manner and that adequate funds would be available for this purpose. Subsequent to the rule, the NRC issued Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors," [4] which provided additional guidance to the licensees of nuclear facilities on the financial methods acceptable to the NRC staff for complying with the requirements of the rule. The regulatory guide addressed the funding requirements and provided guidance on the content and form of the financial assurance mechanisms indicated in the rule.

The rule defined three decommissioning alternatives as being acceptable to the NRC: DECON, SAFSTOR, and ENTOMB. The DECON alternative, the option evaluated for this analysis, assumes that any contaminated or activated portion of the plant's systems, structures, and facilities are removed or decontaminated to levels that permit the site to be released for unrestricted use shortly after the cessation of plant operations. The rule also placed limits on the time allowed to complete the decommissioning process. For SAFSTOR, the process is restricted in overall duration to 60 years, unless it can be shown that a longer duration is necessary to protect public health and safety. The guidelines for ENTOMB are similar, providing the NRC with both sufficient leverage and flexibility to ensure that these deferred options are only used in situations where it is reasonable and consistent with the definition of

decommissioning. At the conclusion of a 60-year dormancy period (or longer for ENTOMB if the NRC approves such a case), the site would still require significant remediation to meet the unrestricted release limits for license termination. To use a decommissioning scenario in which the license has not been terminated within 60 years of the final shutdown date, FirstEnergy will need Commission approval pursuant to 10 CFR 50.82(a)(3) for completion of decommissioning beyond 60 years.

The ENTOMB alternative has not been viewed as a viable option for power reactors due to the significant time required to isolate the long-lived radionuclides for decay to permissible levels. However, with recent rulemaking permitting the controlled release of a site, the NRC has re-evaluated this alternative.<sup>[5]</sup> The resulting feasibility study, based upon an assessment by Pacific Northwest National Laboratory, concluded that the method did have conditional merit for some, if not most, reactors.<sup>[6]</sup> However, the staff also found that additional rulemaking would be needed before this option could be treated as a generic alternative. Rulemaking has been deferred pending the completion of additional research studies, e.g., on engineered barriers. However, this study assumes that the ENTOMB alternative is a viable option for TMI-2 and that a storage period of 100 years would be acceptable.

The NRC published revisions to the general requirements for decommissioning nuclear power plants in 1996.<sup>[7]</sup> When the regulations were adopted in 1988, it was assumed that the majority of licensees would decommission at the end of the facility's licensed life. Since that time, several licensees permanently and prematurely ceased operations. Exemptions from certain operating requirements were required once the reactor was defueled to facilitate the decommissioning. Each case was handled individually, without clearly defined generic requirements. The NRC amended the decommissioning regulations in 1996 to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process. The new amendments allow for greater public participation and better define the transition process from operations to decommissioning.

#### 1.3.1 Nuclear Waste Policy Act

Congress passed the Nuclear Waste Policy Act<sup>[8]</sup> in 1982, assigning the federal government's long-standing responsibility for disposal of the spent nuclear fuel created by the commercial nuclear generating plants to the DOE. The DOE was to begin accepting spent fuel by January 31, 1998; however, to date no progress in the removal of spent fuel from commercial generating sites has been made.

Today, the country is at an impasse on high-level waste disposal, even with the License Application for a geologic repository submitted by the DOE to the NRC in 2008. The current administration has cut the budget for the repository program while promising to “conduct a comprehensive review of policies for managing the back end of the nuclear fuel cycle ... and make recommendations for a new plan.”<sup>[9]</sup> Towards this goal, the administration appointed a Blue Ribbon Commission on America’s Nuclear Future (Blue Ribbon Commission) to make recommendations for a new plan for nuclear waste disposal. The Blue Ribbon Commission’s charter includes a requirement that it consider “[o]ptions for safe storage of used nuclear fuel while final disposition pathways are selected and deployed.”

On January 26, 2012, the Blue Ribbon Commission issued its “Report to the Secretary of Energy” containing a number of recommendations on nuclear waste disposal. Two of the recommendations that may impact decommissioning planning are:

- “[T]he United States [should] establish a program that leads to the timely development of one or more consolidated storage facilities”<sup>[10]</sup>
- “[T]he United States should undertake an integrated nuclear waste management program that leads to the timely development of one or more permanent deep geological facilities for the safe disposal of spent fuel and high-level nuclear waste.”

In January 2013, the DOE issued the “Strategy for the Management and Disposal of Used Nuclear Fuel and High-Level Radioactive Waste,” in response to the recommendations made by the Blue Ribbon Commission and as “a framework for moving toward a sustainable program to deploy an integrated system capable of transporting, storing, and disposing of used nuclear fuel...”<sup>[11]</sup>

“With the appropriate authorizations from Congress, the Administration currently plans to implement a program over the next 10 years that:

- Sites, designs and licenses, constructs and begins operations of a pilot interim storage facility by 2021 with an initial focus on accepting used nuclear fuel from shut-down reactor sites;
- Advances toward the siting and licensing of a larger interim storage facility to be available by 2025 that will have sufficient capacity to provide flexibility in the waste management system

and allows for acceptance of enough used nuclear fuel to reduce expected government liabilities; and

- Makes demonstrable progress on the siting and characterization of repository sites to facilitate the availability of a geologic repository by 2048.”

Completion of the decommissioning process is dependent upon the DOE's ability to remove spent fuel from the site in a timely manner. DOE's repository program had assumed that spent fuel allocations would be accepted for disposal from the nation's commercial nuclear plants, with limited exceptions, in the order (the “queue”) in which it was discharged from the reactor.<sup>[12]</sup>

The estimates for TMI-2 assume the timely removal of waste designated for geologic disposal, without the need for interim on site storage (once containerized).

### 1.3.2 Low-Level Radioactive Waste Acts

The contaminated and activated material generated in the decontamination and dismantling of a commercial nuclear reactor is generally classified as low-level radioactive waste, although not all of the material is suitable for shallow-land disposal. With the passage of the “Low-Level Radioactive Waste Disposal Act”<sup>[13]</sup> in 1980 and its Amendments of 1985, <sup>[14]</sup> the states became ultimately responsible for the disposition of low-level radioactive waste generated within their own borders. It was expected that groups of states would combine together to jointly deal with their radioactive wastes; these organizations are referred to as waste disposal compacts.

Few approved facilities for the disposal of LLW are currently available. Construction of the newest facility, in Texas, is now complete and the facility was declared operational by the operator, Waste Control Specialists (WCS), in November 2011. The facility will be able to accept limited quantities of non-Compact waste; however, at this time the cost for non-Compact generators is being negotiated on an individual basis.

All options and services currently available to FirstEnergy for disposition of the various waste streams produced by the decommissioning process were considered. The majority of the low-level radioactive waste designated for direct disposal (Class A <sup>[15]</sup>) can be sent to EnergySolutions' facility in Clive, Utah. Therefore, disposal costs for Class A waste were based upon FirstEnergy's agreement with



*EnergySolutions*. This facility is not licensed to receive the higher activity portion (Classes B and C) of the decommissioning waste stream.

The Texas facility is licensed to receive the higher activity waste forms (Classes B and C). As such, for this analysis, disposal costs for the Class B and C waste were based upon the preliminary and indicative information on the cost for such from WCS.

Waste exceeding Class C limits (limited to material closest to the reactor core, or material contaminated with spent fuel debris from the March 1979 accident) is generally not suitable for shallow-land disposal (i.e., low-level radioactive waste with concentrations of radionuclides that exceed the limits established by the NRC for Class C radioactive waste, referred to as Greater Than Class C (GTCC)). The Low-Level Radioactive Waste Policy Amendments Act of 1985 assigned the federal government the responsibility for the disposal of this material. The Act also stated that the beneficiaries of the activities resulting in the generation of such radioactive waste bear all reasonable costs of disposing of such waste. However, to date, the federal government has not identified a cost for disposing of GTCC or a schedule for acceptance.

For purposes of this analysis, this material is packaged in the same multipurpose canisters used for spent fuel storage/transport (e.g., at TMI-1) and designated for geologic disposal. The GTCC is shipped directly to a disposal facility as it is generated.

A significant portion of the metallic waste generated during decommissioning may only be potentially contaminated by radioactive materials. This waste can be surveyed on site or shipped off site to licensed facilities for further analysis, for processing and/or for conditioning/recovery. Reduction in the volume of low-level radioactive waste requiring disposal in a licensed low-level radioactive waste disposal facility can be accomplished through a variety of methods, including analyses and surveys or decontamination to eliminate the portion of waste that does not require disposal as radioactive waste, compaction, incineration or metal melt. The estimates reflect the savings from waste recovery/volume reduction.

### 1.3.3 Radiological Criteria for License Termination

In 1997, the NRC published Subpart E, "Radiological Criteria for License Termination," amending 10 CFR §20. This subpart provides radiological criteria for releasing a facility for unrestricted use. The regulation states that the site can be released for unrestricted use if radioactivity levels are such that the average member of a critical group would not receive a Total Effective Dose Equivalent (TEDE) in excess of 25 millirem per year, and provided that residual radioactivity has been reduced to levels that are As Low As Reasonably Achievable (ALARA). The decommissioning estimates for TMI-2 assume that the site will be remediated to a residual level consistent with the NRC-prescribed level.

It should be noted that the NRC and the Environmental Protection Agency (EPA) differ on the amount of residual radioactivity considered acceptable in site remediation. The EPA has two limits that apply to radioactive materials. An EPA limit of 15 millirem per year is derived from criteria established by the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA or Superfund).<sup>[16]</sup> An additional limit of 4 millirem per year, as defined in 40 CFR §141.16, is applied to drinking water.<sup>[17]</sup>

On October 9, 2002, the NRC signed an agreement with the EPA on the radiological decommissioning and decontamination of NRC-licensed sites. The Memorandum of Understanding (MOU) <sup>[18]</sup> provides that EPA will defer exercise of authority under CERCLA for the majority of facilities decommissioned under NRC authority. The MOU also includes provisions for NRC and EPA consultation for certain sites when, at the time of license termination, (1) groundwater contamination exceeds EPA-permitted levels; (2) NRC contemplates restricted release of the site; and/or (3) residual radioactive soil concentrations exceed levels defined in the MOU.

The MOU does not impose any new requirements on NRC licensees and should reduce the involvement of the EPA with NRC licensees who are decommissioning. Most sites are expected to meet the NRC criteria for unrestricted use, and the NRC believes that only a few sites will have groundwater or soil contamination in excess of the levels specified in the MOU that trigger consultation with the EPA. However, if there are other hazardous materials on the site, the EPA may be involved in the cleanup. As such, the possibility of dual regulation remains for certain licensees. The present study does not include any costs for this occurrence.

**TABLE 1.1**  
**INVENTORY OF SPENT FUEL**  
**AUXILIARY AND FUEL HANDLING BUILDINGS <sup>[19]</sup>**

<u>Cubical</u>	<u>Location</u>	<u>SNF</u> <u>Quantity (g)</u>
AX004	Seal Injection Valve Room	30
AX006	Make-up Pump 1B	70
AX007	Make-up Pump 1A	230
AX015a	Cleanup Filters	50
AX015b	Cleanup Filters	50
AX114	MU&P Demineralizer 1A	1,060
AX115	MU&P Demineralizer 1B	130
AX019	Waste Disposal Liquid Valve Room	10
FH001	MU Suction Valve Room	460
AX012	AB Sump Tank Room	100
AX020	Reactor Coolant Bleed Tank 1B	1,750
AX020	Reactor Coolant Bleed Tank 1C	1,750
AX021	Reactor Coolant Bleed Tank 1A	310
AX024	AB Sump Filters	20
AX112	Seal Return Coolers and Filter Room	300
AX116	Makeup Tank Room	310
AX117	MU&P Filter Room	60
AX131	Miscellaneous Waste Tank Room	100
AX128	Instrument and Valve Room	10
AX218	Concentrated Waste Storage Tanks	10
AX501	RB Spray Pump 1A	10
AX502	RB Spray Pump 1B	10
AX503	DHR Pump 1A	10
AX504	DHR Pump 1B	10
FH003a	MU Discharge Valves	10
FH003b	MU Discharge Valves	100
FH004	Westinghouse Valve Room	160

TABLE 1.1  
(continued)  
INVENTORY OF SPENT FUEL  
AUXILIARY AND FUEL HANDLING BUILDINGS

<u>Cubical</u>	<u>Location</u>	SNF <u>Quantity (g)</u>
FH101	MU&P Valve Room	320
FH112	Annulus	10
FH109	Spent Fuel Pool "A"	3,800
	Embedded Valves & Piping (MU System)	170
	Embedded Valves & Piping (WDL System)	40
	<b>TOTAL</b>	<hr/> <b>11,460</b>

**TABLE 1.2  
INVENTORY OF SPENT FUEL  
REACTOR BUILDING**

<u>Area/Component</u>	<u>SNF Quantity (g)</u>
Reactor Vessel	925,000
RV Head Assembly	1,300
RV Upper Plenum Assembly	2,100
Fuel Transfer Canal	18,900
Core Flood System	4,900
"A" D-ring	21,000
Upper Endfitting Storage Area	5,900
Reactor Coolant Drain Tank	100
Letdown Coolers	3,700
RB Basement and Sump	1,300
Tool Decontamination Facility (347')	100
Defueling Water Cleanup System	3,700
Defueling Tool Rack	600
Temp React Vessel Filtration System	4,400
RB Drains	5,100
<b>Total</b>	<b>998,100</b>

TABLE 1.3  
INVENTORY OF SPENT FUEL  
REACTOR COOLANT SYSTEM

<u>Component</u>	<u>SNF Quantity (g)</u>
Pressurizer (including surge line)	500
Decay Heat Drop Line	1,500
<b>"A" SIDE</b>	
OTSG Upper Tubesheet	1,400
Tube Bundle	1,700
Lower Head and J-legs	4,000
Hot Legs	900
Cold Legs	7,200
Core Flood Line	600
<b>"B" SIDE</b>	
OTSG Upper Tubesheet	36,000
Tube Bundle	9,100
Lower Head and J-legs	10,100
Hot Legs	1,800
Cold Legs	2,400
Core Flood Line	400
RCS Surface Films	4,600
Reactor Coolant Pumps	6,200
<b>Total</b>	<b>88,400</b>

## **2. DECOMMISSIONING ALTERNATIVES**

Detailed cost estimates were developed to decommission TMI-2 for three scenarios. Although the alternatives differ with respect to technique, process, cost, and schedule, they attain the same result: the ultimate release of the site for unrestricted use.

Three decommissioning cost scenarios were evaluated for the nuclear unit. The scenarios assume that Exelon will operate the adjacent Unit 1 until its license expiration date in 2034. The scenarios are defined as follows:

1. **DECON:** The adjacent TMI-1 is promptly decommissioned upon the scheduled cessation of operations in 2034. TMI-2 transitions from a PDMS status to decommissioning in 2040. The decommissioning program for TMI-2 runs concurrently with the TMI-1 decommissioning effort; license termination of Unit 2 occurs in 2053, approximately 10 years after Unit 1 completes its decommissioning program (exclusive of the on-site ISFSI operations for Unit 1 fuel).
2. **Delayed DECON:** Unit 1 defers decommissioning until its spent fuel has been removed from the site. This scenario assumes that the decontamination and dismantling activities at TMI-2 are synchronized with the adjacent unit such that the licenses for both units are terminated concurrently.
3. **SAFSTOR:** TMI-1 is placed into long-term storage. TMI-2 remains in storage until such time that decommissioning activities can be coordinated with Unit 1. As with the first scenario, termination of the licenses is coordinated.

The nomenclature for these three scenarios is consistent with the Unit 1 decommissioning cost estimate. For each of the scenarios, Post-Defueling Monitored Storage (PDMS) costs of approximately \$3.1 million per year have been included from 2013 until Unit 1 shutdown in 2034 (DECON continues the PDMS charges until 2040). Other decommissioning costs (including dormancy costs for the Delayed DECON and SAFSTOR scenarios) are only accrued following TMI-1 shutdown.

The conceptual approach that the NRC has described in its regulations divides decommissioning into three phases. The initial phase addresses the transition of reactor operations (i.e., power production) to facility de-activation and closure. The second phase encompasses activities during the storage period or during major decommissioning activities, or a combination of the two. The third phase pertains to the activities involved in license termination.

The decommissioning estimates developed for TMI-2 are also divided into phases or periods; however, demarcation of the phases is based upon major milestones within the project or significant changes in the projected expenditures.

The following sections describe the basic activities associated with each alternative. The three scenarios are essentially identical; all being variations of the NRC's SAFSTOR scenario following a dormancy period. The technical assumptions are unchanged with the only difference in the second and third scenarios being the delay in start of decommissioning expenditures and the additional storage cost during the delay period.

Although detailed procedures for each activity identified are not provided, and the actual sequence of work may vary, the activity descriptions provide a basis not only for estimating but also for the expected scope of work, i.e., engineering and planning at the time of decommissioning.

The conceptual approach that the NRC has described in its regulations divides decommissioning into three phases. The initial phase commences with the effective date of permanent cessation of operations and involves the transition of both nuclear unit and licensee from reactor operations (i.e., power production) to facilitate de-activation and closure. This phase was completed when TMI-2 began the PDMS phase; the plant is in SAFSTOR dormancy.

The second phase encompasses activities during the storage period or during major decommissioning activities, or a combination of the two. The third phase pertains to the activities involved in license termination. The decommissioning estimates developed for TMI-2 are also divided into phases or periods; however, demarcation of the phases is based upon major milestones within the project or significant changes in the projected expenditures.

## **2.1 DECON**

As stated previously, the naming convention of the three Unit 2 decommissioning scenarios is consistent with the Unit 1 decommissioning scenarios. This scenario runs concurrent with the Unit 1 DECON scenario, and therefore is referred to as DECON for Unit 2, even though the unit is currently in SAFSTOR dormancy.

### **2.1.1 Period 2 - Dormancy**

The second phase identified by the NRC in its rule addresses licensed activities during a storage period and is applicable to the PDMS phase from 2013 to 2040 for the DECON alternative (the delayed scenarios



terminate PDMS with Unit 1 shutdown, and begin a standard SAFSTOR dormancy program in 2034). TMI-2 has been in a dormant condition since entry into PDMS in December 1993. This estimate includes the yearly \$3.1 million PDMS costs for maintaining TMI-2 until the start of decommissioning in 2040.

Dormancy activities during PDMS include a 24-hour security force (primarily provided by the operating Unit 1), preventive and corrective maintenance on security systems, area lighting, general building maintenance, heating and ventilation of buildings, routine radiological inspections of contaminated structures, maintenance of structural integrity, and a site environmental and radiation monitoring program. Maintenance personnel perform equipment maintenance, inspection activities, routine services to maintain safe conditions, adequate lighting, heating, and ventilation, and periodic preventive maintenance on essential site services. Most site labor activities are provided by Exelon personnel under contract to FirstEnergy.

An environmental surveillance program is carried out during the dormancy period to ensure that releases of radioactive material to the environment are prevented and/or detected and controlled. Appropriate emergency procedures are established and initiated for potential releases that exceed prescribed limits.

Security during the dormancy period is conducted primarily to prevent unauthorized entry and to protect the public from the consequences of its own actions. Security is provided by fences, sensors, alarms, and other surveillance equipment. Fire and radiation alarms are also monitored.

#### 2.1.2 Period 3 - Preparations

Preparations include the planning for the removal of the remaining fuel-bearing components, decontamination of the structures and the dismantling of the remaining equipment and facilities. Typically, the process is described within a Post-Shutdown Decommissioning Activities Report (PSDAR) or a Decommissioning Plan (DP). Although the exact format and content of the decommissioning planning document has not been identified, as a minimum Technical Specification 3.2.1.1 requires NRC approval prior to removal of greater than 42 kilograms of fuel from the reactor vessel. Thus in addition to the planning document, changes may be required to the existing technical specifications prior to the start of major decommissioning activities.

### Engineering and Planning

The decommissioning program outlined in the PSDAR or DP will be designed to accomplish the required tasks within the ALARA guidelines (as defined in 10 CFR §20) for protection of personnel from exposure to radiation hazards. It will also address the continued protection of the health and safety of the public and the environment during the dismantling activity. Consequently, with the development of the decommissioning plan, activity specifications, cost-benefit and safety analyses, and work packages and procedures, would be assembled to support the proposed decontamination and dismantling activities.

The estimate assumes that FirstEnergy will provide project oversight. However, the majority of the professional, managerial, technical and administrative support staff will be provided by a decommissioning operations contractor (DOC).

### Site Preparations

In preparation for active decommissioning, the following activities are initiated:

- Characterization of the site and surrounding environs. This includes radiation surveys of the reactor building including: the basement and elevator block wall area, areas surrounding major components (including the reactor vessel and its internals, steam generators), internal piping, and primary shield cores. Surveys of the auxiliary and fuel handling building with emphasis on areas with known and potential alpha contamination and known fission products. Surveys and sample analysis will also be performed on exterior buildings, land areas surrounding the facility, subsurface soil and groundwater.
- Specification of transport and disposal requirements for highly radioactive waste and/or hazardous waste, including shielding and waste stabilization.
- Development of procedures for occupational exposure control, control and release of liquid and gaseous effluent, processing of radwaste (including dry-active waste, resins, filter media, metallic and non-metallic components generated in decommissioning), site security and emergency programs, and industrial safety.

### 2.1.3 Period 4 - Decommissioning Operations

This period includes the physical decommissioning activities associated with the removal and disposal of contaminated and highly radioactive components and structures, including the successful termination of the license. Significant decommissioning activities in this phase include:

- Construction of temporary facilities and/or modification of existing facilities to support dismantling activities. This may include a centralized processing area to facilitate equipment removal and component preparations for off-site disposal.
- Refurbishment of the containment air control envelope building located outside the reactor building equipment hatch. A prefabricated metal containment building located on the 305' level of the reactor building will be required for the handling of highly contaminated material being removed from the basement or the operating deck elevations.
- Modification of the containment structure to facilitate handling of large equipment. This will include an evaluation to determine whether a temporary crane should be installed or whether the existing polar crane should be refurbished (the reactor vessel head will be the heaviest lift under the current removal scenario with the in-situ segmentation of the reactor vessel and steam generators).
- Reconfiguration and modification of site structures and facilities as needed to support decommissioning operations. This may include the upgrading of roads and rail facilities (on- and off-site) to facilitate hauling and transport. Modifications may also be required to the refueling area of the building to support the segmentation of the reactor vessel internals and component extraction.
- Design and fabrication of temporary and permanent shielding to support removal and transportation activities, construction of contamination control envelopes, and the procurement of specialty tooling.
- Procurement (lease or purchase) of shipping canisters, cask liners, and industrial packages.
- Decontamination of components and structures as required to control (minimize) worker exposure.
- Decontamination of the reactor building so as to reduce working area dose rates and improve working conditions. The reactor building basement is known to be highly contaminated and will

require remote operations and tooling for the initial decontamination effort.

- Inventory, decontamination and removal of legacy equipment inventory left over from the defueling campaign.
- Installation of a water processing system to filter and treat water from the reactor coolant system and fuel handling pool.
- Removal of piping and components no longer essential to support decommissioning operations.
- Removal of control rod drive housings and the head service structure from reactor vessel head. Segmentation of the vessel closure head.
- Segmentation of the upper internals assemblies. The plenum is currently stored in the fuel transfer canal. Segmentation will maximize the loading of the shielded transport casks, i.e., by weight and activity. The operations are conducted under water using remotely operated tooling and contamination controls.
- Disassembly and segmentation of the remaining reactor internals, including the core former and lower core support assembly. All internals components below the top of the fuel are expected to exceed Class C disposal requirements due to fuel contamination. As such, the segments will be packaged in modified fuel storage canisters for geologic disposal.
- Segmentation of the reactor vessel. A shielded platform is installed for segmentation as cutting operations are performed in-air using remotely operated equipment within a contamination control envelope. The water level is maintained just below the cut to minimize the working area dose rates. Segments are transferred in-air to containers that are stored under water, for example, in an isolated area of the refueling canal.
- Removal of the steam generators and pressurizer for material recovery and controlled disposal. Due to the high internal and external radioactivity, these components can not serve as their own shipping containers. The steam generators are assumed to be segmented in-place. The pressurizer is assumed to be cut in half and shipped in a sealed and shielded shipping and burial container. Steel shielding will be added, as necessary, to those external areas of the package to meet transportation limits and regulations.
- Removal of free standing concrete structures in the reactor building.

- Removal of the remaining internal structures within the reactor building including: the polar crane, inner pools and wall liners, biological shield, D-rings, floors and walls.

At least two years prior to the anticipated date of license termination, a License Termination Plan (LTP) is required. Submitted as a supplement to the FSAR or its equivalent, the plan must include: a site characterization, description of the remaining dismantling activities, plans for site remediation, procedures for the final radiation survey, designation of the end use of the site, an updated cost estimate to complete the decommissioning, and any associated environmental concerns. The NRC will notice the receipt of the plan, make the plan available for public comment, and schedule a local hearing. LTP approval will be subject to any conditions and limitations as deemed appropriate by the Commission. The licensee may then commence with the final remediation of site facilities and services, including:

- Removal of remaining plant systems and associated components as they become nonessential to the decommissioning program or worker health and safety (e.g., waste collection and treatment systems, electrical power and ventilation systems).
- Processing of the structural material in the reactor, auxiliary and fuel handling buildings. Approximately 90% of the concrete removed at this stage is assumed to meet free release criteria. The remainder is sent to a waste processor. The free-released concrete is available as fill. Excess concrete is disposed of in an industrial landfill.
- Removal of contaminated yard piping and any contaminated soil.
- Transfer of greater-than-Class C (GTCC) material to the DOE.
- Surveys of the decontaminated areas not designated for complete removal and disposal.
- Remediation and removal of the contaminated equipment and material from the auxiliary and fuel buildings and any other contaminated facility. Certain areas in the auxiliary and spent fuel handling buildings contain very high contamination and radiation levels and will require additional resource and increased radiological protection to complete the decontamination. Radiation and contamination controls will be utilized until residual levels indicate that the structures and equipment can be released for unrestricted access and conventional demolition. This activity may necessitate the dismantling and disposition of most of the systems

and components (both clean and contaminated) located within these buildings. This activity facilitates surface decontamination and subsequent verification surveys required prior to obtaining release for demolition.

- Most of the power block structures (Reactor, Auxiliary and Fuel Handling) will be removed to below the building foundations / basemat to ensure that no radioactive material remains on site.
- Material that is designated as scrap or general disposal (survey and release) is transferred to a designed waste processing vendor for a confirmatory survey and, if permitted, released for unrestricted disposition. Contaminated material is characterized and segregated for additional off-site processing (disassembly, chemical cleaning, volume reduction, and waste treatment), and/or packaged for controlled disposal at a low-level radioactive waste disposal facility.

Incorporated into the LTP is the Final Survey Plan. This plan identifies the radiological surveys to be performed once the decontamination activities are completed and is developed using the guidance provided in the "Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM)."<sup>[20]</sup> This document incorporates the statistical approaches to survey design and data interpretation used by the EPA. It also identifies state-of-the-art, commercially available instrumentation and procedures for conducting radiological surveys. Use of this guidance ensures that the surveys are conducted in a manner that provides a high degree of confidence that applicable NRC criteria are satisfied. Once the survey is complete, the results are provided to the NRC in a format that can be verified. The NRC then reviews and evaluates the information, performs an independent confirmation of radiological site conditions, and makes a determination on final termination of the license.

The NRC will terminate the license if it determines that site remediation has been performed in accordance with the LTP, and that the terminal radiation survey and associated documentation demonstrate that the facility is suitable for release.

#### 2.1.4 Period 5 - Site Restoration

Following completion of decommissioning operations, site restoration activities will begin. Efficient removal of the contaminated materials and verification that residual radionuclide concentrations are below the NRC limits will result in substantial damage to many of the remaining structures.

This cost study presumes that non-essential structures and site facilities are dismantled as a continuation of the decommissioning activity. Foundations and exterior walls are removed to a nominal depth of three feet below grade. The three-foot depth allows for the placement of gravel for drainage, as well as topsoil, so that vegetation can be established for erosion control. Site areas affected by the dismantling activities are restored and the plant area graded as required to prevent ponding and inhibit the refloating of subsurface materials.

Concrete rubble produced by demolition activities is processed to remove rebar and miscellaneous embedments. The processed material is then used on site to backfill voids. Excess materials are trucked to an off-site area for disposal as construction debris.

## **2.2 SAFSTOR and Delayed DECON**

The decontamination and dismantling activities in this scenario are identical to those described in Section 2.1 for DECON. However, the start of active decommissioning is deferred to coordinate with the timing of the Unit 1 Delayed DECON and SAFSTOR scenarios. As such, the presence of the dormancy period incurs storage costs (correspondingly greater for the SAFSTOR scenario, with its longer dormancy period).

While it is expected that radiation dose levels will decrease over the duration of the longer dormancy period, the nature of radionuclides involved and the difficulties in working in plant areas contaminated with these radionuclides will require similar operational and radiological controls to those envisioned for earlier scenario. As such, there have been no changes incorporated into the costs to perform the field decommissioning activities identified in Section 2.1 for this scenario. Note that, with Unit 1 permanently shut down, there are dormancy costs for Unit 2 included in the estimate following the cessation of the PDMS charges in 2034.

### **3. COST ESTIMATE**

The cost estimates prepared for decommissioning TMI-2 consider the radiological status, unique conditions of the site, including the NSSS, power generation systems, support services, site buildings, and ancillary facilities. The basis of the estimates, including the sources of information relied upon, the estimating methodology employed, site-specific considerations, and other pertinent assumptions, is described in this section.

#### **3.1 BASIS OF ESTIMATE**

The estimates rely upon site-specific, technical information originally developed in an evaluation prepared for the GPU Nuclear Corporation in 1995-96, and last updated for FirstEnergy in 2008. The information was reviewed for the current analysis and updated as deemed appropriate. The site-specific considerations and assumptions used in the previous evaluation were also revisited. Modifications were incorporated where new information was available or experience from ongoing decommissioning programs provided viable alternatives or improved processes.

Some of the technical assumptions that were used are due to the unique nature and characteristics of the plant as a result of the March 1979 accident. Following the accident, TMI-2 was defueled and extensive decontamination activities were performed. This successfully removed approximately 99% of the original fuel and resulting fuel debris. Removal of the residual 1% was neither cost effective nor warranted due to the high radiation fields in the reactor building and adjoining auxiliary and fuel handling buildings. The remaining equipment and components containing spent nuclear fuel (SNF) will be removed, sealed and/or encapsulated in preparation for disposal during the decommissioning program.

#### **3.2 METHODOLOGY**

The methodology used to develop the estimates follows the basic approach originally presented in the AIF/NESP-036 study report, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates,"<sup>[21]</sup> and the DOE "Decommissioning Handbook."<sup>[22]</sup> These documents present a unit factor method for estimating decommissioning activity costs, which simplifies the estimating calculations. Unit factors for concrete removal (\$/cubic yard), steel removal (\$/ton), and cutting costs (\$/inch) were developed using local labor rates. The activity-dependent costs were estimated with the item quantities (cubic yards and tons), developed from



plant drawings and inventory documents. Removal rates and material costs for the conventional disposition of components and structures relied upon information available in the industry publication, "Building Construction Cost Data," published by R.S. Means.<sup>[23]</sup>

This analysis reflects lessons learned from TLG's involvement in the Shippingport Station Decommissioning Project, completed in 1989, as well as the decommissioning of the Cintichem reactor, hot cells, and associated facilities, completed in 1997. In addition, the planning and engineering for the Pathfinder, Shoreham, Rancho Seco, Trojan, Yankee Rowe, Big Rock Point, Maine Yankee, Humboldt Bay-3, Oyster Creek, Connecticut Yankee, and San Onofre-1 nuclear units have provided additional insight into the process, the regulatory aspects, and the technical challenges of decommissioning commercial nuclear units.

The unit factor method provides a demonstrable basis for establishing reliable cost estimates. The detail provided in the unit factors, including activity duration, labor costs (by craft), and equipment and consumable costs, ensures that essential elements have not been omitted. Appendix A presents the detailed development of a typical unit factor. Appendix B provides the values contained within one set of factors developed for this analysis.

#### Work Difficulty Factors

TLG has historically applied work difficulty adjustment factors (WDFs) to account for the inefficiencies in working in a power plant environment and increase the time required to perform the activity. WDFs were assigned to each unique set of unit factors, commensurate with the inefficiencies associated with working in confined, hazardous environments. The WDF sets were developed considering the extremely difficult working conditions associated with working in high radiation areas and in areas with high alpha particle contamination. The same work difficulty factor sets were used for all three scenarios. This assumption was based upon the relatively high levels of long-lived radioactivity that exists today plus the high levels of alpha contamination.

The factors and their associated range of values were developed in conjunction with the AIF/NESP-036 study. The application of the factors is discussed in more detail in that publication. Given the radiological status of some areas at TMI-2, the range of the WDF's was increased. The ranges used for the WDFs are identified in the following table.

### Work Difficulty Factors

	Other Power Block	Fuel/Aux Buildings	Reactor Building	NSSS Components
Access	20%	30%	30%	40%
Respiratory Protection	0-25%	200%	50%	200%
Radiation/ALARA	10-25%	40%	40%	100%
Protective Clothing	0-30%	50%	50%	50%
Work Break	8.33%	8.33%	8.33%	8.33%

### Scheduling Program Durations

The unit factors, adjusted by the WDFs as described above, are applied against the inventory of materials to be removed in the radiologically controlled areas.

As shown above, higher WDF's sets were assigned to systems located in the reactor building and to systems which contain SNF and/or high levels of radioactive materials. The resulting man-hours, or crew-hours, are used in the development of the decommissioning program schedule, using resource loading and event sequencing considerations. The scheduling of conventional removal and dismantling activities are based upon productivity information available from the "Building Construction Cost Data" publication.

An activity duration critical path is used to determine the total decommissioning program schedule. The schedule is relied upon in calculating the carrying costs, which include program management, administration, field engineering, equipment rental, and support services such as quality control and security. This systematic approach for assembling decommissioning estimates ensures a high degree of confidence in the reliability of the resulting cost estimate.

### 3.3 IMPACT OF DECOMMISSIONING MULTIPLE REACTOR UNITS

The DECON scenario for TMI-2 decommissioning operates independently from the adjacent Unit 2. The delayed decommissioning modes, Delayed DECON and SAFSTOR, consider opportunities to achieve economies of scale, by sharing costs between units, and coordinating the sequence of work activities. There will also be schedule constraints, particularly where there are requirements for specialty equipment and staff, or practical limitations on when final status surveys can take place. A summary of the principal impacts are listed below.

- Consistent with the agreement between FirstEnergy and Exelon regarding the timing of decommissioning activities at TMI-2, it is assumed that decommissioning at TMI-2 will not begin prior to 2034. Under the terms of this agreement, decommissioning activities at Unit 2 cannot begin while Unit 1 is still in commercial operation. The decommissioning scenarios used in this analysis are structured to integrate to the extent possible with a Unit 1 decommissioning scenario.
- Since the security program for the site is likely to be an integrated approach, the security guard force is assumed to be shared to varying degrees between the units, depending upon the level of activities at each unit. This reduces the security costs for the decommissioning estimates for both units on site.
- The final radiological survey schedule is also affected by a two-unit decommissioning schedule. It would be considered impractical to try to complete the final status survey of Unit 1, while Unit 2 still has ongoing radiological remediation work and waste handling in process. As such, this analysis has structured the decommissioning scenarios for Unit 2 to coordinate the final status survey for the station.

### **3.4 FINANCIAL COMPONENTS OF THE COST MODEL**

TLG's proprietary decommissioning cost model, DECCER, produces a number of distinct cost elements. These direct expenditures, however, do not comprise the total cost to accomplish the project goal, i.e., license termination and site restoration.

#### **3.4.1 Contingency**

Inherent in any cost estimate that does not rely on historical data is the inability to specify the precise source of costs imposed by factors such as tool breakage, accidents, illnesses, weather delays, and labor stoppages. In the DECCER cost model, contingency fulfills this role. Contingency is added to each line item to account for costs that are difficult or impossible to develop analytically. Such costs are historically inevitable over the duration of a job of this magnitude; therefore, this cost analysis includes funds to cover these types of expenses.

The activity- and period-dependent costs are combined to develop the total decommissioning cost. A contingency is then applied on a line-item basis, using one or more of the contingency types listed in the AIF/NESP-036 study. "Contingencies" are defined in the American Association of Cost Engineers "Project and Cost Engineers'

Handbook"<sup>[24]</sup> as "specific provision for unforeseeable elements of cost within the defined project scope; particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur." The cost elements in this analysis are based upon ideal conditions and maximum efficiency; therefore, consistent with industry practice, a contingency factor has been applied. In the AIF/NESP-036 study, the types of unforeseeable events that are likely to occur in decommissioning are discussed and guidelines are provided for percentage contingency in each category. It should be noted that contingency, as used in this analysis, does not account for price escalation and inflation in the cost of decommissioning over the time intervals identified for each scenario.

The use and role of contingency within decommissioning estimates is not a "safety factor issue." Safety factors provide additional security and address situations that may never occur. Contingency funds are expected to be fully expended throughout the program. They also provide assurance that sufficient funding is available to accomplish the intended tasks. An estimate without contingency, or from which contingency has been removed, can disrupt the orderly progression of events and jeopardize a successful conclusion to the decommissioning process.

For example, the most technologically challenging task in decommissioning a commercial nuclear station is the disposition of the reactor vessel and internal components, highly radioactive following the accident. The disposition of these components forms the basis of the critical path (schedule) for decommissioning operations. Cost and schedule are interdependent, and any deviation in schedule has a significant impact on cost for performing a specific activity.

Disposition of the reactor vessel internals involves the underwater cutting of complex components that are radioactive and highly contaminated with fuel debris. Costs are based upon optimum segmentation, handling, and packaging scenarios. The schedule is primarily dependent upon the turnaround time for the heavily shielded shipping casks, including preparation, loading, and decontamination of the containers for transport. The number of casks required is a function of the pieces generated in the segmentation activity, a value calculated on optimum performance of the tooling employed in cutting the various subassemblies. The expected optimization, however, may not be achieved, resulting in delays and additional program costs. For this reason, contingency must be included to mitigate the consequences of

the expected inefficiencies inherent in this complex activity, along with related concerns associated with the operation of highly specialized tooling, field conditions, and water clarity.

Contingency funds are an integral part of the total cost to complete the decommissioning process. Exclusion of this component puts at risk a successful completion of the intended tasks and, potentially, subsequent related activities. For this study, TLG examined the major activity-related problems (decontamination, segmentation, equipment handling, packaging, transport, and waste disposal) that necessitate a contingency. Individual activity contingencies ranged from 10% to 75%, depending on the degree of difficulty judged to be appropriate from TLG's actual decommissioning experience. The contingency values used in this study are as follows:

Decontamination	50%
Contaminated Component Removal	25%
Contaminated Component Packaging	10%
Contaminated Component Transport	15%
Low-Level Radioactive Waste Disposal	25%
Reactor Segmentation	75%
NSSS Component Removal	25%
Reactor Waste Packaging	25%
Reactor Waste Transport	25%
Reactor Vessel Component Disposal	50%
GTCC Disposal	15%
Non-Radioactive Component Removal	15%
Heavy Equipment and Tooling	15%
Supplies	25%
Engineering	15%
Energy	15%
Characterization and Termination Surveys	30%
Construction	15%
Taxes and Fees	10%
Insurance	10%
Staffing	15%
Operations and Maintenance Expenses	15%

The contingency values are applied to the appropriate components of the estimates on a line item basis. A composite value is then reported at the end of each estimate. For example, the composite contingency value

reported for the DECON alternative is 20.3%. Values for the other alternatives are delineated within the detailed cost tables in Appendices D and E.

#### 3.4.2 Financial Risk

In addition to the routine uncertainties addressed by contingency, another cost element that is sometimes necessary to consider when bounding decommissioning costs relates to uncertainty, or risk. Examples can include changes in work scope, pricing, job performance, and other variations that could conceivably, but not necessarily, occur. Consideration is sometimes necessary to generate a level of confidence in the estimate, within a range of probabilities. TLG considers these types of costs under the broad term "financial risk." Included within the category of financial risk are:

- Delays in approval of the decommissioning plan due to intervention, public participation in local community meetings, legal challenges, and national and local hearings.
- Changes in the project work scope from the baseline estimate, involving the discovery of unexpected levels of contaminants, contamination in places not previously expected, contaminated soil previously undiscovered (either radioactive or hazardous material contamination), variations in plant inventory or configuration not indicated by the as-built drawings.
- Regulatory changes, e.g., affecting worker health and safety, site release criteria, waste transportation, and disposal.
- Policy decisions altering national commitments, e.g., in the ability to accommodate certain waste forms for disposition or in the timetable for such, e.g., the start and rate of acceptance of spent fuel by the DOE.
- Pricing changes for basic inputs, such as labor, energy, materials, and burial. Some of these inputs may vary slightly, e.g. -10% to +20%; burial could vary from -50% to +200% or more.

It has been TLG's experience that the results of a risk analysis, when compared with the base case estimate for decommissioning, indicate that the chances of the base decommissioning estimate's being too high is a low probability, and the chances that the estimate is too low is a higher probability. This is mostly due to the pricing uncertainty for low-level radioactive waste burial, and to a lesser extent due to schedule

increases from changes in plant conditions and to pricing variations in the cost of labor (both craft and staff). This cost study, however, does not include any additional costs for financial risk since there is insufficient historical data from which to project future liabilities. Consequently, the areas of uncertainty or risk should be revisited periodically and addressed through repeated revisions or updates of the base estimate.

### **3.5 SITE-SPECIFIC CONSIDERATIONS**

There are a number of site-specific considerations that affect the method for dismantling and removal of equipment from the site and the degree of restoration required. The cost impact of the considerations identified below is included in this cost study. Unless otherwise noted, these assumptions are applicable to all three scenarios.

#### **3.5.1 Spent Fuel Management**

The cost to dispose of spent fuel generated from plant operations is not reflected within the estimates to decommission the TMI-2 site. The majority of the spent fuel was removed during the TMI-2 Clean-up Program's reactor vessel defueling effort which concluded in January 1990. Title to the spent fuel that was removed was transferred to the DOE.

The remainder of the fuel (about 1%) is dispersed within the primary system and to a lesser extent in other systems and structures. This residual material will be removed as radioactive waste and is included in the waste disposal volumes discussed in Section 5.

#### **Repository Availability**

There will be some wastes generated in the decommissioning of TMI-2 that are not suitable for shallow land burial and therefore cannot be shipped for disposal to either Waste Control Specialists or EnergySolutions. This material, primarily associated with systems and structures contaminated with fuel debris, requires greater isolation from the environment.

The estimates for TMI-2 assume the timely removal of waste designated for geologic disposal, without the need for interim on site storage (once containerized).

### 3.5.2 Reactor Vessel and Internal Components

The majority of the reactor internal components have already been removed as a result of the accident recovery effort in the 1980's. These components are currently being stored within the reactor building. This estimate assumes that these components are segmented and shipped in shielded, reusable transportation casks commensurate with the start of major reactor vessel removal activities, i.e., Period 4a of each scenario.

The reactor pressure vessel and remaining internal components (essentially the core barrel, core former, thermal shield, and flow distributor) are segmented and packaged for disposal in shielded, reusable transportation casks. Segmentation of the remaining internal components is performed in the refueling canal, where a turntable and remote cutter are installed. The vessel is segmented in place, using a mast-mounted cutter supported off the lower head and directed from a shielded work platform installed overhead in the reactor cavity. Transportation cask specifications and transportation regulations will dictate segmentation and packaging methodology.

It is anticipated that all neutron-activated components in the reactor vessel and internals would meet existing disposal requirements as delineated in 10 CFR §61, due to the short operating history. However, the fission products and transuranic material present on all surfaces in the vessel and internals are expected to exceed Class C limits, in particular for those components located below the top of the core. The reactor vessel and the upper portions of the internals are assumed to meet Class A limits following decontamination.

The dismantling of the reactor internals will generate radioactive waste considered unsuitable for shallow land disposal, i.e., GTCC. Although the material is not classified as high-level waste, the DOE has indicated it will accept this waste for disposal at the future high-level waste repository.<sup>[25]</sup> However, the DOE has not been forthcoming with an acceptance criteria or disposition schedule for this material, and numerous questions remain as to the ultimate disposal cost and waste form requirements.

For purposes of this analysis, the GTCC has been packaged and disposed of as high-level waste. It is also assumed that the DOE will accept the GTCC material in a timely manner so as not to affect the TMI-2 decommissioning schedule. No additional costs are included for the temporary storage of GTCC material.



Intact disposal of the reactor vessel and internal components can provide savings in cost and worker exposure by eliminating the complex segmentation requirements, isolation of the GTCC material, and transport/storage of the resulting waste packages. Portland General Electric (PGE) was able to dispose of the Trojan reactor as an intact package. However, its location on the Columbia River simplified the transportation analysis since:

- the reactor package could be secured to the transport vehicle for the entire journey, i.e., the package was not lifted during transport;
- there were no man-made or natural terrain features between the plant site and the disposal location that could produce a large drop; and
- transport speeds were very low, limited by the overland transport vehicle and the river barge.

As a member of the Northwest Compact, PGE had a site available for disposal of the package - the US Ecology facility in Washington State. The characteristics of this arid site proved favorable in demonstrating compliance with land disposal regulations.

It is not known whether this option will be available for TMI-2. Future viability of this option will depend upon the ultimate location of the disposal site, as well as the disposal site licensee's ability to accept highly radioactive packages and effectively isolate them from the environment. Consequently, the study assumes the reactor vessel will require segmentation, as a bounding condition.

### **3.5.3 Steam Generators**

With the high levels of radioactivity and contamination both in the reactor building and within the steam generators, this estimate assumes that the steam generators will be segmented in place instead of one piece removal.

The removal sequence assumed for the estimate is as follows:

- Remove the upper steam generator channel head by wire sawing the shell and tubes immediately below the upper tube sheet.
- Segment and decontaminate the upper channel head in the fuel transfer pool.

- Install a steam generator work platform to allow in-place underwater segmentation of the steam generator internals.
- Remove the steam generator tubing and associated shroud and support plates.
- Remove the steam generator cylindrical shell.
- Remove the lower steam generator channel head.
- Segment and decontaminate the lower channel head in the fuel transfer pool.

The steam generator tubing is packaged and shipped and buried as Class B waste. Steam generator tube support plates, shrouds, and shell plates are transported and buried as Class A waste. The estimate assumes that the steam generator channel heads will be decontaminated using a combination of machining and ultra high pressure (UHP) water sprays such that the components can be shipped and buried as Class A waste.

Waste that is generated as a result of the machining and normal filtering of the water in the steam generators and the fuel transfer pool is assumed to be highly radioactive and is packaged and transferred to the DOE as GTCC waste.

#### 3.5.4 Other Primary System Components

The following discussion deals with the decontamination, removal and disposition of the pressurizer, reactor coolant piping, reactor coolant pumps and motors, and the core flood tanks.

A combination of in-place decontamination, and remote decontamination of components in the fuel transfer pool was assumed in the estimate.

The pressurizer and the core flood tanks are decontaminated in-place using UHP. Once decontaminated, the pressurizer is cut in half, removed from the reactor building, grouted, and packaged in a shielded container for rail shipment and burial as Class A waste. The core flood tanks are assumed to be segmented, packaged and shipped as Class A waste.

Hot leg piping is accessed by cutting a hole in the core barrel. A combination of underwater remote retrieval and vacuuming is used to remove fuel and fission product material. Hot and cold leg piping and

fittings are removed and placed in the fuel transfer pool for additional decontamination. Hydrolasing is used to remove radioactive materials. Removed material is collected using filters and demineralizers, packaged, and transferred to the DOE as GTCC material. Decontaminated piping is packaged, shipped and buried as Class A waste.

The reactor coolant pump motors are removed intact and placed in shielded containers for rail transport and burial as Class A material.

Reactor coolant pumps are disassembled and placed in the fuel transfer pool for decontamination. Pump components are decontaminated using UHP to remove the majority of the radioactive material. Following decontamination, the components are packaged in shielded containers for rail transport and buried as Class A material. Material removed as a result of the decontamination process is collected using filters and shipped as GTCC material. The estimates also assume that process water used for reactor coolant system decontamination and in the fuel transfer pool is processed using cesium/strontium preferential cation demineralizers. The resin waste is processed and buried as Class C radioactive waste.

### 3.5.5 Other Systems Known to Contain High Levels of Radioactivity

Systems in the reactor building and portions of systems in the auxiliary and fuel handling buildings are known to contain high levels of radioactivity and potentially spent fuel material from the accident. The estimates recognize the difficulty in removing these components by increasing the work difficulty factors associated with removal of these systems. The estimates also assume that these components will be packaged for direct disposal (no recycling). The disposal costs of these waste streams were also adjusted, as appropriate, to include curie surcharges commensurate with the higher radioactivity levels.

These systems and components will be decontaminated with UHP sprays to removal fuel solids and sludge from fuel bearing components in the fuel and auxiliary buildings. Solids and sludge resulting from the UHP process will be transferred to the reactor building to be packaged in canisters used for NSSS decontamination.

### 3.5.6 Reactor Building Structures Decontamination

Significant radioactive contamination exists throughout the TMI-2 reactor building. This contamination is due to fission products ( $^{90}\text{Sr}$  and  $^{137}\text{Cs}$  in particular) released from the damaged fuel. The radiation levels are not expected to decrease significantly from current levels due to the long half lives of these elements. The dispersion of spent fuel within the reactor building includes alpha-decaying isotopes in addition to the beta and gamma radiation normally encountered during decommissioning. These unusual conditions require additional controls and more engineered decommissioning methods to perform the structure decontamination and demolition.

Based upon these conditions, the estimates assume that the entire interior structure of the reactor building is removed and disposed as potentially contaminated material.

The lower elevations of the reactor building are highly contaminated. Significant activity has been absorbed in the concrete block walls, in the four-foot thick D-ring concrete walls, and on the lower level concrete floors. Initial decontamination of this area (Period 4a) is assumed to be performed using remotely-operated machines. Surface material will be bulk removed from the concrete walls, packaged in shielded casks and, on average concentration, buried as Class B waste (i.e., most of the debris mass will be Class A, but there will be hot spots ranging to Class C or GTCC).

Once the highly contaminated surfaces are decontaminated, free standing concrete walls will be removed (in Period 4b using more conventional means) and shipped for direct burial as radioactive waste.

The upper portion of the containment inner steel liner and the entire polar crane will be removed using conventional radioactive demolition techniques (in Period 4b) and packaged, shipped and buried as radioactive waste. Following liner removal, the outer reactor building concrete walls will be demolished. This remaining structural material from the reactor building will be surveyed on site, with 90% of the concrete volume assumed to meet free release criteria. The remaining 10% is sent to a waste processor. The free released concrete is acceptable for use as fill. Excess material will be sent to an industrial landfill.

### 3.5.7 Demolition of Other Contaminated Structures

Significant contamination exists within the auxiliary and fuel buildings. Similar to the reactor building, locations within these buildings will require special engineered methods to safely decontaminate and dispose of the structures.

The estimate assumes that the entire auxiliary and fuel building structures (all walls and floors down to the footings) will be removed and the resultant structural material monitored and processed with the same criteria as the reactor building.

Selected areas of the buildings will require remote operated machines and dedicated engineered ventilation systems and enclosures to allow decontamination and material removal.

### 3.5.8 Main Turbine and Condenser

The main turbine will be dismantled using conventional maintenance procedures. The remaining turbine internals will be removed to a laydown area. The lower turbine casings will be removed from their anchors by controlled demolition. This study recognizes that one of the low pressure turbine rotors and the main electrical generator has already been removed from the site. The main condensers will also be disassembled and moved to a laydown area. Material is then prepared for transportation to an off-site recycling facility where it will be surveyed and designated for either decontamination or volume reduction, conventional disposal, or controlled disposal. Components will be packaged and readied for transport in accordance with the intended disposition.

### 3.5.9 Transportation Methods

Contaminated piping, components, and structural material other than the highly contaminated reactor coolant system components and reactor building structures will qualify as LSA-I, II or III or Surface Contaminated Object, SCO-I or II, as described in Title 49.<sup>[26]</sup> The contaminated material will be packaged in Industrial Packages (IP-1, IP-2 or IP-3, as defined in subpart 173.411) for transport unless demonstrated to qualify as their own shipping containers. It is anticipated that the reactor vessel, after decontamination with UHP water sprays, and due to its limited operating lifetime, will qualify as LSA II or III, once the reactor internals and remaining fuel debris is

removed. Portions of the reactor vessel internal components are expected to be transported to the DOE's geologic repository in spent fuel casks by rail.

Waste resulting from filtering and demineralization of the reactor coolant system, and processing the fuel transfer pool water is assumed to require shipment in shielded truck casks. Transport of other highly radioactive waste such as reactor coolant system components, and waste from the decontamination of the reactor building basement are by shielded truck cask. Truck cask shipments may exceed 95,000 pounds, including payload, supplementary shielding, cask tie-downs, and tractor-trailer. The maximum level of activity per shipment assumed permissible was based upon the license limits of the available shielded transport casks. The segmentation scheme for the vessel and internal segments is designed to meet these limits.

The transport of large intact components, e.g., large heat exchangers and other oversized components are by a combination of truck, rail, and/or multi-wheeled transporter.

Truck transportation costs are estimated using published tariffs from Tri-State Motor Transit.<sup>[27]</sup>

The low-level radioactive waste requiring controlled disposal will be sent to the EnergySolutions facility in Clive, Utah. Memphis, Tennessee, is used as the destination for off-site processing. Bulk material shipped off site to the waste processor or to EnergySolutions is primarily moved via gondola railcars.

### 3.5.10 Low-Level Radioactive Waste Disposal

To the greatest extent practical, metallic material generated in the decontamination and dismantling processes is treated to reduce the total volume requiring controlled disposal. The treated material, meeting the regulatory and/or site release criterion, is released as scrap, requiring no further cost consideration. Conditioning and recovery of the waste stream is performed off site at a licensed processing center.

All options and services currently available to FirstEnergy for disposition of the various waste streams produced by the decommissioning process were considered. The majority of the low-level radioactive waste designated for direct disposal can be sent to EnergySolutions' facility in Clive, Utah. Therefore, disposal costs for

Class A waste were based upon FirstEnergy's agreement with EnergySolutions. This facility is not licensed to receive the higher activity portion (Classes B and C) of the decommissioning waste stream.

Very low-level radioactive waste, e.g., structural steel and contaminated concrete, is sent to a waste processing facility. More highly contaminated and activated material is sent to EnergySolutions. Disposal fees are based upon current charges for operating waste.

Waste Control Specialists (WCS) is licensed to receive the higher activity waste forms (Classes B and C). As such, for this analysis, disposal costs for the Class B and C waste were based upon the preliminary and indicative information on the cost for such from WCS.

The Idaho National Engineering and Environmental Laboratory (INEEL) is currently storing waste from the TMI-2 defueling operation. Costs have been included in this estimate to pay INEEL for the final disposal of this waste; the timing of when this payment occurs will be dependent upon the DOE's schedule for cleanup of INEEL. This estimate assumes that the payment occurs during Period 4 of each cost scenario.

This study assumes that most of the concrete resulting from the demolition of the reactor, auxiliary and fuel handling buildings can be surveyed and released on site for fill of below grade voids, or shipped off site to a local construction debris landfill. Should there be restrictions to this approach; the cost impact on the decommissioning program could become quite large, potentially up to tens of millions of dollars.

#### 3.5.11 Additional Decommissioning Facilities

Additional specialized facilities are required in support of the decommissioning. These include refurbishment of the containment air control envelope building located outside the reactor building equipment hatch, and the contamination control cubicle located outside the other personnel airlock, for reactor building radiological control and access. Construction of a prefabricated metal enclosure at the 305 foot elevation within the reactor building for the handling of highly-contaminated material will be required. A radioactive waste packaging and processing facility will also be required (Note that such a facility already exists on site, but will require refurbishment).

### 3.5.12 Remediation of Soil and Underground Piping

The estimates include the cost to remove certain underground piping. An allowance is also included for the removal, packaging, transportation and disposal of approximately 49,000 cubic feet of contaminated soil.

### 3.5.13 Site Conditions Following Decommissioning

The NRC will terminate (or amend) the site licenses if it determines that site remediation has been performed in accordance with the license termination plan, and that the termination survey and associated documentation demonstrate that the facility is suitable for release. The NRC's involvement in the decommissioning process will end at this point. Building codes and environmental regulations will dictate the next step in the decommissioning process, as well as the owner's own future plans for the site.

Non-essential structures or buildings severely damaged in decontamination process are removed to a nominal depth of three feet below grade. Concrete rubble generated from demolition activities is processed and made available as clean fill. The excavations will be regraded such that the power block area will have a final contour consistent with adjacent surroundings.

This estimate assumes the reactor, auxiliary, fuel buildings will be removed completely, i.e., down to and including their foundations and basemats. Concrete from these buildings will be surveyed on-site using conventional monitoring equipment; concrete which meets the release criteria will be disposed of either on site as fill, or in an off-site landfill.

## **3.6 ASSUMPTIONS**

The following are the major assumptions made in the development of the estimates for decommissioning the site.

### 3.6.1 Estimating Basis

The study follows the principles of ALARA through the use of work duration adjustment factors. These factors address the impact of activities such as radiological protection instruction, mock-up training, and the use of respiratory protection and protective clothing. The factors lengthen a task's duration, increasing costs and lengthening the overall schedule. ALARA planning is considered in the costs for engineering and



planning, and in the development of activity specifications and detailed procedures. Changes to worker exposure limits may impact the decommissioning cost and project schedule.

All costs are reported in 2013 dollars.

No costs have been included for the preparation of an environmental impact statement, should it be required.

### 3.6.2 Labor Costs

The craft labor required to decontaminate and dismantle the nuclear units will be acquired through standard site contracting practices. The current cost of labor at the site is used as an estimating basis. Costs for site administration, operations, construction, and maintenance personnel are based upon average salary information provided by FirstEnergy or from comparable industry information.

FirstEnergy will provide limited oversight support staff in the areas of overall management, licensing, radiological and industrial safety and engineering. It will also hire a DOC to provide the balance of the professional, management, administrative and physical staff.

This study assumes that there is some sharing of security staffing positions with the adjacent Unit 1. This has the effect of lowering site security costs.

### 3.6.3 Design Conditions

Fuel cladding failure as a result of the accident will most likely prevent shipment of untreated major NSSS components under current transportation regulations and disposal requirements. Therefore, this estimate assumes that aggressive mechanical decontamination of reactor coolant system components is required prior to shipment.

The estimated curie contents of the vessel and internals are neutron activation products derived from those listed in NUREG/CR-3474.<sup>[28]</sup> Actual estimates are derived from the curie/gram values contained therein and adjusted for the different mass of the TMI-2 components, the operating history of 95 effective full-power days, and different periods of decay. Additional short-lived isotopes were derived from CR-0130<sup>[29]</sup> and CR-0672<sup>[30]</sup> and benchmarked to the long-lived values from CR-3474. The activation products present in the reactor vessel base

metal are assumed to be the controlling factor in their disposal, following surface decontamination of fuel debris.

Reactor vessel internals whose elevation in the reactor places them at or below the original top of the fuel assemblies are assumed to be both sufficiently geometrically complex to preclude effective decontamination and contaminated with spent fuel so as to require disposal as GTCC material.

Control elements and incore detector assemblies are assumed to have been removed with the damaged fuel.

Neutron activation of the reactor building structure and the biological shield is considered minimal due to the short operating life of TMI-2.

#### 3.6.4 General

The plant staff will perform the following activities (FirstEnergy staff will be augmented as necessary, either by direct hiring, or by subcontracting to fulfill the staff requirements):

- Drain and collect lubricating oils for recycle and/or sale.
- Process defueling waste inventories, i.e., the estimates include costs for the removal of lead shielding and spent fuel handling equipment that remains in the reactor building.

#### Scrap and Salvage

Material located within the radiation controlled area, and not shipped for direct disposal, is sent off-site for survey and release.

Furniture, tools, mobile equipment such as forklifts, trucks, bulldozers, and other property owned by FirstEnergy (and outside the radiation controlled area) is removed at no cost or credit to the decommissioning project. Disposition may include relocation to other facilities. Spare parts are also available for alternative use.

#### Energy

For estimating purposes, the plant is assumed to be de-energized, with the exception of those facilities associated with long term dormancy. Replacement power costs are used for the cost of energy consumption

during decommissioning for tooling, lighting, ventilation, and essential services.

#### Insurance

Costs for continuing coverage (nuclear liability and property insurance) during dormancy and decommissioning are included and based upon current PDMS premiums and anticipated shared costs with the adjacent Unit 1. Reductions in premiums, throughout the decommissioning process, are based upon the guidance and the limits for coverage defined in the NRC's proposed rulemaking "Financial Protection Requirements for Permanently Shutdown Nuclear Power Reactors."<sup>[31]</sup> The NRC's financial protection requirements are based on various reactor configurations.

#### Taxes

Property taxes are not included.

#### Site Modifications

The perimeter fence and in-plant security barriers will be moved, as appropriate, to conform to the Site Security Plan in force during the various stages of the project.

### **3.7 COST ESTIMATE SUMMARY**

A schedule of expenditures for each scenario is provided in Tables 3.1 through 3.3. Decommissioning costs are reported in the year of projected expenditure; however, the values are provided in thousands of 2013 dollars. Costs are not inflated, escalated, or discounted over the period of expenditure. The annual expenditures are based upon the detailed activity costs reported in Appendices C through E, along with the schedule discussed in Section 4.

**TABLE 3.1**  
**DECON ALTERNATIVE**  
**SCHEDULE OF TOTAL ANNUAL EXPENDITURES**  
(thousands, 2013 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2013	2,486	0	224	0	326	3,036
2014	2,486	0	224	0	326	3,036
2015	2,486	0	224	0	326	3,036
2016	2,493	0	224	0	327	3,044
2017	2,486	0	224	0	326	3,036
2018	2,486	0	224	0	326	3,036
2019	2,486	0	224	0	326	3,036
2020	2,493	0	224	0	327	3,044
2021	2,486	0	224	0	326	3,036
2022	2,486	0	224	0	326	3,036
2023	2,486	0	224	0	326	3,036
2024	2,493	0	224	0	327	3,044
2025	2,486	0	224	0	326	3,036
2026	2,486	0	224	0	326	3,036
2027	2,486	0	224	0	326	3,036
2028	2,493	0	224	0	327	3,044
2029	2,486	0	224	0	326	3,036
2030	2,486	0	224	0	326	3,036
2031	2,486	0	224	0	326	3,036
2032	2,493	0	224	0	327	3,044
2033	2,486	0	224	0	326	3,036
2034	2,486	0	224	0	326	3,036
2035	2,486	0	224	0	326	3,036
2036	2,493	0	224	0	327	3,044
2037	2,486	0	224	0	326	3,036
2038	2,486	0	224	0	326	3,036
2039	2,486	0	224	0	326	3,036

**TABLE 3.1**  
**(continued)**  
**DECON ALTERNATIVE**  
**SCHEDULE OF TOTAL ANNUAL EXPENDITURES**  
(thousands, 2013 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2040	42,184	1,311	854	22	9,056	53,427
2041	57,835	6,878	1,122	14,512	7,989	88,337
2042	50,240	15,149	1,122	33,610	10,808	110,929
2043	50,240	15,149	1,122	33,610	10,808	110,929
2044	50,377	15,191	1,125	33,702	10,838	111,233
2045	50,240	15,149	1,122	33,610	10,808	110,929
2046	47,661	12,938	1,024	27,517	8,718	97,858
2047	42,771	8,743	838	15,960	4,752	73,063
2048	42,888	8,767	840	16,004	4,765	73,263
2049	42,771	8,743	838	15,960	4,752	73,063
2050	42,771	8,743	838	15,960	4,752	73,063
2051	41,768	8,391	810	15,131	4,570	70,671
2052	24,331	4,863	255	814	1,091	31,354
2053	18,079	7,945	104	1,820	471	28,418
<b>Total</b>	<b>671,323</b>	<b>137,959</b>	<b>18,061</b>	<b>258,232</b>	<b>102,989</b>	<b>1,188,564</b>

**TABLE 3.2**

**DELAYED DECON ALTERNATIVE  
SCHEDULE OF TOTAL ANNUAL EXPENDITURES**  
(thousands, 2013 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2013	2,486	0	224	0	326	3,036
2014	2,486	0	224	0	326	3,036
2015	2,486	0	224	0	326	3,036
2016	2,493	0	224	0	327	3,044
2017	2,486	0	224	0	326	3,036
2018	2,486	0	224	0	326	3,036
2019	2,486	0	224	0	326	3,036
2020	2,493	0	224	0	327	3,044
2021	2,486	0	224	0	326	3,036
2022	2,486	0	224	0	326	3,036
2023	2,486	0	224	0	326	3,036
2024	2,493	0	224	0	327	3,044
2025	2,486	0	224	0	326	3,036
2026	2,486	0	224	0	326	3,036
2027	2,486	0	224	0	326	3,036
2028	2,493	0	224	0	327	3,044
2029	2,486	0	224	0	326	3,036
2030	2,486	0	224	0	326	3,036
2031	2,486	0	224	0	326	3,036
2032	2,493	0	224	0	327	3,044
2033	2,486	0	224	0	326	3,036
2034	1,150	240	236	4	482	2,112
2035	588	341	242	6	547	1,724
2036	590	342	242	6	548	1,728
2037	588	341	242	6	547	1,724
2038	588	341	242	6	547	1,724
2039	588	341	242	6	547	1,724

**TABLE 3.2**  
**(continued)**  
**DELAYED DECON ALTERNATIVE**  
**SCHEDULE OF TOTAL ANNUAL EXPENDITURES**  
(thousands, 2013 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2040	590	342	242	6	548	1,728
2041	588	341	242	6	547	1,724
2042	588	341	242	6	547	1,724
2043	588	341	242	6	547	1,724
2044	590	342	242	6	548	1,728
2045	21,420	885	555	15	4,901	27,776
2046	59,412	3,573	1,122	5,617	9,680	79,404
2047	51,713	13,861	1,122	30,900	9,785	107,381
2048	50,377	15,181	1,125	33,687	10,824	111,194
2049	50,239	15,140	1,122	33,595	10,795	110,890
2050	50,239	15,140	1,122	33,595	10,795	110,890
2051	50,239	15,140	1,122	33,595	10,795	110,890
2052	40,986	8,757	840	15,988	4,751	71,322
2053	40,874	8,733	838	15,945	4,738	71,128
2054	40,874	8,733	838	15,945	4,738	71,128
2055	40,874	8,733	838	15,945	4,738	71,128
2056	40,986	8,757	840	15,988	4,751	71,322
2057	28,132	3,949	456	4,649	2,275	39,461
2058	24,464	11,029	156	2,509	700	38,859
2059	1,008	469	6	107	28	1,619
<b>Total</b>	<b>651,122</b>	<b>141,727</b>	<b>19,459</b>	<b>258,143</b>	<b>107,103</b>	<b>1,177,554</b>

TABLE 3.3

SAFSTOR ALTERNATIVE  
SCHEDULE OF TOTAL ANNUAL EXPENDITURES  
(thousands, 2013 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2013	2,486	0	224	0	326	3,036
2014	2,486	0	224	0	326	3,036
2015	2,486	0	224	0	326	3,036
2016	2,493	0	224	0	327	3,044
2017	2,486	0	224	0	326	3,036
2018	2,486	0	224	0	326	3,036
2019	2,486	0	224	0	326	3,036
2020	2,493	0	224	0	327	3,044
2021	2,486	0	224	0	326	3,036
2022	2,486	0	224	0	326	3,036
2023	2,486	0	224	0	326	3,036
2024	2,493	0	224	0	327	3,044
2025	2,486	0	224	0	326	3,036
2026	2,486	0	224	0	326	3,036
2027	2,486	0	224	0	326	3,036
2028	2,493	0	224	0	327	3,044
2029	2,486	0	224	0	326	3,036
2030	2,486	0	224	0	326	3,036
2031	2,486	0	224	0	326	3,036
2032	2,493	0	224	0	327	3,044
2033	2,486	0	224	0	326	3,036
2034	1,147	239	236	4	481	2,107
2035	584	339	242	6	546	1,716
2036	585	340	242	6	548	1,721
2037	584	339	242	6	546	1,716
2038	584	339	242	6	546	1,716
2039	584	339	242	6	546	1,716
2040	585	340	242	6	548	1,721
2041	584	339	242	6	546	1,716
2042	584	339	242	6	546	1,716
2043	584	339	242	6	546	1,716
2044	585	340	242	6	548	1,721



**TABLE 3.3**  
**(continued)**  
**SAFSTOR ALTERNATIVE**  
**SCHEDULE OF TOTAL ANNUAL EXPENDITURES**  
(thousands, 2013 dollars)

Year	Labor	Equipment &		Burial	Other	Total	
		Materials	Energy				
2045		584	339	242	6	546	1,716
2046		584	339	242	6	546	1,716
2047		584	339	242	6	546	1,716
2048		585	340	242	6	548	1,721
2049		584	339	242	6	546	1,716
2050		584	339	242	6	546	1,716
2051		584	339	242	6	546	1,716
2052		585	340	242	6	548	1,721
2053		584	339	242	6	546	1,716
2054		584	339	242	6	546	1,716
2055		584	339	242	6	546	1,716
2056		585	340	242	6	548	1,721
2057		584	339	242	6	546	1,716
2058		584	339	242	6	546	1,716
2059		584	339	242	6	546	1,716
2060		585	340	242	6	548	1,721
2061		584	339	242	6	546	1,716
2062		584	339	242	6	546	1,716
2063		584	339	242	6	546	1,716
2064		585	340	242	6	548	1,721
2065		584	339	242	6	546	1,716
2066		584	339	242	6	546	1,716
2067		584	339	242	6	546	1,716
2068		585	340	242	6	548	1,721
2069		584	339	242	6	546	1,716
2070		584	339	242	6	546	1,716
2071		584	339	242	6	546	1,716
2072		585	340	242	6	548	1,721
2073		584	339	242	6	546	1,716
2074		584	339	242	6	546	1,716
2075		584	339	242	6	546	1,716
2076		585	340	242	6	548	1,721

**TABLE 3.3**  
**(continued)**  
**SAFSTOR ALTERNATIVE**  
**SCHEDULE OF TOTAL ANNUAL EXPENDITURES**  
(thousands, 2013 dollars)

Year	Labor	Equipment & Materials	Energy	Burial	Other	Total
2077	584	339	242	6	546	1,716
2078	584	339	242	6	546	1,716
2079	584	339	242	6	546	1,716
2080	585	340	242	6	548	1,721
2081	5,872	477	321	8	1,651	8,330
2082	59,162	2,301	1,122	1,449	11,987	76,021
2083	54,312	11,604	1,122	26,141	7,999	101,178
2084	50,377	15,177	1,125	33,673	10,818	111,171
2085	50,239	15,136	1,122	33,581	10,789	110,867
2086	50,239	15,136	1,122	33,581	10,789	110,867
2087	50,239	15,136	1,122	33,581	10,789	110,867
2088	43,421	10,455	916	20,657	6,353	81,802
2089	40,801	8,729	838	15,920	4,729	71,017
2090	40,801	8,729	838	15,920	4,729	71,017
2091	40,801	8,729	838	15,920	4,729	71,017
2092	40,913	8,753	840	15,963	4,742	71,211
2093	32,864	5,738	599	8,866	3,193	51,259
2094	24,035	8,524	196	1,821	857	35,434
2095	7,527	3,503	46	803	207	12,086
<hr/>						
Total	671,870	153,977	28,227	258,157	126,834	1,239,065

## **4. SCHEDULE ESTIMATE**

The schedules for the decommissioning scenarios considered in this study follow the sequence presented in the AIF/NESP-036 study, with minor changes to reflect recent experience and site-specific constraints.

A schedule or sequence of activities is presented in Figure 4.1 through 4.3 for the three decommissioning scenarios. The key activities listed in the schedule do not reflect a one-to-one correspondence with those activities in the cost tables, but reflect dividing some activities for clarity and combining others for convenience. The schedule was prepared using the "Microsoft Project 2010" computer software.<sup>[32]</sup>

### **4.1 SCHEDULE ESTIMATE ASSUMPTIONS**

The schedule reflects the results of a precedence network developed for the site decommissioning activities, i.e., a PERT (Program Evaluation and Review Technique) Software Package. The work activity durations used in the precedence network reflect the actual man-hour estimates from the cost tables, adjusted by stretching certain activities over their slack range and shifting the start and end dates of others. The following assumptions were made in the development of the decommissioning schedule:

- The DECON alternative begins decommissioning of TMI-2 in 2040. The existing PDMS yearly costs of \$3.1 million are continued until that date.
- The existing PDMS yearly costs cease upon the shutdown of the adjacent Unit 1 on April 19, 2034 for the Delayed DECON and SAFSTOR scenarios; normal SAFSTOR dormancy costs will commence at that date until decommissioning begins.
- The Delayed DECON alternative defers decommissioning of TMI-2 until TMI-1's spent fuel has been removed from the site. This scenario assumes that the decontamination and dismantling activities at TMI-2 are synchronized with the adjacent unit such that the licenses for both units are terminated concurrently.
- The SAFSTOR alternative places TMI-2 into long-term storage along with TMI-1. TMI-2 remains in storage until such time that decommissioning activities can be coordinated with Unit 1. As with the second scenario, termination of the licenses is concurrent.
- All work (except vessel and internals removal and some of the decontamination of NSSS components in the refueling canal) is per-

formed during an 8-hour workday, 5 days per week, with no overtime. There are eleven paid holidays per year.


- Steam generator removal activities are performed with limited parallel work on the A and B steam generators.
- Reactor and internals removal activities are performed by using separate crews for different activities working on different shifts, with a corresponding backshift charge for the second shift.
- Multiple crews work parallel activities to the maximum extent possible, consistent with optimum efficiency, adequate access for cutting, removal and laydown space, and with the stringent safety measures necessary during demolition of heavy components and structures.
- Reactor building basement decontamination using remote equipment will occur prior to the start of reactor coolant system component removal.

## **4.2 PROJECT SCHEDULE**


The period-dependent costs presented in the detailed cost tables are based upon the durations developed in the schedule for decommissioning TMI-2. Durations are established between several milestones in each project period; these durations are used to establish a critical path for the entire project. In turn, the critical path duration for each period is used as the basis for determining the period-dependent costs.

Project timelines are provided in Figures 4.2 through 4.4.


FIGURE 4.1  
DECON  
ACTIVITY SCHEDULE




**FIGURE 4.2  
DECOMMISSIONING TIMELINE  
DECON  
(not to scale)**



**FIGURE 4.3**  
**DECOMMISSIONING TIMELINE**  
**DELAYED DECON**  
(not to scale)



**FIGURE 4.4**  
**DECOMMISSIONING TIMELINE**  
**SAFSTOR**  
(not to scale)





## **5. RADIOACTIVE WASTES**

The objectives of the decommissioning process are the removal of all radioactive material from the site that would restrict its future use and the termination of the NRC license. This currently requires the remediation of all radioactive material at the site in excess of applicable legal limits. Under the Atomic Energy Act,<sup>[33]</sup> the NRC is responsible for protecting the public from sources of ionizing radiation. Title 10 of the Code of Federal Regulations delineates the production, utilization, and disposal of radioactive materials and processes. In particular, §71 defines radioactive material as it pertains to packaging and transportation and §61 specifies its disposition.

Most of the materials being transported for controlled burial are categorized as Low Specific Activity (LSA) or Surface Contaminated Object (SCO) materials containing Type A quantities, as defined in 49 CFR §173-178. Shipping containers are required to be Industrial Packages (IP-1, IP-2 or IP-3, as defined in subpart 173.411). For this study, commercially available steel containers are presumed to be used for the disposal of piping, small components, and concrete. Larger components can serve as their own containers, with proper closure of all openings, access ways, and penetrations.

Figure 5.1 summarizes the categories of radioactive waste streams and their disposition. Figure 5.2 identifies of the intended disposal site and processing center.

The volumes of radioactive waste generated during the various decommissioning activities at the site is shown on a line-item basis in Appendices C, D, and E and summarized in Tables 5.1 through 5.3. The quantified waste volume summaries shown in these tables are consistent with §61 classifications. The volumes are calculated based on the exterior dimensions for containerized material and on the displaced volume of components serving as their own waste containers.

The reactor vessel, internals, other reactor coolant system components, and certain structural materials are categorized as large quantity shipments and, accordingly, will be shipped in reusable, shielded truck casks with disposable liners or LSA boxes shipped within shielded vans. In calculating disposal costs, the burial fees are applied against the liner volume, as well as the special handling requirements of the payload.

Most of the waste generated by the decommissioning process appears to be Class C or less, based upon the available information regarding the amount of fission products and transuranics present in the buildings, and the quantities of building materials assumed shipped as radioactive waste. This basis should be reexamined if

additional characterization information becomes available in the future regarding the quantities of fission products and transuranics in more localized surveys.

No process system containing/handling radioactive substances at the time of decommissioning is presumed to meet material release criteria by decay alone, i.e., systems radioactive in 2013 will still be radioactive over the time period during which the decommissioning is accomplished, due to the presence of long-lived radionuclides. While the dose rates decrease with time, radionuclides such as <sup>137</sup>Cs will still control the disposition requirements.


The waste material generated in the decontamination and dismantling of TMI-2 is primarily generated during Period 4 of the defined alternatives.

Disposal fees are calculated using current disposal agreements, with surcharges added for the highly activated components, for example, generated in the segmentation of the reactor vessel. The cost to dispose of the majority of the material generated from the decontamination and dismantling activities is based upon FirstEnergy's disposal agreement with EnergySolutions for its facility in Clive, Utah.


EnergySolutions is not able to accept the higher activity waste (Class B and C) generated in the decontamination of the reactor vessel and segmentation of the components closest to the core. As such, for this analysis, disposal costs for the Class B and C waste were based upon the preliminary and indicative information on the cost for such from WCS.

FIGURE 5.1

TMI-2 WASTE STREAMS SUMMARY



**FIGURE 5.2  
DECOMMISSIONING WASTE DESTINATIONS  
RADIOLOGICAL**



**TABLE 5.1**  
**DECON ALTERNATIVE**  
**DECOMMISSIONING WASTE SUMMARY**

Waste	Cost Basis	Class <sup>[1]</sup>	Waste Volume (cubic feet)	Weight (pounds)
Geologic Repository	Spent Fuel	GTCC	2,856	564,685
	Equivalent		357	20,514
Primary waste stream				
	WCS	C	2,734	237,772
	WCS	B	26,918	1,928,673
Secondary waste stream				
	EnergySolutions	A	177,759	13,891,318
Tertiary waste stream				
Concrete	EnergySolutions	A	613,465	66,003,571
Soil	EnergySolutions	A	48,992	3,723,414
DAW	EnergySolutions	A	17,010	340,195
Survey & Release			61,736	3,704,137
Processed Waste (Off-Site)	Recycling Vendors		67,958	2,843,938
Total <sup>[2]</sup>			1,019,785	93,258,217

<sup>[1]</sup> Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

<sup>[2]</sup> Columns may not add due to rounding

**TABLE 5.2**  
**DELAYED DECON ALTERNATIVE**  
**DECOMMISSIONING WASTE SUMMARY**

Waste	Cost Basis	Class <sup>[1]</sup>	Waste Volume (cubic feet)	Weight (pounds)
Geologic Repository	Spent Fuel	GTCC	2,856	564,685
	Equivalent		357	20,514
Primary waste stream				
	WCS	C	2,734	237,772
	WCS	B	26,918	1,928,673
Secondary waste stream				
	EnergySolutions	A	177,438	13,872,058
Tertiary waste stream				
Concrete	EnergySolutions	A	613,465	66,003,572
Soil	EnergySolutions	A	48,992	3,723,414
DAW	EnergySolutions	A	18,060	361,194
Survey & Release			61,736	3,704,137
Processed Waste (Off-Site)	Recycling Vendors		67,958	2,843,938
Total <sup>[2]</sup>			1,020,514	93,259,957

<sup>[1]</sup> Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

<sup>[2]</sup> Columns may not add due to rounding

**TABLE 5.3**  
**SAFSTOR ALTERNATIVE**  
**DECOMMISSIONING WASTE SUMMARY**

Waste	Cost Basis	Class <sup>[1]</sup>	Waste Volume (cubic feet)	Weight (pounds)
Geologic Repository	Spent Fuel	GTCC	2,856	564,685
	Equivalent		357	20,514
Primary waste stream				
	WCS	C	2,734	237,772
	WCS	B	26,918	1,928,673
Secondary waste stream				
	EnergySolutions	A	176,490	13,805,128
Tertiary waste stream				
Concrete	EnergySolutions	A	613,465	66,003,568
Soil	EnergySolutions	A	48,992	3,723,414
DAW	EnergySolutions	A	21,415	428,298
Survey & Release			61,736	3,704,137
Processed Waste (Off-Site)	Recycling Vendors		68,950	2,895,277
Total <sup>[2]</sup>			1,023,913	93,311,466

<sup>[1]</sup> Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

<sup>[2]</sup> Columns may not add due to rounding.

## 6. RESULTS

The analysis to estimate the costs to decommission TMI-2 relied upon the site-specific, technical information developed in 1995-96 and last updated in 2008. While not an engineering study, the estimates provide FirstEnergy with sufficient information to assess its financial obligations, as they pertain to the eventual decommissioning of the nuclear station.

The estimates described in this report are based on numerous fundamental assumptions, including regulatory requirements, project contingencies, radioactive waste disposal options, and site remediation requirements. The decommissioning scenarios assume that the remainder of the spent fuel (less than 1%), which is dispersed throughout the reactor coolant and support systems, is packaged, shipped and buried as radioactive waste. Some of the waste that is generated is assumed to be GTCC. This waste is assumed to be transferred to the DOE at the time that it is processed and collected during the decommissioning. No costs have been included for the temporary storage of GTCC material.

The cost projected to decommission TMI-2, i.e., by the DECON alternative, is estimated to be \$1.19 billion. The majority of this cost (approximately 97%) is associated with the physical decontamination and dismantling of the nuclear unit so that the license can be terminated. The remaining 3% is for the demolition of the designated structures and limited restoration of the site. The costs for the other decommission alternatives, Delayed DECON and SAFSTOR, are estimated at \$1.18 billion and \$1.24 billion, respectively.

The primary cost contributors, identified in Tables 6.1 through 6.3, are either labor-related or associated with the management and disposition of the radioactive waste. Program management is the largest single contributor to the overall cost. The magnitude of the expense is a function of both the size of the organization required to manage the decommissioning, as well as the duration of the program. It is assumed, for purposes of this analysis, that FirstEnergy will oversee the decommissioning program, using a DOC to manage the decommissioning labor force and the associated subcontractors. The size and composition of the management organization varies with the decommissioning phase and associated site activities. However, once the license is terminated, the staff is substantially reduced for the conventional demolition and restoration of the site.

The cost for waste disposal includes only those costs associated with the controlled disposition of the radioactive waste generated from decontamination and dismantling activities, including plant equipment and components, structural material, filters, resins and dry-active waste. As described in Section 5, disposal of



the lower level material, including concrete and structural steel, is at the EnergySolutions facility. The more highly radioactive waste is sent to Waste Control Specialists in Texas. Highly contaminated components, requiring additional isolation from the environment, are packaged for geologic disposal.

Removal costs reflect the labor-intensive nature of the decommissioning process, as well as the management controls required to ensure a safe and successful program. Decontamination and packaging costs also have a large labor component that is based upon prevailing union wages. Non-radiological demolition is a natural extension of the decommissioning process. The methods employed in decontamination and dismantling are generally destructive and indiscriminate in inflicting collateral damage. With a work force mobilized to support decommissioning operations, non-radiological demolition can be an integrated activity and a logical expansion of the work being performed in the process of terminating the license.

The reported cost for transport includes the tariffs and surcharges associated with moving large components and/or overweight shielded casks overland, as well as the general expense, e.g., labor and fuel, of transporting material to the destinations identified in this report.

License termination survey costs are associated with the labor intensive and complex activity of verifying that contamination has been removed from the site to the levels specified by the regulating agency. This process involves a systematic survey of all remaining plant surface areas and surrounding environs, sampling, isotopic analysis, and documentation of the findings. The status of any plant components and materials not removed in the decommissioning process will also require confirmation and will add to the expense of surveying the facilities alone. Due to the complete removal of the reactor, auxiliary and fuel buildings, the final termination survey effort is reduced.

The remaining costs include allocations for heavy equipment and temporary services, as well as for other expenses such as regulatory fees and the premiums for nuclear insurance.

**TABLE 6.1**  
**DECON ALTERNATIVE**  
**DECOMMISSIONING COST ELEMENTS**  
(thousands of 2013 dollars)

Cost Element	Total	Percentage
Decontamination	35,403	3.0
Removal	189,064	15.9
Packaging	28,008	2.4
Transportation	26,427	2.2
Waste Disposal	276,112	23.2
Off-site Waste Processing	11,053	0.9
Program Management <sup>[1]</sup>	484,509	40.8
Security	55,590	4.7
Insurance and Regulatory Fees	15,766	1.3
Energy	18,061	1.5
Characterization and Licensing Surveys	10,844	0.9
Property Taxes	0	0.0
Miscellaneous Equipment	23,851	2.0
Site O&M	4,968	0.4
PDMS Monitoring	8,908	0.8
Total <sup>[2]</sup>	1,188,564	100.0

Cost Element	Total	Percentage
License Termination	1,149,098	96.7
Site Restoration	39,467	3.3
Total <sup>[2]</sup>	1,188,564	100.0

<sup>[1]</sup> Includes engineering costs

<sup>[2]</sup> Columns may not add due to rounding

**TABLE 6.2**  
**DELAYED DECON ALTERNATIVE**  
**DECOMMISSIONING COST ELEMENTS**  
(thousands of 2013 dollars)

Cost Element	Total <sup>[1]</sup>	Percentage
Decontamination	35,321	3.0
Removal	190,858	16.2
Packaging	28,007	2.4
Transportation	26,310	2.2
Waste Disposal	276,022	23.4
Off-site Waste Processing	11,053	0.9
Program Management <sup>[2]</sup>	472,755	40.2
Security	46,850	4.0
Insurance and Regulatory Fees	21,899	1.9
Energy	19,459	1.7
Characterization and Licensing Surveys	10,844	0.9
Property Taxes	0	0.0
Miscellaneous Equipment	26,259	2.2
Site O&M	4,968	0.4
PDMS Monitoring	6,949	0.6
Total <sup>[3]</sup>	1,177,554	100.0

Cost Element	Total	Percentage
License Termination	1,139,536	96.8
Site Restoration	38,018	3.2
Total <sup>[3]</sup>	1,177,554	100.0

<sup>[1]</sup> Includes dormancy costs following TMI-1 shutdown in 2034

<sup>[2]</sup> Includes engineering costs

<sup>[3]</sup> Columns may not add due to rounding

**TABLE 6.3**  
**SAFSTOR ALTERNATIVE**  
**DECOMMISSIONING COST ELEMENTS**  
(thousands of 2013 dollars)

Cost Element	Total <sup>[1]</sup>	Percentage
Decontamination	35,286	2.9
Removal	196,595	15.9
Packaging	28,065	2.3
Transportation	26,298	2.1
Waste Disposal	275,884	22.3
Off-site Waste Processing	11,206	0.9
Program Management <sup>[2]</sup>	482,930	39.0
Security	56,699	4.6
Insurance and Regulatory Fees	41,497	3.4
Energy	28,227	2.3
Characterization and Licensing Surveys	10,844	0.9
Property Taxes	0	0.0
Miscellaneous Equipment	33,617	2.7
Site O&M	4,968	0.4
PDMS Monitoring	6,949	0.6
Total <sup>[3]</sup>	1,239,065	100.0

Cost Element	Total	Percentage
License Termination	1,201,047	96.9
Site Restoration	38,018	3.1
Total <sup>[3]</sup>	1,239,065	100.0

<sup>[1]</sup> Includes dormancy costs following TMI-1 shutdown in 2034

<sup>[2]</sup> Includes engineering costs

<sup>[3]</sup> Columns may not add due to rounding

## **7. REFERENCES**

1. "Decommissioning Cost Estimate for the Three Mile Island, Unit 2," Document No. G01-1196-003, TLG Services, Inc., February 1996
2. "Decommissioning Cost Estimate for Three Mile Island Unit 2," Document No. F07-1601-002, TLG Services, Inc., January 2009
3. U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72, "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018 et seq.), June 27, 1988
4. U.S. Nuclear Regulatory Commission, Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors," October 2003
5. U.S. Code of Federal Regulations, Title 10, Part 20, Subpart E, "Radiological Criteria for License Termination." Federal Register, Volume 62, Number 139 (p 39058 et seq.), July 21, 1997
6. U.S. Code of Federal Regulations, Title 10, Parts 20 and 50, "Entombment Options for Power Reactors," Advanced Notice of Proposed Rulemaking, Federal Register Volume 66, Number 200, October 16, 2001
7. U.S. Code of Federal Regulations, Title 10, Parts 2, 50 and 51, "Decommissioning of Nuclear Power Reactors," Nuclear Regulatory Commission, Federal Register Volume 61 (p 39278 et seq.), July 29, 1996
8. "Nuclear Waste Policy Act of 1982 and Amendments," U.S. Department of Energy's Office of Civilian Radioactive Management, 1982
9. Blue Ribbon Commission on America's Nuclear Future's Charter, <http://cybercemetery.unt.edu/archive/brc/20120620215336/http://brc.gov/index.php?q=page/charter>
10. "Blue Ribbon Commission on America's Nuclear Future, Report to the Secretary of Energy," [http://www.brc.gov/sites/default/files/documents/brc\\_finalreport\\_jan2012.pdf](http://www.brc.gov/sites/default/files/documents/brc_finalreport_jan2012.pdf), January 2012
11. Strategy for the Management and Disposal of Used Nuclear Fuel and High-Level Radioactive Waste," U.S. DOE, January 11, 2013

**7. REFERENCES**  
(continued)

12. "Acceptance Priority Ranking & Annual Capacity Report," DOE/RW-0567, July 2004
13. "Low-Level Radioactive Waste Policy Act," Public Law 96-573, 1980
14. "Low-Level Radioactive Waste Policy Amendments Act of 1985," Public Law 99-240, January 15, 1986
15. Waste is classified in accordance with U.S. Code of Federal Regulations, Title 10, Part 61.55
16. "Establishment of Cleanup Levels for CERCLA Sites with Radioactive Contamination," EPA Memorandum OSWER No. 9200.4-18, August 22, 1997
17. U.S. Code of Federal Regulations, Title 40, Part 141.16, "Maximum contaminant levels for beta particle and photon radioactivity from man-made radionuclides in community water systems."
18. "Memorandum of Understanding between the Environmental Protection Agency and the Nuclear Regulatory Commission: Consultation and Finality on Decommissioning and Decontamination of Contaminated Sites," OSWER 9295.8-06a, October 9, 2002
19. Three Mile Island Unit 2 Post Defueling Monitored Storage Safety Analysis Report, 1995 Update, Chapter 4 (Fuel), GPU Nuclear Corporation 1995
20. "Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM)," NUREG/CR-1575, Rev. 1, EPA 402-R-97-016, Rev. 1, August 2000
21. T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986
22. W.J. Manion and T.S. LaGuardia, "Decommissioning Handbook," U.S. Department of Energy, DOE/EV/10128-1, November 1980

**7. REFERENCES**  
(continued)

23. "Building Construction Cost Data 2013," Robert Snow Means Company, Inc., Kingston, Massachusetts
24. Project and Cost Engineers' Handbook, Second Edition, p. 239, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York, 1984
25. "Strategy for Management and Disposal of Greater-Than-Class C Low-Level Radioactive Waste," Federal Register Volume 60, Number 48 (p 13424 et seq.), March 1995
26. U.S. Department of Transportation, Title 49 of the Code of Federal Regulations, "Transportation," Parts 173 through 178, 1996
27. Tri-State Motor Transit Company, published tariffs, Interstate Commerce Commission (ICC), Docket No. MC-109397 and Supplements, 2000
28. J.C. Evans et al., "Long-Lived Activation Products in Reactor Materials" NUREG/CR-3474, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. August 1984
29. R.I. Smith, G.J. Konzek, W.E. Kennedy, Jr., "Technology, Safety and Costs of Decommissioning a Reference Pressurized Water Reactor Power Station," NUREG/CR-0130 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. June 1978
30. H.D. Oak, et al., "Technology, Safety and Costs of Decommissioning a Reference Boiling Water Reactor Power Station," NUREG/CR-0672 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. June 1980
31. "Financial Protection Requirements for Permanently Shutdown Nuclear Power Reactors," 10 CFR Parts 50 and 140, Federal Register Notice, Vol. 62, No. 210, October 30, 1997
32. "Microsoft Project 2010," Microsoft Corporation, Redmond, WA, 2010
33. "Atomic Energy Act of 1954," (68 Stat. 919)

**APPENDIX A**

**UNIT COST FACTOR DEVELOPMENT**



## APPENDIX A UNIT COST FACTOR DEVELOPMENT

Example: Unit Factor for Removal of Contaminated Heat Exchanger < 3,000 lbs.

### 1. SCOPE

Heat exchangers weighing < 3,000 lbs. will be removed in one piece using a crane or small hoist. They will be disconnected from the inlet and outlet piping. The heat exchanger will be sent to the waste processing area.

### 2. CALCULATIONS

Act ID	Activity Description	Activity Duration (minutes)	Critical Duration (minutes)*
a	Remove insulation	60	(b)
b	Mount pipe cutters	60	60
c	Install contamination controls	20	(b)
d	Disconnect inlet and outlet lines	60	60
e	Cap openings	20	(d)
f	Rig for removal	30	30
g	Unbolt from mounts	30	30
h	Remove contamination controls	15	15
i	Remove, wrap, send to waste processing area	<u>60</u>	<u>60</u>
Totals (Activity/Critical)		355	255

Duration adjustment(s):

+ Respiratory protection adjustment (25% of critical duration) 64

+ Radiation/ALARA adjustment (25% of critical duration) 64

Adjusted work duration 383

+ Protective clothing adjustment (30% of adjusted duration) 115

Productive work duration 498

+ Work break adjustment (8.33 % of productive duration) 42

Total work duration (minutes) 540

**\*\*\* Total duration = 9.000 hr \*\*\***

\* alpha designators indicate activities that can be performed in parallel

**APPENDIX A**  
(continued)

**3. LABOR REQUIRED**

Crew	Number	Duration (hours)	Rate (\$/hr)	Cost (\$)
Laborers	3.00	9.000	33.92	\$915.84
Craftsmen	2.00	9.000	59.98	1,079.64
Foreman	1.00	9.000	61.79	556.11
General Foreman	0.25	9.000	65.28	146.88
Fire Watch	0.05	9.000	33.92	15.26
Health Physics Technician	1.00	9.000	48.84	<u>439.56</u>
Total Labor Cost				\$3,153.29

**4. EQUIPMENT & CONSUMABLES COSTS**

Equipment Costs	none
Consumables/Materials Costs	
- Universal Sorbent 50 @ \$0.49 sq ft <sup>(1)</sup>	\$24.50
- Tarpaulins (oil resistant/fire retardant) 50 @ \$0.22/sq ft <sup>(2)</sup>	\$11.00
- Gas torch consumables 1 @ \$13.49/hr x 1 hr <sup>(3)</sup>	<u>\$13.49</u>
Subtotal cost of equipment and materials	\$48.99
Overhead & profit on equipment and materials @ 16.00 %	<u>\$7.84</u>
Total costs, equipment & material	\$56.83

**TOTAL COST:**

Removal of contaminated heat exchanger <3000 pounds:	\$3,210.12
Total labor cost:	\$3,153.29
Total equipment/material costs:	\$56.83
Total craft labor man-hours required per unit:	65.700

## **5. NOTES AND REFERENCES**

- Work difficulty factors were developed in conjunction with the Atomic Industrial Forum's (now NEI) program to standardize nuclear decommissioning cost estimates and are delineated in Volume 1, Chapter 5 of the "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.
- References for equipment & consumables costs:
  1. [www.mcmaster.com](http://www.mcmaster.com) online catalog, McMaster Carr Spill Control (7193T88)
  2. R.S. Means (2013) Division 01 56, Section 13.60-0600, page 22
  3. R.S. Means (2013) Division 01 54 33, Section 40-6360, page 688
- Material and consumable costs were adjusted using the regional indices for Harrisburg, Pennsylvania.

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(SAFSTOR: Power Block Structures Only)**

## APPENDIX B

### UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Removal of clean instrument and sampling tubing, \$/linear foot	0.65
Removal of clean pipe 0.25 to 2 inches diameter, \$/linear foot	5.73
Removal of clean pipe >2 to 4 inches diameter, \$/linear foot	8.28
Removal of clean pipe >4 to 8 inches diameter, \$/linear foot	18.21
Removal of clean pipe >8 to 14 inches diameter, \$/linear foot	32.80
Removal of clean pipe >14 to 20 inches diameter, \$/linear foot	42.69
Removal of clean pipe >20 to 36 inches diameter, \$/linear foot	62.52
Removal of clean pipe >36 inches diameter, \$/linear foot	74.66
Removal of clean valve >2 to 4 inches	122.01
Removal of clean valve >4 to 8 inches	182.14
Removal of clean valve >8 to 14 inches	328.02
Removal of clean valve >14 to 20 inches	426.90
Removal of clean valve >20 to 36 inches	625.24
Removal of clean valve >36 inches	746.63
Removal of clean pipe hanger for small bore piping	41.06
Removal of clean pipe hanger for large bore piping	128.91
Removal of clean pump, <300 pound	307.22
Removal of clean pump, 300-1000 pound	837.90
Removal of clean pump, 1000-10,000 pound	2,992.23
Removal of clean pump, >10,000 pound	5,785.54
Removal of clean pump motor, 300-1000 pound	358.40
Removal of clean pump motor, 1000-10,000 pound	1,246.71
Removal of clean pump motor, >10,000 pound	2,802.79
Removal of clean heat exchanger <3000 pound	1,685.84
Removal of clean heat exchanger >3000 pound	4,237.90
Removal of clean feedwater heater/deaerator	11,387.33
Removal of clean moisture separator/reheater	22,925.30
Removal of clean tank, <300 gallons	395.46
Removal of clean tank, 300-3000 gallon	1,240.33
Removal of clean tank, >3000 gallons, \$/square foot surface area	10.06

## APPENDIX B

### UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Removal of clean electrical equipment, <300 pound	172.57
Removal of clean electrical equipment, 300-1000 pound	578.96
Removal of clean electrical equipment, 1000-10,000 pound	1,148.82
Removal of clean electrical equipment, >10,000 pound	2,659.64
Removal of clean electrical transformer < 30 tons	1,878.11
Removal of clean electrical transformer > 30 tons	5,319.28
Removal of clean standby diesel generator, <100 kW	1,888.50
Removal of clean standby diesel generator, 100 kW to 1 MW	4,212.30
Removal of clean standby diesel generator, >1 MW	8,718.57
Removal of clean electrical cable tray, \$/linear foot	15.55
Removal of clean electrical conduit, \$/linear foot	6.65
Removal of clean mechanical equipment, <300 pound	172.57
Removal of clean mechanical equipment, 300-1000 pound	578.96
Removal of clean mechanical equipment, 1000-10,000 pound	1,148.82
Removal of clean mechanical equipment, >10,000 pound	2,659.64
Removal of clean HVAC equipment, <300 pound	201.26
Removal of clean HVAC equipment, 300-1000 pound	680.14
Removal of clean HVAC equipment, 1000-10,000 pound	1,360.00
Removal of clean HVAC equipment, >10,000 pound	2,659.64
Removal of clean HVAC ductwork, \$/pound	0.69
Removal of contaminated instrument and sampling tubing, \$/linear foot	1.10
Removal of contaminated pipe 0.25 to 2 inches diameter, \$/linear foot	15.52
Removal of contaminated pipe >2 to 4 inches diameter, \$/linear foot	26.14
Removal of contaminated pipe >4 to 8 inches diameter, \$/linear foot	43.62
Removal of contaminated pipe >8 to 14 inches diameter, \$/linear foot	83.77
Removal of contaminated pipe >14 to 20 inches diameter, \$/linear foot	100.79
Removal of contaminated pipe >20 to 36 inches diameter, \$/linear foot	138.62
Removal of contaminated pipe >36 inches diameter, \$/linear foot	164.58
Removal of contaminated valve >2 to 4 inches	329.26
Removal of contaminated valve >4 to 8 inches	398.41

## APPENDIX B

### UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Removal of contaminated valve >8 to 14 inches	796.48
Removal of contaminated valve >14 to 20 inches	1,012.72
Removal of contaminated valve >20 to 36 inches	1,345.01
Removal of contaminated valve >36 inches	1,604.65
Removal of contaminated pipe hanger for small bore piping	106.09
Removal of contaminated pipe hanger for large bore piping	326.47
Removal of contaminated pump, <300 pound	696.25
Removal of contaminated pump, 300-1000 pound	1,655.34
Removal of contaminated pump, 1000-10,000 pound	5,414.54
Removal of contaminated pump, >10,000 pound	13,160.39
Removal of contaminated pump motor, 300-1000 pound	711.77
Removal of contaminated pump motor, 1000-10,000 pound	2,199.17
Removal of contaminated pump motor, >10,000 pound	4,965.06
Removal of contaminated heat exchanger <3000 pound	3,210.12
Removal of contaminated heat exchanger >3000 pound	9,308.12
Removal of contaminated tank, <300 gallons	1,162.67
Removal of contaminated tank, >300 gallons, \$/square foot	23.76
Removal of contaminated electrical equipment, <300 pound	545.67
Removal of contaminated electrical equipment, 300-1000 pound	1,339.76
Removal of contaminated electrical equipment, 1000-10,000 pound	2,573.65
Removal of contaminated electrical equipment, >10,000 pound	5,210.82
Removal of contaminated electrical cable tray, \$/linear foot	26.68
Removal of contaminated electrical conduit, \$/linear foot	12.65
Removal of contaminated mechanical equipment, <300 pound	614.05
Removal of contaminated mechanical equipment, 300-1000 pound	1,514.27
Removal of contaminated mechanical equipment, 1000-10,000 pound	2,913.58
Removal of contaminated mechanical equipment, >10,000 pound	5,210.82
Removal of contaminated HVAC equipment, <300 pound	614.05
Removal of contaminated HVAC equipment, 300-1000 pound	1,514.27
Removal of contaminated HVAC equipment, 1000-10,000 pound	2,913.58

## APPENDIX B

### UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Removal of contaminated HVAC equipment, >10,000 pound	5,210.82
Removal of contaminated HVAC ductwork, \$/pound	1.57
Removal/plasma arc cut of contaminated thin metal components, \$/linear in.	3.03
Additional decontamination of surface by washing, \$/square foot	5.90
Additional decontamination of surfaces by hydrolasing, \$/square foot	29.59
Decontamination rig hook up and flush, \$/ 250 foot length	5,166.38
Chemical flush of components/systems, \$/gallon	15.07
Removal of clean standard reinforced concrete, \$/cubic yard	161.72
Removal of grade slab concrete, \$/cubic yard	204.76
Removal of clean concrete floors, \$/cubic yard	384.77
Removal of sections of clean concrete floors, \$/cubic yard	1,172.57
Removal of clean heavily rein concrete w/#9 rebar, \$/cubic yard	246.65
Removal of contaminated heavily rein concrete w/#9 rebar, \$/cubic yard	1,631.53
Removal of clean heavily rein concrete w/#18 rebar, \$/cubic yard	312.17
Removal of contaminated heavily rein concrete w/#18 rebar, \$/cubic yard	2,151.28
Removal heavily rein concrete w/#18 rebar & steel embedments, \$/cubic yard	472.38
Removal of below-grade suspended floors, \$/cubic yard	384.77
Removal of clean monolithic concrete structures, \$/cubic yard	970.85
Removal of contaminated monolithic concrete structures, \$/cubic yard	1,625.26
Removal of clean foundation concrete, \$/cubic yard	773.12
Removal of contaminated foundation concrete, \$/cubic yard	1,512.45
Explosive demolition of bulk concrete, \$/cubic yard	34.41
Removal of clean hollow masonry block wall, \$/cubic yard	127.29
Removal of contaminated hollow masonry block wall, \$/cubic yard	225.66
Removal of clean solid masonry block wall, \$/cubic yard	127.29
Removal of contaminated solid masonry block wall, \$/cubic yard	225.66
Backfill of below-grade voids, \$/cubic yard	29.40
Removal of subterranean tunnels/voids, \$/linear foot	140.98
Placement of concrete for below-grade voids, \$/cubic yard	106.48
Excavation of clean material, \$/cubic yard	3.72



## APPENDIX B

### UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Excavation of contaminated material, \$/cubic yard	32.49
Removal of clean concrete rubble (tipping fee included), \$/cubic yard	23.55
Removal of contaminated concrete rubble, \$/cubic yard	22.75
Removal of building by volume, \$/cubic foot	0.34
Removal of clean building metal siding, \$/square foot	1.67
Removal of contaminated building metal siding, \$/square foot	2.95
Removal of standard asphalt roofing, \$/square foot	2.60
Removal of transite panels, \$/square foot	2.56
Scarifying contaminated concrete surfaces (drill & spall), \$/square foot	9.36
Scabbling contaminated concrete floors, \$/square foot	5.46
Scabbling contaminated concrete walls, \$/square foot	14.71
Scabbling contaminated ceilings, \$/square foot	50.37
Scabbling structural steel, \$/square foot	4.69
Removal of clean overhead crane/monorail < 10 ton capacity	850.33
Removal of contaminated overhead crane/monorail < 10 ton capacity	1,454.77
Removal of clean overhead crane/monorail >10-50 ton capacity	2,042.99
Removal of contaminated overhead crane/monorail >10-50 ton capacity	3,473.58
Removal of polar crane > 50 ton capacity	7,581.02
Removal of gantry crane > 50 ton capacity	30,668.72
Removal of structural steel, \$/pound	0.24
Removal of clean steel floor grating, \$/square foot	6.17
Removal of contaminated steel floor grating, \$/square foot	10.94
Removal of clean free standing steel liner, \$/square foot	15.27
Removal of contaminated free standing steel liner, \$/square foot	27.59
Removal of clean concrete-anchored steel liner, \$/square foot	7.55
Removal of contaminated concrete-anchored steel liner, \$/square foot	32.10
Placement of scaffolding in clean areas, \$/square foot	13.55
Placement of scaffolding in contaminated areas, \$/square foot	18.24
Landscaping with topsoil, \$/acre	21,312.72
Cost of CPC B-88 LSA box & preparation for use	1,727.27

**APPENDIX B**

**UNIT COST FACTOR LISTING  
(Power Block Structures Only)**

<b>Unit Cost Factor</b>	<b>Cost/Unit(\$)</b>
Cost of CPC B-25 LSA box & preparation for use	1,584.45
Cost of CPC B-12V 12 gauge LSA box & preparation for use	1,301.09
Cost of CPC B-144 LSA box & preparation for use	8,595.11
Cost of LSA drum & preparation for use	192.13
Cost of cask liner for CNSI 8 120A cask (resins)	7,110.93
Cost of cask liner for CNSI 8 120A cask (filters)	6,993.18
Decontamination of surfaces with vacuuming, \$/square foot	0.96

**APPENDIX C  
DETAILED COST ANALYSIS  
DECON**

Table C  
Three Mile Island Unit 2  
DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Burial Volumes			Burial/Processed Wt. Lbs.	Griff Manhours	Utility and Contractor Manhours
															Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet			
PERIOD 0a - PDMS Monitoring																				
Period On Collateral Costs																				
0a.3.1	PDMS Monitoring	-	-	-	-	-	-	7,746	1,102	8,908	8,908	-	-	-	-	-	-	-	-	-
0a.3	Subtotal Period On Collateral Costs	-	-	-	-	-	-	7,746	1,102	8,908	8,908	-	-	-	-	-	-	-	-	-
Period On Period-Dependent Costs																				
0a.4.1	Insurance	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0a.4.2	Property taxes	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0a.4.3	Plant energy budget	-	-	-	-	-	-	5,318	786	6,116	6,116	-	-	-	-	-	-	-	-	-
0a.4.3	Utility Staff Cost	-	-	-	-	-	-	66,059	8,659	74,718	74,718	-	-	-	-	-	-	-	-	284,886
0a.4.4	Subtotal Period On Period-Dependent Costs	-	-	-	-	-	-	64,377	9,467	74,033	74,033	-	-	-	-	-	-	-	-	284,886
0a.0	TOTAL PERIOD 0a COST	-	-	-	-	-	-	72,123	10,818	82,942	82,942	-	-	-	-	-	-	-	-	-
PERIOD 3a - Reactivate Site Following SAFSTOR Dormancy																				
Period 3a Direct Decommissioning Activities																				
3a.1.1	Prepare preliminary decommissioning cost	-	-	-	-	-	-	257	39	296	296	-	-	-	-	-	-	-	-	1,950
3a.1.2	Review plant design & specs.	-	-	-	-	-	-	1,213	182	1,395	1,395	-	-	-	-	-	-	-	-	9,200
3a.1.3	Perform detailed end survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2,000
3a.1.4	End product description	-	-	-	-	-	-	254	40	294	294	-	-	-	-	-	-	-	-	5,200
3a.1.5	Detailed by-product inventory	-	-	-	-	-	-	696	103	798	798	-	-	-	-	-	-	-	-	12,480
3a.1.6	Define major work sequence	-	-	-	-	-	-	1,977	274	2,274	2,274	-	-	-	-	-	-	-	-	3,200
3a.1.7	Perform SER and EA	-	-	-	-	-	-	8,226	1,234	9,460	9,460	-	-	-	-	-	-	-	-	400
3a.1.8	Perform Site-Specific Cost Study	-	-	-	-	-	-	1,318	186	1,516	1,516	-	-	-	-	-	-	-	-	10,000
3a.1.9	Prepare/submit License Termination Plan	-	-	-	-	-	-	2,162	324	2,466	2,466	-	-	-	-	-	-	-	-	16,400
3a.1.10	Receive NRC approval of termination plan	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Activity Specifications																				
3a.1.1.1.1	Re-activate plant & temporary facilities	-	-	-	-	-	-	1,457	219	1,676	1,676	-	168	-	-	-	-	-	-	11,005
3a.1.1.1.2	Plant systems	-	-	-	-	-	-	1,099	165	1,263	1,263	-	126	-	-	-	-	-	-	8,333
3a.1.1.1.3	Reactor internals	-	-	-	-	-	-	1,872	281	2,153	2,153	-	-	-	-	-	-	-	-	14,200
3a.1.1.1.4	Reactor vessel	-	-	-	-	-	-	1,285	183	1,478	1,478	-	-	-	-	-	-	-	-	9,700
3a.1.1.1.5	Biological shield	-	-	-	-	-	-	1,777	274	2,051	2,051	-	-	-	-	-	-	-	-	12,480
3a.1.1.1.6	Steam generators	-	-	-	-	-	-	1,645	247	1,892	1,892	-	-	-	-	-	-	-	-	3,200
3a.1.1.1.7	Reinforced concrete	-	-	-	-	-	-	422	63	485	485	-	243	-	-	-	-	-	-	400
3a.1.1.1.8	Main Turbine	-	-	-	-	-	-	53	8	61	61	-	61	-	-	-	-	-	-	400
3a.1.1.1.9	Main Condensers	-	-	-	-	-	-	411	62	473	473	-	237	-	-	-	-	-	-	3,400
3a.1.1.1.10	Plant structures & buildings	-	-	-	-	-	-	2,535	384	2,919	2,919	-	237	-	-	-	-	-	-	18,400
3a.1.1.1.11	Waste management	-	-	-	-	-	-	2,425	364	2,790	2,790	-	68	-	-	-	-	-	-	900
3a.1.1.1.12	Facility & site cleanup	-	-	-	-	-	-	1,047	16	1,063	1,063	-	953	-	-	-	-	-	-	82,738
3a.1.1.1	Total	-	-	-	-	-	-	10,907	1,636	12,544	12,544	-	-	-	-	-	-	-	-	4,800
Planning & Site Preparations																				
3a.1.1.2	Prepare dismantling sequence	-	-	-	-	-	-	633	95	728	728	-	-	-	-	-	-	-	-	5,000
3a.1.1.3	Plant prep & temp. access	-	-	-	-	-	-	2,535	385	3,335	3,335	-	-	-	-	-	-	-	-	2,400
3a.1.1.4	Design water clean-up system	-	-	-	-	-	-	738	111	849	849	-	-	-	-	-	-	-	-	-
3a.1.1.5	Rigging/Cont. Ctrl. Exports/tooling/etc.	-	-	-	-	-	-	2,200	330	2,530	2,530	-	-	-	-	-	-	-	-	-
3a.1.1.6	Procure caskloaders & containers	-	-	-	-	-	-	324	49	373	373	-	-	-	-	-	-	-	-	-
3a.1	Subtotal Period 3a Activity Costs	-	-	-	-	-	-	33,808	5,071	38,877	38,877	-	963	-	-	-	-	-	-	217,748
Period 3a Additional Costs																				
3a.2.1	Reactor vessel	-	-	-	-	-	-	330	50	380	380	-	-	-	-	-	-	-	-	-
3a.2.2	Reactor internals	-	-	-	-	-	-	1,290	194	1,484	1,484	-	-	-	-	-	-	-	-	-
3a.2.3	Reactor Concrete Refurbishment	-	-	-	-	-	-	6,450	968	7,418	7,418	-	-	-	-	-	-	-	-	-
3a.2.4	Reactor Vessel Refurbishment	-	-	-	-	-	-	1,290	194	1,484	1,484	-	-	-	-	-	-	-	-	-
3a.2	Subtotal Period 3a Additional Costs	-	-	-	-	-	-	9,360	1,404	10,764	10,764	-	-	-	-	-	-	-	-	-
3a.0	TOTAL PERIOD 3a COST	-	-	-	-	-	-	43,269	6,475	49,744	49,744	-	-	-	-	-	-	-	-	-

Table C  
Three Mile Island Unit 2  
DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Special Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet	Burial / Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours
Period 3a Period-Dependent Costs																					
3a.4.1	Insurance	-	-	-	-	-	-	208	21	229	226	-	-	-	-	-	-	-	-	-	-
3a.4.2	Property taxes	-	633	-	-	-	-	-	166	779	779	-	-	-	-	-	-	-	-	-	-
3a.4.3	Health physics supplies	-	430	-	-	-	-	-	166	494	494	-	-	-	-	-	-	-	-	-	-
3a.4.4	Health physics personnel	-	-	-	-	-	-	-	64	494	494	-	-	-	-	-	-	-	-	-	-
3a.4.5	Disposal of DAW generated	-	-	9	-	-	25	-	8	50	50	-	-	-	-	-	-	-	-	22	-
3a.4.6	Plant energy budget	-	-	-	-	-	-	976	146	1,122	1,122	-	-	-	-	-	-	-	-	-	-
3a.4.7	NRC Fees	-	-	-	-	-	-	1,276	127	1,402	1,402	-	-	-	-	-	-	-	-	-	-
3a.4.8	Site O&M	-	-	-	-	-	-	3,222	355	4,242	4,242	-	-	-	-	-	-	-	-	-	-
3a.4.9	Site O&M Staff Cost	-	-	-	-	-	-	1,711	185	2,100	2,100	-	-	-	-	-	-	-	-	-	-
3a.4.10	DOE Staff Cost	-	-	-	-	-	-	11,763	1,764	13,527	13,527	-	-	-	-	-	-	-	-	-	-
3a.4.11	Utility Staff Cost	-	-	-	-	-	-	2,623	353	3,017	3,017	-	-	-	-	-	-	-	-	-	-
3a.4	Subtotal Period 3a Period-Dependent Costs	-	1,053	9	8	-	25	20,853	3,252	25,230	25,230	-	-	-	-	-	-	-	-	22	276,879
3a.0	TOTAL PERIOD 3a COST	-	1,053	9	8	-	25	64,018	9,757	74,870	74,868	-	-	-	-	-	-	-	-	22	494,927
PERIOD 3b - Decommissioning Preparations																					
Period 3b Direct Decommissioning Activities																					
Detailed Work Procedures																					
3b.1.1.1	Plant removal	-	-	-	-	-	-	1,248	187	1,435	1,292	-	-	-	-	-	-	-	-	-	9,496
3b.1.1.2	Plant removal materials	-	-	-	-	-	-	689	99	788	756	-	-	-	-	-	-	-	-	-	5,090
3b.1.1.3	Remaining buildings	-	-	-	-	-	-	178	27	205	61	-	-	-	-	-	-	-	-	-	1,350
3b.1.1.4	CRD cooling assembly	-	-	-	-	-	-	198	30	227	227	-	-	-	-	-	-	-	-	-	1,500
3b.1.1.5	CRD housing & ICI tubes	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3b.1.1.6	Access instrumentation	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3b.1.1.7	Access instrumentation	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3b.1.1.8	Facility cleanup	-	-	-	-	-	-	718	108	825	825	-	-	-	-	-	-	-	-	-	5,445
3b.1.1.9	Missile shields	-	-	-	-	-	-	158	24	182	91	-	-	-	-	-	-	-	-	-	1,200
3b.1.1.10	Biological shield	-	-	-	-	-	-	59	9	68	68	-	-	-	-	-	-	-	-	-	450
3b.1.1.11	Steam generators	-	-	-	-	-	-	158	24	182	182	-	-	-	-	-	-	-	-	-	1,200
3b.1.1.12	Reinforced concrete	-	-	-	-	-	-	2,498	364	2,790	2,790	-	-	-	-	-	-	-	-	-	15,000
3b.1.1.13	Reinforced concrete	-	-	-	-	-	-	158	24	182	182	-	-	-	-	-	-	-	-	-	1,200
3b.1.1.14	Main Condensers	-	-	-	-	-	-	206	31	237	237	-	-	-	-	-	-	-	-	-	1,560
3b.1.1.15	Auxiliary building	-	-	-	-	-	-	206	31	237	237	-	-	-	-	-	-	-	-	-	1,560
3b.1.1.16	Reactor building	-	-	-	-	-	-	720	108	828	745	-	-	-	-	-	-	-	-	-	5,460
3b.1.1	Total	-	-	-	-	-	-	7,785	1,198	8,983	7,860	-	-	-	-	-	-	-	-	-	59,931
3b.1	Subtotal Period 3b Activity Costs	-	-	-	-	-	-	7,785	1,198	8,983	7,860	-	-	-	-	-	-	-	-	-	59,931
Period 3b Additional Costs																					
3b.2.1	Lead Shielding Disposal	-	740	225	611	-	5,474	-	1,698	8,717	8,717	-	-	-	-	-	-	-	-	14,333	-
3b.2.2	Stored Defueling Equipment Disposition	-	588	63	104	-	884	-	390	2,059	2,059	-	-	-	-	-	-	-	-	12,077	-
3b.2	Subtotal Period 3b Additional Costs	-	1,328	288	715	-	6,358	-	2,057	10,746	10,746	-	-	-	-	-	-	-	-	26,410	-
Period 3b Collateral Costs																					
3b.3.1	Decon equipment	712	-	-	-	-	-	-	107	819	819	-	-	-	-	-	-	-	-	-	-
3b.3.2	DOE staff relocation expenses	-	-	-	-	-	-	1,385	208	1,593	1,593	-	-	-	-	-	-	-	-	-	-
3b.3.3	Small tool allowance	-	-	-	-	-	-	-	3	21	21	-	-	-	-	-	-	-	-	-	-
3b.3.4	Pipe cutting equipment	-	1,100	-	-	-	-	-	165	1,265	1,265	-	-	-	-	-	-	-	-	-	-
3b.3	Subtotal Period 3b Collateral Costs	712	1,118	-	-	-	-	1,385	482	3,696	3,696	-	-	-	-	-	-	-	-	-	-
Period 3b Period-Dependent Costs																					
3b.4.1	Decon supplies	22	-	-	-	-	-	-	6	28	28	-	-	-	-	-	-	-	-	-	-
3b.4.2	Insurance	-	-	-	-	-	-	104	-	115	115	-	-	-	-	-	-	-	-	-	-
3b.4.3	Property taxes	-	-	-	-	-	-	-	134	672	672	-	-	-	-	-	-	-	-	-	-
3b.4.4	Health physics supplies	-	597	-	-	-	-	-	33	251	251	-	-	-	-	-	-	-	-	-	-
3b.4.5	Health physics personnel	-	218	-	-	-	-	-	5	29	29	-	-	-	-	-	-	-	-	-	-
3b.4.6	Disposal of DAW generated	-	-	5	-	-	15	-	5	29	29	-	-	-	-	-	-	-	-	13	-
3b.4.7	Plant energy budget	-	-	-	-	-	-	465	74	569	569	-	-	-	-	-	-	-	-	-	-
3b.4.8	NRC Fees	-	-	-	-	-	-	645	65	711	711	-	-	-	-	-	-	-	-	-	-
3b.4.9	Site O&M	-	-	-	-	-	-	1,038	111	1,149	1,149	-	-	-	-	-	-	-	-	-	-
3b.4.10	Liquid Resin Waste Processing Equipment/Services	-	-	-	-	-	-	34	34	34	34	-	-	-	-	-	-	-	-	-	-
3b.4.11	DOE Staff Cost	-	-	-	-	-	-	2,150	280	2,430	2,430	-	-	-	-	-	-	-	-	-	-
3b.4.12	DOE Staff Cost	-	-	-	-	-	-	12,648	1,897	14,545	14,545	-	-	-	-	-	-	-	-	-	-
3b.4.13	Utility Staff Cost	-	-	-	-	-	-	1,323	188	1,511	1,511	-	-	-	-	-	-	-	-	-	-
3b.4	Subtotal Period 3b Period-Dependent Costs	22	755	5	5	-	15	17,445	2,757	21,004	21,004	-	-	-	-	-	-	-	-	13	211,270

Table C  
Three Mile Island Unit 2  
DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	WFO Lic. Fees	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet	Partial / Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours	
38.0	TOTAL PERIOD 3b COST	734	3,202	283	720	-	6,372	26,615	6,464	44,400	43,296	-	1,102	-	6,398	-	-	-	1,673,372	26,423	270,321	
PERIOD 3 TOTALS																						
PERIOD 4a - Large Component Removal																						
Period 4a Direct Decommissioning Activities																						
4a.1.1.1	Nuclear Steam Supply System Removal	22	86	16	27	-	387	-	135	674	674	-	-	-	877	-	-	-	100,307	2,255	-	
4a.1.1.1.1	Reactor Coolant Pump	3	12	3	6	-	80	-	26	131	131	-	-	-	188	-	-	-	20,849	315	-	
4a.1.1.1.2	Reactor Coolant Pump & Motors	-	1,257	883	130	-	3,155	-	1,213	6,646	6,646	-	-	-	10,752	-	-	-	1,124,474	31,482	-	
4a.1.1.1.3	Reactor Coolant Pump & Motors	-	1,333	757	177	-	3,178	-	630	3,673	3,673	-	-	-	2,644	-	-	-	462,726	4,162	-	
4a.1.1.1.4	Steam Generators	34	6,990	1,108	3,120	-	31,918	-	10,251	53,188	53,188	-	-	-	24,692	-	-	-	2,396,298	146,491	-	
4a.1.1.1.5	CRDMs/Clad Service Structure Removal	12	55	176	64	-	85	-	12	364	364	-	-	-	1,454	-	-	-	17,112	1,162	-	
4a.1.1.1.6	Reactor Vessel Internal	82	12,078	9,689	587	-	38,734	-	2,055	15,798	15,798	-	-	-	2,654	-	-	-	235,905	48,186	2,871	
4a.1.1.1.8	Vessel & Internals GTCC Disposal	-	10,532	9,692	522	-	13,703	-	2,055	15,798	15,798	-	-	-	9,626	-	-	-	664,685	2,871	-	
4a.1.1.1.9	Reactor Vessel	154	33,125	10,719	5,014	-	53,862	1,341	37,850	147,165	147,165	-	-	-	52,738	-	-	-	5,032,504	286,357	5,741	
4a.1.1.1	Totals	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Removal of Major Equipment																						
4a.1.2	Main Turbine/Generator	-	278	93	23	615	-	-	175	1,184	1,184	-	-	5,598	-	-	-	-	238,364	5,389	-	
4a.1.3	Main Condensers	-	1,271	103	25	680	-	-	434	2,514	2,514	-	-	5,660	-	-	-	-	263,690	23,162	-	
4a.1.4.1	Cascading Costs from Clean Building Demolition	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
4a.1.4.1	Control & Service	-	196	-	-	-	-	-	25	191	191	-	-	-	-	-	-	-	-	2,080	-	
4a.1.4	Totals	-	196	-	-	-	-	-	25	191	191	-	-	-	-	-	-	-	-	2,080	-	
Disposal of Plant Systems																						
4a.1.5.1	Decay Heat Closed Cooling Water	-	290	34	60	697	348	-	274	1,693	1,693	-	-	6,556	1,363	-	-	-	360,509	6,823	-	
4a.1.5.2	Decay Heat Removal (RCA)	-	200	55	74	283	664	-	272	1,527	1,527	-	-	2,611	2,997	-	-	-	273,893	4,350	-	
4a.1.5.3	Decay Heat Removal (Vord)	-	140	-	-	-	-	-	21	161	161	-	161	-	-	-	-	-	-	2,863	-	
4a.1.5.4	Deionized Water (RCA)	-	142	8	11	57	92	-	70	381	381	-	-	547	562	-	-	-	48,162	2,869	-	
4a.1.5.5	Deionized Water (Vord)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	148	-	
4a.1.5.6	Domestic Water (Clean)	-	21	1	2	7	14	-	10	54	54	-	7	63	64	-	-	-	6,162	420	-	
4a.1.5.7	Electrical (Clean)	-	9	-	-	-	-	-	11	11	11	-	11	-	-	-	-	-	-	191	-	
4a.1.5.8	Emergency Feedwater (RCA)	-	65	5	6	43	51	-	37	209	209	-	62	407	196	-	-	-	29,642	1,352	-	
4a.1.5.9	Fire Protection (Clean)	-	54	-	-	-	-	-	8	62	62	-	-	-	-	-	-	-	-	1,167	-	
4a.1.5.10	Fire Protection (RCA)	-	46	3	4	15	31	-	23	123	123	-	-	146	122	-	-	-	14,013	991	-	
4a.1.5.11	Instrument Air (RCA)	-	206	8	10	60	84	-	84	454	454	-	-	568	322	-	-	-	44,895	4,497	-	
4a.1.5.12	HVAC - Auxiliary Building	-	535	15	25	181	195	-	213	1,155	1,155	-	-	1,725	765	-	-	-	120,641	11,076	-	
4a.1.5.13	HVAC - Control Building	-	59	3	9	186	17	-	49	323	323	-	-	1,780	67	-	-	-	76,715	1,131	-	
4a.1.5.14	HVAC - Miscellaneous	-	35	-	-	-	-	-	5	40	40	-	40	-	-	-	-	-	-	719	-	
4a.1.5.15	HVAC - Service Building	-	78	2	5	106	11	-	39	240	240	-	-	1,029	41	-	-	-	44,612	1,435	-	
4a.1.5.16	Hydrogen Purge - Rad Monitoring	-	16	0	0	-	-	-	3	25	25	-	-	8	-	-	-	-	68	413	-	
4a.1.5.17	Industrial Waste Treatment System	-	221	0	0	-	-	-	33	254	254	-	234	-	-	-	-	-	-	969	-	
4a.1.5.18	Instrument Air (RCA)	-	116	8	8	28	75	-	54	290	290	-	-	271	294	-	-	-	30,495	4,869	-	
4a.1.5.19	Intermediate Closed Cooling Water (RCA)	-	95	14	21	40	190	-	85	463	463	-	-	568	743	-	-	-	72,199	1,958	-	
4a.1.5.20	Main Condensate (RCA)	-	202	8	20	430	38	-	128	895	895	-	-	4,101	154	-	-	-	170,354	4,077	-	
4a.1.5.21	Main Condensate (Vord)	-	62	6	8	67	59	-	42	244	244	-	-	643	232	-	-	-	41,616	1,773	-	
4a.1.5.22	Nuclear Services Closed Cycle Cooling	-	68	147	218	1,348	1,718	-	12	90	90	-	90	12,877	6,601	-	-	-	868,928	17,553	-	
4a.1.5.23	Nuclear Services River Water (Clean)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1,764	-	
4a.1.5.24	Nuclear Services River Water (RCA)	-	1,287	80	116	460	1,010	-	669	3,621	3,621	-	-	4,352	3,955	-	-	-	440,046	28,734	-	
4a.1.5.25	Reactor Building Normal Cooling (Clean)	-	14	-	-	-	-	-	2	16	16	-	16	-	-	-	-	-	-	300	-	
4a.1.5.26	Reactor Building Normal Cooling (RCA)	-	254	35	54	182	460	-	228	1,254	1,254	-	-	1,739	1,920	-	-	-	197,000	6,738	-	
4a.1.5.27	SG Secondary Side Vents & Drain	-	71	6	6	-	95	-	33	170	170	-	-	-	-	-	-	-	-	1,522	-	
4a.1.5.28	Sampling Nuclear System	-	231	0	0	-	175	-	106	554	554	-	-	-	-	-	-	-	-	4,862	-	
4a.1.5.29	Station Services Air (RCA)	-	4	0	0	-	-	-	2	11	11	-	-	35	35	-	-	-	-	82	-	
4a.1.5.30	Station Services Air (Vord)	-	260	10	10	16	95	-	93	483	483	-	-	189	372	-	-	-	30,363	6,863	-	
4a.1.5.31	Station Services Air (RCA)	-	145	5	6	17	65	-	54	282	282	-	-	61	181	-	-	-	20,766	3,215	-	
4a.1.5.32	Turbine Plant Sample (RCA)	-	17	1	1	6	8	-	8	41	41	-	-	40	32	-	-	-	4,990	339	-	
4a.1.5	Totals	-	5,602	469	687	4,935	6,480	-	3,550	20,223	10,961	-	641	40,423	21,341	-	-	-	3,061,290	124,129	-	
4a.1.6	Scarfolding in support of decommissioning	-	1,302	16	5	53	18	-	321	1,655	1,655	-	-	804	71	-	-	-	40,884	26,290	-	
4a.1	Subtotal Period 4a Activity Costs	154	41,843	16,400	5,754	5,024	59,460	1,341	42,354	172,581	172,290	-	641	62,384	74,301	-	-	-	2,856	9,596,073	471,407	5,741

Table C  
Three Mile Island Unit 2  
DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Fee Costs	Special Fuel Amount Costs	Site Remediation Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTOC Cu. Feet	Weight Lbs.	Grout Manhours	Utility and Contractor Manhours	
Period 4a Additional Costs																						
4a.2.1	Reactor Building Basement Dose Reduction	-	17	126	3,478	-	46,624	-	11,945	61,189	61,189	-	-	-	-	11,893	1,552	-	1,217,965	-	282	
4a.2.2	Containment Basement Liner Removal	-	123	273	521	-	13,632	-	3,824	17,962	17,962	-	-	-	-	3,126	-	-	126,708	-	2,398	
4a.2.3	Reactor Building SNF & HNF Systems Removal	-	1,901	171	558	-	2,384	-	2,635	10,765	10,765	-	-	-	-	1,127	-	-	75,708	-	398	
4a.2.4	Reactor Building SNF & HNF Systems Removal	2,517	-	-	-	-	-	700	-	2,635	10,765	-	-	-	-	10,293	-	28	679,443	-	84,140	
4a.2.5	NSSS Component Surface Decontamination	7,614	-	1,127	41	-	-	9,071	-	5,287	23,140	-	-	-	-	-	-	329	19,751	-	46,920	
4a.2.6	Core Flood Tanks Removal	-	427	62	75	-	387	-	258	1,289	1,289	-	-	-	-	1,716	-	-	124,165	-	10,059	
4a.2.7	PHAB AX-004 Decontamination	-	151	201	953	-	12,196	377	3,306	17,185	17,185	-	-	-	-	3,390	-	-	228,998	-	4,638	
4a.2.8	Legacy waste stored at INEL	-	-	-	-	-	680	-	96	748	748	-	-	-	-	-	-	-	-	-	-	
4a.2	Subtotal Period 4a Additional Costs	10,200	2,618	2,027	5,923	-	78,219	10,797	28,020	137,865	137,865	-	-	-	-	12,009	19,657	1,552	2,475,308	-	148,683	
Period 4a Collateral Costs																						
4a.3.1	Process decommissioning water waste	40	-	16	99	-	103	-	62	318	318	-	-	-	-	294	-	-	15,838	-	69	
4a.3.2	Process decommissioning chemical flash waste	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
4a.3.3	Small tool allowance	-	431	-	-	-	-	-	-	446	446	-	-	-	-	-	-	-	-	-	-	
4a.3	Subtotal Period 4a Collateral Costs	40	431	16	99	-	103	-	126	814	814	-	-	-	-	294	-	-	15,838	-	69	
Period 4a Period-Dependent Costs																						
4a.4.1	Decom supplies	211	-	-	-	-	-	-	53	264	264	-	-	-	-	-	-	-	-	-	-	
4a.4.2	Insurance	-	-	-	-	-	-	968	-	1,068	1,068	-	-	-	-	-	-	-	-	-	-	
4a.4.3	Property taxes	-	-	-	-	-	-	-	1,917	9,737	9,737	-	-	-	-	-	-	-	-	-	-	
4a.4.4	Health Physics supplies	-	7,790	-	-	-	-	-	1,189	9,190	9,190	-	-	-	-	-	-	-	-	-	-	
4a.4.5	Health Physics supplies	-	7,691	-	-	-	-	-	1,189	9,190	9,190	-	-	-	-	-	-	-	-	-	-	
4a.4.6	Disposal of DAW generated	-	-	169	150	-	457	-	153	919	919	-	-	-	-	9,032	-	-	181,033	-	413	
4a.4.7	Plant energy budget	-	-	-	-	-	-	4,734	-	5,444	5,444	-	-	-	-	-	-	-	-	-	-	
4a.4.8	NRC Fees	-	-	-	-	-	-	-	710	5,444	5,444	-	-	-	-	-	-	-	-	-	-	
4a.4.9	Site O&M	-	-	-	-	-	-	-	4,913	5,784	5,784	-	-	-	-	-	-	-	-	-	-	
4a.4.10	Liquid Effluents Processing Equipment/Services	-	-	-	-	-	-	-	289	1,706	1,706	-	-	-	-	-	-	-	-	-	-	
4a.4.11	Security Staff Cost	-	-	-	-	-	-	-	1,926	2,215	2,215	-	-	-	-	-	-	-	-	-	-	
4a.4.12	DOC Staff Cost	-	-	-	-	-	-	-	2,891	22,163	22,163	-	-	-	-	-	-	-	-	-	-	
4a.4.13	Utility Staff Cost	-	-	-	-	-	-	-	133,912	20,087	153,999	153,999	-	-	-	-	-	-	-	-	-	
4a.4	Subtotal Period 4a Period-Dependent Costs	211	15,781	169	150	-	457	178,884	30,044	228,686	228,686	-	-	-	-	9,032	-	-	181,033	-	413	
4a.0	TOTAL PERIOD 4a COST	10,605	60,673	18,002	11,926	5,624	138,239	192,023	100,544	538,236	538,236	-	-	691	52,384	95,975	23,918	1,252	3,214	12,308,850	620,572	2,360,043
PERIOD 4b - Site Decontamination																						
Period 4b Direct Decommissioning Activities																						
4b.1.1	Remove spent fuel racks	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Disposal of Plant Systems																						
4b.1.2.1	Decay Heat Removal (RH)	-	241	32	35	-	401	-	170	882	882	-	-	-	-	1,570	-	-	103,970	-	5,252	
4b.1.2.2	Electrical (Contaminated) (RE)	-	43	3	4	-	42	-	22	114	114	-	-	-	-	166	-	-	10,890	-	885	
4b.1.2.3	Electrical (Contaminated) (RCA)	-	38	8	12	-	53	-	11	74	74	-	-	-	-	82	-	-	5,416	-	431	
4b.1.2.4	Feedwater (RH)	-	21	2	1	-	21	-	3	15	15	-	-	-	-	28	-	-	1,721	-	86	
4b.1.2.5	Feedwater (RH)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
4b.1.2.6	Fuel Handling (RCA)	-	4	1	1	-	7	-	-	15	15	-	-	-	-	-	-	-	-	-	-	
4b.1.2.7	Fuel Handling (RCA)	-	308	22	32	-	330	-	166	858	858	-	-	-	-	1,292	-	-	85,392	-	6,308	
4b.1.2.8	Gaseous Waste Disposal System (RH)	-	4	0	0	-	3	-	2	10	10	-	-	-	-	12	-	-	829	-	84	
4b.1.2.9	HVAC - Fuel Handling Building	-	810	25	125	-	67	-	91	506	506	-	-	-	-	262	-	-	91,546	-	4,144	
4b.1.2.10	HVAC - Reactor Building	-	218	6	11	-	115	-	256	2,561	2,561	-	-	-	-	1,097	-	-	277,560	-	17,022	
4b.1.2.11	Intermittent Air (RH)	-	27	2	2	-	20	-	12	64	64	-	-	-	-	79	-	-	275,559	-	17,022	
4b.1.2.12	Intermediate Cooling Water (RE)	-	8	6	9	-	95	-	46	240	240	-	-	-	-	373	-	-	24,689	-	1,744	
4b.1.2.13	Nitrogen for Nuclear Radiolysis Sys (RH)	-	8	1	2	-	18	-	7	35	35	-	-	-	-	69	-	-	4,572	-	171	
4b.1.2.14	Nuclear Services River Water (RH)	-	68	15	20	-	205	-	78	407	407	-	-	-	-	804	-	-	53,208	-	1,943	
4b.1.2.15	OTSG Chemical Cleaning System	-	19	2	2	-	23	-	12	60	60	-	-	-	-	39	-	-	5,532	-	183	
4b.1.2.16	Sewage Treatment Plant (Clean)	-	8	-	-	-	-	-	1	10	10	-	-	-	-	10	-	-	-	-	-	
4b.1.2.17	Spent Fuel Cooling	-	436	26	33	-	528	-	206	1,077	1,077	-	-	-	-	452	-	-	103,430	-	9,612	
4b.1.2.18	Spent Fuel Cooling (RH)	-	24	3	3	-	28	-	14	71	71	-	-	-	-	110	-	-	7,258	-	526	
4b.1.2.19	Slump Systems (RH)	-	37	3	4	-	43	-	20	103	103	-	-	-	-	132	-	-	10,068	-	806	
4b.1.2	Subtotal Period 4b Period-Dependent Costs	-	2,699	220	304	-	733	2,869	1,669	6,394	6,394	-	-	-	-	11,234	-	-	1,027,234	-	57,253	
4b.1.2	Totals	-	1,802	23	8	-	140	27	482	2,483	2,483	-	-	-	-	106	-	-	61,281	-	43,935	
4b.1.3	Scaffolding in support of decommissioning	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	

Table C  
Three Mile Island Unit 2  
DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet	Boards / Wt. Lbs.	Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours
40.1.1	Decontamination of Site Buildings	10,224	4,077	1,624	1,474	-	15,372	-	10,333	43,004	43,004	43,004	-	-	59,447	-	-	-	-	3,955,465	292,341	-
40.1.2	40.1.2.1 Reactor	470	864	20	186	34	402	-	301	2,584	2,584	2,584	-	323	-	-	-	-	-	3,955,465	292,341	-
40.1.3	40.1.3.1 Auxiliary	-	14	0	0	-	1,063	-	62	3,064	3,064	3,064	-	-	20,931	-	-	-	-	2,485,020	2,672	-
40.1.4	40.1.4.1 Control Building Area	22	6	0	4	-	0	-	15	54	54	54	-	-	2	-	-	-	-	9,733	562	-
40.1.5	40.1.5.1 Fuel Handling	66	43	0	24	26	38	-	71	290	290	290	-	-	249	-	-	-	-	64,322	2,532	-
40.1.6	40.1.6.1 Turbine	670	951	47	137	84	579	-	756	3,225	3,225	3,225	-	-	893	-	-	-	-	364,809	30,747	-
40.1.7	40.1.7.1 Turbine	65	4	0	1	-	2	-	34	106	106	106	-	-	29	-	-	-	-	2,532	1,451	-
40.1.8	40.1.8.1 Turbine	11,544	6,121	1,753	2,877	144	17,963	-	12,421	52,623	52,623	52,623	-	1,377	99,023	-	-	-	-	7,366,210	326,735	-
40.1	Subtotal Period 4b Activity Costs	11,544	10,622	1,997	3,189	1,017	20,859	-	14,472	63,989	63,989	63,989	-	10	9,574	110,364	-	-	-	8,454,725	427,924	-
40.2	Period 4b Additional Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.2.1	40.2.1.1 Blockfield & D-Rug Removal	-	4,624	706	1,596	-	9,141	-	3,747	19,804	19,804	19,804	-	-	133,795	-	-	-	-	18,995,440	60,993	-
40.2.2	40.2.2.1 RB Exterior Concrete & Basement Removal	-	8,977	282	620	-	3,117	-	3,063	13,059	13,059	13,059	-	-	83,132	-	-	-	-	10,535,000	1,000	-
40.2.3	40.2.3.1 Fuel Handling & Transfer	-	122	122	122	-	5,348	-	1,484	7,832	7,832	7,832	-	-	46,132	-	-	-	-	3,723,414	8,942	-
40.2.4	40.2.4.1 Fuel Handling & Transfer	-	8,841	370	973	-	5,843	-	3,854	19,881	19,881	19,881	-	-	99,586	-	-	-	-	11,960,340	113,206	-
40.2.5	40.2.5.1 Fuel Handling Building Total Removal	-	6,151	83	675	-	4,027	-	2,854	13,589	13,589	13,589	-	-	68,034	-	-	-	-	8,236,080	73,213	-
40.2.6	40.2.6.1 On-site survey & release of concrete	-	2,512	-	989	-	11,688	-	3,965	20,935	20,935	20,935	-	-	199,217	-	-	-	-	17,531,000	25,319	-
40.2.7	40.2.7.1 Detailing fuel container racks	24	21	2	75	-	2,527	-	807	2,867	2,867	2,867	-	-	10,913	-	-	-	-	98,706	961	-
40.2.8	40.2.8.1 Fuel Handling Building	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.2.9	40.2.9.1 Fuel Handling Building	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.2	Subtotal Period 4b Additional Costs	24	31,549	1,679	6,646	-	44,565	-	21,298	110,370	110,370	110,370	-	-	636,268	-	-	-	-	66,737,780	402,574	-
40.3	Period 4b Collateral Costs	48	-	21	131	-	136	-	80	416	416	416	-	-	350	-	-	-	-	21,021	91	-
40.3.1	40.3.1.1 Process decommissioning water waste	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.3.2	40.3.2.1 Process decommissioning chemical tank waste	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.3.3	40.3.3.1 Decommissioning Equipment Disposition	-	551	-	45	697	135	-	157	1,149	1,149	1,149	-	-	6,000	529	-	-	-	304,568	123	-
40.3	Subtotal Period 4b Collateral Costs	48	551	137	175	697	271	-	319	2,196	2,196	2,196	-	-	6,000	879	-	-	-	325,569	215	-
40.4	Period 4b Period-Dependent Costs	1,023	-	-	-	-	-	-	255	1,279	1,279	1,279	-	-	-	-	-	-	-	-	-	-
40.4.1	40.4.1.1 Decon supplies	-	-	-	-	-	-	-	109	1,199	1,199	1,199	-	-	-	-	-	-	-	-	-	-
40.4.2	40.4.2.1 Decon supplies	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.4.3	40.4.3.1 Property taxes	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.4.4	40.4.4.1 Health physics supplies	-	9,348	-	-	-	-	-	2,337	11,685	11,685	11,685	-	-	-	-	-	-	-	-	-	-
40.4.5	40.4.5.1 Heavy equipment rental	-	8,635	-	-	-	-	-	1,295	9,930	9,930	9,930	-	-	-	-	-	-	-	-	-	-
40.4.6	40.4.6.1 Disposal of DAW generated	-	-	121	114	-	347	-	116	697	697	697	-	-	-	-	-	-	-	137,260	313	-
40.4.7	40.4.7.1 NRC Energy budget	-	-	-	-	-	-	-	4,568	4,568	4,568	4,568	-	-	-	-	-	-	-	-	-	-
40.4.8	40.4.8.1 NRC Energy budget	-	-	-	-	-	-	-	4,568	4,568	4,568	4,568	-	-	-	-	-	-	-	-	-	-
40.4.9	40.4.9.1 Site O&M	-	-	-	-	-	-	-	256	1,953	1,953	1,953	-	-	-	-	-	-	-	-	-	-
40.4.10	40.4.10.1 Liquid Radiactive Processing Equipment/Services	-	-	-	-	-	-	-	315	2,418	2,418	2,418	-	-	-	-	-	-	-	-	-	-
40.4.11	40.4.11.1 Security Staff Cost	-	-	-	-	-	-	-	3,155	24,190	24,190	24,190	-	-	-	-	-	-	-	-	-	-
40.4.12	40.4.12.1 DOC Staff Cost	-	-	-	-	-	-	-	17,296	132,146	132,146	132,146	-	-	-	-	-	-	-	-	-	-
40.4.13	40.4.13.1 Utility Staff Cost	-	-	-	-	-	-	-	114,969	1,365,000	1,365,000	1,365,000	-	-	-	-	-	-	-	-	-	-
40.4	Subtotal Period 4b Period-Dependent Costs	1,023	17,983	121	114	-	347	-	28,167	210,667	210,667	210,667	-	-	-	-	-	-	-	-	-	-
40.5	TOTAL PERIOD 4b COST	12,639	60,705	3,833	10,124	1,713	69,042	167,612	64,166	386,954	386,954	386,954	-	10	15,574	754,376	-	-	-	76,655,730	831,026	2,109,183
40.6	Period 4c License Termination	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.6.1	40.6.1.1 Period of Direct Decommissioning Activities	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.6.2	40.6.2.1 ORISE confirmatory survey	-	-	-	-	-	-	-	48	209	209	209	-	-	-	-	-	-	-	-	-	-
40.6.3	40.6.3.1 Terminate license	-	-	-	-	-	-	-	48	209	209	209	-	-	-	-	-	-	-	-	-	-
40.6	Subtotal Period 4c Activity Costs	-	-	-	-	-	-	-	96	418	418	418	-	-	-	-	-	-	-	-	-	-
40.7	Period 4f Additional Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.7.1	40.7.1.1 License Termination Survey	-	-	-	-	-	-	-	6,191	8,048	8,048	8,048	-	-	-	-	-	-	-	-	-	-
40.7	Subtotal Period 4f Additional Costs	-	-	-	-	-	-	-	6,191	8,048	8,048	8,048	-	-	-	-	-	-	-	-	-	-
40.8	Period 4g Collateral Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40.8.1	40.8.1.1 DOC staff relocation expenses	-	-	-	-	-	-	-	208	1,593	1,593	1,593	-	-	-	-	-	-	-	-	-	-
40.8	Subtotal Period 4g Collateral Costs	-	-	-	-	-	-	-	208	1,593	1,593	1,593	-	-	-	-	-	-	-	-	-	-
40.9	TOTAL PERIOD 4c-4g COST	-	-	-	-	-	-	-	208	1,593	1,593	1,593	-	-	-	-	-	-	-	-	-	-



Table C  
Three Mile Island Unit 2  
DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLSW Disposal Cost	Other Cost	Total Contingency	Total Cost	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Burial Volume Class B Cu. Feet	Burial Volume Class C Cu. Feet	GTCC Cu. Feet	Burial/Processed Wh. Lbs.	Craft Manhours	Utility and Contractor Manhours
4f.4.1	Period 4f Period-Dependent Costs																				
4f.4.2	Insurance																				
4f.4.3	Health physics supplies		875							170											
4f.4.4	Disposal of DAW generated			6	5		16			1,094	1,094										
4f.4.5	Plant energy budget							185		32											
4f.4.6	NRC Fees							482		225											
4f.4.7	Site O&M							42		497											
4f.4.8	Site O&M Staff Cost							1,042		1,042											
4f.4.9	DOC Staff Cost							4,629		5,209											
4f.4.10	Utility Staff Cost							1,540		1,771											
4f.4	Subtotal Period 4f Period-Dependent Costs		875	6	5		16	8,174		10,496											
4f.0	TOTAL PERIOD 4f COST		875	6	5		16	15,911		20,345											
	PERIOD 4 TOTALS	23,244	122,253	22,540	22,084	7,337	204,297	375,545	108,244	945,615	944,815		700	67,548	850,367	26,518	2,734	3,214	87,870,900	1,560,810	4,471,887
	PERIOD 5b - Site Restoration																				
	Period 5b Direct Decommissioning Activities																				
5b.1.1.1	Demolition of Remaining Site Buildings																				
5b.1.1.2	5b.1.1.1 Air Intake Tunnel		161						24	185											
5b.1.1.3	5b.1.1.2 Circulating Water Chlorinator		73						11	84											
5b.1.1.4	5b.1.1.3 Circulating Water Intake Flume		64						10	74											
5b.1.1.5	5b.1.1.4 Circulating Water Pumphouse		154						26	180											
5b.1.1.6	5b.1.1.5 Control & Service		3,165						475	3,640											
5b.1.1.7	5b.1.1.6 Control Building Area		891						134	1,024											
5b.1.1.8	5b.1.1.7 Emergency Diesel Generator		737						111	847											
5b.1.1.9	5b.1.1.8 Main & Aux Transformer Foundations		87						13	100											
5b.1.1.10	5b.1.1.9 Mechanical Drive Foundations		20						3	23											
5b.1.1.11	5b.1.1.10 Mechanical Drive Foundations		1,853						279	2,141											
5b.1.1.12	5b.1.1.11 River Water Pumphouse		1,599						240	1,838											
5b.1.1.13	5b.1.1.12 Turbine		737						111	847											
5b.1.1.14	5b.1.1.13 Turbine Generator Pedestal		9,721						1,458	11,179											
5b.1.1	Totals		146						22	168											
5b.1.2	Site Cleanup Activities																				
5b.1.3	Grads & landscape site								62	473											
5b.1	Final report to NRC		9,897						1,542	11,820											
5b.1	Subtotal Period 5b Activity Costs																				
	Period 5b Additional Costs																				
5b.2.1	5b.2.1 River Water Pump House Collection		214						32	246											
5b.2.2	5b.2.2 Concrete Processing		495						76	580											
5b.2.3	5b.2.3 Survey & Release of scrap materials			689	60	2,274		9	439	3,063											
5b.2.4	5b.2.4 Backfill Site		925						139	1,064											
5b.2.5	5b.2.5 Cooling Tower Demolition		4,383						657	5,040											
5b.2	Subtotal Period 5b Additional Costs		6,017	689	60	2,274		9	1,345	10,062											
	Period 5b Collateral Costs																				
5b.3.1	Small tool allowance		121						18	139											
5b.3	Subtotal Period 5b Collateral Costs		121						18	139											

Table C

End Notes:

n/a - indicates that this activity not charged as decommissioning expense.

a - indicates that this activity performed by decommissioning staff.

0 - indicates that this value is less than 0.5 but is non-zero.

a cell containing " - " indicates a zero value

**APPENDIX D  
DETAILED COST ANALYSIS  
DELAYED DECON**

Table D  
Three Mile Island Unit 2  
Delayed DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LEW Direct Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Fee	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Best Volume Class C Cu. Feet	GFCO Cu. Feet	Burial Wt. Lbs.	Craft Manhours	Utility and Construction Manhours
<b>PERIOD 0a - PDMS Monitoring &amp; SAFSTOR Storage</b>																					
Period 0a Direct Decommissioning Activities																					
0a.3.1	PDMS Monitoring	-	-	-	-	-	-	6,042	906	6,949	6,949	-	-	-	-	-	-	-	-	-	-
0a.3	Subtotal Period 0a Collateral Costs	-	-	-	-	-	-	6,042	906	6,949	6,949	-	-	-	-	-	-	-	-	-	-
Period 0a Period-Dependent Costs																					
0a.4.1	Insurance	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0a.4.2	Plant energy budget	-	-	-	-	-	-	4,146	622	4,770	4,770	-	-	-	-	-	-	-	-	-	-
0a.4.3	Plant energy budget	-	-	-	-	-	-	6,910	622	7,532	7,532	-	-	-	-	-	-	-	-	-	-
0a.4.4	Utility Staff Cost	-	-	-	-	-	-	46,069	7,533	53,602	53,602	-	-	-	-	-	-	-	-	-	222,229
0a.4	Subtotal Period 0a Period-Dependent Costs	-	-	-	-	-	-	50,217	7,533	57,750	57,750	-	-	-	-	-	-	-	-	-	222,229
0a.0	TOTAL PERIOD 0a COST	-	-	-	-	-	-	56,360	8,439	64,799	64,799	-	-	-	-	-	-	-	-	-	222,229
<b>PERIOD 2c - SAFSTOR Dormancy without Spent Fuel Storage</b>																					
Period 2c Direct Decommissioning Activities																					
2c.1.1	Quarterly Inspection	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.1.2	Pen-sampled environmental survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.1.3	Pen-sampled environmental survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.1.4	Humorous roof replacement	-	-	-	-	-	-	322	39	460	460	-	-	-	-	-	-	-	-	-	-
2c.1.5	Maintenance supplies	-	-	-	-	-	-	1,566	382	1,948	1,948	-	-	-	-	-	-	-	-	-	-
2c.1	Subtotal Period 2c Activity Costs	-	-	-	-	-	-	1,956	400	2,408	2,408	-	-	-	-	-	-	-	-	-	-
Period 2c Collateral Costs																					
2c.3	Subtotal Period 2c Collateral Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 2c Period-Dependent Costs																					
2c.4.1	Insurance	-	-	-	-	-	-	2,336	234	2,570	2,570	-	-	-	-	-	-	-	-	-	-
2c.4.2	Property taxes	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.4.3	Plant energy budget	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.4.4	Plant energy budget	-	-	-	-	-	-	53	18	107	107	-	-	-	-	-	-	-	-	-	-
2c.4.5	Disposal of DAW generated	-	-	-	-	-	-	2,386	324	2,710	2,710	-	-	-	-	-	-	-	-	-	-
2c.4.6	NRC Fee	-	-	-	-	-	-	3,239	324	3,563	3,563	-	-	-	-	-	-	-	-	-	-
2c.4.7	Security Staff Cost	-	-	-	-	-	-	2,785	418	3,203	3,203	-	-	-	-	-	-	-	-	-	-
2c.4.8	Utility Staff Cost	-	-	-	-	-	-	13,615	2,125	15,740	15,740	-	-	-	-	-	-	-	-	-	-
2c.4	Subtotal Period 2c Period-Dependent Costs	-	-	-	-	-	-	13,615	2,125	15,740	15,740	-	-	-	-	-	-	-	-	-	-
2c.0	TOTAL PERIOD 2c COST	-	-	-	-	-	-	15,472	2,575	18,047	18,047	-	-	-	-	-	-	-	-	-	-
<b>PERIOD 3a - Reactivate Site Following SAFSTOR Dormancy</b>																					
Period 3a Direct Decommissioning Activities																					
3a.1.1	Prepare preliminary decommissioning cost	-	-	-	-	-	-	207	39	246	246	-	-	-	-	-	-	-	-	-	-
3a.1.2	Review plant design & specs.	-	-	-	-	-	-	1,213	182	1,395	1,395	-	-	-	-	-	-	-	-	-	-
3a.1.3	Perform detailed radi survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3a.1.4	Perform detailed radi survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3a.1.5	Developed by-product inventory	-	-	-	-	-	-	686	103	789	789	-	-	-	-	-	-	-	-	-	-
3a.1.6	Define major work sequence	-	-	-	-	-	-	1,977	297	2,274	2,274	-	-	-	-	-	-	-	-	-	-
3a.1.7	Perform SER and EA	-	-	-	-	-	-	8,225	1,234	9,459	9,459	-	-	-	-	-	-	-	-	-	-
3a.1.8	Perform Site-Specific Cost Study	-	-	-	-	-	-	1,318	184	1,502	1,502	-	-	-	-	-	-	-	-	-	-
3a.1.9	Prepare/submit License Termination Plan	-	-	-	-	-	-	2,162	324	2,486	2,486	-	-	-	-	-	-	-	-	-	-
3a.1.10	Reserve NRC approval of termination plan	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Activity Specifications																					
3a.1.11.1	Re-activate plant & temporary facilities	-	-	-	-	-	-	1,457	219	1,676	1,676	-	-	-	-	-	-	-	-	-	-
3a.1.11.2	Plant systems	-	-	-	-	-	-	1,099	186	1,285	1,285	-	-	-	-	-	-	-	-	-	-
3a.1.11.3	Reactor internals	-	-	-	-	-	-	1,263	193	1,456	1,456	-	-	-	-	-	-	-	-	-	-
3a.1.11.4	Reactor internals	-	-	-	-	-	-	1,263	193	1,456	1,456	-	-	-	-	-	-	-	-	-	-
3a.1.11.5	Biological shield	-	-	-	-	-	-	66	10	76	76	-	-	-	-	-	-	-	-	-	-
3a.1.11.6	Steam generators	-	-	-	-	-	-	1,645	247	1,892	1,892	-	-	-	-	-	-	-	-	-	-
3a.1.11.7	Reinforced concrete	-	-	-	-	-	-	422	63	485	485	-	-	-	-	-	-	-	-	-	-

Table D  
Three Mile Island Unit 2  
Delayed DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Cost	Total Contingency	Total Costs	MRC Lab. Cost	Spent Fuel Management Cost	Site Restoration Cost	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet	Part / Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours
<b>Activity Specifications (continued)</b>																					
3a.1.12	Prepare dismantling sequence	-	-	-	-	-	-	-	-	61	-	-	-	-	-	-	-	-	-	-	400
3a.1.11.8	Main Turbine	-	-	-	-	-	-	53	8	61	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.9	Main Condensers	-	-	-	-	-	-	53	8	61	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.10	Plant structures & buildings	-	-	-	-	-	-	53	8	61	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.11	Plant equipment	-	-	-	-	-	-	53	8	61	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.12	Facility & site cleanup	-	-	-	-	-	-	53	8	61	-	-	-	-	-	-	-	-	-	-	-
3a.1.11	Total	-	-	-	-	-	-	119	18	136	-	-	-	-	-	-	-	-	-	-	82,738
<b>Planning &amp; Site Preparations</b>																					
3a.1.12	Prepare dismantling sequence	-	-	-	-	-	-	623	95	718	-	-	-	-	-	-	-	-	-	-	-
3a.1.13	Plant prep & equip. access	-	-	-	-	-	-	2,900	435	3,335	-	-	-	-	-	-	-	-	-	-	-
3a.1.14	Demolition debris	-	-	-	-	-	-	738	111	849	-	-	-	-	-	-	-	-	-	-	-
3a.1.15	Regime/Cont. Cont. Enveloping/etc.	-	-	-	-	-	-	2,290	330	2,620	-	-	-	-	-	-	-	-	-	-	-
3a.1.16	Procure caskholders & containers	-	-	-	-	-	-	49	373	373	-	-	-	-	-	-	-	-	-	-	-
3a.1	Subtotal Period 3a Activity Costs	-	-	-	-	-	-	33,898	6,071	39,969	-	-	-	-	-	-	-	-	-	-	-
<b>Period 3a Additional Costs</b>																					
3a.2.1	Refined Tank Refurbishment	-	-	-	-	-	-	330	50	380	-	-	-	-	-	-	-	-	-	-	-
3a.2.2	Equipment Airlock Refurbishment	-	-	-	-	-	-	1,290	194	1,484	-	-	-	-	-	-	-	-	-	-	-
3a.2.3	RE Polar Crane Refurbishment	-	-	-	-	-	-	6,450	968	7,418	-	-	-	-	-	-	-	-	-	-	-
3a.2.4	RE Cask Handling System	-	-	-	-	-	-	1,290	194	1,484	-	-	-	-	-	-	-	-	-	-	-
3a.2	Subtotal Period 3a Additional Costs	-	-	-	-	-	-	9,360	1,454	10,814	-	-	-	-	-	-	-	-	-	-	-
<b>Period 3a Collateral Costs</b>																					
3a.3	Subtotal Period 3a Collateral Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Period 3a Period-Dependent Costs</b>																					
3a.4.1	Insurance	-	-	-	-	-	-	208	21	229	-	-	-	-	-	-	-	-	-	-	-
3a.4.2	Heavy equipment rental	-	-	-	-	-	-	623	136	759	-	-	-	-	-	-	-	-	-	-	-
3a.4.3	Health physics supplies	-	-	-	-	-	-	430	64	494	-	-	-	-	-	-	-	-	-	-	-
3a.4.4	Heavy equipment rental	-	-	-	-	-	-	25	16	41	-	-	-	-	-	-	-	-	-	-	-
3a.4.5	Disposal of DAW generated	-	-	-	-	-	-	1,778	146	1,924	-	-	-	-	-	-	-	-	-	-	-
3a.4.6	Plant energy budget	-	-	-	-	-	-	322	48	371	-	-	-	-	-	-	-	-	-	-	-
3a.4.7	Site prep & equip. access	-	-	-	-	-	-	3,680	553	4,233	-	-	-	-	-	-	-	-	-	-	-
3a.4.8	Security Staff Cost	-	-	-	-	-	-	11,762	1,764	13,526	-	-	-	-	-	-	-	-	-	-	-
3a.4.9	DOC Staff Cost	-	-	-	-	-	-	2,623	393	3,017	-	-	-	-	-	-	-	-	-	-	-
3a.4.10	Utility Staff Cost	-	-	-	-	-	-	25	20,853	20,878	-	-	-	-	-	-	-	-	-	-	-
3a.4.11	Subtotal Period 3a Period-Dependent Costs	-	-	-	-	-	-	25	20,853	20,878	-	-	-	-	-	-	-	-	-	-	-
3a.4	Subtotal Period 3a Period-Dependent Costs	-	-	-	-	-	-	25	20,853	20,878	-	-	-	-	-	-	-	-	-	-	-
3a.0	TOTAL PERIOD 3a COST	-	-	-	-	-	-	64,018	9,757	73,775	-	-	-	-	-	-	-	-	-	-	-
<b>PERIOD 3b - Decommissioning Preparations</b>																					
<b>Period 3b Direct Decommissioning Activities</b>																					
<b>Detailed Work Procedures</b>																					
3b.1.11	Plant systems	-	-	-	-	-	-	1,248	187	1,435	-	-	-	-	-	-	-	-	-	-	-
3b.1.12	Reactor internals	-	-	-	-	-	-	659	99	758	-	-	-	-	-	-	-	-	-	-	-
3b.1.13	Remaining buildings	-	-	-	-	-	-	178	27	205	-	-	-	-	-	-	-	-	-	-	-
3b.1.14	CRD cooling assembly	-	-	-	-	-	-	186	30	216	-	-	-	-	-	-	-	-	-	-	-
3b.1.15	CRD housing & JCT tubes	-	-	-	-	-	-	186	30	216	-	-	-	-	-	-	-	-	-	-	-
3b.1.16	CRD housing & JCT tubes	-	-	-	-	-	-	186	30	216	-	-	-	-	-	-	-	-	-	-	-
3b.1.17	Reactor vessel	-	-	-	-	-	-	718	106	824	-	-	-	-	-	-	-	-	-	-	-
3b.1.18	Facility cleanup	-	-	-	-	-	-	188	24	212	-	-	-	-	-	-	-	-	-	-	-
3b.1.19	Missile shields	-	-	-	-	-	-	99	15	114	-	-	-	-	-	-	-	-	-	-	-
3b.1.20	Biological shield	-	-	-	-	-	-	99	15	114	-	-	-	-	-	-	-	-	-	-	-
3b.1.21	Reactor generators	-	-	-	-	-	-	2,985	354	3,339	-	-	-	-	-	-	-	-	-	-	-
3b.1.22	Reactor generators	-	-	-	-	-	-	2,985	354	3,339	-	-	-	-	-	-	-	-	-	-	-
3b.1.23	Main Turbine	-	-	-	-	-	-	132	20	152	-	-	-	-	-	-	-	-	-	-	-
3b.1.24	Main Condensers	-	-	-	-	-	-	206	31	237	-	-	-	-	-	-	-	-	-	-	-
3b.1.25	Auxiliary building	-	-	-	-	-	-	206	31	237	-	-	-	-	-	-	-	-	-	-	-
3b.1.26	Reactor building	-	-	-	-	-	-	720	108	828	-	-	-	-	-	-	-	-	-	-	-
3b.1	Subtotal Period 3b Activity Costs	-	-	-	-	-	-	7,785	1,168	8,953	-	-	-	-	-	-	-	-	-	-	-
3b.0	TOTAL PERIOD 3b COST	-	-	-	-	-	-	7,785	1,168	8,953	-	-	-	-	-	-	-	-	-	-	-

Table D  
Three Mile Island Unit 2  
Delayed DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Costs	Total Contingency	Total	NRC Lic. Term. Costs	Start Prod. Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTOC Cu. Feet	Build / Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours
Period 3b Additional Costs																					
3b.2.1	Lead Shielding Disposal	-	740	225	611	-	5,474	-	1,668	8,717	8,717	-	-	-	2,511	-	-	-	1,418,084	14,333	-
3b.2.2	Stored Shielding Equipment Disposition	-	588	63	104	-	884	-	380	2,029	2,029	-	-	-	3,598	-	-	-	1,457,077	25,410	-
3b.2	Subtotal Period 3b Additional Costs	-	1,328	288	715	-	6,358	-	2,047	10,746	10,746	-	-	-	6,079	-	-	-	1,867,569	-	-
Period 3b Collateral Costs																					
3b.3.1	Decon equipment	712	-	-	-	-	-	-	107	819	819	-	-	-	-	-	-	-	-	-	-
3b.3.2	DOE staff relocation expenses	-	-	-	-	-	-	1,385	208	1,593	1,593	-	-	-	-	-	-	-	-	-	-
3b.3.3	Small tool allowance	-	18	-	-	-	-	-	1	19	19	-	-	-	-	-	-	-	-	-	-
3b.3.4	Site cleanup equipment	-	1,118	-	-	-	-	-	165	1,283	1,283	-	-	-	-	-	-	-	-	-	-
3b.3	Subtotal Period 3b Collateral Costs	712	1,118	-	-	-	-	1,385	482	3,698	3,698	-	-	-	-	-	-	-	-	-	-
Period 3b Period-Dependent Costs																					
3b.4.1	Decon supplies	22	-	-	-	-	-	-	6	28	28	-	-	-	-	-	-	-	-	-	-
3b.4.2	Insurance	-	-	-	-	-	-	104	16	116	116	-	-	-	-	-	-	-	-	-	-
3b.4.3	Heavy equipment	-	-	-	-	-	-	-	134	672	672	-	-	-	-	-	-	-	-	-	-
3b.4.4	Health physics supplies	-	537	-	-	-	-	-	33	261	261	-	-	-	-	-	-	-	5,763	13	-
3b.4.5	Heavy equipment rental	-	218	-	-	-	-	-	6	29	29	-	-	-	-	-	-	-	-	-	-
3b.4.6	Disposal of DAW generated	-	-	5	5	-	15	-	485	74	669	-	-	-	-	-	-	-	-	-	-
3b.4.7	Plant energy budget	-	-	-	-	-	-	-	74	669	669	-	-	-	-	-	-	-	-	-	-
3b.4.8	SRC Fee	-	-	-	-	-	-	-	24	184	184	-	-	-	-	-	-	-	-	-	-
3b.4.9	Security	-	-	-	-	-	-	-	165	24	184	-	-	-	-	-	-	-	-	-	-
3b.4.10	Liquid Waste Processing Equipment/Services	-	-	-	-	-	-	-	201	30	231	-	-	-	-	-	-	-	-	-	-
3b.4.11	Security Staff Cost	-	-	-	-	-	-	-	1,870	280	2,150	-	-	-	-	-	-	-	-	-	-
3b.4.12	DOE Staff Cost	-	-	-	-	-	-	-	12,643	1,897	14,540	-	-	-	-	-	-	-	-	-	-
3b.4.13	Utility Staff Cost	-	-	-	-	-	-	-	1,323	188	1,511	-	-	-	-	-	-	-	-	-	-
3b.4	Subtotal Period 3b Period-Dependent Costs	22	755	5	5	-	15	17,445	2,757	21,064	21,064	-	-	-	-	-	-	-	5,763	13	-
3b.0	TOTAL PERIOD 3b COST	734	3,202	293	720	-	6,372	25,615	6,464	44,400	43,298	-	-	-	-	-	-	-	1,673,372	25,423	764,948
PERIOD 3 TOTALS		734	4,255	301	728	-	6,397	90,834	16,222	119,271	117,206	-	-	-	-	-	-	-	1,683,165	26,446	764,948
Period 4a - Large Component Removal																					
Period 4a Direct Decommissioning Activities																					
Nuclear Steam Supply System Removal																					
4a.1.1.1	Reactor Coolant Piping	22	68	15	27	-	387	-	135	674	674	-	-	-	-	-	-	-	180,957	2,935	-
4a.1.1.2	Pressure Relief Valve	3	12	3	130	-	3,158	-	1,213	6,546	6,546	-	-	-	-	-	-	-	30,819	2,935	-
4a.1.1.3	Pressure Relief Valve	-	1,267	883	177	-	1,775	-	639	3,673	3,673	-	-	-	-	-	-	-	1,124,474	31,482	-
4a.1.1.4	Pressure Relief Valve	-	1,333	757	177	-	3,158	-	10,231	53,188	53,188	-	-	-	-	-	-	-	2,386,356	148,491	-
4a.1.1.5	Steam Generators	34	6,980	1,196	3,129	-	1,855	-	93	584	584	-	-	-	-	-	-	-	47,969	1,312	-
4a.1.1.6	CRDMs/Cl Service Structure Removal	12	65	175	64	-	934	-	12,979	38,360	38,360	-	-	-	-	-	-	-	543,585	48,160	-
4a.1.1.7	Reactor Vessel Internals	82	12,878	9,989	967	-	13,824	-	10,468	28,119	28,119	-	-	-	-	-	-	-	976,373	48,160	-
4a.1.1.8	Reactor Vessel Internals GTOC Disposal	-	-	2,802	532	-	2,824	-	37,850	147,165	147,165	-	-	-	-	-	-	-	5,942,504	283,337	-
4a.1.1.9	Reactor Vessel	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4a.1.1	Totals	154	33,125	15,719	5,014	-	53,962	1,341	37,850	147,165	147,165	-	-	-	-	-	-	-	5,942,504	283,337	-
Removal of Major Equipment																					
4a.1.2	Main Turbine/Generator	-	278	93	23	-	616	-	175	1,184	1,184	-	-	-	-	-	-	-	283,304	5,389	-
4a.1.3	Main Condensers	-	1,271	103	25	-	680	-	434	2,014	2,014	-	-	-	-	-	-	-	268,680	25,102	-
4a.1.4	Control & Service	-	166	-	-	-	-	-	25	191	191	-	-	-	-	-	-	-	-	2,080	-
4a.1.4	Totals	-	166	-	-	-	-	-	25	191	191	-	-	-	-	-	-	-	-	2,080	-
Disposal of Plant Systems																					
4a.1.5.1	Decay Heat Removal System	-	280	34	60	-	697	-	274	1,683	1,683	-	-	-	-	-	-	-	380,569	5,823	-
4a.1.5.2	Decay Heat Removal (RCM)	-	200	55	74	-	263	-	272	1,527	1,527	-	-	-	-	-	-	-	270,883	4,350	-
4a.1.5.3	Decay Heat Removal (RCM)	-	140	8	11	-	67	-	21	161	161	-	-	-	-	-	-	-	46,152	2,863	-
4a.1.5.4	Domestic Water (RCM)	-	6	-	-	-	-	-	70	381	381	-	-	-	-	-	-	-	-	-	-
4a.1.5.5	Domestic Water (RCM)	-	2	-	-	-	-	-	10	61	61	-	-	-	-	-	-	-	-	-	-
4a.1.5.6	Domestic Water (RCM)	-	2	-	-	-	-	-	1	11	11	-	-	-	-	-	-	-	-	-	-
4a.1.5.7	Domestic Water (RCM)	-	2	-	-	-	-	-	1	11	11	-	-	-	-	-	-	-	-	-	-
4a.1.5.8	Emergency Feedwater (RCM)	-	65	5	6	-	43	-	37	206	206	-	-	-	-	-	-	-	26,642	1,332	-
4a.1.5.9	Fire Protection (RCM)	-	54	-	-	-	-	-	62	62	62	-	-	-	-	-	-	-	-	-	-
4a.1.5.10	Fire Protection (RCM)	-	48	3	4	-	15	-	23	123	123	-	-	-	-	-	-	-	14,013	991	-
4a.1.5.11	Gaseous Waste Disposal System (RCM)	-	208	8	10	-	60	-	84	454	454	-	-	-	-	-	-	-	4,866	4,971	-

Table D  
Three Mile Island Unit 2  
Delayed DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLSW Disposal Cost	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Start Fed. Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GFQC Cu. Feet	Basal / Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours
4a.15.12	Disposal of Plant Systems (continued)																				
4a.15.13	HVAC - Auxiliary Building	620	16	26	181	195	181	195	213	1,155	1,155	1,155	1,155	1,723	765	-	-	-	120,641	11,070	-
4a.15.14	HVAC - Control Building	30	3	9	166	17	166	17	4	323	323	323	323	1,780	67	-	-	-	76,716	1,135	-
4a.15.15	HVAC - Service Building	70	2	5	108	11	108	11	39	240	240	240	240	1,029	41	-	-	-	44,512	1,435	-
4a.15.16	Hydrogen Purge - Rad Monitoring	18	0	0	0	2	0	2	3	26	26	26	26	4	8	-	-	-	689	413	-
4a.15.17	Industrial Waste Treatment System	221	0	0	0	0	0	0	33	254	254	254	254	271	294	-	-	-	30,465	4,899	-
4a.15.18	Instrument Air (ICA)	116	8	8	28	75	28	75	54	290	290	290	290	4,301	154	-	-	-	175,354	2,374	-
4a.15.19	Intermediate Closed Cooling Water (RCA)	292	14	21	60	183	60	183	128	826	826	826	826	643	232	-	-	-	41,516	4,077	-
4a.15.20	Low Pressure Steam (LPS)	82	4	5	25	43	25	43	42	214	214	214	214	12,877	6,801	-	-	-	988,028	17,553	-
4a.15.21	Main Bypass & Steam (RCA)	848	147	216	1,349	1,718	1,349	1,718	891	5,169	5,169	5,169	5,169	4,392	3,955	-	-	-	440,046	1,764	-
4a.15.22	Nuclear Services Closed Cycle Cooling	78	0	0	0	0	0	0	12	90	90	90	90	80	-	-	-	-	28,724	-	-
4a.15.23	Nuclear Services River Water (RCA)	1,297	80	115	460	1,010	460	1,010	699	3,621	3,621	3,621	3,621	1,720	1,920	-	-	-	197,600	5,738	-
4a.15.24	Nuclear Services River Water (RCA)	264	4	6	38	182	38	182	228	1,254	1,254	1,254	1,254	1,720	1,920	-	-	-	14,436	1,322	-
4a.15.25	Reactor Building Normal Cooling (Clean)	71	5	5	5	5	5	5	33	170	170	170	170	170	170	-	-	-	46,402	4,992	-
4a.15.26	Reactor Building Normal Cooling (RCA)	231	15	17	17	175	17	175	106	644	644	644	644	35	4	-	-	-	1,682	82	-
4a.15.27	Secondary Side Tanks & Drums	4	0	0	0	1	0	1	2	11	11	11	11	139	372	-	-	-	30,363	3,863	-
4a.15.28	Sampling Nuclear System	260	10	10	10	15	10	15	93	483	483	483	483	61	32	-	-	-	4,580	339	-
4a.15.29	Seawater Treatment Plant (RCA)	17	1	1	1	1	1	1	8	41	41	41	41	61	32	-	-	-	4,580	339	-
4a.15.30	Station Service Air	6,892	469	687	4,235	5,460	4,235	5,460	3,560	20,223	19,981	19,981	19,981	40,423	21,541	-	-	-	3,081,230	124,129	-
4a.15.31	Steam System (RCA)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4a.15.32	Steam Plant Sample (RCA)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4a.15.35	Totals	114	41,843	16,400	5,754	5,624	5,624	59,460	1,341	42,354	172,931	172,931	172,931	53,384	74,351	7,382	-	2,856	9,536,673	471,407	5,741
4a.1.6	Scaffolding in support of decommissioning	-	1,202	16	5	93	18	-	321	1,655	-	-	-	804	71	-	-	-	40,854	29,290	-
4a.1	Subtotal Period 4a Activity Costs	114	41,843	16,400	5,754	5,624	5,624	59,460	1,341	42,354	172,931	172,931	172,931	53,384	74,351	7,382	-	2,856	9,536,673	471,407	5,741
Period 4a Additional Costs																					
4a.2.1	Reactor Building Basement Dose Reduction	17	126	3,478	-	-	-	45,624	-	11,845	61,189	61,189	61,189	-	-	-	-	-	1,217,965	282	-
4a.2.2	Containment Basement Liner Removal	-	123	273	521	-	-	13,532	3,324	17,992	17,992	17,992	17,992	-	-	-	-	-	126,709	2,266	-
4a.2.3	Reactor Building SNF & HOT Systems Removal	2,117	677	297	587	-	-	4,065	1,068	5,497	5,497	5,497	5,497	-	-	-	-	-	75,706	84	-
4a.2.4	Reactor Building / Auxiliary SNF & HOT Systems Removal	7,114	1,127	587	41	-	-	2,384	700	9,071	9,071	9,071	9,071	-	-	-	-	-	19,751	46,920	-
4a.2.5	NSSS / Auxiliary SNF & HOT Systems Removal	70	427	62	75	-	-	397	298	1,289	1,289	1,289	1,289	-	-	-	-	-	124,165	10,069	-
4a.2.7	Core Flood Tanks Removal	161	201	953	-	-	-	12,196	377	3,968	17,185	17,185	17,185	-	-	-	-	-	228,566	4,638	-
4a.2.8	Legacy waste stored at INEEL	-	-	650	-	-	-	78,219	10,797	28,020	137,805	137,805	137,805	-	-	-	-	-	2,475,368	148,683	-
4a.2	Subtotal Period 4a Additional Costs	10,260	2,618	2,027	5,923	-	-	78,219	10,797	28,020	137,805	137,805	137,805	-	-	-	-	-	2,475,368	148,683	-
Period 4a Collateral Costs																					
4a.3.1	Process decommissioning water waste	13	-	7	41	-	-	43	-	129	129	129	129	-	-	-	-	-	6,958	29	-
4a.3.2	Process decommissioning chemical flash waste	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4a.3.3	Small tool allowance	-	431	-	-	-	-	-	65	495	446	446	446	-	-	-	-	-	-	-	-
4a.3	Subtotal Period 4a Collateral Costs	13	431	7	41	-	-	43	89	625	575	575	575	-	-	-	-	-	6,958	29	-
Period 4a Period-Dependent Costs																					
4a.4.1	Decon supplies	211	-	-	-	-	-	-	53	264	264	264	264	-	-	-	-	-	-	-	-
4a.4.2	Insurance	-	-	-	-	-	-	-	100	1,098	1,098	1,098	1,098	-	-	-	-	-	-	-	-
4a.4.3	Property taxes	-	-	-	-	-	-	-	1,977	9,717	9,717	9,717	9,717	-	-	-	-	-	-	-	-
4a.4.4	Health physics supplies	7,789	-	-	-	-	-	-	1,167	9,190	9,190	9,190	9,190	-	-	-	-	-	-	-	-
4a.4.5	Heavy equipment rental	7,391	-	-	-	-	-	-	1,167	9,190	9,190	9,190	9,190	-	-	-	-	-	-	-	-
4a.4.6	Heavy equipment rental	-	-	-	-	-	-	-	1,167	9,190	9,190	9,190	9,190	-	-	-	-	-	-	-	-
4a.4.7	Plant energy budget	-	-	-	-	-	-	-	457	4,734	5,444	5,444	5,444	-	-	-	-	-	181,033	413	-
4a.4.8	NEC Fees	-	-	-	-	-	-	-	4,734	5,444	5,444	5,444	5,444	-	-	-	-	-	-	-	-
4a.4.9	Site O&M	-	-	-	-	-	-	-	4,813	5,294	5,294	5,294	5,294	-	-	-	-	-	-	-	-
4a.4.10	Liquid Radiactive Processing Equipment/Services	-	-	-	-	-	-	-	235	1,798	1,798	1,798	1,798	-	-	-	-	-	-	-	-
4a.4.11	Equipment/Services	-	-	-	-	-	-	-	235	1,798	1,798	1,798	1,798	-	-	-	-	-	-	-	-
4a.4.12	DOCS Staff Cost	-	-	-	-	-	-	-	2,809	32,165	32,165	32,165	32,165	-	-	-	-	-	-	-	-
4a.4.13	DOCS Staff Cost	-	-	-	-	-	-	-	2,809	32,165	32,165	32,165	32,165	-	-	-	-	-	-	-	-
4a.4.14	Utility Staff Cost	-	-	-	-	-	-	-	20,087	153,999	153,999	153,999	153,999	-	-	-	-	-	-	-	-
4a.4	Subtotal Period 4a Period-Dependent Costs	211	15,761	159	150	-	-	457	12,684	1,900	14,564	14,564	14,564	-	-	-	-	-	181,033	413	-
4a.0	TOTAL PERIOD 4a COST	10,579	60,973	18,593	11,869	5,624	138,179	192,023	100,567	538,046	537,365	537,365	537,365	691	52,384	26,518	1,252	3,214	12,199,680	620,532	2,965,043
PERIOD 4b - Site Decommissioning																					
Period 4b Direct Decommissioning Activities																					
4b.1.1	Remove spent fuel racks	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Table D  
Three Mile Island Unit 2  
Delayed DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Packaging Costs	LSRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Material Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GYOC Cu. Feet	Residual / Processed Wt. Lbs.	Crust Manhours	Utility and Contractor Manhours	
Decommissioning of Plant Systems																						
4b.12.1	Decay Heat Removal (RH)	-	241	32	30	-	-	401	-	170	882	882	-	-	1,570	-	-	-	-	103,970	5,302	-
4b.12.2	Electrical Contaminated - RH	-	43	3	4	-	-	43	-	22	111	111	-	-	-	-	-	-	-	15	56	-
4b.12.3	Electrical Contaminated - RCA	-	28	8	25	-	570	-	-	12	1,114	1,114	-	-	-	-	-	-	-	234,690	5,745	-
4b.12.4	Fire Protection (RH)	-	31	8	12	-	-	123	-	43	224	224	-	-	-	-	-	-	-	31,951	435	-
4b.12.5	Fire Protection (RH)	-	2	2	2	-	-	21	-	11	66	66	-	-	-	-	-	-	-	6,416	451	-
4b.12.6	Fuel Handling (RH)	-	4	1	1	-	-	7	-	3	15	15	-	-	-	-	-	-	-	1,751	86	-
4b.12.7	Fuel Handling (RCA)	-	308	22	32	-	-	330	-	166	898	898	-	-	-	-	-	-	-	65,392	6,396	-
4b.12.8	Residual Waste Disposal System (RH)	-	4	0	0	-	-	4	-	2	10	10	-	-	-	-	-	-	-	1,414	44	-
4b.12.9	Residual Waste Disposal Building	-	214	0	10	-	115	-	-	91	506	506	-	-	-	-	-	-	-	61,848	4,591	-
4b.12.10	HVAC - Reactor Building	-	810	78	103	-	-	1,064	-	491	2,543	2,543	-	-	-	-	-	-	-	275,559	17,022	-
4b.12.11	Instrument Air (RH)	-	27	2	2	-	-	30	-	12	64	64	-	-	-	-	-	-	-	5,215	590	-
4b.12.12	Intermediate Chilled Cooling Water (RH)	-	81	8	9	-	-	93	-	46	240	240	-	-	-	-	-	-	-	24,089	1,744	-
4b.12.13	Nitrogen for Nuclear Refueling Sys (RH)	-	8	1	2	-	-	18	-	7	35	35	-	-	-	-	-	-	-	4,572	171	-
4b.12.14	Nuclear Service Water (RH)	-	68	15	20	-	-	203	-	12	47	47	-	-	-	-	-	-	-	1,433	143	-
4b.12.15	ONGC Chemical Treatment System	-	19	8	2	-	-	25	-	12	60	60	-	-	-	-	-	-	-	5,524	403	-
4b.12.16	Sewage Treatment Plant (Churn)	-	8	-	-	-	-	-	-	1	10	10	-	-	-	-	-	-	-	180	180	-
4b.12.17	Spent Fuel Cooling	-	436	26	33	-	47	328	-	206	1,077	1,077	-	-	-	-	-	-	-	103,430	9,612	-
4b.12.18	Spent Fuel Cooling (RH)	-	24	2	3	-	-	28	-	14	71	71	-	-	-	-	-	-	-	7,258	525	-
4b.12.19	Sump Systems (RH)	-	37	3	4	-	-	39	-	20	103	103	-	-	-	-	-	-	-	10,086	809	-
4b.1.2	Totals	-	2,659	220	304	733	2,668	-	1,569	8,394	8,394	-	-	10	6,591	11,234	-	-	-	1,087,234	67,263	-
Decommissioning of Site Buildings																						
4b.1.3	Scaffolding in support of decommissioning	-	1,802	23	8	-	-	27	-	482	2,483	2,483	-	-	-	-	-	-	-	61,281	43,935	-
Decommissioning of Auxiliary Costs																						
4b.1	Subtotal Period 4b Activity Costs	11,544	10,622	1,997	3,189	1,017	20,859	-	14,472	63,699	63,699	-	-	10	9,574	110,364	-	-	-	8,454,726	427,924	-
Period 4b Additional Costs																						
4b.2.1	BioShield & D-Ring Removal	-	4,824	766	1,536	-	-	9,141	-	3,747	19,804	19,804	-	-	-	-	-	-	-	18,895,440	90,895	-
4b.2.2	RS Exterior Concrete & Basement Removal	-	8,752	262	320	-	-	3,117	-	3,053	15,629	15,629	-	-	-	-	-	-	-	6,375,849	120,240	-
4b.2.3	Underground Piping & Yard Soil	-	722	123	1,639	-	-	2,674	-	1,195	6,804	6,804	-	-	-	-	-	-	-	3,725,414	8,942	-
4b.2.4	Process NSSS decon & segmentation liquid inventory	-	-	72	269	-	-	5,348	-	1,464	7,832	7,832	-	-	-	-	-	-	-	126,857	779	-
4b.2.5	Auxiliary Building Total Removal	-	8,841	370	973	-	-	5,843	-	3,834	19,881	19,881	-	-	-	-	-	-	-	11,950,340	113,205	-
4b.2.6	Fuel Handling Building Total Removal	-	6,151	83	675	-	-	4,927	-	2,654	13,589	13,589	-	-	-	-	-	-	-	8,235,080	73,213	-
4b.2.7	On-site survey & release of concrete	-	2,512	-	969	-	-	11,685	-	3,965	20,365	20,365	-	-	-	-	-	-	-	17,337,060	25,319	-
4b.2.8	Detailing fuel container racks	-	24	21	15	-	-	2,627	-	897	3,887	3,887	-	-	-	-	-	-	-	38,766	981	-
4b.2.9	LSW - Spent Fuel Handling	-	-	-	-	-	-	-	-	1,900	11,370	11,370	-	-	-	-	-	-	-	98,737,790	402,574	-
4b.2	Subtotal Period 4b Additional Costs	24	31,349	1,579	6,546	-	-	44,953	-	21,298	110,370	110,370	-	-	-	-	-	-	-	98,737,790	402,574	-
Period 4b Collateral Costs																						
4b.3.1	Process decommissioning water waste	19	-	11	68	-	-	71	-	39	208	208	-	-	-	-	-	-	-	10,939	46	-
4b.3.2	Process decommissioning chemical waste	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4b.3.3	Spent fuel container waste	-	561	-	-	-	-	-	-	83	633	633	-	-	-	-	-	-	-	-	-	-
4b.3.4	Decommissioning Equipment Disposition	-	-	116	46	697	135	-	-	157	1,149	1,149	-	-	-	-	-	-	-	304,968	123	-
4b.3	Subtotal Period 4b Collateral Costs	19	551	127	113	697	206	-	278	1,960	1,960	-	-	-	-	-	-	-	-	315,907	171	-



### Table D

**TLG Services, Inc.**

Table D  
Three Mile Island Unit 2  
Delayed DECON Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Cost	Total Contingency	Total Cost	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Erection Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet	Spent / Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours
06.1.1.1.1	Demolition of Remaining Site Buildings (continued)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
06.1.1.1.2	Miscellaneous Yard Foundations	-	20	-	-	-	-	-	3	23	-	-	-	-	-	-	-	-	-	-	294
06.1.1.1.3	River Water Pump/Blower	-	1,862	-	-	-	-	-	279	2,141	-	-	-	-	-	-	-	-	-	-	21,750
06.1.1.1.4	Turbine	-	1,495	-	-	-	-	-	111	1,847	-	-	-	-	-	-	-	-	-	-	26,780
06.1.1.1.5	Turbine Generator Foundation	-	737	-	-	-	-	-	111	847	-	-	-	-	-	-	-	-	-	-	8,464
06.1.1.1	Totals	-	9,721	-	-	-	-	-	1,438	11,179	-	-	-	-	-	-	-	-	-	-	127,770
06.1.2	Site Cleanup Activities	-	146	-	-	-	-	-	22	168	-	-	-	-	-	-	-	-	-	-	770
06.1.3	Grade & Landscape Site	-	-	-	-	-	-	-	411	411	-	-	-	-	-	-	-	-	-	-	3,120
06.1.3	Final Prep for NRC	-	-	-	-	-	-	-	411	411	-	-	-	-	-	-	-	-	-	-	3,120
06.1	Subtotal Period 06 Activity Costs	-	9,867	-	-	-	-	-	1,642	11,820	473	-	-	-	-	-	-	-	-	-	128,540
06.2	Period 06 Additional Costs	-	214	-	-	-	-	-	32	246	-	-	-	-	-	-	-	-	-	-	2,116
06.2.1	River Water Pump House Cofferdam	-	496	-	-	-	-	-	439	3,663	-	-	-	-	-	-	-	-	-	-	3,704
06.2.2	Concrete Processing	-	889	-	-	-	-	-	139	1,064	-	-	-	-	-	-	-	-	-	-	6,932
06.2.3	Release of scrap materials	-	925	-	-	-	-	-	60	5,040	-	-	-	-	-	-	-	-	-	-	24,392
06.2.3	Backfill Storage	-	4,383	-	-	-	-	-	1,343	10,662	3,863	-	-	-	-	-	-	-	-	-	39,324
06.2.3	Cooling Tower Demolition	-	6,017	-	-	-	-	-	9	10,662	3,863	-	-	-	-	-	-	-	-	-	39,324
06.2	Subtotal Period 06 Additional Costs	-	6,017	-	-	-	-	-	9	10,662	3,863	-	-	-	-	-	-	-	-	-	39,324
06.3	Period 06 Collateral Costs	-	121	-	-	-	-	-	18	139	-	-	-	-	-	-	-	-	-	-	-
06.3	Subtotal Period 06 Collateral Costs	-	121	-	-	-	-	-	18	139	-	-	-	-	-	-	-	-	-	-	-
06.4	Period 06 Period-Dependent Costs	-	-	-	-	-	-	-	21	226	-	-	-	-	-	-	-	-	-	-	-
06.4.1	Insurance	-	-	-	-	-	-	-	249	2,678	-	-	-	-	-	-	-	-	-	-	-
06.4.2	Property taxes	-	-	-	-	-	-	-	20	160	-	-	-	-	-	-	-	-	-	-	-
06.4.3	Plant equipment rental	-	2,329	-	-	-	-	-	130	1,500	-	-	-	-	-	-	-	-	-	-	-
06.4.4	Plant equipment	-	-	-	-	-	-	-	322	371	-	-	-	-	-	-	-	-	-	-	-
06.4.5	Site O&M	-	-	-	-	-	-	-	153	176	-	-	-	-	-	-	-	-	-	-	-
06.4.6	Security Staff Cost	-	-	-	-	-	-	-	1,426	10,932	-	-	-	-	-	-	-	-	-	-	-
06.4.7	BOG Staff Cost	-	-	-	-	-	-	-	2,329	10,932	-	-	-	-	-	-	-	-	-	-	-
06.4.8	Utility Staff Cost	-	-	-	-	-	-	-	2,329	10,932	-	-	-	-	-	-	-	-	-	-	-
06.4	Subtotal Period 06 Period-Dependent Costs	-	2,329	-	-	-	-	-	2,329	10,932	-	-	-	-	-	-	-	-	-	-	-
06.0	TOTAL PERIOD 06 COST	-	18,334	889	60	2,274	-	12,740	5,090	39,348	4,136	-	-	-	-	-	-	-	-	-	168,465
PERIOD 5 TOTALS		-	18,334	889	60	2,274	-	12,740	5,090	39,348	4,136	-	-	-	-	-	-	-	-	-	168,465
TOTAL COST TO DECOMMISSION		24,923	146,378	23,736	22,740	9,612	210,622	641,627	199,122	1,177,544	1,139,536	-	-	-	-	-	-	-	-	-	1,755,485
TOTAL COST TO DECOMMISSION WITH 20.25% CONTINGENCY:		\$1,177,544 thousands of 2013 dollars																			
TOTAL NRC LICENSE TERMINATION COST IS 94.77% OR:		\$1,119,536 thousands of 2013 dollars																			
NON-NUCLEAR DEMOLITION COST IS 1.25% OR:		\$24,018 thousands of 2013 dollars																			
TOTAL LOW-LEVEL RADIOACTIVE WASTE BURIED (EXCLUDING GTCC):		887,607 cubic feet																			
TOTAL GREATER THAN CLASS C RADIOACTIVE WASTE VOLUME GENERATED:		3,214 Cubic Feet																			
TOTAL SCRAP METAL REMOVED:		19,201 Tons																			
TOTAL CRAFT LABOR REQUIREMENTS:		1,735,685 Man-hours																			

End Notes:  
a - indicates that this activity not changed as decommissioning expense.  
a\* - indicates that this activity performed by decommissioning staff.  
0 - indicates that this value is less than 0.5 but is non-zero.  
a cell containing "\*" - indicates a zero value

**APPENDIX E  
DETAILED COST ANALYSIS  
SAFSTOR**

Table E  
Three Mile Island Unit 2  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Costs	Total Contingency	Total Costs	NEC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	Gravel Cu. Feet	Gravel Wh. Lbs.	Gravel Picked Wh. Lbs.	Crack Manhours	Utility and Containment Manhours
<b>PERIOD 0a - PDMS Monitoring &amp; SAFSTOR Storage</b>																						
Period 0a Direct Decommissioning Activities																						
Period 0a Collateral Costs																						
0a.3.1	PDMS Monitoring	-	-	-	-	-	-	6,042	905	6,949	6,949	-	-	-	-	-	-	-	-	-	-	-
0a.3	Subtotal Period 0a Collateral Costs	-	-	-	-	-	-	6,042	905	6,949	6,949	-	-	-	-	-	-	-	-	-	-	-
Period 0a Period-Dependent Costs																						
0a.4.1	Security	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0a.4.2	Plant energy budget	-	-	-	-	-	-	4,148	622	4,770	4,770	-	-	-	-	-	-	-	-	-	-	-
0a.4.3	Plant energy budget	-	-	-	-	-	-	46,069	7,513	53,582	53,582	-	-	-	-	-	-	-	-	-	-	-
0a.4.4	Utility Staff Cost	-	-	-	-	-	-	90,217	7,513	97,730	97,730	-	-	-	-	-	-	-	-	-	-	-
0a.4	Subtotal Period 0a Period-Dependent Costs	-	-	-	-	-	-	140,926	15,548	156,474	156,474	-	-	-	-	-	-	-	-	-	-	-
0a.0	TOTAL PERIOD 0a COST	-	-	-	-	-	-	146,968	16,453	163,421	163,421	-	-	-	-	-	-	-	-	-	-	-
<b>PERIOD 2c - SAFSTOR Dormancy without Spent Fuel Storage</b>																						
Period 2c Direct Decommissioning Activities																						
2c.1.1	Quarterly Inspection	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.1.2	Site environmental survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.1.3	Preparatory	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.1.4	Bioluminescent roof replacement	-	-	-	-	-	-	1,350	203	1,553	1,553	-	-	-	-	-	-	-	-	-	-	-
2c.1.5	Maintenance supplies	-	-	-	-	-	-	6,571	1,643	8,213	8,213	-	-	-	-	-	-	-	-	-	-	-
2c.1	Subtotal Period 2c Activity Costs	-	-	-	-	-	-	7,921	1,846	9,766	9,766	-	-	-	-	-	-	-	-	-	-	-
Period 2c Collateral Costs																						
2c.3	Subtotal Period 2c Collateral Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 2c Period-Dependent Costs																						
2c.4.1	Insurance	-	-	-	-	-	-	9,803	980	10,783	10,783	-	-	-	-	-	-	-	-	-	-	-
2c.4.2	Property taxes	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.4.3	Electricity	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2c.4.4	Disposal of DAW generated	-	-	-	-	-	-	223	74	297	297	-	-	-	-	-	-	-	-	-	-	-
2c.4.5	Plant energy budget	-	-	-	-	-	-	10,010	1,502	11,512	11,512	-	-	-	-	-	-	-	-	-	-	-
2c.4.6	NEC Fee	-	-	-	-	-	-	13,589	1,359	14,948	14,948	-	-	-	-	-	-	-	-	-	-	-
2c.4.7	Security Staff Cost	-	-	-	-	-	-	11,888	1,189	13,077	13,077	-	-	-	-	-	-	-	-	-	-	-
2c.4.8	Utility Staff Cost	-	-	-	-	-	-	4,613	461	5,074	5,074	-	-	-	-	-	-	-	-	-	-	-
2c.4	Subtotal Period 2c Period-Dependent Costs	-	-	-	-	-	-	39,803	4,845	44,648	44,648	-	-	-	-	-	-	-	-	-	-	-
2c.0	TOTAL PERIOD 2c COST	-	-	-	-	-	-	47,724	6,691	54,415	54,415	-	-	-	-	-	-	-	-	-	-	-
<b>PERIOD 2c TOTALS</b>																						
2c.0	TOTAL PERIOD 2c COST	-	-	-	-	-	-	47,724	6,691	54,415	54,415	-	-	-	-	-	-	-	-	-	-	-
<b>PERIOD 3a - Reactivate Site Following SAFSTOR Dormancy</b>																						
Period 3a Direct Decommissioning Activities																						
3a.1.1	Prepare preliminary decommissioning cost	-	-	-	-	-	-	257	39	296	296	-	-	-	-	-	-	-	-	-	-	-
3a.1.2	Review plant design & specs.	-	-	-	-	-	-	1,213	182	1,395	1,395	-	-	-	-	-	-	-	-	-	-	-
3a.1.3	Perform detailed rad survey	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3a.1.4	Perform detailed rad survey	-	-	-	-	-	-	254	40	294	294	-	-	-	-	-	-	-	-	-	-	-
3a.1.5	Detailed in-product inventory	-	-	-	-	-	-	686	103	789	789	-	-	-	-	-	-	-	-	-	-	-
3a.1.6	Define major work sequence	-	-	-	-	-	-	1,977	297	2,274	2,274	-	-	-	-	-	-	-	-	-	-	-
3a.1.7	Perform SER and EA	-	-	-	-	-	-	8,226	1,224	9,450	9,450	-	-	-	-	-	-	-	-	-	-	-
3a.1.8	Perform Site-Specific Cost Study	-	-	-	-	-	-	1,318	186	1,504	1,504	-	-	-	-	-	-	-	-	-	-	-
3a.1.9	Prepare Final License Termination Plan	-	-	-	-	-	-	2,162	324	2,486	2,486	-	-	-	-	-	-	-	-	-	-	-
3a.1.10	Receive NRC approval of termination plan	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Activity Specifications																						
3a.1.11.1	Re-activate plant & temporary facilities	-	-	-	-	-	-	1,457	219	1,676	1,676	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.2	Plant systems	-	-	-	-	-	-	1,069	165	1,234	1,234	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.3	Reactor internals	-	-	-	-	-	-	1,265	193	1,458	1,458	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.4	Biological shield	-	-	-	-	-	-	66	10	76	76	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.5	Steam generators	-	-	-	-	-	-	1,645	247	1,892	1,892	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.6	Reinforced concrete	-	-	-	-	-	-	452	68	520	520	-	-	-	-	-	-	-	-	-	-	-
3a.1.11.7	Main Turbine	-	-	-	-	-	-	53	8	61	61	-	-	-	-	-	-	-	-	-	-	-

Table E  
Three Mile Island Unit 2  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Costs	Total Contingency	Total Costs	NGO Lic. Term.	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Glass B Cu. Feet	Class C Glass C Cu. Feet	BTGC Wh. Lbs.	Burial/Processed Wh. Lbs.	Craft Manhours	Utility and Outfitting Manhours
<b>Activity Specifications (continued)</b>																				
3a.1.1.1.9	Main Condensers	-	-	-	-	-	-	53	8	61	-	-	-	-	-	-	-	-	-	400
3a.1.1.1.10	Plant structures & buildings	-	-	-	-	-	-	411	32	473	-	-	237	-	-	-	-	-	-	3,120
3a.1.1.1.11	Plant equipment	-	-	-	-	-	-	2,575	304	2,879	-	-	-	-	-	-	-	-	-	18,000
3a.1.1.1.12	Facility & site cleanup	-	-	-	-	-	-	119	18	136	-	-	68	-	-	-	-	-	-	900
3a.1.1.1	Total	-	-	-	-	-	-	10,907	1,938	12,544	11,481	-	963	-	-	-	-	-	-	82,738
<b>Planning &amp; Site Preparations</b>																				
3a.1.1.2	Prepare dismantling sequence	-	-	-	-	-	-	833	95	728	728	-	-	-	-	-	-	-	-	4,800
3a.1.1.3	Plant prep. & ramp access	-	-	-	-	-	-	2,535	425	3,325	3,325	-	-	-	-	-	-	-	-	5,900
3a.1.1.4	Decontamination	-	-	-	-	-	-	738	111	849	849	-	-	-	-	-	-	-	-	-
3a.1.1.5	Regrouping Cont. Over Exposed Areas, etc.	-	-	-	-	-	-	2,200	330	2,530	2,530	-	-	-	-	-	-	-	-	-
3a.1.1.6	Procure caskloaders & containers	-	-	-	-	-	-	33,806	49	37,373	37,373	-	-	-	-	-	-	-	-	2,460
3a.1	Subtotal Period 3a Activity Costs	-	-	-	-	-	-	33,806	5,071	38,877	37,914	-	963	-	-	-	-	-	-	217,748
<b>Period 3a Additional Costs</b>																				
3a.2.1	Railroad Track Refurbishment	-	-	-	-	-	-	330	50	380	380	-	-	-	-	-	-	-	-	-
3a.2.2	Equipment Anticlock Refurbishment	-	-	-	-	-	-	1,290	194	1,484	1,484	-	-	-	-	-	-	-	-	-
3a.2.3	RB Polar Crane Refurbishment	-	-	-	-	-	-	6,450	958	7,418	7,418	-	-	-	-	-	-	-	-	-
3a.2.4	RB Cask Handling System	-	-	-	-	-	-	1,290	194	1,484	1,484	-	-	-	-	-	-	-	-	-
3a.2	Subtotal Period 3a Additional Costs	-	-	-	-	-	-	9,360	1,404	10,764	10,764	-	-	-	-	-	-	-	-	-
<b>Period 3a Collateral Costs</b>																				
3a.3	Subtotal Period 3a Collateral Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Period 3a Period-Dependent Costs</b>																				
3a.4.1	Insurance	-	-	-	-	-	-	206	21	226	226	-	-	-	-	-	-	-	-	-
3a.4.2	Permit fees	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3a.4.3	Health physics supplies	-	-	-	-	-	-	-	166	779	779	-	-	-	-	-	-	-	-	-
3a.4.4	Heavy equipment rental	-	-	-	-	-	-	-	64	494	494	-	-	-	-	-	-	-	-	-
3a.4.5	Disposal of DAW generated	-	-	-	-	-	-	976	146	1,122	1,122	-	-	-	-	-	-	-	-	-
3a.4.6	Plant energy budget	-	-	-	-	-	-	-	1,122	1,122	1,122	-	-	-	-	-	-	-	-	-
3a.4.7	SRG (Steam Recovery Generator)	-	-	-	-	-	-	1,322	147	1,469	1,469	-	-	-	-	-	-	-	-	-
3a.4.8	SRG (Steam Recovery Generator)	-	-	-	-	-	-	3,089	653	4,242	4,242	-	-	-	-	-	-	-	-	-
3a.4.9	Security Staff Cost	-	-	-	-	-	-	11,762	1,764	13,527	13,527	-	-	-	-	-	-	-	-	-
3a.4.10	DOC Staff Cost	-	-	-	-	-	-	2,623	383	3,017	3,017	-	-	-	-	-	-	-	-	-
3a.4.11	Utility Staff Cost	-	-	-	-	-	-	20,853	3,252	25,230	25,230	-	-	-	-	-	-	-	-	-
3a.4	Subtotal Period 3a Period-Dependent Costs	-	-	-	-	-	-	64,018	9,737	73,948	73,948	-	963	-	-	-	-	-	-	-
3a.0	TOTAL PERIOD 3a COST	-	-	-	-	-	-	64,018	9,737	73,948	73,948	-	963	-	-	-	-	-	-	-
<b>PERIOD 3b - Decommissioning Preparations</b>																				
<b>Period 3b Direct Decommissioning Activities</b>																				
<b>Detailed Work Procedures</b>																				
3b.1.1.1	Plant systems	-	-	-	-	-	-	1,348	187	1,435	1,435	-	144	-	-	-	-	-	-	-
3b.1.1.2	Reactor internals	-	-	-	-	-	-	629	99	728	728	-	-	-	-	-	-	-	-	-
3b.1.1.3	Remaining buildings	-	-	-	-	-	-	178	27	205	205	-	153	-	-	-	-	-	-	-
3b.1.1.4	CRD cooling assembly	-	-	-	-	-	-	198	30	227	227	-	-	-	-	-	-	-	-	-
3b.1.1.5	CRD bearings & ICI tubes	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3b.1.1.6	Reactor vessel	-	-	-	-	-	-	718	108	825	825	-	-	-	-	-	-	-	-	-
3b.1.1.7	Reactor vessel	-	-	-	-	-	-	158	24	182	182	-	91	-	-	-	-	-	-	-
3b.1.1.8	Facility cleanup	-	-	-	-	-	-	69	9	78	78	-	-	-	-	-	-	-	-	-
3b.1.1.9	Miscellaneous	-	-	-	-	-	-	188	24	212	212	-	-	-	-	-	-	-	-	-
3b.1.1.10	Biological shield	-	-	-	-	-	-	2,152	306	2,458	2,458	-	-	-	-	-	-	-	-	-
3b.1.1.11	Steam generators	-	-	-	-	-	-	132	20	152	152	-	76	-	-	-	-	-	-	-
3b.1.1.12	Steam generators	-	-	-	-	-	-	306	31	337	337	-	-	-	-	-	-	-	-	-
3b.1.1.13	Main Turbine	-	-	-	-	-	-	206	31	237	237	-	237	-	-	-	-	-	-	-
3b.1.1.14	Main Condensers	-	-	-	-	-	-	108	828	745	745	-	83	-	-	-	-	-	-	-
3b.1.1.15	Auxiliary building	-	-	-	-	-	-	720	108	828	828	-	1,102	-	-	-	-	-	-	-
3b.1.1.16	Reactor building	-	-	-	-	-	-	7,785	1,188	8,973	8,973	-	-	-	-	-	-	-	-	-
3b.1.1	Subtotal Period 3b Activity Costs	-	-	-	-	-	-	7,785	1,188	8,973	8,973	-	1,102	-	-	-	-	-	-	-

Table E  
Three Mile Island Unit 2  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decom Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet	Burial/Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours	
Period 3b Additional Costs																						
3b.2.1	Lead Shielding Disposal	-	740	225	611	-	-	5,474	-	6,717	8,717	-	-	-	-	2,311	-	-	-	1,418,084	14,333	-
3b.2.2	Stored Defueling Equipment Disposition	-	688	63	104	-	-	884	-	2,029	2,029	-	-	-	-	3,698	-	-	-	240,505	12,077	-
3b.2	Subtotal Period 3b Additional Costs	-	1,428	288	715	-	-	6,358	-	2,097	10,746	-	-	-	-	6,079	-	-	-	1,657,589	26,410	-
Period 3b Collateral Costs																						
3b.3.1	Decom equipment	712	-	-	-	-	-	-	107	819	819	-	-	-	-	-	-	-	-	-	-	-
3b.3.2	DOC staff relocation expenses	-	-	-	-	-	-	1,385	-	208	1,593	-	-	-	-	-	-	-	-	-	-	-
3b.3.3	Small tool allowance	-	6	-	-	-	-	-	3	21	21	-	-	-	-	-	-	-	-	-	-	-
3b.3.4	Pipe cutting equipment	-	1,100	-	-	-	-	-	-	165	1,265	-	-	-	-	-	-	-	-	-	-	-
3b.3	Subtotal Period 3b Collateral Costs	712	1,118	-	-	-	-	1,385	482	3,698	3,698	-	-	-	-	-	-	-	-	-	-	-
Period 3b Period-Dependent Costs																						
3b.4.1	Decom supplies	22	-	-	-	-	-	-	6	28	28	-	-	-	-	-	-	-	-	-	-	-
3b.4.2	Insurance	-	-	-	-	-	-	104	-	115	115	-	-	-	-	-	-	-	-	-	-	-
3b.4.3	Property taxes	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3b.4.4	Health physics supplies	-	537	-	-	-	-	-	134	672	672	-	-	-	-	-	-	-	-	-	-	-
3b.4.5	Heavy equipment rental	-	216	-	-	-	-	-	33	261	261	-	-	-	-	-	-	-	-	5,783	13	-
3b.4.6	Disposal of DAW generated	-	-	6	5	-	-	15	-	29	29	-	-	-	-	289	-	-	-	-	-	-
3b.4.7	Plant energy budget	-	-	-	-	-	-	-	495	74	569	-	-	-	-	-	-	-	-	-	-	-
3b.4.8	NRC Fees	-	-	-	-	-	-	-	64	209	209	-	-	-	-	-	-	-	-	-	-	-
3b.4.9	Site O&M	-	-	-	-	-	-	-	163	24	188	188	-	-	-	-	-	-	-	-	-	-
3b.4.10	Liquid Radioactive Processing Equipment/Services	-	-	-	-	-	-	-	201	30	231	231	-	-	-	-	-	-	-	-	-	-
3b.4.11	Security Staff Cost	-	-	-	-	-	-	-	1,870	260	2,160	2,160	-	-	-	-	-	-	-	-	-	-
3b.4.12	DOC Staff Cost	-	-	-	-	-	-	-	12,843	1,897	14,340	14,340	-	-	-	-	-	-	-	-	-	-
3b.4.13	Utility Staff Cost	-	-	-	-	-	-	-	1,414	141	1,555	1,555	-	-	-	-	-	-	-	-	-	-
3b.4	Subtotal Period 3b Period-Dependent Costs	22	755	5	5	-	-	15	17,445	2,737	21,004	21,004	-	-	-	289	-	-	-	5,783	13	-
3b.0	TOTAL PERIOD 3b COST	734	3,202	293	720	-	-	6,372	26,615	6,464	44,490	43,296	1,102	-	-	6,368	-	-	-	1,673,372	26,423	-
3b.0	TOTAL PERIOD 3b COST	734	4,255	301	728	-	-	6,397	90,634	16,222	119,271	117,266	2,065	-	-	6,858	-	-	-	1,683,185	26,446	-
PERIOD 3 TOTALS																						
PERIOD 4a - Large Component Renewal																						
Period 4a Direct Decommissioning Activities																						
Nuclear Steam Supply System Removal																						
4a.1.1.1	Reactor Coolant Pump	22	88	15	25	24	348	-	129	651	651	-	-	-	83	750	-	-	-	99,483	2,285	-
4a.1.1.2	Pressurizer Relief Tank	3	12	3	6	5	72	-	25	127	127	-	-	-	19	169	-	-	-	20,849	315	-
4a.1.1.3	Reactor Coolant Pumps & Motors	-	1,267	883	130	-	3,155	-	1,213	6,648	6,648	-	-	-	10,762	-	-	-	-	1,124,474	81,482	-
4a.1.1.4	Pressurizer	34	1,333	1,707	177	-	3,178	-	1,025	6,303	6,303	-	-	-	2,644	-	-	-	-	463,736	4,192	-
4a.1.1.5	Steam Generators	32	6,960	1,196	3,129	-	21,518	-	10,251	53,188	53,188	-	-	-	24,892	7,262	-	-	-	2,386,266	149,431	-
4a.1.1.6	CRDMs/Refueling Structure Removal	12	55	1,175	84	-	185	-	53	584	584	-	-	-	1,454	-	-	-	-	47,869	1,312	-
4a.1.1.7	Reactor Vessel Internals	82	12,878	9,689	957	-	934	671	12,979	38,390	38,390	-	-	-	2,804	-	-	-	-	235,955	48,160	-
4a.1.1.8	Vessel & Internals GTCC Disposal	-	-	-	-	-	13,703	-	2,055	15,758	15,758	-	-	-	-	-	-	-	-	864,685	-	-
4a.1.1.9	Reactor Vessel	-	10,832	2,802	522	-	2,824	671	10,468	28,119	28,119	-	-	-	9,626	-	-	-	-	975,373	48,160	-
4a.1.1	Totals	154	33,125	15,719	6,011	29	53,913	1,341	37,842	147,137	147,137	-	-	-	102	52,632	7,262	-	-	5,581,680	285,357	-
Removal of Major Equipment																						
4a.1.2	Main Turbine/Generator	-	278	93	23	615	-	-	176	1,184	1,184	-	-	-	5,298	-	-	-	-	238,394	5,389	-
4a.1.3	Main Condensers	-	1,271	103	25	680	-	-	434	2,514	2,514	-	-	-	5,660	-	-	-	-	263,680	25,162	-
Cascading Costs from Clean Building Demolition																						
4a.1.4.1	Control & Service	-	165	-	-	-	-	-	25	191	191	-	-	-	-	-	-	-	-	-	2,040	-
4a.1.4	Totals	-	165	-	-	-	-	-	25	191	191	-	-	-	-	-	-	-	-	-	2,040	-
Disposal of Plant Systems																						
4a.1.5.1	Decay Heat Closed Cooling Water	-	280	34	60	697	348	-	274	1,593	1,593	-	-	-	6,596	1,353	-	-	-	390,399	8,823	-
4a.1.5.2	Decay Heat Removal (RCA)	-	200	55	74	263	664	-	272	1,527	1,527	-	-	-	2,311	2,397	-	-	-	215,855	4,823	-
4a.1.5.3	Decay Heat Removal (RCA)	-	142	8	11	57	92	-	70	381	381	-	-	-	547	362	-	-	-	2,863	2,863	-
4a.1.5.4	Domestic Water (RCA)	-	6	-	-	-	-	-	1	7	7	-	-	-	-	-	-	-	-	46,162	148	-
4a.1.5.5	Domestic Water (RCA)	-	21	1	2	7	14	-	10	54	54	-	-	-	63	54	-	-	-	6,162	420	-
4a.1.5.7	Electrical (Clean)	-	9	-	-	-	-	-	1	11	11	-	-	-	-	-	-	-	-	191	191	-
4a.1.5.8	Emergency Feedwater (RCA)	-	65	-	6	43	51	-	8	206	206	-	-	-	407	166	-	-	-	29,643	1,167	-
4a.1.5.9	Fire Protection (RCA)	-	48	-	3	4	15	31	23	123	123	-	-	-	62	146	-	-	-	14,013	991	-
4a.1.5.10	Fire Protection (RCA)	-	208	8	10	60	84	-	84	454	454	-	-	-	558	332	-	-	-	44,866	4,397	-
4a.1.5.11	Gaseous Waste Disposal System (RCA)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Table E  
Three Mile Island Unit 2  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	Off-Site Processing Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GRCC Cu. Feet	Burial/ Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours	
4a.1.5.12	HVAC - Auxiliary Building	-	525	15	26	181	195	-	213	1,155	1,155	-	-	1,725	705	-	-	-	-	120,641	11,076	-
4a.1.5.13	HVAC - Control Building	-	59	3	9	166	17	-	49	323	323	-	-	1,780	67	-	-	-	-	76,715	1,131	-
4a.1.5.14	HVAC - Miscellaneous	-	35	-	-	108	11	-	39	240	240	-	-	1,029	41	-	-	-	-	44,512	1,435	-
4a.1.5.15	HVAC - Service Building	-	15	0	0	0	0	-	0	0	0	-	-	4	8	-	-	-	-	669	413	-
4a.1.5.16	Hydrogen Purge - Rad Monitoring	-	221	-	-	-	-	-	33	254	254	-	-	254	-	-	-	-	-	4,899	-	-
4a.1.5.17	Industrial Waste Treatment System	-	116	8	28	75	75	-	54	290	290	-	-	271	254	-	-	-	-	30,495	2,374	-
4a.1.5.18	Instrument Air (RCA)	-	95	14	21	60	190	-	85	463	463	-	-	4,091	157	-	-	-	-	168,742	1,958	-
4a.1.5.19	Intermediate Closed Cooling Water (RCA)	-	202	8	20	430	38	-	128	826	826	-	-	643	292	-	-	-	-	176,354	3,277	-
4a.1.5.20	Main Condensate (RCA)	-	82	6	6	12	14	-	62	144	144	-	-	8	-	-	-	-	-	17,472	1,042	-
4a.1.5.21	Main Reheat & Steam (RCA)	-	84	17	17	1349	1,718	-	891	5,169	5,169	-	-	12,877	6,801	-	-	-	-	968,028	17,553	-
4a.1.5.22	Nuclear Services Closed Cycle Cooling	-	78	-	-	-	-	-	12	90	90	-	-	90	-	-	-	-	-	1,764	-	-
4a.1.5.23	Nuclear Services River Water (RCA)	-	1,287	80	115	480	1,010	-	669	3,621	3,621	-	-	4,382	3,565	-	-	-	-	440,046	28,724	-
4a.1.5.24	Nuclear Services River Water (RCA)	-	14	-	-	182	490	-	2	16	16	-	-	16	-	-	-	-	-	340	-	-
4a.1.5.25	Reactor Building Normal Cooling (Clean)	-	294	36	54	182	490	-	23	1,264	1,264	-	-	1,739	1,930	-	-	-	-	197,600	5,788	-
4a.1.5.26	Reactor Building Normal Cooling (Clean)	-	214	36	54	182	490	-	23	1,264	1,264	-	-	1,739	1,930	-	-	-	-	197,600	5,788	-
4a.1.5.27	Secondary Side Vents & Driums	-	17	17	17	-	-	-	106	544	544	-	-	682	4,992	-	-	-	-	46,402	4,992	-
4a.1.5.28	Sampling Nuclear System	-	231	15	17	-	-	-	106	544	544	-	-	682	4,992	-	-	-	-	46,402	4,992	-
4a.1.5.29	Sewage Treatment Plant (RCA)	-	4	0	0	4	1	-	2	11	11	-	-	35	4	-	-	-	-	1,682	82	-
4a.1.5.30	Station Service Air	-	260	10	10	10	95	-	93	483	483	-	-	139	372	-	-	-	-	30,363	5,863	-
4a.1.5.31	Swamp Systems (RCA)	-	145	5	6	17	56	-	54	282	282	-	-	181	215	-	-	-	-	20,766	3,216	-
4a.1.5.32	Turbine Plant Sample (RCA)	-	17	1	1	1	8	-	8	41	41	-	-	61	32	-	-	-	-	1,680	339	-
4a.1.5	Total	-	8,802	469	687	4,236	5,480	-	3,550	30,223	30,223	-	-	641	40,423	21,641	-	-	-	3,081,230	124,129	-
4a.1.6	Scaffolding in support of decommissioning	-	1,202	16	4	104	-	-	318	1,643	1,643	-	-	893	-	-	-	-	-	40,189	29,260	-
4a.1	Subtotal Period 4a Activity Costs	154	41,843	16,401	5,750	5,984	59,395	1,341	42,343	172,891	172,891	-	-	641	52,575	74,173	7,262	-	2,856	9,535,183	471,407	5,741
4a.2.1	Period 4a Additional Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4a.2.2	Reactor Building Basement Dose Reduction	-	17	126	3,378	-	45,924	-	11,945	61,189	61,189	-	-	-	-	-	-	-	-	1,217,965	282	-
4a.2.3	Containment Basement Liner Removal	-	123	273	521	-	13,552	-	3,524	17,952	17,952	-	-	-	-	-	-	-	-	129,709	2,286	-
4a.2.4	Reactor Building SNF & ROT Systems Removal	-	1,901	171	568	-	4,955	-	2,636	10,765	10,765	-	-	-	-	-	-	-	-	75,708	358	-
4a.2.5	Fuel Handling / Auxiliary SNF & ROT Systems Removal	2,517	7,614	1,127	41	-	2,384	700	9,071	23,140	23,140	-	-	-	-	-	-	-	-	679,443	84,140	-
4a.2.6	SNSS Component Surface Decontamination	70	437	113	13	-	397	-	827	1,340	1,340	-	-	-	-	-	-	-	-	124,193	10,050	-
4a.2.7	FLHIS AX-200 Decontamination	-	151	201	933	-	12,196	377	8,306	17,185	17,185	-	-	-	-	-	-	-	-	228,566	4,638	-
4a.2.8	Legacy waste stored at INEEL	-	-	-	-	-	650	-	98	748	748	-	-	-	-	-	-	-	-	-	-	-
4a.2	Subtotal Period 4a Additional Costs	10,260	2,618	2,027	6,823	-	78,219	10,797	28,020	137,805	137,805	-	-	-	-	-	-	-	-	2,475,308	148,683	-
4a.3	Period 4a Collateral Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4a.3.1	Process decommissioning water waste	3	-	3	19	-	20	-	10	56	56	-	-	-	-	-	-	-	-	3,121	14	-
4a.3.2	Process decommissioning chemical flush waste	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4a.3.3	Small tool allowance	3	431	3	19	-	20	-	65	465	465	-	-	-	-	-	-	-	-	-	-	-
4a.3	Subtotal Period 4a Collateral Costs	6	434	6	38	-	40	-	75	551	551	-	-	-	-	-	-	-	-	3,121	14	-
4a.4	Period 4a Period-Dependent Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4a.4.1	Reactor building supplies	211	-	-	-	-	-	-	53	264	264	-	-	-	-	-	-	-	-	-	-	-
4a.4.2	Reactor building supplies	-	-	-	-	-	-	-	100	1,098	1,098	-	-	-	-	-	-	-	-	-	-	-
4a.4.3	Health physics supplies	-	-	-	-	-	-	-	1,947	9,737	9,737	-	-	-	-	-	-	-	-	-	-	-
4a.4.4	Health physics supplies	-	7,789	-	-	-	-	-	1,199	9,190	9,190	-	-	-	-	-	-	-	-	-	-	-
4a.4.5	Heavy equipment rental	-	7,991	-	-	-	-	-	1,199	9,190	9,190	-	-	-	-	-	-	-	-	-	-	-
4a.4.6	Disposal of DAW generated	-	-	169	-	-	-	-	153	919	919	-	-	-	-	-	-	-	-	-	-	-
4a.4.7	Disposal of DAW generated	-	-	-	-	-	-	-	710	5,419	5,419	-	-	-	-	-	-	-	-	-	-	-
4a.4.8	NEC Fee	-	-	-	-	-	-	-	481	5,294	5,294	-	-	-	-	-	-	-	-	-	-	-
4a.4.9	Site O&M	-	-	-	-	-	-	-	235	1,798	1,798	-	-	-	-	-	-	-	-	-	-	-
4a.4.10	Liquid Waste Processing Equipment/Services	-	-	-	-	-	-	-	289	2,215	2,215	-	-	-	-	-	-	-	-	-	-	-
4a.4.11	Security Staff Cost	-	-	-	-	-	-	-	2,891	22,163	22,163	-	-	-	-	-	-	-	-	-	-	-
4a.4.12	DOC Staff Cost	-	-	-	-	-	-	-	13,159	131,590	131,590	-	-	-	-	-	-	-	-	-	-	-
4a.4.13	DOC Staff Cost	-	-	-	-	-	-	-	13,159	131,590	131,590	-	-	-	-	-	-	-	-	-	-	-
4a.4	Subtotal Period 4a Period-Dependent Costs	211	15,780	159	160	-	457	178,884	30,043	228,685	228,685	-	-	-	-	-	-	-	-	181,033	413	-
4a.6	TOTAL PERIOD 4a COST	10,968	60,673	18,690	11,843	5,984	138,091	192,023	100,482	537,933	537,933	-	-	691	62,575	96,286	26,918	1,202	3,214	12,194,650	620,317	2,286,043

Table E  
Three Mile Island Unit 2  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Costs	Total Contingency	Total Costs	Site Restoration Costs	Spent Fuel Management Costs	Class A Waste Cu. Feet	Class B Waste Cu. Feet	Class C Waste Cu. Feet	GFCC Waste Cu. Feet	Residual Waste Wh. Lbs.	Processed Volume Cu. Feet	Uplift and Containment Manhours
4b.1.1	Decommissioning of Plant Systems	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4b.1.2.1	Decommissioning of Reactor (RB)	241	32	32	39	401	-	-	170	832	-	-	1,070	-	-	-	103,970	-	5,302
4b.1.2.2	Electrical (Contaminated - RCA)	43	3	3	3	42	-	-	22	114	-	-	-	-	-	-	10,880	-	395
4b.1.2.3	Electrical (Non-contaminated - RCA)	255	3	3	3	570	-	-	175	1,114	-	-	-	-	-	-	21,880	-	835
4b.1.2.4	Fire Protection (RB)	38	12	12	12	123	-	-	224	224	-	-	483	-	-	-	31,951	-	835
4b.1.2.5	Fire Protection (RB)	21	2	2	2	21	-	-	11	66	-	-	82	-	-	-	6,416	-	461
4b.1.2.6	Fuel Handling (RCA)	4	1	1	1	7	-	-	3	15	-	-	15	-	-	-	1,751	-	86
4b.1.2.7	Fuel Handling (RB)	308	22	32	32	330	-	-	166	838	-	-	1,292	-	-	-	65,392	-	6,306
4b.1.2.8	Gaseous Waste Disposal System (RB)	4	0	0	0	4	-	-	2	10	-	-	10	-	-	-	1,451	-	4
4b.1.2.9	Gas Handling Building	516	11	11	11	1,115	-	-	20	1,136	-	-	212	-	-	-	61,849	-	4,591
4b.1.2.10	RVAC - Reactor Building	816	76	103	103	1,095	-	-	491	2,543	-	-	1,097	-	-	-	275,569	-	17,022
4b.1.2.11	Instrument Air (RB)	27	2	2	2	30	-	-	12	64	-	-	179	-	-	-	5,215	-	980
4b.1.2.12	Intermediate Closed Cooling Water (RB)	81	8	9	9	95	-	-	46	240	-	-	373	-	-	-	24,089	-	1,744
4b.1.2.13	Nitrogen for Nuclear Radiolysis Sys (RB)	8	1	1	1	18	-	-	7	35	-	-	69	-	-	-	4,572	-	171
4b.1.2.14	Nuclear Services Water (RB)	85	15	20	20	205	-	-	78	407	-	-	864	-	-	-	33,306	-	1,433
4b.1.2.15	TRAC Chemical Waste System	12	2	2	2	20	-	-	1	10	-	-	10	-	-	-	6,552	-	180
4b.1.2.16	Sump Treatment Plant (Clean)	8	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4b.1.2.17	Spent Fuel Cooling	436	26	33	33	328	-	-	206	1,077	-	-	442	-	-	-	103,430	-	9,812
4b.1.2.18	Spent Fuel Cooling (RB)	24	2	3	3	28	-	-	14	71	-	-	110	-	-	-	7,258	-	525
4b.1.2.19	Sump Systems (RB)	37	3	4	4	38	-	-	103	103	-	-	152	-	-	-	10,068	-	809
4b.1.2	Totals	2,959	220	304	304	733	-	-	1,659	8,394	-	-	6,591	-	-	-	1,027,234	-	87,453
4b.1.3	Scaffolding in support of decommissioning	-	1,802	24	6	186	-	-	477	2,465	-	-	1,340	-	-	-	90,283	-	43,938
4b.1.4	Decommissioning of Site Buildings	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4b.1.4.1	Reactor	10,224	4,077	1,624	1,474	15,272	-	-	10,333	43,004	-	-	39,547	-	-	-	3,595,465	-	262,541
4b.1.4.2	Archives	476	15	15	15	462	-	-	23	484	-	-	323	-	-	-	2,482,520	-	2,574
4b.1.4.3	Control Building	1,036	60	60	60	1,156	-	-	622	3,564	-	-	28,691	-	-	-	9,763	-	663
4b.1.4.4	Control Building	22	5	5	5	37	-	-	15	64	-	-	2	-	-	-	64,322	-	2,532
4b.1.4.5	Control Building Area	86	43	2	24	38	-	-	71	290	-	-	249	-	-	-	394,809	-	30,747
4b.1.4.6	Fuel Handling	670	951	47	137	84	-	-	756	3,225	-	-	803	-	-	-	2,332	-	1,451
4b.1.4.7	Turbine	65	4	0	0	2	-	-	34	106	-	-	39	-	-	-	7,386,210	-	335,735
4b.1.4	Totals	11,544	6,121	1,703	2,877	17,963	-	-	12,421	62,823	-	-	1,377	-	-	-	8,453,726	-	427,924
4b.1	Subtotal Period 4b Activity Costs	11,544	10,822	1,997	3,187	1,032	-	-	14,467	63,681	-	-	9,708	-	-	-	18,985,440	-	1,511,480
Period 4b Additional Costs		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4b.2.1	Biohazard & D-Ring Removal	-	4,624	766	1,595	-	-	-	3,747	19,804	-	-	185,795	-	-	-	18,985,440	-	60,893
4b.2.2	Reactor Building	-	8,177	1,232	1,232	-	-	-	1,035	9,409	-	-	48,982	-	-	-	3,723,414	-	8,942
4b.2.3	Process NSSS decontamination liquid inventory	-	722	72	269	-	-	-	1,464	7,532	-	-	-	-	-	-	126,837	-	779
4b.2.4	Process NSSS decontamination liquid inventory	-	8,841	370	973	-	-	-	3,854	19,581	-	-	99,586	-	-	-	11,950,340	-	113,205
4b.2.5	Fuel Handling Building Total Removal	-	6,151	83	875	-	-	-	2,954	13,089	-	-	68,634	-	-	-	8,238,090	-	73,213
4b.2.6	On-site survey & release of concrete	-	2,512	-	969	-	-	-	3,965	20,935	-	-	199,217	-	-	-	17,331,090	-	25,319
4b.2.7	On-site survey & release of concrete	-	21	2	76	-	-	-	807	2,887	-	-	10,319	-	-	-	88,706	-	961
4b.2.8	On-site survey & release of concrete	-	1,036	1,036	1,036	-	-	-	2,887	2,887	-	-	636,309	-	-	-	68,737,760	-	402,574
4b.2	Subtotal Period 4b Additional Costs	-	31,549	1,079	6,646	-	-	-	21,268	110,370	-	-	1,462	-	-	-	-	-	-
Period 4b Collateral Costs		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4b.3.1	Process decommissioning water waste	6	-	6	39	-	-	-	20	113	-	-	106	-	-	-	6,345	-	26
4b.3.2	Process decommissioning chemical wash waste	-	-	-	-	-	-	-	83	633	-	-	-	-	-	-	-	-	-
4b.3.3	Process decommissioning chemical wash waste	-	561	-	-	-	-	-	133	1,060	-	-	-	-	-	-	300,000	-	123
4b.3.4	Decommissioning Equipment Disposition	-	117	35	774	-	-	-	236	1,806	-	-	6,567	-	-	-	396,345	-	151
4b.3	Subtotal Period 4b Collateral Costs	6	551	124	75	774	-	-	41	-	-	-	106	-	-	-	-	-	-
Period 4b Period-Dependent Costs		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4b.4.1	Decon supplies	1,023	-	-	-	-	-	-	956	1,279	-	-	-	-	-	-	-	-	-
4b.4.2	Decon supplies	-	-	-	-	-	-	-	109	1,199	-	-	-	-	-	-	-	-	-
4b.4.3	Property taxes	-	-	-	-	-	-	-	2,337	11,685	-	-	-	-	-	-	-	-	-
4b.4.4	Health physics supplies	-	9,348	-	-	-	-	-	1,295	9,950	-	-	-	-	-	-	-	-	-
4b.4.5	Heavy equipment rental	-	8,635	-	-	-	-	-	116	897	-	-	-	-	-	-	-	-	-
4b.4.6	Disposal of DAW generated	-	-	121	114	-	-	-	347	4,421	-	-	-	-	-	-	187,260	-	313
4b.4.7	Heavy equipment budget	-	-	-	-	-	-	-	439	4,826	-	-	-	-	-	-	-	-	-
4b.4.8	NRC Fees	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-



Table E  
Three Mile Island Unit 2  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Costs	Total Contingency	Total Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet	Residual Processed Wt. Lbs.	Cost / Wt. Lbs.	Credit Manhours	Utility and Contractor Manhours
Period 4b Period-Dependent Costs (continued)																				
4b.4.9	Site O&M	-	-	-	-	-	-	1,707	260	1,963	-	-	-	-	-	-	-	-	-	-
4b.4.10	Liquid Radiactive Processing Equipment/Services	-	-	-	-	-	-	2,103	313	2,416	-	-	-	-	-	-	-	-	-	-
4b.4.11	Site O&M Cost	-	-	-	-	-	-	13,741	13,741	13,741	-	-	-	-	-	-	-	-	-	208,020
4b.4.12	DPC Staff Cost	-	-	-	-	-	-	114,909	17,248	132,157	-	-	-	-	-	-	-	-	-	1,612,674
4b.4.13	Utility Staff Cost	-	-	-	-	-	-	13,823	2,073	15,896	-	-	-	-	-	-	-	-	-	138,071
4b.4.14	Subtotal Period 4b Period-Dependent Costs	1,023	17,962	121	114	-	347	153,847	26,897	200,240	-	-	-	-	-	-	-	-	313	1,953,766
4b.0	TOTAL PERIOD 4b COST	12,897	60,704	3,920	10,021	1,908	65,785	155,546	62,718	376,097	-	10	16,375	753,496	-	1,482	-	75,632,090	830,962	1,987,025
PERIOD 4c - License Termination																				
Period 4c Direct Decommissioning Activities																				
4c.1.1	ORISE confirmatory survey	-	-	-	-	-	-	161	48	209	-	-	-	-	-	-	-	-	-	-
4c.1.2	Terminate license	-	-	-	-	-	-	161	48	209	-	-	-	-	-	-	-	-	-	-
4c.1	Subtotal Period 4c Activity Costs	-	-	-	-	-	-	322	96	418	-	-	-	-	-	-	-	-	-	-
Period 4c Additional Costs																				
4c.2.1	License Termination Survey	-	-	-	-	-	-	6,191	1,857	8,048	-	-	-	-	-	-	-	-	-	-
4c.2	Subtotal Period 4c Additional Costs	-	-	-	-	-	-	6,191	1,857	8,048	-	-	-	-	-	-	-	-	-	-
Period 4c Collateral Costs																				
4c.3.1	DPC staff relocation expenses	-	-	-	-	-	-	1,365	208	1,563	-	-	-	-	-	-	-	-	-	-
4c.3	Subtotal Period 4c Collateral Costs	-	-	-	-	-	-	1,365	208	1,563	-	-	-	-	-	-	-	-	-	-
Period 4c Period-Dependent Costs																				
4c.4.1	Insurance	-	-	-	-	-	-	154	15	170	-	-	-	-	-	-	-	-	-	-
4c.4.2	Electricity	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4c.4.3	Health physics supplies	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4c.4.4	Disposal of DAW generated	-	-	-	-	-	-	16	6	32	-	-	-	-	-	-	-	-	-	-
4c.4.5	Plant energy budget	-	-	-	-	-	-	195	29	225	-	-	-	-	-	-	-	-	-	-
4c.4.6	NRC Fee	-	-	-	-	-	-	452	43	497	-	-	-	-	-	-	-	-	-	-
4c.4.7	Site O&M	-	-	-	-	-	-	698	106	709	-	-	-	-	-	-	-	-	-	-
4c.4.8	DPC Staff Cost	-	-	-	-	-	-	4,659	679	5,209	-	-	-	-	-	-	-	-	-	-
4c.4.9	Utility Staff Cost	-	-	-	-	-	-	1,540	321	1,771	-	-	-	-	-	-	-	-	-	-
4c.4.10	Subtotal Period 4c Period-Dependent Costs	-	-	-	-	-	-	7,782	1,381	10,044	-	-	-	-	-	-	-	-	-	-
4c.4	TOTAL PERIOD 4c COST	-	-	-	-	-	-	16,538	3,474	19,894	-	-	-	-	-	-	-	-	-	-
4c.0	TOTAL PERIOD 4c COST	-	-	-	-	-	-	16,538	3,474	19,894	-	-	-	-	-	-	-	-	-	-
4c.0	TOTAL PERIOD 4c COST	23,166	122,252	22,515	21,869	7,470	203,893	366,097	166,674	933,925	-	700	68,590	849,098	26,518	2,734	3,214	87,836,090	1,560,691	4,323,465
PERIOD 5b - Site Restoration																				
Period 5b Direct Decommissioning Activities																				
5b.1.1.1	Demolition of Remaining Site Buildings	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.2	Excavating Water Chlorinator	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.3	Excavating Water Baffle Flume	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.4	Excavating Water Pump House	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.5	Excavating Water Pump House	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.6	Control & Service	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.7	Control Building Area	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.8	Emergency Diesel Generator	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.9	Main & Aux Transformer Foundations	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.10	Mechanical Draft Cooling Towers	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.11	Water Treatment Foundations	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.12	River Water Pump House	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.13	Turbine	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1.14	Turbine Generator Pedestal	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1	TOTAL PERIOD 5b Activity Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.1	TOTAL PERIOD 5b Activity Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Site Characterization Activities																				
5b.1.2	Grade & Landscape site	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1.3	Final report to NRC	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5b.1	Subtotal Period 5b Activity Costs	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Table E  
Three Mile Island Unit 2  
SAFSTOR Decommissioning Cost Estimate  
(Thousands of 2013 Dollars)

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Cost	Transport Cost	Off-Site Processing Cost	LLRW Disposal Cost	Other Costs	Total Contingency	Total Costs	Lic. Term. Costs	Start Fed. Management Costs	Site Restoration Costs	Processed Volume Cu. Feet	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet	Burial / Processed Wt. Lbs.	Craft Manhours	Utility and Contractor Manhours
Period 0b Additional Costs																					
0b.2.1	River Water Pump House Cofferdam	-	214	-	-	-	-	-	32	246	-	-	-	-	-	-	-	-	-	2,110	-
0b.2.2	Concrete Processing	-	496	-	-	-	-	9	439	3,653	-	-	-	-	-	-	-	-	-	3,704	-
0b.2.3	Scrap & Release of scrap materials	-	925	-	60	2,274	-	-	139	1,044	-	-	-	-	-	-	-	-	-	6,952	-
0b.2.4	Scrap & Release of scrap materials	-	4,383	-	-	-	-	-	657	5,040	-	-	-	-	-	-	-	-	-	24,392	-
0b.2.5	Coilcase Tower Demolition	-	6,017	-	60	2,274	-	9	1,343	10,992	3,663	-	-	-	-	-	-	-	-	3,704,137	39,924
0b.2	Subtotal Period 0b Additional Costs	-																			
Period 0b Collateral Costs																					
0b.3.1	Small tool allowance	-	121	-	-	-	-	-	18	139	-	-	-	-	-	-	-	-	-	-	-
0b.3	Subtotal Period 0b Collateral Costs	-																			
Period 0b Period-Dependent Costs																					
0b.4.1	Insurance	-	-	-	-	-	-	206	21	226	-	-	-	-	-	-	-	-	-	-	-
0b.4.2	Property taxes	-	-	-	-	-	-	-	349	2,678	-	-	-	-	-	-	-	-	-	-	-
0b.4.3	Heavy equipment rental	-	2,299	-	-	-	-	-	20	190	-	-	-	-	-	-	-	-	-	-	-
0b.4.4	Heavy equipment fuel	-	-	-	-	-	-	-	48	371	-	-	-	-	-	-	-	-	-	-	-
0b.4.5	Site O&M	-	-	-	-	-	-	-	23	176	-	-	-	-	-	-	-	-	-	-	-
0b.4.6	Security Staff Cost	-	-	-	-	-	-	9,006	1,495	10,502	-	-	-	-	-	-	-	-	-	-	-
0b.4.7	DOC Staff Cost	-	-	-	-	-	-	-	2,877	15,836	-	-	-	-	-	-	-	-	-	-	-
0b.4.8	Utility Staff Cost	-	2,299	-	-	-	-	-	2,877	15,836	-	-	-	-	-	-	-	-	-	-	-
0b.4	Subtotal Period 0b Period-Dependent Costs	-																			
0b.0	TOTAL PERIOD 0b COST	-	18,334	889	60	2,274	-	12,740	5,090	39,386	4,136	-	-	-	-	-	-	-	3,704,137	168,465	138,691
PERIOD 0 TOTALS		-	18,334	889	60	2,274	-	12,740	5,090	39,386	4,136	-	-	-	-	-	-	-	3,704,137	168,465	138,691
TOTAL COST TO DECOMMISSION		24,899	159,867	23,783	22,706	9,744	218,612	590,345	297,168	1,339,945	1,201,047	-	-	156,686	860,391	24,918	1,734	2,214	84,311,460	1,753,802	1,747,465
TOTAL COST TO DECOMMISSION WITH 10.0% CONTINGENCY:																					
TOTAL NRC LICENSE TERMINATION COST IS 94.95% OF:																					
NON-NUCLEAR DEMOLITION COST IS 3.07% OF:																					
TOTAL LOW-LEVEL RADIOACTIVE WASTE VOLUME BURIED (EXCLUDING GTCC):																					
TOTAL GREATER THAN CLASS C RADWASTE VOLUME GENERATED:																					
TOTAL SCRAP METAL REMOVED:																					
TOTAL CRAFT LABOR REQUIREMENTS:																					

End Notes:  
n/a - indicates that this activity not charged as decommissioning expense.  
0 - indicates that this activity performed by decommissioning staff.  
a cell containing "-" indicates a zero value

Enclosure B  
TMI-15-036


*Escalation Analysis for Three Mile Island Unit 2*  
*2013 Site-Specific Decommissioning Cost Estimate*  
February 2015  
(15 pages follow)

**ESCALATION ANALYSIS**

**for**

**THREE MILE ISLAND UNIT 2**

**2013 SITE-SPECIFIC DECOMMISSIONING COST ESTIMATE**



*prepared for*

**FirstEnergy Corporation**


*prepared by*

**TLG Services, Inc.  
Bridgewater, Connecticut**

**February 2015**

**APPROVALS**

**Project Manager**

  
Francis W. Seymore

2/18/15  
Date

**Technical Manager**

  
Geoffrey M. Griffiths

2/18/2015  
Date

**REVISION LOG**

No.	Date	Item Revised	Reason for Revision
0	2-18-2015		Original Issue

## **DECOMMISSIONING COST ESCALATION STUDY**

### **Purpose**

This report presents escalated costs for the estimates of the costs to decommission Three Mile Island Unit 2 (TMI-2) for the selected decommissioning scenarios. The estimates, escalated to the year of expenditure dollars, are designed to provide FirstEnergy Corporation (FirstEnergy), with the information to assess its current decommissioning liability, as it relates to TMI-2.

### **Basis**

This escalation analysis is based upon the recent decommissioning cost analysis performed for Three Mile Island Unit 2.<sup>1</sup> Explanatory information from this report is provided below.

Three decommissioning scenarios were evaluated for Three Mile Island Unit 2 (TMI-2). The scenarios selected are representative of alternatives available to the owners and are defined as follows:

1. **DECON** The adjacent TMI-1 is promptly decommissioned upon the scheduled cessation of operations in 2034. TMI-2 transitions from a Post-Defueling Monitored Storage (PDMS) status to decommissioning in 2040. The decommissioning program for TMI-2 commences after TMI-1 shutdown and is managed independently from the TMI-1 decommissioning effort; license termination of Unit 2 occurs in 2053, approximately 60 years after TMI-2 first entered PDMS.
2. **Delayed DECON** Decommissioning of TMI-2 commences upon the removal of TMI-1's spent fuel from the site in 2051. The decommissioning program for TMI-2 runs concurrently with the TMI-1 decommissioning effort and concludes with the termination of both licenses.
3. **SAFSTOR** TMI-1 is placed into safe-storage with decommissioning deferred 60 years. TMI-2 remains in storage with decommissioning deferred until it can be sequenced with TMI-1. The decommissioning program for TMI-2 runs concurrently with the TMI-1 decommissioning effort and concludes with the termination of both licenses.

---

<sup>1</sup> "Decommissioning Cost Analysis for Three Mile Island Unit 2," Document F07-1676-001, Rev. 0, TLG Services, Inc., December 2014.

The site-specific cost estimate was prepared by TLG Services, Inc. (TLG) in year 2013 (i.e., nominal) dollars. Because the actual decommissioning will not occur for many years and may continue for decades, the nominal-dollar estimates must be escalated into the year of expenditure. That is, we must determine the dollar value of each year's expenditure at the time it is expected to be incurred. Those escalated dollars then provide the basis for financial planning and asset management. Because many of the decommissioning activities occur long in the future, small fluctuations in escalation on the cost side, and investment earnings on the trust balance side, have an exponential impact on the resources required over the long periods of time typically associated with decommissioning scenarios.

In this analysis, TLG reviewed each applicable cost component separately to determine the rate by which each component was expected to escalate annually. Using an accepted aggregation methodology TLG determined the overall average rate the decommissioning costs were expected to escalate annually for each unit and each scenario. The average rates are provided in the results section.

The following narrative describes the methodology used to escalate the schedule of decommissioning expenditures.

### **Background**

TLG developed the cost to decommission TMI-2 in year 2013 dollars; the mathematics to transform those costs to the year in which they will actually be incurred is relatively straightforward. The key to the analysis is selecting the appropriate forecasting indices for each of the major cost components. For that, TLG has relied upon guidance from the Nuclear Regulatory Commission (NRC) and the industry-wide recognized expertise of IHS Global Insight.

The NRC divides its reference costs for decommissioning into categories of labor, energy, and Low Level Radioactive Waste (LLRW) disposal. To provide guidance to operators and regulators and promote uniformity, the NRC periodically reissues NUREG-1307, "Report on Waste Burial Charges." NUREG-1307 is helpful in that it identifies the appropriate indices that should be used to escalate the labor and energy cost components and provides historical changes in low level radioactive waste disposal costs.

TLG also allocates its costs for decommissioning into categories, with the NRC's labor category further subdivided into "labor" and "equipment and materials," and an "other" category added for regulatory fees, property taxes and other unique or one-time expenditures.



Consistent with standards defined in the Financial Accounting Standards Board (FASB) Accounting Standards Codification (ASC), Topic 410-20,<sup>[2]</sup> TLG develops future cash flows by escalating four of the cost categories (labor, equipment and materials, energy and other) with indices provided by IHS Global Insight of Lexington, MA. IHS Global Insight is a privately held company which acquired Global Insight in 2008. The combined company includes well-known businesses such as Cambridge Energy Research Associates (CERA), Jane's Information Group, and IHS Herold; it also includes the former companies known as DRI (Data Resources, Inc.) and WEFA (Wharton Econometric Forecasting Associates). Since Global Insight has no direct index for escalation of low level radioactive waste disposal costs, the escalation rate for LLRW disposal has been established using a broad-based inflation index (CPI, Services) combined with a comparative retrospective LLRW disposal cost escalation analysis.

The timeframe of decommissioning typically exceeds that of the published indices; therefore for years beyond the published index, the inflation factor is determined using a "moving-average" method, averaging the most recent 25 years of indices to determine the future year index. This is a well-accepted methodology for determining longer-term projections and one that has been reviewed and deemed appropriate by IHS Global Insight as well.

### **Assumptions and Methodology**

The base year (2013) costs were extracted from the "Decommissioning Cost Analysis for Three Mile Island Unit 2," issued in December 2014, specifically the Total costs cash flows from Tables 3.1 through 3.3.

The decommissioning cost analysis analyzed the DECON, Delayed DECON and SAFSTOR scenarios. The primary objectives of the TMI-2 decommissioning project are to remove the facility from service, reduce residual radioactivity to levels permitting unrestricted release, restore the site, perform this work safely, and complete the work in a cost effective manner. The selection of a preferred decommissioning alternative is influenced by a number of factors. These factors include the cost of each decommissioning alternative, minimization of occupational radiation exposure, availability of low-level waste disposal facilities, regulatory requirements, and public concerns. In addition, the existing agreement between FirstEnergy and the NRC requires decommissioning to be completed within 60 years of the beginning of the Post-Defueling Monitored Storage period, which began in 1993. The DECON scenario in the cost estimate meets this requirement.

---

<sup>2</sup> Accounting Standards Codification, Topic 410-20, Financial Accounting Standards Board, July 2009. ASC 410-20-55-14 states: "It is expected that uncertainties about the amount and timing of future cash flows can be accommodated by using the expected present value technique and therefore will not prevent the determination of a reasonable estimate of fair value."

Under the agreement with the owners of the adjacent Unit 1, TMI-2 will not begin decommissioning prior to the final shutdown of Unit 1. The Delayed DECON and SAFSTOR methodology coordinates the Unit 1 and Unit 2 decommissioning operations to a limited extent for cost sharing. The DECON methodology assumes that TMI-2 decommissions independent of Unit 1 activities. Contaminated materials are removed, packaged, shipped and disposed of offsite. Clean materials are surveyed for radioactive contamination and released as scrap metal or construction debris. In accordance with 10 CFR 50.82(a)(9), a license termination plan will be developed and submitted for NRC approval at least two years prior to termination of the license. Following the license termination survey and termination of the NRC license, all remaining site structures are removed to three foot below grade elevation, and the subgrade voids backfilled with concrete rubble and structural fill. The site is finally graded to conform to the surrounding area, and native vegetation placed for erosion control.

Under the SAFSTOR methodology, the facility is placed in a safe and stable condition and maintained in that state, allowing levels of radioactivity to decrease through radioactive decay, followed by decontamination and dismantlement. After the safe storage period, the facility will be decontaminated and dismantled to levels that permit license termination, similar to the DECON methodology.

Decommissioning costs were divided into the five escalation categories, for which future rate of inflation factors were established. The five categories are:

<i>Labor</i>	Wages, fringes and benefits for craft, salaries and benefits for professional workers, clerical, administrative, service, contract workers, as well as for certain trades
<i>Equipment &amp; Material</i>	Heavy equipment, specialty tooling, packaging, small tools, construction materials, consumables, rental equipment and temporary construction facilities (trailers)
<i>Energy</i>	Electrical power purchases (as a large industrial customer) to support site operations
<i>LLRW Disposal</i>	Costs for the processing of low-level radioactive waste as well as for the controlled disposal of material that cannot be recovered (released for unrestricted use)
<i>Other</i>	Site operating costs (not already accounted for), for example, taxes, fees, and costs for specialized services and project support activities (may include unspecified contributions from labor, equipment and materials, and

transportation), and payments for one-time disposal services (e.g., Greater-than-Class-C radioactive waste, or GTCC)

The currently projected total costs (in thousands of 2013 dollars) to decommission the nuclear station, with the two scenarios analyzed, are as follows:

DECON	\$1,188,564
Delayed DECON	\$1,177,554
SAFSTOR	\$1,239,065

The costs include the monies anticipated to be spent for operating license termination (radiological remediation) and site restoration activities. The costs are based on several key assumptions in areas of regulation, component characterization, high-level radioactive waste management, low-level radioactive waste disposal, performance uncertainties (contingency) and site remediation and restoration requirements.

The following table reflects the percentage of each cost component relative to the total costs to decommission TMI-2:

Escalation Category	DECON		Delayed DECON		SAFSTOR	
	Costs (Thousands of 2013\$)	% of Total Cost	Costs (Thousands of 2013\$)	% of Total Cost	Costs (Thousands of 2013\$)	% of Total Cost
Labor	671,323	56.5	651,122	55.3	671,870	54.2
Equipment & Material	137,959	11.6	141,727	12.0	153,977	12.4
Energy	18,061	1.5	19,459	1.7	28,227	2.3
LLRW Disposal	258,232	21.7	258,143	21.9	258,157	20.8
Other Items	102,989	8.7	107,103	9.1	126,834	10.2

### Escalation

The following escalation indices were established for each of the five cost categories. The escalation indices for Labor, Equipment and Material, Energy and Other were provided by IHS Global Insight Company via their DataInsight-Web online service. The indices used show the last update as 13 October 2014. Global Insight does not provide historical or projected costs for disposal of radioactive waste. As such, a TLG-developed LLRW Disposal/Recycling index was used in this escalation

analysis. This index is a combination of historical information through 2014 from NRC publications for disposal site rates and projections using the Consumer Price Index, Services information provided by Global Insight as discussed previously.

Forecast data for labor, equipment/ materials, energy, and general inflation were available through 2039. In order to extrapolate beyond the available Global Insight data, TLG calculated a 25-year moving average inflation factor to extend the Global Insight indices through 2095, the end point of the TMI-2 decommissioning scenarios.

### **Index Selection**

The following table identifies the Global Insight forecast data sets used for the four cost categories (exclusive of LLRW disposal). Consistent with the NRC's guidance, TLG escalates the labor component of its decommissioning cost estimates using an Employment Cost Index (ECI) and the energy cost component with a Producer Price Index (PPI).

Use of the Consumer Price Index, Services (CUSASNS) for general services, site operating costs and one-time expenditures is consistent with the intent of the index (the measure of the average change in prices over time of goods and services).

<b>Global Insight Forecast Database</b>	<b>TLG Cost Category</b>
ECI Total Compensation (ECIPCTNS)	Labor Expenditures Inflation
Producer Price Index, Machinery & Equipment (WPIP11)	Equipment/Material Expenditures Inflation
Producer Price Index, Fuels and Related Products and Power (WPIP05)	Energy Expenditures Inflation
Consumer Price Index, Services (CUSASNS)	Other Items Expenditures Inflation
TLG-Developed LLRW Disposal Price Index [Historical data based upon Barnwell published tariffs; forecast data based upon the Consumer Price Index, Services (CUSASNS) plus 1% additional to reflect above-inflation increases observed at the Barnwell burial site]	LLRW Disposal / Recycling

## **Labor**

The decommissioning process is labor intensive, with labor representing more than half of the total cost. The estimates for TMI-2 include the cost of the craft labor performing field activities, the field supervision and support services, project management, administration, security, and costs for specialty contractors. The Employment Cost Index (ECI) is a measure of changes in labor costs. It is one of the principal economic indicators used by the Federal Reserve Bank. The index shows changes in wages and salaries and benefit costs, as well as changes in total compensation. The ECIPCTNS index, provided by Global Insight, is a forecast of future changes in the cost of labor, defined as compensation per employee hour worked. The self-employed, owners-managers, and unpaid family workers are excluded from coverage. The ECI is designed as a fixed-weight index at the occupational level, thus eliminating the effects of employment shifts among occupations. Both components of compensation, wages/salaries, and benefits, are covered.

In addition to TLG's judgment, IHS Global Insight has confirmed that the selected index is appropriate to use in determining the rate at which the labor costs will escalate over time.

## **Equipment and Material**

Equipment and material costs in the decommissioning estimates include small tools and consumables as well as the heavy construction equipment involved in the dismantling, demolition and movement of materials around the site. The Producer Price Indexes (PPI) measures monthly average changes in selling prices received by domestic producers for their output. Most of the information used in the PPI is obtained by sampling of industries in the mining and manufacturing sectors of the economy. The indexes reflect price trends for a constant set of goods and services representing the total output of an industry.

TLG uses a broad-based escalation index, the Producer Price Index for Machinery and Equipment (WPIP11).

In addition to TLG's judgment, IHS Global Insight has confirmed that the selected index is appropriate to use in determining the rate at which the equipment and material costs will escalate over time.

## **Energy**

Energy costs in the decommissioning estimate include only direct energy purchases, primarily electric power and fuel oil for heating. TLG uses a broad-based power escalation index, the Producer Price Index for Fuels and Related Products and Power (WPIP05). While the WPIP05 index has some volatility (since it tracks in

part the price of oil), the cost of energy in the decommissioning estimates is a small percentage and therefore has little effect on the overall escalation rate for decommissioning cost.

In addition to TLG's judgment, IHS Global Insight has confirmed that the selected index is appropriate to use in determining the rate at which energy costs will escalate over time.

### **Low Level Radioactive Waste Disposal**

The inflation index used for radioactive waste burial costs is the Global Insight Consumer Price Index, Services (CUSASNS), with an additional 1% per year to account for differences observed (over the past 14 years) between low-level waste disposal rates reported in NRC NUREG-1307 documents and general services inflation rate (CUUR0000SAS) reported by the Bureau of Labor Statistics.

### **Other**

"Other" costs in the decommissioning estimates include such items as licensing fees, taxes, special services (for example, a fee for the geologic disposal of GTCC waste), as well as labor-intensive activities such as radiological surveys that include costs for off-site analytical services. Because the "Other" costs contain this variety of cost components, TLG uses a Consumer Price Index to project future expenditures. The CPI, Services index (CUSASNS) measures changes in the prices of goods and services. It is therefore more representative of the non-labor cost elements included in the decommissioning estimates. Accordingly, the use of the CPI for "Other" costs reflects more accurately the cost components with the "Other" category than the use of the "Labor" escalation factor as a proxy.

In addition to TLG's judgment, IHS Global Insight has confirmed that the selected index is appropriate to use in determining the rate at which the "other" costs will escalate over time.

### **Results**

With the proper escalation indices identified, TLG escalated the cost per year for the five escalation categories using the Global Insight index corresponding to that year and escalation category. Tables 1 through 3 provide escalated schedules of annual expenditures for the DECON, Delayed DECON and SAFSTOR scenarios for TMI-2. The schedules detail each of the five escalation categories through to the end of each scenario's decommissioning period for Total Costs, as well as the cost categories of License Termination and Site Restoration.

No discounting of the escalated dollars was performed.

Using the escalated cash flows for each unit, TLG determined the single-value yearly escalation rate which yielded the same sum of escalated dollars for each of the four tables. The rate, referred to as a composite average annual escalation rate, is tabulated for the four decommissioning cost cash flows as follows:

DECON	2.77%
Delayed DECON	2.78%
SAFSTOR	2.85%

In a similar fashion, the composite average annual escalation rates for each of the five escalation categories can be developed. The following table details the composite annual average rates for the three decommissioning scenarios.

Escalation Category	Composite Average Annual Rate (%)		
	DECON	Delayed DECON	SAFSTOR
Labor	2.713	2.707	2.687
Equipment/ & Material	1.146	1.153	1.176
Energy	2.200	2.193	2.149
LLRW Disposal	3.599	3.607	3.632
Other Items	2.628	2.631	2.644
Overall	2.774	2.784	2.853

Similarly, the composite average annual escalation rates for the three cost categories identified in the decommissioning cost estimate can also be developed. The values for the three decommissioning scenarios are provided in the following table.

Escalation Category	Composite Average Annual Rate (%)		
	DECON	Delayed DECON	SAFSTOR
License Termination	2.795	2.805	2.871
Site Restoration	2.331	2.324	2.381
Overall	2.774	2.784	2.853

Three Mile Island Unit 2  
Escalation Analysis

ESCALATION ANALYSIS OF CASH FLOWS

Source Documentation for Estimate: Decommissioning Cost Analysis for Three Mile Island Unit 2  
R07-1676-001 Rev. 0

Table 3.1

Financial Escalation Analysis-2013 Update-Three Mile Island Unit 2

Unit Identification: DECON

Estimate Issue Year: 2013

Decommissioning Scenario: Decommissioning following Unit 1 Shutdown

Operating Lifetime: Decommissioning following Unit 1 Shutdown

Cost Category	Single Value Escalation % by Major Cost Categories		Total Costs
	Single-value	Escalated	
Cost Category	2013	2013 \$	
Total Costs	2,774%	1,180,954	2,635,592
License Termination Costs	2,789%	1,140,097	2,738,652
Site Restoration Costs	2,531%	38,457	85,938
Labor Costs	1,114%	1,127,865	1,650,466
Equipment & Material Costs	2,200%	18,091	32,500
LLRW Disposal Costs	3,859%	259,232	616,375
Other Costs	2,629%	102,969	227,727

Financial Escalation Analysis-2013 Update-Three Mile Island Unit 2  
DECON Cash Flows by Category - Decommissioning following Unit 1 Shutdown

Year	Labor	Equipment & Materials	Energy	LLRW Disposal	Other	Yearly Totals
2013	2,486	0	224	0	326	3,036
2014	2,538	0	230	0	335	3,103
2015	2,606	0	227	0	344	3,177
2016	2,690	0	229	0	353	3,272
2017	2,788	0	232	0	361	3,381
2018	2,895	0	241	0	371	3,467
2019	2,942	0	247	0	380	3,569
2020	3,036	0	255	0	390	3,681
2021	3,116	0	264	0	399	3,778
2022	3,179	0	274	0	409	3,867
2023	3,295	0	285	0	419	3,999
2024	3,399	0	300	0	432	4,131
2025	3,482	0	312	0	442	4,231
2026	3,572	0	317	0	454	4,338
2027	3,663	0	322	0	466	4,446
2028	3,767	0	327	0	480	4,569
2029	3,852	0	333	0	491	4,670
2030	3,951	0	337	0	505	4,788
2031	4,053	0	343	0	518	4,908
2032	4,169	0	349	0	533	5,045
2033	4,285	0	355	0	546	5,160
2034	4,376	0	362	0	560	5,291
2035	4,491	0	378	0	583	5,429
2036	4,623	0	385	0	607	5,597
2037	4,732	0	391	0	623	5,717
2038	4,858	0	391	0	640	5,886
2039	4,989	0	391	0	640	6,020
2040	5,126	0	391	0	640	6,020
2041	5,269	0	391	0	640	6,020
2042	5,416	0	391	0	640	6,020
2043	5,567	0	391	0	640	6,020
2044	5,722	0	391	0	640	6,020
2045	5,881	0	391	0	640	6,020
2046	6,044	0	391	0	640	6,020
2047	6,211	0	391	0	640	6,020
2048	6,382	0	391	0	640	6,020
2049	6,557	0	391	0	640	6,020
2050	6,736	0	391	0	640	6,020
2051	6,919	0	391	0	640	6,020
2052	7,105	0	391	0	640	6,020
2053	7,295	0	391	0	640	6,020
Totals	1,557,508	201,462	32,500	616,375	227,727	2,835,592

Financial Escalation Analysis-2013 Update-Three Mile Island Unit 2  
DECON Cash Flows by Category - Decommissioning following Unit 1 Shutdown

Year	Labor	Equipment & Materials	Energy	LLRW Disposal	Other	Yearly Totals
2013	2,486	0	224	0	326	3,036
2014	2,538	0	230	0	335	3,103
2015	2,606	0	227	0	344	3,177
2016	2,690	0	229	0	353	3,272
2017	2,788	0	232	0	361	3,381
2018	2,895	0	241	0	371	3,467
2019	2,942	0	247	0	380	3,569
2020	3,036	0	255	0	390	3,681
2021	3,116	0	264	0	399	3,778
2022	3,179	0	274	0	409	3,867
2023	3,295	0	285	0	419	3,999
2024	3,399	0	300	0	432	4,131
2025	3,482	0	312	0	442	4,231
2026	3,572	0	317	0	454	4,338
2027	3,663	0	322	0	466	4,446
2028	3,767	0	327	0	480	4,569
2029	3,852	0	333	0	491	4,670
2030	3,951	0	337	0	505	4,788
2031	4,053	0	343	0	518	4,908
2032	4,169	0	349	0	533	5,045
2033	4,285	0	355	0	546	5,160
2034	4,376	0	362	0	560	5,291
2035	4,491	0	378	0	583	5,429
2036	4,623	0	385	0	607	5,597
2037	4,732	0	391	0	623	5,717
2038	4,858	0	391	0	640	5,886
2039	4,989	0	391	0	640	6,020
2040	5,126	0	391	0	640	6,020
2041	5,269	0	391	0	640	6,020
2042	5,416	0	391	0	640	6,020
2043	5,567	0	391	0	640	6,020
2044	5,722	0	391	0	640	6,020
2045	5,881	0	391	0	640	6,020
2046	6,044	0	391	0	640	6,020
2047	6,211	0	391	0	640	6,020
2048	6,382	0	391	0	640	6,020
2049	6,557	0	391	0	640	6,020
2050	6,736	0	391	0	640	6,020
2051	6,919	0	391	0	640	6,020
2052	7,105	0	391	0	640	6,020
2053	7,295	0	391	0	640	6,020
Totals	1,480,397	183,690	32,167	616,375	226,023	2,738,652

Financial Escalation Analysis-2013 Update-Three Mile Island Unit 2  
DECON Cash Flows by Category - Decommissioning following Unit 1 Shutdown

Year	Labor	Equipment & Materials	Energy	LLRW Disposal	Other	Yearly Totals
2013	0	0	0	0	0	0
2014	0	0	0	0	0	0
2015	0	0	0	0	0	0
2016	0	0	0	0	0	0
2017	0	0	0	0	0	0
2018	0	0	0	0	0	0
2019	0	0	0	0	0	0
2020	0	0	0	0	0	0
2021	0	0	0	0	0	0
2022	0	0	0	0	0	0
2023	0	0	0	0	0	0
2024	0	0	0	0	0	0
2025	0	0	0	0	0	0
2026	0	0	0	0	0	0
2027	0	0	0	0	0	0
2028	0	0	0	0	0	0
2029	0	0	0	0	0	0
2030	0	0	0	0	0	0
2031	0	0	0	0	0	0
2032	0	0	0	0	0	0
2033	0	0	0	0	0	0
2034	0	0	0	0	0	0
2035	0	0	0	0	0	0
2036	0	0	0	0	0	0
2037	0	0	0	0	0	0
2038	0	0	0	0	0	0
2039	0	0	0	0	0	0
2040	0	0	0	0	0	0
2041	0	0	0	0	0	0
2042	0	0	0	0	0	0
2043	0	0	0	0	0	0
2044	0	0	0	0	0	0
2045	0	0	0	0	0	0
2046	0	0	0	0	0	0
2047	0	0	0	0	0	0
2048	0	0	0	0	0	0
2049	0	0	0	0	0	0
2050	0	0	0	0	0	0
2051	0	0	0	0	0	0
2052	0	0	0	0	0	0
2053	0	0	0	0	0	0
Totals	77,112	17,769	353	0	1,704	96,938



Three Mile Island Unit 2  
Escalation Analysis

ESCALATION ANALYSIS OF CASHFLOWS

Source Documentation for Estimate: Decommissioning Cost Analysis for Three Mile Island Unit 2  
Unit Identification: F07-1676-003 Rev. 0  
Table 3.2

Unit Identification: F07-1676-003 Rev. 0  
Estimate Basis Year: 2013  
Decommissioning Scenario: Delayed DECON  
Operating Lifetime: Decommissioning Concurrent with Unit 1 Delayed DECON

Cost Category	Single Value Escalation % by Major Cost Categories		Total Costs	
	2013	2013	2013	2013
Yearly Total	1,172,554	1,172,554	3,340,384	3,340,384
Yearly Total	2,805%	2,805%	3,135,769	3,135,769
Site Restoration Costs	2,324%	2,324%	35,018	105,226
Labor Costs	2,707%	2,707%	851,122	1,726,358
Equipment & Material Costs	1,153%	1,153%	141,727	219,719
Energy Costs	2,182%	2,182%	19,459	38,059
LLRW Disposal Costs	3,807%	3,807%	268,143	986,590
Other Costs	2,831%	2,831%	107,103	286,348

Financial Escalation Analysis-2013 Update-Three Mile Island Unit 2										
Delayed DECON Cash Flows by Category - Decommissioning Concurrent with Unit 1 Delayed DECON										
Year	Labor	Materials	Energy	LLRW Disposal	Other	Yearly Totals	Year	Labor	Materials	Energy
2013	2,486	0	224	0	326	3,036	2013	2,486	0	224
2014	2,538	0	230	0	335	3,103	2014	2,538	0	230
2015	2,608	0	227	0	344	3,177	2015	2,608	0	227
2016	2,690	0	229	0	353	3,272	2016	2,690	0	229
2017	2,768	0	232	0	361	3,361	2017	2,768	0	232
2018	2,855	0	241	0	371	3,467	2018	2,855	0	241
2019	2,942	0	247	0	380	3,569	2019	2,942	0	247
2020	3,036	0	255	0	390	3,681	2020	3,036	0	255
2021	3,116	0	264	0	399	3,779	2021	3,116	0	264
2022	3,204	0	274	0	409	3,887	2022	3,204	0	274
2023	3,295	0	285	0	419	3,999	2023	3,295	0	285
2024	3,399	0	300	0	432	4,131	2024	3,399	0	300
2025	3,482	0	307	0	442	4,231	2025	3,482	0	307
2026	3,572	0	312	0	454	4,338	2026	3,572	0	312
2027	3,663	0	317	0	466	4,446	2027	3,663	0	317
2028	3,767	0	322	0	480	4,569	2028	3,767	0	322
2029	3,852	0	327	0	491	4,670	2029	3,852	0	327
2030	3,951	0	333	0	504	4,780	2030	3,951	0	333
2031	4,052	0	337	0	518	4,897	2031	4,052	0	337
2032	4,156	0	343	0	533	5,045	2032	4,156	0	343
2033	4,265	0	349	0	546	5,160	2033	4,265	0	349
2034	4,379	0	352	0	559	5,290	2034	4,379	0	352
2035	4,498	0	357	0	572	5,427	2035	4,498	0	357
2036	4,622	0	361	0	586	5,569	2036	4,622	0	361
2037	4,751	0	366	0	600	5,717	2037	4,751	0	366
2038	4,885	0	371	0	615	5,871	2038	4,885	0	371
2039	5,024	0	376	0	630	6,030	2039	5,024	0	376
2040	5,168	0	381	0	646	6,195	2040	5,168	0	381
2041	5,317	0	386	0	662	6,365	2041	5,317	0	386
2042	5,471	0	391	0	679	6,541	2042	5,471	0	391
2043	5,630	0	396	0	696	6,722	2043	5,630	0	396
2044	5,794	0	401	0	714	6,909	2044	5,794	0	401
2045	5,963	0	406	0	732	7,101	2045	5,963	0	406
2046	6,137	0	411	0	751	7,299	2046	6,137	0	411
2047	6,316	0	416	0	770	7,502	2047	6,316	0	416
2048	6,500	0	421	0	790	7,711	2048	6,500	0	421
2049	6,689	0	426	0	810	7,925	2049	6,689	0	426
2050	6,883	0	431	0	831	8,145	2050	6,883	0	431
2051	7,082	0	436	0	852	8,370	2051	7,082	0	436
2052	7,286	0	441	0	874	8,600	2052	7,286	0	441
2053	7,495	0	446	0	896	8,836	2053	7,495	0	446
2054	7,709	0	451	0	919	9,079	2054	7,709	0	451
2055	7,928	0	456	0	943	9,327	2055	7,928	0	456
2056	8,152	0	461	0	968	9,580	2056	8,152	0	461
2057	8,381	0	466	0	993	9,839	2057	8,381	0	466
2058	8,615	0	471	0	1,019	10,103	2058	8,615	0	471
2059	8,854	0	476	0	1,045	10,373	2059	8,854	0	476
Totals	1,726,358	0	11,240	0	1,113	1,848,601	Totals	1,726,358	0	11,240

Financial Escalation Analysis-2013 Update-Three Mile Island Unit 2										
Delayed DECON Cash Flows by Category - Decommissioning Concurrent with Unit 1 Delayed DECON										
Year	Labor	Materials	Energy	LLRW Disposal	Other	Yearly Totals	Year	Labor	Materials	Energy
2013	2,486	0	224	0	326	3,036	2013	2,486	0	224
2014	2,538	0	230	0	335	3,103	2014	2,538	0	230
2015	2,608	0	227	0	344	3,177	2015	2,608	0	227
2016	2,690	0	229	0	353	3,272	2016	2,690	0	229
2017	2,768	0	232	0	361	3,361	2017	2,768	0	232
2018	2,855	0	241	0	371	3,467	2018	2,855	0	241
2019	2,942	0	247	0	380	3,569	2019	2,942	0	247
2020	3,036	0	255	0	390	3,681	2020	3,036	0	255
2021	3,116	0	264	0	399	3,779	2021	3,116	0	264
2022	3,204	0	274	0	409	3,887	2022	3,204	0	274
2023	3,295	0	285	0	419	3,999	2023	3,295	0	285
2024	3,399	0	300	0	432	4,131	2024	3,399	0	300
2025	3,482	0	307	0	442	4,231	2025	3,482	0	307
2026	3,572	0	312	0	454	4,338	2026	3,572	0	312
2027	3,663	0	317	0	466	4,446	2027	3,663	0	317
2028	3,767	0	322	0	480	4,569	2028	3,767	0	322
2029	3,852	0	327	0	491	4,670	2029	3,852	0	327
2030	3,951	0	333	0	504	4,780	2030	3,951	0	333
2031	4,052	0	337	0	518	4,897	2031	4,052	0	337
2032	4,156	0	343	0	533	5,045	2032	4,156	0	343
2033	4,265	0	349	0	546	5,160	2033	4,265	0	349
2034	4,379	0	352	0	559	5,290	2034	4,379	0	352
2035	4,498	0	357	0	572	5,427	2035	4,498	0	357
2036	4,622	0	361	0	586	5,569	2036	4,622	0	361
2037	4,751	0	366	0	600	5,717	2037	4,751	0	366
2038	4,885	0	371	0	615	5,871	2038	4,885	0	371
2039	5,024	0	376	0	630	6,030	2039	5,024	0	376
2040	5,168	0	381	0	646	6,195	2040	5,168	0	381
2041	5,317	0	386	0	662	6,365	2041	5,317	0	386
2042	5,471	0	391	0	679	6,541	2042	5,471	0	391
2043	5,630	0	396	0	696	6,722	2043	5,630	0	396
2044	5,794	0	401	0	714	6,909	2044	5,794	0	401
2045	5,963	0	406	0	732	7,101	2045	5,963	0	406
2046	6,137	0	411	0	751	7,299	2046	6,137	0	411
2047	6,316	0	416	0	770	7,502	2047	6,316	0	416
2048	6,500	0	421	0	790	7,711	2048	6,500	0	421
2049	6,689	0	426	0	810	7,925	2049	6,689	0	426
2050	6,883	0	431	0	831	8,145	2050	6,883	0	431
2051	7,082	0	436	0	852	8,370	2051	7,082	0	436
2052	7,286	0	441	0	874	8,600	2052	7,286	0	441
2053	7,495	0	446	0	896	8,836	2053	7,495	0	446
2054	7,709	0	451	0	919	9,079	2054	7,709	0	451
2055	7,928	0	456	0	943	9,327	2055	7,928	0	456
2056	8,152	0	461	0	968	9,580	2056	8,152	0	461
2057	8,381	0	466	0	993	9,839	2057	8,381	0	466
2058	8,615	0	471	0	1,019	10,103	2058	8,615	0	471
2059	8,854	0	476	0	1,045	10,373	2059	8,854	0	476
Totals	1,726,358	0	11,240	0	1,113	1,848,601	Totals	1,726,358	0	11,240

Financial Escalation Analysis-2013 Update-Three Mile Island Unit 2										
Delayed DECON Cash Flows by Category - Decommissioning Concurrent with Unit 1 Delayed DECON										
Year	Labor	Materials Equipment & Supplies	Energy	LLRW Disposal	Other	Yearly Totals				
2013	0	0	0	0	0	0				
2014	0	0	0	0	0	0				
2015	0	0	0	0	0	0				
2016	0	0	0	0	0	0				
2017	0	0	0	0	0	0				
2018	0	0	0	0	0	0				
2019	0	0	0	0	0	0				
2020	0	0	0	0	0	0				
2021	0	0	0	0	0	0				
2022	0	0	0	0	0	0				
2023	0	0	0	0	0	0				
2024	0	0	0	0	0	0				
2025	0	0	0	0	0	0				
2026	0	0	0	0	0	0				
2027	0	0	0	0	0	0				
2028	0	0	0	0	0	0				
2029	0	0	0	0	0	0				
2030	0	0	0	0	0	0				
2031	0	0	0	0	0	0				
2032	0	0	0	0	0	0				
2033	0	0	0	0	0	0				
2034	0	0	0	0	0	0				
2035	0	0	0	0	0	0				
2036	0	0	0	0	0	0				
2037	0	0	0	0	0	0				
2038	0	0	0	0	0	0				
2039	0	0	0	0	0	0				
2040	0	0	0	0	0	0				
2041	0	0	0	0	0	0				
2042	0	0	0	0	0	0				
2043	0	0	0	0	0	0				
2044	0	0	0	0	0	0				
2045	868	0	0	0	0	868				
2046	3,375	0	0	0	0	3,375				
2047	1,356	19	0	0	0	1,375				
2048	331	19	0	0	0	350				
2049	339	19	0	0	0	358				
2050	348	20	0	0	0	368				
2051	358	20	0	0	0	378				
2052	5	0	0	0	0	5				
2053	5	0	0	0	0	5				
2054	5	0	0	0	0	5				
2055	5	0	0	0	0	5				
2056	5	0	0	0	0	5				
2057	6	0	0	0	0	6				
2058	2	0	0	0	0	2				
2059	73,861	18,073	376	0	1,878	94,118				
2060	3,256	784	16	0	4	4,056				
Totals	63,622	18,951	392	0	1,861	105,226				

