

Daniel j. Evans, CHP
 8 White Oak Road
 Ansonia, CT. 06401
 June 25, 2015

Shirley Xu
 Materials Safety Licensing Branch
 Division of Material Safety, States, Tribal and Rulemaking Programs
 Office of Nuclear Material Safety and Safeguards
 Nuclear Regulatory Commission

Subject:
 Request for additional information correspondence dated June 16, 2015

Dear Shirley Xu:

There were four points specified in your correspondence requesting additional information or clarification in relation our application for radioactive material distribution license for the purpose of importing and distributing LUMINOX brand watches. The wristwatches contain radioactive tritium for the purpose of creating a "glow-in-the-dark" watch face.

1. *"Please provide the model numbers you will be distributing and the maximum quantity of byproduct material in each model as required by 10 CFR 32.14(b)(1). Additionally, provide the sealed sources model number used in each watch model number and byproduct activity per hand and per dial for each watch model".*

Information contained in our original application states maximum quantity of byproduct material and distribution of the material in the watch dial. I have included it here again for purpose of clarity.

Byproduct Material	Sealed Source Model Number	Activity/Distribution
Hydrogen -3 (Tritium)	Sealed Gaseous Tritium Light Sources (GTLS); (mb-microtec Models X00/A, X00B, and X00C)	<25 mCi per timepiece 5 mCi per hand 15 mCi per dial

The model numbers for each watch are indicated in the detailed description of each watch as represented in the attachment to this letter. All the models use the sealed sources model numbers indicated in the table above.

2. *"In your response dated May 18, 2015, ADAMS Accession No. ML15138A318, item No. 1, you stated that a description of each watch offered for sale is included in an attachment. There is no attachment to the response letter. 10 CFR 32.14(b)(2) requires the details of construction and design of each product. Please submit the details of construction and design of each individual model of the watches you plan to distribute."*

I noted in our submission that the description of watches was not correctly labeled as an attachment and was instead included in the body of the submittal. A detailed description of each watch is again included here as a formal labeled attachment.

3. *"In the same response letter mentioned above, item No. 2, you stated that the gaseous tritium vial, placed strategically along the watch face and hands, can be verified to have no leakage by visual inspection. 10 CFR 32.14(b)(3) and (d) requires that the method of containment or binding of the byproducts material in the product; and that the byproduct material be properly contained in the product under the most severe conditions that are likely to be encountered in normal use and handling. Please describe the method of containment that will meet the requirements."*

Each individual quantity of tritium gas is contained in an individual miniature glass container and placed strategically along the watch face or hands. The individual 'packets' are constructed of sturdy hardened glass vials. The entire watch face is then protected by a sturdy crystal bezel that resists cracking or scratching as you would naturally expect from a wristwatch. The watches are all verified water-resistant to various depths and are recognized as one of the sturdiest and most rugged wrist watches in the industry.

In the event of an individual failure of a vial, the uptake and corresponding whole body dose to the wearer could be computed as a scholastic exercise and have no relevance related to real world total body burden.

4. *"In your response letter mentioned above, item No. 3, you stated that manufacturer "Luminox" is noted on watch face. 10 CFR 32.14(b)(6) requires that labeling or marking its container with the identification of the manufacturer or initial transferor of the product and the byproduct material in the product."*

Since Plus LLC is the initial transferor, the labeling of the container will need to identify the initial transferor. Please submit a proposed label for the container (e.g. Drawing, imaging)."

PLUS, LLC will apply a label to the packaging container of the watch. The watch itself is clearly labeled as 'LUMINOX'. Please see attachment two for a visual example of the labeling of the package. The labeling of the watch itself can be identified in attachment one.

Sincerely,



Daniel j. Evans, CHP

Reference Docket No. 030-38784

PLUS, LLC Distribution License Application Clarification

Page 4

Attachment 1 - Details and Description of Each Product



PORTRAIT SHEET

SENTRY 0200 SERIES, 43 MM

- A VINTAGE-INSPIRED CUSHION-SHAPED WATCH
- PERFECT TIMEPIECE FOR SPORTING AND OUTDOOR ENTHUSIASTS

Article	Case	Dial	Color of light tubes in darkness				Band/Color
			Bezel	Dial	Dial	Hand	
			1+11H	3,5,7,9H		Hour/Min.	2/4/6/8&10/12
0201.SL	Black	Black/White	SLC3	Orange	Green	Superluminous	Black PU
0201.BO	Black	Black/Black	SLC3	Orange	Ice Blue	Superluminous	Black PU
0215.SL	Black	Black/Red	SLC3	Orange	Green	Superluminous	Black PU

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	43mm
Water Resistance	100 meters, 10 ATM, 330 feet, individually tested
Movement	Ronda 515 HH6
Battery/Battery life	371/45 month
Case	Carbon reinforced PC
Bezel	Carbon reinforced PC, unidirectional turning bezel, at 12h fitted with colored light tube with sapphire crystal
Case back	Carbon reinforced PC
Crystal	Mineral, especially hardened
Crown	316L stainless steel
Height	14,06mm
Weight	60g

Standard band

FP.0200.20 Black PU strap with steel signature brushed buckle, 22mm

Standard Giftbox

GBO.L002 Eyewear signature box 160 x 70 x 40mm, black exterior, grey interior

Manual

GGM.L002.GMT Instruction Manual



PORTRAIT SHEET

ANU 4200 SERIES, 45 MM

- ANU = AUTHORISED FOR NAVY USE
- FIRST LINE GEAR FOR ELITE MARITIME COMMANDOS

Article	Case	Dial	Color of light tubes in darkness					Band/Color
			Bezel	Dial 12H	Dial 1-11H	Hand Hour/Min.	Sec.	
4221	Steel PVD	Black/Gray	Green	Orange	Green	Green	Green	Black PU
4221.CW	Steel PVD	Black/Gray	Green	Orange	Green	Green	Green	Black Nylon

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	45mm
Water Resistance	200 meters, 20 ATM, 660 feet, individually tested
Movement	RONDA 715 Lith HH6
Battery/Battery life	CR2060 / 10 years *
Case	316L stainless steel PVD black with crown protection
Bezel	316L stainless steel, unidirectional turning bezel, at 12h fitted with colored tube with sapphire crystal
Case back	316L stainless steel
Crystal	Sapphire glass, single antireflective coated
Crown	316L stainless steel PVD black, screwed
Height	13mm
Weight	

* Due to the additional weight of the LLTs on the watch hands, battery life may be shorter

Standard band

FP.8800.20	Black PU signature strap with black PVD steel brushed signature buckle, loop-lock, 23 mm
FN.4220.20	Black nylon strap with nylon web and black PVD brushed steel loops, 23 mm

Standard Giftbox

GBO.L001	Giftbox square, dark gray, 140 x 140 x 100 mm
----------	---

Manual

GGM.L002.GMT	Instruction Manual
--------------	--------------------



PORTRAIT SHEET

MODERN MARINER 6250 SERIES, 45MM

- NAUTICAL INSPIRED FEATURES
- 10 YEAR LITHIUM BATTERY
- LEATHER OR BRACELET BAND

Article	Case	Dial	Color of light tubes in darkness				Band/Color	
			Bezel	Dial 12H	Dial 1-11H	Hand Hour/Min. Sec.		
6251	Steel	Black	Ice Blue	Ice Blue	Green	Ice Blue	Ice Blue	Black leather
6251.BO	Steel Black	Black	Ice Blue	Orange	Ice Blue	Ice Blue	Ice Blue	Black leather
6252	Steel	Black	Ice Blue	Ice Blue	Green	Ice Blue	Ice Blue	Steel bracelet
6252.BO	Steel Black	Black	Ice Blue	Orange	Ice Blue	Ice Blue	Ice Blue	Black Steel bracelet
6265	Steel	Black	Ice Blue	Ice Blue	Green	Ice Blue	Ice Blue	Black leather

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	45mm
Water Resistance	200 meters, 20 ATM, 600 feet, individually tested
Movement	Ronda 715 lith HH6
Battery/Battery life	Lithium CR2016
Case	316L stainless steel with crown protection
Bezel	316L stainless steel, unidirectional turning bezel, at 12h fitted with colored light tube with sapphire crystal
Case back	316L stainless steel, screwed
Crystal	Sapphire glass, single antireflective coating
Crown	316L st.steel PVD black screwed
Height	10mm
Weight	98g

Standard band

FE.6250.20Q	Black leather with black stitches, red lining, signature brushed buckle, 24mm
FE.6250.21Q	Black leather with red stitches, red lining, signature brushed buckle, 24mm
FE.6250.22B	Black leather with d'grey stitches, IP black signature brushed buckle, 24mm
FM.L.BRAC.6250	316L solid brushed steel bracelet, folded signature brushed buckle, 24mm
FM.LBRAC.6250.60	316L solid brushed steel bracelet IP black, folded signature brushed buckle, 24mm

Standard Giftbox

GBO.L001	Giftbox square, grey, woven carbon fibre look at top 110 x 110 x 86 mm
----------	--

Manual

GGM.L002	Instruction Manual
----------	--------------------



PORTRAIT SHEET

F-117 NIGHTHAWK™ 6400 SERIES 45 MM

- ORIGINAL F-117 NIGHTHAWK LICENSED BY LOCKHEED MARTIN
- ESPECIALLY DESIGNED FOR US AIR FORCE PILOTS FLYING THE F-117 NIGHTHAWK STEALTH JETS
- THE CASE HAS A DETAILED ENGRAVING OF THE F-117 NIGHTHAWK STEALTH JET
- A LARGER, BOLDER, MORE ANGULAR DESIGN THEN 3400 SERIES

Article	Case	Dial	Color of light tubes in darkness					Band/Color
			Bezel	Dial	Dial	Hand	Sec.	
6402	Steel PVD Black	Black/White	Green	Orange	Green	Green	Green	Steel PVD Black
6402.BO	Steel PVD Black	Black/Black	Ice Blue	Orange	Ice Blue	Ice blue	Ice Blue	Steel PVD Black

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	45mm
Water Resistance	200 meters, 20 ATM, 660 feet, individually tested
Movement	Ronda 715 HH6 LITHIUM
Battery/Battery life	CR2016/10 years
Case	316L stainless steel PVD Black
Bezel	316L stainless steel PVD Black, unidirectional turning bezel, at 12h fitted with colored light tube with sapphire glass crystal
Case back	316L stainless steel PVD black, screwed
Crystal	Sapphire, single antireflective coated
Crown	316L st. steel PVD black screwed
Height	12,38mm
Weight	102g

Standard band

FM.L.BRAC.6400	316L solid stainless steel bracelet with folded signature buckle, all PVD black, 23mm
----------------	---

Standard Giftbox

GBO.L001	Giftbox square, grey, woven carbon fibre look at top 110 x 110 x 86 mm
----------	--

Manual

GGM.L002	Instruction Manual
----------	--------------------



PORTRAIT SHEET

NAVY SEAL COLOMARK 7050 SERIES, 38 MM

Article	Case	Dial	Color of light tubes in darkness					Band/Color
			Bezel	Dial 12H	Dial 1-11H	Hand Hour/Min.	Sec.	
7051	Black	Black/White	Green	Green	Green	Green	Green	Black PU
7051.BO	Black	Black/Black	Ice Blue	Yellow	Ice Blue	Ice Blue	Ice Blue	Black PU
7065	Black	Black/Pink	Ice Blue	Ice Blue	Ice Blue	Green	Green	Black PU
7057.WO	White	White/Silver		Ice Blue	White	White	White	White Silicon

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	38mm
Water Resistance	200 meters, 20 ATM, 660 feet, individually tested
Movement	Ronda 505 HH6
Battery/Battery life	371/56 months
Case*	Carbon reinforced PC
Bezel*	Carbon reinforced PC, unidirectional turning bezel, at 12h fitted with colored light tube with sapphire crystal
Case back*	Carbon reinforced PC Crystal Mineral, especially hardened Crown 316L stainless steel
Height	11,80mm
Weight	39g
*7057.WO	fibreglass polymer reinforced

Standard band

FP.7050.20	Black PU signature strap with steel brushed signature buckle, Loop-lock, 20mm
FP.7050.10	White Silicon signature strap with steel brushed buckle

Standard Giftbox

GBO.L002	Eyewear signature box 160x70x40mm, black exterior, grey interior
----------	--

Manual

GGM.L002.GMT	Instruction Manual
--------------	--------------------



PORTRAIT SHEET

RECON POINT MAN 8820 SERIES, 45 MM

- THIS WATCH IS A SIMPLE AND EFFICIENT NAVIGATION TOOL FOR LAND USE
- IT CAN BE USED TO DETERMINE BEARINGS WHENEVER THE SUN IS VISIBLE
- IT ALSO OFFERS A TACHYMETER SCALED TO MEASURE WALKING SPEEDS
- THE BEZEL'S COMPASS ROSE HELPS TO ESTABLISH THE WEARER'S POSITION AND ORIENTEERING

Article	Case	Dial	Color of light tubes in darkness				Band/Color	
			Bezel	Dial	Dial	Hand		
			12H	1-11H	Hour/Min.	Sec.		
8821.KM	PC Carbon	Black	Yellow	Ice Blue	Yellow	Ice Blue	Yellow	Black PU
8822.MI	PC Carbon	Black	Yellow	Ice Blue	Yellow	Ice Blue	Yellow	Black PU
8823.KM	PC Carbon	Black	Yellow	Ice Blue	Yellow	Ice Blue	Yellow	Nato strap grey
8824.MI	PC Carbon	Black	Yellow	Ice Blue	Yellow	Ice Blue	Yellow	Nato strap grey
8825.KM	PC Carbon	Black	Yellow	Ice Blue	Yellow	Ice Blue	Yellow	Nato strap green
8826.MI	PC Carbon	Black	Yellow	Ice Blue	Yellow	Ice Blue	Yellow	Nato strap green

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	45mm
Water Resistance	200 meters, 20 ATM, 660 feet, individually tested
Movement	Ronda 515 HH6
Battery/Battery life	395/60 months
Case	PC carbon reinforced
Bezel	PC carbon reinforced, unidirectional turning bezel, at 12h 1xYellow LLT protected by metalized sapphire glass window
Case back	316L stainless steel IP black
Crystal	Sapphire, single antireflective coating
Crown	316L, steel, IP black, screwed
Height	13,10mm
Weight	72g

Standard band

FP.3050.20.BPL	23mm, black PU signature strap with steel brushed signature buckle, Loop-lock
FN.3900.80.	2 22mm, grey Nato signature strap with 2 brushed steel loops in front and 1 brushed steel loop in back
FN.3900.60.2	22mm, green Nato signature strap with 2 brushed steel loops in front and 1 brushed steel loop in back
FN.3900.80.3	22mm, grey Nylon signature strap with 2 brushed steel loops
FN.3900.60.3	22mm, green Nylon signature strap with 2 brushed steel loops

Standard Giftbox

GBO.L014	Eyeware pouch for RECON, 170x80x85mm, black
----------	---

Manual

GGM.L002.GMT	Instruction Manual
GGM.L019	Manuel RECON



PORTRAIT SHEET

NAVY SEAL COLORMARK CHRONOGRAPH 3080 SERIES, 44 MM

- THE CRYSTAL IS HARDENED AND TEMPERED, HIGHLY SCRATCH RESISTANT
- CASE, CASE BACK AND BEZEL ARE MADE OF MOLDED CARBON-REINFORCED POLYMER

Article	Case	Dial	Color of light tubes in darkness					Band/Color
			Bezel	Dial 12H	Dial 1-11H	Hand Hour/Min. Sec.		
3081	Black	Black/White	Green	Green	Ice Blue	Ice Blue	Green	Black PU
3081.BO	Black	Black/Black	Ice Blue	Orange	Ice Blue	Ice Blue	Ice Blue	Black PU
3082	Black	Black/White	Green	Green	Ice Blue	Ice Blue	Green	PC/Carbon Bracelet
3082.BO	Black	Black/Black	Ice Blue	Orange	Ice Blue	Ice Blue	Ice Blue	PC/Carbon Bracelet
3083	Black	Black/Blue	Yellow	Yellow	Ice Blue	Ice Blue	Yellow	Black PU
3089	Black	Black/Orange	Orange	Orange	Ice Blue	Yellow	Yellow	Black PU

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	44mm
Water Resistance	200 meters, 20 ATM, 660 feet, individually tested
Movement	Ronda 5030.D
Battery/Battery life	395/54 months
Case	PC carbon reinforced
Bezel	PC carbon reinforced, unidirectional turning bezel, at 12h fitted with colored light tube with sapphire crystal.
Case back	PC carbon reinforced
Crystal	Mineral, especially hardened
Crown	316L stainless steel
Height	14,60mm
Weight	65g

Standard band

FP3050.20	Black PU signature strap with steel brushed signature buckle, loop-lock, 23mm
FP.3050.23BPL	Black PC & 10% carbon reinforced bracelet with IP black signature buckle, 23mm

Standard Giftbox

GBO.L002	Eyewear signature box 160x70x40mm, black exterior, grey interior
----------	--

Manual

GGM.L001	Instruction Manual
GGM.L014	Chrono Instruction Manual



PORTRAIT SHEET

NAVY SEAL COLORMARK 3050 SERIES, 44 MM

Article	Case	Dial	Color of light tubes in darkness					Band/Color
			Bezel	Dial 12H	Dial 1-11H	Hand Hour/Min. Sec.		
3051	Black	Black/White	Green	Green	Blue	Green	Green	Black PU
3051.BO	Black	Black/Ice Blue	Orange	Ice Blue	Ice Blue	Ice Blue	Ice Blue	Black PU
3052	Black	Black/White	Green	Green	Blue	Green	Green	Black Polym.Bracelet
3052.BO	Black	Black/Ice Blue	Orange	Ice Blue	Ice Blue	Ice Blue	Ice Blue	Black Polym. Bracelet
3053	Black	Black/Blue	Yellow	Yellow	Blue	Yellow	Ice Blue	Black PU
3057.WO	White	White/Silver	Ice Blue	Ice Blue	White	White	White	White PU
3059	Black	Black/Orange	Orange	Orange	Yellow	Yellow	Green	Black PU
3067	Black	Black/Green	Ice Blue	Ice Blue	Green	Ice Blue	Green	Black PU

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	44mm
Water Resistance	200 meters, 20 ATM, 660 feet, individually tested
Movement	RONDA 515 HH6
Battery/Battery life	395/60 months
Case	PC carbon reinforced (white case/bezel/case back: PC glass-fibre reinforced)
Bezel	PC carbon reinforced, unidirectional turning bezel, at 12h fitted with colored light tube with sapphire crystal.
Case back	PC carbon reinforced
Crystal	Mineral, especially hardened
Crown	316L stainless steel
Height	13,88mm
Weight	65g

Standard band

FP.3050.20	Black PU signature strap with steel brushed signature buckle, loop-lock, 23mm
FP.3050.10	White PU signature strap with steel brushed signature buckle, loop-lock, 23mm
FP.3050.23BPL	Black Polymer bracelet with IP black signature buckle, 23mm

Standard Giftbox

GBO.L002	Eyewear signature box 160x70 x40mm, black exterior, grey interior
----------	---

Manual

GGM.L002	Instruction Manual
----------	--------------------



PORTRAIT SHEET

ORIGINAL NAVY SEAL 3000 SERIES, 43 MM

Article	Case	Dial	Color of light tubes in darkness					Band/Color
			Bezel	Dial 12H	Dial 1-11H	Hand Hour/Min.	Sec.	
3001	Black	Black/White	Green	Orange	Green	Green	Green	Black PU
3001.BO	Black	Black/ Black	Ice Blue	Yellow	Ice Blue	Ice Blue	Yellow	Black PU
3003	Black	Blue/White	Green	Orange	Green	Green	Green	Black PU

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	43mm
Water Resistance	200 meters, 20 ATM, 660 feet, individually tested
Movement	RONDA 515 HH6
Battery/Battery life	395/60 months
Case	Carbon reinforced PC
Bezel	Carbon reinforced PC, unidirectional turning bezel, at 12h fitted with colored tube with sapphire crystal
Case back	Carbon reinforced PC
Crystal	Mineral, especially hardened
Crown	316L stainless steel
Height	10,97mm
Weight	46g

Standard band

FP.L.DPB	Black PU strap with steel signature buckle, 22mm
FP.3000.21HPL	Black PU strap with steel signature buckle in IP Gun plated, 22mm

Standard Giftbox

GBO.L002	Eyewear signature box 160x70x40mm, black exterior, grey interior
----------	--

Manual

GGM.L002.GMT	Instruction Manual
--------------	--------------------



PORTRAIT SHEET

ATACAMA FIELD CHRONOGRAPH ALARM 1940 SERIES, 45 MM

- ATACAMA DESERT IN CHILE IS ONE OF THE DRIEST AREAS IN THE WORLD
- RUGGED APPEAL TO CATCH THE FEELING OF THIS DESERT
- DISTRESSED LEATHER STRAPS AND ONE BRACELET VERSION

Article	Case	Dial	Color of light tubes in darkness				Band/Color
			Bezel	Dial 12H	Dial 1-11H	Hand Hour/Min. Sec.	
1941	PVD Gun	Black carbon		Orange	Green	Green	Black leather
1941.BO	PVD Black	Black carbon		Orange	Blue	Blue	Black leather
1942	PVD Gun	Black carbon		Orange	Green	Green	Steel bracelet
1943	PVD Gun	Blue		Orange	Green	Green	Grey leather
1945	PVD Black	Black/Brown		Orange	Green	Green	Brown leather
1947	PVD Gun	Ivory/Brown		Orange	Green	Green	D. brown leather

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	45mm
Water Resistance	100 meters, 10 ATM, 330 feet, individually tested
Movement	RONDA 5130.D Chronograph Alarm
Battery/Battery life	395/50 months
Case	316L PVD black or PVD gun
Bezel	
Case back	316L PVD black or PVD gun, screwed, soundbox
Crystal	Sapphire, single antireflective coated
Crown	316L PVD black or PVD Gun, screwed
Height	13mm
Weight	80g

Standard band

FM.L.BRAC.1920.IPH	316L solid steel bracelet PVD Gun plated, with solid signature buckle, 26mm
FE.1920.20H.80RI	black leather, grey stitches, 2 PVD Gun brushed rivets and signature buckle, 26mm
FE.1920.20B.60RI	black leather, dark grey stitches, 2 PVD black brushed rivets and signature buckle, 26mm
FE.1920.71B.60RI	brown leather, d'brown stitches, 2 steel PVD black brushed rivets and signature buckle, 26mm
FE.1920.72H.80RI	dark brown leather, creamy stitches, 2 PVD gun brushed rivets and signature buckle, 26mm
FE.1920.80H.80RI	grey leather, dark grey stitches, 2 PVD gun brushed rivets and signature buckle, 26mm

Standard Giftbox

GBO.L001	Giftbox square, grey woven carbon fibre look at top, size 110 x 110 x 84mm
----------	--

Manual

GGM.L002.GMT	Instruction Manual
GGM.L003	



PORTRAIT SHEET

ATACAMA FIELD DAY DATE 1920 SERIES, 45 MM

- ATACAMA DESERT IN CHILE IS ONE OF THE DRIEST AREAS IN THE WORLD
- RUGGED APPEAL TO CATCH THE FEELING OF THIS DESERT
- DISTRESSED LEATHER STRAPS AND ONE BRACELET VERSION

Article	Case	Dial	Color of light tubes in darkness				Band/Color
			Bezel	Dial 12H	Dial 1-11H	Hand Hour/Min. Sec.	
1921	PVD Gun	Black carbon		Orange	Green	Green	Black leather
1921.BO	PVD Black	Black carbon		Orange	Blue	Blue	Black leather
1922	PVD Gun	Black carbon		Orange	Green	Green	PVD Gun
1923	PVD Gun	Blue		Orange	Green	Green	D. Grey Leather
1925	PVD Black	Black/Brown		Orange	Green	Green	Brown leather
1927	PVD Gun	Ivory/Brown		Orange	Green	Green	D. Brown leather

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	45mm
Water Resistance	200 meters, 20 ATM, 660 feet, individually tested
Movement	RONDA 517 Day-Date, HH6
Battery/Battery life	395/50 months
Case	316L PVD black or PVD gun
Bezel	
Case back	316L stainless steel PVD black or gun, screwed, sapphire crystal
Crystal	Sapphire, single antireflective coated
Crown	316L PVD black or PVD Gun, screwed
Height	13mm
Weight	80g

Standard band

FM.L.BRAC.1920.IPH	316L solid steel bracelet PVD Gun plated, with solid signature buckle, 26mm
FE.1920.20H.80RI	black leather, grey stitches, 2 PVD Gun brushed rivets and signature buckle, 26mm
FE.1920.20B.60RI	black leather, dark grey stitches, 2 PVD black brushed rivets and signature buckle, 26mm
FE.1920.71B.60RI	brown leather, d'brown stitches, 2 steel PVD black brushed rivets and signature buckle, 26mm
FE.1920.72H.80RI	dark brown leather, creamy stitches, 2 PVD Gun brushed rivets and signature buckle, 26mm
FE.1920.80H.80RI	grey leather, dark grey stitches, 2 PVD Gun brushed rivets and signature buckle, 26mm

Standard Giftbox

GBO.L001	Giftbox square, grey woven carbon fibre look at top, size 110 x 110 x 84mm
----------	--

Manual

GGM.L002.GMT	Instruction Manual
--------------	--------------------



PORTRAIT SHEET

FIELD AUTOMATIC DAY DATE 1800 SERIES, 43 MM

- AUTOMATIC DAY-DATE MOVEMENT
- SEE-THROUGH CASE BACKS TO VIEW THE MOVEMENT
- SMOOTH BUFFALO LEATHER STRAPS

Article	Case	Dial	Color of light tubes in darkness				Band/Color
			Bezel	Dial 12H	Dial 1-11H	Hand Hour/Min. Sec.	
1801	Steel	Black		Orange	Green	Green	Brown leather
1801.BO	PVD Black	Black		Yellow	Ice Blue	Ice Blue	Black leather

Main Characteristics

Origin	Swiss Made
Always Visible	Constant glow for up to 25 years in any light condition
Size/Diameter	43mm
Water Resistance	100 meters, 10 ATM, 330 feet, individually tested
Movement	ETA 2878 Automatic Day-Date, HH5
Battery/Battery life	
Case	316L stainless steel or PVD black
Bezel	316L stainless steel or PVD black, fix bezel
Case back	316L stainless steel or PVD black, screwed, sapphire crystal
Crystal	Sapphire, single antireflective coated
Crown	316L stainless steel or PVD black, screwed
Height	13,3mm
Weight	91g

Standard band

FE.1800.20Q	black leather, creamy stitches, steel brushed signature buckle, 23mm
FE.1800.20B	black leather, d'grey stitches, steel brushed signature buckle, 23mm

Standard Giftbox

GBO.L017	Black wooden box, black PU with red oval pillow for watch, size 240 x 140 x 97 mm
----------	---


Manual

GGM.L002.GMT	Instruction Manual
GGM.L013	Automatic Manual

Reference Docket No. 030-38784

PLUS, LLC Distribution License Application Clarification


Attachment 2 – Images of Container with Labeling




Manufacturer brand on one side of container




Initial transferor label on other side of container



Details of initial transferor included in label



Timepiece secured within container





earthsmart
FedEx carbon-neutral
envelope shipping


ORIGIN ID: ZSMA (400) 734-1030
LUIZ MORALES
LUXIM CORPORATION
3542 BASSETT STREET
SANTA CLARA, CA 95054
UNITED STATES US

SHIP DATE: 29JUN15
ACTWT: 1.0 LB MAN
CAD: 0338379/CAFE2807

BILL SENDER

TO **SHIRLEY XU**
U.S. NUCLEAR REGULATORY COMMISSION
MAIL STOP: T0E18
OFFICE OF NMSS
WASHINGTON DC 205550001

INV: REF: DEPT:




WED - 01 JUL AA

FedEx
TRK# 6096 6797 0950
0201

THU - 02 JUL AA
** 2DAY **

SC NSFA

20555
DC-US
IAD



FTD 5030252 30JUN15 COAA 537C1/B566/EE4B

RT **609** 1 16:30 D
FZ 0950 07.02

521C1/B566/6F03
J141214073001UV