

REGULATORY INFORMATION DISTRIBUTION SYSTEM (RIDS)

ACCESSION NBR: 8012020592 DOC. DATE: 80/11/25 NOTARIZED: NO  
 FACIL: 50-269 Oconee Nuclear Station, Unit 1, Duke Power Co.  
 50-270 Oconee Nuclear Station, Unit 2, Duke Power Co.  
 AUTH. NAME: AUTHOR AFFILIATION  
 PARKER, W.O. Duke Power Co.  
 RECIP. NAME: RECIPIENT AFFILIATION  
 DENTON, H.R. Office of Nuclear Reactor Regulation, Director

DOCKET #  
05000269  
 05000270

SUBJECT: Forwards addl info re seismic analysis of spent fuel racks proposed for use in spent fuel pool shared by units. Info. provides simplified calculation of sliding of Westinghouse free-standing racks.

DISTRIBUTION CODE: A001S COPIES RECEIVED: LTR 1 ENCL 1 SIZE: 4  
 TITLE: General Distribution for after Issuance of Operating License

NOTES: M Cunningham: all amends to FSAR & changes to Tech Specs. 05000269  
 AEOD, Ornstein: lcc.  
 M Cunningham: all amends to FSAR & changes to Tech Specs. 05000270  
 AEOD, Ornstein: lcc.

ACTION:	RECIPIENT	COPIES	COPIES		RECIPIENT	COPIES	COPIES	
	ID CODE/NAME		LITR	ENCL	ID CODE/NAME		LITR	ENCL
	REID, R.	04	13	13				
INTERNAL:	D/DIR, HUM	FAC08	1	1	I&E.	06	2	2
	NRC PDR	02	1	1	OELO	11	1	0
	OR ASSESS BR	10	1	0	<u>REG FILE</u>	01	1	1
EXTERNAL:	ACRS	09	16	16	LPDR	03	1	1
	NSIC	05	1	1				

DEC 3 1980

TOTAL NUMBER OF COPIES REQUIRED: LITR 39 ENCL 37  
~~38~~ ~~36~~

L.T.

RECEIVED DISTRIBUTION SERVICES UNIT

DEC 1 AM 11 40

US NRC DISTRIBUTION SERVICES BRANCH

# DUKE POWER COMPANY

POWER BUILDING

422 SOUTH CHURCH STREET, CHARLOTTE, N. C. 28242

WILLIAM O. PARKER, JR.  
VICE PRESIDENT  
STEAM PRODUCTION

November 25, 1980

TELEPHONE: AREA 704  
373-4083

Mr. Harold R. Denton, Director  
Office of Nuclear Reactor Regulation  
U. S. Nuclear Regulatory Commission  
Washington, D. C. 20555

Attention: Mr. R. W. Reid, Chief  
Operating Reactors Branch No. 4


Subject: Oconee Nuclear Station  
Docket Nos. 50-269, -270

Dear Sir:

Please find attached additional information concerning the seismic analysis of the spent fuel racks proposed for use in the spent fuel pool shared by Oconee Units 1 and 2. The attached information provides a simplified calculation of the sliding of the Westinghouse free-standing racks. This calculation, which by its simplification is more conservative than the non-linear analysis, shows a maximum sliding of 0.33 inches for the design seismic event. This result is within 10% of the result obtained by non-linear analysis. Furthermore, a factor of safety for impact of the rack with the wall was determined by the attached calculation to be 3.15.

Duke Power Company considers that the attached information supports the conclusions of the previously submitted non-linear analysis. Both analyses show that although sliding of the racks would occur for the assumptions of a design seismic event and conservative coefficient of friction, the sliding would be minimal and impact with the spent fuel pool wall would not occur.

Very truly yours,



William O. Parker, Jr.

FTP:scs  
Attachment

*Accl  
5/11*

8012020592

*P*

ADDITIONAL INFORMATION FOR NRC REVIEW OF THE  
PROPOSED OCONEE SPENT FUEL RERACK CONCERNING THE SEISMIC ANALYSIS

SIMPLIFIED CALCULATION OF SLIDING OF THE  
WESTINGHOUSE FREE-STANDING RACKS FOR OCONEE UNITS 1 & 2

Description/Basis of Calculation:

The maximum sliding distance of the Westinghouse free-standing fuel rack for Oconee can be obtained by equating the strain energy developed in the fuel rack, in response to the SSE seismic event, to the energy dissipated by friction, during sliding between the fuel rack supports and the pool floor. The maximum strain energy in the fuel rack, produced by the SSE seismic event, can be calculated from given values used in the linear analysis referenced in the original licensing submittal.

Given Information:

Generalized Stiffness:

8x12 Fuel Rack Module  $K_G = 414,000 \text{ lb/in}$

First Mode Frequency:  $f_1 \text{ Horizontal} = 4.6 \text{ Hz}$

Dominant Mode:  $f_1 \text{ Vertical} > 33 \text{ Hz}$

Fuel Rack Dead Weight:

8x12 Module  $W = 169,200 \text{ lbs}$

Distance from Rack to Wall:  $D = 3.3 \text{ in}$

Maximum Acceleration from  
Response Spectra of Pool:

Horizontal @ 4.6 Hz,  $a_H = 174 \text{ in/sec}^2$   
Vertical @ 33 Hz,  $a_V = 0.2 \text{ g's}$

Coefficient of Friction

Minimum Value:  $\mu = 0.2$

Maximum Energy Produced by the SSE Seismic Event:

Maximum Displacement:

$$\begin{aligned} X_{\max} &= a_H/\omega^2 = a_H/(2\pi f_1)^2 \\ &= 174/(2\pi 4.6)^2 = 0.208 \text{ in} \end{aligned}$$

Maximum Strain Energy:

$$\begin{aligned} U_{\max} &= 1/2 K_G X_{\max}^2 \\ &= 1/2 \times 414,000 \times (0.208)^2 = 8960 \text{ in-lbs} \end{aligned}$$

Frictional Energy Dissipated During Sliding:

Minimum Normal Force:

$$\begin{aligned} F_N &= (1-a_V)W \\ &= (1-0.2) 169,200 = 135,400 \text{ lbs} \end{aligned}$$

Frictional Energy Dissipation  
During Sliding:

$$\begin{aligned} E_s &= \mu F_N d \\ &= 0.2 \times 135,400 d = 27,080 d \text{ in-lbs} \end{aligned}$$

Maximum Sliding Distance Caused by SSE Seismic Event:

Maximum Strain Energy = Frictional Energy

$$U_{\max} = E_s$$

Maximum Sliding Distance:

$$\begin{aligned} d &= \frac{U_{\max}}{\mu F_N} \\ &= \frac{8960}{27080} = 0.331 \text{ in} \end{aligned}$$

Factor of Safety:

A factor of safety is defined as the ratio of the maximum acceleration level (necessary to cause impact between the rack and the wall) to the design acceleration level (based on the SSE seismic event).

Frictional Energy Dissipated During Sliding to Wall:

$$E_s = \mu F_N D$$
$$= 0.2 \times 135,400 \times 3.3 = 89,360 \text{ in-lbs}$$

Energy Produced by Seismic Event Necessary to Cause Impact:

Strain Energy = Frictional Energy

$$1/2 K_G X_{\max}^2 = E_s$$

$$X_{\max} = \sqrt{2E_s/K_G}$$

$$= \frac{\sqrt{2 \times 89360}}{\sqrt{414,000}} = 0.657 \text{ in}$$

Maximum Acceleration Level Necessary to Cause Impact:

$$A_{\max} = X_{\max} (2\pi f_1)^2$$

$$= 0.657 (2 \times \pi \times 4.6)^2 = 549 \text{ in/sec}^2$$

Ratio of Maximum Acceleration Level to Design Acceleration Level:

Factor of Safety:

$$R = A_{\max}/a_H$$

$$= 549/174 = 3.15$$

Conclusion:

Based on the above calculations the maximum sliding distance caused by the SSE seismic event is 0.331 inches. The distance between the rack and the wall is 3.3 inches. A seismic event with the maximum acceleration level of 549 in/sec<sup>2</sup> is required before the rack could slide 3.3 inches and impact could occur. The factor of safety or ratio of maximum acceleration level to design acceleration level was calculated. This calculation shows that the Westinghouse free-standing racks are designed with a factor of safety of 3.15.