

# TMI T1R21 SG Tube In-service Inspection NRC Call

Tim Heindl

Steam Generator Program Engineer

November 9, 2015



**Exelon** Generation.

# Agenda

---

- Design Overview of TMI-1 Enhanced Once-Through Steam Generator (EOTSG)
- T1R21 Steam Generator (SG) Inspection Overview
- SG Tube Inspection Discussion Points
- Q&A

## **Acquisition Status:**

“A” OTSG - Acquired 86.0%, Analyzed 82.9%

“B” OTSG - Acquired 96.0%, Analyzed 95.8%

# TMI-1 EOTSG Overview

## Tube Information


- Number of Tubes: 15,597
- Tube Material: Alloy 690TT
- Nominal OD: 0.625 inch
- Nominal Thickness: 0.037 inch
- Tube Length: 673.375 inch

## Support Information

- TSP Material: SA 240 type 410M SS
- TSP Thickness: 1.18"
- TSPs Trefoil broached (15<sup>th</sup> TSP drilled on periphery)
- Tubes hydraulically expanded full length of the TS

## Normal Operating Parameters

- NOP (Primary) = 2,155 psig
- NOPD = 1271 psid
- $T_{\text{Hot}} = 603^{\circ}\text{F}$



# T1R21 Steam Generator Inspections

---

## **Inspection Scope:**

- 100% full-length inspection (bobbin probe)
- 2-Tube Periphery for Loose Parts (combo array probe) TTS to 01S
- Diagnostic Exams and Tube Plugging as needed

## **Other Actions Taken:**

- Revised plant heat-up procedures to equalize temperatures to mitigate wear
- Met with NRC Region I & Site Residents to achieve alignment on inspection scenarios/strategy

# 1. Primary-to-Secondary Leakage

---

**No observable primary-to-secondary leakage (PSL)  
during Cycle 20.**

- RM-A-5/15 monitor PSLR Continuously.
- No observable trends.

## 2. Secondary Side Pressure Tests

---

There were no secondary side pressure tests performed during T1R21.

- A drip or bubble test was not required due to the absence of existing primary-to-secondary leakage.

## 3. EPRI Guideline Exceptions

TMI-1 has not taken any exceptions or deviations from the EPRI SGMP Guidelines.

# 4. Detailed Scope Evaluation

Base Scope Work Description	EOTSG A Scope	EOTSG B Scope	Head (Upper/Lower)	Basis / Notes
100% Full length bobbin coil eddy current examination	15,592	15,533	Upper	<b>Satisfies Technical Specifications</b>
100% Remote visual inspection of tube plugs	5 tubes	64 tubes	Both	<b>Required</b> examination of plugs per EPRI Examination Guidelines (Reference 3)
Remote visual inspection of channel head and tubesheet cladding	Primary Bowls	Primary Bowls	Both	<b>Required</b> exam per Exelon SG Program Procedures.
Array probe examination of periphery tubes (LTS to TSP 01S); Includes a full length bobbin coil examination	901	862	Upper	<b>Diagnostic examination</b> of areas susceptible to loose parts and TSP wear
X-Probe examination of tubes with previous indications; Includes a full length bobbin coil examination	~125	~200	Upper	<b>Diagnostic examination</b> of previous indications. Number may be reduced based on previous indications (ex/ new T-T wear, T-TSP $\geq 25\%$ )
X-probe special interest exams of tubes based on bobbin results.	0	0	Upper	<b>Diagnostic exam</b> of all Bobbin I-Code indications, new DNG indications $\geq 1.0V$ , and other indications as necessary.
MRPC sizing of indications recorded during bobbin/array coil examinations.	As Needed	As Needed	Upper	<b>Contingent activity</b>
Rolled Plug Installation (and required stabilization)	As Needed	As Needed	Both	<b>Contingent activity.</b> Visual inspection of new plugs and verification of plug installation parameters.
Secondary side inspections (SSI)	NONE	NONE	N/A	<b>Contingent activity.</b> SSI and/or FOSAR only used with positive indication of loose parts presence.

- 100% full length exam of both OTSGs with bobbin probe
- 2-tube periphery array combo probe exam from TTS to 01S
- All bobbin “I” codes, PLPs, new DNGs/DNTs  $\geq 1.0V$  examined with array probe
- Deepest 20 TTW indications in both OTSGs examined with array probe and  $\geq$  sample of new and repeat indications for flaw characterization.
- TSP SI Thresholds:
  - New  $\geq 20\%$  TW
  - Repeat  $\geq 25\%$  TW
  - Growth  $\geq \Delta 12\%$  TW
- No expansion criteria due to 100% base scope exam.


# 5. Summary of Inspection Results

---


	Tube-to-Tube Wear		TSP Wear	
	A	B	A	B
Number of New	6	6	2023	2132
Number of Repeat	105	276	2502	3282
Total Indications	111	282	4525	5414
Avg. Growth Rate	0.19%/EFPY	0.31%/EFPY	0.54%/EFPY	0.83%/EFPY
95 <sup>th</sup> Percentile	1.06%/EFPY	1.06%/EFPY	3.17%/EFPY	4.23%/EFPY
Largest New	10%	10%	33%	35%
Largest Repeat	20%	17%	24%	64%
Location of Largest Flaw	70-100	22-63	137-1	2-4



# “A” OTSG TSP Wear Distribution



# “B” OTSG TSP Wear Distribution



## 6. Repair/Plugging Plans

---

- All tubes repaired will be mechanically roll plugged and stabilized in accordance with stabilization criteria.
- All tubes with indications  $\geq 40\%$  through-wall (TW) will be plugged per Tech Specs.
- A total of 25 tubes are currently  $\geq 40\%$  the Tech Spec Plugging Limit.
- The team has developed a base plugging strategy which provides a 99% POS in the W-axis.

## 7. In-situ Pressure Test / Tube Pulls

---

**There are currently zero indications that exceed the Condition Monitoring limit (e.g., no in situ pressure testing is required).**

## 8. Loose Parts

---

- Inspections performed to detect loose parts:
  - Two (2) tube periphery with array probe – Approximately 902 tubes/SG
- Loose parts detected to date:
  - NONE
- Loose parts removal plan/damage:
  - N/A – No loose parts to date

## 9. Secondary Inspections/Maintenance

- No secondary inspections or maintenance planned for T1R21 steam generator inspections
- Perform sludge mapping with ECT

# 10. Unexpected or Unusual Results

---

**There are no unexpected or unusual results from the T1R21 eddy current inspections.**

➤ **T1R20 Operational Assessment Prediction:**

- Median deepest projected indication is 69% TW
- Upper 95<sup>th</sup> value, max projected depth is 77% TW
- Number of New Flaws Predicted: 3,000 in B OTSG

➤ **Results of the T1R21 inspection are within the previous OA projections and bounded by T1R20 results.**

# 11. Schedule

---

- “A” OTSG – Acquired 86.0%, Analyzed 82.9%
- “B” OTSG – Acquired 96.0%, Analyzed 95.8%
- Expected to complete eddy current inspections 11/10 @ 02:00
- Tube Plugging (as needed) window is 11/10/15 – 11/13/15