

INSTRUCTION SHEET

COMAR 26.12.01.01

Title: Regulations for the Control of Ionizing Radiation (1994)

SUPPLEMENT No. 28

---

Instructions: Supplement 28 to the document "Regulations for the Control of Ionizing Radiation (1994)" includes the following pages (all pages are inclusive):

<u>Remove Pages</u>	<u>Insert Pages (future)</u>
Cover Sheet	Cover Sheet
xiii through xiv	xiii through xiv
A1 through A2	A1 through A2
A5 through A8	A5 through A8
A11 through A12	A11 through A12
C24-1 through C24-2	C24-1 through C24-2
C51-2 through C52	C51-2 through C52
D111 through D112	D111 through D112
E7 through E8	E7 through E8
E13 through E16	E13 through E16
T1 through T10	T1 through T10
T13 through T32	T13 through T32 (24 pages)
T39 through T40	T39 through T40 (4 pages)
T45 through T46	T45 through T46
T49 through T50	T49 through T50
T53 through T56	T53 through T56
V5 through V6	V5 through V6
V11 through V14	V11 through V14
V27 through V28	V27 through V28
V31 through V32	V31 through V32

Verify to make certain that you have the pages listed above.

INQUIRIES TO: Michael Kurman  
Radiological Health Program  
Maryland Department of the Environment  
1800 Washington Boulevard  
Baltimore, MD 21230

Telephone: (410) 537-3208

E-mail: [michael.kurman@maryland.gov](mailto:michael.kurman@maryland.gov)




## Code of Maryland Regulations 26.12.01.01

Adopted: September 9, 1995

Effective: October 9, 1995

Supplement 1 – Effective: December 16, 1996	Supplement 15 – Effective: December 17, 2007
Supplement 2 – Effective: November 3, 1997	Supplement 16 – Effective: June 15, 2009
Supplement 3 – Effective: June 29, 1998	Supplement 17 – Effective: June 15, 2009
Supplement 4 – Effective: December 28, 1998	Supplement 18 – Effective: November 15, 2010
Supplement 5 – Effective: June 14, 1999	Supplement 19 – Effective: November 15, 2010
Supplement 6 – Effective: February 7, 2000	Supplement 20 – Effective: September 19, 2011
Supplement 7 – Effective: April 1, 2002	Supplement 21 – Effective: August 6, 2012
Supplement 8 – Effective: October 13, 2003	Supplement 22 – Effective: October 29, 2012
Supplement 9 – Effective: October 27, 2003	Supplement 23 – Effective: January 6, 2014
Supplement 10 – Effective: March 29, 2004	Supplement 24 – Effective: September 15, 2014
Supplement 11 – Effective: June 7, 2004	Supplement 25 – Effective: June 22, 2015
Supplement 12 – Effective: June 20, 2005	Supplement 26 – Effective: September 14, 2015
Supplement 13 – Effective: December 8, 2005	Supplement 27 – Effective: October 26, 2015
Supplement 14 – Effective: October 9, 2006	Supplement 28

### **REGULATIONS FOR THE CONTROL OF IONIZING RADIATION (1994)**



RADIOLOGICAL HEALTH PROGRAM  
AIR AND RADIATION MANAGEMENT ADMINISTRATION  
MARYLAND DEPARTMENT OF THE ENVIRONMENT  
1800 WASHINGTON BOULEVARD  
BALTIMORE, MARYLAND 21230



<u>Section T.91</u>	<u>Records</u> .....	<u>T16</u>
Section T.97	Advance Notification of Shipment of Irradiated Reactor Fuel and Nuclear Waste ....	T16-1

**Quality Assurance**

Section T.101	Quality Assurance Requirements .....	T18
Section T.103	Quality Assurance Organization .....	T19
Section T.105	Quality Assurance Program.....	T20
<u>Section T.106</u>	<u>Changes to Quality Assurance Program</u> .....	<u>T21</u>
Section T.127	Handling, Storage and Shipping Control.....	T21-1
Section T.129	Inspection, Test and Operating Status.....	T21-1
Section T.131	Nonconforming Materials, Parts, or Components .....	T21-1
Section T.133	Corrective Action .....	T22
Section T.135	Quality Assurance Records .....	T22
Section T.137	Audits .....	T22

**Appendix**

Appendix A	Determination of A1 and A2 .....	T23
------------	----------------------------------	-----

**PART V – PHYSICAL PROTECTION OF CATEGORY 1 AND CATEGORY 2 QUANTITIES OF RADIOACTIVE MATERIAL**

**General Provisions**

Section V.1	Purpose.....	V1
Section V.3	Scope .....	V1
Section V.5	Definitions.....	V1
Section V.11	Specific Exemptions.....	V3

**Background Investigations and Access Authorization Program**

Section V.21	Personnel Access Authorization Requirements for Category 1 or Category 2 Quantities of Radioactive Material.....	V4
Section V.23	Access Authorization Program Requirements.....	V5
Section V.25	Background Investigations .....	V9
Section V.27	Requirements for Criminal History Records Checks of Individuals Granted Unescorted Access to Category 1 or Category 2 Quantities of Radioactive Material.....	V11
Section V.29	Relief from Fingerprinting, Identification, and Criminal History Records Checks and Other Elements of Background Investigations for Designated Categories of Individuals Permitted Unescorted Access to Certain Radioactive Materials .....	V13
Section V.31	Protection of Information .....	V14
Section V.33	Access Authorization Program Review.....	V15

**Physical Protection Requirements During Use**

Section V.41	Security Program.....	V16
Section V.43	General Security Program Requirements .....	V16
Section V.45	LLEA Coordination.....	V20

Section V.47	Security Zones.....	V20
Section V.49	Monitoring, Detection, and Assessment.....	V21
Section V.51	Maintenance and Testing.....	V23
Section V.53	Requirements for Mobile Devices.....	V23
Section V.55	Security Program Review.....	V23
Section V.57	Reporting of Events.....	V24

**Physical Protection in Transit**

Section V.71	Additional Requirements for Transfer of Category 1 and Category 2 Quantities of Radioactive Material .....	V24
Section V.73	Applicability of Physical Protection of Category 1 and Category 2 Quantities of Radioactive Material During Transit.....	V25
Section V.75	Preplanning and Coordination of Shipment of Category 1 or Category 2 Quantities of Radioactive Material .....	V26
Section V.77	Advance Notification of Shipment of Category 1 Quantities of Radioactive Material .....	V27
Section V.79	Requirements for Physical Protection of Category 1 and Category 2 Quantities of Radioactive Material During Shipment.....	V29
Section V.81	Reporting of Events.....	V31

**Records**

Section V.101	Form of Records.....	V33
Section V.103	Record Retention.....	V33

**Enforcement**

Section V.105	Inspections.....	V33
Appendix A	– Category 1 and Category 2 Radioactive Materials.....	V34

**PART W - RADIATION SAFETY REQUIREMENTS FOR WIRELINE SERVICE OPERATIONS AND SUBSURFACE TRACER STUDIES**

Section W.1	Purpose.....	W1
Section W.2	Scope .....	W1
Section W.3	Definitions.....	W1

**Prohibition**

Section W.4	Prohibition.....	W2
-------------	------------------	----

## PART A

### GENERAL PROVISIONS

Sec. A.1 Scope. Except as otherwise specifically provided, these regulations apply to all persons who receive, possess, use, transfer, own, or acquire any source of radiation; provided, however, that nothing in these regulations shall apply to any person to the extent such person is subject to regulation by the U.S. Nuclear Regulatory Commission.<sup>1</sup> This part also gives notice to all persons who knowingly provide to any licensee, applicant, certificate of registration holder, contractor, or subcontractor, components, equipment, materials, or other goods or services, that relate to a licensee's, applicant's or certificate of registration holder's activities subject to these regulations, that they may be individually subject to Maryland Department of the Environment enforcement actions for violation of A.16.

Sec. A.2 Definitions. As used in these regulations, these terms have the definitions set forth below. Additional definitions used only in a certain part will be found in that part.

"A1" means the maximum activity of special form radioactive material permitted in a Type A package.

"A2" means the maximum activity of radioactive material, other than special form radioactive material, permitted in a Type A package. These values are either listed in Appendix A of Part T of these regulations, Table I, or may be derived in accordance with the procedure prescribed in Appendix A of Part T of these regulations.

"Absorbed dose" [See "Dose"]

"Accelerator-produced radioactive material" means any material made radioactive by a particle accelerator.

"Act" means the Annotated Code of Maryland, Environment Article, Title 8 "Radiation."

"Activity" means the rate of disintegration (or transformation) or decay of radioactive material. The units of activity are the becquerel (Bq) and the curie (Ci).

"Adult" means an individual 18 or more years of age.

"Agency" means the Maryland Department of Environment, Radiological Health Program.

"Agreement State" means any State with which the U.S. Nuclear Regulatory Commission or the U.S. Atomic Energy Commission has entered into an effective agreement under subsection 274b. of the Atomic Energy Act of 1954, as amended.

"Airborne radioactive material" means any radioactive material dispersed in the air in the form of dusts, fumes, particulates, mists, vapors, or gases.

"Airborne radioactivity area" means a room, enclosure, or area in which airborne radioactive material exists in concentrations:

(1) In excess of the derived air concentrations (DACs) specified in Appendix B, Table I of Part D of these regulations, or

(2) To such a degree that an individual present in the area without respirator protective equipment could exceed, during the hours an individual is present in a week, an intake of 0.6 percent of the annual limit on intake (ALI) or 12 DAC hours.

"Annually" means ~~either~~ at intervals not to exceed one year ~~(12 consecutive months), or,~~

~~(2) once per year, at about the same time per year (plus or minus one month).~~

<sup>1</sup> Attention is directed to the fact that regulation by the State of source material, byproduct material, and special nuclear material in quantities not sufficient to form a critical mass is subject to the provisions of the agreement between the State and the U.S. Nuclear Regulatory Commission and to 10 CFR Part 150 of the Commission's regulations.

"As low as reasonably achievable (ALARA)" means making every reasonable effort to maintain exposures to radiation as far below the dose limits in these regulations as is practical, consistent with the purpose for which the licensed or registered activity is undertaken, taking into account the state of technology, the economics of improvements in relation to state of technology, the economics of improvements in relation to benefits to the public health and safety, and other societal and socioeconomic considerations, and in relation to utilization of nuclear energy and licensed or registered sources of radiation in the public interest.

"Authorized nuclear pharmacist" means a pharmacist who:

- (1) Meets the requirements in Sections G.55(a) and G.59; or
- (2) Is identified as an authorized nuclear pharmacist on:
  - (i) A specific license issued by the Agreement State or NRC that authorizes medical use or the practice of nuclear pharmacy;
  - (ii) A permit issued by an NRC master material licensee that authorizes medical use or the practice of nuclear pharmacy;
  - (iii) An authorization issued by an Agreement State or NRC broad scope medical use licensee that authorizes medical use or the practice of nuclear pharmacy; or
  - (iv) A permit issued by an NRC master material license broad scope medical use permittee that authorizes medical use or the practice of nuclear pharmacy; or
- (3) Is identified as an authorized nuclear pharmacist by a commercial nuclear pharmacy that has been authorized to identify authorized nuclear pharmacists; or
- (4) Is designated as an authorized nuclear pharmacist in accordance with Sec. C.28(j)(2)(iv).

"Background radiation" means radiation from cosmic sources; naturally occurring radioactive materials, including radon, except as a decay product of source or special nuclear material, and including global fallout as it exists in the environment from the testing of nuclear explosive devices or from past nuclear accidents such as Chernobyl that contribute to background radiation and are not under the control of the licensee. "Background radiation" does not include sources of radiation from radioactive materials or radiation producing machines regulated by the Agency.

"Becquerel" (Bq) means the SI unit of activity. One becquerel is equal to 1 disintegration or transformation per second (S-1).

"Bioassay" means the determination of kinds, quantities or concentrations and, in some cases, the locations of radioactive material in the human body, whether by direct measurement, in vivo counting, or by analysis and evaluation of materials excreted or removed from the human body. For purposes of these regulations, "radiobioassay" is an equivalent term.

"Byproduct material" means:

- (1) Any radioactive material (except special nuclear material) yielded in, or made radioactive by, exposure to the radiation incident to the process of producing or using special nuclear material;
- (2) The tailings or wastes produced by the extraction or concentration of uranium or thorium from ore processed primarily for its source material content, including discrete surface wastes resulting from uranium solution extraction processes. Underground ore bodies depleted by these solution extraction operations do not constitute "byproduct material" within this definition;
- (3)
  - (i) Any discrete source of radium-226 that is produced, extracted, or converted after extraction, before, on, or after August 8, 2005, for use for a commercial, medical, or research activity; or



- (7) "External dose" means that portion of the dose equivalent received from any source of radiation outside the body.
- (8) "Lens dose equivalent (LDE)" applies to the external exposure of the lens of the eye and is taken as the dose equivalent at a tissue depth of 0.3 centimeter (300 mg/cm<sup>2</sup>).
- (9) "Shallow dose equivalent" (H<sub>s</sub>), which applies to the external exposure of the skin of the whole body or the skin of an extremity, is taken as the dose equivalent at a tissue depth of 0.007 centimeter (7 mg/cm<sup>2</sup>).
- (10) "Total effective dose equivalent" (TEDE) means the sum of the effective dose equivalent (for external exposures) and the committed effective dose equivalent (for internal exposures).
- (11) "Total organ dose equivalent" (TODE) means the sum of the deep dose equivalent and the committed dose equivalent to the organ receiving the highest dose as described in D.1107(a)(vi) of this regulation.

"Dose equivalent" [see "Dose"]

"Dose Limits" means the permissible upper bounds of radiation doses established in accordance with this regulation. For purposes of this regulation, "limits" is an equivalent term.

"Effective dose equivalent" [See "Dose"]

"Embryo/fetus" means the developing human organism from conception until the time of birth.

"Entrance or access point" means any opening through which an individual or extremity of an individual could gain access to radiation areas or to licensed or registered radioactive materials. This includes entry or exit portals of sufficient size to permit human entry, irrespective of their intended use.

"Explosive material" means any chemical compound, mixture, or device which produces a substantial instantaneous release of gas and heat spontaneously or by contact with sparks or flame.

"Exposure" means being exposed to ionizing radiation or to radioactive material.

"Exposure" means the quotient of dQ by dm where "dQ" is the absolute value of the total charge of the ions of one sign produced in air when all the electrons (negatrons and positrons) liberated by photons in a volume element of air having mass "dm" are completely stopped in air. The special unit of exposure is the roentgen (R). See A.13 "Units of Exposure and Dose" for SI equivalent.<sup>2</sup>

"Exposure rate" means the exposure per unit of time, such as roentgen per minute and milliroentgen per hour.

"External dose" [See "Dose"]

"Extremity" means hand, elbow, arm below the elbow, foot, knee, and leg below the knee.

"Eye dose equivalent" [See "Dose"]

"Facility" means the location at which one or more sources of radiation are installed or located within one building, vehicle, or under one roof and are under the same administrative control.

"Film badge" [See "Individual monitoring devices"]

"Former U.S. Atomic Energy Commission (AEC) or U.S. Nuclear Regulatory Commission (NRC) licensed facilities" means nuclear reactors, nuclear fuel reprocessing plants, uranium enrichment plants, or critical mass experimental facilities where AEC or NRC licenses have been terminated.

<sup>2</sup> When not underlined as above, the term 'Exposure' has a more general meaning in this regulation.

"General applicable environmental radiation standards" means standards issued by the U.S. Environmental Protection Agency (EPA) under the authority of the Atomic Energy Act of 1954, as amended, that impose limits on radiation exposures or levels, or concentrations or quantities of radioactive material, in the general environment outside the boundaries of locations under the control of persons possessing or using radioactive material.

"Gray" (Gy) means the SI unit of absorbed dose. One gray is equal to an absorbed dose of 1 joule per kilogram (100 rad).

"Hazardous waste" means those wastes designated as hazardous by U.S. Environmental Protection Agency regulations in 40 CFR Part 261.

"Healing arts" means a system of rules or methods of performing particular actions including the systematic application of knowledge or skill in effecting a desired result acquired by experience, study, or observation relating to the science of medical diagnosis, treatment, or surgery.

"High radiation area" means an area, accessible to individuals, in which radiation levels from radiation sources external to the body could result in an individual receiving a dose equivalent in excess of 1 mSv (0.1 rem) in 1 hour at 30 centimeters from the radiation source or 30 centimeters from any surface that the radiation penetrates.

"Human use" means the internal or external administration of radiation or radioactive material to human beings.

"Individual" means any human being.

"Individual monitoring" means the assessment of:

- (1) Dose equivalent (a) by the use of individual monitoring devices or (b) by the use of survey data; or
- (2) Committed effective dose equivalent (a) by bioassay or (b) by determination of the time-weighted air concentrations to which an individual has been exposed, that is, DAC-hours. [See definition of DAC-hours in Part D.]

"Individual monitoring devices" (individual monitoring equipment) means devices accredited by the National Voluntary Laboratory Accreditation Program (NVLAP) designed to be worn by a single individual for the assessment of dose equivalent, such as film badges, thermoluminescence dosimeters (TLDs), ~~pocket ionization chambers, and personal ("lapel") air sampling devices and personal dosimeters capable of recording personnel dose.~~

"Inspection" means an official examination or observation including but not limited to, tests, surveys, and monitoring to determine compliance with rules, regulations, orders, requirements, and conditions of the Agency.

"Interlock" means a device arranged or connected such that the occurrence of an event or condition is required before a second event or condition can occur or continue to occur.

Commented [mdk1]: Moved from A7.

"Internal dose" means that portion of the dose equivalent received from radioactive material taken into the body.

"License" means a license to possess or use radioactive material, including a license amendment, issued by the Agency.

"Licensed material" means radioactive material received, possessed, used, transferred or disposed of under a general or specific license issued by the Agency.

"Licensed practitioner of the healing arts" means a person duly licensed to practice medicine and surgery, osteopathic medicine and surgery, chiropractic, dentistry, podiatry, or veterinary medicine and surgery approved by a health regulatory board of Maryland for the ascertainment, cure, relief, palliation, adjustment, or correction of any human/animal disease, ailment, deformity, or injury.

"Licensee" means any person who is licensed by the Agency in accordance with these regulations.

"Licensing State" means any State with regulations equivalent to the Suggested State Regulations for Control of Radiation relating to, and an effective program for, the regulatory control of NARM and which has been granted final designation by the Conference of Radiation Control Program Directors, Inc.

"Limits" [See "Dose Limits"]

"Lost or missing licensed material" means licensed material whose location is unknown. This definition includes licensed material that has been shipped but has not reached its planned destination and whose location cannot be readily traced in the transportation system.

"Major processor" means a user processing, handling, or manufacturing radioactive material exceeding Type A quantities as unsealed sources or material, or exceeding 4 times Type B quantities as sealed sources, but does not include nuclear medicine programs, universities, industrial radiographers, or small industrial programs. Type A and B quantities are defined in [Section 71.4 of 10 CFR Part 71](#) [Section T.4 of this regulation](#).

"Medical use" means the intentional internal or external administration of radioactive material, or the radiation therefrom, to patients or human research subjects in the practice of the healing arts.

"Member of the public" means any individual except when that individual is receiving an occupational dose.

"Minor" means an individual less than 18 years of age.

"Monitoring" means the measurement of radiation, radioactive material concentrations, surface area activities or quantities of radioactive material and the use of the results of these measurements to evaluate potential exposures and doses. For purposes of these regulations, "radiation monitoring" and "radiation protection monitoring" are equivalent terms.

"NARM" means any naturally occurring or accelerator-produced radioactive material. It does not include byproduct, source, or special nuclear material.

"Natural radioactivity" means radioactivity of naturally occurring nuclides.

**Commented [mdk2]:** Since Supp. 27 the NRC reg. is in our regulations.

“Normal form radioactive material” means radioactive material that has not been demonstrated to qualify as “special form radioactive material.”

"Nuclear Regulatory Commission" (NRC) means the U.S. Nuclear Regulatory Commission or its duly authorized representatives.

"Occupational dose" means the dose received by an individual in the course of employment in which the individual's assigned duties involved exposure to sources of radiation, whether in the possession of the licensee, registrant, or other person. This includes exposure to radiation from registered and unregistered radiation machines or exposure to radioactive material from licensed and unlicensed sources of radiation. Occupational dose does not include dose received from background radiation, from any medical administration the individual has received, from exposure to individuals administered radioactive material and released in accordance with Sec. G.75, from voluntary participation in medical research programs, or as a member of the public.

"Package" means the packaging together with its radioactive contents as presented for transport.

"Particle accelerator" means any machine capable of accelerating electrons, protons, deuterons, or other charged particles in a vacuum and of discharging the resultant particulate or other radiation into a medium at energies usually in excess of 1 MeV.

"Person" means an individual, receiver, trustee, guardian, personal representative, fiduciary, or representative of any kind and any partnership, firm, association, corporation, or other entity. "Person" includes any public or municipal corporation and any agency, bureau, department, or instrumentality of State or local government and, to the extent authorized by federal law, federal government.

[“Personal dosimeter” \[See “Individual monitoring devices”\]](#)

"Personnel monitoring equipment" [See "Individual monitoring devices"]

"Pharmacist" means an individual licensed by a State or Territory of the United States, the District of Columbia, or the Commonwealth of Puerto Rico to practice pharmacy.

"Physician" means an individual who is authorized under the Maryland Medical Practice Act to practice medicine in this State.

“Positron emission tomography (PET) radionuclide production facility” means a facility operating a cyclotron or accelerator for the purpose of producing PET radionuclides.

“Prescribed dose” means:

- (1) For gamma stereotactic radiosurgery, the total dose as documented in the written directive;
- (2) For teletherapy, the total dose and dose per fraction as documented in the written directive;
- (3) For manual brachytherapy, either the total source strength and exposure time or the total dose, as documented in the written directive; or
- (4) For remote brachytherapy afterloaders, the total dose and dose per fraction as documented in the written directive.

"Source material milling" means any activity that results in the production of byproduct material as defined by definition (2) of byproduct material.

"Source of radiation" means any radioactive material or any device or equipment emitting, or capable of producing, radiation.

"Special form radioactive material" means radioactive material that satisfies the following conditions:

- (1) It is either a single solid piece or is contained in a sealed capsule that can be opened only by destroying the capsule;
- (2) The piece or capsule has at least one dimension not less than 5 mm (0.2 in); and
- (3) ~~It~~ satisfies the requirements of 10 CFR 71.75. A special form encapsulation designed in accordance with the requirements of 10 CFR 71.4 in effect on June 30, 1983 (see 10 CFR Part 71, revised as of January 1, 1983), and constructed before July 1, 1985; ~~and~~ a special form encapsulation designed in accordance with the requirements of 10 CFR 71.4 in effect on March 31, 1996 (see 10 CFR Part 71, revised as of January 1, 1983), and constructed before April 1, 1998; and special form material that was successfully tested before September 10, 2015 in accordance with the requirements of 10 CFR 71.75(d) in effect before September 10, 2015 may continue to be used. Any other special form encapsulation must meet the specifications of this definition.

**Commented [mdk3]:** RATS 2015-3, 10 CFR 71.4 Definition of Special form radioactive material

"Special nuclear material" means:

- (1) Plutonium, uranium-233, uranium enriched in the isotope 233 or in the isotope 235, and any other material that the U.S. Nuclear Regulatory Commission, pursuant to the provisions of section 51 of the Atomic Energy Act of 1954, as amended, determines to be special nuclear material, but does not include source material; or,
- (2) Any material artificially enriched by any of the foregoing but does not include source material.

"Special nuclear material in quantities not sufficient to form a critical mass" means uranium enriched in the isotope U-235 in quantities not exceeding 350 grams of contained U-235; uranium-233 in quantities not exceeding 200 grams; plutonium in quantities not exceeding 200 grams; or any combination of them in accordance with the following formula: For each kind of special nuclear material, determine the ratio between the quantity of that special nuclear material and the quantity specified above for the same kind of special nuclear material. The sum of such ratios for all of the kinds of special nuclear material in combination shall not exceed 1. For example, the following quantities in combination would not exceed the limitation and are within the formula:

$$\frac{175(\text{grams contained U-235})}{350} + \frac{50(\text{grams U-233})}{200} + \frac{50(\text{grams Pu})}{200} = 1$$

"Survey" means an evaluation of the radiological conditions and potential hazards incident to the production, use, transfer, release, disposal, or presence of sources of radiation. When appropriate, such evaluation includes, but is not limited to, tests, physical examinations, and measurements of levels of radiation or concentrations of radioactive material present.

"Teletherapy" means therapeutic irradiation in which the source of radiation is at a distance from the body.

"Temporary jobsite" means any location where a portable source of radiation is used or stored, other than a location listed in a specific license or registration, for a period of no longer than 365 continuous days.

"Test" means the process of verifying compliance with an applicable regulation.

"These regulations" means all parts of COMAR 26.12 "Radiation Management."

"Total effective dose equivalent" [See "Dose"]

"Total organ dose equivalent" [See "Dose"]

"U.S. Department of Energy" means the Department of Energy established by Public Law 95-91, August 4, 1977, 91 Stat. 565, 42 U.S.C. 7101 et seq., to the extent that the Department exercises functions formerly vested in the U.S. Atomic Energy Commission, its Chairman, members, officers and components and transferred to the U.S. Energy Research and Development Administration and to the Administrator thereof pursuant to sections 104(b), (c) and (d) of the Energy Reorganization Act of 1974 (Public Law 93-438, October 11, 1974, 88 Stat. 1233 to 1237, 42 U.S.C. 5814, effective January 19, 1975) and retransferred to the Secretary of Energy pursuant to section 301(a) of the Department of Energy Organization Act (Public Law 95-91, August 4, 1977, 91 Stat. 565 to 578, 42 U.S.C. 7151, effective October 1, 1977).

"Unrefined and unprocessed ore" means ore in its natural form prior to any processing, such as grinding, roasting, beneficiating, or refining. Processing does not include sieving or encapsulation of ore or preparation of samples for laboratory analysis.

"Unrestricted area" means any area, access to which is not limited by the licensee or registrant.

"Very high radiation area" means an area, accessible to individuals, in which radiation levels could result in an individual receiving an absorbed dose in excess of 5 Gy (500 rad) in 1 hour at 1 meter from a source of radiation or from any surface that the radiation penetrates.<sup>3</sup>

"Waste" means those low-level radioactive wastes containing source, special nuclear, or byproduct material that are acceptable for disposal in a land disposal facility. For the purposes of this definition, low-level radioactive waste means radioactive waste not classified as high-level radioactive waste, transuranic waste, spent nuclear fuel, or byproduct material as defined in paragraphs (2), (3), and (4) of the definition of Byproduct material set forth in this section.

<sup>3</sup> At very high doses received at high dose rates, units of absorbed dose, gray and rad, are appropriate, rather than units of dose equivalent, sievert and rem.

Sec. C.25 General Requirements for the Issuance of Specific Licenses.

- (a) A license application will be approved if the Agency determines that:
- (1) the applicant is qualified by reason of training and experience to use the material in question for the purpose requested in accordance with these regulations in such a manner as to minimize danger to public health and safety or property;
  - (2) the applicant's proposed equipment, facilities, and procedures are adequate to minimize danger to public health and safety or property;
  - (3) the issuance of the license will not be inimical to the health and safety of the public;
  - (4) the applicant satisfies any applicable special requirements in C.26, C.27, C.28, Part E, Part G, or Part W of these regulations;
  - (5) the applicant maintains an office in Maryland
    - (i) which is open for business during normal business hours,
    - (ii) where records are immediately available for inspection,
    - (iii) and where the radioactive material equipment or device will be available for inspection
      - (a) at either the office location, or
      - (b) at a temporary job site convenient to the inspector;
  - (6) the applicant has met the requirements for financial assurance and recordkeeping for decommission specified in C.29;
  - (7) the environmental report, if required by the Agency under C.25(b), is acceptable;
  - (8) the radioactive material being licensed is not an isotope of Cesium for the use or storage in a liquid or water environment; and
  - (9) the applicant has adequately described in the application how facility design and procedures for operation will, in accordance with Section D.1406, minimize, to the extent practicable, the introduction of residual radioactivity into the site, including the subsurface, facilitate eventual decommissioning, and minimize, to the extent practicable, the generation of radioactive waste.
- (b) In the case of an application for a license or amendment to an existing license to receive and possess radioactive material for the conduct of any activity which the Agency determines will significantly affect the quality of the environment, the applicant shall prepare an environmental report. The report shall address the environmental, economic, technical and other benefits against environmental costs considering available alternatives, with any appropriate conditions to protect environmental values. Commencement of construction prior to such conclusion shall be grounds for denial of a license to receive and possess radioactive material in such plant or facility. As used in this paragraph the term "commencement of construction" means any clearing of land, excavation, or other substantial action that would adversely affect the environment of a site. The term does not mean site exploration, necessary roads for site exploration, borings to determine foundation conditions, or other preconstruction monitoring or testing to establish background information related to the suitability of the site or the protection of environmental values.
- (c) Each specific license application shall contain a provision for an emergency plan as specified in C.23.

(d) A specific licensee may not possess devices containing sealed sources, other than hydrogen-3, with a half-life greater than 30 days and in any form other than gas, that have not been used for a period longer than 3 years. When devices containing a shutter are not being used, the shutter must be locked in the closed position. The reporting requirements in Sec. D.1211(f) shall apply.

(e) A specific licensee which possesses devices containing sealed sources shall:

(1) For devices equipped with an “on-off” mechanism and indicator, assure that each device is tested for proper operation of the “on-off” mechanism and indicator at no longer than 6-month intervals; and

(2) Maintain records of the tests required by C.25(e)(1) for a period of 3 years after the next required test of the “on-off” mechanism and indicator is performed or until the sealed source is transferred or disposed of.

(The remainder of this page is blank.)

**Formatted:** List Paragraph, Indent: Left: 0.44", First line: 0", Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.42" + Indent at: 0.67", Tab stops: 0.69", Left



(g) After the certificate is issued, the Agency may conduct an additional review as it determines is necessary to ensure compliance with current regulatory standards. In conducting its review, the Agency will complete its evaluation in accordance with criteria specified in Section C.37. The Agency may request such additional information as it considers necessary to conduct its review and the certificate holder shall provide the information as requested.

(h) For sources or devices containing naturally occurring or accelerator produced radioactive material manufactured prior to November 30, 2007 that are not registered with the Agency under Section C.37, with the NRC under 10 CFR 32.210, or with an Agreement State, and for which the applicant is unable to provide all categories of information specified in Section C.37, the applicant shall provide:

- (1) All available information identified in Section C.37 concerning the source, and, if applicable, the device; and
- (2) Sufficient additional information to demonstrate that there is reasonable assurance that the radiation safety properties of the source or device are adequate to protect health and minimize danger to life and property. Such information shall include a description of the source or device, a description of radiation safety features, the intended use and associated operating experience, and the results of a recent leak test.

(i) Inactivation of Certificates.

(1) A certificate holder who no longer manufactures or initially transfers any of the sealed source(s) or device(s) covered by a particular certificate issued by the Agency shall request inactivation of the registration certificate. Such a request must be made to the Agency by an appropriate method approved by the Agency and must normally be made no later than two years after initial distribution of all of the source(s) or device(s) covered by the certificate has ceased. However, if the certificate holder determines that an initial transfer was in fact the last initial transfer more than two years after that transfer, the certificate holder shall request inactivation of the certificate within 90 days of this determination and briefly describe the circumstances of the delay.

(2) If a distribution license is to be terminated in accordance with Part C of this regulation, the licensee shall request inactivation of its registration certificates associated with that distribution license before the Agency will terminate the license. Such a request for inactivation of certificate(s) must indicate that the license is being terminated and include the associated specific license number.

(3) A specific license to manufacture or initially transfer a source or device covered only by an inactivated certificate no longer authorizes the licensee to initially transfer such sources or devices for use. Servicing of devices must be in accordance with any conditions in the certificate, including in the case of an inactive certificate.

Sec. C.38 Records.

(a) Each person who receives radioactive material through a license issued pursuant to the regulations in this part shall keep records showing the receipt, transfer, and disposal of the radioactive material as follows:

(1) The licensee shall retain each record of receipt of radioactive material as long as the material is possessed and for three years following transfer or disposal of the material.

(2) ~~The licensee who transferred the material shall retain each record of transfer of source or byproduct material until the Department terminates each license that authorizes the activity that is subject to the recordkeeping requirement for three years after each transfer unless a specific requirement in another part of these regulations dictates otherwise.~~

Commented [mdk4]: RATS 2015-4 10 CFR 40.61(a)(2)

(3) The licensee who disposed of the material shall retain each record of disposal of radioactive material until the Department terminates each license that authorizes disposal of the material.

(b) The licensee shall retain each record that is required by the regulations in this Part and Part D or by license condition for the period specified by the appropriate regulation or license condition. If a retention period is not otherwise specified by regulation or license condition, the record must be retained until the Department terminates each license that authorizes the activity that is subject to the recordkeeping requirement.

- (c) (1) Records which must be maintained pursuant to this Part and Part D may be the original or a reproduced copy or microform if such reproduced copy or microform is duly authenticated by authorized personnel and the microform is capable of producing a clear and legible copy after storage for the period specified by Department regulations. The record may also be stored in electronic media with the capability for producing legible, accurate, and complete records during the required retention period. Records such as letters, drawings, and specifications, must include all pertinent information such as stamps, initials, and signatures. The licensee shall maintain adequate safeguards against tampering with and loss of records.
- (2) If there is a conflict between the Department's regulations in this Part and Part D, license condition, or other written Department approval or authorization pertaining to the retention period for the same type of record, the retention period specified in the regulations in this Part and Part D for such records shall apply unless the Department, pursuant to Sec. A(3)(a), has granted a specific exemption from the record retention requirements specified in the regulations in this Part or Part D.
- (d) Prior to license termination, each licensee authorized to possess radioactive material with a half-life greater than 120 days, in an unsealed form, shall forward the following records to the Agency:
- (1) Records of disposal of licensed material made under Secs. D.1002 (including burials authorized before September 21, 1986), D.1003, D.1005, D.1006; and
- (2) Records required by Sec. D.1103(b)(iv).
- (e) If licensed activities are transferred or assigned in accordance with Sec. C.31(b), each licensee authorized to possess radioactive material, with a half-life greater than 120 days, in an unsealed form, shall transfer the following records to the new licensee and the new licensee will be responsible for maintaining these records until the license is terminated:
- (1) Records of disposal of licensed material made under D.1002 (including burials authorized before January 28, 1981), D.1103, D.1105, D.1106; and
- (2) Records required by D.1103(b)(iv).
- (f) Prior to license termination, each licensee shall forward the records required by C.29(f) to the Agency.

### **Transfer of Material**

#### Sec. C.40 Transfer of Material.

- (a) No licensee shall transfer radioactive material except as authorized pursuant to C.40.
- (b) Except as otherwise provided in his license and subject to the provisions of C.40(c) and (d), any licensee may transfer radioactive material:
- (1) to the Agency;<sup>11</sup>
- (2) to the U.S. Department of Energy;
- (3) to any person exempt from these regulations to the extent permitted under such exemption;
- (4) to any person authorized to receive such material under terms of a general license or its equivalent, or a specific license or equivalent licensing document, issued by the Agency, the U.S. Nuclear Regulatory Commission, any Agreement State or any Licensing State, or to any person otherwise authorized to receive such material by the Federal Government or any agency thereof, the Agency, an Agreement State, or a Licensing State; or
- (5) as otherwise authorized by the Agency in writing.

<sup>11</sup> A licensee may transfer material to the Agency only after receiving prior written approval from the Agency.

- (3) Has access to the area restricted for a reason other than to allow isotopes with a half-life of less than 24 hours to decay prior to decontamination.
- ii. An event in which equipment is disabled or fails to function as designed when:
  - (1) The equipment is required by regulation or license condition to prevent releases exceeding regulatory limits, to prevent exposures to radiation and radioactive materials exceeding regulatory limits, or to mitigate the consequences of an accident;
  - (2) The equipment is required to be available and operable when it is disabled or fails to function; and
  - (3) No redundant equipment is available and operable to perform the required safety function.
- iii. An event that requires unplanned medical treatment at a medical facility of an individual with spreadable radioactive contamination on the individual's clothing or body.
- iv. An unplanned fire or explosion damaging any licensed material or any device, container, or equipment containing licensed material when:
  - (1) The quantity of material involved is greater than five times the lowest annual limit on intake specified in Appendix B of Part D; and
  - (2) The damage affects the integrity of the licensed material or its container.
- c. Preparation and submission of reports. Reports made by licensees in response to the requirements of this section must be made as follows:
  - i. Licensees shall make reports required by paragraphs a. and b. of this section by telephone to the Agency. To the extent that the information is available at the time of notification, the information provided in these reports must include:
    - (1) The caller's name and call back number;
    - (2) A description of the event, including date and time;
    - (3) The exact location of the event;
    - (4) The isotopes, quantities, and chemical and physical form of the licensed material involved; and
    - (5) Any personnel radiation exposure data available.
  - ii. **Written report.** Each licensee who makes a report required by paragraph a. or b. of this section shall submit a written follow-up report within 30 days of the initial report. Written reports prepared pursuant to other regulations may be submitted to fulfill this requirement if the reports contain all of the necessary information and the appropriate distribution is made. These reports must be sent to the Agency. The reports must include the following:
    - (1) A description of the event, including the probable cause and the manufacturer and model number (if applicable) of any equipment that failed or malfunctioned;
    - (2) The exact location of the event;
    - (3) The isotopes, quantities, and chemical and physical form of the licensed material involved;

**Commented [mdk5]:** RATS 2015-1 10 CFR 70.50(c)(2)

- (4) Date and time of event;
  - (5) Corrective actions taken or planned and the results of any evaluations or assessments; and
  - (6) The extent of exposure of individuals to radiation or to radioactive materials without identification of individuals by name.
- d. Each specific licensee shall notify the Agency in writing immediately following the filing of a voluntary or involuntary petition for bankruptcy under any Chapter of Title 11 (Bankruptcy) of the United States Code by or against:
- i. The licensee;
  - ii. An entity (as that term is defined in 11 U.S.C. 101(14)) controlling the licensee or listing the license or licensee as property of the estate; or
  - iii. An affiliate (as that term is defined in 11 U.S.C. 101(2)) of the licensee.
- e. The notification specified in D.1211d. shall indicate the bankruptcy court in which the petition for bankruptcy was filed, a copy of the bankruptcy petition, and the date of the filing of the petition.
- f. A specific licensee shall notify the Agency in writing of the possession of a device containing a sealed source, other than hydrogen-3, with a half-life greater than 30 days and in any form other than gas, that has not been used for a period longer than 3 years.

Sec. D.1220 Notification of Failure To Comply or Existence of a Defect and Its Evaluation.

- a. Each individual, corporation, partnership, dedicating entity, or other entity subject to the regulations in this part shall adopt appropriate procedures to--
- i. Evaluate deviations and failures to comply to identify defects and failures to comply associated with substantial safety hazards as soon as practicable, and, except as provided in paragraph (a)(ii) of this section, in all cases within 60 days of discovery, in order to identify a reportable defect or failure to comply that could create a substantial safety hazard, were it to remain uncorrected;
  - ii. Ensure that if an evaluation of an identified deviation or failure to comply potentially associated with a substantial safety hazard cannot be completed within 60 days from discovery of the deviation or failure to comply, an interim report is prepared and submitted to the Department through a director or responsible officer or designated person as discussed in Sec. D.1220(d)(v). The interim report should describe the deviation or failure to comply that is being evaluated and should also state when the evaluation will be completed. This interim report must be submitted in writing within 60 days of discovery of the deviation or failure to comply; and
  - iii. Ensure that a director or responsible officer subject to the regulations of this part is informed as soon as practicable, and, in all cases, within the 5 working days after completion of the evaluation described in Sec. D.1220(a)(i) or Sec. D.1220(a)(ii) if the construction or operation of a facility or activity, or a basic component supplied for such facility or activity--
    - (1) Fails to comply with COMAR 26.12.01.01 Regulations for the Control of Ionizing Radiation (1994), or any applicable rule, order, or license of the Department relating to a substantial safety hazard, or
    - (2) Contains a defect.

## APPENDIX D

### REQUIREMENTS FOR TRANSFER OF LOW-LEVEL RADIOACTIVE WASTE FOR DISPOSAL AT LAND DISPOSAL FACILITIES AND MANIFESTS

For the purpose of Part D of these regulations, the requirements for transfer of low-level radioactive waste for disposal at land disposal facilities and manifests shall be as specified by ~~10 CFR 20.2006 (1998) "Transfer for Disposal and Manifests."~~ Appendix G to 10 CFR Part 20 ("Requirements for Transfers of Low-Level Radioactive Waste Intended for Disposal at Licensed Land Disposal Facilities and Manifests").

Commented [mdk6]: RATS 2015-5 10 CFR Part 20

**APPENDIX E**

**CLASSIFICATION AND CHARACTERISTICS OF LOW-LEVEL  
RADIOACTIVE WASTE**

For the purpose of Part D of these regulations, the classification and characteristics of low-level radioactive waste shall be as specified by COMAR 26.15 "Disposal of Controlled Hazardous Substances--Radioactive Hazardous Substances."

- (6) Guide tubes must be used when moving the source out of the device.
- (7) An exposure head or similar device designed to prevent the source assembly from passing out of the end of the guide tube must be attached to the outermost end of the guide tube during industrial radiography operations.
- (8) The guide tube exposure head connection must be able to withstand the tensile test for control units specified in ANSI N432-1980.
- (9) Source changers must provide a system for ensuring that the source will not be accidentally withdrawn from the changer when connecting or disconnecting the drive cable to or from a source assembly.

(d) All radiographic exposure devices and associated equipment in use after January 10, 1996, must comply with the requirements of this section.

(e) Notwithstanding paragraph (a)(1) of this section, equipment used in industrial radiographic operations need not comply with Sec. 8.9.2(c) of the Endurance Test in American National Standards Institute N432-1980, if the prototype equipment has been tested using a torque value representative of the torque that an individual using the radiography equipment can realistically exert on the lever or crankshaft of the drive mechanism.

#### Sec. E.21 Limits on External Radiation Levels from Storage Containers and Source Changers.

The maximum exposure rate limits for storage containers and source changers are 2 millisieverts (200 millirem) per hour at any exterior surface, and 0.1 millisieverts (10 millirem) per hour at 1 meter from any exterior surface with the sealed source in the shielded position.

#### Sec. E.23 Locking of Radiation Machines, Radiographic Exposure Devices, Storage Containers and Source Changers.

(a) Each radiation machine and radiographic exposure device must have a lock to prevent unauthorized use, or have an outer locked container designed to prevent unauthorized or accidental removal of the sealed source from its shielded position. The radiation machine or exposure device and/or its container must be kept locked (and if a keyed-lock, with the key removed at all times) when not under the direct surveillance of a radiographer or a radiographer's assistant except at permanent radiographic installations as stated in Sec. E.51. In addition, during radiographic operations the sealed source assembly must be secured in the shielded position each time the source is returned to that position.

(b) Each sealed source storage container and source changer must have a lock or outer locked container designed to prevent unauthorized or accidental removal of the sealed source from its shielded position. Storage containers and source changers must be kept locked (and if a keyed-lock, with the key removed at all times) when containing sealed sources except when under the direct surveillance of a radiographer or a radiographer's assistant.

Sec. E.25 Radiation Survey Instruments.

(a) The licensee shall keep sufficient calibrated and operable radiation survey instruments at each location where a radiation machine or radioactive material is present to make the radiation surveys required by this part and by Part D of this regulation. Instrumentation required by this section must be capable of measuring a range from 0.02 millisieverts (2 millirems) per hour through 0.01 sievert (1 rem) per hour.

(b) The licensee shall have each radiation survey instrument required under paragraph (a) of this section calibrated--

(1) At intervals not to exceed ~~36~~ months and after instrument servicing, except for battery changes;

Commented [mdk7]: Relax time interval.

(2) For linear scale instruments, at two points located approximately one-third and two-thirds of full-scale on each scale; for logarithmic scale instruments, at mid-range of each decade, and at two points of at least one decade; and for digital instruments, at 3 points between 0.02 and 10 millisieverts (2 and 1000 millirems) per hour; and

(3) So that an accuracy within plus or minus 20 percent of the calibration source can be demonstrated at each point checked.

(c) The licensee shall maintain records of the results of the instrument calibrations in accordance with Sec. E.65.

Sec. E.27 Leak Testing and Replacement of Sealed Sources.

(a) The replacement of any sealed source fastened to or contained in a radiographic exposure device and leak testing of any sealed source must be performed by persons authorized to do so by the Agency, the NRC or an Agreement State.

(b) The opening, repair, or modification of any sealed source must be performed by persons specifically authorized to do so by the Agency, the NRC or an Agreement State.



- (c) The specific duties and authorities of the RSO include, but are not limited to:
- (1) Establishing and overseeing all operating, emergency, and ALARA procedures as required by Part D of this chapter, and reviewing them regularly to ensure that the procedures in use conform to current Part D procedures, conform to other Agency regulations and to the license conditions;
  - (2) Overseeing and approving all phases of the training program for radiographic personnel, ensuring that appropriate and effective radiation protection practices are taught;
  - (3) Ensuring that required radiation surveys and leak tests are performed and documented in accordance with the regulations, including any corrective measures when levels of radiation exceed established limits;
  - (4) Ensuring that personnel monitoring devices are calibrated and used properly by occupationally-exposed personnel, that records are kept of the monitoring results, and that timely notifications are made as required by Sec. D.1203 of this chapter; and
  - (5) Ensuring that operations are conducted safely and to assume control for instituting corrective actions including stopping of operations when necessary.
- (d) Licensees will have until May 28, 2000 to meet the requirements of paragraph (a) or (b) of this section.

Sec. E.43 Training.

- (a) The licensee may not permit any individual to act as a radiographer until the individual--
- (1) Has received training in the subjects in paragraph (g) of this section, in addition to a minimum of 2 months of on-the-job training, and is certified through a radiographer certification program by a certifying entity that has been approved by the NRC or an Agreement State (an independent organization that would like to be recognized as a certifying entity shall submit its request to the Director, Office of Nuclear Materials Safety and Safeguards, U.S. Nuclear Regulatory Commission, Washington, D.C. 20555-0001), or
  - (2) The licensee may, until May 28, 2000, allow an individual who has not met the requirement of paragraph (a)(1) of this section, to act as a radiographer after the individual has received training in the subjects outlined in paragraph (g) of this section and demonstrated an understanding of these subjects by successful completion of a written examination that was previously submitted to and approved by the Department.

Commented [mdk8]: Moved from E14

(b) In addition, the licensee may not permit any individual to act as a radiographer until the individual--

(1) Has received copies of and instruction in:

(a) The regulations governing industrial radiography contained in Part E of this chapter, or the equivalent regulations of an Agreement State or the NRC;

(b) The regulations governing radiation protection standards and notices, instructions, and reports to workers contained in Parts D and J of this chapter, or the equivalent regulations of the NRC or an Agreement State;

(c) Applicable DOT regulations as referenced in 10 CFR Part 71;

(d) The Agency, NRC or Agreement State license(s) under which the radiographer will perform industrial radiography; and

(e) The licensee's operating and emergency procedures.

(2) Has demonstrated understanding of the licensee's license and operating and emergency procedures by successful completion of a written or oral examination covering this material.

(3) Has received training in the use of the licensee's radiographic exposure devices, sealed sources, in the daily inspection of devices and associated equipment, and in the use of radiation survey instruments.

(4) Has demonstrated understanding of the use of radiographic exposure devices, sources, survey instruments and associated equipment described in paragraphs (b)(1) and (b)(3) of this section by successful completion of a practical examination covering this material.

(c) The licensee may not permit any individual to act as a radiographer's assistant until the individual--

(1) Has received copies of and instruction in:

(a) The regulations governing industrial radiography contained in Part E of this chapter, or the equivalent regulations of an Agreement State or the NRC;

(b) The regulations governing radiation protection standards and notices, instructions, and reports to workers contained in Parts D and J of this chapter, or the equivalent regulations of the NRC or an Agreement State;

(c) Applicable DOT regulations as referenced in 10 CFR Part 71;

(d) The Agency, NRC or Agreement State license(s) under which the radiographer's assistant will perform industrial radiography; and

(e) The licensee's operating and emergency procedures.

(2) Has developed competence to use, under the personal supervision of the radiographer, the radiographic exposure devices, sealed sources, associated equipment, and radiation survey instruments that the assistant will use; and

(3) Has demonstrated understanding of the instructions provided under (c)(1) of this section by successfully completing a written test on the subjects covered and has demonstrated competence in the use of hardware described in (c)(2) of this section by successful completion of a practical examination on the use of such hardware.

(d) The licensee shall provide annual refresher safety training for each radiographer and radiographer's assistant at intervals not to exceed 12 months.

(e) Except as provided in paragraph (e)(4), the RSO or designee shall conduct an inspection program of the job performance of each radiographer and radiographer's assistant to ensure that the regulations governing industrial radiography contained in Part E of this chapter, or the equivalent regulations of the NRC or an Agreement State, the license requirements, and the applicant's operating and emergency procedures are followed. The inspection program must:

(1) Include observation of the performance of each radiographer and radiographer's assistant during an actual industrial radiographic operation, at intervals not to exceed ~~36~~ months; and

(2) Provide that, if a radiographer or a radiographer's assistant has not participated in an industrial radiographic operation for more than 3 months since the last inspection, the radiographer must demonstrate knowledge of the training requirements of Sec. E.43(b)(3) and the radiographer's assistant must re-demonstrate knowledge of the training requirements of Sec. E.43(c)(2) by a practical examination before these individuals can next participate in a radiographic operation.

(3) The Department may consider alternatives in those situations where the individual serves as both radiographer and RSO.

Commented [mdk9]: Relax time interval.

Commented [mdk10]: Moved from Page E16

(4) In those operations where a single individual serves as both radiographer and RSO, and performs all radiography operations, an inspection program is not required.

(f) The licensee shall maintain records of the above training to include certification documents, written and practical examinations, refresher safety training and inspections of job performance in accordance with Sec. E.79.

(g) The licensee shall include the following subjects required in paragraph (a) of this section:

(1) Fundamentals of radiation safety including--

- (i) Characteristics of x-ray and gamma radiation;
- (ii) Units of radiation dose and quantity of radioactivity;
- (iii) Hazards of exposure to radiation;
- (iv) Levels of radiation from radiation machines and licensed material; and
- (v) Methods of controlling radiation dose (time, distance, and shielding);

(2) Radiation detection instruments including--

- (i) Use, operation, calibration, and limitations of radiation survey instruments;
- (ii) Survey techniques; and
- (iii) Use of personnel monitoring equipment;

(3) Equipment to be used including--

- (i) Operation and control of radiation machines, radiographic exposure equipment, remote handling equipment, and storage containers, including pictures or models of source assemblies (pigtailed);
- (ii) Storage, control, and disposal of licensed material and radiation machines; and

## PART T

### PACKAGING AND TRANSPORTATION OF RADIOACTIVE MATERIAL

#### GENERAL PROVISIONS

Sec. T.1 Purpose and Scope. The regulations in this Part establish requirements for packaging, preparation for shipment, and transportation of radioactive material and apply to any licensee authorized by specific or general license issued by the Agency to receive, possess, use or transfer radioactive material, if the licensee delivers that material to a carrier for transport, transports the material outside the site of usage as specified in its Agency license, or transports that material on public highways. No provision of this Part authorizes possession of licensed material.

Sec. T.2 Reserved.

Sec. T.3 Requirement for License. Except as authorized in a general license or a specific license issued by the Agency pursuant to ~~Section~~ T.17 through T.23 of these regulations, or as exempted in this Part, no licensee may –

- (a) Deliver licensed material to a carrier for transport; or
- (b) Transport licensed material.

Sec. T.4 Definitions. To ensure compatibility with international transportation standards, all limits in this Part are given in terms of dual units: The International System of Units (SI) followed or preceded by U.S. standard or customary units. The U.S. customary units are not exact equivalents, but are rounded to a convenient value, providing a functionally equivalent unit. For the purpose of this Part, either unit may be used. As used in this Part, the following definitions apply:

“A<sub>1</sub>” means the maximum activity of special form radioactive material permitted in a Type A package.

“A<sub>2</sub>” means the maximum activity of radioactive material, other than special form, LSA and SCO material, permitted in a Type A package. These values are either listed in Appendix A of this Part, Table A-1, or may be derived in accordance with the procedures prescribed in Appendix A of this Part.

“Carrier” means a person engaged in the transportation of passengers or property by land or water as a common, contract, or private carrier, or by civil aircraft.

“Certificate holder” means a person who has been issued a certificate of compliance or other package approval by the U.S. Nuclear Regulatory Commission.

“Certificate of Compliance (CoC)” means the certificate issued by the NRC which approves the design of a package for the transportation of radioactive material.

“Consignment” means each shipment of a package or groups of packages or load of radioactive material offered by a shipper for transport.

“Contamination” means the presence of a radioactive substance on a surface in quantities in excess of 0.4 Bq/cm<sup>2</sup> (1X10<sup>-5</sup> μCi/cm<sup>2</sup>) for beta and gamma emitters and low toxicity alpha emitters, or 0.04 Bq/cm<sup>2</sup> (1X10<sup>-6</sup> μCi/cm<sup>2</sup>) for all other alpha emitters.

- (1) “Fixed contamination” means contamination that cannot be removed from a surface during normal conditions of transport.

Commented [mdk11]: 10 CFR 71.4 RATS 2015-3

(2) “Non-fixed contamination” means contamination that can be removed from a surface during normal conditions of transport.

“Conveyance” means:

- (1) “For transport by public highway or rail” any transport vehicle or large freight container;
- (2) “For transport by water” any vessel, or any hold, compartment, or defined deck area of a vessel including any transport vehicle on board the vessel; and
- (3) “For transport by aircraft” any aircraft.

Commented [mdk12]: Moved from T1

“Criticality Safety Index (CSI)” means the dimensionless number (rounded up to the next tenth) assigned to and placed on the label of a fissile material package, to designate the degree of control of accumulation of packages, overpacks or freight containers containing fissile material during transportation. Determination of the criticality safety index is described in T.22, T.23, and 10 CFR 71.59. The criticality safety index for an overpack, freight container, consignment or conveyance containing fissile material packages is the arithmetic sum of the criticality safety indices of all the fissile material packages contained within the overpack, freight container, consignment or conveyance.

Commented [mdk13]: 10 CFR 71.4 RATS 2015-3

“Deuterium” means, for the purposes of T.15 and T.22, deuterium and any deuterium compounds, including heavy water, in which the ratio of deuterium atoms to hydrogen atoms exceeds 1:5000.

“DOT” means the U.S. Department of Transportation.

“Exclusive use” means the sole use by a single consignor of a conveyance for which all initial, intermediate, and final loading and unloading are carried out in accordance with the direction of the consignor or consignee. The consignor and the carrier must ensure that any loading or unloading is performed by personnel having radiological training and resources appropriate for safe handling of the consignment. The consignor must issue specific instructions, in writing, for maintenance of exclusive use shipment controls, and include them with the shipping paper information provided to the carrier by the consignor.

“Fissile material” means the radionuclides plutonium-239, plutonium-241, uranium-233, uranium-235, or any combination of these radionuclides. Fissile material means the fissile nuclides themselves, not material containing fissile nuclides. Unirradiated natural uranium and depleted uranium, and natural uranium or depleted uranium that has been irradiated in thermal reactors only, are not included in this definition. Certain exclusions from fissile material controls are provided in T.15.

“Graphite” means, for the purposes of T.15 and T.22, graphite with a boron equivalent content less than 5 parts per million and density greater than 1.5 grams per cubic centimeter.

“Indian Tribe” means an Indian or Alaska native Tribe, band, nation, pueblo, village, or community that the Secretary of the Interior acknowledges to exist as an Indian Tribe pursuant to the Federally Recognized Indian Tribe List Act of 1994, 25 U.S.C. 479a.

Commented [mdk14]: RATS 2015-5

“Low Specific Activity (LSA) material” means radioactive material with limited specific activity which is nonfissile or is excepted under T.15, and which satisfies the descriptions and limits set forth below. Shielding materials surrounding the LSA material may not be considered in determining the estimated average specific activity of the package contents. The LSA material must be in one of three groups:

Commented [mdk15]: 10 CFR 71.4 RATS 2015-3

- (1) LSA-I.
  - (i) Uranium and thorium ores, concentrates of uranium and thorium ores, and other ores containing naturally occurring radionuclides ~~which are not~~ that are intended to be processed for the use of these radionuclides;

~~(ii)~~ Solid unirradiated natural uranium, ~~or~~ depleted uranium, ~~or~~ natural thorium or their ~~solid or liquid~~ compounds or mixtures, provided they are unirradiated and in solid or liquid form;

Commented [mdk16]: Moved from T2

~~(iii)~~ Radioactive material other than fissile material, for which the  $A_2$  value is unlimited; or

(iv) Other radioactive material in which the activity is distributed throughout and the estimated average specific activity does not exceed 30 times the value for exempt material activity concentration determined in accordance with Appendix A.

(2) LSA-II.

(i) Water with tritium concentration up to 0.8 TBq/liter (20.0 Ci/liter); or

(ii) Other radioactive material in which the activity is distributed throughout, and the estimated average specific activity does not exceed  $10^{-4}$  A<sub>2</sub>/g for solids and gases, and  $10^{-5}$  A<sub>2</sub>/g for liquids.

(3) LSA-III. Solids (e.g., consolidated wastes, activated materials), excluding powders, that satisfy the requirements of 10 CFR 71.77, in which:

(i) The radioactive material is distributed throughout a solid or a collection of solid objects, or is essentially uniformly distributed in a solid compact binding agent (such as concrete, bitumen, ceramic, etc.); ~~and~~

(ii) The radioactive material is relatively insoluble, or it is intrinsically contained in a relatively insoluble material, so that, even under loss of packaging, the loss of radioactive material per package by leaching, when placed in water for 7 days, ~~would~~will not exceed 0.1 A<sub>2</sub>; and

(iii) The estimated average specific activity of the solid, excluding any shielding material, does not exceed  $2 \times 10^{-3}$  A<sub>2</sub>/g.

“Low toxicity alpha emitters” means natural uranium, depleted uranium, natural thorium; uranium-235, uranium-238, thorium-232, thorium-228 or thorium-230 when contained in ores or physical or chemical concentrates or tailings; or alpha emitters with a half-life of less than 10 days.

“Natural thorium” means thorium with the naturally occurring distribution of thorium isotopes (essentially 100 weight percent thorium-232).

“Package” means the packaging together with its radioactive contents as presented for transport.

(1) “Fissile material package” or Type AF package, Type BF package, Type B(U)F package, or Type B(M)F package means a fissile material packaging together with its fissile material contents.

(2) “Type A package” means a Type A packaging together with its radioactive contents. A Type A package is defined and must comply with the DOT regulations in 49 CFR Part 173.

(3) “Type B package” means a Type B packaging together with its radioactive contents. On approval, a Type B package design is designated by the NRC as B(U) unless the package has a maximum normal operating pressure of more than 700 kPa (100 lb/in<sup>2</sup>) gauge or a pressure relief device that would allow the release of radioactive material to the environment under the tests specified in 10 CFR 71.73 (hypothetical accident conditions), in which case it will receive a designation B(M). B(U) refers to the need for unilateral approval of international shipments; B(M) refers to the need for multilateral approval of international shipments. There is no distinction made in how packages with these designations may be used in domestic transportation. To determine their distinction for international transportation, see DOT regulations in 49 CFR Part 173. A Type B package approved before September 6, 1983, was designated only as Type B. Limitations on its use are specified in 10 CFR Part 19.

“Packaging” means the assembly of components necessary to ensure compliance with the packaging requirements of this Part. It may consist of one or more receptacles, absorbent materials, spacing structures, thermal insulation, radiation shielding, and devices for cooling or absorbing mechanical shocks. The vehicle, tie-down system, and auxiliary equipment may be designated as part of the packaging.

“Specific activity of a radionuclide” means the radioactivity of the radionuclide per unit mass of that nuclide. The specific activity of a material in which the radionuclide is essentially uniformly distributed is the radioactivity per unit mass of the material.

“State” means a State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, American Samoa, and the Commonwealth of the Northern Mariana Islands.

“Surface Contaminated Object (SCO)” means a solid object that is not itself classed as radioactive material, but which has radioactive material distributed on any of its surfaces. SCO must be in one of two groups with surface activity not exceeding the following limits:

- (1) SCO-I: A solid object on which:
  - (i) The non-fixed contamination on the accessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 4 Bq/cm<sup>2</sup> (10<sup>-4</sup> microcurie/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 0.4 Bq/cm<sup>2</sup> (10<sup>-5</sup> microcurie/cm<sup>2</sup>) for all other alpha emitters;
  - (ii) The fixed contamination on the accessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 4x10<sup>4</sup> Bq/cm<sup>2</sup> (1.0 microcurie/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 4x10<sup>3</sup> Bq/cm<sup>2</sup> (0.1 microcurie/cm<sup>2</sup>) for all other alpha emitters; and
  - (iii) The non-fixed contamination plus the fixed contamination on the inaccessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 4 x 10<sup>4</sup> Bq/cm<sup>2</sup> (1 microcurie/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 4 x 10<sup>3</sup> Bq/cm<sup>2</sup> (0.1 microcurie/cm<sup>2</sup>) for all other alpha emitters.



(2) SCO-II: A solid object on which the limits for SCO-I are exceeded and on which:

(i) The non-fixed contamination on the accessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 400 Bq/cm<sup>2</sup> (10<sup>-2</sup> microcurie/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters or 40 Bq/cm<sup>2</sup> (10<sup>-3</sup> microcurie/cm<sup>2</sup>) for all other alpha emitters;

(ii) The fixed contamination on the accessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 8 x 10<sup>5</sup> Bq/cm<sup>2</sup> (20 microcuries/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 8 x 10<sup>4</sup> Bq/cm<sup>2</sup> (2 microcuries/cm<sup>2</sup>) for all other alpha emitters; and

(iii) The non-fixed contamination plus the fixed contamination on the inaccessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 8 x 10<sup>5</sup> Bq/cm<sup>2</sup> (20 microcuries/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 8 x 10<sup>4</sup> Bq/cm<sup>2</sup> (2 microcuries/cm<sup>2</sup>) for all other alpha emitters.

“Transport index (TI)” means the dimensionless number (rounded up to the next tenth) placed on the label of a package, to designate the degree of control to be exercised by the carrier during transportation. The transport index is the number determined by multiplying the maximum radiation level in millisievert (mSv) per hour at 1 meter (3.3 ft) from the external surface of the package by 100 (equivalent to the maximum radiation level in millirem per hour at 1 meter (3.3 ft)).

“Tribal official” means the highest ranking individual that represents Tribal leadership, such as the Chief, President, or Tribal Council leadership.

“Type A quantity” means a quantity of radioactive material, the aggregate radioactivity of which does not exceed A<sub>1</sub> for special form radioactive material, or A<sub>2</sub> for normal form radioactive material, where A<sub>1</sub> and A<sub>2</sub> are given in Table A-1 of this Part, or may be determined by procedures described in Appendix A of this Part.

“Type B quantity” means a quantity of radioactive material greater than a Type A quantity.

“Unirradiated uranium” means uranium containing not more than 2 x 10<sup>3</sup> Bq of plutonium per gram of uranium-235, not more than 9 x 10<sup>6</sup> Bq of fission products per gram of uranium-235, and not more than 5 x 10<sup>3</sup> g of uranium-236 per gram of uranium-235.

“Uranium – natural, depleted, enriched”:

(1) “Natural uranium” means uranium (which may be chemically separated) with the naturally occurring distribution of uranium isotopes (approximately 0.711 weight percent uranium-235, and the remainder by weight essentially uranium-238).

(2) “Depleted uranium” means uranium containing less uranium-235 than the naturally occurring distribution of uranium isotopes.

(3) “Enriched uranium” means uranium containing more uranium-235 than the naturally occurring distribution of uranium isotopes.

Commented [mdk17]: 10 CFR 71.4 RATS 2015-3

Sec. T.5 Transportation of Licensed Material.

(a) In addition to the requirements of this Part, each licensee who transports licensed material outside the site of usage, as specified in its Agency license, or where transport is on public highways, or who delivers licensed material to a carrier for transport, shall comply with the applicable requirements of the DOT regulations in 49 CFR Parts 107, 171 through 180, and 390 through 397, appropriate to the mode of transport.

- (1) The licensee shall particularly note DOT regulations in the following areas:
  - (i) Packaging--49 CFR Part 173: Subparts A, B, and I.
  - (ii) Marking and labeling--49 CFR Part 172: Subpart D; and §§ 172.400 through 172.407 and §§ 172.436 through 172.441 of Subpart E.
  - (iii) Placarding--49 CFR Part 172: Subpart F, especially §§ 172.500 through 172.519 and §172.556; and Appendices B and C.
  - (iv) Accident reporting--49 CFR Part 171: §§ 171.15 and 171.16.
  - (v) Shipping papers and emergency information--49 CFR Part 172: Subparts C and G.
  - (vi) Hazardous material employee training--49 CFR Part 172: Subpart H.
  - (vii) Security plans--49 CFR Part 172: Subpart I.
  - (viii) Hazardous material shipper/carrier registration--49 CFR Part 107: Subpart G.
- (2) The licensee shall also note DOT regulations pertaining to the following modes of transportation:
  - (i) Rail--49 CFR Part 174: Subparts A through D and K.
  - (ii) Air--49 CFR Part 175.
  - (iii) Vessel--49 CFR Part 176: Subparts A through F and M.
  - (iv) Public Highway--49 CFR Part 177 and Parts 390 through 397.

(b) If DOT regulations are not applicable to a shipment of licensed material, the licensee shall conform to the standards and requirements of the DOT specified in paragraph (a) of this section to the same extent as if the shipment or transportation were subject to DOT regulations. A request for modification, waiver, or exemption from those requirements, and any notification referred to in those requirements, must be filed with, or made to, the Maryland Agency Department of the Environment, Radiological Health Program, 1800 Washington Boulevard, Baltimore, Maryland 21230.

Secs. T.6 – T.12 Reserved.

## EXEMPTIONS

### Sec. T.13 Exemption of Physicians.

Any physician licensed by a State to dispense drugs in the practice of medicine is exempt from Sec. T.5 with respect to transport by the physician of licensed material for use in the practice of medicine. However, any physician operating under this exemption must be licensed under 10 CFR Part 35 or the equivalent Maryland or other Agreement State regulations.

### Sec. T.14 Exemption for Low-Level Materials.

A licensee is exempt from all requirements of this Part with respect to shipment or carriage of the following low-level materials:

- (1) Natural material and ores containing naturally occurring radionuclides that are either in their natural state, or have only been processed for purposes other than for the extraction of the radionuclides, and which are not intended to be processed for the use of these radionuclides, provided the activity concentration of the material does not exceed 10 times the applicable radionuclide activity concentration values specified in Appendix A, Table A-2, or Table A-3 of this Part.
- (2) Materials for which the activity concentration is not greater than the activity concentration values specified in Appendix A, Table A-2, or Table A-3 of this Part, or for which the consignment activity is not greater than the limit for an exempt consignment found in Appendix A, Table A-2, or Table A-3 of this Part.
- (3) Non-radioactive solid objects with radioactive substances present on any surfaces in quantities not in excess of the levels cited in the definition of contamination in T.4.

Commented [mdk18]: 10 CFR 71.14 RATS 2015-3

### Sec. T.15 Exemption from Classification as Fissile Material.

Fissile material meeting the requirements of at least one of the paragraphs (a) through (f) of this section are exempt from classification as fissile material and from the fissile material package standards of 10 CFR §71.55 and 71.59, but are subject to all other requirements of this Part, except as noted.

- (a) Individual package containing 2 grams or less fissile material.
- (b) Individual or bulk packaging containing 15 grams or less of fissile material provided the package has at least 200 grams of solid nonfissile material for every gram of fissile material. Lead, beryllium, graphite, and hydrogenous material enriched in deuterium may be present in the package but must not be included in determining the required mass for solid nonfissile material.
- (c) (1) Low concentrations of solid fissile material commingled with solid nonfissile material, provided that:
  - (i) There is at least 2000 grams of solid nonfissile material for every gram of fissile material, and
  - (ii) There is no more than 180 grams of fissile material distributed within 360 kg of contiguous nonfissile material.
- (2) Lead, beryllium, graphite, and hydrogenous material enriched in deuterium may be present in the package but must not be included in determining the required mass of solid nonfissile material.

- (d) Uranium enriched in uranium-235 to a maximum of 1 percent by weight, and with total plutonium and uranium-233 content of up to 1 percent of the mass of uranium-235, provided that the mass of any beryllium, graphite, and hydrogenous material enriched in deuterium constitutes less than 5 percent of the uranium mass, and that the fissile material is distributed homogeneously and does not form a lattice arrangement within the package.
- (e) Liquid solutions of uranyl nitrate enriched in uranium-235 to a maximum of 2 percent by mass, with a total plutonium and uranium-233 content not exceeding 0.002 percent of the mass of uranium, and with a minimum nitrogen to uranium atomic ratio (N/U) of 2. The material must be contained in at least a DOT Type A package.
- (f) Packages containing, individually, a total plutonium mass of not more than 1000 grams, of which not more than 20 percent by mass may consist of plutonium-239, plutonium-241, or any combination of these radionuclides.

Commented [mdk19]: 10 CFR 71.15(d) RATS 2015-3

Sec. T.16 Reserved.

#### GENERAL LICENSES

Sec. T.17 General License: NRC-Approved Package.

- (a) A general license is hereby issued to any licensee of the Agency to transport, or to deliver to a carrier for transport, licensed material in a package for which a license, Certificate of Compliance (CoC), or other approval has been issued by the NRC.
- (b) This general license applies only to a licensee who has a quality assurance program approved by the NRC as satisfying the provisions of 10 CFR Part 71 Subpart H.
- (c) Each licensee issued a general license under paragraph (a) of this section shall--This general license applies only to a licensee who--
- (1) MaintainHas a copy of the Certificate of Compliance, or other approval of the package, and ~~has~~ the drawings and other documents referenced in the approval relating to the use and maintenance of the packaging and to the actions to be taken before shipment;
- (2) Complies with the terms and conditions of the license, certificate, or other approval, as applicable, and the applicable requirements of T.1 – T.5, T.81 – T.97, and T.101 – T.137; and
- (3) Submits in writing before the first use of the package to: the NRC, before the licensee's first use of the package, ATTN: Document Control Desk, Director, Division of Spent Fuel Storage and Transportation, Office of Nuclear Material Safety and Safeguards, using an appropriate method listed in 10 CFR Sec. 71.1(a), the licensee's name and license number and the package identification number specified in the package approval.
- (d) This general license applies only when the package approval authorizes use of the package under this general license.
- (e) For a Type B or fissile material package, the design of which was approved by ~~the~~ NRC before April 1, 1996, the general license is subject to the additional restrictions of 10 CFR Sec. 71.19.

Commented [mdk20]: 10 CFR 71.17 RATS 2015-3

Secs. T.18 – T.20 Reserved.

Supp. 4628 T8

Sec. T.21 General License: Use of Foreign Approved Package

Commented [mdk21]: 10 CFR 71.21 RATS 2015-3

(a) A general license is issued to any licensee of the Agency to transport, or to deliver to a carrier for transport, licensed material in a package, the design of which has been approved in a foreign national competent authority certificate, that has been revalidated by the DOT as meeting the applicable requirements of 49 CFR 171.~~4223~~.

(b) Except as otherwise provided in this section, the general license applies only to a licensee who has a quality assurance program approved by the NRC as satisfying the applicable provisions of ~~10 CFR Part 71 Subpart HT.101 through T.137~~.

(c) This general license applies only to shipments made to or from locations outside the United States.

(d) ~~Each licensee issued a general license under paragraph (a) of this section shall--This general license applies only to a licensee who-~~

(1) ~~Has~~Maintain a copy of the applicable certificate, the revalidation, and the drawings and other documents referenced in the certificate, relating to the use and maintenance of the packaging and to the actions to be taken before shipment; and

(2) ~~Complies~~ with the terms and conditions of the certificate and revalidation, and with the applicable requirements of T.1 through T.5, T.81 through T.97, and T.101 through T.137. ~~With respect to the quality assurance provisions of T.101 through T.137, the licensee is exempt from design, construction, and fabrication considerations.~~

Sec. T.22 General License: Fissile Material

(a) A general license is issued to any licensee of the Agency to transport fissile material, or to deliver fissile material to a carrier for transport, if the material is shipped in accordance with this section. The fissile material need not be contained in a package which meets the standards of T.47 and 10 CFR Part 71 Subparts E and F; however, the material must be contained in a Type A package. The Type A package must also meet the DOT requirements of 49 CFR 173.417(a).

(b) The general license applies only to a licensee who has a quality assurance program approved by the NRC as satisfying the provisions of 10 CFR Part 71 Subpart H.

(c) The general license applies only when a package's contents:

(1) Contain no more than a Type A quantity of radioactive material; and

(2) Contain less than 500 total grams of beryllium, graphite, or hydrogenous material enriched in deuterium.

(d) The general license applies only to packages containing fissile material that are labeled with a CSI which:

- (1) Has been determined in accordance with paragraph (e) of this section;
  - (2) Has a value less than or equal to 10; and
  - (3) For a shipment of multiple packages containing fissile material, the sum of the CSIs must be less than or equal to 50 (for shipment on a nonexclusive use conveyance) and less than or equal to 100 (for shipment on an exclusive use conveyance).
- (e) (1) The value for the CSI must be greater than or equal to the number calculated by the following equation:

$$CSI = 10 \left[ \frac{\text{grams of } ^{235}\text{U}}{X} + \frac{\text{grams of } ^{233}\text{U}}{Y} + \frac{\text{grams of Pu}}{Z} \right];$$

- (2) The calculated CSI must be rounded up to the first decimal place;
- (3) The values of X, Y, and Z used in the CSI equation must be taken from Tables T-1 or T-2, as appropriate;
- (4) If Table T-2 is used to obtain the value of X, then the values for the terms in the equation for uranium-233 and plutonium must be assumed to be zero; and
- (5) Table T-1 values for X, Y, and Z must be used to determine the CSI if:
  - (i) Uranium-233 is present in the package;
  - (ii) The mass of plutonium exceeds 1 percent of the mass of uranium-235;
  - (iii) The uranium is of unknown uranium-235 enrichment or greater than 24 weight percent enrichment; or
  - (iv) Substances having a moderating effectiveness (i.e., an average hydrogen density greater than H<sub>2</sub>O) (e.g., certain hydrocarbon oils or plastics) are present in any form, except as polyethylene used for packing or wrapping.

*PACKAGE APPROVAL STANDARDS*

Sec. T.47 External Radiation Standards for All Packages.

(a) Except as provided in paragraph (b) of this section, each package of radioactive materials offered for transportation must be designed and prepared for shipment so that under conditions normally incident to transportation the radiation level does not exceed 2 mSv/h (200 mrem/h) at any point on the external surface of the package, and the transport index does not exceed 10.

(b) A package that exceeds the radiation level limits specified in paragraph (a) of this section must be transported by exclusive use shipment only, and the radiation levels for such shipment must not exceed the following during transportation:

(1) 2 mSv/h (200 mrem/h) on the external surface of the package, unless the following conditions are met, in which case the limit is 10 mSv/h (1000 mrem/h):

- (i) The shipment is made in a closed transport vehicle;
- (ii) The package is secured within the vehicle so that its position remains fixed during transportation; and
- (iii) There are no loading or unloading operations between the beginning and end of the transportation;

(2) 2 mSv/h (200 mrem/h) at any point on the outer surface of the vehicle, including the top and underside of the vehicle; or in the case of a flat-bed style vehicle, at any point on the vertical planes projected from the outer edges of the vehicle, on the upper surface of the load or enclosure, if used, and on the lower external surface of the vehicle; and

(3) 0.1 mSv/h (10 mrem/h) at any point 2 meters (80 in.) from the outer lateral surfaces of the vehicle (excluding the top and underside of the vehicle); or in the case of a flat-bed style vehicle, at any point 2 meters (6.6 feet) from the vertical planes projected by the outer edges of the vehicle (excluding the top and underside of the vehicle); and

(4) 0.02 mSv/h (2 mrem/h) in any normally occupied space, except that this provision does not apply to private carriers, if exposed personnel under their control wear radiation dosimetry devices in conformance with Sec. D.502.

(c) For shipments made under the provisions of paragraph (b) of this section, the shipper shall provide specific written instructions to the carrier for maintenance of the exclusive use shipment controls. The instructions must be included with the shipping paper information.

(d) The written instructions required for exclusive use shipments must be sufficient so that, when followed, they will cause the carrier to avoid actions that will unnecessarily delay delivery or unnecessarily result in increased radiation levels or radiation exposures to transport workers or members of the general public.

Secs. T.48 – T.80 Reserved.

*OPERATING CONTROLS AND PROCEDURES*

Sec. T.81 Applicability of Operating Controls and Procedures.

A licensee subject to this Part, who, under a general or specific license, transports licensed material or delivers licensed material to a carrier for transport, shall comply with the requirements of T.81 – T.97, with the quality assurance requirements of T.101 - T.137, and with the general provisions of T.1 - T.5.

Sec. T.82 Reserved.

Sec. T.83 Assumptions as to Unknown Properties.

When the isotropic abundance, mass, concentration, degree of irradiation, degree of moderation, or other pertinent property of fissile material in any package is not known, the licensee shall package the fissile material as if the unknown properties have credible values that will cause the maximum neutron multiplication.

Sec. T.84 Reserved.

Sec. T.85 Preliminary Determinations.

Before the first use of any packaging for the shipment of licensed material--

(a) ~~The licensee certificate holder shall ascertain that there are no cracks, pinholes, uncontrolled voids, or other defects that could significantly reduce the effectiveness of the packaging;~~

**Commented [mdk22]:** 10 CFR 71.85(a)-(c) RATS 2015-3 Now NRC, but have regulation so we will retain.

(b) Where the maximum normal operating pressure will exceed 35 kPa (5 lbf/in<sup>2</sup>) gauge, the licensee certificate holder shall test the containment system at an internal pressure at least 50 percent higher than the maximum normal operating pressure, to verify the capability of that system to maintain its structural integrity at that pressure; ~~and~~

(c) The licensee certificate holder shall conspicuously and durably mark the packaging with its model number, serial number, gross weight, and a package identification number assigned by the NRC. Before applying the model number, the licensee certificate holder shall determine that the packaging has been fabricated in accordance with the design approved by the NRC; ~~and~~

~~(d) The licensee shall ascertain that the determinations in paragraphs (a) through (c) of this section have been made.~~

**Commented [mdk23]:** 10 CFR 71.85(d) RATS 2015-3

Sec. T.86 Reserved.

Supp. ~~4628~~



Sec. T.87 Routine Determinations.

Before each shipment of licensed material, the licensee shall ensure that the package with its contents satisfies the applicable requirements of this Part and of the license. The licensee shall determine that--

- (a) The package is proper for the contents to be shipped;
- (b) The package is in unimpaired physical condition except for superficial defects such as marks or dents;
- (c) Each closure device of the packaging, including any required gasket, is properly installed and secured and free of defects;
- (d) Any system for containing liquid is adequately sealed and has adequate space or other specified provision for expansion of the liquid;
- (e) Any pressure relief device is operable and set in accordance with written procedures;
- (f) The package has been loaded and closed in accordance with written procedures;
- (g) For fissile material, any moderator or neutron absorber, if required, is present and in proper condition;
- (h) Any structural part of the package that could be used to lift or tie down the package during transport is rendered inoperable for that purpose, unless it satisfies the design requirements of 10 CFR 71.45;
- (i) The level of non-fixed (removable) radioactive contamination on the external surfaces of each package offered for shipment is As Low As Reasonably Achievable, and within the limits specified in DOT regulations in 49 CFR 173.443;
- (j) External radiation levels around the package and around the vehicle, if applicable, will not exceed the limits specified in T.47 at any time during transportation; and
- (k) Accessible package surface temperatures will not exceed the limits specified in 10 CFR 71.43(g) at any time during transportation.

Sec. T.88 Air Transport of Plutonium.

(a) Notwithstanding the provisions of any general licenses and notwithstanding any exemptions stated directly in this Part or included indirectly by citation of 49 CFR Chapter I, as may be applicable, the licensee shall assure that plutonium in any form, whether for import, export, or domestic shipment, is not transported by air or delivered to a carrier for air transport ~~unless:~~

- (1) The plutonium is contained in a medical device designed for individual human application; or
- (2) The plutonium is contained in a material in which the specific activity is less than or equal to the activity concentration values for plutonium specified in Appendix A, Table A-2, of this Part, and in which the radioactivity is essentially uniformly distributed; or
- (3) The plutonium is shipped in a single package containing no more than an A<sub>2</sub> quantity of plutonium in any isotope or form, and is shipped in accordance with T.5; or

Commented [mdk24]: Moved from T16

(4) The plutonium is shipped in a package specifically authorized for the shipment of plutonium by air in the Certificate of Compliance for that package issued by the NRC.

(b) Nothing in paragraph (a) of this section is to be interpreted as removing or diminishing the requirements of 10 CFR 73.24.

(c) For a shipment of plutonium by air which is subject to paragraph (a)(4) of this section, the licensee shall, through special arrangement with the carrier, require compliance with 49 CFR 175.704, DOT regulations applicable to the air transport of plutonium.

Sec. T.89 Opening Instructions.

Before delivery of a package to a carrier for transport, the licensee shall ensure that any special instructions needed to safely open the package have been sent to, or otherwise made available to, the consignee for the consignee's use in accordance with Sec. D.906(e).

Sec. T.90 – T.96 Reserved.

Sec. T.91 Records.

(a) Each licensee shall maintain, for a period of 3 years after shipment, a record of each shipment of licensed material not exempt under T.14, showing where applicable --

- (1) Identification of the packaging by model number and serial number;
- (2) Verification that there are no significant defects in the packaging, as shipped;
- (3) Volume and identification of coolant;
- (4) Type and quantity of licensed material in each package, and the total quantity of each shipment;
- (5) For each item of irradiated fissile material –
  - (i) Identification by model number and serial number;
  - (ii) Irradiation and decay history to the extent appropriate to demonstrate that its nuclear and thermal characteristics comply with license conditions; and
  - (iii) Any abnormal or unusual condition relevant to radiation safety;
- (6) Date of the shipment;
- (7) For fissile packages and for Type B packages, any special controls exercised;
- (8) Name and address of the transferee;
- (9) Address to which the shipment was made; and
- (10) Results of the determinations required by T.87 and by the conditions of the package approval.

(a)(b) Reserved.

Supp. 2728

Commented [mdk25]: 10 CFR 71.91 RATS 2015-3

Commented [mdk26]: Added from 10 CFR 71.91

(c) The licensee, certificate holder, and an applicant for a CoC, shall make available to the Agency for inspection, upon reasonable notice, of all records required by this part. Records are only valid if stamped, initialed, or signed and dated by authorized personnel, or otherwise authenticated.

Commented [mdk27]: 10 CFR 71.91(c)&(d) RATS 2015-3

(d) The licensee, certificate holder, and an applicant for a CoC shall maintain sufficient written records to furnish evidence of the quantity of packaging. The records to be maintained include results of the determinations required by T.85: design, fabrication, and assembly records; results of reviews, inspections, tests, and audits; results of monitoring work performance and materials analyses; and results of maintenance, modification, and repair activities. Inspection, test, and audit records must identify the inspector or data recorder, the type of observation, the results, the acceptability, and the action taken in connection with any deficiencies noted. These records must be retained for 3 years after the life of the packaging to which they apply.

T.92 – T.96 Reserved.

Sec. T.97 Advance Notification of Shipment of Irradiated Reactor Fuel and Nuclear Waste.

Commented [mdk28]: Moved from T16

(a) (1) As specified in paragraphs (b), (c) and (d) of this section, each licensee shall provide advance notification to the governor of a State, or the governor's designee, of the shipment of licensed material, within or across the boundary of the State, before the transport, or delivery to a carrier, for transport, of licensed material outside the confines of the licensee's plant or other place of use or storage.

(2) As specified in paragraphs (b), (c), and (d) of this section, each licensee shall provide advance notification to the Tribal official of participating Tribes referenced in paragraph (c)(3)(iii) of this section, or the official's designee, of the shipment of licensed material, within or across the boundary of the Tribe's reservation, before the transport, or delivery to a carrier, for transport, of licensed material outside the confines of the licensee's plant or other place of use or storage.

(b) Advance notification is required under this section for shipments of irradiated reactor fuel in quantities less than that subject to advance notification requirements of 10 CFR 73.37(f). Advance notification is also required under this section for shipment of licensed material, other than irradiated fuel, meeting the following three conditions:

- (1) The licensed material is required by this Part to be in Type B packaging for transportation;
- (2) The licensed material is being transported to or across a State boundary en route to a disposal facility or to a collection point for transport to a disposal facility; and

(3) The quantity of licensed material in a single package exceeds the least of the following:

Commented [mdk29]: Moved from Page T17

- (i) 3000 times the A1 value of the radionuclides as specified in Appendix A, Table A-1 for special form radioactive material;
- (ii) 3000 times the A2 value of the radionuclides as specified in Appendix A, Table A-1 for normal form radioactive material; or
- (iii) 1000 TBq (27,000 Ci).

(This page is deliberately blank.)

(c) Procedures for submitting advance notification.

(1) The notification must be made in writing to:

- (i) The office of each appropriate governor or governor's designee;
- (ii) The office of each appropriate Tribal official or Tribal official's designee; and
- (iii) The Director, Division of Security Policy, Office of Nuclear Security and Incident Response, U.S. Nuclear Regulatory Commission.

(2) A notification delivered by mail must be postmarked at least 7 days before the beginning of the 7-day period during which departure of the shipment is estimated to occur.

(3) A notification delivered by any other means than mail must reach the office of the governor or of the governor's designee or the Tribal official or Tribal official's designee at least 4 days before the beginning of the 7-day period during which departure of the shipment is estimated to occur.

(i) A list of the names and mailing addresses of the governors' designees receiving advance notification of transportation of nuclear waste was published in the Federal Register on June 30, 1995 (60 FR 34306).

(ii) ~~The list of governor's designees and Tribal official's designees of participating Tribes will be published annually in the Federal Register on or about June 30 to reflect any changes in information.~~ Contact information for each State, including telephone and mailing addresses of governors and governor's designees, and participating Tribes, including telephone and mailing addresses of Tribal officials and Tribal official's designees, is available on the NRC Web site at: <https://scp.nrc.gov/special/designee.pdf>.

(iii) A list of the names and mailing addresses of the governors' designees and Tribal officials' designees of participating Tribes is available on request from the Director, Division of Material Safety, State, Tribal, and Rulemaking Programs, Office of Nuclear Material Safety and Safeguards, U.S. Nuclear Regulatory Commission, Washington, DC 20555-0001.

(4) The licensee shall retain a copy of the notification as a record for 3 years.

(d) Information to be furnished in advance notification of shipment. Each advance notification of shipment of irradiated reactor fuel or nuclear waste must contain the following information:

(1) The name, address, and telephone number of the shipper, carrier, and receiver of the irradiated reactor fuel or nuclear waste shipment;

(2) A description of the irradiated reactor fuel or nuclear waste contained in the shipment, as specified in the regulations of DOT in 49 CFR 172.202 and 172.203(d);

(3) The point of origin of the shipment and the 7-day period during which departure of the shipment is estimated to occur;

(4) The 7-day period during which arrival of the shipment at State boundaries or Tribal reservation boundaries is estimated to occur;

Commented [mdk30]: 10 CFR 71.97(c)(3)(ii) RATS 2015-5

(5) The destination of the shipment, and the 7-day period during which arrival of the shipment is estimated to occur; and

(6) A point of contact, with a telephone number, for current shipment information.

(e) Revision notice. A licensee who finds that schedule information previously furnished to a governor or governor's designee or to a Tribal official or Tribal official's designee, in accordance with this section, will not be met, shall telephone a responsible individual in the office of the governor of the State or of the governor's designee or the Tribal official or the Tribal official's designee and inform that individual of the extent of the delay beyond the schedule originally reported. The licensee shall maintain a record of the name of the individual contacted for 3 years.

(f) Cancellation notice.

(1) Each licensee who cancels an irradiated reactor fuel or nuclear waste shipment for which advance notification has been sent shall send a cancellation notice to the governor of each State or to the governor's designee previously notified, each Tribal official or to the Tribal official's designee previously notified, and the Director, Division of Security Policy, Office of Nuclear Security and Incident Response, U.S. Nuclear Regulatory Commission.

(2) The licensee shall state in the notice that it is a cancellation and identify the advance notification that is being canceled. The licensee shall retain a copy of the notice as a record for 3 years.

Secs. T.98 – T.100 Reserved.

#### *QUALITY ASSURANCE*

Sec. T.101 Quality Assurance Requirements.

(a) Purpose. Secs. T.101 through T.137 describe quality assurance requirements applying to design, purchase, fabrication, handling, shipping, storing, cleaning, assembly, inspection, testing, operation, maintenance, repair, and modification of components of packaging that are important to safety. As used in these sections, "quality assurance" comprises all those planned and systematic actions necessary to provide adequate confidence that a system or component will perform satisfactorily in service. Quality assurance includes quality control, which comprises those quality assurance actions related to control of the physical characteristics and quality of the material or component to predetermined requirements. Each certificate holder and applicant for a package approval ~~The licensee~~ is responsible for satisfying the quality assurance requirements ~~as they that~~ apply to design, fabrication, testing, and modification of packaging subject to these sections. Each licensee is responsible for satisfying the quality assurance ~~requirements provision that which~~ applies to its use of a packaging for the shipment of licensed material subject to these sections.

Commented [mdk31]: 10 CFR 71.101 RATS 2015-3

(b) Establishment of program. Each licensee, certificate holder, and applicant for a CoC shall establish, maintain, and execute a quality assurance program satisfying each of the applicable criteria of Secs. T.101 through T.137 and satisfying any specific provisions that are applicable to the licensee's activities including procurement of packaging. The licensee, certificate holder, and applicant for a CoC shall ~~apply each of~~ execute the applicable criteria in a graded approach, ~~i.e.,~~ to an extent that is commensurate ~~consistent~~ with the quality assurance requirement's ~~its~~ importance to safety.

(c) Approval of program. Before the use of any package for the shipment of licensed material subject to Secs. T.101 through T.137, each licensee shall obtain NRC approval of its quality assurance program ~~in accordance with 10 CFR Part 71 Subpart H. Using an appropriate method of communication listed in 10 CFR § 71.1(a), each licensee shall file a description of its quality assurance program, including a discussion of which requirements of Sections T.101 through T.137 are applicable and how they will be satisfied, by submitting the description to:~~ ATTN: Document Control Desk, Director, Division of Spent Fuel Management, Office of Nuclear Safety and Safeguards, U.S. Nuclear Regulatory Commission.

**Commented [mdk32]:** Moved from T18. 10 CFR 71.101(c)(1) RATS 2015-3.

(d) Radiography containers. A program for transport container inspection and maintenance limited to radiographic exposure devices, source changers, or packages transporting these devices and meeting the requirements of Sec. E.31(b) of this regulation or equivalent NRC or Agreement State requirement, is deemed to satisfy the requirements of T.17(b) and T.101(b).

Sec. T.102 Reserved.

Sec. T.103 Quality Assurance Organization.

(a) ~~The licensee<sup>4</sup>, certificate holder, and applicant for a Certificate of Compliance shall be responsible for the establishment and execution of the quality assurance program. The licensee, certificate holder, and applicant for a Certificate of Compliance may delegate to others, such as contractors, agents, or consultants, the work of establishing and executing the quality assurance program, or any part of the quality assurance program, but shall retain responsibility for the program. The licensee shall clearly establish and delineate, in writing, the authority and duties of persons and organizations performing activities affecting the safety-related functions of structures, systems, and components.~~ These activities include performing the functions associated with attaining quality objectives and the quality assurance functions.

**Commented [mdk33]:** 10 CFR 71.103 RATS 2015-3

(b) The quality assurance functions are --

- (1) Assuring that an appropriate quality assurance program is established and effectively executed; and
- (2) Verifying, by procedures such as checking, auditing, and inspection, that activities affecting the safety-related functions have been performed correctly.

(c) The persons and organizations performing quality assurance functions must have sufficient authority and organizational freedom to --

- (1) Identify quality problems;
- (2) Initiate, recommend, or provide solutions; and
- (3) Verify implementation of solutions.

(d) The persons and organizations performing quality assurance functions shall report to a management level that assures that the required authority and organizational freedom, including sufficient independence from cost and schedule, when opposed to safety considerations, are provided.

~~While the term "licensee" is used in these criteria, the requirements are applicable to whatever design, fabrication, assembly, and testing of the package is accomplished with respect to a package prior to the time a package approval is issued.~~

**Commented [mdk34]:** See 80 FR 33994 (June 12, 2015), Paragraph K

(e) Because of the many variables involved, such as the number of personnel, the type of activity being performed, and the location or locations where activities are performed, the organizational structure for executing the quality assurance program may take various forms, provided that the persons and organizations assigned the quality assurance functions have the required authority and organizational freedom.

(f) Irrespective of the organizational structure, the individual(s) assigned the responsibility for assuring effective execution of any portion of the quality assurance program, at any location where activities subject to this section are being performed, must have direct access to the levels of management necessary to perform this function.

Sec. T.104 Reserved.

Sec. T.105 Quality Assurance Program.

(a) The licensee shall establish, at the earliest practicable time consistent with the schedule for accomplishing the activities, a quality assurance program that complies with the requirements of Secs. T.101 through T.137. The licensee shall document the quality assurance program by written procedures or instructions and shall carry out the program in accordance with those procedures throughout the period during which the packaging is used. The licensee shall identify the material and components to be covered by the quality assurance program, the major organizations participating in the program, and the designated functions of these organizations.

(b) The licensee, through its quality assurance program, shall provide control over activities affecting the quality of the identified materials and components to an extent consistent with their importance to safety, and as necessary to assure conformance to the approved design of each individual package used for the shipment of radioactive material. The licensee shall assure that activities affecting quality are accomplished under suitably controlled conditions. Controlled conditions include the use of appropriate equipment; suitable environmental conditions for accomplishing the activity, such as adequate cleanliness; and assurance that all prerequisites for the given activity have been satisfied. The licensee shall take into account the need for special controls, processes, test equipment, tools, and skills to attain the required quality, and the need for verification of quality by inspection and test.

(c) The licensee shall base the requirements and procedures of its quality assurance program on the following considerations concerning the complexity and proposed use of the package and its components:

- (1) The impact of malfunction or failure of the item to safety;
- (2) The design and fabrication complexity or uniqueness of the item;
- (3) The need for special controls and surveillance over processes and equipment;
- (4) The degree to which functional compliance can be demonstrated by inspection or test; and
- (5) The quality history and degree of standardization of the item.

Commented [mdk35]: Moved from T21



(d) The licensee shall provide for indoctrination and training of personnel performing activities affecting quality, as necessary to assure that suitable proficiency is achieved and maintained. The licensee shall review the status and adequacy of the quality assurance program at established intervals. Management of other organizations participating in the quality assurance program shall review regularly the status and adequacy of that part of the quality assurance program which they are executing.

Sec. T.106 Changes to Quality Assurance Program.

Commented [mdk36]: 10 CFR 71.106 RATS 2015-3

(a) Each quality assurance program approval holder shall submit in accordance with 10 CFR § 71.1(a), a description of a proposed change to its NRC-approved quality assurance program that will reduce commitments in the program description as approved by the NRC. The quality assurance program approval holder shall not implement the change before receiving NRC approval.

(1) The description of a proposed change to the NRC-approved quality assurance program must identify the change, the reason for the change, and the basis for concluding that the revised program incorporating the change continues to satisfy the applicable requirements of T.101 through T.137.

(2) [Reserved.]

(b) Each quality assurance program approval holder may change a previously approved quality assurance program without prior NRC approval, if the change does not reduce the commitments in the quality assurance program previously approved by the NRC. Changes to the quality assurance program that do not reduce the commitments shall be submitted to the NRC every 24 months, in accordance with 10 CFR § 71.1(a). In addition to quality assurance program changes involving administrative improvements and clarifications, spelling corrections, and non-substantive changes to punctuation or editorial items, the following changes are not considered reductions in commitment.

(1) The use of a quality assurance standard approved by the NRC that is more recent than the quality assurance standard in the certificate holder's or applicant's current quality assurance program at the time of the change;

(2) The use of generic organizational position titles that clearly denote the position function, supplemented as necessary by descriptive text, rather than specific titles, provided that there is no substantive change to either the functions of the position or reporting responsibilities;

(3) The use of generic organizational charts to indicate functional relationships, authorities, and responsibilities, or alternatively, the use of descriptive text, provided that there is no substantive change to the functional relationships, authorities, or responsibilities;

(4) The elimination of quality assurance program information that duplicates language in quality assurance regulatory guides and quality assurance standards to which the quality assurance program approval holder has committed to on record; and

(5) Organizational revisions that ensure that persons and organizations performing quality assurance functions continue to have the requisite authority and organizational freedom, including sufficient independence from cost and schedule when opposed to safety considerations.

(c) Each quality assurance program approval holder shall maintain records of quality assurance program changes.

Secs. T.1076 – T.126 Reserved.

Sec. T.127 Handling, Storage, and Shipping Control. The licensee shall establish measures to control, in accordance with instructions, the handling, storage, shipping, cleaning, and preservation of materials and equipment to be used in packaging to prevent damage or deterioration. When necessary for particular products, special protective environments, such as inert gas atmosphere, and specific moisture content and temperature levels must be specified and provided.

Commented [mdk37]: Moved from T21

Sec. T.128 Reserved.

Sec. T.129 Inspection, Test, and Operating Status.

(a) The licensee shall establish measures to indicate, by the use of markings such as stamps, tags, labels, routing cards, or other suitable means, the status of inspections and tests performed upon individual items of the packaging. These measures must provide for the identification of items that have satisfactorily passed required inspections and tests, where necessary to preclude inadvertent bypassing of the inspections and tests.

(b) The licensee shall establish measures to identify the operating status of components of the packaging, such as tagging valves and switches, to prevent inadvertent operation.

Sec. T.130 Reserved.

Sec. T.131 Nonconforming Materials, Parts, or Components. The licensee shall establish measures to control materials, parts, or components that do not conform to the licensee's requirements to prevent their inadvertent use or installation. These measures must include, as appropriate, procedures for identification, documentation, segregation, disposition, and notification to affected organizations. Nonconforming items must be reviewed and accepted, rejected, repaired, or reworked in accordance with documented procedures.

Sec. T.132 Reserved.

(This page intentionally blank.)

T21-2

Supp. 28

Sec. T.133 Corrective Action. The licensee shall establish measures to assure that conditions adverse to quality, such as deficiencies, deviations, defective material and equipment, and nonconformances, are promptly identified and corrected. In the case of a significant condition adverse to quality, the measures must assure that the cause of the condition is determined and corrective action taken to preclude repetition. The identification of the significant condition adverse to quality, the cause of the condition, and the corrective action taken must be documented and reported to appropriate levels of management.

Sec. T.134 Reserved.

Sec. T.135 Quality Assurance Records. The licensee, certificate holder, and applicant for a Certificate of Compliance shall maintain sufficient written records to describe the activities affecting quality. These records must include changes to the quality assurance program as required by T.106; the documented instructions, procedures, or drawings of a type appropriate to the circumstances to prescribe quality assurance activities including appropriate quantitative and qualitative acceptance criteria for determining that activities important to quality have been satisfactorily accomplished, and ~~must include~~ closely related specifications such as required qualifications of personnel, procedures, and equipment. The records must include the instructions or procedures which establish a records retention program that is consistent with applicable regulations and designates factors such as duration, location, and assigned responsibility. The licensee, certificate holder, and applicant for a Certificate of Compliance shall retain these records for 3 years beyond the date when the licensee, certificate holder, and applicant for a Certificate of Compliance last engages in the activity for which the quality assurance program was developed. If any portion of the quality assurance program, written procedures or instructions is superseded, the licensee, certificate holder, and applicant for a Certificate of Compliance shall retain the superseded material for 3 years after it is superseded.

Commented [mdk38]: 10 CFR 71.135 RATS 2015-3

Commented [mdk39]: From 10 CFR 71.111

Sec. T.136 Reserved.

Sec. T.137 Audits. The licensee shall carry out a comprehensive system of planned and periodic audits, to verify compliance with all aspects of the quality assurance program, and to determine the effectiveness of the program. The audits must be performed in accordance with written procedures or checklists by appropriately trained personnel not having direct responsibilities in the areas being audited. Audited results must be documented and reviewed by management having responsibility in the area audited. Follow-up action, including reaudit of deficient areas, must be taken where indicated.

**Part T**  
**Appendix A**  
**Determination of A<sub>1</sub> and A<sub>2</sub>**

Commented [mdk40]: All changes are Category B

I. Values of A<sub>1</sub> and A<sub>2</sub> for individual radionuclides, which are the bases for many activity limits elsewhere in these regulations, are given in Table A-1. The curie (Ci) values specified are obtained by converting from the Terabecquerel (TBq) value. The Terabecquerel values are the regulatory standard. The curie values are for information only and are not intended to be the regulatory standard. Where values of A<sub>1</sub> or A<sub>2</sub> are unlimited, it is for radiation control purposes only. For nuclear criticality safety, some materials are subject to controls placed on fissile material.

II. a. For individual radionuclides whose identities are known, but which are not listed in Table A-1, the A<sub>1</sub> and A<sub>2</sub> values contained in Table A-3 may be used. Otherwise, the licensee shall obtain prior Agency approval of the A<sub>1</sub> and A<sub>2</sub> values for radionuclides not listed in Table A-1, before shipping the material.

b. For individual radionuclides whose identities are known, but which are not listed in Table A-2, the exempt material activity concentration and exempt consignment activity values contained in Table A-3 may be used. Otherwise, the licensee shall obtain prior Agency approval of the exempt material activity concentration and exempt consignment activity values for radionuclides not listed in Table A-2, before shipping the material.

c. The licensee shall submit requests for prior approval, described under paragraphs II.a. and II.b. of this Appendix, to the Agency, in accordance with T.1.

III. In the calculations of A<sub>1</sub> and A<sub>2</sub> for a radionuclide not in Table A-1, a single radioactive decay chain, in which radionuclides are present in their naturally occurring proportions, and in which no daughter radionuclide has a half-life either longer than 10 days, or longer than that of the parent radionuclide, shall be considered as a single radionuclide, and the activity to be taken into account, and the A<sub>1</sub> or A<sub>2</sub> value to be applied, shall be those corresponding to the parent radionuclide of that chain. In the case of radioactive decay chains in which any daughter radionuclide has a half-life either longer than 10 days, or greater than that of the parent radionuclide, the parent and those daughter radionuclides shall be considered as mixtures of different radionuclides.

IV. For mixtures of radionuclides whose identities and respective activities are known, the following conditions apply:

a. For special form radioactive material, the maximum quantity transported in a Type A package is as follows:

$$\sum_i \frac{B(i)}{A_1(i)} \leq 1$$

where B(i) is the activity of radionuclide i in special form, and A<sub>1</sub>(i) is the A<sub>1</sub> value for radionuclide i.

Commented [mdk41]: 10 CFR Part 71 Appendix A RATS 2015-3

b. For normal form radioactive material, the maximum quantity transported in a Type A package is as follows:

$$\sum_i \frac{B(i)}{A_2(i)} \leq 1$$

where B(i) is the activity of radionuclide i in normal form, and A<sub>2</sub>(i) is the A<sub>2</sub> value for radionuclide i.

c. If the package contains both special and normal form radioactive material, the activity that may be transported in a Type A package is as follows:

$$\sum_i \frac{B(i)}{A_1(i)} + \sum_j \frac{C(j)}{A_2(j)} \leq 1$$

where B(i) is the activity of radionuclide i as special form radioactive material, A<sub>1</sub>(i) is the A<sub>1</sub> value for radionuclide i, C(j) is the activity of radionuclide j as normal form radioactive material, and A<sub>2</sub>(j) is the A<sub>2</sub> value for radionuclide j.

ed. Alternatively, the A<sub>1</sub> value for mixtures of special form material may be determined as follows:

$$A_1 \text{ for mixture} = \frac{1}{\sum_i \frac{f(i)}{A_1(i)}}$$

where f(i) is the fraction of activity for radionuclide i in the mixture and A<sub>1</sub>(i) is the appropriate A<sub>1</sub> value for radionuclide i.

ee.- Alternatively, the A<sub>2</sub> value for mixtures of normal form material may be determined as follows:

$$A_2 \text{ for mixture} = \frac{1}{\sum_i \frac{f(i)}{A_2(i)}}$$

where f(i) is the fraction of activity for radionuclide i in the mixture and A<sub>2</sub>(i) is the appropriate A<sub>2</sub> value for radionuclide i.

f. The exempt activity concentration for mixtures of nuclides may be determined as follows:

$$\text{Exempt activity concentration for mixture} = \frac{1}{\sum_i \frac{f(i)}{[A](i)}}$$

where f(i) is the fraction of activity concentration of radionuclide i in the mixture and [A](i) is the activity concentration for exempt material containing radionuclide i.

g. The activity limit for an exempt consignment for mixtures of radionuclides may be determined as follows:

$$\text{Exempt consignment activity limit for mixture} = \frac{1}{\sum_i \frac{f(i)}{A(i)}}$$

where  $f(i)$  is the fraction of activity of radionuclide  $i$  in the mixture and  $A(i)$  is the activity limit for exempt consignments for radionuclide  $i$ .

V. (a) When the identity of each radionuclide is known, but the individual activities of some of the radionuclides are not known, the radionuclides may be grouped, and the lowest  $A_1$  or  $A_2$  value, as appropriate, for the radionuclides in each group may be used in applying the formulas in paragraph IV. Groups may be based on the total alpha activity and the total beta/gamma activity when these are known, using the lowest  $A_1$  or  $A_2$  values for the alpha emitters and beta/gamma emitters.

(b) When the identity of each radionuclide is known but the individual activities of some of the radionuclides are not known, the radionuclides may be grouped and the lowest [A] (activity concentration for exempt material) or A (activity limit for exempt consignment) value, as appropriate, for the radionuclides in each group may be used in applying the formulas in paragraph IV of this appendix. Groups may be based on the total alpha activity and the total beta/gamma activity when these are known, using the lowest [A] or A values for the alpha emitters and beta/gamma emitters, respectively.

Commented [mdk42]: Moved from T24

**Table A-1—A<sub>1</sub> and A<sub>2</sub> VALUES FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	A <sub>1</sub> (TBq)	A <sub>1</sub> (Ci) <sup>b</sup>	A <sub>2</sub> (TBq)	A <sub>2</sub> (Ci) <sup>b</sup>	Specific activity	
						(TBq/g)	(Ci/g)
Ac-225 (a)	Actinium (89)	8.0X10 <sup>-1</sup>	2.2X10 <sup>1</sup>	6.0X10 <sup>-3</sup>	1.6X10 <sup>-1</sup>	2.1X10 <sup>3</sup>	5.8X10 <sup>4</sup>
Ac-227 (a)		9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	9.0X10 <sup>-5</sup>	2.4X10 <sup>-3</sup>	2.7	7.2X10 <sup>1</sup>
Ac-228		6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	8.4X10 <sup>4</sup>	2.2X10 <sup>6</sup>
Ag-105	Silver (47)	2.0	5.4X10 <sup>1</sup>	2.0	5.4X10 <sup>1</sup>	1.1X10 <sup>3</sup>	3.0X10 <sup>4</sup>
Ag-108m (a)		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	9.7X10 <sup>-1</sup>	2.6X10 <sup>1</sup>
Ag-110m (a)		4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	1.8X10 <sup>2</sup>	4.7X10 <sup>3</sup>
Ag-111		2.0	5.4X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	5.8X10 <sup>3</sup>	1.6X10 <sup>5</sup>
Al-26	Aluminum (13)	1.0X10 <sup>-1</sup>	2.7	1.0X10 <sup>-1</sup>	2.7	7.0X10 <sup>-4</sup>	1.9X10 <sup>-2</sup>
Am-241	Americium (95)	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	1.0X10 <sup>-3</sup>	2.7X10 <sup>-2</sup>	1.3X10 <sup>-1</sup>	3.4
Am-242m (a)		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	1.0X10 <sup>-3</sup>	2.7X10 <sup>-2</sup>	3.6X10 <sup>-1</sup>	1.0X10 <sup>1</sup>
Am-243 (a)		5.0	1.4X10 <sup>2</sup>	1.0X10 <sup>-3</sup>	2.7X10 <sup>-2</sup>	7.4X10 <sup>-3</sup>	2.0X10 <sup>-1</sup>
Ar-37	Argon (18)	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	3.7X10 <sup>3</sup>	9.9X10 <sup>4</sup>
Ar-39		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	1.3	3.4X10 <sup>1</sup>
Ar-41		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	1.5X10 <sup>6</sup>	4.2X10 <sup>7</sup>
As-72	Arsenic (33)	3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	6.2X10 <sup>4</sup>	1.7X10 <sup>6</sup>
As-73		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	8.2X10 <sup>2</sup>	2.2X10 <sup>4</sup>
As-74		1.0	2.7X10 <sup>1</sup>	9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	3.7X10 <sup>3</sup>	9.9X10 <sup>4</sup>
As-76		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	5.8X10 <sup>4</sup>	1.6X10 <sup>6</sup>
As-77		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	3.9X10 <sup>4</sup>	1.0X10 <sup>6</sup>
At-211 (a)	Astatine (85)	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	7.6X10 <sup>4</sup>	2.1X10 <sup>6</sup>
Au-193	Gold (79)	7.0	1.9X10 <sup>2</sup>	2.0	5.4X10 <sup>1</sup>	3.4X10 <sup>4</sup>	9.2X10 <sup>5</sup>
Au-194		1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	1.5X10 <sup>4</sup>	4.1X10 <sup>5</sup>
Au-195		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	6.0	1.6X10 <sup>2</sup>	1.4X10 <sup>2</sup>	3.7X10 <sup>3</sup>
Au-198		1.0	2.7X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	9.0X10 <sup>3</sup>	2.4X10 <sup>5</sup>
Au-199		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	7.7X10 <sup>3</sup>	2.1X10 <sup>5</sup>
Ba-131 (a)	Barium (56)	2.0	5.4X10 <sup>1</sup>	2.0	5.4X10 <sup>1</sup>	3.1X10 <sup>3</sup>	8.4X10 <sup>4</sup>
Ba-133		3.0	8.1X10 <sup>1</sup>	3.0	8.1X10 <sup>1</sup>	9.4	2.6X10 <sup>2</sup>
Ba-133m		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	2.2X10 <sup>4</sup>	6.1X10 <sup>5</sup>
Ba-140 (a)		5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	3.0X10 <sup>-1</sup>	8.1	2.7X10 <sup>3</sup>	7.3X10 <sup>4</sup>
Be-7	Beryllium (4)	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	1.3X10 <sup>4</sup>	3.5X10 <sup>5</sup>
Be-10		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	8.3X10 <sup>-4</sup>	2.2X10 <sup>-2</sup>



Table A-1—A<sub>1</sub> and A<sub>2</sub> VALUES FOR RADIONUCLIDES

Symbol of radionuclide	Element and atomic number	A <sub>1</sub> (TBq)	A <sub>1</sub> (Ci) <sup>b</sup>	A <sub>2</sub> (TBq)	A <sub>2</sub> (Ci) <sup>b</sup>	Specific activity	
						(TBq/g)	(Ci/g)
Bi-205	Bismuth (83)	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	1.5X10 <sup>3</sup>	4.2X10 <sup>4</sup>
Bi-206		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	3.8X10 <sup>3</sup>	1.0X10 <sup>5</sup>
Bi-207		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	1.9	5.2X10 <sup>1</sup>
Bi-210		1.0	2.7X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	4.6X10 <sup>3</sup>	1.2X10 <sup>5</sup>
Bi-210m (a)		6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	2.0X10 <sup>-2</sup>	5.4X10 <sup>-1</sup>	2.1X10 <sup>-5</sup>	5.7X10 <sup>-4</sup>
Bi-212 (a)		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	5.4X10 <sup>5</sup>	1.5X10 <sup>7</sup>
Bk-247	Berkelium (97)	8.0	2.2X10 <sup>2</sup>	8.0X10 <sup>-4</sup>	2.2X10 <sup>-2</sup>	3.8X10 <sup>-2</sup>	1.0
Bk-249 (a)		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	3.0X10 <sup>-1</sup>	8.1	6.1X10 <sup>1</sup>	1.6X10 <sup>3</sup>
Br-76	Bromine (35)	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	9.4X10 <sup>4</sup>	2.5X10 <sup>6</sup>
Br-77		3.0	8.1X10 <sup>1</sup>	3.0	8.1X10 <sup>1</sup>	2.6X10 <sup>4</sup>	7.1X10 <sup>5</sup>
Br-82		4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>4</sup>	1.1X10 <sup>6</sup>
C-11	Carbon (6)	1.0	2.7X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	3.1X10 <sup>7</sup>	8.4X10 <sup>8</sup>
C-14		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	3.0	8.1X10 <sup>1</sup>	1.6X10 <sup>-1</sup>	4.5
Ca-41	Calcium (20)	Unlimited	Unlimited	Unlimited	Unlimited	3.1X10 <sup>-3</sup>	8.5X10 <sup>-2</sup>
Ca-45		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	1.0	2.7X10 <sup>1</sup>	6.6X10 <sup>2</sup>	1.8X10 <sup>4</sup>
Ca-47 (a)		3.0	8.1X10 <sup>1</sup>	3.0X10 <sup>-1</sup>	8.1	2.3X10 <sup>4</sup>	6.1X10 <sup>5</sup>
Cd-109	Cadmium (48)	3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	2.0	5.4X10 <sup>1</sup>	9.6X10 <sup>1</sup>	2.6X10 <sup>3</sup>
Cd-113m		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	8.3	2.2X10 <sup>2</sup>
Cd-115 (a)		3.0	8.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	1.9X10 <sup>4</sup>	5.1X10 <sup>5</sup>
Cd-115m		5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	9.4X10 <sup>2</sup>	2.5X10 <sup>4</sup>
Ce-139	Cerium (58)	7.0	1.9X10 <sup>2</sup>	2.0	5.4X10 <sup>1</sup>	2.5X10 <sup>2</sup>	6.8X10 <sup>3</sup>
Ce-141		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	1.1X10 <sup>3</sup>	2.8X10 <sup>4</sup>
Ce-143		9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	2.5X10 <sup>4</sup>	6.6X10 <sup>5</sup>
Ce-144 (a)		2.0X10 <sup>-1</sup>	5.4	2.0X10 <sup>-1</sup>	5.4	1.2X10 <sup>2</sup>	3.2X10 <sup>3</sup>
Cf-248	Californium (98)	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	6.0X10 <sup>-3</sup>	1.6X10 <sup>-1</sup>	5.8X10 <sup>1</sup>	1.6X10 <sup>3</sup>
Cf-249		3.0	8.1X10 <sup>1</sup>	8.0X10 <sup>-4</sup>	2.2X10 <sup>-2</sup>	1.5X10 <sup>-1</sup>	4.1
Cf-250		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	2.0X10 <sup>-3</sup>	5.4X10 <sup>-2</sup>	4.0	1.1X10 <sup>2</sup>
Cf-251		7.0	1.9X10 <sup>2</sup>	7.0X10 <sup>-4</sup>	1.9X10 <sup>-2</sup>	5.9X10 <sup>-2</sup>	1.6
Cf-252 (h)		1.0 X 10 <sup>-1</sup>	2.7	3.0X10 <sup>-3</sup>	8.1X10 <sup>-2</sup>	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>
Cf-253 (a)		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	4.0X10 <sup>-2</sup>	1.1	1.1X10 <sup>3</sup>	2.9X10 <sup>4</sup>

**Table A-1—A<sub>1</sub> and A<sub>2</sub> VALUES FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	A <sub>1</sub> (TBq)	A <sub>1</sub> (Ci) <sup>b</sup>	A <sub>2</sub> (TBq)	A <sub>2</sub> (Ci) <sup>b</sup>	Specific activity	
						(TBq/g)	(Ci/g)
Cf-254		1.0X10 <sup>-3</sup>	2.7X10 <sup>-2</sup>	1.0X10 <sup>-3</sup>	2.7X10 <sup>-2</sup>	3.1X10 <sup>2</sup>	8.5X10 <sup>3</sup>
Cl-36	Chlorine (17)	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	1.2X10 <sup>-3</sup>	3.3X10 <sup>-2</sup>
Cl-38		2.0X10 <sup>-1</sup>	5.4	2.0X10 <sup>-1</sup>	5.4	4.9X10 <sup>6</sup>	1.3X10 <sup>8</sup>
Cm-240	Curium (96)	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	2.0X10 <sup>-2</sup>	5.4X10 <sup>-1</sup>	7.5X10 <sup>2</sup>	2.0X10 <sup>4</sup>
Cm-241		2.0	5.4X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	6.1X10 <sup>2</sup>	1.7X10 <sup>4</sup>
Cm-242		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	1.0X10 <sup>-2</sup>	2.7X10 <sup>-1</sup>	1.2X10 <sup>2</sup>	3.3X10 <sup>3</sup>
Cm-243		9.0	2.4X10 <sup>2</sup>	1.0X10 <sup>-3</sup>	2.7X10 <sup>-2</sup>	1.9X10 <sup>-3</sup>	5.2X10 <sup>1</sup>
Cm-244		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	2.0X10 <sup>-3</sup>	5.4X10 <sup>-2</sup>	3.0	8.1X10 <sup>1</sup>
Cm-245		9.0	2.4X10 <sup>2</sup>	9.0X10 <sup>-4</sup>	2.4X10 <sup>-2</sup>	6.4X10 <sup>-3</sup>	1.7X10 <sup>-1</sup>
Cm-246		9.0	2.4X10 <sup>2</sup>	9.0X10 <sup>-4</sup>	2.4X10 <sup>-2</sup>	1.1X10 <sup>-2</sup>	3.1X10 <sup>-1</sup>
Cm-247 (a)		3.0	8.1X10 <sup>1</sup>	1.0X10 <sup>-3</sup>	2.7X10 <sup>-2</sup>	3.4X10 <sup>-6</sup>	9.3X10 <sup>-5</sup>
Cm-248		2.0X10 <sup>-2</sup>	5.4X10 <sup>-1</sup>	3.0X10 <sup>-4</sup>	8.1X10 <sup>-3</sup>	1.6X10 <sup>-4</sup>	4.2X10 <sup>-3</sup>
Co-55	Cobalt (27)	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	1.1X10 <sup>5</sup>	3.1X10 <sup>6</sup>
Co-56		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	1.1X10 <sup>3</sup>	3.0X10 <sup>4</sup>
Co-57		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	3.1X10 <sup>2</sup>	8.4X10 <sup>3</sup>
Co-58		1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	1.2X10 <sup>3</sup>	3.2X10 <sup>4</sup>
Co-58m		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	2.2X10 <sup>5</sup>	5.9X10 <sup>6</sup>
Co-60		4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.2X10 <sup>1</sup>	1.1X10 <sup>3</sup>
Cr-51	Chromium (24)	3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	3.4X10 <sup>3</sup>	9.2X10 <sup>4</sup>
Cs-129	Cesium (55)	4.0	1.1X10 <sup>2</sup>	4.0	1.1X10 <sup>2</sup>	2.8X10 <sup>4</sup>	7.6X10 <sup>5</sup>
Cs-131		3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	3.8X10 <sup>3</sup>	1.0X10 <sup>5</sup>
Cs-132		1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	5.7X10 <sup>3</sup>	1.5X10 <sup>5</sup>
Cs-134		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	4.8X10 <sup>1</sup>	1.3X10 <sup>3</sup>
Cs-134m		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	3.0X10 <sup>5</sup>	8.0X10 <sup>6</sup>
Cs-135		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	1.0	2.7X10 <sup>1</sup>	4.3X10 <sup>-5</sup>	1.2X10 <sup>-3</sup>
Cs-136		5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	2.7X10 <sup>3</sup>	7.3X10 <sup>4</sup>
Cs-137 (a)		2.0	5.4X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	3.2	8.7X10 <sup>1</sup>
Cu-64	Copper (29)	6.0	1.6X10 <sup>2</sup>	1.0	2.7X10 <sup>1</sup>	1.4X10 <sup>5</sup>	3.9X10 <sup>6</sup>
Cu-67		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	2.8X10 <sup>4</sup>	7.6X10 <sup>5</sup>
Dy-159	Dysprosium (66)	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	2.1X10 <sup>2</sup>	5.7X10 <sup>3</sup>

**Table A-1—A<sub>1</sub> and A<sub>2</sub> VALUES FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	A <sub>1</sub> (TBq)	A <sub>1</sub> (Ci) <sup>b</sup>	A <sub>2</sub> (TBq)	A <sub>2</sub> (Ci) <sup>b</sup>	Specific activity	
						(TBq/g)	(Ci/g)
Dy-165		9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	3.0X10 <sup>5</sup>	8.2X10 <sup>6</sup>
Dy-166 (a)		9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	3.0X10 <sup>-1</sup>	8.1	8.6X10 <sup>3</sup>	2.3X10 <sup>5</sup>
Er-169	Erbium (68)	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	1.0	2.7X10 <sup>1</sup>	3.1X10 <sup>3</sup>	8.3X10 <sup>4</sup>
Er-171		8.0X10 <sup>-1</sup>	2.2X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	9.0X10 <sup>4</sup>	2.4X10 <sup>6</sup>
Eu-147	Europium (63)	2.0	5.4X10 <sup>1</sup>	2.0	5.4X10 <sup>1</sup>	1.4X10 <sup>3</sup>	3.7X10 <sup>4</sup>
Eu-148		5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	6.0X10 <sup>2</sup>	1.6X10 <sup>4</sup>
Eu-149		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	3.5X10 <sup>2</sup>	9.4X10 <sup>3</sup>
Eu-150 (short lived)		2.0	5.4X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	6.1X10 <sup>4</sup>	1.6X10 <sup>6</sup>
Eu-150 (long lived)		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	6.1X10 <sup>4</sup>	1.6X10 <sup>6</sup>
Eu-152		1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	6.5	1.8X10 <sup>2</sup>
Eu-152m		8.0X10 <sup>-1</sup>	2.2X10 <sup>1</sup>	8.0X10 <sup>-1</sup>	2.2X10 <sup>1</sup>	8.2X10 <sup>4</sup>	2.2X10 <sup>6</sup>
Eu-154		9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	9.8	2.6X10 <sup>2</sup>
Eu-155		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	3.0	8.1X10 <sup>1</sup>	1.8X10 <sup>1</sup>	4.9X10 <sup>2</sup>
Eu-156		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	2.0X10 <sup>3</sup>	5.5X10 <sup>4</sup>
F-18	Fluorine (9)	1.0	2.7X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	3.5X10 <sup>6</sup>	9.5X10 <sup>7</sup>
Fe-52 (a)	Iron (26)	3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	2.7X10 <sup>5</sup>	7.3X10 <sup>6</sup>
Fe-55		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	8.8X10 <sup>1</sup>	2.4X10 <sup>3</sup>
Fe-59		9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	1.8X10 <sup>3</sup>	5.0X10 <sup>4</sup>
Fe-60 (a)		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	2.0X10 <sup>-1</sup>	5.4	7.4X10 <sup>-4</sup>	2.0X10 <sup>-2</sup>
Ga-67	Gallium (31)	7.0	1.9X10 <sup>2</sup>	3.0	8.1X10 <sup>1</sup>	2.2X10 <sup>4</sup>	6.0X10 <sup>5</sup>
Ga-68		5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	1.5X10 <sup>6</sup>	4.1X10 <sup>7</sup>
Ga-72		4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	1.1X10 <sup>5</sup>	3.1X10 <sup>6</sup>
Gd-146 (a)	Gadolinium (64)	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	6.9X10 <sup>2</sup>	1.9X10 <sup>4</sup>
Gd-148		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	2.0X10 <sup>-3</sup>	5.4X10 <sup>-2</sup>	1.2	3.2X10 <sup>1</sup>
Gd-153		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	9.0	2.4X10 <sup>2</sup>	1.3X10 <sup>2</sup>	3.5X10 <sup>3</sup>
Gd-159		3.0	8.1X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	3.9X10 <sup>4</sup>	1.1X10 <sup>6</sup>
Ge-68 (a)	Germanium (32)	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	2.6X10 <sup>2</sup>	7.1X10 <sup>3</sup>
Ge-71		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	5.8X10 <sup>3</sup>	1.6X10 <sup>5</sup>
Ge-77		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	1.3X10 <sup>5</sup>	3.6X10 <sup>6</sup>

**Table A-1—A<sub>1</sub> and A<sub>2</sub> VALUES FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	A <sub>1</sub> (TBq)	A <sub>1</sub> (Ci) <sup>b</sup>	A <sub>2</sub> (TBq)	A <sub>2</sub> (Ci) <sup>b</sup>	Specific activity	
						(TBq/g)	(Ci/g)
Hf-172 (a)	Hafnium (72)	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	4.1X10 <sup>1</sup>	1.1X10 <sup>3</sup>
Hf-175		3.0	8.1X10 <sup>1</sup>	3.0	8.1X10 <sup>1</sup>	3.9X10 <sup>2</sup>	1.1X10 <sup>4</sup>
Hf-181		2.0	5.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	6.3X10 <sup>2</sup>	1.7X10 <sup>4</sup>
Hf-182		Unlimited	Unlimited	Unlimited	Unlimited	8.1X10 <sup>-6</sup>	2.2X10 <sup>-4</sup>
Hg-194 (a)	Mercury (80)	1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	1.3X10 <sup>-1</sup>	3.5
Hg-195m (a)		3.0	8.1X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	1.5X10 <sup>4</sup>	4.0X10 <sup>5</sup>
Hg-197		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	9.2X10 <sup>3</sup>	2.5X10 <sup>5</sup>
Hg-197m		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	2.5X10 <sup>4</sup>	6.7X10 <sup>5</sup>
Hg-203		5.0	1.4X10 <sup>2</sup>	1.0	2.7X10 <sup>1</sup>	5.1X10 <sup>2</sup>	1.4X10 <sup>4</sup>
Ho-166	Holmium (67)	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	2.6X10 <sup>4</sup>	7.0X10 <sup>5</sup>
Ho-166m		6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	6.6X10 <sup>-2</sup>	1.8
I-123	Iodine (53)	6.0	1.6X10 <sup>2</sup>	3.0	8.1X10 <sup>1</sup>	7.1X10 <sup>4</sup>	1.9X10 <sup>6</sup>
I-124		1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	9.3X10 <sup>3</sup>	2.5X10 <sup>5</sup>
I-125		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	3.0	8.1X10 <sup>1</sup>	6.4X10 <sup>2</sup>	1.7X10 <sup>4</sup>
I-126		2.0	5.4X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	2.9X10 <sup>3</sup>	8.0X10 <sup>4</sup>
I-129		Unlimited	Unlimited	Unlimited	Unlimited	6.5X10 <sup>-6</sup>	1.8X10 <sup>-4</sup>
I-131		3.0	8.1X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	4.6X10 <sup>3</sup>	1.2X10 <sup>5</sup>
I-132		4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	3.8X10 <sup>5</sup>	1.0X10 <sup>7</sup>
I-133		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	4.2X10 <sup>4</sup>	1.1X10 <sup>6</sup>
I-134		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	9.9X10 <sup>5</sup>	2.7X10 <sup>7</sup>
I-135 (a)		6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	1.3X10 <sup>5</sup>	3.5X10 <sup>6</sup>
In-111	Indium (49)	3.0	8.1X10 <sup>1</sup>	3.0	8.1X10 <sup>1</sup>	1.5X10 <sup>4</sup>	4.2X10 <sup>5</sup>
In-113m		4.0	1.1X10 <sup>2</sup>	2.0	5.4X10 <sup>1</sup>	6.2X10 <sup>5</sup>	1.7X10 <sup>7</sup>
In-114m (a)		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	8.6X10 <sup>2</sup>	2.3X10 <sup>4</sup>
In-115m		7.0	1.9X10 <sup>2</sup>	1.0	2.7X10 <sup>1</sup>	2.2X10 <sup>5</sup>	6.1X10 <sup>6</sup>
Ir-189 (a)	Iridium (77)	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	1.9X10 <sup>3</sup>	5.2X10 <sup>4</sup>
Ir-190		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	2.3X10 <sup>3</sup>	6.2X10 <sup>4</sup>
Ir-192-(e)		(c)1.0	(c)2.7X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	3.4X10 <sup>2</sup>	9.2X10 <sup>3</sup>
Ir-194		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	3.1X10 <sup>4</sup>	8.4X10 <sup>5</sup>
K-40	Potassium (19)	9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	2.4X10 <sup>-7</sup>	6.4X10 <sup>-6</sup>

**Table A-1—A<sub>1</sub> and A<sub>2</sub> VALUES FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	A <sub>1</sub> (TBq)	A <sub>1</sub> (Ci) <sup>b</sup>	A <sub>2</sub> (TBq)	A <sub>2</sub> (Ci) <sup>b</sup>	Specific activity	
						(TBq/g)	(Ci/g)
K-42		2.0X10 <sup>-1</sup>	5.4	2.0X10 <sup>-1</sup>	5.4	2.2X10 <sup>5</sup>	6.0X10 <sup>6</sup>
K-43		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	1.2X10 <sup>5</sup>	3.3X10 <sup>6</sup>
<u>Kr-79</u>	<u>Krypton (36)</u>	<u>4.0</u>	<u>1.1 X 10<sup>2</sup></u>	<u>2.0</u>	<u>5.4 X 10<sup>1</sup></u>	<u>4.2 X 10<sup>4</sup></u>	<u>1.1 X 10<sup>6</sup></u>
Kr-81	<u>Krypton (36)</u>	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	7.8X10 <sup>-4</sup>	2.1X10 <sup>-2</sup>
Kr-85		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	1.5X10 <sup>1</sup>	3.9X10 <sup>2</sup>
Kr-85m		8.0	2.2X10 <sup>2</sup>	3.0	8.1X10 <sup>1</sup>	3.0X10 <sup>5</sup>	8.2X10 <sup>6</sup>
Kr-87		2.0X10 <sup>-1</sup>	5.4	2.0X10 <sup>-1</sup>	5.4	1.0X10 <sup>6</sup>	2.8X10 <sup>7</sup>
La-137	Lanthanum (57)	3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	6.0	1.6X10 <sup>2</sup>	1.6X10 <sup>-3</sup>	4.4X10 <sup>-2</sup>
La-140		4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	2.1X10 <sup>4</sup>	5.6X10 <sup>5</sup>
Lu-172	Lutetium (71)	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	4.2X10 <sup>3</sup>	1.1X10 <sup>5</sup>
Lu-173		8.0	2.2X10 <sup>2</sup>	8.0	2.2X10 <sup>2</sup>	5.6X10 <sup>1</sup>	1.5X10 <sup>3</sup>
Lu-174		9.0	2.4X10 <sup>2</sup>	9.0	2.4X10 <sup>2</sup>	2.3X10 <sup>1</sup>	6.2X10 <sup>2</sup>
Lu-174m		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	2.0X10 <sup>2</sup>	5.3X10 <sup>3</sup>
Lu-177		3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	4.1X10 <sup>3</sup>	1.1X10 <sup>5</sup>
Mg-28 (a)	Magnesium (12)	3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	2.0X10 <sup>5</sup>	5.4X10 <sup>6</sup>
Mn-52	Manganese (25)	3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	1.6X10 <sup>4</sup>	4.4X10 <sup>5</sup>
Mn-53		Unlimited	Unlimited	Unlimited	Unlimited	6.8X10 <sup>-5</sup>	1.8X10 <sup>-3</sup>
Mn-54		1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	2.9X10 <sup>2</sup>	7.7X10 <sup>3</sup>
Mn-56		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	8.0X10 <sup>5</sup>	2.2X10 <sup>7</sup>
Mo-93	Molybdenum (42)	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	4.1X10 <sup>-2</sup>	1.1
Mo-99 (a) (ih)		1.0	2.7X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	1.8X10 <sup>4</sup>	4.8X10 <sup>5</sup>
N-13	Nitrogen (7)	9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	5.4X10 <sup>7</sup>	1.5X10 <sup>9</sup>
Na-22	Sodium (11)	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	2.3X10 <sup>2</sup>	6.3X10 <sup>3</sup>
Na-24		2.0X10 <sup>-1</sup>	5.4	2.0X10 <sup>-1</sup>	5.4	3.2X10 <sup>5</sup>	8.7X10 <sup>6</sup>
Nb-93m	Niobium (41)	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	8.8	2.4X10 <sup>2</sup>
Nb-94		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	6.9X10 <sup>-3</sup>	1.9X10 <sup>-1</sup>
Nb-95		1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	1.5X10 <sup>3</sup>	3.9X10 <sup>4</sup>
Nb-97		9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	9.9X10 <sup>5</sup>	2.7X10 <sup>7</sup>
Nd-147	Neodymium (60)	6.0	1.6X10 <sup>2</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	3.0X10 <sup>3</sup>	8.1X10 <sup>4</sup>
Nd-149		6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	4.5X10 <sup>5</sup>	1.2X10 <sup>7</sup>
Ni-59	Nickel (28)	Unlimited	Unlimited	Unlimited	Unlimited	3.0X10 <sup>-3</sup>	8.0X10 <sup>-2</sup>

**Table A-1—A<sub>1</sub> and A<sub>2</sub> VALUES FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	A <sub>1</sub> (TBq)	A <sub>1</sub> (Ci) <sup>b</sup>	A <sub>2</sub> (TBq)	A <sub>2</sub> (Ci) <sup>b</sup>	Specific activity	
						(TBq/g)	(Ci/g)
Ni-63		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	2.1	5.7X10 <sup>1</sup>
Ni-65		4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	7.1X10 <sup>5</sup>	1.9X10 <sup>7</sup>
Np-235	Neptunium (93)	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	5.2X10 <sup>1</sup>	1.4X10 <sup>3</sup>
Np-236 (short-lived)		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	2.0	5.4X10 <sup>1</sup>	4.7X10 <sup>-4</sup>	1.3X10 <sup>-2</sup>
Np-236 (long-lived)		9.0X10 <sup>0</sup>	2.4X10 <sup>2</sup>	2.0X10 <sup>-2</sup>	5.4X10 <sup>-1</sup>	4.7X10 <sup>-4</sup>	1.3X10 <sup>-2</sup>
Np-237		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	2.0X10 <sup>-3</sup>	5.4X10 <sup>-2</sup>	2.6X10 <sup>-5</sup>	7.1X10 <sup>-4</sup>
Np-239		7.0	1.9X10 <sup>2</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	8.6X10 <sup>3</sup>	2.3X10 <sup>5</sup>
Os-185	Osmium (76)	1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	2.8X10 <sup>2</sup>	7.5X10 <sup>3</sup>
Os-191		1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	2.0	5.4X10 <sup>1</sup>	1.6X10 <sup>3</sup>	4.4X10 <sup>4</sup>
Os-191m		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	4.6X10 <sup>4</sup>	1.3X10 <sup>6</sup>
Os-193		2.0	5.4X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	2.0X10 <sup>4</sup>	5.3X10 <sup>5</sup>
Os-194 (a)		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	1.1X10 <sup>1</sup>	3.1X10 <sup>2</sup>
P-32	Phosphorus (15)	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	1.1X10 <sup>4</sup>	2.9X10 <sup>5</sup>
P-33		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	1.0	2.7X10 <sup>1</sup>	5.8X10 <sup>3</sup>	1.6X10 <sup>5</sup>
Pa-230 (a)	Protactinium (91)	2.0	5.4X10 <sup>1</sup>	7.0X10 <sup>-2</sup>	1.9	1.2X10 <sup>3</sup>	3.3X10 <sup>4</sup>
Pa-231		4.0	1.1X10 <sup>2</sup>	4.0X10 <sup>-4</sup>	1.1X10 <sup>-2</sup>	1.7X10 <sup>-3</sup>	4.7X10 <sup>-2</sup>
Pa-233		5.0	1.4X10 <sup>2</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.7X10 <sup>2</sup>	2.1X10 <sup>4</sup>
Pb-201	Lead (82)	1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	6.2X10 <sup>4</sup>	1.7X10 <sup>6</sup>
Pb-202		4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	1.2X10 <sup>-4</sup>	3.4X10 <sup>-3</sup>
Pb-203		4.0	1.1X10 <sup>2</sup>	3.0	8.1X10 <sup>1</sup>	1.1X10 <sup>4</sup>	3.0X10 <sup>5</sup>
Pb-205		Unlimited	Unlimited	Unlimited	Unlimited	4.5X10 <sup>-6</sup>	1.2X10 <sup>-4</sup>
Pb-210 (a)		1.0	2.7X10 <sup>1</sup>	5.0X10 <sup>-2</sup>	1.4	2.8	7.6X10 <sup>1</sup>
Pb-212 (a)		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	2.0X10 <sup>-1</sup>	5.4	5.1X10 <sup>4</sup>	1.4X10 <sup>6</sup>
Pd-103 (a)	Palladium (46)	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	4.0X10 <sup>1</sup>	1.1X10 <sup>3</sup>	2.8X10 <sup>3</sup>	7.5X10 <sup>4</sup>
Pd-107		Unlimited	Unlimited	Unlimited	Unlimited	1.9X10 <sup>-5</sup>	5.1X10 <sup>-4</sup>
Pd-109		2.0	5.4X10 <sup>1</sup>	5.0X10 <sup>-1</sup>	1.4X10 <sup>1</sup>	7.9X10 <sup>4</sup>	2.1X10 <sup>6</sup>
Pm-143	Promethium (61)	3.0	8.1X10 <sup>1</sup>	3.0	8.1X10 <sup>1</sup>	1.3X10 <sup>2</sup>	3.4X10 <sup>3</sup>
Pm-144		7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	7.0X10 <sup>-1</sup>	1.9X10 <sup>1</sup>	9.2X10 <sup>1</sup>	2.5X10 <sup>3</sup>
Pm-145		3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	5.2	1.4X10 <sup>2</sup>

**Table A-1—A<sub>1</sub> and A<sub>2</sub> VALUES FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	A <sub>1</sub> (TBq)	A <sub>1</sub> (Ci) <sup>b</sup>	A <sub>2</sub> (TBq)	A <sub>2</sub> (Ci) <sup>b</sup>	Specific activity	
						(TBq/g)	(Ci/g)
Xe-133		2.0X10 <sup>1</sup>	5.4X10 <sup>2</sup>	1.0X10 <sup>1</sup>	2.7X10 <sup>2</sup>	6.9X10 <sup>3</sup>	1.9X10 <sup>5</sup>
Xe-135		3.0	8.1X10 <sup>1</sup>	2.0	5.4X10 <sup>1</sup>	9.5X10 <sup>4</sup>	2.6X10 <sup>6</sup>
Y-87 (a)	Yttrium (39)	1.0	2.7X10 <sup>1</sup>	1.0	2.7X10 <sup>1</sup>	1.7X10 <sup>4</sup>	4.5X10 <sup>5</sup>
Y-88		4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	5.2X10 <sup>2</sup>	1.4X10 <sup>4</sup>
Y-90		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	2.0X10 <sup>4</sup>	5.4X10 <sup>5</sup>
Y-91		6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	9.1X10 <sup>2</sup>	2.5X10 <sup>4</sup>
Y-91m		2.0	5.4X10 <sup>1</sup>	2.0	5.4X10 <sup>1</sup>	1.5X10 <sup>6</sup>	4.2X10 <sup>7</sup>
Y-92		2.0X10 <sup>-1</sup>	5.4	2.0X10 <sup>-1</sup>	5.4	3.6X10 <sup>5</sup>	9.6X10 <sup>6</sup>
Y-93		3.0X10 <sup>-1</sup>	8.1	3.0X10 <sup>-1</sup>	8.1	1.2X10 <sup>5</sup>	3.3X10 <sup>6</sup>
Yb-169	Ytterbium (70)	4.0	1.1X10 <sup>2</sup>	1.0	2.7X10 <sup>1</sup>	8.9X10 <sup>2</sup>	2.4X10 <sup>4</sup>
Yb-175		3.0X10 <sup>1</sup>	8.1X10 <sup>2</sup>	9.0X10 <sup>-1</sup>	2.4X10 <sup>1</sup>	6.6X10 <sup>3</sup>	1.8X10 <sup>5</sup>
Zn-65	Zinc (30)	2.0	5.4X10 <sup>1</sup>	2.0	5.4X10 <sup>1</sup>	3.0X10 <sup>2</sup>	8.2X10 <sup>3</sup>
Zn-69		3.0	8.1X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	1.8X10 <sup>6</sup>	4.9X10 <sup>7</sup>
Zn-69m (a)		3.0	8.1X10 <sup>1</sup>	6.0X10 <sup>-1</sup>	1.6X10 <sup>1</sup>	1.2X10 <sup>5</sup>	3.3X10 <sup>6</sup>
Zr-88	Zirconium (40)	3.0	8.1X10 <sup>1</sup>	3.0	8.1X10 <sup>1</sup>	6.6X10 <sup>2</sup>	1.8X10 <sup>4</sup>
Zr-93		Unlimited	Unlimited	Unlimited	Unlimited	9.3X10 <sup>-5</sup>	2.5X10 <sup>-3</sup>
Zr-95 (a)		2.0	5.4X10 <sup>1</sup>	8.0X10 <sup>-1</sup>	2.2X10 <sup>1</sup>	7.9X10 <sup>2</sup>	2.1X10 <sup>4</sup>
Zr-97 (a)		4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	4.0X10 <sup>-1</sup>	1.1X10 <sup>1</sup>	7.1X10 <sup>4</sup>	1.9X10 <sup>6</sup>

<sup>a</sup> A<sub>1</sub> and/or A<sub>2</sub> values include contributions from daughter nuclides with half-lives less than 10 days, as listed in the following:-

Mg-28	Al-28
Ca-47	Sc-47
Ti-44	Sc-44
Fe-52	Mn-52m
Fe-60	Co-60m
Zn-69m	Zn-69
Ge-68	Ga-68
Rb-83	Kr-83m
Sr-82	Rb-82
Sr-90	Y-90
Sr-91	Y-91m
Sr-92	Y-92
Y-87	Sr-87m
Zr-95	Nb-95m
Zr-97	Nb-97m, Nb-97
Mo-99	Tc-99m
Tc-95m	Tc-95

**Commented [mdk43]:** All new material RATS 2015-3

Tc-96m	Tc-96
Ru-106	Rh-106
Pd-103	Rh-103m
Ag-108m	Ag-108
Ag-110m	Ag-110
Cd-115	In-115m
In-114m	In-114
Sn-113	In-113m
Sn-121m	Sn-121
Sn-126	Sb-126m
Te-127m	Te-127
Te-129m	Te-129
Te-131m	Te-131
Te-132	I-132
I-135	Xe-135m
Xe-122	I-122
Cs-137	Ba-137m
Ba-131	Cs-131
Ba-140	La-140
Ce-144	Pr-144m, Pr-144
Pm-148m	Pm-148
Gd-146	Eu-146
Dy-166	Ho-166
Hf-172	Lu-172
W-178	Ta-178
W-188	Re-188
Re-189	Os-189m
Os-194	Ir-194
Ir-189	Os-189m
Pt-188	Ir-188
Hg-194	Au-194
Hg-195m	Hg-195
Pb-210	Bi-210
Pb-212	Bi-212, Tl-208, Po-212
Bi-210m	Tl-206
Bi-212	Tl-208, Po-212
At-211	Po-211
Rn-222	Po-218, Pb-214, At-218, Bi-214, Po-214
Ra-223	Rn-219, Po-215, Pb-211, Bi-211, Po-211, Tl-207
Ra-224	Rn-220, Po-216, Pb-212, Bi-212, Tl-208, Po-212
Ra-225	Ac-225, Fr-221, At-217, Bi-213, Tl-209, Po-213, Pb-209
Ra-226	Rn-222, Po-218, Pb-214, At-218, Bi-214, Po-214
Ra-228	Ac-228
Ac-225	Fr-221, At-217, Bi-213, Tl-209, Po-213, Pb-209
Ac-227	Fr-223
Th-228	Ra-224, Rn-220, Po-216, Pb-212, Bi-212, Tl-208, Po-212
Th-234	Pa-234m, Pa-234
Pa-230	Ac-226, Th-226, Fr-222, Ra-222, Rn-218, Po-214
U-230	Th-226, Ra-222, Rn-218, Po-214
U-235	Th-231
Pu-241	U-237
Pu-244	U-240, Np-240m
Am-242m	Am-242, Np-238
Am-243	Np-239
Cm-247	Pu-243
Bk-249	Am-245
Cf-253	Cm-249

[Supp. 28](#)

[T39-1](#)



<sup>b</sup> The values of  $A_1$  and  $A_2$  in Curies (Ci) are approximate and for information only; the regulatory standard units are Terabecquerels (TBq); (see Appendix A to Part 71 - Determination of  $A_1$  and  $A_2$ , Section I.).

<sup>c</sup> The ~~activity of Ir-192 in special form quantity~~ may be determined from a measurement of the rate of decay or a measurement of the radiation level at a prescribed distance from the source.

<sup>d</sup> These values apply only to compounds of uranium that take the chemical form of  $UF_6$ ,  $UO_2F_2$  and  $UO_2(NO_3)_2$  in both normal and accident conditions of transport.

<sup>e</sup> These values apply only to compounds of uranium that take the chemical form of  $UO_3$ ,  $UF_4$ ,  $UCl_4$  and hexavalent compounds in both normal and accident conditions of transport.

<sup>f</sup> These values apply to all compounds of uranium other than those specified in notes (d) and (e) of this table.

<sup>g</sup> These values apply to unirradiated uranium only.

~~<sup>h</sup>  $A_1 = 0.1$  TBq (2.7 Ci) and  $A_2 = 0.001$  TBq (0.027 Ci) for Cf-252 for domestic use.~~

~~<sup>i</sup>  $A_2 = 0.74$  TBq (20 Ci) for Mo-99 for domestic use.~~

**Table A-2—EXEMPT MATERIAL ACTIVITY CONCENTRATIONS AND EXEMPT CONSIGNMENT ACTIVITY LIMITS FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	Activity concentration for exempt material (Bq/g)	Activity concentration for exempt material (Ci/g)	Activity limit for exempt consignment (Bq)	Activity limit for exempt consignment (Ci)
Ac-225	Actinium (89)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Ac-227		1.0X10 <sup>-1</sup>	2.7X10 <sup>-12</sup>	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>
Ac-228		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ag-105	Silver (47)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ag-108m (b)		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ag-110m		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ag-111		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Al-26	Aluminum (13)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Am-241	Americium (95)	1.0	2.7X10 <sup>-11</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Am-242m (b)		1.0	2.7X10 <sup>-11</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Am-243 (b)		1.0	2.7X10 <sup>-11</sup>	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>
Ar-37	Argon (18)	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>	1.0X10 <sup>8</sup>	2.7X10 <sup>-3</sup>
Ar-39		1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Ar-41		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>9</sup>	2.7X10 <sup>-2</sup>
As-72	Arsenic (33)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
As-73		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
As-74		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
As-76		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
As-77		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
At-211	Astatine (85)	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Au-193	Gold (79)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Au-194		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Au-195		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Au-198		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Au-199		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ba-131	Barium (56)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ba-133		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ba-133m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ba-140 (b)		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>

**Table A-2—EXEMPT MATERIAL ACTIVITY CONCENTRATIONS AND EXEMPT CONSIGNMENT ACTIVITY LIMITS FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	Activity concentration for exempt material (Bq/g)	Activity concentration for exempt material (Ci/g)	Activity limit for exempt consignment (Bq)	Activity limit for exempt consignment (Ci)
In-115m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ir-189	Iridium (77)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Ir-190		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ir-192		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Ir-194		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
K-40	Potassium (19)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
K-42		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
K-43		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
<u>Kr-79</u>	<u>Krypton (36)</u>	<u>1.0X10<sup>3</sup></u>	<u>2.7X10<sup>-8</sup></u>	<u>1.0X10<sup>5</sup></u>	<u>2.7X10<sup>-6</sup></u>
Kr-81	<u>Krypton (36)</u>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Kr-85		1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Kr-85m		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>10</sup>	2.7X10 <sup>-1</sup>
Kr-87		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>9</sup>	2.7X10 <sup>-2</sup>
La-137	Lanthanum (57)	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
La-140		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Lu-172	Lutetium (71)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Lu-173		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Lu-174		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Lu-174m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Lu-177		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Mg-28	Magnesium (12)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Mn-52	Manganese (25)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Mn-53		1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>9</sup>	2.7X10 <sup>-2</sup>
Mn-54		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Mn-56		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Mo-93	Molybdenum (42)	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>8</sup>	2.7X10 <sup>-3</sup>
Mo-99		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
N-13	Nitrogen (7)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>9</sup>	2.7X10 <sup>-2</sup>
Na-22	Sodium (11)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Na-24		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>

**Table A-2—EXEMPT MATERIAL ACTIVITY CONCENTRATIONS AND EXEMPT CONSIGNMENT ACTIVITY LIMITS FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	Activity concentration for exempt material (Bq/g)	Activity concentration for exempt material (Ci/g)	Activity limit for exempt consignment (Bq)	Activity limit for exempt consignment (Ci)
Nb-93m	Niobium (41)	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Nb-94		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Nb-95		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Nb-97		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Nd-147	Neodymium (60)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Nd-149		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ni-59	Nickel (28)	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>8</sup>	2.7X10 <sup>-3</sup>
Ni-63		1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>	1.0X10 <sup>8</sup>	2.7X10 <sup>-3</sup>
Ni-65		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Np-235	Neptunium (93)	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Np-236 (short-lived)		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Np-236 (long-lived)		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Np-237 (b)		1.0	2.7X10 <sup>-11</sup>	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>
Np-239		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Os-185	Osmium (76)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Os-191		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Os-191m		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Os-193		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Os-194		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
P-32	Phosphorus (15)	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
P-33		1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>	1.0X10 <sup>8</sup>	2.7X10 <sup>-3</sup>
Pa-230	Protactinium (91)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Pa-231		1.0	2.7X10 <sup>-11</sup>	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>
Pa-233		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Pb-201	Lead (82)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Pb-202		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Pb-203		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Pb-205		1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>

**Table A-2—EXEMPT MATERIAL ACTIVITY CONCENTRATIONS AND EXEMPT CONSIGNMENT ACTIVITY LIMITS FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	Activity concentration for exempt material (Bq/g)	Activity concentration for exempt material (Ci/g)	Activity limit for exempt consignment (Bq)	Activity limit for exempt consignment (Ci)
Ru-106 (b)		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
S-35	Sulphur (16)	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>	1.0X10 <sup>8</sup>	2.7X10 <sup>-3</sup>
Sb-122	Antimony (51)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Sb-124		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sb-125		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sb-126		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Sc-44	Scandium (21)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Sc-46		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sc-47		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sc-48		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Se-75	Selenium (34)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Se-79		1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Si-31	Silicon (14)	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Si-32		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sm-145	Samarium (62)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Sm-147		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Sm-151		1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>8</sup>	2.7X10 <sup>-3</sup>
Sm-153		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sn-113	Tin (50)	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Sn-117m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sn-119m		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Sn-121m		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Sn-123		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sn-125		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Sn-126		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Sr-82	Strontium (38)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Sr-85		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sr-85m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Sr-87m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>

**Table A-2—EXEMPT MATERIAL ACTIVITY CONCENTRATIONS AND EXEMPT CONSIGNMENT ACTIVITY LIMITS FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	Activity concentration for exempt material (Bq/g)	Activity concentration for exempt material (Ci/g)	Activity limit for exempt consignment (Bq)	Activity limit for exempt consignment (Ci)
Sr-89		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Sr-90 (b)		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Sr-91		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Sr-92		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
T(H-3)	Tritium (1)	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>	1.0X10 <sup>9</sup>	2.7X10 <sup>-2</sup>
Ta-178 (long-lived)	Tantalum (73)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Ta-179		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Ta-182		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Tb-157	Terbium (65)	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Tb-158		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Tb-160		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Tc-95m	Technetium (43)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Tc-96		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Tc-96m		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Tc-97		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>8</sup>	2.7X10 <sup>-3</sup>
Tc-97m		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Tc-98		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Tc-99		1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Tc-99m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Te-121	Tellurium (52)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Te-121m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup> 1.0X10 <sup>6</sup>	2.7X10 <sup>-6-5</sup>
Te-123m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Te-125m		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Te-127		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Te-127m		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Te-129		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Te-129m		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Te-131m		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Te-132		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>

**Table A-2—EXEMPT MATERIAL ACTIVITY CONCENTRATIONS AND EXEMPT CONSIGNMENT ACTIVITY LIMITS FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	Activity concentration for exempt material (Bq/g)	Activity concentration for exempt material (Ci/g)	Activity limit for exempt consignment (Bq)	Activity limit for exempt consignment (Ci)
U (enriched to 20% or less) (g)		1.0	2.7X10 <sup>-11</sup>	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>
U (dep)		1.0	2.7X10 <sup>-11</sup>	1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>
V-48	Vanadium (23)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
V-49		1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
W-178	Tungsten (74)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
W-181		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
W-185		1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
W-187		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
W-188		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Xe-122	Xenon (54)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>9</sup>	2.7X10 <sup>-2</sup>
Xe-123		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>9</sup>	2.7X10 <sup>-2</sup>
Xe-127		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Xe-131m		1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Xe-133		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>
Xe-135		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>10</sup>	2.7X10 <sup>-1</sup>
Y-87	Yttrium (39)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Y-88		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Y-90		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Y-91		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Y-91m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Y-92		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Y-93		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>
Yb-169	Ytterbium (70)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Yb-175		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Zn-65	Zinc (30)	1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Zn-69		1.0X10 <sup>4</sup>	2.7X10 <sup>-7</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Zn-69m		1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Zr-88	Zirconium (40)	1.0X10 <sup>2</sup>	2.7X10 <sup>-9</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>

**Table A-2—EXEMPT MATERIAL ACTIVITY CONCENTRATIONS AND EXEMPT CONSIGNMENT ACTIVITY LIMITS FOR RADIONUCLIDES**

Symbol of radionuclide	Element and atomic number	Activity concentration for exempt material (Bq/g)	Activity concentration for exempt material (Ci/g)	Activity limit for exempt consignment (Bq)	Activity limit for exempt consignment (Ci)
Zr-93 (b)		1.0X10 <sup>3</sup>	2.7X10 <sup>-8</sup>	1.0X10 <sup>7</sup>	2.7X10 <sup>-4</sup>
Zr-95		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>6</sup>	2.7X10 <sup>-5</sup>
Zr-97 (b)		1.0X10 <sup>1</sup>	2.7X10 <sup>-10</sup>	1.0X10 <sup>5</sup>	2.7X10 <sup>-6</sup>

<sup>a</sup> [Reserved]

<sup>b</sup> Parent nuclides and their progeny included in secular equilibrium are listed in the following as follows:

Commented [mdk44]: RATS 2015-3

Sr-90	Y-90
Zr-93	Nb-93m
Zr-97	Nb-97
Ru-106	Rh-106
<del>Ag-108m</del>	<del>Ag-108</del>
Cs-137	Ba-137m
<del>Ce-134</del>	<del>La-134</del>
Ce-144	Pr-144
Ba-140	La-140
Bi-212	Tl-208 (0.36), Po-212 (0.64)
Pb-210	Bi-210, Po-210
Pb-212	Bi-212, Tl-208 (0.36), Po-212 (0.64)
<del>Rn-220</del>	<del>Po-216</del>
Rn-222	Po-218, Pb-214, Bi-214, Po-214
Ra-223	Rn-219, Po-215, Pb-211, Bi-211, Tl-207
Ra-224	Rn-220, Po-216, Pb-212, Bi-212, Tl-208 (0.36), Po-212 (0.64)
Ra-226	Rn-222, Po-218, Pb-214, Bi-214, Po-214, Pb-210, Bi-210, Po-210
Ra-228	Ac-228
<del>Th-226</del>	<del>Ra-222, Rn-218, Po-214</del>
Th-228	Ra-224, Rn-220, Po-216, Pb-212, Bi-212, Tl-208 (0.36), Po-212 (0.64)
Th-229	Ra-225, Ac-225, Fr-221, At-217, Bi-213, Po-213, Pb-209
Th-nat	Ra-228, Ac-228, Th-228, Ra-224, Rn-220, Po-216, Pb-212, Bi-212, Tl-208 (0.36), Po-212 (0.64)
Th-234	Pa-234m
U-230	Th-226, Ra-222, Rn-218, Po-214
U-232	Th-228, Ra-224, Rn-220, Po-216, Pb-212, Bi-212, Tl-208 (0.36), Po-212 (0.64)
U-235	Th-231
U-238	Th-234, Pa-234m

Supp. 4628

T54



U-nat	Th-234, Pa-234m, U-234, Th-230, Ra-226, Rn-222, Po-218, Pb-214, Bi-214, Po-214, Pb-210, Bi-210, Po-210
<del>U-240</del>	<del>Np-240m</del>
Np-237	Pa-233
Am-242m	Am-242
Am-243	Np-239

<sup>c</sup> [Reserved]

<sup>d</sup> These values apply only to compounds of uranium that take the chemical form of UF<sub>6</sub>, UO<sub>2</sub>F<sub>2</sub> and UO<sub>2</sub>(NO<sub>3</sub>)<sub>2</sub> in both normal and accident conditions of transport.

<sup>e</sup> These values apply only to compounds of uranium that take the chemical form of UO<sub>3</sub>, UF<sub>4</sub>, UCl<sub>4</sub> and hexavalent compounds in both normal and accident conditions of transport.

<sup>f</sup> These values apply to all compounds of uranium other than those specified in notes (d) and (e) of this table.

<sup>g</sup> These values apply to unirradiated uranium only.

**TABLE A-3—GENERAL VALUES FOR A<sub>1</sub> AND A<sub>2</sub>**

Contents	A <sub>1</sub>		A <sub>2</sub>		Activity concentration for exempt material (Bq/g)	Activity concentration for exempt material (Ci/g)	Activity limits for exempt consignments (Bq)	Activity limits for exempt consignments (Ci)
	(TBq)	(Ci)	(TBq)	(Ci)				
Only beta or gamma emitting radionuclides are known to be present	1 x 10 <sup>-1</sup>	2.7 x 10 <sup>0</sup>	2 x 10 <sup>-2</sup>	5.4 x 10 <sup>-1</sup>	1 x 10 <sup>1</sup>	2.7 x 10 <sup>-10</sup>	1 x 10 <sup>4</sup>	2.7 x 10 <sup>-7</sup>
<del>Only alpha emitting radionuclides, but no neutron emitters,</del> are known to be present <sup>a</sup>	2 x 10 <sup>-1</sup>	5.4 x 10 <sup>0</sup>	9 x 10 <sup>-5</sup>	2.4 x 10 <sup>-3</sup>	1 x 10 <sup>-1</sup>	2.7 x 10 <sup>-12</sup>	1 x 10 <sup>3</sup>	2.7 x 10 <sup>-8</sup>
<del>Neutron emitting nuclides are known to be present or no</del> relevant data are available	1 x 10 <sup>-3</sup>	2.7 x 10 <sup>-2</sup>	9 x 10 <sup>-5</sup>	2.4 x 10 <sup>-3</sup>	1 x 10 <sup>-1</sup>	2.7 x 10 <sup>-12</sup>	1 x 10 <sup>3</sup>	2.7 x 10 <sup>-8</sup>

<sup>a</sup> If beta or gamma emitting nuclides are known to be present, the A<sub>1</sub> value of 0.1 TBq (2.7 Ci) should be used.

**TABLE A-4—ACTIVITY-MASS RELATIONSHIPS FOR URANIUM**

Commented [mdk45]: Entire table moved to T56

Uranium Enrichment <sup>1</sup> wt % U-235 present	Specific Activity	
	TBq/g	Ci/g
0.45	$1.8 \times 10^{-8}$	$5.0 \times 10^{-7}$
0.72	$2.6 \times 10^{-8}$	$7.1 \times 10^{-7}$
1	$2.8 \times 10^{-8}$	$7.6 \times 10^{-7}$
1.5	$3.7 \times 10^{-8}$	$1.0 \times 10^{-6}$
5	$1.0 \times 10^{-7}$	$2.7 \times 10^{-6}$
10	$1.8 \times 10^{-7}$	$4.8 \times 10^{-6}$
20	$3.7 \times 10^{-7}$	$1.0 \times 10^{-5}$
35	$7.4 \times 10^{-7}$	$2.0 \times 10^{-5}$
50	$9.3 \times 10^{-7}$	$2.5 \times 10^{-5}$
90	$2.2 \times 10^{-6}$	$5.8 \times 10^{-5}$
93	$2.6 \times 10^{-6}$	$7.0 \times 10^{-5}$
95	$3.4 \times 10^{-6}$	$9.1 \times 10^{-5}$

<sup>1</sup> The figures for uranium include representative values for the activity of the uranium-234 that is concentrated during the enrichment process.

b. General Performance Objective. The licensee's access authorization program must ensure that the individuals specified in V.21(c)(i) are trustworthy and reliable.

c. Applicability.

i. Licensees shall subject the following individuals to an access authorization program in accordance with V.23:

(1) Any individual whose assigned duties require unescorted access to category 1 or category 2 quantities of radioactive material or to any device that contains the radioactive material; and

(2) Reviewing officials.

ii. Licensees need not subject the categories of individuals listed in Subsections V.29(a)(i) – (xiii) to the investigation elements of the access authorization program.

iii. Licensees shall approve for unescorted access to category 1 or category 2 quantities of radioactive material only those individuals with job duties that require unescorted access to category 1 or category 2 quantities of radioactive material.

iv. Licensees may include individuals needing access to safeguards information-modified handling under 10 CFR Part 73 in the access authorization program under Sections V21 – V33.

Sec. V.22 [Reserved].

Sec. V.23 Access Authorization Program Requirements.

a. Granting Unescorted Access Authorization.

i. Licensees shall implement the requirements of Sections V.21 – V.33 for granting initial or reinstated unescorted access authorization.

ii. Individuals who have been determined to be trustworthy and reliable shall also complete the security training required by V.43(c) before being allowed unescorted access to category 1 or category 2 quantities of radioactive material.

b. Reviewing Officials.

i. Reviewing officials are the only individuals who may make trustworthiness and reliability determinations that allow individuals to have unescorted access to category 1 or category 2 quantities of radioactive materials possessed by the licensee.

ii. Each licensee shall name one or more individuals to be reviewing officials. After completing the background investigation on the reviewing official, the licensee shall provide under oath or affirmation, a certification that the reviewing official is deemed trustworthy and reliable by the licensee. The fingerprints of the named reviewing official must be taken by a law enforcement agency, Federal or State agencies that provide fingerprinting services to the public, or commercial fingerprinting services authorized by a State to take fingerprints. ~~The licensee shall recertify that the reviewing official is deemed trustworthy and reliable every 10 years in accordance with Section V.25(bc).~~

Commented [mdk46]: 10 CFR 37.23(b)(2) RATS 2015-4

iii. Reviewing officials must be permitted to have unescorted access to category 1 or category 2 quantities of radioactive materials or access to safeguards information or safeguards information-modified handling, if the licensee possesses safeguards information or safeguards information-modified handling.

iv. Reviewing officials cannot approve other individuals to act as reviewing officials.

v. A reviewing official does not need to undergo a new background investigation before being named by the licensee as the reviewing official if:

(1) The individual has undergone a background investigation that included fingerprinting and an FBI criminal history records check and has been determined to be trustworthy and reliable by the licensee; or

(2) The individual is subject to a category listed in Section V.29(a).

c. Informed Consent.

i. Licensees may not initiate a background investigation without the informed and signed consent of the subject individual. This consent must include authorization to share personal information with other individuals or organizations as necessary to complete the background investigation. Before a final adverse determination, the licensee shall provide the individual with an opportunity to correct any inaccurate or incomplete information that is developed during the background investigation. Licensees do not need to obtain signed consent from those individuals that meet the requirements of Section V.25(b). A signed consent must be obtained prior to any reinvestigation.

ii. The subject individual may withdraw his or her consent at any time. Licensees shall inform the individual that:

(1) If an individual withdraws his or her consent, the licensee may not initiate any elements of the background investigation that were not in progress at the time the individual withdrew his or her consent; and

(2) The withdrawal of consent for the background investigation is sufficient cause for denial or termination of unescorted access authorization.

Sec. V.27 Requirements for Criminal History Records Checks of Individuals Granted Unescorted Access to Category 1 or Category 2 Quantities of Radioactive Material.

a. General Performance Objective and Requirements.

i. Except for those individuals listed in Section V.29 and those individuals grandfathered under Section V.25(b), each licensee subject to the provisions of this Part shall fingerprint each individual who is to be permitted unescorted access to category 1 or category 2 quantities of radioactive material. Licensees shall transmit all collected fingerprints to the NRC for transmission to the FBI. The licensee shall use the information received from the FBI as Part of the required background investigation to determine whether to grant or deny further unescorted access to category 1 or category 2 quantities of radioactive materials for that individual.

ii. The licensee shall notify each affected individual that his or her fingerprints will be used to secure a review of his or her criminal history record, and shall inform him or her of the procedures for revising the record or adding explanations to the record.

iii. Fingerprinting is not required if a licensee is reinstating an individual's unescorted access authorization to category 1 or category 2 quantities of radioactive materials if:

(1) The individual returns to the same facility that granted unescorted access authorization within 365 days of the termination of his or her unescorted access authorization; and

(2) The previous access was terminated under favorable conditions.

iv. Fingerprints do not need to be taken if an individual who is an employee of a licensee, contractor, manufacturer, or supplier has been granted unescorted access to category 1 or category 2 quantities of radioactive material, access to safeguards information, or safeguards information-modified handling by another licensee, based upon a background investigation conducted under this Part, the Fingerprint Orders, or 10 CFR Part 73. An existing criminal history records check file may be transferred to the licensee asked to grant unescorted access in accordance with the provisions of V.31(c).

v. Licensees shall use the information obtained as Part of a criminal history records check solely for the purpose of determining an individual's suitability for unescorted access authorization to category 1 or category 2 quantities of radioactive materials, access to safeguards information, or safeguards information-modified handling.

b. Prohibitions.

i. Licensees may not base a final determination to deny an individual unescorted access authorization to category 1 or category 2 quantities of radioactive material solely on the basis of information received from the FBI involving:

- (1) An arrest more than 1 year old for which there is no information of the disposition of the case; or
- (2) An arrest that resulted in dismissal of the charge or an acquittal.

ii. Licensees may not use information received from a criminal history records check obtained under this Part in a manner that would infringe upon the rights of any individual under the First Amendment to the Constitution of the United States, nor shall licensees use the information in any way that would discriminate among individuals on the basis of race, religion, national origin, gender, or age.

c. Procedures for Processing of Fingerprint Checks.

i. For the purpose of complying with this Part, licensees shall use an appropriate method listed in 10 CFR 37.7 to submit to the U.S. Nuclear Regulatory Commission, Director, Division of Facilities and Security, 11545 Rockville Pike, ATTN: Criminal History Program/Mail Stop T-03B46M, Rockville, Maryland 20852-2738, one completed, legible standard fingerprint card (Form FD-258, ORIMDNRCOOOZ), electronic fingerprint scan or, where practicable, other fingerprint record for each individual requiring unescorted access to category 1 or category 2 quantities of radioactive material. Copies of these forms may be obtained by writing the Office of ~~the Chief Information Services Officer~~, U.S. Nuclear Regulatory Commission, Washington, DC 20555-0001, by calling 1-630-829-9565, or by e-mail to [FORMS.Resource@nrc.gov](mailto:FORMS.Resource@nrc.gov). Guidance on submitting electronic fingerprints can be found at <http://www.nrc.gov/site-help/e-submittals.html>.

ii. Fees for the processing of fingerprint checks are due upon application. Licensees shall submit payment with the application for the processing of fingerprints through corporate check, certified check, cashier's check, money order, or electronic payment, made payable to "U.S. NRC." (For guidance on making electronic payments, contact the Security Branch, Division of Facilities and Security at 301-415-7513.) Combined payment for multiple applications is acceptable. The U.S. Nuclear Regulatory Commission publishes the amount of the fingerprint check application fee on the NRC's public Web site. (To find the current fee amount, go to the Electronic Submittals page at <http://www.nrc.gov/site-help/e-submittals.html> and see the link for the Criminal History Program under Electronic Submission Systems.)

iii. The NRC will forward to the submitting licensee all data received from the FBI as a result of the licensee's application(s) for criminal history records checks.

Sec. V.28 [Reserved].

Sec. V.29 Relief from Fingerprinting, Identification, and Criminal History Records Checks and Other Elements of Background Investigations for Designated Categories of Individuals Permitted Unescorted Access to Certain Radioactive Materials.

a. Fingerprinting, and the identification and criminal history records checks required by Section 149 of the Atomic Energy Act of 1954, as amended, and other elements of the background investigation are not required for the following individuals prior to granting unescorted access to category 1 or category 2 quantities of radioactive materials:

- i. An employee of the NRC or of the Executive Branch of the U.S. Government who has undergone fingerprinting for a prior U.S. Government criminal history records check;
- ii. A Member of Congress;
- iii. An employee of a member of Congress or Congressional committee who has undergone fingerprinting for a prior U.S. Government criminal history records check;
- iv. The Governor of a State or his or her designated State employee representative;
- v. Federal, State, or local law enforcement personnel;
- vi. State Radiation Control Program Directors and State Homeland Security Advisors or their designated State employee representatives;
- vii. Agreement State employees conducting security inspections on behalf of the NRC under an agreement executed under Section 274.i. of the Atomic Energy Act;
- viii. Representatives of the International Atomic Energy Agency (IAEA) engaged in activities associated with the U.S./IAEA Safeguards Agreement who have been certified by the NRC;
- ix. Emergency response personnel who are responding to an emergency;
- x. Commercial vehicle drivers for road shipments of category 1 and category 2 quantities of radioactive material;
- xi. Package handlers at transportation facilities such as freight terminals and railroad yards;
- xii. Any individual who has an active Federal security clearance, provided that he or she makes available the appropriate documentation. Written confirmation from the agency/employer that granted the Federal security clearance or reviewed the criminal history records check must be provided to the licensee. The licensee shall retain this documentation for a period of 3 years from the date the individual no longer requires unescorted access to category 1 or category 2 quantities of radioactive material; and

Commented [mdk48]: 10 CFR 37.29(a)(10) RATS 2015-2

xiii. Any individual employed by a service provider licensee for which the service provider licensee has conducted the background investigation for the individual and approved the individual for unescorted access to category 1 or category 2 quantities of radioactive material. Written verification from the service provider must be provided to the licensee. The licensee shall retain the documentation for a period of 3 years from the date the individual no longer requires unescorted access to category 1 or category 2 quantities of radioactive material.

b. Fingerprinting, and the identification and criminal history records checks required by Section 149 of the Atomic Energy Act of 1954, as amended, are not required for an individual who has had a favorably adjudicated U.S. Government criminal history records check within the last 5 years, under a comparable U.S. Government program involving fingerprinting and an FBI identification and criminal history records check provided that he or she makes available the appropriate documentation. Written confirmation from the agency/employer that reviewed the criminal history records check must be provided to the licensee. The licensee shall retain this documentation for a period of 3 years from the date the individual no longer requires unescorted access to category 1 or category 2 quantities of radioactive material. These programs include, but are not limited to:

- i. National Agency Check;
- ii. Transportation Worker Identification Credentials (TWIC) under 49 CFR part 1572;
- iii. Bureau of Alcohol, Tobacco, Firearms, and Explosives background check and clearances under 27 CFR part 555;
- iv. Health and Human Services security risk assessments for possession and use of select agents and toxins under 42 CFR part 73;
- v. Hazardous Material security threat assessment for hazardous material endorsement to commercial driver's license under 49 CFR part 1572; and
- vi. Customs and Border Protection's Free and Secure Trade (FAST) Program.

Sec. V30 [Reserved].

Sec. V.31 Protection of Information.

a. Each licensee who obtains background information on an individual under this Part shall establish and maintain a system of files and written procedures for protection of the record and the personal information from unauthorized disclosure.



(2) Identify the security resources, equipment, and technology used to satisfy the requirements of this Part.

ii. The security plan must be reviewed and approved by the individual with overall responsibility for the security program.

iii. A licensee shall revise its security plan as necessary to ensure the effective implementation of Agency requirements. The licensee shall ensure that:

(1) The revision has been reviewed and approved by the individual with overall responsibility for the security program; and

(2) The affected individuals are instructed on the revised plan before the changes are implemented.

iv. The licensee shall retain a copy of the current security plan as a record for 3 years after the security plan is no longer required. If any portion of the plan is superseded, the licensee shall retain the superseded material for 3 years after the record is superseded.

b. Implementing Procedures.

i. The licensee shall develop and maintain written procedures that document how the requirements of this Part and the security plan will be met.

ii. The implementing procedures and revisions to these procedures must be approved in writing by the individual with overall responsibility for the security program.

iii. The licensee shall retain a copy of the current procedure as a record for 3 years after the procedure is no longer needed. Superseded portions of the procedure must be retained for 3 years after the record is superseded.

c. Training.

i. Each licensee shall conduct training to ensure that those individuals implementing the security program possess and maintain the knowledge, skills, and abilities to carry out their assigned duties and responsibilities effectively. The training must include instruction in:

(1) The licensee's security program and procedures to secure category 1 or category 2 quantities of radioactive material, and in the purposes and functions of the security measures employed;

(2) The responsibility to report promptly to the licensee any condition that causes or may cause a violation of Agency requirements;

(3) The responsibility of the licensee to report promptly to the local law enforcement agency and licensee any actual or attempted theft, sabotage, or diversion of category 1 or category 2 quantities of radioactive material; and

(4) The appropriate response to security alarms.

ii. In determining those individuals who shall be trained on the security program, the licensee shall consider each individual's assigned activities during authorized use and response to potential situations involving actual or attempted theft, diversion, or sabotage of category 1 or category 2 quantities of radioactive material. The extent of the training must be commensurate with the individual's potential involvement in the security of category 1 or category 2 quantities of radioactive material.

iii. Refresher training must be provided at a frequency not to exceed 12 months and when significant changes have been made to the security program. This training must include:

(1) Review of the training requirements of paragraph (c) of this section and any changes made to the security program since the last training;

(2) Reports on any relevant security issues, problems, and lessons learned;

(3) Relevant results of Agency inspections; and

(4) Relevant results of the licensee's program review and testing and maintenance.

iv. The licensee shall maintain records of the initial and refresher training for 3 years from the date of the training. The training records must include dates of the training, topics covered, a list of licensee personnel in attendance, and related information.

d. Protection of Information.

i. Licensees authorized to possess category 1 or category 2 quantities of radioactive material shall limit access to and unauthorized disclosure of their security plan, implementing procedures, and the list of individuals that have been approved for unescorted access.

ii. Efforts to limit access shall include the development, implementation, and maintenance of written policies and procedures for controlling access to, and for proper handling and protection against unauthorized disclosure of, the security plan and implementing procedures.

Commented [mdk49]: 10 CFR 37.43(d)(1) RATS 2015-2 No change

d. Each licensee, who transports or plans to transport a shipment of a category 2 quantity of radioactive material, and determines that the shipment will arrive after the no-later-than arrival time provided pursuant to V.75(b), shall promptly notify the receiving licensee of the new no-later-than arrival time.

e. The licensee shall retain for 3 years a copy of the documentation for preplanning and coordination and any revision thereof.

Sec. V.76 [Reserved].

Sec. V.77 Advance Notification of Shipment of Category 1 Quantities of Radioactive Material.

As specified in paragraphs (a) and (b) of this section, each licensee shall provide advance notification to the Agency and to the governor of a State, or the governor's designee, of the shipment of licensed material in a category 1 quantity, through or across the boundary of the State, before the transport, or delivery to a carrier for transport of the licensed material outside the confines of the licensee's facility or other place of use or storage.

a. Procedures for Submitting Advance Notification.

i. The notification must be made to the Agency and to the office of the Governor's designee. Notification to the Agency must be made in accordance with Section A.12 of this regulation. The contact information, including telephone and mailing addresses, of governors and governors' designees, is available on the NRC's Web site at ~~<http://nrc-stp.ornl.gov/special/designee.pdf>~~ <https://scp.nrc.gov/special/designee.pdf>.

ii. A notification delivered by mail must be postmarked at least 7 days before transport of the shipment commences at the shipping facility.

iii. A notification delivered by any means other than mail must reach the Agency at least 4 days before the transport of the shipment commences and must reach the office of the governor or the governor's designee at least 4 days before transport of a shipment within or through the State.

b. Information To Be Furnished in Advance Notification of Shipment. Each advance notification of shipment of category 1 quantities of radioactive material must contain the following information, if available at the time of notification:

Commented [mdk50]: 10 CFR 37.77(a)(1) RATS 2015-5

- i. The name, address, and telephone number of the shipper, carrier, and receiver of the category 1 radioactive material;
- ii. The license numbers of the shipper and receiver;
- iii. A description of the radioactive material contained in the shipment, including the radionuclides and quantity;
- iv. The point of origin of the shipment and the estimated time and date that shipment will commence;
- v. The estimated time and date that the shipment is expected to enter each State along the route;
- vi. The estimated time and date of arrival of the shipment at the destination; and
- vii. A point of contact, with a telephone number, for current shipment information.

c. Revision Notice.

- i. The licensee shall provide any information not previously available at the time of the initial notification, as soon as the information becomes available but not later than commencement of the shipment, to the governor of the State or the governor's designee and to the Agency.
- ii. A licensee shall promptly notify the governor of the State or the governor's designee of any changes to the information provided in accordance with paragraphs (b) and (c)(1) of this section. The licensee shall also immediately notify the Agency of any such changes.

d. Cancellation Notice. Each licensee who cancels a shipment for which advance notification has been sent shall send a cancellation notice to the governor of each State or to the governor's designee previously notified and to the Agency. The licensee shall send the cancellation notice before the shipment would have commenced or as soon thereafter as possible. The licensee shall state in the notice that it is a cancellation and identify the advance notification that is being cancelled.

e. Records. The licensee shall retain a copy of the advance notification and any revision and cancellation notices as a record for 3 years.

f. Protection of Information. State officials, State employees, and other individuals, who receive schedule information of the kind specified in V.77(b) shall protect that information against unauthorized disclosure as specified in V.43(d).

Commented [mdk51]: 10 CFR 37.77(f) RATS 2015-2

Sec. V.78 [Reserved].

(2) Ensure that periodic reports to the communications center are made at preset intervals.

ii. Each licensee who transports, or delivers to a carrier for transport, in a single shipment, a category 2 quantity of radioactive material shall:

(1) Use carriers that have established package tracking systems. An established package tracking system is a documented, proven, and reliable system routinely used to transport objects of value. In order for a package tracking system to maintain constant control and/or surveillance, the package tracking system must allow the shipper or transporter to identify when and where the package was last and when it should arrive at the next point of control.

(2) Use carriers that maintain constant control and/or surveillance during transit and have the capability for immediate communication to summon appropriate response or assistance; and

(3) Use carriers that have established tracking systems that require an authorized signature prior to releasing the package for delivery or return.

c. Investigations. Each licensee who makes arrangements for the shipment of category 1 quantities of radioactive material shall immediately conduct an investigation upon the discovery that a category 1 shipment is lost or missing. Each licensee who makes arrangements for the shipment of category 2 quantities of radioactive material shall immediately conduct an investigation, in coordination with the receiving licensee, of any shipment that has not arrived by the designated no-later-than arrival time.

Sec. V.80 [Reserved].

Sec. V.81 Reporting of Events.

a. The shipping licensee shall notify the appropriate LLEA and the ~~NRC's Operations Center (301-816-5100)~~ Agency within 1 hour of its determination that a shipment of category 1 quantities of radioactive material is lost or missing. The appropriate LLEA would be the law enforcement agency in the area of the shipment's last confirmed location. During the investigation required by V.79(c), the shipping licensee will provide agreed upon updates to the Agency on the status of the investigation.

b. The shipping licensee shall notify the Agency within 4 hours of its determination that a shipment of category 2 quantities of radioactive material is lost or missing. If, after 24 hours of its determination that the shipment is lost or missing, the radioactive material has not been located and secured, the licensee shall immediately notify the Agency.

- c. The shipping licensee shall notify the designated LLEA along the shipment route as soon as possible upon discovery of any actual or attempted theft or diversion of a shipment or suspicious activities related to the theft or diversion of a shipment of a category 1 quantity of radioactive material. As soon as possible after notifying the LLEA, the licensee shall notify the Agency upon discovery of any actual or attempted theft or diversion of a shipment, or any suspicious activity related to the shipment of category 1 radioactive material.
- d. The shipping licensee shall notify the Agency as soon as possible upon discovery of any actual or attempted theft or diversion of a shipment, or any suspicious activity related to the shipment, of a category 2 quantity of radioactive material.
- e. The shipping licensee shall notify the Agency and the LLEA as soon as possible upon recovery of any lost or missing category 1 quantities of radioactive material.
- f. The shipping licensee shall notify the Agency as soon as possible upon recovery of any lost or missing category 2 quantities of radioactive material.
- g. The initial telephonic notification required by V.81(a) through (d) must be followed within a period of 30 days by a written report submitted to the Agency at the address specified in Section A.12 of this regulation. A written report is not required for notifications on suspicious activities required by V.81(c) and (d). In addition, the licensee shall provide one copy of the written report addressed to the Director, Division of Security Policy, Office of Nuclear Security and Incident Response, U.S. Nuclear Regulatory Commission, Washington, DC 20555-0001. The report must set forth the following information:
- i. A description of the licensed material involved, including kind, quantity, and chemical and physical form;
  - ii. A description of the circumstances under which the loss or theft occurred;
  - iii. A statement of the disposition, or probable disposition, of the licensed material involved;
  - iv. Actions that have been taken, or will be taken, to recover the material; and
  - v. Procedures or measures that have been, or will be, adopted to ensure against a recurrence of the loss or theft of licensed material.
- h. Subsequent to filing the written report, the licensee shall also report any additional substantive information on the loss or theft within 30 days after the licensee learns of such information.

Sec. V.82 – V.100 [Reserved].