

Distribution:

1. Gardner, Troy R
2. Mc Ginnis, Vickie L
3. Mccree, Victor M
4. OPS HUMAN PERFORMANCE -
5. OPS TRNG MGR.
6. QATS-
7. RESIDENT NRC INSPECT
8. SCIENTECH CLEARWTR, FL
9. SERV BLDG FILE ROOM -
10. U S NUC REG WASHINGTON, DC
11. USNRC
12. WESTINGHOUSE ELECTRIC CO LLC

Duke Energy
DOCUMENT TRANSMITTAL FORM

Facility: MCGUIRE NUCLEAR STATION
SUBJECT
MNS TS 3.7.11 - AMENDMENT 282/261

Page 1 of 1

Date: 4/28/2016

Document Transmittal #: TR-NUC-MC-002843

Purpose: Issue

Released By:

Duke Energy
13225 Hagers Ferry Road
Document Management
MG02DM
Huntersville, NC 28078
MNSDCRM@duke-energy.com

Document ID	1	2	3	4	5	6	7	8	9	10	11	12
LICN - MC - MNS-TS-3.7.11 - 001 - ISSUED	FYI E	FYI E	FYI E	FYI E	R&A E	FYI E	R&A LP	R&A E	FYI E	R&A E	R&A E	R&A E

Remarks:

ADD
NRR

3.7 PLANT SYSTEMS

3.7.11 Auxiliary Building Filtered Ventilation Exhaust System (ABFVES)

LCO 3.7.11 Two ABFVES shall be OPERABLE.

-----NOTE-----

The Auxiliary Building pressure boundary may be opened intermittently under administrative controls.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTIONS

CONDITION		REQUIRED ACTION		COMPLETION TIME
A.	One ABFVES inoperable.	A.1	Restore ABFVES to OPERABLE status.	7 days*
B.	Two ABFVES inoperable.	B.1	Restore one ABFVES to OPERABLE status.	24 hours
C.	Required Action and associated Completion Time not met.	C.1	Be in MODE 3.	6 hours
		<u>AND</u>		
		C.2	Be in MODE 5.	36 hours

-----NOTE-----

* 'A' Train ABFVES is allowed to be inoperable for a total of 14 days for the correction of a degraded condition on the 'A' Train supply piping from the Standby Nuclear Service Water Pond (SNSWP). The 14 days may be taken consecutively or in parts until completion of the activity, or by March 1, 2017, whichever occurs first. During the period in which the 'A' Train NSWS supply piping from the SNSWP is not available, the 'A' Train NSWS will remain aligned to Lake Norman until the system is ready for post maintenance testing. Any maintenance that is performed on the remaining portions of 'A' Train NSWS during the period in which the 'A' NSWS from the SNSWP supply piping is not available will be limited to a 72 hour completion time. The latter will not count against the 14 day completion time. Allowance of the extended Completion Time is contingent on meeting the Compensatory Measures and Commitments as described in MNS LAR submittal correspondence letter MNS-16-005.

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
SR 3.7.11.1 Operate each ABFVES for ≥ 15 minutes.	In accordance with the Surveillance Frequency Control Program
SR 3.7.11.2 Perform required ABFVES filter testing in accordance with the Ventilation Filter Testing Program (VFTP).	In accordance with the VFTP
SR 3.7.11.3 Verify each ABFVES actuates on an actual or simulated actuation signal.	In accordance with the Surveillance Frequency Control Program
SR 3.7.11.4 Verify one ABFVES can maintain a pressure ≤ -0.125 inches water gauge in the ECCS pump room area relative to atmospheric pressure during the post accident mode of operation.	In accordance with the Surveillance Frequency Control Program