

ATTACHMENT TO LICENSE AMENDMENT NO. 70

FACILITY OPERATING LICENSE NO. DPR-63


DOCKET NO. 50-220

Revise the Appendix A Technical Specifications by removing and inserting the following pages:

<u>Existing Page</u>	<u>Revised Page</u>
4c	4c
89	89
--	89a
90	90
91	91

The revised areas are indicated by marginal lines.

8504110250 850327  
PDR ADDCK 05000220  
P PDR



### 1.28 Ventilation Exhaust Treatment System

A ventilation exhaust treatment system is any system designed and installed to reduce gaseous radiiodine or radioactive material in particulate form in effluents by passing ventilation or vent exhaust gases through charcoal adsorbers and/or HEPA filters for the purpose of removing iodines or particulates from the gaseous exhaust stream prior to the release to the environment. Such a system is not considered to have any effect on noble gas effluents. Engineered Safety Feature (ESF) atmospheric cleanup systems are not considered to be ventilation exhaust treatment system components.

### 1.29 Venting

Venting is the controlled process of discharging air or gas from a confinement to maintain temperature, pressure, humidity, concentration, or other operating condition, in such a manner that replacement air or gas is not provided or required during venting. Vent, used in system names, does not imply a venting process.

### 1.30 Reactor Coolant Leakage

#### a. Identified Leakage

- (1) Leakage into closed systems, such as pump seal or valve packing leaks that are captured, flow metered and conducted to a sump or collecting tank, or
- (2) Leakage into the primary containment atmosphere from sources that are both specifically located and known not to be from a through-wall crack in the piping within the reactor coolant pressure boundary.

#### b. Unidentified Leakage

All other leakage of reactor coolant into the primary containment area.

