

HI-STORE Consolidated Interim Storage Facility

New Mexico

Safety Analysis Report

LICENSING REPORT

on

The HI-STORE CIS FACILITY

by

Holtec International
Holtec Center
One Holtec Drive
Marlton, NJ 08053, USA
(holtecinternational.com)

USNRC Docket # 72-1051
Holtec Project 5025
Holtec Report # HI-2167374

Safety Category: Safety Significant

NOTICE OF COPYRIGHTED STATUS

This document is a copyrighted intellectual property of Holtec International. All rights reserved. Excerpting any part of this document, except for public domain citations included herein, by any person or entity except the USNRC, a Holtec User Group (HUG) member company, or a foreign regulatory authority with jurisdiction over a Holtec owned or a Holtec client owned nuclear facility without an unambiguous written consent from Holtec International is unlawful.

HOLTEC INTERNATIONAL

DOCUMENT NUMBER: HI-2167374 PROJECT NUMBER: 5025

DOCUMENT ISSUANCE AND REVISION STATUS

DOCUMENT NAME: HI-STORE SAR DOCUMENT CATEGORY: ☒ GENERIC ☐ PROJECT SPECIFIC

No.	Document Portion††	REVISION No. 0			REVISION No. _____			REVISION No. _____		
		Author's Initials	Date Approved	VIR #	Author's Initials	Date Approved	VIR #	Author's Initials	Date Approved	VIR #
1.	Chapter 1	RN	3/26/17	433260						
2.	Chapter 2	NC	3/24/17	88079						
3.	Chapter 3	PT	3/24/17	639686						
4.	Chapter 4	RM	3/24/17	775630						
5.	Chapter 5	CB	3/27/17	874213						
6.	Chapter 6	AM	3/24/17	694937						
7.	Chapter 7	RT	3/24/17	261577						
8.	Chapter 8	SPA	3/24/17	805110						
9.	Chapter 9	KM	3/24/17	542961						
10.	Chapter 10	RM	3/24/17	510691						
11.	Chapter 11	RT	3/24/17	389816						
12.	Chapter 12	RN	3/24/17	434315						
13.	Chapter 13	NC	3/23/17	822414						
14.	Chapter 14	RN	3/24/17	415742						
15.	Chapter 15	IR	3/24/17	927380						
16.	Chapter 16	RN	3/24/17	379742						
17.	Chapter 17	RK	3/24/17	11220						

HOLTEC INTERNATIONAL

DOCUMENT ISSUANCE AND REVISION STATUS

DOCUMENT NAME: HI-STORE SAR

DOCUMENT CATEGORY: ☒ GENERIC ☐ PROJECT SPECIFIC

18.	Chapter 18	RK	3/24/17	627410						
19.	Chapter 19	RN	3/24/17	60499						

†† Chapter or section number.

DOCUMENT NUMBER: HI-2167374 PROJECT NUMBER: 5025

DOCUMENT CATEGORIZATION

In accordance with the Holtec Quality Assurance Manual and associated Holtec Quality Procedures (HQPs), this document is categorized as a:

- ☐ Calculation Package[3] (Per HQP 3.2)
- ☒ Technical Report (Per HQP 3.2)(Such as a Licensing Report)
- ☐ Design Criterion Document (Per HQP 3.4)
- ☐ Design Specification (Per HQP 3.4)
- ☐ Other (Specify):

DOCUMENT FORMATTING

The formatting of the contents of this document is in accordance with the instructions of HQP 3.2 or 3.4 except as noted below:

DECLARATION OF PROPRIETARY STATUS

☒ Nonproprietary ☐ Holtec Proprietary ☐ Privileged Intellectual Property (PIP)

Documents labeled Privileged Intellectual Property contain extremely valuable intellectual/commercial property of Holtec International. They cannot be released to external organizations or entities without explicit approval of a company corporate officer. The recipient of Holtec's proprietary or Top Secret document bears full and undivided responsibility to safeguard it against loss or duplication.

Notes:

1. This document has been subjected to review, verification and approval process set forth in the Holtec Quality Assurance Procedures Manual. Password controlled signatures of Holtec personnel who participated in the preparation, review, and QA validation of this document are saved in the N-drive of the company's network. The Validation Identifier Record (VIR) number is a random number that is generated by the computer after the specific revision of this document has undergone the required review and approval process, and the appropriate Holtec personnel have recorded their password-controlled electronic concurrence to the document.

2. A revision to this document will be ordered by the Project Manager and carried out if any of its contents is materially affected during evolution of this project. The determination as to the need for revision will be made by the Project Manager with input from others, as deemed necessary by him.

3. Revisions to this document may be made by adding supplements to the document and replacing the "Table of Contents", this page and the "Revision Log".

GLOSSARY OF TERMS USED IN HI-STORE CIS FACILITY LICENSING REPORT

Accident Condition Storage Temperature is the maximum 24 hour- average of the ambient temperature at an ISFSI site. The accident condition temperature serves as the input air temperature for a cask system to compute the accident condition peak cladding temperature for which a regulatory limit is specified in ISG11 Rev 3.

AFR is an acronym for Away from Reactor storage**.**

Aging Management Program (AMP), outlined in Chapter 18, is a carefully crafted collection of processes and procedures deemed to be necessary for an effective monitoring, inspection, testing and recovery/remediation plan for the ISFSI to ensure safe operation for its entire Service life.

ALARA is an acronym for As Low- As –Reasonably- Achievable

Ambient Temperature for Short Term Operations (operations involving use of a transport cask, a Lifting device and/ or a on-site transport device) is defined as the 24 hour average of the local temperature as forecast by the National Weather Service.

Ancillary or Ancillary Equipment is the generic name of a device used to carry out "Short Term Operations.

BWR is an acronym for Boiling Water Reactor.

Canister means an all-welded vessel containing used fuel that has been qualified to serve as a confinement boundary under the rules of 10CFR 72. The terms MPC, DSC, etc., are also used to indicate a seal-welded spent fuel canister.

Canister Transfer Facility (CTF) is a below-grade placement location where the transport cask is temporarily placed to effectuate vertical canister transfer between the transport cask and the HI-TRAC CS.

Canister Transfer means transfer operations necessary to translocate a loaded canister between a transport cask, HI-TRAC CS and/or the HI-STORM UMAX storage system.

Cask Crane is the gantry crane installed in the Cask Transfer Building for heavy load handling activities

Cask Receiving Area is the physical location where loaded casks are received. Consists of a vehicle entrance, vehicle parking area, VCT access port, cask and cask appurtenance lifting apparatus, cask tilting apparatus, location for storage of cask transport appurtenances (e.g., personnel barrier, impact limiters, etc.), location for cask lid removal and installation, location for transfer of the cask to the VCT, cask inspection and work area. The cask receiving area may be partially or completely enclosed.

Cask Transfer Building (CTB) means the sheet metal enclosure that houses the Canister Transfer Facility (CTF) and the cask receiving area and provides storage space for ancillary equipment used in short term operations.

Cavity Enclosure Container (CEC) means a thick-walled cylindrical steel weldment that defines the storage cavity in HI-STORM UMAX for the storage of the canister.

CG is an acronym for the center- of- gravity.

Closure Lid means the METCON lid that is installed on the CEC to provide physical and shielding protection to the stored canister.

Commercial Spent Fuel (CSF) refers to nuclear fuel used to produce energy in a commercial nuclear power plant.

Confinement Boundary means the outline formed by the cylindrical enclosure of the canister shell welded to a solid baseplate, and at least one top lid to create a hermetically sealed enclosure.

Confinement System means the canister which encloses and confines the spent nuclear fuel during storage.

Container Flange means the ring flange that is welded to the upper extremity of the Container Shell.

Container Shell means the cylindrical portion of the Cavity Enclosure Container

Controlled Area means that area immediately surrounding the ISFSI over which the HI-STORE Facility owner (Holtec) exercises authority over its use and within which all Short Term Operations are performed.

Controlled Low-Strength Material (CLSM) is a self-compacted, cementitious material used primarily as a backfill in place of compacted fill. Many terms are currently used to describe this material, such as flowable fill, unshrinkable fill, controlled density fill, flowable mortar, flowable fly ash, fly ash slurry, plastic soil-cement and soil-cement slurry (ACI 229R-99). CLSM and lean concrete are also referred to as "*Self-hardening Engineered Subgrade* (SES)"

Cooling Time (or post-irradiation cooling time) for a spent fuel assembly is the time elapsed after its discharge from the reactor to the time it is loaded into the canister.

Critical Characteristic means a feature of a SSC that is necessary for the proper safety function of the SSC. Critical characteristics of a material are those attributes that have been identified, in the associated material specification, as necessary to render the material's intended function.

Design Basis Earthquake (DBE) is the seismic input applicable to the cask's long term storage on the ISFSI pad.

Design Basis Load (DBL) is a loading defined in this SAR to *bound* one or more events that are applicable to the storage system during its service life. Thus, the snow pressure loading on the cask's lid specified in this SAR is a DBL because it is set substantially above the pressure from accumulated snow set down in the national consensus standard for the 48 contiguous United States.

Design Basis Missile (DBM) is the applicable missiles used to evaluate the safety of the storage system

Design Extended Condition Earthquake (DECE) is a beyond design basis seismic input that exceeds the 10,000 year return earthquake at the site.

Design Heat Load or Design Basis Heat Load is the computed heat rejection capacity of the HI-STORM system with a certified canister loaded with CSF stored in uniform storage with the ambient at the normal temperature and the peak cladding temperature (PCT) at 400ºC. The Design Heat Load is less than the thermal capacity of the system by a suitable margin that reflects the conservatism in the system thermal analysis..

Design Life is the minimum duration for which the SSC or Facility is engineered to perform its intended function set forth in this SAR, if operated and maintained in accordance with this document.

Design Report is a document prepared, reviewed and QA validated in accordance with the provisions of 10CFR72 Subpart G. The Design Report shall demonstrate compliance with the requirements set forth in the Design Specification. A Design Report is mandatory for systems, structures, and components (SCCs) designated as Important to Safety. This SAR serves as the Design Report for the HI-STORE Facility.

Design Specification is a document prepared in accordance with the quality assurance requirements of 10CFR72 Subpart G to provide a complete set of design criteria and functional requirements for a system, structure, or component or Facility intended to be used in the operation, of the HI-STORE CIS Facility. This document serves as the Design Specification for the HI-STORE CIS Facility.

Divider Shell means a cylindrical shell bearing insulation over most of its inner or outer surface that divides the annular space between the canister and the CEC shell into two discrete regions for down- flow and up-flow of air in the HI-STORM UMAX VVM.

Dry Cask Storage System (DCSS) is a system that stores spent fuel or high level waste in a dry condition.

Enclosure Vessel means the pressure vessel defined by the cylindrical shell, baseplate, top lid and associated welds that provides confinement for the helium gas contained within the canister. The Enclosure Vessel (EV) and the fuel basket together constitute the canister.

Equivalent (or Equal) Material is a material with critical characteristics (see definition above) that meet or exceed those specified for the designated material.

Facility is used as an abbreviated name for the HI-STORE Consolidated Interim Storage facility

Fracture Toughness is a property which is a measure of the ability of a material to limit crack propagation under a suddenly applied load.

FSAR is an acronym for Final Safety Analysis Report (10CFR72).

Fuel Basket means a honeycombed structural weldment with square openings which can accept a fuel assembly of the type for which it is designed.

Gantry Crane is the device used in conjunction with special lifting devices that perform elements of the cask lifting operations in the Cask Receiving Area.

High Burnup Fuel (HBF) refers to fuel with a burnup greater than 45,000 MWD/MTU

HI-STORE or HI-STORE CIS is the consolidated interim storage facility envisaged to be built and operated in Southeastern New Mexico.

HI-STORM VVM means the vertical ventilated module wherein the canister is stored in the upright orientation.

HI-STORM UMAX System consists of loaded canisters stored in the HI-STORM UMAX VVM under Docket Number 72-1040.

HI-STORM 100 System consists of any loaded canister model placed within any design variant of the HI-STORM overpack in Docket Number 72-1014.

HI-STORM FW System is the larger capacity, variable height counterpart of the HI-STORM 100 system certified in Docket Number 72-1032

HI-TRAC CS is the shielded transfer cask used for performing canister transfer between the transport cask and the HI-STORM UMAX system at HI-STORE.

Holtite*TM* is the trademarked name of a family of neutron shield materials owned by Holtec International.

HP is an acronym for Health Physics

HS is an acronym for HI-STORE Specific, used in relation to the ancillaries at the facility.

Important to Safety (ITS) means a SSC function or condition required to store spent nuclear fuel safely; to prevent damage to spent nuclear fuel during handling and storage, and to provide reasonable assurance that spent nuclear fuel can be received, handled, packaged, stored, and retrieved without undue risk to the health and safety of the public.

Independent Spent Fuel Storage Installation (ISFSI) means a facility designed, constructed, and licensed for the interim storage of spent nuclear fuel and other radioactive materials associated with spent fuel storage in accordance with 10CFR72. An ISFSI may be located at a nuclear plant or at an AFR.

Interim Storage means an autonomous monitored canister storage facility from which the stored canister can be retrieved, if necessary.

Interfacing Components means the weldments certified in other dockets that will be used with the HI-STORM UMAX VVM assemblies for transferring and storing canisters in at the HI-STORE Facility. The canister is an Interfacing Component.

ISFSI Pad means the reinforced concrete pad that defines the top extremity of the HI-STORM UMAX VVM and provides the support surface for the cask handling device.

License Life means the duration for which the system is authorized by virtue of its certification by the U.S. NRC.

Licensing Drawings or Licensing Drawing Package is an integral part of this SAR wherein the essential geometric and material information on HI-STORM UMAX is compiled to enable the safety evaluations pursuant to 10CFR72 to be carried out.

Long-term Storage means the period of passive storage in the HI-STORM UMAX VVMs at the AFR facility.

Lowest Service Temperature (LST) is the minimum metal temperature of a part for the specified service condition.

METCON means a steel structure fortified by plain concrete.

Mined Geological Disposal System (MGDS) is a nuclear waste repository excavated deep within a stable geologic environment

MSE is an acronym for "Most Severe Earthquake," utilized to denote the ultra-high earthquake resistant options used in the HI-STORM UMAX generic license. These options are not currently utilized at the HI-STORE facility.

Nil Ductility Transition Temperature (NDT) is defined as the temperature at which the fracture stress in a material with a small flaw is equal to the yield stress in the same material if it had no flaws.

Neutron Absorber is a generic term used in this SAR to indicate any neutron absorber material qualified for use in the canister certified for storage in the HI-STORM UMAX VVM.

Neutron Shielding means a material used to thermalize and capture neutrons emanating from the radioactive spent nuclear fuel.

Normal Storage Condition temperature refers to the integrated time average of the annual ambient temperature at an ISFSI site. It is used, as prescribed in ISG11Rev3 and NUREG-1536, as the reference air inlet temperature in the ventilated cask's thermal analysis for computing the fuel cladding temperature. In non-ventilated casks, it is used as the surrounding ambient temperature for the thermal analysis of the cask under the so-called normal condition of storage.

Off-Normal Storage Condition refers to the highest three- day average of ambient air temperature at an ISFSI site. The off-normal temperature serves as the air temperature for computing the off-normal peak cladding temperature in a cask system for which an explicit cladding temperature limit is specified in ISG11 Rev3.

Operating Basis Earthquake is the three-dimensional seismic motion that is assumed to apply to any site activity whose duration exceeds one work shift. For conservatism, the OBE is set equal to the bounding value of 1000 year return earthquake for the HI-STORE site.(Short duration activities lasting less than a work shift are considered seismic-exempt operations)

Plain Concrete is concrete that is unreinforced by re-bars with a nominal or a range of densities specified in this document.

Post-Core Decay Time (PCDT) is synonymous with cooling time.

PWR is an acronym for pressurized water reactor.

Reactivity is used synonymously with effective neutron multiplication factor or k-effective.

Redundant Drop Protection Features are mechanical elements of a hydraulic lifting device used to prevent the uncontrolled lowering of a load in the event of a loss of power or loss of hydraulic pressure.

Safe Shutdown Earthquake (SSE) is a site's seismic input applicable to the cask's long term storage on the ISFSI pad, also called DBE.

Safety Report is a generic term to identify a SAR or any other term that connotes a compilation of all safety analyses and evaluations necessary to demonstrate compliance of a SSC to the its applicable codes and regulations.

Safety Significant is a generic term in Holtec's QA system to indicate *Safety Related* (used in 10CFR 50) and *Important- to -Safety* (Used in 10CFR71 and 10CFR72)

SAR is an acronym for Safety Analysis Report.

Self-hardening Engineered Subgrade (SES) means CLSM or lean concrete in this SAR.

Service Life means the duration for which the SSC is reasonably expected to perform its intended function, if operated and maintained in accordance with the provisions of this Safety Report. Service Life may be much longer than the Design Life because of the conservatism inherent in the codes, standards, and procedures used to design, fabricate, operate, and maintain the SSC.

Severity Index is the indicator of the safety importance and operational fragility of a SSC (used in Chapter 18) which informs the level of monitoring, inspection and remediation measures required in its Aging Management Program (AMP). The canister has the highest severity index (=3); NITS items have the severity index of 0.

Shield Gate means the split-plate structure that provides the ability to open and close the bottom closure structure in the HI-TRAC CS transfer cask.

Short-term Operations means those normal operational evolutions necessary to support canister loading into or unloading from the HI-STORM UMAX storage system. These include, but are not limited to canister transfer, and onsite handling of a loaded transport cask as described in this SAR.

Single Failure Proof means that the handling system is designed so that all directly loaded tension and compression members are engineered to satisfy the enhanced safety criteria of Paragraphs 5.1.6(1)(a) and (b) of NUREG-0612.

SNF is an acronym for spent nuclear fuel.

Special Lifting Devices are components that meet the definition of ANSI N14.6.

SSC is an acronym for Structures, Systems and Components.

STP is an acronym Standard Temperature and Pressure conditions.

Support Foundation Pad (SFP) means the reinforced concrete pad located underground on which the CECs are situated.

Sub-Grade is the 3-D continuum adjacent to each CEC that occupies the vertical space between the SFP below and the ISFSI Pad above.

Thermal Capacity of the HI-STORM system is defined as the amount of heat the storage system, containing a canister loaded with CSF stored in *storage,* will actually reject with the ambient environment at the normal temperature and the peak fuel cladding temperature (PCT) below the ISG-11 Rev 3 limit.

Thermo-siphon is the term used to describe the buoyancy-driven natural convection circulation of helium within the canister.

Tilt Frame is the device used for tilting of the Transport Cask or HI-TRAC between the vertical and horizontal orientations.

Top-of Grade (TOG) of the ISFSI is identified as the riding surface of the cask transporter.

Traveler means the set of sequential instructions used in a controlled manufacturing program to ensure that all required tests and examinations required upon the completion of each significant manufacturing activity are performed and documented for archival reference.

UG is an acronym for HI-STORM UMAX Generic License components.

Unconditionally Safe Threshold (UST) value is a term-of-art that is assigned to the result of a safety analysis which represents the lowest value that can be wrought by a "change" without requiring a modification to the material in the SAR. The UST is set higher than the required factor-of-safety pursuant to Chapter 4 herein. The significance of a "change" in the safety factor is measured with the UST as the reference value.

Under-grade is the space below the SFP.

Vertical Cask Transporter (VCT) is the generic name for a device that has the ability to raise or lower a cask or a canister with the built-in safety of a redundant drop protection system. A VCT may be designed to be limited in its operation space to the ISFSI pad area and/or it may have the capability to translocate the cask over a suitably engineered haul path.

VVM is an acronym for Vertical Ventilated Module

ZPA is an acronym for "zero period acceleration".

SAR SECTION REVISION STATUS, LIST OF AFFECTED SECTIONS AND REVISION SUMMARY

SAR Report No.: HI-2167374	**SAR Revision Number:** 0

FSAR Title:	Licensing Report on the HI-STORE CIS Facility

This SAR is submitted to the USNRC in support of Holtec International's application to secure a site-specific license under 10CFR Part 72.

SAR review and verification are controlled at the chapter level and changes are annotated at the chapter level.

A section in a chapter is identified by two numerals separated by a decimal. Each section begins on a fresh page. Unless indicated as a "complete revision" in the summary description of change below, if any change in the content is made, then the change is indicated by a "bar" in the right page margin and the revision number of the entire chapter including applicable figures (annotated in the footer) is changed.

A summary description of change is provided below for each SAR chapter. Minor editorial changes to this SAR may not be summarized in the description of change.

Chapter 1

Affected Section or Table No.	Current Revision No.	Summary Description of Change
All	0	Initial Issue

Chapter 2

Section or Table No.	Current Revision No.	Summary Description of Change
All	0	Initial Issue

Chapter 3		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue
Chapter 4		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue
Chapter 5		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue
Chapter 6		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue
Chapter 7 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 8 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 9 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 10 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 11 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 12 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 13 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 14 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 15 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 16 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 17 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 18 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Chapter 19 Changes		
Section or Table No.	**Current Revision No.**	**Summary Description of Change**
All	0	Initial Issue

Table of Contents

CHAPTER 1: GENERAL DESCRIPTION 1-1
1.0 INTRODUCTION 1-1
1.0.1 72.48 Evaluations 1-3
1.1 GENERAL DESCRIPTION OF INSTALLATION 1-9
1.2 GENERAL SYSTEMS DESCRIPTION 1-11
1.2.1 HI-STORM UMAX System Overview 1-11
1.2.2 Constituents of the HI-STORM UMAX Vertical Ventilated Module and ISFSI Structures 1-12
1.2.3 Design Characteristics of the HI-STORM UMAX VVM 1-16
1.2.4 HI-TRAC CS 1-18
1.2.5 Operational Characteristics of the HI-STORM UMAX 1-19
1.2.6 Cask Contents 1-21
1.2.7 Ancillary Equipment Used at HI-STORE CIS 1-21
1.3 IDENTIFICATION OF AGENTS AND CONTRACTORS 1-30
1.4 MATERIAL INCORPORATED BY REFERENCE 1-37
1.5 LICENSING DRAWINGS 1-38
1.6 REGULATORY COMPLIANCE 1-39
CHAPTER 2: SITE CHARACTERISTICS 2-1
2.0 INTRODUCTION 2-1
2.1 GEOGRAPHY AND DEMOGRAPHY 2-2
2.1.1 Site Location 2-2
2.1.2 Site Description 2-2
2.1.3 Population Distribution and Trends 2-6
2.1.4 Land and Water Use 2-7
2.2 NEARBY INDUSTRIAL, TRANSPORTATION, AND MILITARY FACILITIES 2-28
2.3 METEOROLOGY 2-32
2.3.1 Regional Climatology 2-32
2.3.2 Local Meteorology 2-34
2.3.3 Onsite Meteorological Measurement Program 2-34
2.4 SURFACE HYDROLOGY 2-43
2.4.1 Hydrologic Description 2-43

2.4.2 Floods 2-43
2.4.3 Probable Maximum Flood (PMF) 2-44
2.4.4 Potential Dam Failures (Seismically-Induced) 2-45
2.4.5 Probable Maximum Surge and Seiche Flooding 2-45
2.4.6 Probable Maximum Tsunami Flooding 2-45
2.4.7 Ice Flooding 2-45
2.4.8 Flood Protection Requirements 2-45
2.4.9 Environmental Acceptance of Effluents 2-45
2.5 SUBSURFACE HYDROLOGY 2-46
2.6 GEOLOGY AND SEISMOLOGY 2-50
2.6.1 Basic Geologic and Seismic Information 2-50
2.6.2 Vibratory Ground Motion 2-51
2.6.3 Surface Faulting 2-53
2.6.4 Stability of Subsurface Materials 2-53
2.6.5 Slope Stability 2-54
2.7 SITE SPECIFIC DATA FOR THERMAL AND STRUCTURAL ANALYSES 2-66
2.8 SAFETY-RELEVANT ENVIRONMENTAL DETERMINATIONS 2-69
2.9 REGULATORY COMPLIANCE 2-70
CHAPTER 3: OPERATIONS AT THE HI-STORE FACILITY 3-1
3.0 INTRODUCTION 3-1
3.1 DESCRIPTION OF OPERATIONS 3-3
3.1.1 Operations at Originating Nuclear Power Plant 3-4
3.1.2 Operations Between the Originating Nuclear Power Plant and HI-STORE 3-4
3.1.3 Operations Between the Railroad Mainline and HI-STORE 3-4
3.1.4 Operations at HI-STORE 3-5
3.1.5 Identification of Subjects for Safety Analysis 3-8
3.2 SPENT FUEL AND HIGH-LEVEL WASTE HANDLING SYSTEMS 3-17
3.2.1 Spent Fuel Canister Receipt, Handling, and Transfer 3-17
3.2.2 Spent Fuel Canister Storage 3-19
3.3 OTHER OPERATING SYSTEMS 3-21
3.4 OPERATION SUPPORT SYSTEMS 3-22
3.4.1 Instrumentation and Control Systems 3-22

3.4.2 System and Component Spares 3-22
3.5 CONTROL ROOM AND CONTROL AREA 3-23
3.6 ANALYTICAL SAMPLING 3-24
3.7 POOL AND POOL FACILITY SYSTEMS 3-25
3.8 REGULATORY COMPLIANCE 3-26
CHAPTER 4: DESIGN CRITERIA FOR THE HI-STORE CIS SSCS 4-1
4.0 INTRODUCTION 4-1
4.1 MATERIALS TO BE STORED 4-4
4.1.1 Spent Fuel Canisters 4-4
4.1.2 High-Level Radioactive Waste 4-4
4.2 CLASSIFICATION OF STRUCTURES, SYSTEMS AND COMPONENTS 4-10
4.3 DESIGN CRITERIA FOR SSCS IMPORTANT TO SAFETY 4-15
4.3.1 Multi-Purpose Canisters (MPCs) 4-15
4.3.2 VVM Components and ISFSI Structures 4-15
4.3.3 HI-TRAC CS 4-17
4.3.4 HI-STAR 190 4-18
4.3.5 Cask Transfer Facility (CTF) 4-19
4.3.6 Applicable Earthquake Loadings for the HI-STORE CIS Facility 4-20
4.4 ACCEPTANCE CRITERIA FOR CASK COMPONENTS 4-31
4.4.1 Stress and Deformation Limits 4-31
4.4.2 Thermal Limits 4-32
4.4.3 Dose Limits 4-32
4.5 LIFTING DEVICES (CTB CRANE & VCT, SPECIAL LIFTING DEVICES, AND MISCELLANEOUS ANCILLARIES 4-37
4.5.1 Design Requirements Applicable to Lifting Devices and Special Lifting Devices 4-37
4.5.2 Cask Transfer Building (CTB) Crane 4-38
4.5.3 Vertical Cask Transporter 4-40
4.5.4 Miscellaneous Ancillaries 4-44
4.6 DESIGN CRITERIA FOR CASK TRANSFER BUILDING (CTB) 4-59
4.6.1 Design Features of CTB 4-59
4.6.2 CTB Slab 4-59
4.7 SUMMARY OF DESIGN CRITERIA 4-63

APP 4.A STRESS LIMITS FOR ASME SECTION III SUBSECTION NF LINEAR STRUCTURES AND PLATE & SHELL TYPE STRUCTURES 4A-1
4.A.1 Linear Structures 4A-1
4.A.2 Stress Limit Criteria for Plate and Shell Structures 4A-5
CHAPTER 5: INSTALLATION AND STRUCTURAL EVALUATION 5-1
5.0 INTRODUCTION 5-1
5.1 CONFINEMENT STRUCTURES, SYSTEMS AND COMPONENTS 5-5
5.1.1 Description of Structural Design 5-5
5.1.2 Design Criteria 5-5
5.1.3 Material Properties 5-5
5.1.4 Structural Analyses 5-6
5.2 POOL AND POOL CONFINEMENT FACILITIES 5-7
5.3 REINFORCED CONCRETE STRUCTURES 5-8
5.3.1 HI-STORM UMAX ISFSI Pad and Support Foundation Pad 5-8
5.3.2 Canister Transfer Facility 5-9
5.3.3 Canister Transfer Building Slab 5-9
5.4 OTHER SSCs IMPORTANT to SAFETY 5-12
5.4.1 HI-STORM UMAX VVM 5-12
5.4.2 HI-TRAC CS 5-14
5.4.3 Cask Transfer Building Crane 5-17
5.4.4 Transport Cask Lift Yoke 5-17
5.4.5 MPC Lift Attachment 5-18
5.4.6 Other Special Lifting Devices 5-19
5.5 OTHER SSCs 5-33
5.5.1 Cask Tilt Frame 5-33
5.5.2 Vertical Cask Transporter 5-34
5.6 REGULATORY COMPLIANCE 5-39
CHAPTER 6: THERMAL EVALUATION 6-1
6.0 INTRODUCTION 6-1
6.1 DECAY HEAT REMOVAL SYSTEMS 6-7
6.2 MATERIAL TEMPERATURE LIMITS 6-9
6.3 THERMAL LOADS AND ENVIRONMENTAL CONDITIONS 6-10

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

6.4 ANALYTICAL METHODS, MODELS, AND CALCULATIONS 6-12
6.4.1 Applicable Systems 6-12
6.4.2 Analysis Methodology 6-13
6.4.3 Calculations and Results 6-16
6.5 SAFETY UNDER OFF-NORMAL AND ACCIDENT EVENTS 6-35
6.5.1 Off-Normal Events 6-35
6.5.2 Accident Events 6-35
6.5.3 SSCs Important to Safety Guidance for Fire Protection Program 6-40
6.6 REGULATORY COMPLIANCE 6-45
APPENDIX 6A: HOLTEC VALIDATION OF FLUENT FOR CASK APPLICATIONS 6A-1
6A.1 INTRODUCTION 6A-1
6A.2 CODE DEVELOPER VALIDATION 6A-2
6A.3 HOLTEC VALIDATION 6A-4
CHAPTER 7: SHIELDING EVALUATION 7-1
7.0 INTRODUCTION 7-1
7.1 CONTAINED RADIATION SOURCES 7-4
7.1.1 General Specification and Approach for Neutron and Gamma Sources 7-4
7.1.2 Design Basis Assemblies 7-4
7.2 STORAGE AND TRANSFER SYSTEMS 7-7
7.2.1 Design Criteria 7-7
7.2.2 Design Features 7-7
7.3 SHIELDING COMPOSITION AND DETAILS 7-8
7.3.1 Composition and Material Properties 7-8
7.3.2 Shielding Details 7-8
7.4 SHIELDING ANALYSES METHODS AND RESULTS 7-10
7.4.1 Computational Methods and Data 7-10
7.4.2 Dose and Dose Rate Estimates 7-10
7.5 SUMMARY 7-20
CHAPTER 8: CRITICALITY EVALUATION 8-1
8.0 INTRODUCTION 8-1
8.1 CRITICALITY DESIGN CRITERIA AND FEATURES 8-3
8.1.1 Criteria 8-3

8.1.2 Features 8-3
8.2 STORED MATERIAL SPECIFICATIONS 8-4
8.3 EVALUATION 8-5
8.3.1 Model Configuration 8-5
8.3.2 Accidental Criticality 8-5
8.4 APPLICANT CRITICALITY ANALYSIS 8-7
8.5 CRITICALITY MONITORING 8-8
CHAPTER 9: CONFINEMENT EVALUATION 9-1
9.0 INTRODUCTION 9-1
9.1 ACCEPTANCE CRITERIA 9-3
9.2 CONFINEMENT OF RADIOACTIVE MATERIALS 9-4
9.2.1 Storage Systems 9-4
9.2.2 Operational Activities 9-5
9.3 POOL AND WASTE MANAGEMENT FACILITIES 9-8
9.3.1 Pool Facilities 9-8
9.3.2 Waste Management Facilities 9-8
9.4 CONFINEMENT MONITORING 9-9
9.4.1 Storage Confinement Systems 9-9
9.4.2 Effluents 9-9
9.5 PROTECTION OF STORED MATERIALS FROM DEGRADATION 9-10
9.5.1 Confinement Casks or Systems 9-10
9.5.2 Pool and Waste Management Systems 9-10
9.6 SUMMARY 9-11
CHAPTER 10: CONDUCT OF OPERATIONS 10-1
10.0 INTRODUCTION 10-1
10.1 ORGANIZATIONAL STRUCTURE 10-2
10.1.1 Corporate and On-site Organization 10-2
10.1.2 Support Staff (ISFSI Specialists) 10-2
10.2 PREOPERATIONAL TESTING AND STARTUP OPERATIONS 10-5
10.2.1 Administrative Procedures for Conducting the Test Program 10-5
10.2.2 Preoperational Testing Plan 10-5
10.2.3 Evaluation of Tests 10-7

10.2.4 Corrective Actions 10-7
10.3 NORMAL OPERATIONS 10-10
10.3.1 Procedures 10-10
10.3.2 Records 10-10
10.3.3 Conduct of Operations 10-11
10.3.4 Maintenance Program for the HI-STORM UMAX VVM & HI-TRAC CS 10-16
10.3.5 Maintenance Program for the Canister 10-18
10.4 PERSONNEL SELECTION, TRAINING, AND CERTIFICATION 10-23
10.4.1 Personnel Organization 10-23
10.4.2 Selection and Training of Operating Personnel 10-23
10.4.3 Selection and Training of Security Guards 10-23
10.5 EMERGENCY PLANNING 10-26
10.6 PHYSICAL SECURITY AND SAFEGUARDS CONTINGENCY PLANS 10-27
10.7 SUMMARY 10-28
CHAPTER 11: RADIATION PROTECTION EVALUATION 11-1
11.0 INTRODUCTION 11-1
11.0.1 Ensuring Occupational Radiation Exposures are As Low As is Reasonably Achievable 11-1
11.1 AS-LOW-AS-REASONABLY-ACHIEVABLE (ALARA) CONSIDERATIONS 11-4
11.1.1 ALARA Policies and Programs 11-4
11.1.2 Design Considerations 11-5
11.1.3 Operational Considerations 11-8
11.2 RADIATION PROTECTION DESIGN FEATURES 11-10
11.2.1 Installation Design Features 11-10
11.2.2 Access Control 11-11
11.2.3 Radiation Shielding 11-11
11.2.4 Confinement and Ventilation 11-12
11.2.5 Area Radiation and Airborne Radioactivity Monitoring Instrumentation 11-12
11.3 DOSE ASSESSMENT 11-14
11.3.1 Onsite Dose 11-14
11.3.2 Offsite Dose 11-14
11.4 RADIATION PROTECTION PROGRAM 11-17

11.4.1 Organizational Structure 11-17
11.4.2 Equipment, Instrumentation, and Facilities 11-18
11.4.3 Policies and Procedures 11-19
11.5 REGULATORY COMPLIANCE 11-21
CHAPTER 12: QUALITY ASSURANCE PROGRAM 12-1
12.0 INTRODUCTION 12-1
12.0.1 Overview 12-1
12.0.2 Graded Approach to Quality Assurance 12-2
12.1 REGULATORY COMPLIANCE 12-3
CHAPTER 13: DECOMISSIONING EVALUATION 13-1
13.0 INTRODUCTION 13-1
13.1 DESIGN FEATURES 13-3
13.2 OPERATIONAL FEATURES 13-4
13.3 DECOMMISSIONING PLAN 13-5
13.3.1 General Provisions 13-5
13.3.2 Cost Estimate 13-5
13.3.3 Financial Assurance Mechanism 13-6
13.4 REGULATORY COMPLIANCE 13-7
CHAPTER 14: WASTE CONFINEMENT AND MANAGEMENT EVALUATION 14-1
14.0 INTRODUCTION 14-1
14.1 WASTE SOURCES 14-2
14.2 OFF-GAS TREATMENT AND VENTILATION 14-3
14.3 LIQUID WASTE TREATMENT AND RETENTION 14-4
14.4 SOLID WASTES 14-5
14.5 RADIOLOGICAL IMPACT OF NORMAL OPERATIONS 14-6
14.6 REGULATORY COMPLIANCE 14-7
CHAPTER 15: ACCIDENT ANALYSIS 15-1
15.0 INTRODUCTION 15-1
15.1 ACCEPTANCE CRITERIA 15-3
15.1.1 Off-Normal Events 15-3
15.1.2 Accident Events 15-3
15.2 OFF-NORMAL EVENTS 15-4

15.2.1 Off-Normal Pressure 15-4
15.2.2 Off-Normal Environmental Temperature 15-5
15.2.3 Leakage of One Seal 15-5
15.2.4 Partial Blockage of the Air Inlet Plenum 15-5
15.2.5 Hypothetical Non-Quiescent Wind 15-6
15.2.6 Cask Drop Less Than Design Allowable Height 15-6
15.2.7 Off-Normal Events Associated with Pool Facilities 15-6
15.2.8 Safety Evaluation 15-6
15.3 ACCIDENTS 15-7
15.3.1 Fire Accident 15-7
15.3.2 Partial Blockage of MPC Basket Vent Holes 15-10
15.3.3 Tornado Missiles 15-10
15.3.4 Flood 15-11
15.3.5 Earthquake 15-12
15.3.6 100% Fuel Rods Rupture 15-13
15.3.7 Confinement Boundary Leakage 15-14
15.3.8 Explosion 15-14
15.3.9 Lightning 15-14
15.3.10 100% Blockage of Air Inlets 15-14
15.3.11 Burial Under Debris 15-14
15.3.12 Extreme Environmental Temperature 15-14
15.3.13 Cask Tipover 15-14
15.3.14 Cask Drop 15-14
15.3.15 Loss of Shielding 15-15
15.3.16 Adiabatic Heatup 15-15
15.3.17 Accidents at Nearby Sites 15-15
15.3.18 Accidents Associated with Pool Facilities 15-15
15.3.19 Building Structural Failure onto SSCs 15-15
15.3.20 100% Rod Rupture Accident Coincident with Accident Events 15-16
15.4 OTHER NON-SPECIFIED ACCIDENTS 15-18
15.5 I&C SYSTEMS 15-19
15.6 REGULATORY COMPLIANCE 15-20

CHAPTER 16: TECHNICAL SPECIFICAITONS 16-1
16.0 INTRODUCTION 16-1
16.1 FUNCTIONAL/OPERATING LIMITS, MONITORING INSTRUMENTS, AND LIMITING CONTROL SETTINGS 16-3
16.2 LIMITING CONDITIONS 16-4
16.3 SURVEILLANCE REQUIREMENTS 16-5
16.4 DESIGN FEATURES 16-6
16.5 ADMINISTRATIVE CONTROLS 16-7
16.6 REGULATORY COMPLIANCE 16-9
APPENDIX 16.A TECHNICAL SPECIFICATIONS (LCO) BASES FOR THE HOLTEC CIS FACILITY 16.A-1
CHAPTER 17: MATERIAL CONSIDERATIONS 17-1
17.0 INTRODUCTION 17-1
17.1 MATERIAL DEGRADATION MODES 17-6
17.2 MATERIAL SELECTION 17-11
17.2.1 Structural Materials 17-11
17.2.2 Non-Structural Materials 17-12
17.3 APPLICABLE CODES AND STANDARDS 17-16
17.4 MATERIAL PROPERTIES 17-17
17.4.1 Mechanical Properties 17-17
17.4.2 Thermal Properties 17-17
17.4.3 Protection Against Brittle Fracture of Ferritic Steel Parts 17-17
17.4.4 Protection Against Creep 17-18
17.5 WELDING MATERIAL AND WELDING SPECIFICATION 17-20
17.6 BOLTS AND FASTNERS 17-22
17.7 COATINGS AND CORROSION MITICATION 17-23
17.7.1 Exterior Coating 17-23
17.8 GAMMA AND NEUTRON SHIELDING MATERIALS 17-25
17.8.1 Plain Concrete 17-25
17.9 NEUTRON ABSORBING MATERIALS 17-26
17.10 SEALS 17-27
17.11 CHEMICAL AND GALVANIC REATIONS 17-28

17.12 FUEL CLADDING INTEGRITY 17-30
17.13 EXAMINATIONS AND TESTING 17-31
17.14 REGULATORY COMPLIANCE 17-32
CHAPTER 18. AGING MANAGEMENT PROGRAM 18-1
18.0 INTRODUCTION 18-1
18.1 SCOPING EVALUATION AND SEVERITY INDEX 18-4
18.2 MAINTENANCE PROGRAM FOR THE HI-STORM UMAX VVM & HI-TRAC CS 18-6
18.3 MECHANISMS FOR AGING OF SSCS 18-7
18.4 UNIQUE ASPECTS OF THE HI-STORE CIS WITH NEXUS TO ITS AMP 18-13
18.5 CANISTER AGING MANAGEMENT PROGRAM 18-14
18.5.1 Visual Examination 18-14
18.5.2 Accelerated Coupon Testing 18-14
18.5.3 Eddy Current Testing 18-15
18.6 HI-TRAC CS TRANSFER CASK AGING MANAGEMENT PROGRAM 18-18
18.7 VVM AGING MANAGEMENT PROGRAM 18-20
18.8 REINFORCED CONCRETE AGING MANAGEMENT PROGRAM 18-21
18.9 HBF AGING MANAGEMENT PROGRAM 18-22
18.10 LIFTING DEVICE AGING MANAGEMENT PROGRAM 18-23
18.11 LEARNING BASED AMP 18-24
18.12 TIMING OF AGING MANAGEMENT IMPLEMENTATION 18-26
18.12.1 Canisters 18-26
18.12.2 All Other SSCs 18-26
18.13 AMELIORATING THE RISK OF CANISTER DEGRADATION OVER A LONG TERM STORAGE DURATION 18-27
18.14 RECOVERY PLAN 18-28
CHAPTER 19: REFERENCES 19-1

CHAPTER 1: GENERAL DESCRIPTION*

1.0 INTRODUCTION

This Safety Analysis report, prepared pursuant to 10CFR72.24, provides the necessary information to justify the licensing of an Independent Spent Fuel Storage Installation (ISFSI) facility on an extensively assayed and environmentally qualified land in southeastern New Mexico. The storage facility has been named HI-STORE CIS, the acronym CIS intended to denote consolidated interim storage pursuant to the Presidential Blue Ribbon Commission report [1.0.1] subsequently adopted by the US Department of Energy (USDOE).

It is planned to situate HI-STORE CIS on a large parcel of presently unused land owned by ELEA, LLC. ELEA was formed in 2006 in accordance with an enabling legislation passed in New Mexico and consists of an alliance of (in alphabetical order) the city of Carlsbad, the county of Eddy, the city of Hobbs and the county of Lea which together, as shown in the geographical layout in Figure 1.0.1 completely surround the proposed site. (ELEA is a composite of **E**ddy and **Lea** counties which are members of the alliance). As HI-STORE CIS is an autonomous facility without any physical nexus to an operating reactor, it qualifies being referred to as an away-from-reactor (AFR) facility.

The ELEA/ Holtec compact envisages Holtec securing the site specific license pursuant to 10CFR72.6 for the HI-STORE CIS from the USNRC, carrying out the necessary detailed designs & site construction, and managing CIS' security, maintenance and ongoing operations. Thus Holtec International will serve as the operator of the HI-STORE CIS with undivided responsibility for its safety and security. Holtec International has also committed to ELEA that the storage technology deployed at the HI-STORE CIS will meet the site boundary dose limit specified in 10CFR72 [1.0.5] with substantial margins under any normal and credible accident scenarios.

The HI-STORE CIS will be built in several stages of storage system groups to correspond to the (expected) increasing need from the industry and the US government. The first stage of the storage module group and other overview information on the site germane to its intended use can be found in Table 1.0.1.

The major milestone dates for licensing, building and commissioning the HI-STORE CIS facility are presented in Table 1.0.2. This milestone schedule presumes continued DOE and NRC support and enthusiasm on the part of the utilities to avail themselves of this facility.

This license application accordingly contains the necessary information specified in Regulatory Guide 3.50 [1.0.2] and in NUREG-1567 [1.0.3] to articulate the safety case for the site specific license pursuant to 10CFR72.6. In accordance with 10CFR72.24, the site-specific license for HI-STORE CIS requires a comprehensive consideration of all aspects of the facility that bear upon its safe and ALARA installation and operation. These include:

* All references are in placed within square brackets in this report and are compiled in Chapter 19 of this report

- Siting of the AFR site and design of the storage and security system. Site-specific demonstration of compliance with regulatory dose limits. Implementation of a facility-specific ALARA program.
- An evaluation of site-specific hazards and design conditions that may exist at the AFR site or the transfer route between the plant's cask Receiving Area and the storage location. These include all naturally occurring extreme environmental phenomena that are defined as credible events in the Environmental Report[1.0.4] for the HI-STORE CIS facility
- Determination that the physical and nucleonic characteristics and the condition of the SNF assemblies to be stored meet the fuel acceptance requirements for the site.
- Detailed site-specific operating, maintenance, and inspection procedures prepared in accordance with the generic procedures and requirements provided in Chapters 3 and 10 herein.
- Performance of pre-operational testing.
- Implementation of a safeguards and accountability program in accordance with 10CFR73. Preparation of a physical security plan in accordance with 10CFR73.55.
- Essentials of the site emergency plan, quality assurance (QA) program, training program, and radiation protection program.

In addition to the sixteen chapters set forth in NUREG-1567, Chapters 17 and 18 have been added to this SAR to explicitly address material selection considerations and long term Ageing Management.

This safety analysis report on the HI-STORE CIS is limited at this time to the canisters and contents approved by the NRC in the generic docket (# 72-1040) for HI-STORM UMAX. Table 1.0.3 identifies systems, components, and/or documents submitted to and approved by the NRC in other dockets and incorporated in this application by reference. Table 1.0.3 indicates the native and subsequent adoption dockets for systems and documents incorporated by reference (including systems/components safety analyses) into this HI-STORE application.

Within this report, all figures, tables and references cited are identified by the double decimal system *m.n.i*, where *m* is the chapter number, *n* is the section number, and *i* is the table number. For a complete listing of Tables and Figure the Table of Contents should be consulted. For example, Figure 1.2.1 is the first figure in Section 1.2 of Chapter 1. Similarly, the following convention is used in the organization of chapters:

a. A chapter is identified by a whole numeral, say *m* (i.e., *m*=3 means Chapter 3)

b. A section is identified by one decimal separating two numerals. Thus, Section 3.1 is section 1 in Chapter 3.

c. A subsection has three numerals separated by two decimals. Thus, Subsection 3.2.1 is subsection 1 in Section 3.2.

d. A paragraph is denoted by four numerals separated by three decimals. Thus, Paragraph 3.2.1.1 is paragraph 1 in Subsection 3.2.1.

e. A subparagraph has five numerals separated by four decimals. Thus, Subparagraph 3.2.1.1.1 is subparagraph 1 in Paragraph 3.2.1.1.

Tables and figures associated within a section are placed after the text narrative. The drawing packages are controlled separately within the Holtec QA program with individual revision numbers and are included in Section 1.5 of this chapter.

Finally, the Glossary contains a listing of the terminology and notation used in this SAR.

1.0.1 10 CFR 72.48 Evaluations

It is noted that the information incorporated herein by reference is based on the docketed, NRC – approved licensing basis. If any change is made to a canister under the original licensing basis using 10CFR72.48, such change will need to be evaluated against the HI-STORM UMAX FSAR before the canister can be stored in a HI-STORM UMAX system.

Canister records must be provided to the HI-STORE facility personnel prior to shipment of a canister. These records must be reviewed and any applicable 10CFR72.48 screenings or evaluations written against the canister's original licensing basis evaluated against the HI-STORE site specific license to determine if a change requiring NRC approval is necessary.

To facilitate evaluation and to avoid clutter in this SAR, the numerical results of the safety analyses summarized in this document are reported along with, where practicable, an "unconditionally safe threshold" value. The unconditionally safe threshold value (please see Glossary) is defined as the numerical result that defines the boundary of a materially non-consequential & insignificant change that does not require the use of a 10CFR72.48 change process avoiding the need to modify the material in the SAR; rather, the documentation of the "change" may be limited to the calculation package and other actionable project documents. A result that exceeds the unconditionally safe threshold (UST) value requires the implementation of the 10CFR72.48 process to determine the admissibility of the proposed change.

Table 1.0.1: Overview of the HI-STORE Facility		
Item	**Data**	**Comment**
Land area of the site	1045 acres	Overall land area
Maximum design capacity Envisaged in this license application (UMAX/Canisters)	10,000	Each stage is envisaged to have 500 storage cavities.
Maximum quantity of Uranium (Note 1)	173,600 MTUs	Each stage is envisaged to have 8,680 MTUs
Maximum number of stages envisaged for the HI-STORE CIS Facility to reach design capacity	Up to 20 stages	Each construction stage to take up to 1 year to complete
Capacity of the installation for the first licensing application	500	19 subsequent expansion phases to be constructed over course of 20 years and under future licensing applications
Total land area occupied by the storage system at maximum capacity	Approx. 288 acres	Includes restricted ISFSI area, parking lot, administrative building, security building and batch plant
Land area occupied by the CIS storage systems as a percentage of the total site area	Approx. 28%	See comment above.
Storage system type used at the site	HI-STORM UMAX (NRC Docket # 72-1040 [1.0.6])	Introduced in Section 1.2
Distance of the nearest permanent human settlement from the site	1.5 miles	Ranch north of the site, see Chapter 2
Distance from nearest loaded UMAX VVM to Site Boundary (Controlled Area Boundary)	400 meters (1,312 feet)	Occupancy at this distance is conservatively assumed to be 2000 hours per year, see Chapter 7
Approximate number of permanent residents in 6 miles radius from the center of the site	Less than 20 (average)	Total of five ranches, see Chapter 2
Elevation of the site above sea level, feet	3520 to 3540	No risk of flood, see Chapter 2
Geological formation	Stable	No known faults in the region, see Chapter 2

Table 1.0.1: Overview of the HI-STORE Facility		
Location(distance) of the existing rail terminal from the site	3.8 miles west (SWR) 32 miles east (TNMR)	Southwestern Railroad (SWR) Texas-New Mexico Railroad (TNMR)
Maximum excavation depth required to build the facility	Approx. 25 feet	Construction activity will not be in contact with groundwater

Note 1: Maximum quantity of uranium per loaded canister is for design basis PWR fuel assembly (MPC-37) for the HI-STORM UMAX. The quantity of uranium per loaded MPC-37 canister bounds the quantity per loaded canisters containing BWR fuel assembly.

Table 1.0.2: Projected Milestone dates for HI-STORE CIS*	
Activity	**Scheduled or expected date**
License Application Submitted	March 2017
License Application Approval	March 2019
Site preparation begins	June 2018
Site construction begins	December 2018
Site and ISFSI construction completed	March 2021
Protected area and security infrastructure established	June 2021
Site Specific procedures prepared, vetted and adopted	December 2021
Site QA and Safety program installed	December 2021
Facility pre-commissioning (dry run) begins	December 2021
Facility declared operational –NRC's concurrence secured	June 2022
First batch of canisters arrives at the site's Receiving Area	June 2022

* Pursuant to the provisions in 10CFR72.40(b), the site construction of the HI-STORE CIS facility will require regulatory approval. Additionally, in accordance with 10CFR72.22, the construction program will be undertaken only after a definitive agreement with the prospective user/payer for storing the used fuel (USDOE and/or a nuclear plant owner) at HI-STORE CIS has been established. These regulatory and contractual predicates may adversely affect the schedule dates and durations set forth in this table.

Table 1.0.3: Systems and Documents Incorporated by Reference for HI-STORE (Note 1)		
System/Document	**Native Docket)**	**Secondary Adoption Docket**
HI-STORM UMAX System	72-1040	N/A
HI-STORM FW Canisters (MPCs 37 and 89)	72-1032	72-1040
Holtec International QA Manual	71-0784	72-1040
Note 1: Where specifically incorporated by reference in this report, additional information such as report title, sections or specific analyses within reports incorporated by reference, and technical justification of applicability to HI-STORE CIS Facility are provided.		

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

Figure 1.0.1: Geographical Layout of Proposed HI-STORM UMAX CIS ISFSI Site

1.1 GENERAL DESCRIPTION OF INSTALLATION

The HI-STORE CIS Facility layout drawing in Section 1.5 provides the general arrangement of the HI-STORE CIS Facility. The facility (site) layout drawing depicts the site at design basis capacity (Table 1.0.1). However, this application is limited to the initial licensing capacity (Table 1.0.1). As shown in the layout drawing, the HI-STORE CIS consists of the following SSCs:

a. The HI-STORM UMAX VVMs (Figure 1.2.2)

b. Rail Spur and Cask receiving area

c. Equipment Building to store HI-TRAC, the Vertical Cask Transporter, ancillaries and spare parts.

d. Administrative Building to house inspection, security and administrative staff as well as access control facilities.

e. Security Building at the entrance to ISFSI to house security personnel, some health physics staff as required and some health physics or other monitoring instruments.

The following features of the Facility are important to its safety and security functions and to its emergency preparedness:

a. Each ISFSI pad is separated from its adjacent pad by a substantial mass of earth (Table 1.1.1) to ensure that the excavation for a pad with an adjacent operating ISFSI would not introduce a geo-structural or shielding problem.

b. As can be seen from Figure 1.2.1, there are no large obstructions in the storage region that may block the visual ability to identify an intruder.

c. The storage pads and ISFSI at large are equipped with an efficient drainage system.

d. Parking facility for cars, trucks and other conveyances are located far from the fuel storage area to preclude the risk of a mass fire from combustion of fuel or transmission fluid.

e. A substantial area adjacent to the loaded ISFSI is cleared of any brush or foliage that may serve as a fire stimulant.

f. The data in Table 1.1.1 provides additional information on the HI-STORE Facility. The HI-STORE facility systems descriptions are provided in Section 1.2.

Table 1.1.1: HI-STORE CIS General arrangement data	
Item	**Value**
Nominal layout of each pad	25 by 20
Inter-cavity pitch	17 feet
Pad to Pad distance	100 feet
Nominal Size of the Equipment Storage Building (non-safety)	60 feet by 75 feet
Nominal size of the Admin Building (non-safety)	50 feet by 75 feet
Nominal Size of the Cask Transfer Building (CTB) (Length/Width/Height)	350 x 100 x 60 (feet)

1.2 GENERAL SYSTEMS DESCRIPTION

1.2.1 HI-STORM UMAX System Overview

The centerpiece of the HI-STORE CIS facility is the HI-STORM UMAX canister storage system certified in NRC docket # 72-1040. HI-STORM UMAX is the subterranean version of HI-STORM FW and HI-STORM 100 of which the latter was the reference storage system for the licensed AFR site scheduled to be sited in the PFS LLC's Skull Valley, Utah licensed in 2006 in docket # 72-22. The HI-STORM UMAX stores a hermetically sealed canister containing spent nuclear fuel in a subterranean in-ground Vertical Ventilated Module (VVM). The safety evaluation of HI-STORM UMAX is maintained in USNRC docket # 72-1040. The annex identifier UMAX is an acronym of Underground MAXimum safety.

HI-STORM UMAX is a dry, in-ground spent fuel storage system consisting of any number of Vertical Ventilated Modules (VVMs) each containing one canister. The HI-STORM UMAX has all the safety attributes that are attributed to in-ground storage, such as enhanced protection from incident projectiles and threats from extreme environmental phenomena such as hurricanes, tornado borne missiles, earthquakes, tsunamis, fires, and explosions. Figure 1.2.1 provides a pictorial illustration of an array of HI-STORM UMAX systems that depicts its security-friendly diminutive profile.

The HI-STORM UMAX version that will be employed in the HI-STORE CIS is essentially the design (without the ultra-high earthquake-resistant options, referred to as MSE options) licensed in the HI-STORM UMAX docket (72-1040). The only other respect in which the HI-STORE VVM design differs from the generic FSAR design is the provision that the storage cavity depth is made fixed (not variable, as permitted in the general certification) at two discrete dimensions. The height of the lateral seismic restraint at the top of the canister is adjusted to accord with the height of the canister that will be stored in the cavity, and a second set of seismic restraints are situated between the Divider Shell and Cavity Enclosure Container (CEC) at the same height and location as the lateral seismic restraint. As a result, the structural performance of the system remains unaffected and other safety metrics such as shielding and thermal (heat rejection) are either unaffected or improved (depending on the height of the canister being stored).

To differentiate this minor tweak to the HI-STORM UMAX configuration deployed in the past, the HI-STORM UMAX drawings in Section 1.5 of this chapter refer to the HI-STORE VVM as Version C. Version C's certification basis remains in docket # 72-1040; it is not a new embodiment from a certification standpoint. The drawing package for Version C is included in this SAR principally to avoid having to refer to the drawing sets in the HI-STORM UMAX FSAR, which include several geometric options not used in the Version C design.

The essential characteristics of HI-STORM UMAX that make it uniquely suitable to serve as the heart of the proposed consolidated interim storage facility are:

a. The canister is stored below-grade which makes it essentially invulnerable to the various extreme environmental phenomena that arise in nature. The intensity of the earthquake

for which the HI-STORM UMAX system is qualified (documented in this SAR) bounds the Design Basis Earthquake for the site.

b. The HI-STORM UMAX storage system provides an essentially inviolable protection to the stored canisters against incident missiles such as a crashing aircraft. The source of the structural protection of the canister in HI-STORM UMAX lies in the fact that the only path for an incident missile to access the canister is by piercing the thick lid which is made of a steel weldment buttressed by concrete. The lateral surface of the canister is protected by a self-hardening engineered subgrade (SES) around each canister and by the surrounding expanse of the earth beyond. While the top lid is presently designed for 10CFR72 Design Basis Missiles, it can be effortlessly swapped for an even more impregnable lid structure if the level severity of threat to the facility were to increase in the future.

c. The storage cavity of HI-STORM UMAX is sufficiently large to accommodate *every* canister type licensed under different 10CFR72 dockets and in use in the United States at this time. Therefore, it is possible to qualify the entire universe of used fuel canisters presently deployed at the ISFSIs around the country for storage in the HI-STORM UMAX system. HI-STORM UMAX is intended to provide a safe and regulation-compliant storage for even NUHOMS canisters which are normally stored horizontally. (The safety analysis in support of LAR# 3 to the HI-STORM UMAX CoC indicates that all metrics for safe storage including decay heat rejection are maintained or improved when a canister is rotated to the vertical storage orientation in HI-STORM UMAX from its native horizontal storage in NUHOMS. LAR # 3 to the HI-STORM UMAX CoC is not a part of this application, but may be incorporated through a licensing action at a later date)

d. Because the on-site canister transfer operation (described in Section 10.3 herein) occurs vertically (specifically, doesn't involve horizontal pushing or pulling of the heavy loaded canister against surface friction), there is no risk of gouging or scratching of the ASME code boundary of the canister. This is an important benefit at a CIS site where (presumably) thousands of canisters will be handled.

e. As can be ascertained from the design information in this SAR, the HI-STORM UMAX CIS features no above-ground important-to-safety building structure. All canister transfer facilities are below-ground.

f. As described in the canister Aging Management Program [1.2.1], a canister installed in a HI-STORM UMAX cavity can be remotely examined to assay the state of integrity of its confinement boundary shell making its long term monitoring a low dose activity.

g. Because of its below-ground fuel storage configuration, the HI-STORM UMAX CIS meets the site boundary accident dose limit of 10CFR72.106 with large margins, as quantified in Section 7.4 of this SAR. The minuscule accreted dose, zero effluent release, and extreme hazard-resistance features of the HI-STORM UMAX CIS facility will make

its footprint on the environment vanishingly small, as described in the Environmental Report [1.0.4].

h. The canister's confinement boundary consists of thick circular stainless steel plate-type parts at the two extremities joined by a relatively thin shell. As a result, it is the canister's shell that has been the focus of stress corrosion cracking threat over prolonged periods of storage. Unlike horizontally disposed canister, the canister shell in HI-STORM UMAX is not in physical contact with any other structure precluding the risk of crevice corrosion, galvanic corrosion, etc.

Finally, it is instructive to note that the canister in HI-STORM UMAX is laterally confined at its top and bottom extremities inside the HI-STORM UMAX VVM cavity so that it would not significantly move or rattle under a seismic event. Thus the thermal-hydraulic flow configuration around the canister is fixed for the duration of storage. This lateral fixity feature in the HI-STORM UMAX storage system along with its subterranean disposition are key reasons that underlie its ability to withstand severe earthquakes.

All HI-STORM UMAX System components are and their sub-components are categorized as ITS, as applicable, in accordance with NUREG/CR-6407 [1.2.2].

To summarize, the HI-STORM UMAX System has been engineered to:

- maximize shielding and physical protection for the canister;
- minimize the extent of handling of the SNF;
- minimize dose to operators during loading and handling;
- require minimal ongoing surveillance and maintenance by plant staff;
- facilitate SNF transfer of the loaded canister to a compatible transport overpack for transportation;

1.2.2 Constituents of the HI-STORM UMAX Vertical Ventilated Module and ISFSI Structures

The HI-STORM UMAX VVM, shown in the licensing drawing in Section 1.5 provides for storage of the canister in a vertical configuration inside a subterranean cylindrical cavity entirely below the top-of-grade (TOG) of the ISFSI. The key constituents of a HI-STORM UMAX VVM and ISFSI structures are:

(i) VVM Components

a. The Cavity Enclosure Container (CEC)

b. The Divider Shell

c. The Closure Lid

(ii) ISFSI Structures

d. The ISFSI Pad

e. The Support Foundation Pad

f. The Subgrade and Under-grade

A brief description of each constituent part is provided in the following:

a. Cavity Enclosure Container:

The Cavity Enclosure Container (CEC) consists of a thick walled shell integrally welded to a bottom plate. The top of the container shell is stiffened by a ring shaped flange which is also integrally welded. The constituent parts of the CEC are made of low carbon steel plate. In its installed configuration, the CEC is interfaced with the surrounding subgrade for most of its height except for the top region where it is encased in the ISFSI pad.

With the Closure Lid removed, the CEC is a closed bottom, open top, thick walled cylindrical vessel that has no penetrations or openings. Thus, groundwater has no path for intrusion into the interior space of the CEC. Likewise, any water that may be introduced into the CEC through the air passages in the top lid will not drain into the groundwater.

The CEC top contains an air plenum box which works in conjunction with the Closure Lid to channel incoming air into the down-comer flowing region of the CEC. The air plenum box also contains rigid embedded locations for securing the HI-TRAC CS against movement during Canister Transfer operations.

b. Divider Shell:

The Divider Shell is important to the thermal performance of the VVM system. The Divider Shell, as its name implies, is a removable vertical cylindrical shell concentrically situated in the CEC that divides the CEC into an inlet flow down-comer and an outlet flow passage. The Divider Shell divides the radial space between the canister and the CEC cavity into two annuli. The bottom end of the Divider Shell has cutouts to enable movement of air from the down-comer to the up-flow region around the canister. The cutouts in the Divider Shell are sufficiently tall to ensure that if the cavity were to be filled with water, the bottom region of the canister would be submerged to a depth of several inches. This design feature ensures adequate thermal performance of the system if flood water were to block air flow. The Divider Shell is not attached to the CEC which allows its convenient removal for decommissioning or for any in-service maintenance or periodic inspection.

The cylindrical surface of the Divider Shell is equipped with insulation to prevent significant preheating of the inlet air. The insulation material is selected to be water and radiation resistant as well as non-degradable under accidental wetting.

c. The Closure Lid:

The Closure Lid is a steel structure filled with plain concrete that can withstand the impact of the Design Basis Missiles defined for the site. Both the inlet and outlet vents are located at the grade level. The Closure Lid internals form segregated air channels for air inlet and outlet. A set of inlet passage located on top of the CEC provide maximum separation from the large outlet passage which is located in the center of the lid and channel the inlet air into the CEC's air

plenum box. As depicted in the licensing drawings in Section 1.5, the geometry of the inlet and outlet ducts make the HI-STORM UMAX VVM essentially insensitive to the direction and speed of the wind.

The Closure Lid fulfills the following principal performance objectives:

1 The Closure Lid is physically constrained against horizontal movement during a Design Basis Earthquake event or a tornado missile strike.

2 To minimize the radiation emitted from the storage cavity, a portion of the Closure Lid extends into the cylindrical space above the canister. This cylindrical below-surface extension of the Closure Lid is also made of steel filled with shielding concrete to maximize the blockage of skyward radiation issuing from the canister.

3 As can be seen from the drawings in Section 1.5, the Closure Lid is substantially larger in diameter than the CEC and the canister is positioned to be at a significant vertical depth below the top of the Container Flange. These geometric provisions ensure that the Closure Lid will not fall into the canister storage cavity space and strike the canister were to accidentally drop during its handling. Because the Closure Lid is the only removable heavy load, the carefully engineered design features to facilitate recovery from its accidental drop provide added assurance that a handling accident at the ISFSI will not lead to any radiological release. This additional measure against accidental Closure Lid drop does not replace the drop prevention features mandated in this Safety Report on heavy load lifting devices (such as the cask transporter) that have been a standard and established requirement in the HI-STORM dockets.

d. The ISFSI Pad:

The ISFSI Pad serves to augment shielding, to provide a sufficiently stiff riding surface for the cask transporter, to act as a barrier against gravity-induced seepage of rain or floodwater around the VVM body as well as to shield against a missile. The ISFSI pad is a monolithic reinforced concrete structure that provides the load bearing surface for the cask transporter. The appropriate requirements on the structural strength of the ISFSI pad are specified in Section 4.3.

e. The Support Foundation Pad:

The Support Foundation Pad (SFP) is the underground pad which supports the HI-STORM UMAX ISFSI. The SFP on which the VVM rests must be designed to minimize long-term settlement. The SFP and the under-grade must have sufficient strength to support the weight of all the loaded VVMs during long-term storage and earthquake conditions. As the weight of the loaded VVM is comparable to the weight of the subgrade which it replaces, the additional pressure acting on the SFP is quite small. The appropriate requirements on the structural strength of the SFP are specified in Section 4.3.

f. The Subgrade and Under-grade:

The lateral space between each CEC, the SFP and the ISFSI pad is referred to as the subgrade and is filled with a Controlled Low-Strength Material (CLSM). Alternatively, “lean concrete” may also be used.

CLSM is a self-compacted, cementitious material used primarily as a backfill in place of compacted fill. ACI 229R-99 notes several terms, such as flowable fill, unshrinkable fill, controlled density fill, flowable mortar, flowable fly ash, fly ash slurry, plastic soil-cement and soil-cement slurry to describe CLSMs. ACI 116R-00 defines lean concrete as a material with low cementitious content. CLSM and lean concrete are also referred to as "Self-hardening Engineered Subgrade" (SES).

The subgrade material must meet the shear velocity and density requirements in Section 4.3. The space below the SFP is referred to as the under-grade.

Evaluations in Section 5.4 show that the Self-hardening Engineered Subgrade (SES) provides a stable lateral support system to the ISFSI under the Design Basis Earthquake. The interface between the SES and the native subgrade defines the radiation protection boundary of the ISFSI.

1.2.3 Design Characteristics of the HI-STORM UMAX VVM

All HI-STORM UMAX locations are alike except for their cavity depth. The design of HI-STORM UMAX cavities has been standardized into certain discrete depths as tabulated in the Licensing Drawing Package (Section 1.5). Different depth HI-STORM UMAX cavities enable canisters of different heights to be housed in the cavity of appropriate depth. The maximum HI-STORM UMAX cavity depth corresponds to that certified in docket # 72-1040.

The liberal pitch between the CEC cavities, as shown in the Licensing Drawing package, allows the Cask Transporter to traverse over any storage cavity and independently access any storage location. Thus, any canister located in any storage cavity can be independently accessed and retrieved using a qualified Vertical Cask Transporter (VCT) and a suitable transfer cask.

The essential design and operational features of the HI-STORM UMAX System are:

a. Because of its underground staging in HI-STORM UMAX, tip-over of the canister in storage is not possible.

b. In HI-STORM UMAX Version C, there are two fixed cavity depths referred to as Type SL and Type XL, respectively. Type SL cavity is sized to permit storage of all BWR fuel bearing canisters and PWR canisters that are shorter than the reference BWR canister. Type XL is a deeper cavity sized to accommodate the canisters that accommodate SNF from South Texas and AP-1000 plants (which are exceptionally long). The vast majority of the storage cavities will be of the "SL" type. For all canister heights, the VVM constraint at the top of the canister are positioned to engage with the structurally robust canister lid where the Divider Shell is also hardened against lateral loads.

c. To exploit the biological shielding provided by the surrounding soil subgrade, the canister is entirely situated well below the top-of-grade level. The open plenum above the canister also acts to boost the ventilation action of the coolant air.

d. Removal of water from the bottom of the storage cavity can be carried out by the simple expedient use of a flexible hose inserted through the air inlet or outlet passageways.

e. All practical efforts are made to coat exposed surfaces of the VVM with proven low VOC and/or ANSI/NSF Standard 61 [1.2.3] compliant surface preservatives to preclude toxicological effects on the environment to the maximum reasonable extent.

1.2.3.1 Shielding Materials

Steel, concrete, and the subgrade are the principal shielding materials in the HI-STORM UMAX. The steel and concrete shielding materials in the Closure Lid provide additional gamma and neutron attenuation to reduce dose rates.

The fuel basket structure provides the initial attenuation of gamma and neutron radiation emitted by the radioactive contents. The canister shell, baseplate, and thick lid provide additional gamma attenuation to reduce direct radiation.

1.2.3.2 Lifting Devices

Lifting and handling devices used to load or unload a canister into the HI-STORM UMAX VVM shall be designed per Paragraph 1.2.1.5 of the HI-STORM FW FSAR (docket # 72-1032).

The lifting and handling of all heavy loads that are within 10CFR72 jurisdiction, such as the HI-TRAC (Transfer Cask) and the HI-STORM UMAX Closure Lid, shall be carried out using single failure proof (see definition in the Glossary) equipment with below-the-hook lifting devices that comply with the stress limits of ANSI N14.6 [1.2.4] and/or applicable portions of NUREG-0612 [1.2.7].

1.2.3.3 Threaded Anchor Locations

Threaded anchor locations are provided in the CEC Flange region of each CEC. These will serve as the anchoring location for the device used for canister transfer (Section 10.3). Threaded anchor locations serve no function during long term storage.

1.2.3.4 Design Life

The design life of the HI-STORM UMAX System is set forth in Table 17.0.1. This is accomplished by using materials of construction with a long proven history in the nuclear industry, specifying materials known to withstand their operating environments with little to no degradation (Section 17.2), and protecting material from corrosion by using appropriate mitigation measures.

Maintenance programs, as specified in Section 10.3, are also implemented to ensure that the service life will exceed the design life. The design considerations that assure the HI-STORM UMAX System performs as designed include the following:

HI-STORM UMAX VVM and HI-TRAC CS Transfer Cask:

a. Exposure to Environmental Effects

b. Material Degradation

c. Maintenance and Inspection Provisions

Canisters:

a. Corrosion
b. Structural Fatigue Effects
c. Maintenance of Helium Atmosphere
d. Allowable Fuel Cladding Temperatures
e. Neutron Absorber Boron Depletion

The adequacy of the materials for the designated design life is discussed in Chapter 18 of this report.

1.2.4 HI-TRAC CS

The proposed transfer cask for the HI-STORE CIS facility to carry out all on-site canister transfer operations is termed HI-TRAC CS which is a variation of the HI-TRAC VW transfer cask licensed in docket number 72-1032 for the HI-STORM FW and later adopted for HI-STORM UMAX system in docket number 72-1040. HI-TRAC CS utilizes steel and higher density concrete, meeting the requirements in Appendix 1.D of the HI-STORM 100 FSAR [1.3.3] to provide dose attenuation. HI-TRAC CS is also characterized by a split lid configuration wherein the bottom lid is in in the form of two halves with both halves engineered to retract or approach symmetrically. Figure 1.2.3a shows HI-TRAC CS in fully closed and fully open bottom lid configurations.

The design and operational features of HI-TRAC CS are summarized in the following:

a. The body of the cask features two concentric steel shells buttressed by a set of thick radial ribs that are welded to the two shells. The interstitial annular space between the two shells is filled with densified plain concrete that meets the requirements of Appendix 1.D of the HI-STORM 100 FSAR (docket # 72-1014) [1.3.3]. The appellation "CS" indicates that the transfer cask is "*concrete shielded*".

b. The bottom of the HI-TRAC features a pair of articulating, half-moon-shaped shield gates housed in a heavy steel weldment. The shield gates are made of multiple stacked, thick-steel plates on a low-friction bearing pad. The shield gates slide in the housing to allow the passage of the MPC from the HI-TRAC to the HI-STORM UMAX and vice versa. In the closed position, the shield gates support the weight of the MPC and provide shielding from the bottom of the loaded MPC. The major advantage of the split door configuration is that, in the fully retracted state, it does not intrude on the space occupied by the air vent projection in adjacent HI-STORM UMAX cavities and does not protrude into the canister vertical travel space. The shield gates feature air passages which allow for once-through air cooling of the canister (Figure 1.2.3b). The air cooling features of the HI-TRAC CS supplement the conductive and radiation cooling of the HI-TRAC CS. Ambient air rises through multiple Z-shaped passages in the shield gates, up through the annulus and out the open top of the HI-TRAC CS. A segmented alignment ring on the bottom of the HI-TRAC is used to concentrically align the HI-TRAC with the HI—STORM UMAX CEC during MPC transfer into the HI-STORM UMAX. The segmented alignment ring allows air to enter the region beneath the shield gates such that MPC

cooling air flow is assured even if the HI-TRAC is placed flat on the ground. The air passage inlets through the shield gates passively uses the ground to shield personnel from downward-streaming radiation. The top region of the cask body features a set of lifting trunnions. The Trunnions are for lifting and handling of the HI-TRAC via the cask handling crane or VCT. The HI-TRAC bottom region also features a set of trunnions suitable for cask's tilting operations.

c. The bottom region of the cask is outfitted with a heavy wall steel structure that houses the articulating shield gates. The shield gates ride on a low friction surface to enable them to be pulled apart (or pushed together) with a modest force to open the cask's cavity for canister transfer when needed. Shield gate opening and closure occurs via a set of hydraulic cylinders located on the outer edges of the shield gate housing.

d. The shielding concrete in the transfer cask is installed through suitably sized openings in the cask's top closure plate which also provide the exit path for any gases that may be generated during a hypothetical fire event. The HI-TRAC concrete space is supplemented with an internal cylindrical steel ring that supplements the gamma shielding in the shield gate region.

e. During the canister transfer operation, the transfer cask is secured to the top pad of the recipient cavity (HI-STORM UMAX ISFSI pad or the CTF pad) by a set of anchor bolts which eliminates kinematic stability concerns during the Design Basis Earthquake (DBE) event or any other credible environmental mechanical loading applicable to the site.

f. The top of the transfer cask features a thick annular steel ring which serves to prevent an inadvertent lifting of the canister beyond the biological shielding space provided by the transfer cask and also provides shielding axially.

g. The transfer cask is engineered to directly mate with the HI-STORM UMAX cavity as well as the Canister Transfer Facility (CTF) cavity eliminating the need for the traditional Mating Device ancillary. Elimination of the Mating Device has the salutary advantage of reducing the aggregate crew dose (i.e., promoting ALARA).

The Licensing drawing package in Section 1.5 of this chapter provides the necessary design details of HI-TRAC CS that support the required safety analyses documented in this SAR.

1.2.5 Operational Characteristics of the HI-STORM UMAX

The major operational steps to load a HI-STORM UMAX cavity consists of the following: The cask transporter carrying the transfer cask with the loaded canister aligns over the top of the HI-STORM UMAX and the HI-TRAC is placed on the HI-STORM UMAX VVM. The canister inside the transfer cask is lifted slightly by the VCT to allow the HI-TRAC's shield gates be opened. The canister is slowly lowered into the VVM cavity below. The transfer equipment is removed and the Closure Lid is installed. The principal operational characteristics of short term operations at an ISFSI are:

a. Prior to loading the VVM, the Closure Lid or other temporary lid is removed and the Divider Shell is installed.

b. The HI-TRAC CS cask is mounted on the VVM cavity and secured with large fasteners that are sized to protect the cask from tip- over under the site's DBE.

c. The canister is lowered into the storage cavity.

d. After the HI-TRAC Transfer Cask is removed then the Closure Lid is installed.

The loading operation is characterized by the following essential features:

a. The vertical insertion (or withdrawal) of the canister eliminates the risk of gouging or binding of the canister with the CEC parts.

b. All load handling operations are carried out using the Vertical Cask Transporter (VCT) that meets the criteria for lifting devices in Subsection 1.3.3 to preclude uncontrolled lowering of the load.

Details of the generic operational steps involving either installation or removal of the loaded canister at the HI-STORE CIS facility are provided in Section 10.3 along with reference to the safety measures that are known from experience to avert human performance errors. The visual depiction of the required operational steps in Figures 3.1.1 (a-v) provides a brief illustration of the loading steps for the HI-STORM UMAX CIS.

1.2.5.1 Design Features

The design features of the HI-STORM UMAX System are intended to meet the following principal performance characteristics under all credible modes of operation:

a. Prevent unacceptable release of contained radioactive material at all times.

b. Minimize occupational and site boundary dose.

c. Permit retrievability of contents (the canister must be recoverable after accident conditions in accordance with ISGs 2 and 3 [1.2.5, 1.2.6]).

Chapter 11 identifies the many design features built into the HI-STORM UMAX System to minimize dose and maximize personnel safety. Among the design features intrinsic to the system that facilitate meeting the above objectives are:

a. The loaded canister is always maintained in a vertical orientation during its handling at the ISFSI and is handled using ANSI N14.6 [1.2.4] compliant ancillaries.

b. Almost all personnel activities during canister transfer occur at ground level which helps promote safety and ALARA.

1.2.5.2 Identification of Subjects for Safety and Reliability Analysis

(a) Criticality Prevention

Every canister brought over to the HI-STORE facility must be approved under a USNRC docket to store used nuclear fuel or HLW. Therefore, the criticality compliance of the canister at HI-STORE is assured, as discussed in Chapter 8 of this report.

(b) Chemical Safety

There are no chemical safety hazards associated with operations of the HI-STORM UMAX System. No chemicals are stored inside the Protected Area.

(c) Operation Shutdown Modes

The HI-STORM UMAX System is totally passive and consequently, operation shutdown modes are unnecessary.

(d) Instrumentation

As stated earlier, the HI-STORM UMAX canister, which is seal welded, non-destructively examined, and pressure tested, confines the radioactive contents. The HI-STORM UMAX is a completely passive system with appropriate margins of safety; therefore, it is not necessary to deploy any instrumentation to monitor the cask in the storage mode.

(e) Maintenance Program

Because of its passive nature, the HI-STORM UMAX System requires minimal maintenance over its lifetime. Section 10.3 describes the maintenance program set forth for the HI-STORM UMAX System.

1.2.6 Cask Contents

This sub-section contains information on the cask contents pursuant to 10CFR 72.236(a),(m).

Only those canisters certified to be stored in the HI-STORM UMAX system in Docket # 72-1040 are permitted to be stored at HI-STORE CIS Facility.

Section 4.1 provides additional details.

1.2.7 Ancillary Equipment Used at HI-STORE CIS

Ancillary equipment for the HI-STORE CIS are those that are needed to conduct cask and canister handling and transfer operations in full compliance with the safety and ALARA commitments.

The major ancillary equipment includes:

a. Vertical Cask Transporter

b. Gantry Crane

c. Cask Tilt Frame

d. Special Lifting Devices

The above list does not include minor ancillaries that are available for procurement to the applicable ANSI standards such as common rigging, ladders, platforms, equipment stands, service and mobile cranes for handling non-critical loads, etc. The above list does not include commercial test and measurement equipment such as radiological survey equipment, leak testing equipment and cask test connectors.

The Design Criteria for the above major ancillaries are provided in Section 4.5, and analyses are presented in Sections 5.4 and 5.5; a brief description is provided below.

a. Vertical Cask Transporter

The Vertical Cask Transporter (VCT) is the principal load handling device used for MPC transfer operations at the HI-STORE CIS. Used in conjunction with the special lifting devices, it provides the critical lifting and handling functions associated with the canister transfer operations. It is a custom-designed equipment consisting of a set of caterpillars or multiple wheels, a diesel engine with a robust gear train and transmission housed in a rugged structural frame that also supports a set of hydraulically-actuated lifting towers. Figure 1.2.4 illustrates the general configuration of a VCT. The VCT uses the same controls and redundant drop protection features used to prevent an unplanned lowering of the critical load under a loss-of-power or hydraulic system failure as used at other ISFSIs in the United States where the VCT is performing the canister transfer operations.

b. Gantry Crane:

The Cask Handling Crane System consists of a crane, trolley, and hoist(s). The Crane System is electrically driven and rides on crane rails which are mounted to its supporting structure in the Cask Receiving Area. The trolley rides on crane rails mounted to the top of the crane girders and has at least one electric wire rope hoist for load lifting. The hoist hook will be used to lift the load and shall interface with the required rigging and below the hook lifting devices as required for the process.

The Crane System shall comply with ASME NOG-1 [3.0.1], and the latest revision of CMAA 70 [4.5.2], and OSHA. Design criteria for the Gantry crane is in Chapter 4 of this SAR.

c. Cask Tilt Frame:

The Cask Tilt Frame is used in conjunction with the Gantry Crane and its special lifting devices to transfer the HI-STAR 190 Transport Cask between the vertical and horizontal orientations. The Cask Tilt Frame consist of a set of trunnion support stanchions and a cask support saddle. The trunnion support stanchions engage the cask's rotation trunnions and provide a low-friction rotation point for cask tilting. The saddle supports the upper portion of the cask when the cask reaches the horizontal orientation. A brief illustration of the upending of a HI-STAR 190 Transport Cask or using the Crane and Tilt Frame through insertion into the CTF is demonstrated in Chapter 3. Downending of the HI-STAR 190 is performed in the reverse order for shipments away from the CIS.

d. Special Lifting Devices:

The Special Lifting Devices include those lifting components used to connect the cask or canister to the Gantry Crane or the VCT's lift points, as illustrated in Figure 1.2.4. Special Lifting Devices are defined in ANSI N14.6 [1.2.4].



Figure 1.2.1: Illustration of an Array of HI-STORM UMAX Systems



Figure 1.2.2(a): VVM Components Shown in Exploded, Cut-Away View



Figure 1.2.2(b): VVM Components Shown in Assembled, Cut-Away View



Figure 1.2.2(c): UMAX ISFSI in Partial Cut-Away View



Figure 1.2.3a: HI-TRAC General Configuration Shown with Shield Gates Closed and Open

Figure 1.2.3b: [PROPRIETARY INFORMATION WITHHELD PER 10CFR2.390]



Figure 1.2.4: Vertical Cask Transporter (VCT) with loaded HI-TRAC CS Transfer Cask and Special Lifting Device

1.3 IDENTIFICATION OF AGENTS AND CONTRACTORS

This section contains the necessary information to fulfill the requirements pertaining to the qualifications of the applicant pursuant to 10CFR72.22. Holtec International, with its operation centers in Florida, New Jersey, Pennsylvania, and Ohio in The United States, is the system designer and applicant for certification of the HI-STORE CIS facility.

Holtec International is an engineering technology company with a principal focus on the power industry. Holtec International Nuclear Power Division (NPD) specializes in spent fuel storage technologies. NPD has carried out turnkey wet storage capacity expansions (engineering, licensing, fabrication, removal of existing racks, performance of underwater modifications, volume reduction of the old racks and hardware, installation of new racks, and commissioning of the fuel pool for increased storage capacity) in numerous nuclear plants around the world. Over 90 plants in the U.S., Britain, Brazil, Korea, Mexico, China and Taiwan have utilized the Company's wet storage technology to establish their state-of-the-art in-pool storage capacities.

Holtec's NPD is also a turnkey provider of dry storage and transportation technologies to nuclear plants around the globe. The company is contracted by 59 nuclear units in the U.S. and 42 overseas to provide the company's dry storage and transport systems. Utilities in Belgium, China, Korea, Spain, South Africa, Sweden, Ukraine, the United Kingdom and Switzerland are also active users of Holtec International's dry storage and transport systems.

Four U.S. commercial plants, namely, Dresden Unit 1, Trojan, Indian Point Unit 1, and Humboldt Bay have thus far been completely defueled using Holtec International's technology. For many of its dry storage clients, Holtec International provides all phases of dry storage including: the required site-specific safety evaluations; ancillary designs; manufacturing of all capital equipment; preparation of site construction procedures; personnel training; dry runs; and fuel loading. The USNRC dockets in 10CFR71 and 10CFR72 currently maintained by the Company (as of February 2017) are listed in Table 1.3.1.

Holtec International's corporate engineering consists of professional engineers and experts with extensive experience in every discipline germane to the fuel storage technologies, namely structural mechanics, heat transfer, computational fluid dynamics, and nuclear physics. Virtually all engineering analyses for Holtec's fuel storage projects (including HI-STORM UMAX) are carried out by the company's full-time staff. The Company is actively engaged in a continuous improvement program of the state-of-the-art in dry storage and transport of spent nuclear fuel. The active patents and patent applications in the areas of dry storage and transport of SNF held by the Company (ca. June 2016) are listed in Table 1.3.2. Table 1.3.3 lists Holtec patents on dry storage technologies that have been published by the US patent office but not yet granted. Many of these listed patents have been utilized in the design of the HI-STORM UMAX System.

Holtec International's quality assurance (QA) program was originally developed to meet NRC requirements delineated in 10CFR50 [1.3.1], Appendix B, and was expanded to include provisions of 10CFR71 [1.3.2], Subpart H, and 10CFR72 [1.0.5], Subpart G, for structures, systems, and components designated as important to safety. The Holtec quality assurance program, which satisfies all 18 criteria in 10CFR72, Subpart G, that apply to the design,

fabrication, construction, testing, operation, modification, and decommissioning of structures, systems, and components important to safety is incorporated by reference into this SAR. Holtec International's QA program has been certified by the USNRC (Certificate No. 71-0784) [12.0.1].

The HI-STORM UMAX System will be fabricated by the manufacturing plants owned by Holtec International and operated under the Company's QA program. The Company's HMD in Pittsburgh is a long-term ASME N-Stamp holder and fabricator of nuclear components. In particular, HMD has been manufacturing HI-STORM and HI-STAR system components since the inception of Holtec International's dry storage and transportation program in the 1990s. HMD routinely manufactures ASME code components for use in the U.S. and overseas nuclear plants. Holtec International's engineering and manufacturing organizations have been subject to triennial inspections by the USNRC. If another fabricator is to be used for the fabrication of any part of the HI-STORM UMAX System, the proposed fabricator will be evaluated and audited in accordance with Holtec International's QA program approved by the USNRC.

Holtec International's Nuclear Power Division (NPD) also carries out site services for dry storage deployments at nuclear power plants. Numerous nuclear plants, such as Trojan and Waterford 3 , Waterford 3, Pilgrim and Comanche Peak have deployed dry storage at their sites using a turnkey contract with Holtec International.

The Company has considerable prior experience in the design and licensing of AFRs sites, having successfully led the licensing of PFS, LLC's Skull Valley in Utah (2005) and the "Central Spent Fuel Storage Facility" in Ukraine (ongoing).

Table 1.3.1:
USNRC DOCKETS ASSIGNED TO HOLTEC INTERNATIONAL

System Name	Docket Number
HI-STORM 100 (Storage)	72-1014 [1.3.3]
HI-STAR 100 (Storage)	72-1008 [1.3.4]
HI-STAR ATB 1T (Transportation)	71-9375
HI-STAR 100 (Transportation)	71-9261 [1.3.5]
HI-STAR 180 (Transportation)	71-9325
HI-STAR 180D (Transportation)	71-9367
HI-STAR 190 (Transportation)	71-9373 [1.3.6]
HI-STAR 60 (Transportation)	71-9336
HI-STAR 80 (Transportation)	71-9374
Holtec Quality Assurance Program	71-0784 [12.0.1]
HI-STORM FW (Storage)	72-1032 [1.3.7]
HI-STORM UMAX (Storage)	72-1040 [1.0.6]

Table 1.3.2: Dry Storage and Transport Patents Held by Holtec International		
Item No.	**Colloquial Name of the Patent**	**USPTO Patent Number**
1.	Honeycomb Fuel Basket	5,898,747
2.	Radiation Absorbing Refractory Composition (METAMIC)	5,965,829
3.	HI-STORM 100S Overpack	6,064,710
4.	Extrusion Fabrication Process for Discontinuous Carbide Particulate Metal Matrix Composites and Super Hypereutectic A1/S1(METAMIC-CLASSIC)	6,042,779
5.	Duct Photon Attenuator	6,519,307B1
6.	HI-TRAC Operation	6,587,536B1
7.	Cask Mating Device (Hermetically Sealable Transfer Cask)	6,625,246B1
8.	Improved Ventilator Overpack	6,718,000B2
9.	Below Grade Transfer Facility	6,793,450B2
10.	HERMIT (Seismic Cask Stabilization Device)	6,848,223B2
11.	Cask Mating Device (operation)	6,853,697
12.	Davit Crane	6,957,942B2
13.	Duct-Fed Underground HI-STORM	7,068,748B2
14.	Forced Helium Dehydrator (design)	7,096,600B2
15.	Below Grade Cask Transfer Facility	7,139,358B2
16.	Forced Gas Flow Canister Dehydration (alternate embodiment)	7,210,247B2
17.	HI-TRAC Operation (Maximizing Radiation Shielding During Cask Transfer Procedures)	7,330,525
18.	HI-STORM 100U	7,330,526B2
19.	Flood Resistant HI-STORM	7,590,213B1
20.	HI-STORM 100M (Underground Manifolded module assembly)	7,676,016B2
21.	Dew Point Temperature Based Canister Dehydration	7,707,741B2
22.	Optimized Weight Transfer Cask with Detachable Shielding	7,786,456B2
23.	VESCAP (Apparatus, System, and Method for Facilitating Transfer of High Level Radioactive Waste to and/or From a Pool	7,820,870B2
24.	HI-STORM 100F (Counter-flow Underground Vertical Ventilated Module)	7,933,374B2
25.	Apparatus for Transporting and/or Storing Radioactive Materials Having Jacket Adapted to Facilitate Thermo-siphon Fluid Flow	7,994,380B2
26.	Method of Removing Radioactive Materials from Submerged State and/or Preparing Spent Nuclear Fuel for Dry Storage	8,067,659B2
27.	HI-STORM 100US	8,098,790B1
28.	Canister Apparatus and Basket for Transporting, Storing and/or Supporting Spent Nuclear Fuel(Double Wall Canister)	8,135,107B2
29.	Apparatus System and Method for Low Profile Translation of High Level Radioactive Waste Containment Structure (Low Profile	8,345,813

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

Table 1.3.2: Dry Storage and Transport Patents Held by Holtec International		
Item No.	**Colloquial Name of the Patent**	**USPTO Patent Number**
	Transporter)	
30.	Method of Storing High Level Waste (HI-STORM 100F)	8,345,813B2
31.	Apparatus for Providing Additional Radiation Shielding to a Container Holding Radioactive Materials, and Method of Using the same to Handle and/or Process Radioactive Materials	8,415,521B2
32.	Systems and Methods for Storing Spent Nuclear Fuel	8,625,732
33.	System and Method for the Ventilated Storage of High Level Radioactive Waste in a Clustered Arrangement	8,660230B2
34.	Method of Transferring High Level Radioactive Materials, and System for the Same	8,718,221B2
35.	Manifold System for the Ventilated Storage of High Level Waste and a Method of Using the Same to Store High Level Waste in a Below-Grade Environment	8,718,220B2
36.	Method and Apparatus for Preparing Spent Nuclear Fuel for Dry Storage	8,737,559B2
37.	Apparatus for Storing and/or Transporting High Level Radioactive Waste, and Method for Manufacturing the Same	8,798,224B2
38.	Method for Controlling Temperature of a Portion of a Radioactive Waste Storage System and for Implementing the Same	9,105,365B2
39.	Ventilated System for Storing High Level Radioactive Waste	8,905,259B2

Table 1.3.3: Holtec International Pending Patents on Fuel Storage				
	Title	**Submittal Date**	**USPTO FILE NUMBER**	**Publication Number**
1.	System And Method For The Ventilated Storage Of High Level Radioactive Waste In A Clustered Arrangement(HIC-Storm)	22-Dec-08	*12340948*	US20090159550
2.	Spent Fuel Basket, Apparatus And Method Using The Same For Storing High Level Radioactive Waste (HI-STAR 180)	02-Jul-07	*11772610*	US20080031396
3.	System And Method For Storing Spent Nuclear Fuel Having Manifolded Underground Vertical Ventilated Module (100M)	19-Feb-10	*12709094*	US20100150297
4.	Cask Apparatus, System And Method For Transporting And/Or Storing High Level Waste (HI-SAFE)	28-Apr-10	*12769622*	US20100272225
5.	Spent Fuel Basket For Storing High Level Radioactive Waste (HEXCOMB Racks)	29-Oct-08	*12260914*	US20090175404
6.	Shield Transfer Canister for Inter-Unit Transfer of Spent Nuclear Fuel	16-Dec-10	*12970901*	US20110150164
7.	Method of Removing Radioactive Materials from a Submerged State and/or Preparing Spent Nuclear Fuel for Dry Storage	29-Nov-11	*13306948*	US20120142991
8.	System and Method of Storing and/or Transferring High Level Radioactive Waste	18-Apr-13	*61625859*	W02013158914
9.	Container and System for Handling Damaged Nuclear Fuel and Method of Making Same	19-Feb-14	*61525583*	W02013055445
10.	Subterranean Canister Storage System For Monitored Retrievable Storage of Nuclear Materials	10-Mar-14	*61532397*	US20140226777A1
11.	Vertical Ventilated Cask with Distributed Air Inlets for Storing Fissile Nuclear Materials	13-May-14	*14358032*	US2014329455A1
12.	A Radioactive Material Storage Canister and Method for Sealing Same	03-Jul-14	*61746094*	US20150340112
13.	Method of Storing High Level Radioactive Waste	07-Jul-14	*13736452*	US20140192946A1
14.	System and Method for Minimizing Movement of Nuclear Fuel Racks During a Seismic Event	26-Feb-15	*61694058*	US20150310947

Table 1.3.3: Holtec International Pending Patents on Fuel Storage				
	Title	**Submittal Date**	**USPTO FILE NUMBER**	**Publication Number**
15.	System and Method for Storing and Leak Testing a Radioactive Materials Storage Canister	26-Feb-15	*61695837*	W02014036561
16.	High-Density Subterranean Storage System for Nuclear Fuel and Radioactive Waste	10-Dec-15	*14760215*	US20150357066A1
17.	System for Storing High Level Radioactive Waste	07-Jul-16	*15053608*	US20160196887A1
18.	Storage System for Nuclear Fuel	14-Jul-16	*14912754*	US20160203884A1

1.4 MATERIAL INCORPORATED BY REFERENCE

Materials incorporated by reference into this report are discussed in Section 1.0 and identified in Table 1.0.3. The majority of this information is incorporated from the HI-STORM UMAX docket, with some supplementary information from the HI-STORM FW. Each individual chapter provides a table which identifies the specific material incorporated by reference into each chapter, with specific sections and specific references.

1.5 LICENSING DRAWINGS

The licensing drawings for the HI-STORM UMAX System, the HI-TRAC Transfer Cask and other important to safety ancillary systems/components employed at the HI-STORE CIS, pursuant to the requirements of 10CFR72.24(c)(3), are provided in this section. The licensing drawings contain the necessary information to enable the margins of safety under different operating modes for the facility to be quantified in a conservative manner to support its safety case.

The drawing packages developed specifically for the proposed HI-STORE facility are listed in Table 1.5.1 and placed in their numerical sequence at the end of this chapter.

Table 1.5.1: Drawing Packages for the HI-STORE CIS Facility		**Revision**
Drawing Number	**Caption**	
10868	HI-TRAC CS	0
10895	Cask Transfer Facility (CTF)	0
10899	Tilt Frame	0
10875	HI-STORM UMAX Vertical Ventilated Module (Version C)	0
10902	Lift Yoke for HI-STAR 190	1
10900	Lift Yoke got HI-TRAC CS	1
10894	HI-STAR Horizontal Lift Beam	0
10901	HI-TRAC CS Lift Link	0
10891	MPC Lift Attachment	1
10889	MPC Lifting Device Extension	1
10912	Cask Transfer Building Floor Slab	0
10940	HI-STORE Site Plan and General Arrangement	0
6505	MPC-37 Enclosure Vessel	17
6512	MPC-89 Enclosure Vessel	18

[PROPRIETARY DRAWINGS WITHHELD PER 10CFR2.390]

1.6 REGULATORY COMPLIANCE

This section ensures compliance with 10CFR72.18, 72.22, 72.24 and 72.44 as indicated in NUREG 1567 [1.0.3] Section 1.

10CFR72.18 discusses material incorporated by reference, which is discussed in Section 1.4.

10CFR72.22 requires that general and financial information about the applicant is provided, including age, address, description of business, estimated cost of construction and operation of the facility and decommissioning, which is discussed in Section 1.3 (with the exception as indicated below).

10CFR72.24 requires that the application includes technical information, including overview of the installation, principal characteristics of the ISFSI (dimensions, weights, and construction materials, licensing drawings), facility allowance for decommissioning (retrievability), and general description of contents to be stored at the facility. Information regarding facility systems descriptions and agents and contractors are required to be provided.

10CFR72.44 describes the license conditions, which are provided in the license document for the facility.

The chapter complies with 10CFR72 requirements above and follows the guidance of NUREG-1567 [1.0.3] with the following qualifications:

1. For proprietary reasons financial information, including cost of construction, operation and decommissioning will be submitted separately from this SAR.

2. Due to the significant quantity of material incorporated by reference into this SAR, information regarding weights will be incorporated by reference into other chapters for analysis purposes. As such, to maintain adequate configuration control, information on weights will be included in Chapter 5 (Structural) of this report. Similarly, information on contents to be stored in the HI-STORM UMAX is provided in Chapter 4 of this report.

CHAPTER 2: SITE CHARACTERISTICS*

2.0 INTRODUCTION

This chapter presents the relevant characteristics of the proposed HI-STORE Consolidated Interim Storage (CIS) Facility site (Site). The purpose of this chapter is to: (1) characterize local land and water use and population so that individuals and populations likely to be affected can be identified; (2) identify the external natural and man-induced phenomena for inclusion in design basis considerations; and (3) characterize the transport processes which could move any released contamination from the facility to the maximally exposed individuals and populations. More details regarding the environmental characteristics of the Site and surroundings is found in the Environmental Report (ER) [1.0.4].

* All references are placed within square brackets in this report and are compiled in Chapter 19 of this report

2.1 GEOGRAPHY AND DEMOGRAPHY

2.1.1 Site Location

The center of the Site is at latitude 32.583 north and longitude 103.708 west, in Lea County, New Mexico, 32 miles east of Carlsbad and 34 miles west of Hobbs (Figure 2.1.1). Larger population centers are Roswell, New Mexico, 74 miles to the northwest; Odessa, Texas, 92 miles to the southeast; and Midland, Texas, also to the southeast at 103 miles. The nearest international airport is located between Midland and Odessa, Texas 98 miles to the southeast.

2.1.2 Site Description

The Site is currently owned by the Eddy-Lea Energy Alliance (ELEA), a limited liability company owned by the cities of Carlsbad and Hobbs, and Eddy County and Lea County. In April 2016, Holtec and ELEA signed a memorandum of agreement (MOA) [2.1.1] covering the design, licensing, construction and operation of the Site. Among other things, that MOA provides the terms by which Holtec could purchase the Site. On July 19, 2016, the New Mexico Board of Finance approved the sale of the Site to Holtec [2.1.2].

The Site consists of mostly undeveloped land used for cattle grazing with the only boundary being a four-strand barb wire fence along the south side of the property until it nears Laguna Gatuna, where it turns south to the highway. This fence is the boundary between two grazing allotments administered by the Bureau of Land Management (BLM). The majority of allotments are grazed year-round with some type of rotational grazing. Figure 2.1.2 depicts the Site boundaries.

Rangelands comprise a substantial portion of the Site and provide forage for livestock. Pasture rotation, with some of the pastures being rested for a least a portion of the growing season, is standard management practice for grazing allotments. Vegetative monitoring studies to collect data on the utilization of the land, and the amount of precipitation by pasture from each study allotment are conducted annually on Federal lands to compare production with consumption. Currently, the BLM permits nine animal unit months[1] per 640 acres [2.1.3]. Because the Site is privately held, it does not fall under the BLM range management rules, although the rules apply to most of the adjacent lands that are managed by the same rancher.

The following list of structures is shown on Figures 2.1.2, 2.1.11, and 2.1.13. An aerial view of the Site is shown in Figure 2.1.3 and several plot views of the HI-STORE CIS Facility with all Phases complete are shown in Figures 2.1.4(a), (b), and (c).

- A communications tower in the southwest corner of the Site;
- A former producing gas and distillate well is located near the communications tower;
- A small water drinker (livestock) is located along the aqueduct in the northern half of the Site;
- Oil recovery facility (abandoned) that still has tanks and associated hardware left in place in the northeast corner;

[1] An "animal unit month" is the amount of forage needed to feed a cow for one month.

- An oil recovery facility with tanks and associated hardware still in place in the far southwest corner;
- Existing natural gas pipelines run underground along the North-South axis to the East of the Site;
- A temporary flexible pipeline for natural gas runs aboveground diagonally through the center of the Site.

As can be seen in Figure 2.1.2, the oil recovery facility that is currently in place in the southwest corner of the Site is a potential fire hazard to the SSCs of the CIS Facility. Table 2.1.4 lists conservative values for input parameters used to assess the risk this oil recovery facility poses to the SSCs of the CIS Facility. A detailed discussion of this evaluation is presented in Subsection 6.5.2.

The natural gas pipelines can be seen in Figures 2.1.11 and 2.1.13. The temporary flexible pipeline that runs aboveground through the center of the Site will be moved prior to or during the early construction phases of the CIS Facility. The natural gas pipelines which run along the North-South axis to the East of the site are underground and not considered to present a threat to the CIS Facility operations.

No water wells are located on the Site. However, the Site has been associated with oil and gas exploration and development with at least 18 plugged and abandoned oil and gas wells located on the property. However, none of these plugged and abandoned oil and gas wells are located within the area where the ISFSI would be located or where any land would be disturbed and they are not expected to affect the construction and operation of the CIS Facility. The plugged wells are estimated to be 30-70 years old. It is possible that hydrocarbon contamination exists at the Site as a result of these past practices [1.0.4]. There are no active wells on the Site and there are no plans to use any of the plugged and abandoned wells on the Site.

United States Department of Agriculture (USDA) Natural Resources Conservation Service (NRCS) Soil Survey Maps of Lea County, NM [2.1.4] were reviewed in order to identify the soil units present at the Site. A Soil Survey Map is provided as Figure 2.1.5. About 90 percent of the soils within the Site are classified as Simona-Upton association (SR) and Simona fine sandy loam (SE). Simona soils are calcareous eolian deposits derived from sedimentary rock and consist of fine sandy loam underlain by gravelly fine sandy loam and cemented material, and gravelly fine sandy loam underlain by fine sandy loam and cemented material. The remaining soils (approximately 10 percent) consist of Midessa and wink fine sandy loam (MN), Mobeetie Potter Association (MW), Stony rolling land (SY), and Mixed alluvial land (MU). Details regarding the Site soil types and characteristics were compiled from Appendix D of the ER [1.0.4], and are summarized below.

Simona-Upton Association (SR)

Simona (50 percent of soil unit)

- 0 to 8 inches: gravelly fine sandy loam; saturated hydraulic conductivity (Ksat) of 14.11 to 42.34 micrometers per second.
- 8 to 16 inches: fine sandy loam; Ksat of 14.11 to 42.34 micrometers per second.

- 16 to 26 inches: cemented material (Petrocalcic Restrictive Layer i.e. Caliche); Ksat of 0.00 to 0.42 micrometers per second.

Upton (35 percent of soil unit)

- 0 to 8 inches: gravelly loam; Ksat of 4.23 to 14.11 micrometers per second.
- 8 to 18 inches: cemented material; Ksat of 0.07 to 4.23 micrometers per second.
- 18 to 60 inches: very gravelly loam; Ksat of 4.23 to 14.11 micrometers per second.

Simona fine sandy loam (SE)

- 0 to 8 inches: fine sandy loam; Ksat of 14.11 to 42.34 micrometers per second.
- 8 to 16 inches: gravelly fine sandy loam; Ksat of 14.11 to 42.34 micrometers per second.
- 16 to 26 inches: cemented material (Petrocalcic Restrictive Layer i.e. Caliche); Ksat of 0.0 to 0.42 micrometers per second.

Midessa and wink fine sandy loams (MN)

Midessa (45 percent of soil unit)

- 0 to 4 inches: fine sandy loam; Ksat of 14.11 to 42.34 micrometers per second.
- 4 to 22 inches: clay loam; Ksat of 1.35 to 1.55 micrometers per second.
- 22 to 60 inches: clay loam; Ksat of 4.23 to 14.11 micrometers per second.

Wink (40 percent of soil unit)

- 0 to 12 inches: fine sandy loam; Ksat of 14.11 to 43.34 micrometers per second.
- 12 to 23 inches: sandy loam; Ksat of 14.11 to 43.34 micrometers per second.
- 23 to 60 inches: sandy loam; Ksat of 14.11 to 43.34 micrometers per second.

Mobeetie-Potter Association (MW)

Mobeetie (70 percent of soil unit)

- 0 to 4 inches: fine sandy loam; Ksat of 14.11 to 43.34 micrometers per second.
- 4 to 24 inches: fines sandy loam; Ksat of 14.11 to 43.34 micrometers per second.
- 24 to 60 inches: fine sandy loam; Ksat of 14.11 to 43.34 micrometers per second.

Potter (24 percent of soil unit)

- 0 to 4 inches: gravelly fine sandy loam; Ksat of 4.23 to 14.11 micrometers per second.
- 4 to 14 inches: extremely cobbly loam; Ksat of 4.23 to 42.34 micrometers per second.

Stony rolling land (SY)

Torriorthents (85 percent of soil unit)

- 0 to 20 inches: extremely gravelly sandy loam; Ksat of 14.11 to 42.34 micrometers per second.
- 20 to 60 inches: bedrock; Ksat of 0.42 to 14.00 micrometers per second.

Mixed alluvial land (MU)

Ustifluvents (85 percent of soil unit)

- 0 to 60 inches: stratified sand to loamy fine sand to loam to sandy clay loam to clay loam to clay; Ksat of 0.42 to 141.14 micrometers per second.

Appendix D of the ER [1.0.4] provides additional information regarding soil descriptions, soil features, and physical, chemical, and engineering properties, including soil salinity. Laboratory analyses of soil samples within the Site indicated chloride concentrations of 26-43,000 mg/kg in the soil [2.1.3]. The soil samples were taken in the eastern portion of the Site, in areas previously used for oilfield disposal. The highest chloride concentrations are considered to be localized and not reflective of the concentrations where the CISF would be located [2.1.3]. A review of the available soil data, including engineering properties of the Site soils, indicates favorable conditions for foundations, utilities, surface pavement, and other improvements [2.1.3]. Removal of fill would not induce seismic activity or affect subsurface faults [1.0.4]. Section 4.3 of the ER [1.0.4] provides additional details regarding the potential impacts of the CIS Facility on soils, including a discussion of construction activities adjacent to a finished ISFSI structure. Holtec plans to perform more detailed site characterization studies, including a complete site survey and additional soil borings, once the license approval has been received from the NRC.

Vegetation and habitats within the Site and immediately surrounding area are common within the region. The Site does not support any vegetation of significance. Significance is defined in this document as any plant, animal, or habitat that: (1) has high public interest or economic value or both; or (2) may be critical to the structure and function of the ecosystem or provide a broader ecological perspective of the region.

The Project area is in the primary vegetation community of Desert Grasslands, which is widespread at lower elevations in southern and western New Mexico. These communities are characterized by significant amounts of grasses and less than 10 percent of total cover being forbs and shrubs [2.1.5]. Typical vegetation in Desert Grassland communities include black grama (*Bouteloua eriopoda)*, blue grama (*Bouteloua gracilis)*, bluestem, buffalo grass (*Bouteloua dactyloides)*, western wheatgrass (*Pascopyrum smithii*), galletas (*Hilaria spp.)*, tobosa (*Pleuraphis mutica)*, alkali sacaton (*Sporobolus airoides*), three-awn (*Aristida spp*.), mesquite (*Prosopis spp*.), serviceberry (*Amelanchier denticulate)*, skunkbush sumac (*Rhus trilobata*), sand sagebrush (*Artemisia filifolia)*, Apache plume (*Fallugia paradoxa*), creosotebush (*Larrea tridentata)*, and cliffrose (*Purshia mexicana*). With appropriate moisture (generally more than is typically experienced) sunflower (*Helianthus annuus*), croton (*Croton spp.)*, and pigweed (*Amaranthus palmeri)* may grow in disturbed or ponded depressions.

A biological survey in October of 2016 (Appendix B in the ER [1.0.4]) also documented a variety of mesquite scrubland and very few grassland species. This further indicates that

vegetation in the area has changed from a desert grassland to mesquite scrubland due to overgrazing. The dominant species documented during this survey include broom snakeweed, honey mesquite, prairie verbena *(Glandularia bipinnatifida)*, prickly pear (*Opuntia engelmannii)*, scarlet globemallow *(Sphaeralcea coccinea)*, silverleaf nightshade *(Solanum elaeagnifolium)*, tobosa grass, western peppergrass *(Lepidium montanum)*, and wooly croton *(Croton capitatus)*.

The topography of the Site shows a high point located on the southern border of the Site and gentle slopes leading to the two drainages (Laguna Plata and Laguna Gatuna). Both of these drainages would be able to accept a one day severe storm total within the 7.5 inch range with excess free board space. The natural drainage of the Site is useful by providing a natural area for impoundment of excess runoff during severe storms [2.1.3]. Figures 2.1.6 – 2.1.8 depict the topography for the Site and the surrounding area.

There are no United States Army Corps of Engineers (USACE) jurisdictional wetlands on the Site [2.1.3]. Additionally, there no floodplains identified or mapped for the Site or Lea County, New Mexico [2.1.6, 2.1.7].

2.1.3 Population Distribution and Trends

This section describes population distribution and trends for the 50-mile region of influence (ROI) surrounding the proposed Site including Lea and Eddy Counties in New Mexico and Andrews and Gaines Counties in Texas (see Figure 2.1.9). Lea County is primarily rural, as are the other counties in the ROI. Between 2000 and 2010, the population in the ROI has grown at a slower rate in comparison to New Mexico-wide population growth. Population estimates in the ROI are projected to grow at a slower rate than New Mexico, increasing 10 percent between 2015 and 2025 while New Mexico is projected to increase 19 percent during the same time period. Table 2.1.1 lists historical population and Table 2.1.2 lists projected population in the ROI and New Mexico and Texas.

The population in the ROI in 2015 was estimated to be 166,914 [2.1.9]. In 2015, 43 percent of the population of the ROI resided in Lea County, New Mexico. Between 2010 and 2015, the counties within the ROI all experienced an increase in population. Gaines County, Texas had the greatest increase at 14 percent, while Eddy County, New Mexico had the lowest increase at seven percent during the same time period.

The nearest residence to the Site is the Salt Lake Ranch located 1.5 miles north of the Site. There are additional residences at the Bingham Ranch, two miles to the south, and near the Controlled Recovery Inc. complex, three miles to the southwest. There is an average population of less than 20 residents among the five ranches within a six mile radius. This is a population density of less than 5 residents per square mile [2.1.3]. Table 2.1.3 presents the population density per square mile of land for the ROI in 2010. Figure 2.1.10 presents a sector map of population in segments surrounding the Site for distances of 1, 2, 3, 4, and 5 miles. As shown on that Figure, there are only 9 people living within 5 miles of the proposed Site.

The nearest local school facilities, daycare, nursing homes and hospitals are located in Hobbs, NM. The educational institutions include three colleges, a high school and an alternative high school, three middle schools, twelve elementary schools, and two private schools. The Lea Regional Medical Center is the nearest hospital. There are no school facilities or hospitals located within 5 miles of the proposed Site.

Because the only mechanism for radiological exposure would be from radiation (neutrons and gamma rays) emitted from the storage casks, the highest public dose would result from an individual located as close to the SNF casks as possible. For details on the radiation protection evaluation for the Site, see Chapter 11 of this SAR.

2.1.4 Land and Water Use

As shown on Figure 2.1.11, almost all of the land immediately surrounding the Site is owned and managed by the BLM. Land uses in the area are limited to oil and gas exploration and production, oil and gas related services industries, livestock grazing, and limited recreational activity. Lands within six miles of the Site are privately owned, state lands, or BLM lands. Land use within six miles of the Site falls into two categories; livestock grazing and mineral extraction.

Within 50 miles of the Site, except for the communities located in the area, the land use and ownership is essentially the same as within the six mile radius. Along with the mining, grazing, and oil/gas activity, agriculture is a major activity [2.1.3].

Lea County is approximately 2.8 million acres in size. Property ownership is 17 percent Federal government, 31 percent state government, and 52 percent private. The Federally-owned land is primarily located in the southwestern portion of the county, the state-owned land is predominately located throughout the middle, and the privately owned land primarily extends from north to south in the county's eastern portion. Large tracts of land in Lea County are privately owned by farmers, ranchers, oil, gas, and mining companies. Urbanized areas near cities and towns include ownership of smaller tracts of land for residential, municipal, and commercial purposes. Approximately 93 percent of Lea County is used as range land for grazing, and approximately 4 percent is used for crop farming. Urban areas and the roadway system account for the remaining land use. Most of the land actively farmed in Lea County is irrigated [2.1.14].

Mineral extraction in the area consists of underground potash mining and oil/gas extraction. Both industries support major facilities on the surface, although mining surface facilities are confined to a fairly small area. Intrepid Mining LLC (Intrepid) owns two potash mines located within 6 miles of the Site. The Intrepid North mine, located nearly 6 miles to the west, is no longer actively mining potash underground. However, the surface facilities are still being used in the manufacture of potash products. The Intrepid East facility is still mining its underground potash ore [2.1.3]; however, it too is nearly 6 miles to the southwest of the site. Mineral resources near the Site, as determined from the USGS Mineral Resources Data System and the New Mexico Mining Minerals Division, are mapped on Figure 2.1.12. The USGS and NM MMD databases indicate that the CIS Facility is not co-located with existing mining facilities.

Potash deposits are located around and within the Site as shown on Figure 2.1.13. With regard to potential future drilling on the Site, Holtec has an agreement [2.6.9] with Intrepid such that Holtec controls the mineral rights on the Site and Intrepid will not conduct any potash mining on the Site. An area for a potash mine nearby and west of the Site has been identified as shown on Figure 2.1.13; while the operational and construction footprint for the CIS Facility does not intersect the area for the potash mine (identified on Figure 2.1.13 as "Belco shallow" and "Belco

deep" potash drill islands), the proposed railroad spur has the potential to cross these drill islands.

Water demand in Lea County increased 33 percent from 1985 to 1995 and in 1998, the demand was about 189,000 acre-feet per year. Similar increases in water use from 1985 to 1995 occurred in Irrigated Agriculture (33 percent) Public Supply (26 percent), Domestic (40 percent), Livestock (106 percent) and Commercial (21 percent) use categories. The water use by category, as a percentage of Lea County's total, is 78 percent Irrigated Agricultural, 10 percent for Public Water Supply, 7 percent Mining, and 3 percent Power. Present water use by Domestic, Livestock, Commercial Reservoir Evaporation, and Recreation uses are all less than 1 percent of the total use [2.1.14].

The largest water use in Lea County is for non-municipal irrigation. The New Mexico Office of the State Engineer (NMOSE) has on record a total of 2,007 non-municipal wells with an associated water right of 344,600 acre-feet. The next largest user group is municipalities, with water rights of 48,000 acre-feet). The city of Hobbs is the largest water-rights holder with water rights of 20,100 acre-feet per year [2.1.14].

Over the next 40 years, if unrestrained, the water use in Lea County is estimated to increase to approximately 360,000 acre-feet, 90 percent greater than the 1995 total. The largest part of this increase is anticipated to come from Irrigated Agricultural, which is projected to require 290,000 acre-feet in 2040, in response to demands for feed from Lea County's expanding dairy industry. All other water use categories are expected to increase in Lea County over the next 40 years. Specifically, 55 percent Public Supply, 58 percent Domestic, 364 percent Livestock, 58 percent Commercial, 134 percent Industrial, 32 percent Mining, 57 percent Power, and 55 percent Recreation are estimated above 1995 uses. These other categories account for a total of approximately 70,000 acre-feet per year of the total annual 2040 estimate [2.1.14].

Table 2.1.1

POPULATION ESTIMATES FOR REGION OF INFLUENCE [2.1.9, 2.1.10, 2.1.11]

Area	Census 1990	Census 2000	Census 2010	Population Estimates as of July 1				
				2011	2012	2013	2014	2015
Lea	55,765	55,528	64,727	63,690	64,670	65,681	66,876	71,180
Eddy	48,605	51,633	53,829	53,288	53,693	54,284	54,834	57,578
Andrews	14,338	13,004	14,786	14,500	15,006	15,554	16,126	18,105
Gaines	14,123	14,467	17,526	17,123	17,572	18,019	18,496	20,051
Total ROI	**132,831**	**134,632**	**150,868**	**148,601**	**150,941**	**153,538**	**156,332**	**166,914**
New Mexico	1,515,069	1,819,046	2,059,179	2,037,136	2,055,287	2,069,706	2,080,085	2,085,109
Texas	16,986,510	20,851,820	25,145,561	24,774,187	25,208,897	25,639,373	26,092,033	27,469,114

Table 2.1.2

POPULATION PROJECTIONS FOR THE REGION OF INFLUENCE [2.1.10, 2.1.11]

Area	2020	2025	2030	2035	2040
Lea	78,407	85,773	93,712	102,090	110,661
Eddy	57,908	59,945	61,836	63,595	65,258
Andrews	16,450	17,244	17,973	18,695	19,378
Gaines	20,064	21,420	22,858	24,316	25,644
Total ROI	172,829	184,382	196,379	208,696	220,941
New Mexico	2,351,724	2,487,227	2,613,332	2,727,118	2,827,692
Texas	27,238,610	28,165,689	28,994,210	29,705,207	30,305,304

Table 2.1.3

POPULATION DENSITY PER SQUARE MILE OF LAND FOR THE REGION OF INFLUENCE, 2010 [2.1.12]

Area	2010
County	
Lea	14.7
Eddy	5.4
Andrews	9.9
Gaines	11.7
County Subdivision and Place	
Eunice City, Lea County	970.6
Hobbs City, Lea County	1,424.4
Jal City, Lea County	446.4
Lovington City, Lea County	2,320.9
Carlsbad City, Eddy County	903.3

Table 2.1.4

CONSERVATIVE VALUES USED TO EVALUATE OIL RECOVERY FACILITY FOR FIRE CONSIDERATIONS

Parameter Description	Distance (Units)
Nearest location of Loaded Conveyance on Haul Path to East of Oil Recovery Facility	450 (ft)
Nearest location of Loaded Conveyance on Haul Path to North of Oil Recovery Facility	350 (ft)
Nearest location of HI-STORM for Phase 1 to Oil Recovery Facility	1750 (ft)
Nearest location of HI-STORM for All Phases to Oil Recovery Facility	900 (ft)

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL



Figure 2.1.1: Location of HI-STORE



Figure 2.1.2: HI-STORE CIS Facility Site Boundaries [2.1.3]



Figure 2.1.3: Aerial View of the Site (Full Build-Out) [2.1.8]

Notes: 1. Green square area is ISFSI Pad that would house 10,000 canisters of SNF in a vertical underground configuration.
2. Purple line from left is railroad spur.

Figure 2.1.4(a): [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 2.1.4(b): [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 2.1.4(c): [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]



Figure 2.1.5: Soils Survey Map [2.1.3]



Figure 2.1.6: Topography of Site and Surrounding Area [2.1.3]



Figure 2.1.7: Topography of Site and Surrounding Area [2.1.3]

Figure 2.1.8: Topography of Site and Surrounding Area [2.1.3]



Figure 2.1.9: Region of Influence with a 50-Mile Radius of the Site [2.1.13]



Figure 2.1.10: Sector Population Map



Figure 2.1.11: Surface Land Ownership in the Vicinity of the Site [2.1.15]



Figure 2.1.12: Mineral Resources near the Site



Map of Potash Conflicts

Figure 2.1.13: Potash Resources near the Site

2.2 NEARBY INDUSTRIAL, TRANSPORTATION, MILITARY, AND NUCLEAR FACILITIES

Figure 2.2.1 identifies industrial facilities located within approximately 5 miles of the Site. These facilities are:

- Land Farm — oilfield waste management company that remediates contaminated soil from oil and gas operations. Located 1.9 miles southwest of the Site, contaminated soils are trucked to the facility and remediated using microbial degradation of the hazardous compounds.
- Potash Facility — National Potash Mine, located approximately 4.2 miles west of the Site. This mine first began operations in 1957. Potassium (mainly) is mined below surface with boring machines and lifted to the surface through shafts using hoists.
- Transwestern — gas pipeline compressor station located approximately 5.2 miles southwest of the Site. This station consists of a small building with compressors used to compress natural gas, transporting it through the gas pipeline.
- Caliche — mining operation located approximately 4 miles southwest of the Site. Caliche generally occurs on or near the surface or at depths of 10-20 feet. Caliche is mined using traditional excavation machinery and is used in construction applications.

None of the facilities located within 5 miles of the Site are engaged in operations that would pose a hazard to the Site or affect the design basis of the Site. The closest natural gas pipeline is approximately 2 miles from the Site [2.1.3]. There are no transportation or military installations near the Site. With regard to nuclear facilities, Figure 2.2.2 depicts existing or planned nuclear facilities in the vicinity of the Site. As shown on that Figure, all of these facilities would be within 50-miles of the proposed Site. A brief description of these other nuclear facilities follows:

- **Waste Isolation Pilot Plant (WIPP)**: Located approximately 16 miles southwest of the proposed Site, WIPP is the nation's first underground repository permitted to safely and permanently dispose of transuranic (TRU) radioactive and mixed waste generated through defense activities and programs. WIPP, which has been operational since March 1999, stores TRU in underground salt caverns approximately 2,150 feet deep. From the first receipt of waste in March 1999 through the end of 2014, approximately 90,983 cubic meters of TRU waste has been disposed of at the WIPP facility. The environmental impacts of the WIPP are described in the *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement* (DOE/EIS-0026-S2) [2.2.1], as well as the *Waste Isolation Pilot Plant Annual Site Environmental Report for 2014* [2.2.2].
- **National Enrichment Facility (NEF)**: Located approximately 38 miles southeast of the proposed Site, the NEF is used to enrich uranium for use in manufacturing nuclear fuel for commercial nuclear power reactors. NEF enriches uranium using a gas centrifuge process. The environmental impacts of the NEF are documented in NUREG-1790 [2.2.3].
- **Fluorine Extraction Process & Depleted Uranium De-conversion Plan (FEP/DUP)**: Located approximately 23 miles northeast of the proposed Site, the FEP/DUP will de-convert depleted uranium hexafluoride (DUF6) into fluoride products for commercial resale and uranium oxides for disposal. Construction of that facility is expected to begin

before the end of 2016. The environmental impacts of the FEP/DUP are documented in NUREG-2113 [2.2.4].

- **Waste Control Specialists (WCS) CIS Facility**: In May 2016, WCS submitted a license application to the NRC to construct and operate a CIS Facility in Andrews County, Texas, approximately 39 miles east of the Holtec proposed Site. The WCS CIS Facility would be similar to the Holtec Site, but would utilize AREVA's horizontal canister storage system (NUHOMS) at the facility. A limited number of vertical canisters supplied by NAC may also be stored. The environmental impacts of the WCS CIS Facility are documented in an ER which WCS submitted to the NRC in May 2016 [2.2.5]. In addition, the NRC is expected to prepare an EIS for the WCS CIS Facility.

Figure 2.2.1: Industrial Facilities Within Approximately 5 Miles of the Proposed Site



Figure 2.2.2: Existing or Planned Nuclear Facilities in the Vicinity of the Proposed Site

2.3 METEOROLOGY

2.3.1 Regional Climatology

The climate at the Site is typically semi-arid with generally mild temperatures, low precipitation, low humidity, and with a high evaporation rate. The winter weather typically has high pressure systems that are located in the central part of the western U.S. and low pressure systems located in north-central Mexico. In the summer, the region is typically affected by low pressure systems located over Arizona. Overall, precipitation is low and storms are infrequent. Winds during the spring may cause dust during construction periods; however, it is anticipated to be a minimal and temporary impact in comparison to the naturally occurring dust.

Meteorological information was obtained from various sources, including the Western Regional Climate Center (WRCC) and other sources as noted in this section. The use of the data from the WRCC and other sources are appropriate due to proximity to the proposed Site and are expected to have similar climates. The WRCC is a governmental department closely associated with the National Oceanic and Atmospheric Administration (NOAA) and the National Weather Service (NSW). The data from the WRCC is generally considered to be the authoritative source of meteorological data for the region (see Appendix A, Section A.2 of the ER [1.0.4] for additional details regarding the applicability of data from the WRCC).

Temperatures. Data collected over approximately the past 75 years at the Lea County Regional Airport station [2.3.1] is summarized in Table 2.3.1. The temperature data reported in this summary table includes monthly average values for the minimum, average, and maximum temperatures as well as the monthly extreme values for the minimum and maximum temperatures. Additionally, annual values for these temperature parameters are included.

A site-specific 3-day average ambient temperature is defined by evaluating local weather service records for the Lea County in which the site is situated. The results are as follows:

- Location: Lea Regional Airport
- Records Period: 1980 – 2017
- Maximum 3-Day Average Temperature: 90.7°F

Winds. Prevailing wind directions and wind speeds at the Lea County Regional Airport station are presented in Table 2.3.2 and depicted graphically in Figure 2.3.2. The average wind speed is approximately 12 miles per hour (mph) and the prevailing wind direction is from the south. Winds are typically moderate, between 1 mph and 19 mph blowing 84 percent of the time, with calm winds (winds less than 1.3 mph) occurring only approximately 8 percent of the time [2.3.1].

With respect to wind gusts, the average wind speed of all of the maximum gusts is approximately 25 mph. The prevailing wind direction for wind gusts is wind from southwest during 11 percent of the observations; however, the wind gusts are out of the south, south-southeast, and southeast during 30 percent of the observations. Typical gusts range in speed from 13 mph to 32 mph, comprising of 86 percent of the gusts. Gusts range in speed from 32 mph to 47 mph occurred during 13 percent of the observations, and less than 1 percent of the gusts observed were over 47 mph [2.3.1].

Mixing Heights. Mixing height is the height above the ground where the strong, vertical mixing of the atmosphere occurs. G.C. Holzworth developed mean annual morning and afternoon mixing heights for the contiguous United States [2.3.2]. The results of Holzworth's calculation methods for mixing heights include mean annual morning and afternoon mixing heights at the Site of approximately 1,430 feet and 6,854 feet, respectively [2.3.2]. Table 2.3.3 shows the average morning and afternoon mixing heights for Midland-Odessa, Texas, which is the nearest available area with mixing height data, located approximately 100 miles southeast.

Tornadoes. Tornadoes are typically classified by the F-Scale classification. The F-Scale classification of tornadoes is based on the appearance of the damage that the tornado causes. The six classifications range from F0 to F5 with an F0 tornado having winds of 40-72 mph and an F5 tornado having winds of 261-318 mph [2.3.3]. Note that as of February 1, 2007, an enhanced F-scale for tornado damage went into effect in the United States. The switch to the enhanced F-scale involves:

1. Changing the averaging interval for wind speed estimates from the fastest quarter-mile wind speed to a maximum three-second average wind speed.
2. Changing the minimum tornado wind speed from 40 mph to 65 mph.
3. Changing the wind speed intervals associated with each F scale class.

The enhanced F-scale uses three-second wind gusts estimated at the point of damage based on a judgment of eight levels of damage to 28 indicators. The enhanced F-scale has six classifications, EF0 to EF5, with an EF0 tornado having three-second gusts of 65-85 mph and an EF5 tornado having three-second gusts of over 200 mph [2.3.4].

Based on a United States-wide study performed on a state by state basis, the average tornado probability for any F-scale tornado for the Site is between $1x10^{-6}$ and $2x10^{-4}$, as is presented in Figure 2.3.3 [2.1.3]. Ninety two tornados have occurred in Eddy and Lea counties since 1954. The highest number of tornados in any given year was 15 in 1991; of which, 14 occurred over a two day period. The lowest number of tornado in a year has been zero, with a mean average of 1.5 tornados occurring in a year. Most tornados recorded were F0 in scale and occurred in the spring [2.3.5].

Hurricanes. The Site is located over 500 miles from the oceanic coast. Because hurricanes lose their intensity quickly once they pass over land, impacts from a hurricane at the Site are unlikely.

Thunderstorms. Thunderstorms can occur during every month of the year, but generally occur from March through October of each year. Thunderstorms occur an average of 39 days per year in Carlsbad, New Mexico. The seasonal averages are: 2.7 days in spring (March through May); 8.3 days in summer (June through August); 2.3 days in fall (September through November); and less than 1 day in winter (December through February) [2.3.1]. Occasionally, thunderstorms are accompanied by hail [2.1.14].

Precipitation. A summary of precipitation data collected at the Lea County Regional Airport station resulted in an annual mean average total precipitation of 10.2 inches with monthly mean average totals ranging from 0.24 inches in March to 1.9 inches in September. The monthly minimum total is 0.00 inches and the monthly maximum total is 6.2 inches. The highest daily total is 3.6 inches occurring in December of 2015. A summary of this information is presented in

Table 2.3.4 and depicted graphically with monthly average total precipitation in Figure 2.3.4 [2.3.1].

A summary of snowfall data collected at the Lea County Regional Airport station resulted in an annual mean average total precipitation of 5.13 inches with monthly mean average totals ranging from 1.84 inches in February to 0.0 inches from May to October. The monthly minimum total is 0.00 inches and the monthly maximum total is 21.2 inches. The highest daily total is 10.00 inches occurring in February of 1956 [2.3.1].

Based on the season, atmospheric pressure systems can affect temperature and cause cloud formation. Clouds are formed when warm, moist air rises into the atmosphere and the droplets are cooled. When the droplets cool, the water from the air condenses into tiny droplets and forms clouds. This occurs during low pressure system. These low pressure systems typically occur during the spring and summer. Climatology data indicate the relative humidity throughout the year ranges from 45 percent to 61 percent in the region, with the highest humidity occurring during the early morning hours [2.1.14].

2.3.2 Local Meteorology

There are no on-site weather stations, however due to the proximity of the Lea County Regional Airport weather station to the Site (approximately 30 miles away), it is reasonable to say that the data presented in Section 2.3.1 adequately represents the on-site conditions for Local Meteorology. Additional details regarding the applicability of this data can be seen in Appendix A, Section A.2 of the ER [1.0.4].

2.3.3 Onsite Meteorological Measurement Program

There are no on-site weather stations, however due to the proximity of the Lea County Regional Airport weather station to the Site (approximately 30 miles away), it is reasonable to say that the data presented in Section 2.3.1 adequately represents the on-site conditions for Local Meteorology. Additional details regarding the applicability of this data can be seen in Appendix A, Section A.2 of the ER [1.0.4]. After the license is issued for the CIS Facility, Holtec will establish an on-site meteorological data collection system. That system will collect, at a minimum, temperature, precipitation, and wind data.

Table 2.3.1

LEA COUNTY REGIONAL AIRPORT STATION TEMPERATURE DATA (09/01/1941-06/09/2016) [2.3.1]

Month	Average Monthly Minimum Temperature °F	Average Monthly Maximum Temperature °F	Average Monthly Temperature °F	Extreme Minimum Temperature °F	Extreme Maximum Temperature °F
January	27.72	56.25	41.98	4.00	81.00
February	30.68	61.12	45.90	-11.00	84.00
March	35.67	67.32	51.53	14.00	86.00
April	44.32	75.05	59.69	24.00	93.00
May	53.77	84.05	68.91	28.00	103.00
June	63.71	92.90	78.31	51.00	107.00
July	66.73	93.62	80.17	52.00	108.00
August	65.50	92.57	79.04	55.00	104.00
September	58.29	86.47	72.37	41.00	104.00
October	47.82	75.76	61.79	24.00	94.00
November	34.23	64.42	49.33	4.00	85.00
December	28.78	59.04	43.91	7.00	79.00
Annual	46.34	76.03	61.19	-11.00	108.0

Note: The extreme maximum temperature was recorded in July of 2000 and again in July 2001 at 108°F and the extreme minimum temperature was recorded in February of 1951 at -11°F.

Table 2.3.2

LEA COUNTY REGIONAL AIRPORT STATION ALL WIND DATA (12/01/1948-12/31/2014) [2.3.1]

Wind Speed (mph)	N (%)	NNE (%)	NE (%)	ENE (%)	E (%)	ESE (%)	SE (%)	SSE (%)	S (%)	SSW (%)	SW (%)	WSW (%)	W (%)	WNW (%)	NW (%)	NNW (%)	Total (%)
1.3-4	0.1	0.1	0.2	0.1	0.2	0.2	0.2	0.2	0.3	0.2	0.2	0.1	0.1	0.1	0.1	0.1	2.5
4-8	1	0.8	0.9	0.7	1.8	1.3	1.4	1.4	2.7	1.7	1.3	0.9	0.6	0.5	0.6	0.5	18.2
8-13	2	1.5	1.7	1.5	3	2.8	3.9	4.5	6.2	3.4	2.8	2.3	1.7	1.2	1.1	0.9	40.4
13-19	1.4	1.2	1.1	0.6	1.1	1.2	2.2	2.8	2.9	1.6	1.9	1.8	1	0.7	0.6	0.5	22.7
19-25	0.5	0.4	0.2	0.1	0.1	0.1	0.3	0.6	0.4	0.4	0.7	0.7	0.4	0.3	0.2	0.2	5.6
25-32	0.2	0.1	0.1	0	0	0	0	0.1	0.1	0.1	0.2	0.3	0.1	0.1	0.1	0.1	1.7
32-39	0	0	0	0	0	0	0	0	0	0	0	0.1	0	0	0	0	0.4
39-47	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.1
47+	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Total (%)	5.3	4.1	4.1	3.1	6.2	5.7	7.9	9.5	12.6	7.5	7.2	6.4	3.9	3	2.7	2.3	91.5
Avg. Wind Speed (mph)	12.6	12.4	11.4	10.5	10.0	10.5	11.3	11.9	11.0	11.3	12.9	14.1	12.8	13.4	11.9	12.3	10.8

NOTE: Total Calm Winds (Calm Winds is defined as less than 1.3 mph) is 8.4 percent

Table 2.3.3

AVERAGE MORNING AND AVERAGE AFTERNOON MIXING HEIGHTS [2.3.2]

	Winter (feet)	Spring (feet)	Summer (feet)	Autumn (feet)	Annual (feet)
Morning	951	1,407	1,988	1,375	1,430
Afternoon	4,186	8,035	9,003	6,191	6,854

Table 2.3.4

LEA COUNTY REGIONAL AIRPORT STATION PRECIPITATION DATA (09/01/1941-06/09/2016) [2.3.1]

Month	Monthly Minimum Totals (Inches)	Monthly Maximum Totals (Inches)	Monthly Average Totals (Inches)	Extreme Daily Maximum Totals (Inches)
January	0.00	2.09	0.31	0.68
February	0.00	1.02	0.32	0.68
March	0.00	1.41	0.24	0.52
April	0.00	2.26	0.65	1.40
May	0.00	5.02	1.43	1.72
June	0.00	3.19	0.75	1.77
July	0.00	3.49	1.17	1.98
August	0.04	4.08	1.32	2.28
September	0.05	5.84	1.85	2.13
October	0.00	3.81	1.52	1.73
November	0.00	1.07	0.26	0.95
December	0.00	6.21	0.56	3.63
Annual	2.81	18.66	10.16	3.63

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL



Figure 2.3.1: Lea County Regional Airport Station Temperature Data (09/01/1941-06/09/2016) [2.3.1]



Figure 2.3.2: Lea County Regional Airport Station All Wind Rose (12/01/1948-12/31/2014) [2.3.1]



Figure 2.3.3: Tornado Probability Map [2.1.3]



Figure 2.3.4: Monthly Average Total Precipitation Lea County Regional Airport Station (09/01/1941-06/09/2016) [2.3.1]

2.4 SURFACE HYDROLOGY

2.4.1 Hydrologic Description

The Site lies within the Pecos River Basin (see Figure 3.5.1 of the ER [1.0.4]), which has a maximum basin width of 130 miles, and a drainage area of 44,535 square miles. The Pecos River is the closest surface water feature to the Site. At its nearest approach, the distance from the Site to the Pecos River is 26 miles. Because there are no surface water features near the Site, a detailed discussion of surface water features is not needed. The information that follows is an overview of the surface water features in the area.

Surface drainage at the proposed Site is contained within two local playa lakes that have no external drainage. These playas are generally dry, but retain runoff temporarily [2.1.3]. Runoff does not drain to one of the state's major rivers. The only major natural lakes or ponds within 6 miles of the Site include Laguna Gatuna, Laguna Tonto, Laguna Plata, and Laguna Toston which are ephemeral playas. Surface runoff from the Site flows into Laguna Gatuna to the east and Laguna Plata to the northwest [2.1.3]. Surface water is lost through evaporation, resulting in high salinity conditions in soils associated with the playas. These conditions are not favorable for the development of viable aquatic or riparian habitats.

Other than the playas, the nearest surface water is the Pecos River which is west of the Site. Like most rivers in New Mexico, the Pecos River is described as "extremely variable from year-to-year" due to its dependence on runoff. The principle use of Pecos River water is for agriculture. There are no sensitive or unique aquatic or riparian habitats or wetlands at the Site, nor is there surface water in the vicinity that is potable [2.1.3].

As further discussed in sections 2.4.2 and 2.4.3, the Site can be considered "flood-dry" and therefore it can be concluded that none of the facilities important to safety structures will be affected by the Site's hydrologic features. Additionally, there are no surface water bodies on the Site and groundwater resources are at depths of approximately 300 to 400 feet, therefore no population groups are affected by normal Site operations.

2.4.2 Floods

Floodplains are areas of low-level ground present along rivers, stream channels, or coastal waters subject to periodic or infrequent inundation due to rain or melting snow. Risk of flooding typically depends on local topography, the frequency of precipitation events, and the size of the watershed above the floodplain. Flood potential is evaluated by the Federal Emergency Management Agency (FEMA), which defines the 100-year floodplain as an area that has a one percent chance of inundation by a flood event in any given year. Federal, state, and local regulations often limit floodplain development to passive uses such as recreational and preservation activities to reduce the risks to human health and safety. Floodplain ecosystem functions include natural moderation of floods, flood storage and conveyance, groundwater recharge, nutrient cycling, water quality maintenance, and diversification of plants and animals.

The proposed Site or Lea County has no floodplain identified or mapped for Lea County, New Mexico [2.1.6, 2.1.7]. Elevations in Lea County vary from 2,900 feet in the southeast to 4,400 feet in the northwest. This relief provides two surface water drainage basins in the county. The Texas Gulf Basin, located in the northern portion of Lea County, and the Pecos River Basin,

located in the southern portion of the county, is separated by the Mescalero Ridge and its extended escarpment [2.1.3].

In Lea County neither of the two major drainage basins, the Texas Gulf Basin in the north and east and the Pecos River Basin in the south and west, contain large-scale surface-water bodies or through-flowing drainage systems. The surface water supplies that exist are transitory and limited to quantities of runoff impounded in short drainage ways, shallow lakes, and small depressions, including various playas and lagunas [2.1.3].

The topography of the Site shows a high point located on the southern border of the Site and gentle slopes leading to the two drainages (Laguna Plata and Laguna Gatuna). Both of these drainages would be able to accept a one day severe storm total within the 7.5 inch range with excess free board space. The natural drainage of the Site is useful by providing a natural area for impoundment of excess runoff during severe storms [2.1.3].

2.4.3 Probable Maximum Flood (PMF)

Because there are no significant bodies of water or rivers within 50 miles of the Site, the only plausible flooding hazard to the Site is from stormwater runoff during rain events. To estimate the potential effects of rainfall-induced stormwater runoff, Holtec reviewed precipitation data for the area spanning more than 50-years (see Paragraph 3.6.1.7 of the ER [1.0.4]), as well as other available data developed for other nuclear facilities in the area. The highest daily precipitation in the area was 3.6 inches, which occurred in December of 2015 [1.0.4].

Based on the data reviews, Holtec determined that the probable maximum flood (PMF) for the CIS Facility Site would be similar to the PMF developed by NRC in 2012 for the FEP/DUP site (see NUREG-2116; [2.4.1]). The FEP/DUP is located approximately 23 miles northeast of the proposed Site. Given the proximity of that facility to the proposed Site, the PMF at the FEP/DUP site reasonably represents the PMF that could occur at the Site.

In the Safety Evaluation Report for the FEP/DUP (NUREG-2116; [2.4.1]), the NRC estimated the 1-hour, 24-hour, and 48-hour all-season precipitation corresponding to a 100,000-year return period by extrapolating the NOAA precipitation data [2.4.2] using a linear least-square procedure. Considering the 1-hour, 24-hour, and 48-hour all-season precipitation for a 100,000-year return period, the NRC concluded that the estimated maximum flood (standing water) level would be 4.8 inches [2.4.1].

As discussed in Section 2.4.2, drainages on the Site would be able to accept a one day severe storm total within the 7.5 inch range with excess free board space. Because the Site's drainage areas can handle a greater maximum flood height than what the PMF has been determined to be, the site can be considered to be "flood-dry".

Per Table 2.3.1 of the HI-STORM UMAX FSAR [1.0.6], the HI-STORM UMAX System is able to withstand a maximum flood height of 125 ft. Therefore, all ITS components of the system can be considered safe from flooding concerns.

With regard to the potential for surface erosion from flooding at the Site, as discussed in Section 4.3 of the ER [1.0.4], soils at the Site are considered to be only slightly susceptible to water erosion.

2.4.4 Potential Dam Failures (Seismically-Induced)

The nearest dams are Brantley Dam, approximately 38 miles, and Avalon Dam, approximately 31 miles from the proposed Site. Both dams are at an elevation more than 500 feet below the Site. As a result of the large distances to the nearest bodies of water, these bodies of water do not present a credible disruptive event for the proposed Site.

2.4.5 Probable Maximum Surge and Seiche Flooding

There are no significant bodies of water or rivers within 50 miles of the Site and seiche flooding is excluded as a potential flood hazard.

2.4.6 Probable Maximum Tsunami Flooding

The Site is approximately 500 miles from any coastal area and tsunamis are excluded as a potential flood hazard.

2.4.7 Ice Flooding

The mean annual snowfall is 5.1 inches recorded at the Hobbs weather station. The maximum recorded snow accumulation for Hobbs, NM, is 12.2 inches, and a 100-year, 2-day snowfall is 12.1 inches [2.4.2]. The Site is not subject to flooding caused by ice jams. In the winter, during those periods when the playas are retaining temporary runoff, freezing of the retained water can occur.

2.4.8 Flood Protection Requirements

Because the flooding analyses do not indicate that the Site would be subject to flooding, there are no flood protection requirements.

2.4.9 Environmental Acceptance of Effluents

As stated in Chapter 14, the canister storage system does not create any radioactive materials or have any radioactive waste treatment system and thus provides assurance that there are no radioactive effluents from the spent fuel storage system. Additionally, surface drainage at the proposed Site is contained within two local playa lakes that have no external drainage. Evapo-transpiration at the Site is five times the precipitation rate, indicating that there is little infiltration of precipitation into the subsurface. The near surface water table is approximately 35-50 feet deep, where present and is likely controlled by the water level in the playa lakes. Therefore, there is little to no risk of effluents of any kind being accepted by the environment.

2.5 SUBSURFACE HYDROLOGY

The Site is located in the Capitan Underground Water Basin (UWB) as shown in Figure 2.5.1 [2.5.1]. A declared groundwater basin is an area of the state proclaimed by the State Engineer to be underlying a groundwater source having reasonably ascertainable boundaries. By such proclamation, the State Engineer assumes jurisdiction over the appropriation and use of groundwater from the source. The Capitan UWB covers approximately 731,500 acres in the south-central portion of Lea County. It is located within a geologic province known as the Delaware Basin, a subdivision of the Permian Basin. The Capitan UWB is oriented in a northwest-southeast alignment above an arc-shaped section of a formation known as the Capitan Reef Complex. The Capitan aquifer occurs within dolomite and limestone strata deposited as an ancient reef. The groundwater quality of the Capitan in Lea County is very poor, with total dissolved solids ranging from 10,065 to 165,000 milligrams per liter (mg/L).

Other aquifers in the Capitan UWB are found in the overlying Rustler Formation, Santa Rosa Sandstone, Ogallala Formation, and Cenozoic alluvium and are important sources of groundwater in the Capitan UWB. The depth to the top of the Rustler Formation ranges from 900 to 1,100 feet.

Potable groundwater is available from three geologic units in southern Lea County; the Triassic Dockum shale, the Tertiary Ogallala, and Quaternary alluvium [2.5.2]. No potable groundwater is known to exist in the immediate vicinity of the Site. Shallow groundwater is present in a number of locations in the area, but water quality and quantity are marginal at best and most, if not all, shallow wells that have been drilled in the area are either abandoned or not currently in use. Potable water for the area is generally obtained from potash company pipelines that convey water to area potash refineries from the Ogallala High Plains aquifer on the caprock area of eastern Lea County. At present, water is generally obtained from these pipelines for other area users.

Much of the shallow groundwater near the Site has been directly or indirectly influenced by brine discharges from potash refining or oil and gas production. Potash mines have discharged thousands of acre-feet of near-saturated refinery process brine to Laguna Plata and to Laguna Toston for many years. But discharges ceased in Laguna Plata in the mid-1980s and in Laguna Toston by 2001. Laguna Gatuna was the site of multiple facilities for collection and discharge of brines that were co-produced from oil and gas wells in the entire area; facility permits authorized discharge of almost one million barrels of oilfield brine per month between 1969 and 1992. As a result, saturations of shallow groundwater brine have been created in a number of areas associated with the playa lakes [2.1.3].

Evapo-transpiration at the Site is five times the precipitation rate, indicating that there is little infiltration of precipitation into the subsurface. Regional data indicates that groundwater is on the order of 300 to 400 feet deep. There are numerous low permeability layers between the surface and the expected groundwater level [2.1.3]. Because of the depth of groundwater, excavation during construction would not reach the groundwater. Groundwater at the Site would also not likely be impacted by any potential releases; therefore, groundwater would be unaffected by the proposed activities. The near surface water table appears to be 35-50 feet deep, where present, and is likely controlled by the water level in the playa lakes. No groundwater was encountered in the test boring on the west side of the Site in the vicinity where the ISFSI would be located

[2.1.3]. Consequently, no impacts from the near surface water table would be expected. Additional information regarding groundwater can be found in Sections 3.5.2 and 4.5 of the ER [1.0.4].

Well drilling was conducted at the Site in 2007. Two wells, ELEA-1 and ELEA-2 were drilled on the Site to identify the depth and character of water-bearing rocks. The goals of the drilling investigation were to identify the potential for thin groundwater saturation in lower alluvium perched on the Triassic shale, or deeper groundwater saturation in the Triassic shale. Locations of these wells and other wells in the vicinity are shown on the well location map in Figure 2.5.2.

Piezometer ELEA-1. A small amount of water was initially detected in the well; however the water has steadily declined to within a few inches of the bottom of the well and is attributed to the small amount of bentonite hydration water that was placed in the well to seal the upper annulus during completion. Based on the data obtained from ELEA-1, no shallow groundwater saturation is present at the top of the Triassic shale at the location [2.1.3].

Piezometer ELEA-2. Water level in this well rose slowly over several days to a static depth of 34 feet below land surface (3,497 feet above mean sea level). The water-bearing zone in this well consists of either fractures or tight sandy zones between the depths of 85 and 100 feet; water in this zone is under artesian head of 50 feet. Laboratory analyses of water samples from the well indicate that the water is highly mineralized brine [2.1.3].

From the data collected from the onsite drilling, shallow alluvium is likely non water-bearing at the Site. Groundwater saturation in the Triassic shale appears to be limited to small amounts of highly mineralized water likely associated with the brine in Laguna Gatuna, where the brine is 3,500 feet above mean sea level [2.1.3].

Based on this information presented in this section and the fact that there are no radioactive effluents from the proposed spent fuel storage system, it can be concluded that no buildup of radionuclides will occur in the subsurface hydrologic system.



Figure 2.5.1: Administrative Underground Water Basins in the State of New Mexico [2.5.1]



Figure 2.5.2: Water Wells and Piezometer Locations [2.1.3]

2.6 GEOLOGY AND SEISMOLOGY

This section identifies the geological and seismological characteristics of the Site and its vicinity. The location for the proposed Site, and sites in the vicinity including the WIPP (located 16 miles southwest), and the NEF (located 38 miles southeast), have been thoroughly studied in recent years in preparation for construction of other facilities. Data are available from these investigations in the form of various reports [2.1.3, 2.6.1, 2.6.2]. These documents and related material provide a substantial database and description of regional and site-specific geological conditions at the proposed Site.

2.6.1 Basic Geologic and Seismic Information

The Site is located in the northern portion of the Delaware Basin, a northerly-trending, southward plunging asymmetrical trough with structural relief of greater than 20,000 feet on top of the Precambrian basement rock. The Basin was formed by early Pennsylvanian time, followed by major structural adjustment from Late Pennsylvanian to Early Permian time. During the Triassic period, the area was uplifted, resulting in deposition of clastic continental shales (redbeds). Continuing uplift resulted in erosion and/or nondeposition until the middle to late Cenozoic period, when regional eastward tilting completed structural development of the basin as it exists today. Shallow subsurface structure at the Site consists of gently east sloping beds of Triassic age redbeds, dipping two degrees to the east. Faulting has not occurred in the northern Delaware Basin in the area of the Site. The regional geology suggests that there have been no recent, dramatic changes in geologic processes and rates in the vicinity of the Site [2.1.3].

During most of the Permian period, the Delaware Basin was the site of a deep marine canyon that extended across southeastern New Mexico and west Texas. Major structural elements of the Delaware Basin area are shown in Figure 2.6.1. The major structures of the basin include the Guadalupe Mountains on the west side, the Central Basin Platform on the east side, and the Capitan Reef Complex on the west and north sides of the basin. The reef created steep slopes toward the basin and the thickness of sediments grows precipitously toward the center of the basin from the margin of the reef. The Central Basin Platform forms an abrupt eastern terminus to the Delaware Basin; it is a steeply fault-bound uplift of basement rocks that grew through the early and middle Paleozoic period such that most of the pre-Permian sedimentary section is missing from its apex. Great thickness of organic-rich marine deposits in the basin and the presence of abrupt structures in the Capitan Reef Complex and Central Basin Platform combined to produce a prolific oil and gas province. These areas have been the focus of intense petroleum exploration and development activities since approximately 1920. Surficial geology and subsurface structure across the Delaware Basin are depicted in the maps and cross section in Figures 2.6.2 through 2.6.4. Thickness of sediments in the basin exceeds 20,000 feet, and Permian strata alone account for more than 13,000 feet of sedimentary materials [2.1.3].

The geologic formations of concern beneath the Site comprise, from oldest to youngest, consist of Permian-aged rocks (Wolfcamp series, Leonard series, Guadalupe series, Ochoa series); Triassic-aged rocks (Dockum Group); and Tertiary and Quaternary rocks (Lower Gatuna Formation, Upper Gatuna Formation); and alluvium. A stratigraphic column for the above units in provided in Figure 2.6.5.

The entire Site is underlain by Triassic bedrock consisting of shale, siltstone, and minor, fine-grained, poorly sorted sandstone. Most of the proposed operational area is relatively flat and the shale bedrock is covered by a laterally extensive veneer of 25 feet of Quaternary pediment deposits consisting of well sorted eolian sand and sandy-gravelly materials near the bedrock interface. The Mescalero Caliche unit is near the surface and is about 10 feet thick at the Site.

Most of the proposed operational area is relatively flat ranging from 3,520 feet above mean sea level (AMSL) on the northern end to 3,535 feet AMSL on the southern end. The surficial geology consists of Quaternary Pediment deposits (25 feet thick) overlying Triassic-age shale bedrock. The different soil/geologic layers are described as follows:

- Surface Soil: sandy and well-drained (0 to 2 feet below grade);
- Mescalero Caliche: well developed, naturally cemented calcium carbonate, laterally extensive, tightly bound and erosion resistant (2 to 12 feet below grade);
- Quaternary Sands: well sorted eolian sand and sandy-gravelly materials near the bedrock interface (12 to 25 feet below grade);
- Dockum Group: Triassic-age, predominantly shale, siltstone, and minor, fine-grained, poorly sorted sandstone (25 to greater than 100 feet below grade).

The shallow groundwater table is located at about 35-50 feet below grade, and thus below the Quaternary deposits and within the Triassic bedrock, as measured in site groundwater wells (ELEA-1 and ELEA-2). Excavation to a depth of 25 feet below grade is expected for facility construction; thus, the construction activity will not be in contact with the groundwater table. The hydrogeologic cross section for the Site is show in Figure 2.6.6.

2.6.2 Vibratory Ground Motion

Earthquakes of low to moderate magnitude have been documented within a 200 mile radius of the Site. The vast majority of the earthquake activity is located southeast of the Site in west Texas, and west/northwest of the Site in central New Mexico. The U.S. Geological Survey (USGS) earthquake database was used to query historical earthquakes within a 200 mile radius of the Site [2.6.3]. Results of the search of the 200 mile radius yielded a total of 244 historical earthquakes with magnitude 2.5 or greater between 1900 and the most recent update of the database in 2016. The results indicate the closest earthquake to the Site was 24 miles southwest with a magnitude of 3.1 that occurred on March 18, 2012. Two earthquakes with magnitudes greater than 5.0 were recorded within 200 miles of the Site. An earthquake with magnitude 6.5 occurred on August 16, 1931, located 140 miles southwest of the Site; and an earthquake with magnitude 5.7 occurred on April 14, 1995, located 165 miles south of the Site. The Eunice earthquake of January 2, 1992, located 39 miles east of the Site had a magnitude of 4.6. The results of the USGS earthquake search are plotted on a regional map in Figure 2.6.7.

There are three seismic source zones within a 200 mile radius of the Site: the northern and southern regions of the Southern Basin and Range – Rio Grande rift zone located west and southwest of the Site; and the Central Basin Platform zone located east of the Site. The most active seismic area within 200 miles of Site is the Central Basin Platform east of the Site. Large magnitude earthquakes are not occurring or have not occurred within the recent geologic past along the Central Basin platform due to the absence of Quaternary faults. The seismicity in west Texas, southeast of the Site, is hypothesized as being a result of fluid pressure build-up from

fluid injection, and consequential reduction in effective stress across pre-existing fractures and associated decrease in frictional resistance to sliding. Similarly, recent records (1998 through 2005) from the WIPP seismic monitoring network indicate that the strongest events recorded annually in 1999, 2000, and 2002 through 2005 (typically of 2.5 to 4.0 magnitude during this time period) have been located about 50 miles west of the Site. This seismic activity is suspected to be induced by injection of waste water from natural gas production into deep well or wells [2.1.3].

A review of the seismic risk was based on USGS Geologic Hazards Science Center's 2009 Earthquake Probability Mapping [2.6.4], which generates maps that show the probability of a magnitude 5.0 or higher earthquake within a 30-mile radius of any location within the next 50 years. On a scale of 0.00 (the lowest probability of earthquake) to 1.00 (the highest probability), all Project facilities are within the low probability range of 0.01 to 0.02 as shown in Figure 2.6.8. Earthquake probability is dominated by seismic activity within the Central Basin Platform south and east of the Site.

Probabilistic ground motion for the Site was determined using information from the USGS [2.6.5]. Figure 2.6.9 is a probabilistic ground motion map of the Site, illustrating peak horizontal acceleration with a 2 percent probability of exceedance in 50 years (2,500 year return interval). The Peak Horizontal Ground Acceleration (PGA) value of 0.04 of the acceleration due to gravity (g) to 0.06g estimated by the regional USGS algorithm is similar to values suggested by several site-specific studies for nearby locations. The Geological Characterization Report (GCR) for the WIPP Site [2.6.1] determined acceleration of ≤0.06g for a return interval of 1,000 years, and ≤0.1g for a return interval of 10,000 years (WIPP is located approximately 16 miles southwest of the Site); the results of the GCR were reviewed and confirmed by Sanford et al. [2.6.5]), which estimated a maximum expected acceleration of 0.1g for the WIPP, and again in the Safety Evaluation Report for the WIPP [2.6.6], which describes the GCR results as conservative. The seismic hazard for the National Enrichment Facility (NEF) uranium enrichment facility predicts 0.15g for a return interval of 10,000 years [2.6.2]. The NEF facility is about 38 miles southeast of the Site [2.1.3].

Quaternary-age faulting (exhibiting movement in the past 1.6 million years) is not present in the vicinity of the Site. The nearest Quaternary-age fault is located 85 miles southwest of the Site [2.6.7]. Little is known about this fault except that it is a normal fault, 3.6 miles in length, and has a slip rate of less than 0.01 in/yr. The Guadalupe fault forms a scarp on unconsolidated Quaternary deposits at the western base of the Guadalupe Mountains in the Basin and Range physiographic province. The same USGS database shows numerous other Quaternary-age faults within a 200-mile radius of the Site, located to the west and southwest, most of which are at the distal end of the radius and are near the Rio Grande Rift of central New Mexico. Figure 2.6.10 is a map of New Mexico and West Texas showing Quaternary-age faulting as cataloged by the USGS, and as down-loaded from the database referenced above. The database contains locations and information on faults and associated folds that have been active during the Quaternary.

In all, there are a total of 27 Quaternary faults or fault zones within a 200-mile radius of the Site. A total of four "capable" faults were identified, the closest being the Guadalupe fault (85 miles to the southwest). A "capable" fault is one that has exhibited one or more of the following characteristics (10 CFR 100 [2.6.10] Appendix A.III, Definitions):

- Movement at or near the ground surface at least once within the past 35,000 years or movement of a recurring nature within the past 500,000 years.
- Macro-seismicity instrumentally determined with records of sufficient precision to demonstrate a direct relationship with the fault.
- A structural relationship to a capable fault according to the previous two characteristics such that movement on one could be reasonably expected to be accompanied by movement on the other.

For the purposes of this assessment, capable faults were identified based solely upon the first characteristic above.

2.6.3 Surface Faulting

There are no surface faults at the Site. Tectonic activity in the Delaware Basin is characterized by slow uplift relative to surrounding areas which has resulted in erosion and dissolution of rocks in the Basin. Faulting has not occurred in the northern Delaware Basin in the area of the Site. The regional geology suggests that there have been no recent, dramatic changes in geologic processes and rates in the vicinity of the Site [2.1.3].

2.6.4 Stability of Subsurface Materials

The entire Site is underlain by Triassic bedrock consisting of shale, siltstone, and minor, fine-grained, poorly sorted sandstone. Most of the proposed operational area is relatively flat and the shale bedrock is covered by a laterally extensive veneer of 25 feet of Quaternary pediment deposits consisting of well sorted eolian sand and sandy-gravelly materials near the bedrock interface. The Mescalero Caliche unit is near the surface and is about 10 feet thick at the Site.

Comparison of conditions at the Site with those conditions favorable to karst development indicates that conditions at the Site are not conducive to karst development. No thick sections of soluble rock are present at or near land surface; the shallowest soluble bedrock materials are gypsum and halite beds in the Rustler Formation, which is located at least 1,100 feet below land surface at the Site. Additionally, rainfall rates in the area are low. Mescalero caliche is soluble and situated at or near land surface; however this unit is no more than 10 feet in thickness. Local dissolution of this unit may have resulted in the development of a number of small shallow depressions in the area; however this is not regarded as an active or significant karst process at the Site [2.1.3].

During site reconnaissance, detailed inspection of the areas around the margins of Laguna Gatuna and tributary drainages was performed to identify any tension cracks, disrupted soils, tilting, or other evidence of rapid earth displacement. No tension cracks or other evidence of displacement was observed. Additionally, older cultural features in the area were inspected to identify evidence of tilting, offset, or displacement that could indicate recent land movement. A number of oil wells were drilled along the west flank of Laguna Gatuna beginning in the early 1940's. Most of the wells were abandoned by 1975 and well monuments were installed; several of the well monuments were identified during site reconnaissance. None of the monuments displayed evidence of tilting that might be associated with local earth movements [2.1.3].

A halite preservation and stability assessment entitled, *Report on Evaporite Stability in the Vicinity of the Proposed GNEP Site, Lea County, NM* was performed for the Site as part of the

GNEP siting study [2.1.3]. This study was conducted in order assess existing data on the continuity and stability of evaporites under the Site, with special attention to data within, or adjacent to the boundaries of nearby lakes or playas. The main data sources for the project area include potash exploration drillholes and oil and gas drillholes.

Lithologic logs from potash exploration and geophysical logs from oil and gas exploration around the Site in southwestern Lea County, New Mexico, provide evidence of the extent and stability of evaporites and their possible relationship to the formation of playas in the vicinity.

An elevation map on the uppermost evaporite-bearing bed (top of Permian Rustler Formation) shows continuity across the area. General northeast slopes are revealed, with some flattened slopes associated with Laguna Plata. There are no indications of lowering of the surface by dissolution; the top of Rustler under most of Laguna Plata is actually elevated above the general trend. The surface varies locally due to variable reporting for potash drillholes of the first encounter with the uppermost sulfate bed of the Rustler.

There are no surface, drillhole, or mining indications that subsidence and collapse chimneys occur at the Site or surrounding area. These features are associated with the front of the Capitan reef, which is south of the Site, and with a hydraulic environment that is not known to exist at the Site.

Geophysical logs indicate that halite in the Rustler persists across the Site area. Dissolution from above to create lows on the uppermost Rustler is not a practical process. There is neither subsurface drillhole data nor surface features indicating a dissolution front in the vicinity of the Site. There is no evidence for either past or continuing natural processes that would cause Site instability due to halite dissolution in the near future [2.1.3].

With regard to potential future drilling on the Site, Holtec has an agreement [2.6.9] with Intrepid Mining LLC (Intrepid) such that Holtec controls the mineral rights on the Site and Intrepid will not conduct any potash mining on the Site. Additionally, any future oil drilling or fracking beneath the Site would occur at greater than 5,000 feet depth, which ensures there would be no subsidence concerns [2.1.8].

2.6.5 Slope Stability

The site terrain ranges in elevation from 3,520 to 3,540 feet above mean sea-level sloping gently downward from south to north. Most of the site is flat with slopes ranging from 0 to 3 percent, as shown in Figure 2.6.11. Therefore, there is no risk from slope instability (i.e. landslides) in the vicinity of the Site.



Figure 2.6.1: Major Regional Geological Structures near the Site [2.1.3]



Figure 2.6.2: Geologic Cross Section through the Capitan Reef Area, Eddy and Lea Counties, NM [2.1.3]



Figure 2.6.3: Surficial Geology in the Vicinity of the Site [2.1.3]



Figure 2.6.4: Regional Surficial Geology and Generalized Cross Section Through the Site [2.1.3]



Figure 2.6.5: Permian to Quaternary-aged Stratigraphy of the Delaware Basin [2.1.3]



Figure 2.6.6: Hydrogeologic Cross Section [2.1.3]



Figure 2.6.7: Earthquakes (Magnitude 2.5 or greater) within 200 miles of the Site [2.6.3]



Figure 2.6.8: Probability of earthquake with Magnitude greater than 5.0 within 50 years and 30 miles of the site [2.6.4]



Figure 2.6.9: Peak Ground Acceleration (percent of gravity) (2,500 year return interval) [2.6.4]



Figure 2.6.10: Quaternary faults within 200-mile radius of the site [2.6.8]



Figure 2.6.11: Elevation Contours at the Site

2.7 SITE SPECIFIC DATA FOR THERMAL AND STRUCTURAL ANALYSES

The site characterization effort, summarized in this chapter, enables a conservative set of parameters important to thermal and structural analyses to be established. These parameters are summarized in Table 2.7.1 and are used in Chapter 5 (Structural) and Chapter 6 (Thermal). The ambient temperature in Table 2.7.1 is based on the meteorological data for the site with a small margin added for conservatism.

The 10,000-year return earthquake, adopted as the Design Basis Earthquake (DBE) for the HI-STORE facility, is bounded by the classical Reg. Guide 1.60 response spectrum with its ZPAs denoted in Table 2.7.1. Likewise, the assumed bounding tornado missiles considered for the Site are based on the regulatory guidance and a national standard [2.7.1, 2.7.2]. These are the same missiles considered for the HI-STORM FW MPC Storage System in Docket 72-1032 and the HI-STORM UMAX Canister Storage System in Docket 72-1040.

Table 2.7.1

SITE SPECIFIC DATA FOR THERMAL AND STRUCTURAL ANALYSIS

Parameter	Conservatively assumed value for analysis based on site data	Comment
Normal Ambient Temperature (°F)	62	Bounding Annual Average at the Site
Normal Soil Temperature (°F)	62	Conservatively assumed to be equal to the Normal Ambient Temperature
Off-Normal Ambient Temperature (°F)	91	This temperature is based on 3-day average ambient temperature defined by evaluating local weather service records for the Lea County in which the Site is situated
Extreme Accident Level Ambient Temperature (°F)	108	This temperature value is the extreme maximum ambient temperature recorded at the Site
Reference temperature for short term operations (°F)	0 (min) and 91 (max)	This temperature is based on 3-day average ambient temperature defined by evaluating local weather service records for the Lea County in which the Site is situated
Extreme Minimum Ambient Temperature recorded in the region (°F)	See Table 2.3.1	This temperature value is used in the stress analysis of the site specific ancillaries
Extreme Maximum Ambient Temperature recorded in the region (°F)	See Table 2.3.1	This temperature value is used in the stress analysis of the site specific ancillaries
Site Elevation (feet above mean sea level)	3,520 (min) to 3,540 (max)	
Design Basis Earthquake (DBE) ZPAs in the two horizontal (X and Y) and vertical (Z) directions	See Table 4.3.3	
Design Basis Missiles and their incident velocity	See Table 2.7.2	Data is bounding for the Contiguous United States

TABLE 2.7.2; TORNADO GENERATED MISSILES		
Missile Description	**Mass (kg)**	**Velocity (mph)**
Automobile	1800	126
Rigid solid steel cylinder(8 in. diameter)	125	126
Solid sphere (1 in. diameter)	0.22	126

2.8 SAFETY-RELEVANT ENVIRONMENTAL DETERMINATIONS

The geotechnical information on the proposed HI-STORE CIS Facility presented in this chapter may be summarized in the following points:

- The facility will be located in one of the most sparsely populated areas in the continental United States. The nearest population centers are the cities of Carlsbad (32 miles away) and Hobbs (34 miles away).
- The topography of the land is relatively flat lending to effective intrusion detection by camera surveillance.
- The water table is sufficiently below the bottom of the subterranean HI-STORM UMAX system to preclude the possibility of any ground water intrusion in the storage cavity spaces.
- The land is fallow with limited vegetation to support cattle herds.
- The annual rainfall is meager requiring a modest water drainage infrastructure.
- The tornadic activity in the region is infrequent. The strength of the tornadoes is bounded by the national meteorological tornadic data which has been used to define the Design Basis Missiles for both the HI-STORM FW system and the HI-STORM UMAX system. Therefore, the storage system's ability to withstand the site specific tornados is axiomatically satisfied.
- There are no active volcanoes in the area.
- The area has a stable tectonic plate profile. As a result, the 10,000 year-return earthquake for the site is quite modest and well below the range for which HI-STORM UMAX as licensed in Docket 72-1040.
- There are no chemical plants in the area that would spew aggressive species into the environment. As a result, the ambient air is non-aggressive and a long service life of the stored stainless steel canisters can be predicted with confidence.
- There is no air force base or a major civilian airport in the vicinity of the site and the area is ostensibly not used for any aerial training exercises by the US military.
- The local area has a well-developed rail road infrastructure. The length of additional rail spur required for the site in less than 10 miles.
- By agreement with the applicable third parties, the oil drilling and phosphate extraction activities have been proscribed at and around the site.

The above considerations lead to the conclusion that the proposed Site is suitable for its intended purpose.

2.9 REGULATORY COMPLIANCE

Pursuant to the guidance provided in NUREG-1567, the foregoing material in this Chapter provides:

i. A complete description of the Geography and Demography of the Site as mandated by 10 CFR 72.24, 72.90, 72.96, 72.98, and 72.100;

ii. A complete identification and description of key characteristics of Nearby Facilities as mandated by 10 CFR 72.24, 72.40, 72.90, 72.94, 72.96, 72.98, 72.100, and 72.122;

iii. A complete description of the Meteorology and Surface Hydrology of the Site as mandated by 10 CFR 72.24, 72.40, 72.90, 72.92, 72.98, and 72.122;

iv. A complete description of the Subsurface Hydrology of the Site as mandated by 10 CFR 72.24, 72.98, and 72.122;

v. A complete description of the Geology and Seismology of the Site as mandated by 10 CFR 72.24, 72.40, 72.90, 72.92, 72.98, 72.102, and 72.122;

Therefore, it can be concluded that this SAR provides adequate description and safety assessment of the site which this ISFSI Facility is to be located, in accordance with 10 CFR 72.24(a). Additionally, it can be concluded that the proposed site complies with the criteria of 10 CFR 72 Subpart E, as required by 10 CFR 72.40(a)(2).

CHAPTER 3: OPERATIONS AT THE HI-STORE CIS FACILITY*

3.0 INTRODUCTION

This chapter describes the activities and operations antecedent to safely emplacing a loaded canister in the HI-STORM UMAX VVM at the HI-STORE CIS facility. Chapter 9 of the HI-STORM UMAX FSAR [1.0.6] and the HI-STORM FW FSAR [1.3.7] describe the operations carried out at a nuclear plant to implement on-site dry storage. While fuel loading operations are not a part of the activities at the HI-STORE CIS facility, an informational description is provided herein for reference. As the narrative in this chapter explains, the systems and operations required to effectuate transfer of canisters to the HI-STORM UMAX at HI-STORE meet the intent of 10CFR72.122 in full measure.

In particular, it is shown that the loading operations are characterized by a number of defense-in-depth measures intended to preclude a handling accident or ALARA transgression. For example:

- All lifting and handling devices comply with ANSI 14.6 [1.2.4] with the added requirement that the weakening effect of temperature on the strength of the lifting device is included.
- The standard lifting and handling devices, such as the Vertical Cask Transporter (VCT) comply with the added structural margin requirements set down in Chapter 4 of this SAR.
- The VCT, a key piece of equipment in heavy load handling evolutions, is equipped with a redundant drop protection features.
- The kinematic stability of the loaded equipment for every stability-vulnerable handling evolution under the site's Design Basis Earthquake (DBE) has been established by appropriate analysis.
- All lifting and handling devices are designed to maintain the CG of the lifted SSC aligned with the lift point at all times thus precluding an unstable lift.
- Custom engineered shielding accessories are utilized to meet ALARA goals.
- The gantry crane employed at the facility is designed to be single failure proof in compliance with ASME NOG-1 [3.0.1].
- The HI-STORE CIS facility is a "start clean, stay clean" facility. This means the arriving hardware from the sender plant site has assayed and declared the package to be free of any external contamination.
- The HI-STORE facility is a zero effluent site; no liquid or gaseous effluents are a part of any operation at the facility.

* All references are in placed within square brackets in this report and are compiled in Chapter 19 in this report.

- Even though not required to maintain stability during the site's DBE, the HI-TRAC CS transfer cask is secured by anchor bolts during all operations involving transfer of the loaded canister.

The information presented in this chapter along with the technical basis of the system design described in the canister's FSAR in its host 10CFR72 docket will be used to develop detailed operating procedures. In preparing the site-specific procedures, the conditions of the license and technical specifications, equipment-specific operating instructions, as well as the information in this chapter will be utilized to ensure that the short-term operations shall be carried out with utmost safety and ALARA.

The following generic criteria shall be used to determine whether the site-specific operating procedures developed pursuant to the guidance in this chapter are acceptable for use:

- All heavy load handling instructions are in keeping with the guidance in industry standards and Holtec's Rigging Manual.
- The procedures are in conformance with this SAR and its CoC.
- The procedures are in conformance with the canister's native FSAR (HI-STORM FW System FSAR for MPC-89 and MPC-37) [1.3.7].
- The operational steps are ALARA.
- The procedures contain provisions for documenting successful execution of all safety significant steps for archival reference.
- Procedures contain provisions for classroom and hands-on training and for a Holtec-approved personnel qualification process to ensure that all operations personnel are adequately trained.
- The procedures are sufficiently detailed and articulated to enable craft labor to execute them in literal compliance with their content.

Written procedures are required to be developed or modified to account for such items as handling and storage of systems, structures and components (SSCs) identified as important-to-safety, heavy load handling, specialized instrument calibration, special nuclear material accountability, fuel handling procedures, training, equipment, and process qualifications. The HI-STORE CIS facility management organization shall implement controls to ensure that all critical set points (e.g., Lift Weights) do not exceed the design limit of the specific equipment.

Control of the operation shall be performed in accordance with Holtec's Quality Assurance (QA) program to ensure critical steps are not overlooked and the canister has been confirmed to meet all requirements of the license before being released for on-site storage under 10CFR72.

The organization of the material and contents in this chapter follows the guidelines of NUREG-1567 [1.0.3].

3.1 DESCRIPTION OF OPERATIONS

Operations related to the loading and closure of the canisters of spent fuel to be stored at HI-STORE are performed at the originating nuclear power plant. Spent fuel operations at the originating power plant are performed in accordance with the originating plant Owner's 10CFR50 license, any 10CFR72 site-specific and generic licenses, as well as the Technical Specification of the storage system. Transport of the spent fuel from the plant to HI-STORE is performed in accordance with the requirements of 10CFR71 [1.3.2] and 49CFR171, 172, 173, 174, and 177 [3.1.2, 3.1.3, 10.3.1, 3.1.4, 3.1.5]. The HI-STORE facility will be designed to receive fuel from any licensed canister-based transportation cask. Storage of the spent fuel at HI-STORE is subject to the requirements of the HI-STORE CIS facility license issued pursuant to the regulations of 10CFR72. Compliance with 10CFR72 regulations [1.0.5] begins when the transportation cask enters the Cask Transfer Building (CTB).

The operations that are performed at HI-STORE include the following:

- Receipt and inspection of incoming transportation casks with canisters containing spent nuclear fuel.
- Transfer of canisters from transportation cask to the HI-TRAC CS transfer cask in the Canister Transfer Facility (CTF).
- Transfer of the HI-TRAC CS to the HI-STORM UMAX at the subterranean ISFSI.
- Surveillance of HI-STORM UMAX system.
- Security of HI-STORE.
- Health Physics at HI-STORE.
- Maintenance at HI-STORE.
- Removal of canisters from HI-STORE.
- Inventory documentation management.

Principal operations at the HI-STORE CIS facility involve activities pertaining to handling, transfer and placement of canisters in the facility's VVMs. Future removal of canisters for off-site shipment will involve the reverse of the loading operations. During storage at the HI-STORE facility, several supporting activities are required including monitoring of the storage systems and periodic maintenance of onsite equipment. Holtec International will implement detailed procedures for operating, inspecting, and testing the HI-STORE CIS facility SSCs in accordance with configuration–controlled written procedures similar to the ones employed at its existing user's ISFSIs. These procedures will ensure that the spent fuel handling and storage operations are in accordance with the HI-STORE SAR and the Company's Nuclear Safety and QA programs.

The following description provides an overview of the operational process for the spent fuel storage facility systems. Detailed step-by-step operations are described in Chapter 10.

3.1.1 Operations at Originating Nuclear Power Plant

The spent fuel operations at the originating nuclear power plant and the transport of the loaded canisters to the HI-STORE facility are not a part of HI-STORE operations. The description provided in this subsection is for information only; for a detailed description the reader should consult the canister's host FSAR such as HI-STORM UMAX FSAR [1.0.6].

Typically, an empty canister is placed inside a transfer cask. The canister and transfer cask are placed into the spent fuel pool where the canister is loaded with spent fuel. The canister exterior is prevented from direct contact with potentially contaminated spent fuel pool water by means of a slightly-pressurized clean water annulus with an inflatable top seal. Once the fuel is loaded, the canister lid is placed on the canister and the transfer cask is removed from the spent fuel pool. The canister lid is seal welded to the canister and the canister is drained and dried. The canister is then backfilled with inert helium gas and the drain and fill ports are welded closed and leak tested. The closure ring is installed and seal welded, thereby sealing the canister. The outer surfaces of the transfer cask and the accessible areas of the canister are then checked for surface contamination and decontaminated, if necessary.

Most sealed canisters are placed in dry storage at the nuclear power plant.

At the time of transport, the sealed canister is recovered from storage into the transfer cask and placed in a transportation cask. The transportation cask, containing the loaded canister, is sealed using a bolted top closure lid. The transportation cask annulus is evacuated and backfilled with helium. The closure lid seals are leak tested and the transportation cask is placed horizontally on a transport frame secured to a transport vehicle. The transportation cask is fitted with impact limiters, tie-downs and a personnel barrier to protect personnel from coming in direct contact with the cask body. The transportation cask is then shipped to HI-STORE.

3.1.2 Operations Between the Originating Nuclear Power Plant and HI-STORE

The HI-STORE facility is designed to receive spent fuel waste packages shipped by rail car. Prior to shipment, the originating nuclear power plant must verify that cask storage document packages are included with the transportation cask. These document packages should contain information such as the cask's CCRs, any 10CFR72.48 documentation, aging management records and documentation of the fuel contents of the cask. These document packages will be checked once again when the cask arrives at the HI-STORE site. During transportation, the transportation cask provides a part 71-compliant containment for the canister that is qualified to withstand all applicable licensing basis accidents (10CFR71.73). The package (transportation cask and impact limiters) is licensed in accordance with the requirements of 10CFR71, "Packaging and Transportation of Radioactive Material", and complies with the requirements of 49CFR171, "General Information, Regulations, and Definitions", 49CFR172, "Hazardous Materials Tables and Hazardous Materials Communications Regulations", 49CFR173, "Shippers – General Requirements for Shipments and Packages", 49CFR174, "Carriage by Rail", and 49CFR177, "Carriage by Public Highway" [3.1.2, 3.1.3, 10.3.1, 3.1.4, 3.1.5].

3.1.3 Operations Between the Railroad Mainline and HI-STORE

To reach the HI-STORE site, the transportation rail car is transferred to a newly constructed rail spur located along State Highway 243, where the transportation casks remain on the rail car and are transported approximately 5 miles east to the HI-STORE CIS facility.

3.1.4 Operations at HI-STORE

3.1.4.1 Receipt and Inspection of Incoming Transportation Cask and Canister

This section provides a summary overview of the HI-STORE CIS facility canister handling operations. A more detailed description is provided in Chapter 10. During spent fuel transportation, the sealed canister is contained within the transportation cask, which is mounted horizontally on a rail car or heavy haul trailer. Impact limiters are mounted on both ends of the transportation cask and a personnel barrier covers the transportation cask between the impact limiters. A tie-down secures the cask to the transport vehicle. Figure 3.1.1 pictorially illustrates the cask handling operations.

When the transportation cask arrives at the HI-STORE CIS facility, the transportation cask is visually inspected for any outward indications of damage or degradation prior to entry into the Protected Area (PA). Additionally, a review of the transportation documentation package, which includes verification that a pre-shipment inspection was performed and acceptable, is mandatory prior to receiving a transportation cask into the security vehicle trap.

After initial receipt approval, the cask is moved into the security vehicle trap for physical inspection by security personnel to ensure no unauthorized devices or materials enter the PA. When security clearance is complete, the shipment proceeds into the PA and into the CTB (Figure 3.1.2) where the personnel barrier and tie-down are removed. The transportation cask, in accordance with the Part 71 requirements, is surveyed for dose rates and contamination levels.

The dose rate from the cask on arrival at the HI-STORE CIS facility must be in reasonable accord with the measured dose rate at the originating plant. An excessive discrepancy would warrant a root cause evaluation under Holtec's quality program and appropriate notification to the USNRC.

3.1.4.2 Transfer of Canister from Transportation Cask to HI-TRAC CS

The steps for transferring the sealed canister from the transportation cask to the HI-TRAC CS all occur within the CTB. Using the CTB crane, the transportation cask is lifted from the rail car horizontally and placed onto a tilt frame suitable for the transportation cask being handled. The tilt frame fully supports the cask in the horizontal orientation and allows for cask tilting between the vertical and horizontal orientations. With the transportation cask in the horizontal orientation (fully supported by the tilt frame), the impact limiters are removed and placed aside. The transportation cask closure lid penetration cover is removed and the annulus gas is sampled to confirm the continued effectiveness of the canister's confinement barrier. Following successful testing of the annulus gas, a canister leakage test is performed. The transportation cask is then tilted to vertical, lifted from the tilting frame and placed in the Canister Transfer Facility (CTF). An alignment plate is used to concentrically align the HI-TRAC CS to the transportation cask. The alignment plate provides shielding to personnel performing the canister transfer and allows access for examination of the canister exterior shell surface.

After the cask is installed in the CTF, the closure lid is removed and a cask seal surface protector is installed on the transportation cask's closure lid seal surface to protect it from damage. If necessary, any canister shipping spacers are removed. With the canister lid exposed, a contamination survey is taken on the accessible areas of the canister lid to verify that the canister

is free of removable contamination. The MPC lifting attachment is then connected to the lid. Temporary shielding may be positioned as required to maintain worker dose ALARA.

The HI-TRAC CS is then placed on the CTF alignment plate with its bottom doors open. The CTF anchor studs are secured to the HI-TRAC CS bottom flange to assure the cask's seismic stability during the canister transfer process. The MPC lifting device extension is attached to the overhead crane, lowered through the HI-TRAC CS body using the CTB crane, and connected to the MPC lift attachment. The MPC is lifted into the HI-TRAC CS and the HI-TRAC CS shield gates are closed. With the canister is resting on the shield gates, the MPC lifting device extension is disconnected from the MPC lift attachment. The loaded HI-TRAC CS is then lifted and placed at a location on the floor that is readily accessible to the VCT. It is at this time that the HI-TRAC CS will be surveyed for dose measurements.

3.1.4.3 Placement of the Canisters into the Vertical Ventilated Modules (VVMs)

The HI-TRAC CS loading is now complete and ready for transport to the designated HI-STORM UMAX VVM on the storage pad. In preparation for receiving the loaded canister, the designated VVM's CEC lid is removed and the Divider Shell is installed in the CEC. The VCT lifts the HI-TRAC CS and moves it out of the CTB. The cask is then moved to the appropriate HI-STORM UMAX location by the VCT. The HI-TRAC CS is positioned and lowered onto the ISFSI pad over the CEC to be loaded. Once it is lowered on the pad, the HI-TRAC CS is secured to the CEC in similar manner as at the CTF. The VCT releases from the HI-TRAC CS lifting trunnions and raises the top lift beam. The MPC lifting device extension connects the MPC lift attachment to the VCT through the VCT's top lift beam. The VCT's top lift beam is raised to tension the canister lift slings and raise the canister slightly. The HI-TRAC CS shield gates are opened and the VCTs top lift beam is lowered to lower the canister into the CEC. This continues until the canister is fully seated in the CEC. The MPC lift device extension releases from the VCT's top lift beam. The VCT reconnects to the HI-TRAC CS lifting trunnions. The HI-TRAC CS shield gates are closed and the securing anchor studs and nuts are removed. HI-TRAC CS is lifted and removed from the HI-STORM UMAX location. The MPC lift attachment is unbolted from the canister lid and removed from the CEC. If necessary, the CEC-to-lid seals are installed and the HI-STORM UMAX Closure Lid is installed. The lid rigging is removed and the CEC lid vent screen is installed. Once the rigging is removed and the closure lid is installed, the VVM will be surveyed for dose measurements.

3.1.4.4 Surveillance of the HI-STORM UMAX Storage Systems

While in storage, the proper monitoring of the HI-STORM UMAX storage systems is subject to surveillance guided by written procedures. The temperature of the exiting air from the VVMs provides a telltale indication of compliance with the Technical Specifications. In addition, the cask air vent covers are visually inspected for blockages. An overall site observation surveillance is also performed on a periodic basis to monitor for adverse conditions such as the accumulation of site debris around the air vents, tearing of the vent screens and the like.

Dose rates associated with individual storage systems are measured. This is to ensure adequate shielding of the canister so that radiation exposure to the general public is minimized and occupational doses to personnel working in the vicinity of the storage casks are maintained ALARA. Radiation doses emitted from the storage casks are measured by thermoluminescent

dosimeters (TLDs) located at the protected area (PA) and owner controlled area (OCA) boundaries to ensure doses are within 10CFR20.1301 and 10CFR72.104 or 40CFR191 limits.

3.1.4.5 Security Operations

Security personnel coordinate security related functions that include performing continual surveillance for intruders, responding to intrusion alarms, processing visitors and workers to HI-STORE, searching packages and vehicles, issuing badges to workers, coordinating with local law enforcement agencies, and coordination with appropriate site and off-site emergency response personnel. Security personnel are also responsible for identifying and assessing off-normal and emergency events during off-shift hours of HI-STORE operation. Details for the security personnel are discussed in the HI-STORE Physical Security Plan [3.1.1].

3.1.4.6 Health Physics Operations

The health physics (HP) personnel are responsible for measuring, monitoring and recording all radiological aspects of the HI-STORE facility. These include: taking radiation dose and contamination surveys on incoming spent fuel shipments, monitoring individual radiological exposure, issuing, monitoring and maintaining personnel dosimetry, evaluating off-site radiological conditions, placarding and establishing radiological working conditions, reporting on radiological conditions to appropriate authorities and maintenance of radiological survey equipment. In order to uphold the HI-STORE philosophy of "Start Clean/Stay Clean" HP personnel ensure that contamination levels on the canisters of incoming shipments meet site requirements. Canisters exceeding the limits will be returned to the originating power plant for dispositioning.

During the transfer process, HP personnel monitor doses to ensure that workers are not exposed to unnecessary radiation. In the event high dose rates are detected, temporary shielding, in the form of lead blankets, neutron shielding, portable shield walls, etc., are used to maintain ALARA. HP Personnel perform dose rate surveillances of the loaded storage cask to ensure requirements are met.

In addition to surveillance activities, the HP department monitors onsite and offsite radiation levels to ensure worker and offsite doses are in accordance with regulatory requirements. The HP department is also responsible for calibrating radiation protection instrumentation.

3.1.4.7 Maintenance Operations

Because of their passive nature, the HI-STORM UMAX storage system requires little maintenance over the lifetime of HI-STORE. Typical maintenance tasks may involve occasional replacement and recalibration of temperature monitoring instrumentation, repair of coatings, repair of damaged screens, and general removal of dirt and debris.

Periodic maintenance is required on the overhead bridge crane, service cranes, transfer equipment, HI-TRAC CS and transportation casks. Maintenance of SSCs, which are classified as important-to-safety, ensure that they are safe and reliable throughout the life of HI-STORE per 10CFR72.122(f). Work on these items will only occur when the equipment being maintained is in the unloaded condition.

Maintenance may also be required on the following components: the heavy haul tractor/trailer (if used), rail car and locomotive (if used), cask transporter, security systems, temperature and

radiation monitoring systems, diesel generator, electrical systems, fire protection systems, building HVAC and site infrastructure. The CTB and Storage Building provide the facility to perform maintenance activities. Vehicles may be moved off-site to specialized facilities that are better suited to perform such activities.

Full details of the maintenance requirements are given in Chapter 10. Additional information on the Aging Management of HI-STORE SSCs can be found in Chapter 18.

3.1.4.8 Transfer of Canisters from HI-STORE Offsite

The HI-STORE CIS facility is an interim storage facility. At some point in the future, canisters may be required to be moved offsite. When such a day arrives, a 10CFR71 licensed transportation cask will transport the canisters offsite to another facility. Transfer operations will utilize the CTB to transfer the canisters from HI-TRAC CS to the transportation casks. Once loaded in a transportation cask, the spent fuel canister will be shipped to the designated facility. To accomplish this, the steps for installing the canister in the VVM are basically reversed, resulting in a loaded transportation cask ready for transport.

3.1.4.9 Sequence of Operations

Diagrams illustrating the sequence of operations for canister receipt, transfer, and placement into storage is shown in Figure 3.1.1 for the HI-STORM UMAX storage system.

The number of personnel and the time required for the various operations are provided in Table 11.3.1. This table is used to develop the occupational exposures discussed in Chapter 11.

3.1.5 Identification of Subjects for Safety Analysis

3.1.5.1 Criticality Prevention

Only canisters that have been determined to have no credible leakage shall be stored at the HI-STORE CIS facility. The determination that the canister's confinement boundary is intact and effective to prevent intrusion of any fluids including water is performed at both the plant of origin and upon its arrival at HI-STORE. Thus, while the canister is qualified to remain subcritical even in the presence of water by virtue of its fixed basket geometry and fixed neutron absorbers installed in the canister's Fuel Basket, the guaranteed absence of water inside the canister at the HI-STORE CIS facility makes any loss of criticality safety non-credible. Therefore, no additional criticality prevention measures are needed.

3.1.5.2 Chemical Safety

The HI-STORE CIS facility does not use any chemicals (even water) in its canister handling and storage operations. Therefore, there are no chemical hazards associated with the operation of HI-STORE CIS facility.

3.1.5.3 Operation Shutdown Modes

During storage, there are no operational shutdown modes associated with the HI-STORM UMAX Storage System since the system is passive and relies on natural air circulation for cooling. During canister transfer, the transfer process may be shut down at the end of the day, resuming again on a following day. A discontinuance in the transfer operation is permitted only if:

- All SSCs are in a mechanically secured state,
- No nuclear components are in the lifted condition
- The ventilation flow of air around the canister is uninhibited, and
- The radiation dose around the cask and canister is ALARA.

In summary, all operational shutdown modes at HI-STORE are safe shutdown modes due to the design features of the facility and operational controls imposed through operating procedures.

3.1.5.4 Instrumentation

Due to the totally passive nature of the storage casks, there is no need for any instrumentation to perform safety functions. Temperature monitors are utilized as a means to monitor the cask temperature during storage. Area radiation monitors are used to measure radiation levels in the CTB during canister transfer operations. Portable radiation monitors are used to measure radiation levels during the canister transfer process. HI-STORE operators are equipped with personnel dosimeters whenever they are in the PA. The radiation dose will be monitored at the perimeters of the PA and OCA. Pursuant to the criteria in NUREG/CR-6407 [1.2.2], the temperature and radiation monitors are classified as Not-Important-to-Safety.

3.1.5.5 Maintenance Techniques

Maintenance operations on the equipment and systems don't involve any special techniques that would require a safety analysis.

Preventative maintenance is performed on a regular basis on the overhead transfer crane, canister lifting equipment, cask transporter, heavy haul tractor/trailers, radiation detection and monitoring equipment, cask temperature monitoring equipment, security equipment, fire detection and suppression equipment, etc. Maintenance is performed in accordance with 10CFR72.122(f), ANSI N14.6 [1.2.4], and manufacturer's requirements.



a. Transportation cask is received at the Cask Transfer Building



b. Transportation cask is removed from the transport vehicle



c. Transportation cask is placed in the tilt frame



d. Impact limiters are removed from the transportation cask

Figure 3.1.1: Cask Handling Summary Illustrations



e. Canister is tested for integrity



f. Transportation cask is tilted to vertical



g. Transportation cask is placed in the CTF



h. Closure lid is removed and MPC Lift Attachment is installed

Figure 3.1.1: Cask Handling Summary Illustrations (Continued)



i. HI-TRAC CS is placed over CTF



j. MPC Lifting Device Extension is attached to MPC Lift Attachment



k. Canister is raised into HI-TRAC CS



l. HI-TRAC CS is removed from over the CTF

Figure 3.1.1: Cask Handling Summary Illustrations (Continued)



m. HI-TRAC CS is placed for transfer to VCT



n. VCT engages HI-TRAC CS



o. HI-TRAC CS is brought to the CEC



p. MPC lifting attachments are connected to the VCT

Figure 3.1.1: Cask Handling Summary Illustrations (Continued)



q. Canister lowered into the CEC



r. Canister fully lowered into the CEC



s. MPC lifting extension disconnected and raised



t. HI-TRAC CS Removed from the CEC

Figure 3.1.1: Cask Handling Summary Illustrations (Continued)



u. MPC lifting attachment removed



v. HI-STORM UMAX Lid installed

Figure 3.1.1: Cask Handling Summary Illustrations (Continued)

Figure 3.1.2: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

3.2 SPENT FUEL AND HIGH-LEVEL WASTE HANDLING SYSTEMS

3.2.1 Spent Fuel Canister Receipt, Handling, and Transfer

An operational description of the systems used for the receipt and transfer of spent fuel canisters is provided in the following paragraphs. Special features of these systems to ensure safe handling of the spent fuel canisters are also described.

3.2.1.1 Spent Fuel Canister Receipt

3.2.1.1.1 Functional Description

The transportation casks and impact limiters comprise the system in which the spent nuclear fuel canisters are contained when they arrive at HI-STORE. The transportation cask system protects the enclosed spent fuel canister from physical damage, provides shielding, and allows sufficient cooling of the canister while in transit to HI-STORE.

3.2.1.1.2 Safety Features

Safety features of the transport system include the impact limiters, which help protect the spent fuel inside the transportation cask during transportation. Furthermore, the design features of the transportation cask, which provides gamma and neutron shielding, conductive and radiant cooling, criticality control, and structural strength to protect the spent fuel canister. A tamper-proof device on the cask provides indication of an unauthorized attempt to obtain access to the cask. These safety features are fully described in the HI-STAR transportation cask SAR [1.3.6].

3.2.1.2 Spent Fuel Canister Handling

3.2.1.2.1 Functional Description

The cask handling crane performs handling functions inside the CTB for the transportation cask and the HI-TRAC CS. The MPC lift attachment and MPC lifting device extension connect to the overhead crane for MPC lifting and lowering in the CTB.

Cask handling components include the transportation cask and transfer cask, transport cask horizontal lift beam, lift yokes, tilt frame, VCT, cask handling crane and HI-TRAC CS lift links. The HI-TRAC CS lift links connect the VCT to the HI-TRAC CS lifting trunnions.

The canister handling components consist of the MPC lift attachment and MPC lifting device extension.

3.2.1.2.2 Safety Features

Safety features of the cask handling crane include *single-failure-proof* designs for preventing uncontrolled lowering of the load upon failure of any single component, limit switches for prevention of hook travel beyond safe operating positions, and provisions for lowering a load in the event of an overload trip. The crane is classified as ASME NOG-1 Type 1 [3.0.1]. A Type 1 crane is defined as a crane that is designed and constructed to remain in place and support a critical load during and after a seismic event and has single-failure proof features such that any credible failure of a single component will not result in the loss of capability to stop and/or hold the critical load. Design requirements for the crane include testing, inspection, and maintenance activities in accordance with 10CFR72.122(f) which, are also performed per the QA Program

described in Chapter 12. Strict adherence to the design, testing, inspection, and maintenance criteria as noted above ensure adequate safety margins are provided to prevent damage to the transportation cask, canister, or storage cask during normal, off-normal, and accident conditions. Discussion on design criteria and the subsequent evaluations for these SSCs are found in Chapters 4 and 5, respectively. The crane design include limit switches for prevention of gantry, trolley, and hook travel beyond safe operating positions, limits on gantry, trolley, and hook travel speeds, and provisions for lowering a load in the event of an overload trip. Periodic inspection and testing will be performed to keep the cranes certified to ASME NOG-1 [3.0.1].

Safety features of the HI-TRAC CS handling components include single-failure-proof lift capacity or equivalent safety factor as described in this SAR.

The loaded HI-TRAC CS is restrained during all aspects of canister handling either by the VCT and/or the anchor studs or by the wide base of the HI-TRAC CS during switching from the cask handling crane to the VCT. Evaluation shows that the HI-TRAC CS cannot topple over during an earthquake.

Safety features associated with the VCT include redundant drop protection systems designed to withstand drops that could result from a failure associated with the transporter lift components. The transporter is designed with hydraulic counter-balance valves and anti-drop mechanical locking mechanisms which automatically engage on the loss of hydraulic pressure. Markings on the lift boom and an indictor on the operating console give indication of the lifted height. HI-TRAC CS lifting attachments are designed and tested in accordance with ANSI N14.6 [1.2.4].

The safety features of the canister handling components, slings and MPC lifting attachments, are their redundancy and the required enhanced stress safety margins as described in the HI-STORM UMAX FSAR [1.0.6].

3.2.1.3 Spent Fuel Canister Transfer

3.2.1.3.1 Functional Description

The HI-TRAC CS is used for transfer of the spent fuel canister between the transportation cask and the CEC. The HI-TRAC CS protects the spent fuel canister from physical damage and provides radiation shielding to personnel.

3.2.1.3.2 Safety Features

The HI-TRAC CS provides radiation shielding when carrying a canister loaded with spent fuel. The HI-TRAC CS lifting trunnions are designed to the single-failure proof requirements of NUREG-0612 [1.2.7] so that a load drop event involving the HI-TRAC CS is non-credible.

As described in Subsection 1.2.4, the HI-TRAC CS consists of a radially-connected pair of concentric steel shells filled with high density concrete. Two lifting trunnions and two rotation trunnions are provided for HI-TRAC CS handling. The HI-TRAC CS has a pair of thick movable shield gates at the bottom to allow raising the canister into the transfer cask, lowering of the canister into the storage or transportation cask, or to support the canister weight and provide shielding while in the HI-TRAC CS. The shield gates slide in steel guide rails along each side of the HI-TRAC CS. Steel pins or bolts are used to prevent inadvertent opening of the doors.

The HI-TRAC CS features a top steel ring that prevents the canister from being lifted above the top of the cask thus insuring that the canister remains within the radiation protected envelope of

the transfer cask. A lifting yoke provided with the HI-TRAC CS is used to interface with the cask handling crane. The VCT features lift links which connect the HI-TRAC CS trunnions to the VCT top beam for handling with the VCT.

3.2.2 Spent Fuel Canister Storage

Spent fuel storage consists of the HI-STORM UMAX storage system, which includes spent fuel canisters placed in the steel Canister Enclosure Cavity (CEC) below ground in the HI-STORM UMAX ISFSI. The storage system is entirely passive by design and is completely autonomous (i.e., it requires no support systems for its operation).

Surveillance of the HI-STORM VVM assembly to ensure its continued effectiveness involves the following principal activities:

1. Check for intrusion of foreign objects that may impair the system's thermal performance during normal operations and in the wake of an extreme environmental phenomenon.
2. Check for corrosion damage to the steel parts, namely the CECs (oldest or most vulnerable VVM shall be inspected).
3. Check for structural damage to the ISFSI after an earthquake.
4. Perform the heat removal operability surveillance as specified in the Technical Specifications.
5. Perform ISFSI Security Operations in accordance with the site's security plan.

Routine maintenance on the HI-STORM UMAX System will typically be limited to cleaning and touch-up painting of the exposed steel surfaces, repair, and replacement of damaged vent screens, and removal of vent blockages (e.g., leaves, debris), if any. The heat removal system operability surveillance should be performed after any event that may have an impact on the safe functioning of the HI-STORM UMAX system. These include, but are not limited to, wind storms, snow storms, fire inside the ISFSI, seismic activity, and/or observed animal, bird, or insect infestations. The responses to these conditions involve first assessing the dose impact to perform the corrective action (inspect the HI-STORM VVM cavity, clear the debris, check for any structural damage of the ISFSI pad, and/or replace damaged vent screens); perform the corrective action; and verify that the system is operable (check ventilation flow paths and radiation blockage capability). In the unlikely event of significant damage to the ISFSI, possibly from a Beyond-the-Design Basis earthquake, the situation may warrant removal and visual inspection of the canister, and repair or replacement of the damaged ISFSI areas.

The storage system performs its functions under normal conditions as discussed in Chapter 10 and off-normal and accident level conditions as discussed in Chapter 15. Limits of operation associated with various normal and off-normal conditions are contained in Chapter 16. Surveillance requirements are also contained in Chapter 16.

3.2.2.1 Safety Features

Safety features include a passive dry storage system design and administrative controls. The canister is enclosed in the cavity of the HI-STORM UMAX storage system, which protects the canister from severe natural phenomena (such as tornado-driven missiles), provides required shielding of the canister, and flow paths for natural convection cooling. Because of its

underground disposition, the canister stored inside HI-STORM UMAX cannot tip-over. Safety features are discussed in greater detail in the HI-STORM UMAX FSAR [1.0.6].

3.3 OTHER OPERATING SYSTEMS

The storage casks are passive and require no other operating systems for safe storage of the spent fuel once they are placed into storage. The HI-STORE operating systems are described in this chapter and Chapter 10.

3.4 OPERATION SUPPORT SYSTEMS

3.4.1 Instrumentation and Control Systems

Regulation 10CFR72.122(i) requires that instrumentation and control systems be provided to monitor systems that are classified as Important to Safety. The operation of HI-STORE is passive and self-contained and therefore does not require control systems to ensure the safe operation of the system. However, temperatures of the air exiting the VVMs may be monitored to provide a means for assessing thermal performance of the storage casks. The temperature monitors are equipped with data recorders and alarms located in the Security Building. The temperature monitors are not required for safety and therefore are not subjected to important to safety criteria.

Radiation monitoring is provided to ensure doses remain ALARA and is discussed in Chapter 11. Radiation monitoring is not required to support systems that are classified as Important to Safety.

In the event of an earthquake, Holtec will contact the National Earthquake Information Center, Golden, CO to acquire seismic data for a post-earthquake performance evaluation.

No other instrumentation or control systems are necessary or are utilized. Therefore, the requirements of 10CFR72.122(i) are satisfied.

3.4.2 System and Component Spares

Spare temperature monitoring devices are maintained at the site. However, these devices are not required to maintain safe conditions at the HI-STORE facility. No other instrumentation spares are required.

3.5 CONTROL ROOM AND CONTROL AREA

Regulation 10 CFR72.122(j) requires the control room or control area to be designed to ensure that HI-STORE is safely operated, monitored, and controlled for off-normal or accident conditions. This requirement is not applicable to HI-STORE because the spent fuel storage system is a passive system and hence does not require a control room to ensure safe operation.

3.6 ANALYTICAL SAMPLING

No sampling is required for the safe operation of HI-STORE or to ensure that operations are within prescribed limits. Sampling of the gas inside the transportation cask is performed prior to venting and opening the cask in the CTB. Evaluation of the gas sample determines if the gas can be released to the atmosphere or if it must be filtered and the appropriate radiological protection needed when removing the transportation cask closure. Since the sampling is not required for nuclear safety of the facility, it is not classified as Important-to-Safety.

3.7 POOL AND POOL FACILITY SYSTEMS

The HI-STORE facility does not need a pool for storage or transfer operations. Canisters are received, transferred and stored in the dry condition.

3.8 REGULATORY COMPLIANCE

The operational steps required to place a loaded canister into a HI-STORM UMAX VVM cavity have been described in this chapter. The steps to remove a canister from a loaded VVM, which are essentially reverse of the steps in the loading sequence, have also been provided. These loading steps are sufficiently detailed to lead to the conclusion that the guidelines of safety and ALARA set down in NUREG-1567 [1.0.3] are fully satisfied. In particular, it can be concluded that:

i. There are no radiation streaming paths from the canister during its transfer operation.

ii. The handling operations occur near grade level thus eliminating the need for ladders/platforms and improving the human factors aspects.

iii. There are no exterior freestanding structures in the canister transfer operations and thus there is no risk of uncontrolled load movement under a (hypothetical) extreme environmental event such as tornado or high winds.

iv. The ventilation paths to passively cool the canister using ambient air during the transfer operation is maintained at all times thus protecting the fuel cladding from overheating and eliminating any thermally guided time limit on the duration for implementing the transfer steps.

v. All heavy load handling is carried out by handling devices that are equipped with redundant load drop protection features.

vi. Each storage cavity is independently accessible. Installation or removal of any canister does not have to contend with other stored canisters.

vii. Because the canister insertion (and withdrawal) occurs in the vertical configuration with ample lateral clearances, there is no risk of scratching or gouging of the canister's external surface (Confinement Boundary). Thus the ASME Section III Class 1 prohibition against damage to the pressure retaining boundary is maintained.

It is thus concluded that the HI-STORM UMAX ISFSI is engineered to meet the safety and ALARA imperatives contemplated in 10CFR72 [1.0.5] in full measures.

CHAPTER 4: DESIGN CRITERIA FOR THE HI-STORE CIS SYSTEMS, STRUCTURES AND COMPONENTS*

4.0 INTRODUCTION

This chapter contains safety-relevant information on the HI-STORE CIS facility in the following topical areas:

a. Spent fuel or other high-level radioactive waste containers (canisters) authorized to be stored,

b. Classification of structures, systems and components (SSCs) according to their *importance –to-safety*, and

c. Design criteria and design bases for the HI-STORE CIS facility and associated SSCs during all operational modes, including normal and off-normal operations, Short Term Operations, accident conditions and extreme natural phenomena events.

Unlike the generic HI-STORM UMAX system, the Short-Term Operations at the HI-STORE facility do not involve any activity related to loading fuel into canisters: the canisters arrive at the HI-STORE CIS facility in a NRC-certified transport cask such as HI-STAR 190 (NRC docket # 71-9373). The Short Term Operations begin at the point the transport package is received at the site and end at the point the canister is placed in a HI-STORM VVM for interim storage.

As stated in Chapter 1, the HI-STORM UMAX system (NRC Docket # 72-1040) [1.0.6] is the sole storage system designated to be employed at the HI-STORE CIS facility. As the canisters certified for use in the HI-STORM UMAX system are qualified in the HI-STORM FW system (NRC Docket # 72-1032) [1.3.7], there is a direct nexus between the site specific safety analyses for HI-STORE CIS facility and the analyses that undergird the general certification in [1.0.6] and [1.3.7]. As documented in this chapter, the loadings and conditions for which the HI-STORM UMAX VVM and its canisters are certified in [1.0.6] substantially exceed their counterparts for the HI-STORE CIS facility. This safety analysis reports mandates that only those canisters that are authorized for storage in HI-STORM UMAX under its general certification can be stored at the HI-STORE CIS facility. Furthermore, even among the population of canisters authorized by the HI-STORM UMAX CoC, only those that meet the heat load limit of the transport cask can be transported to the site will be available for storage at the site. Because the transport cask has a much lower heat load capacity than the HI-STORM UMAX ventilated storage system, the limitation imposed by the transport cask winnows the number of canisters eligible for storage at the HI-STORE CIS facility significantly. It is evident that those canisters that meet the heat load limitation of the transport cask, because of the greater innate heat rejection capacity of ventilated systems, will be subject to a less severe thermal state at the HI-STORE CIS facility than that permitted under ISG-11 Rev. 3 [4.0.1] under long term storage.

The HI-STORE facility must be qualified to withstand all credible environmental or operation-related loadings without exceeding its applicable safety limits. To make this safety

* All references are placed within square brackets in this report and are compiled in Chapter 19 of this report.

determination, the credible loadings under all normal, off-normal and faulted states are compared with those that have been qualified in the HI-STORM UMAX FSAR [1.0.6]. Any load that is found to exceed the pre-certified limit in the HI-STORM UMAX FSAR [1.0.6] is so identified in this chapter for further analysis.

As noted subsequently in this chapter, the site specific environmental and accident loads are fewer in number and less severe than those treated in the HI-STORM UMAX FSAR [1.0.6]. This statement applies to the Design Basis Earthquake (DBE) also where the 10,000-year return earthquake is shown to be bounded by the DBE for which the HI-STORM UMAX system is pre-certified. Much of the safety analysis material in this chapter pertains to confirming that each HI-STORE site specific loading is bounded by its counterpart treated in the HI-STORM UMAX FSAR.

Many of the Design Criteria pertaining to the loadings and components common to the HI-STORM UMAX and the HI-STORE CIS systems, such as the MPC and VVM, are incorporated by reference in this SAR, as appropriate, to the HI-STORM UMAX FSAR [1.0.6]. To facilitate convenient access to the referenced material, a list of HI-STORM UMAX FSAR sections germane to this chapter is provided in Table 4.0.1.

TABLE 4.0.1: HI-STORM UMAX FSAR MATERIAL INCORPORATED IN THIS FSAR BY REFERENCE			
Location in HI-STORE SAR	**Subject of the Reference**	**Location in HI-STORM UMAX FSAR [1.0.6]**	**Justification**
Subsection 4.1.1	Spent Fuel to be stored	Section 2.1, with exceptions as described in Subsection 4.1 of this SAR	MPCs to be stored at HI-STORE site are limited to those included in the HI-STORM UMAX FSAR [1.0.6]; exceptions for maximum heat loads and backfill pressure imposed by transport cask are made, but are bounded by HI-STORM UMAX FSAR requirements.
Subsection 4.3.1	MPCs to be stored		
Subsection 4.3.2	Design criteria for HI-STORM UMAX VVM and ISFSI	Section 2.2, with exceptions as described in Subsection 4.3.2.1 of this SAR	Design criteria for HI-STORM UMAX VVM and ISFSI are bounded by HI-STORM UMAX FSAR, except as noted.
Table 4.3.1	MPC Internal Design Pressure	Section 2.3.2.1	Due to the lower heat load limit of the transport cask, the associated internal MPC pressure shall always be less than the MPC design basis pressure in the HI-STORM UMAX FSAR [1.0.6]
Table 4.3.1	High Winds	Section 2.3.2.7	The wind conditions at the ELEA site are bounded by the HI-STORM UMAX FSAR Design Basis Wind.
Table 4.3.1	Design Basis Flood	Section 2.4.7	The Design Basis Flood used to qualify the VVM in the HI-STORM UMAX FSAR exceeds the most severe projection of flood at the ELEA site.

4.1 MATERIALS TO BE STORED

4.1.1 Spent Fuel Canisters

The SNF-bearing canisters that will be stored at the HI-STORE CIS facility are limited to those included in the HI-STORM UMAX FSAR [1.0.6]. No canister that is not included in the HI-STORM UMAX FSAR can be stored at the HI-STORE CIS Facility. Therefore all canisters (and the SNF specified as acceptable for storage in said canisters) to be stored at the facility are incorporated by reference herein, as follows:

- Authorized contents are incorporated by reference from Section 2.1 of the HI-STORM UMAX FSAR [1.0.6], with the following exceptions:
  i. Maximum permissible heat loads specified in Subsection 2.1.9 of the HI-STORM UMAX FSAR [1.0.6], are replaced by more restrictive heat load imposed by the transport cask heat load requirements;
  ii. The helium backfill pressure options of Tables 2.1.8 and 2.1.9 of the HI-STORM UMAX FSAR [1.0.6], which relate to the establishment of the permissible aggregrate heat load, are supplanted by the requirements of this chapter.

Canisters to be stored at the HI-STORE CIS Facility must meet the maximum heat loads shown in Tables 4.1.1 and 4.1.2 of this SAR, in accordance with the regional loading patterns shown in Figures 4.1.1 and 4.1.2 of this SAR (item i).

Requirements for the helium backfill of all canisters to be stored at the HI-STORE CIS are in Table 4.1.3 and 4.1.4 of this SAR (item ii). Although canisters will not be backfilled at site, received canisters will be verified to meet these helium backfill requirements as a condition of acceptance.

4.1.2 High Level Radioactive Waste

This SAR does not consider safety analysis of any canister that is not certified in the HI-STORM UMAX docket [1.0.6]. Accordingly, it does not at the present time include any canister containing non-fissile High Level Radioactive Waste at the HI-STORE CIS facility.

Table 4.1.1: Maximum Decay Heat Load for MPC-37 (PWR Fuel Assembly)

Pattern	Region (Note 1)	Maximum Decay Heat Load per Assembly (kW) (Note 2)	Total Heat Load for Each Pattern (kW)
1	1	0.38	31.82
	2	1.7	
	3	0.50	
2	1	0.42	32.02
	2	1.54	
	3	0.61	
3	1	0.61	32.09
	2	1.23	
	3	0.74	
4	1	0.74	32.06
	2	1.05	
	3	0.8	
5	1	0.8	32.04
	2	0.95	
	3	0.84	
6	1	0.95	31.43
	2	0.84	
	3	0.8	

Note 1: For basket region numbering scheme refer to Figure 4.1.1

Note 2: These maximum fuel storage location decay heat limits must account for decay heat from both the fuel assembly and non-fuel hardware.

Table 4.1.2: Maximum Decay Heat Load MPC-89 (BWR Fuel Assembly)

Pattern	Region (Note 1)	Maximum Decay Heat Load per Location (kW) (Note 2)	Total Heat Load for Each Pattern (kW)
1	1	0.15	32.15
	2	0.62	
	3	0.15	
2	1	0.18	32.02
	2	0.58	
	3	0.18	
3	1	0.27	32.03
	2	0.47	
	3	0.27	
4	1	0.32	32.08
	2	0.41	
	3	0.32	
5	1	0.35	31.95
	2	0.37	
	3	0.35	

Note 1: For basket region numbering scheme refer to Figure 4.1.2.

Note 2: These maximum fuel storage location decay heat limits must account for decay heat from both the fuel assembly and non-fuel hardware.

Table 4.1.3: MPC Backfill Pressure Requirements (Note 1)

MPC Type	Pressure Range
MPC-37	≥ 39.0 psig and ≤ 46.0 psig
MPC-89	≥ 39.0 psig and ≤ 47.5 psig

Note 1: Helium used for backfill of MPC shall have a purity of ≥99.995%. The pressure range is based on a reference temperature of 70°F.

Table 4.1.4: MPC Backfill Pressure Requirements for Sub-Design Basis Heat Load (Note 1)

MPC Type	Pressure Range (Note 2)
MPC-37	≥ 39.0 psig and ≤ 50.0 psig
MPC-89	≥ 39.0 psig and ≤ 50.0 psig

Note 1: Sub-Design Basis Heat Load is defined as 80% of the design basis heat load in every storage location defined in Tables 4.1.1 and 4.1.2 for MPC-37 and MPC-89 respectively.

Note 2: Helium used for backfill of MPC shall have a purity of >99.995%. The pressure range is based on a reference temperature of 70°F.



Legend

Region-Cell ID

Figure 4.1.1: MPC-37 Regional-Cell Identification



Figure 4.1.2: MPC-89 Regional-Cell Identification

4.2 CLASSIFICATION OF STRUCTURES, SYSTEMS, AND COMPONENTS

The systems, structures and components (SSCs) for the HI-STORE CIS facility are designed and analyzed to ensure that they will perform their intended functions under normal, off-normal, and accident conditions to meet all regulatory requirements delineated in 10 CFR Part 72 [1.0.5]. These intended functions include:

i. Providing radionuclide confinement/containment

ii. Enabling heat rejection from cask components and contents to maintain their temperatures within specified regulatory limits

iii. Attenuating emission of radiation to acceptable levels

iv. Maintaining sub-criticality of fissile contents

References [4.2.1] & [4.2.2] provide the guidelines to determine the Important to Safety significance category in accordance with NUREG/CR-6407 [1.2.2] which are:

Category A: The failure or malfunction of a structure, component, or system could directly result in a condition adversely affecting public health and safety.

Category B: The failure or malfunction of a structure, component, or system could indirectly (i.e., in conjunction with the failure of another item) result in a condition adversely affecting public health and safety.

Category C: The failure or malfunction of a system, structure or component (SSC) that would have some effect on the packaging, but would not significantly reduce the effectiveness of the packaging and would not be likely to create a situation adversely affecting public health and safety.

Not-Important-to-Safety: The failure or malfunction of an SSC would not reduce the effectiveness of the system or packaging and would not create a situation adversely affecting public health and safety.

Thus each SSC that constitutes the HI-STORE CIS facility is classified into one of above four categories depending on the severity of consequence in the event of its failure or malfunction due to a credible adverse event.

Chapter 1 contains the description of the SSCs that comprise the HI-STORE CIS facility. The SSCs in Table 4.2.1 can be subdivided in two types, namely

i. Those that are designed and built to meet the requirements of the HI-STORE CIS facility or are assembled at the site (HI-STORE Specific or “HS”)

ii. Those that are pre-qualified and delivered to the site pursuant to the safety requirements in the HI-STORM UMAX docket and arrive at the site ready-for-deployment (UMAX Generic or “UG”)

The ITS category for UG SSCs is defined by their classification in their native docket, principally the HI-STORM UMAX docket [1.0.6]. Those SSCs whose safety classification is not defined in other dockets (HS SSCs) are classified using [4.2.1] & [4.2.2]. Table 4.2.1 provides a compilation of the ITS classification information on *all* of the principal SSCs that are envisaged to be used at the HI-STORE CIS facility including both the "HS" and "UG" types; the latter directly excerpted from the HI-STORM UMAX FSAR [1.0.6] or a referenced docket therein, such as HI-STORM 100 FSAR [1.3.3].

Table 4.2.1
ITS Classification of SSCs that Comprise the HI-STORE CIS Facility

Name of SSC (Note 1)	Function (See Section 1.3)	ITS Classification	Type	Source for ITS determination
Cavity Enclosure Container (CEC)	Cavity Enclosure Container; defines the Canister's storage space	ITS-C	UG	[1.0.6]
CEC Closure Lid	A removable heavy structure placed atop the HI-STORM UMAX CEC that blocks sky shine from the stored Canister.	ITS-C	UG	
CEC Divider Shell	A removable insulated shell that surrounds the stored Canister	ITS-C	UG	
Support Foundation Pad (SFP)	Supports the HI-STORM UMAX VVM	ITS-C	UG	
ISFSI pad	Defines the top surface of the VVM	ITS-C	UG	
CLSM (see Glossary)	Occupies the subterranean space between the CECs	NITS	UG	
SNF Canisters	Provide a leak-tight confinement and criticality control to stored fuel	ITS-A	UG	[1.3.7]
HI-TRAC CS	Serves to facilitate ALARA transfer of the Canister between the transport cask and the HI-STORM UMAX VVM cavity	ITS-A	HS	[1.0.5], [4.2.1], [4.2.2], [1.2.2]
HI-TRAC CS Lift Yoke	Means for attaching HI-TRAC CS to CTB Crane for loaded or unloaded relocation within the CTB.	ITS-A	HS	
Cask Transfer Building (CTB)	Provides weather protection and climate control for canister transfer	NITS	HS	

Table 4.2.1
ITS Classification of SSCs that Comprise the HI-STORE CIS Facility

Name of SSC (Note 1)	Function (See Section 1.3)	ITS Classification	Type	Source for ITS determination
CTB Crane	Used to move, upend and down-end the transport cask (loaded an unloaded); remove the transport cask impact limiters; move and position HI-TRAC CS (loaded and unloaded); handling of other equipment	ITS-A [Note 2]	HS	[1.0.5], [4.2.1], [4.2.2], [1.2.2]
CTB Slab	Provide support for all canister receipt and loading operations within the CTB	ITS-C	HS	
Canister Transfer Facility (CTF)	Underground ventilated structure used to effectuate transfer of canister from the transport cask to the HI-TRAC CS (and reverse operation, if required)	ITS-C	HS	
HI-STAR 190 Transport Cask	Cask in which SNF canisters are received	ITS-A	UG	[1.3.6]
Transport Cask Horizontal Lift Beam	Serves to lift HI-STAR 190 transport cask (using CTB crane)	ITS-A	HS	[1.0.5], [4.2.1], [4.2.2], [1.2.2]
Transport Cask Tilt Frame	Serves to upend/downend HI-STAR 190 transport cask	ITS-C	HS	
Transport Cask Lift Yoke	Means to connect HI-STAR 190 Transport Cask to CTB crane for movement within the CTB	ITS-A	HS	
Vertical Cask Transporter (VCT)	Principal means to translocate the HI-TRAC CS and to effectuate Canister transfer to the HI-STORM UMAX VVM	ITS-A (Note 3)	UG	[1.3.7]

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

Table 4.2.1
ITS Classification of SSCs that Comprise the HI-STORE CIS Facility

Name of SSC (Note 1)	Function (See Section 1.3)	ITS Classification	Type	Source for ITS determination
MPC Lift Attachment	Means of attaching rigging to MPC for download into VVM	ITS-A	HS	[1.0.5], [4.2.1], [4.2.2], [1.2.2]
MPC Lifting Device Extension	Means of attaching MPC Lift Attachment to VCT for download of MPC into VVM	ITS-A	HS	
Special Lifting Devices	Lifting components used to connect the cask or canister to the CTB crane or the VCT lift points	ITS-A	HS	

Note 1: The ancillaries used at the HI-STORE CIS facility are limited to those needed to transfer the arriving canisters into the HI-STORM VVMs. Thus, some ancillaries described in the HI-STORM UMAX FSAR [1.0.6], like the Forced Helium Drying System used to dry the canister internals), are not included in this table.

Note 2: The Cask crane's main girder and vertical columns are ITS-category A; the main hoist, auxiliary hoist and other electrical systems are treated as 'augmented quality" under Holtec's QA program.

Note 3: The VCT is ITS-A because of the Overhead beam. Other components are as listed below (See Figure 4.5.1):

VCT Component I.D.	ITS Category
Cask restraint system	NITS
Cask restraint strap	ITS-B
Control systems	NITS
Engine and drive systems	NITS
Hydraulic system	NITS
Jacks (lift cylinders)	NITS
Lifting towers (structure)	ITS-A
MPC downloader system	ITS-B
Overhead beam	ITS-A
Tracks	NITS
Vehicle frame	NITS
Load Drop Protection System	ITS-B

4.3 DESIGN CRITERIA FOR SSCS IMPORTANT TO SAFETY

4.3.1 Multi-Purpose Canisters (MPCs)

The MPCs that will be stored at the HI-STORE CIS are limited to those included in the HI-STORM UMAX FSAR [1.0.6].

4.3.1.1 Structural

The MPCs to be received and loaded at the HI-STORE CIS facility are comprised of a fuel basket within a welded enclosure vessel. As the only canisters certified for storage in the HI-STORE CIS facility are those qualified in the HI-STORM UMAX FSAR [1.0.6], the structural design criteria for the MPCs is incorporated by reference to Section 2.0.2 of [1.0.6].

4.3.1.2 Thermal

The thermal design criteria for the MPCs (including the design temperature limits of Table 2.3.7) are incorporated by reference from Section 2.0.3 (MPC Design Criteria), of the HI-STORM UMAX FSAR [1.0.6]. The portion of Section 2.0.3 of Reference [1.0.6] related to maximum permissible heat loads and helium backfill is not incorporated by reference, as it has been replaced with the information presented in Section 4.1.1 of this SAR.

4.3.1.3 Shielding

The site boundary dose requirement for the systems (including canisters) stored at HI-STORE is provided in Section 4.4. Compliance to the requirements (see Table 4.4.3) is demonstrated in Chapter 11.

4.3.1.4 Confinement

The MPC provides for confinement of all radioactive materials for all design basis, off-normal and postulated accident conditions. As the only canisters certified for storage in the HI-STORE CIS facility are those qualified in the HI-STORM UMAX FSAR [1.0.6], the confinement criteria for the MPCs is incorporated by reference from Section 2.0.6 of [1.0.6].

4.3.1.5 Criticality Control

Criticality control is maintained by the geometric spacing of the fuel assembles and the spatially distributed B-10 isotope in the Metamic-HT basket within the canister. As the only canisters certified for storage in the HI-STORE CIS facility are those qualified in the HI-STORM UMAX FSAR [1.0.6], the criticality control criteria for the MPCs is incorporated by reference to Section 2.0.5 of [1.0.6].

4.3.2 VVM Components and ISFSI Structures

The design criteria of the HI-STORM UMAX VVM components and ISFSI structures described in Chapter 2 of the HI-STORM UMAX FSAR [1.0.6] are largely applicable to the HI-STORE CIS. The criteria of [1.0.6] that bound the HI-STORE CIS design, and are therefore excluded

from further consideration in this SAR, are outlined in Table 4.3.1. Environmental conditions and constraints that differ from those bounded by [1.0.6], although minor in nature, are described in Table 4.3.2 and evaluated herein. With the following exceptions, all subsections of the HI-STORM UMAX FSAR are relevant to the HI-STORE CIS evaluation:

1 Criteria related to the HI-TRAC VW system. The HI-TRAC VW system is supplanted by the HI-TRAC CS system in this application, with the design criteria for the HI-TRAC CS system described herein.

2 Service conditions related to the used of Forced Helium Drying (FHD) described in Paragraph 2.3.3.5 of the HI-STORM UMAX FSAR. As the HI-STORE CIS facility accepts only pre-packaged canisters, operations related to internal canister drying are not applicable.

Information consistent with the regulatory requirements related to shielding, thermal performance, confinement, radiological, and operational considerations is also provided. The licensing drawing of the HI-STORM UMAX design variant used in the HI-STORE CIS application is included in Section 1.5 of this SAR. The licensing drawing provides information on the necessary critical characteristics that define the HI-STORE CIS UMAX system for this application.

4.3.2.1 Structural

The applicable loads, affected parts under each loading condition, and the applicable structural acceptance criteria related to the HI-STORM UMAX VVM and ISFSI structures that are compiled in Section 2.0 of [1.0.6] provide a complete framework for the required qualifying safety analyses in this SAR. The VVM storage system at the HI-STORE CIS ISFSI will be functionally identical to that certified in the HI-STORM UMAX docket. The conservative approach of basing the HI-STORE CIS design on the certified HI-STORM UMAX design is supported by the following:

1. The subgrade and under-grade soil properties at the HI-STORE CIS site are uniformly better than those assumed for the general certification of the HI-STORM UMAX system.
2. The top-of-pad earthquake spectra corresponding to a 10,000-year earthquake at the HI-STORE CIS site is enveloped by that assumed for the HI-STORM UMAX in its general certification. (Subsection 4.3.6 and Table 4.3.3 provide a summary of the applicable seismic loadings for the HI-STORE CIS facility).
3. The long-term settlement at the HI-STORE CIS ISFSI is computed to be less than that assumed in the certification of the HI-STORM UMAX.
4. The load combinations for the VVM and ISFSI structure at the HI-STORE CIS are consistent with those identified in the HI-STORM UMAX evaluation. Load combinations that are bounded by the HI-STORM UMAX evaluation, and therefore excluded from further evaluation in this application, are listed in Table 4.3.1.

4.3.2.2 Thermal

The design temperatures for the VVM components and ISFSI structures are incorporated by reference from Table 2.3.7 of Reference [1.0.6].

4.3.2.3 Shielding

The site boundary dose requirement for the HI-STORM UMAX ISFSI at HI-STORE is provided in Section 4.4. Compliance to the requirements (see Table 4.4.3) is demonstrated in Chapter 11.

4.3.2.4 Confinement

The VVM and ISFSI structures do not perform any confinement function. Confinement during storage is provided by the SNF storage canisters which are protected from leak by an all- welded stainless steel confinement vessel and are certified in their native docket as subject to a non-credible risk of leakage, see Chapter 9.

4.3.2.5 Criticality Control

The VVM components and ISFSI structures do not perform any criticality control function. Criticality control is maintained during storage by the internal configuration of the SNF storage canisters, as described in Chapter 8.

4.3.3 HI-TRAC CS

The HI-TRAC provides physical protection and radiation shielding of the MPC contents during the extraction of a loaded canister from the transport cask and its subsequent transfer to the HI-STORM UMAX VVM. The design characteristics of the HI-TRAC CS are presented in Chapter 1. The HI-TRAC CS plays a central role in the Short Term Operations that are carried out to translocate the Canister from an arriving transport package to its designated HI-STORM UMAX storage cavity.

4.3.3.1 Structural

The HI-TRAC CS transfer cask includes both structural and non-structural radiation shielding components that are classified as important-to-safety. The structural steel components of the HI-TRAC CS are designed to meet the stress limits of Section III, Subsection NF, of the ASME Code [4.5.1] for all operating modes. The embedded trunnions for lifting and handling of the transfer cask are designed in accordance with the requirements of NUREG-0612 [1.2.7] for interfacing lift points.

Table 4.3.4 lists the loading scenarios for HI-TRAC CS for which its structural qualification must be performed.

4.3.3.2 Thermal

The HI-TRAC CS cask must reject the canister's decay heat to the environment during the normal short term operations and accident scenarios, which are established by considering the operations described in Chapter 10. The thermally-significant loadings are listed in Table 4.3.5.

The permissible temperature limits for all steel and concrete used in short-term operation SSCs used at HI-STORE, including HI-TRAC CS, are provided in Table 4.4.1.

4.3.3.3 Shielding

The HI-TRAC transfer cask provides shielding to maintain occupational exposures ALARA in accordance with 10CFR20 [7.4.1]. The HI-TRAC calculated dose rates for a set of reference conditions are reported in Chapter 7. These dose rates are used to estimate the occupational exposure to the work crew for the Short-Term Operations.

Section 4.4 provides dose limits applicable to the HI-STORE CIS facility.

4.3.3.4 Confinement

The HI-TRAC CS transfer cask does not perform any confinement function.

4.3.3.5 Criticality Control

The HI-TRAC CS transfer cask does not provide any criticality control function.

4.3.4 HI-STAR 190

As discussed in Chapter 3, the HI-STAR 190 transport cask, used to deliver the loaded Canister to the CTB, participates in the Short Term Operations, albeit to a limited extent. The safety analysis of HI-STAR 190 as a transport package under 10CFR71 regulations is documented in [1.3.6]. In order to insure that the transport condition loads that underlie the transport certification of HI-STAR 190 are not exceeded, the Short Term Operations in the CTB are configured such that:

i. The handling of the cask is always carried out using single failure proof devices and systems;

ii. As an additional defense-in-depth, the cask remains equipped with its impact limiters during its handling from the rail car and the free fall height of the cask is maintained below its certified limit in its Part 71 docket;

iii. The cask is kept free of any wrappings that may inhibit its heat rejection function during short term operations;

iv. In this subsection, HI-STAR 190's safety function as a canister containment device to the requirements of Part 72 is set down as a set of design criteria.

4.3.4.1 Structural

The structural qualification of HI-STAR 190 to the loadings of 10CFR71.71 (normal condition) and 10CFR71.73 (accident condition) in [1.3.6] are clearly much more severe than those encountered during its handling in the CTB. Nevertheless, certain structural requirements are unique to the operations in the CTB that are unique to the Short Term Operations. Table 4.3.6 contains the structurally significant loadings on the HI-STAR 190 cask in the Cask Transfer Building. Acceptance criteria are provided in Section 4.4.

4.3.4.2 Thermal

The thermally-significant loadings on HI-STAR 190 that warrant safety demonstration are summarized in Table 4.3.6. The permissible temperature limits for all steel weldments in casks and structures used at HI-STORE, provided in Table 4.4.4, are applicable to the HI-STAR 190.

4.3.4.3 Shielding

HI-STAR 190 is designed to meet the dose attenuation requirements of 10CFR71 [1.3.2] which far exceed those expected of on-site transfer casks. However, HI-STAR 190's contribution to meeting the dose limits of Part 72, set down in Subsection 4.4 herein, is considered in demonstrating compliance.

4.3.4.4 Confinement

The confinement function of the canister is unaffected by the function of HI-STAR 190.

4.3.4.5 Criticality Control

HI-STAR 190 does not participate in the criticality control function.

4.3.5 Canister Transfer Facility (CTF)

The HI-STORE CTF is an underground structure used to effectuate transfer of the SNF canister from the transport cask (HI-STAR 190) to the transfer cask (HI-TRAC CS).

4.3.5.1 Structural

The CTF includes both structural and non-structural radiation shielding components that are classified as important-to-safety. The structural steel components of the CTF are designed to meet the stress limits of Section III, Subsection NF, of the ASME Code [4.5.1] for normal, off-normal and accident conditions, as applicable.

The CTF must withstand the static loads due to the weights of each of its components, including the weight of the HI-TRAC CS transfer cask with the loaded MPC stacked on top during the canister transfer, and the weight of the transport cask with the loaded MPC staged on the CTF foundation slab.

4.3.5.2 Thermal

The allowable temperatures for the CTF structural steel components are based on the maximum temperature for material properties and allowable stress values provided in Section II of the ASME Code. The allowable temperatures for the structural steel and shielding components of the CTF are provided in Table 4.4.1.

4.3.5.3 Shielding

The CTF provides shielding to maintain occupational exposures ALARA in accordance with 10CFR20 [7.4.1]. Dose rates for a set of reference conditions are reported in Chapter 7. These

dose rates are used to perform a generic occupational exposure estimate for MPC transfer operations, as described in Chapter 11.

4.3.5.4 Confinement

The CTF does not perform any confinement function.

4.3.5.5 Criticality Control

The CTF does not perform any criticality control function.

4.3.6 Applicable Earthquake Loadings for the HI-STORE CIS Facility

Guided by the adjudication in the ASLB proceedings on the PFS, LLC docket [4.3.1], the Safe Shutdown Earthquake (SSE) or Design Basis Earthquake (DBE) for the HI-STORE CIS facility has been set to bound the 10,000 year return earthquake, which is discussed in Subsection 2.6.2. Similarly, the Operating Basis Earthquake (OBE) has been set to bound the 1,000 year return earthquake for the site. For additional conservatism and to overcome any potential uncertainty or future adjustments to the site seismological data, a Design Extended Condition Earthquake (DECE) has also been defined for the site, which has a ZPA value that is two-thirds greater than the DBE.

The response spectra of the bounding earthquakes are defined by the Regulatory Guide 1.60 spectra pegged to the respective ZPA values identified in Table 4.3.3. The generation of acceleration time histories, if required, shall meet the criteria specified in SRP 3.7.1 [5.4.1], which has been used to support safety analyses for HI-STORM deployments at numerous nuclear plant sites.

The DBE applies to the HI-STORM UMAX system which will serve to store the Canisters for a relatively long duration (depending on the need and licensing duration granted by the USNRC). In Chapter 5, however, the DECE is conservatively used to inform the structural evaluation of the HI-STORM UMAX system at the HI-STORE site.

The OBE applies to the Short-Term Operations required to load the arriving Canisters at HI-STORE. All equipment configurations, such as the stack-up at the Canister Transfer Facility and that at the HI-STORM UMAX VVM or the Vertical Cask Crawler (VCT) holding the HI-TRAC CS transfer cask by its straps (Figure 4.5.2), are subject to seismic qualification under the Operating Basis Earthquake. However, the seismic calculations in Chapter 5 for Short-Term Operations conservatively use the DBE as input.

Following the universally practiced “lift and set” rule at nuclear power plants, transient activities such as upending of a cask, attaching of slings or installation of fasteners, are treated as transient activities that are not subject to a seismic qualification. For clarity of application, any activity that spans less than a work shift is deemed to be seismic-exempt.

Table 4.3.1 **Loadings Excluded from Further Consideration in the Qualification of Storage System and Ancillaries at the HI-STORE SAR**	
Internal Design Pressure	All canisters brought to the HI-STORE site in the HI-STAR 190 transport cask from operating at-plant ISFSIs must meet the transport cask heat load limit, which is much lower than the acceptable limit defined in Chapter 2 of the HI-STORM UMAX FSAR [1.0.6]. The associated internal design pressure shall therefore always be less than its design basis pressure. The canister internal pressure is incorporated by reference from the HI-STORM UMAX FSAR [1.0.6], Paragraph 2.3.2.1. The HI-TRAC transfer cask and HI-STORM UMAX VVM are not capable of retaining internal pressure due to their open design, and therefore no analysis is required.
Lightning	Lightning is considered to be innocuous to the HI-STORM UMAX ISFSI because of its underground configuration. It is therefore excluded from consideration in both the HI-STORM UMAX and HI-STORE CIS design loadings. The evaluation of the HI-STORM UMAX VVMs related to lightning is incorporated by reference from the HI-STORM UMAX FSAR [1.0.6], Section 2.3.1.
Snow and Ice	The latitude of the ELEA site makes heavy snow accumulation and the comparative low magnitude of snow loading removes snow as a Design Basis Load (DBL) *a priori* from further consideration
High Winds	Regulatory Guide 1.76 [2.7.1], ANSI 57.9 [2.7.2], and ASCE 7-05 [4.6.1] provide the wind data used to define the Design Basis Wind in the HI-STORM UMAX FSAR. The diminutive profile and heavy weight of the closure lid (over 17 tons) makes the HI-STORM UMAX facility immune from any kinematic movement under very high or tornadic wind conditions. The wind conditions at the ELEA site are considered to be bounded by the HI-STORM UMAX FSAR Design Basis Wind. The HI-STORM UMAX systems performance under high wind conditions is incorporated by reference from the HI-STORM UMAX FSAR [1.0.6], Section 2.3.2.7
Tornado Borne Missiles	The Design Basis Missiles (DBMs) analysis in the HI-STORM UMAX FSAR show large margins of safety and are considered to bound the HI-STORE CIS facility conditions. Therefore, a repetitive analysis in this SAR is unnecessary. The HI-STORM UMAX tornado borne missile analysis is incorporated by reference from the HI-STORM UMAX FSAR [1.0.6], Section 2.4.2.

Table 4.3.1 **Loadings Excluded from Further Consideration in the Qualification of Storage System and Ancillaries at the HI-STORE SAR**	
Flood	As shown in Table 4.3.2, the Design Basis Flood used to qualify the VVM in the HI-STORM UMAX FSAR exceeds the most severe projection of flood at the ELEA site. Therefore, flood is eliminated from consideration as a meaningful loading event for HI-STORE CIS. The HI-STORM UMAX system design basis flood evaluation is incorporated by reference from the HI-STORM UMAX FSAR [1.0.6], Section 2.4.7.
Non-Mechanistic Tip-over	Because the HI-STORM UMAX VVM is situated underground, a tip-over event is not a credible accident for this design. It has been excluded in the HI-STORM UMAX safety analysis for the same reason.
Explosion	An explosion event has not been postulated as a Design Basis Load (DBL) for the HI-STORE ISFSI. However, the HI-STORM UMAX VVM is evaluated for a design basis explosion pressure per Table 2.3.1 of [1.0.6]. In addition, the canisters are evaluated for a Design Basis external pressure, under accident conditions, per Table 2.2.1 of [1.3.7].

Table 4.3.2
Environmental Data for the Licensing Basis in the HI-STORM UMAX Docket and the HI-STORE Site for Different Service Conditions

Service Condition	Item	HI-STORM UMAX General License Data	Site Specific Data for HI-STORE CIS
Normal Condition of Storage	Temperature (defined as annual average)	80 deg. F.	62 deg. F (Table 2.7.1)
	Ambient pressure corresponding to elevation above sea level	760 mm Hg	670 mm Hg (See Note 1)
Off-Normal Condition of Storage	Off-normal temperature (defined as the minimum of the 72-hour average of the ambient temperature at an ISFSI site.)	100 deg. F.	91 deg. F (Table 2.7.1)
Accident Condition of Storage	Accident Condition (maximum average ambient temperature over a 24-hour period)	125 deg. F	108 deg. F See Chapter 2
Short Term Operations	Maximum & minimum 3-day average ambient temperature	90 deg. F 0 deg. F	91 deg. F 0 deg. F
Maximum Flood Height (faulted States)	Peak height of the flood water above the ISFSI pad	125 feet	4.8 inches (See Chapter 2, site considered "flood dry")

Note 1: Ambient air pressure at 3500 ft elevation above sea level

Table 4.3.3

Applicable Earthquake and Long Term Settlement data for the Certified HI-STORM UMAX System and the HI-STORE CIS Facility

#	Data	HI-STORM UMAX Generic License Value (see Note 1)	HI-STORE CIS Site Value	Comment
1	ISFSI Pad and SFP concrete density concrete compressive strength rebar yield strength concrete cover on rebar	• 150 lb/ft^3 reference dry density • 4,500 psi minimum concrete compressive strength @ ≤ 28 days • 60,000 psi minimum rebar yield strength • minimum concrete cover on rebar per subsection 7.7.1 of ACI-318(05)	Same as the value certified in the HI-STORM UMAX docket.	See Licensing Drawings in Chapter 1 for details on concrete pad thickness. Grade 60 Rebar. Rebar is #11@9" (each face, each direction) Compressive strength, allowable bearing stress and reference dry density values for ISFSI structures are also applicable to the plain concrete used in the HI-STORM UMAX Closure Lid
2	Depth averaged density of subgrade in Space A (see Figure 4.3.1)	120 lb/ft^3 minimum	120 lb/ft^3 minimum	Required for shielding and structural analysis
3	Depth averaged density of subgrade in Space B (see Figure 4.3.1)	110 lb/ft^3 minimum	110 lb/ft^3 minimum	Required for shielding analysis.
4	Depth averaged density of subgrade in Space C (see Figure 4.3.1)	120 lb/ft^3 nominal	150 lb/ft^3 nominal	Not required for shielding.
5	Depth averaged density of subgrade in Space D (see Figure 4.3.1)	120 lb/ft^3 nominal	150 lb/ft^3 nominal	This space will contain native soil. Not required for shielding.
6	Strain compatible effective shear wave velocity in Space A	1300 ft/sec minimum	1300 ft/sec minimum	This space will typically contain CLSM or lean concrete.

Table 4.3.3

Applicable Earthquake and Long Term Settlement data for the Certified HI-STORM UMAX System and the HI-STORE CIS Facility

#	Data	HI-STORM UMAX Generic License Value (see Note 1)	HI-STORE CIS Site Value	Comment
7	Strain compatible effective shear wave velocity in Space B	450 ft/sec minimum	780 ft/sec minimum	Space will contain native soil.
8	Strain compatible effective shear wave velocity in Space C	485 ft/sec minimum	980 ft/sec minimum	Space may be remediated with vertical reinforcement such as pilings to achieve equivalent Boussinesq stiffness.
9	Strain compatible effective shear wave velocity in Space D, V	485 ft/sec minimum	980 ft/sec minimum	Space will contain native soil.
10	Density of plain concrete in the Closure Lid (nominal)	150 lb/cubic feet	150 lb/cubic feet	Used in shielding calculations
11	Reference compressive strength of plain concrete in the Closure Lid	4,000 psi	4,000 psi	Used in analysis of mechanical loadings on the Closure Lid
12	Minimum compressive strength of SES in Space A (see Figure 4.3.1)	1,000 psi	1,000 psi	Used in tornado missile impact analysis and SSI analysis
13	Two orthogonal horizontal and one vertical ZPAs for 10,000 -year return earthquake (DBE)	-	0.15,0.15, 0.15	5% Damped Reg. Guide 1.60 spectra [4.3.2]
14	Two orthogonal horizontal and one vertical ZPAs for 1000- year return earthquake (OBE)	-	0.10, 0.10, 0.10	2% Damped Reg. Guide 1.60 spectra [4.3.2]
15	Two orthogonal horizontal and one vertical ZPAs for Design Extended Condition Earthquake (DECE)	-	0.25,0.25, 0.25	5% Damped Reg. Guide 1.60 spectra [4.3.2]

Table 4.3.3

Applicable Earthquake and Long Term Settlement data for the Certified HI-STORM UMAX System and the HI-STORE CIS Facility

#	Data	HI-STORM UMAX Generic License Value (see Note 1)	HI-STORE CIS Site Value	Comment
16	Newmark Summation of the ZPAs at the Grade at the HI-STORE site (DECE)(Note 2)	1.3	0.45	The HI-STORM UMAX CoC uses the Newmark summation limit to indicate the severity of an earthquake event. The Newmark 100-40-40 response summation for a 3-D earthquake site is defined as: $A= a_1+0.4a_2+0.4a_3$, where a_1, a_2 and a_3 are the site's ZPAs in three orthogonal directions and $a_1 \geq a_2 \geq a_3$ This approach is consistent with Reg. Guide 1.92 [4.3.3].

Note 1: The HI-STORM UMAX ISFSI design data is reproduced from Table 2.3.2 of the HI-STORM UMAX FSAR [1.0.6].

Note 2: The Newmark summation, A, is the weighted scalar that defines the severity of an earthquake consisting of three orthogonal (vectorial) accelerations. The magnitude of A is used to compare the relative severity of earthquakes.

Table 4.3.4

Structurally Significant Loadings (SSL) for HI-TRAC CS

Structural Loading Case	Description of Loading	Affected part or Interfacing structure	Acceptance criterion
SSL-1	Dead weight of the loaded HI-TRAC CS	Lifting trunnions	NUREG-0612 [1.2.7]
SSL- 2	Site's OBE while the loaded cask is mounted on a HI-STORM UMAX VVM	Threaded anchors fastening the cask to the CEC structure embedded in the ISFSI pad and substrate & shell structure of the cask body loaded as a cantilever beam	ASME Section III Subsection NF [4.5.1] stress limits for Level B service condition.
SSL-3	Site's OBE while the loaded cask is mounted on the CTF surface and anchored to its Threaded Anchor Locations (TAL)	Threaded anchors fastening the cask to the CTB slab & shell structure of the cask body loaded as a cantilever beam	ASME Section III Subsection NF [4.5.1] stress limits for Level B service condition.
SSL-4	Missile from an extreme environmental phenomenon striking the cask while it is mounted on the ISFSI pad	Threaded anchors fastening the cask to the CEC structure embedded in the ISFSI pad and substrate & shell structure of the cask body loaded as a cantilever beam	ASME Section III Subsection NF stress limits for Level D service condition & the canister must be retrievable (not jammed inside the cask due to excessive diametral deformation)

Table 4.3.5
Thermally Significant Loadings (TSL) for HI-TRAC CS

Thermally significant loading Condition	Description of condition	Ref Figure	Acceptance Criterion
TSL-1	Loaded Canister in HI-TRAC CS with its Shield Gate closed (constricted ventilation)	Figure 6.4.2	See Table 4.4.1
TSL-2	Collapse of the Cask Transfer Building (CTB) causing significant blockage of the top ventilation by the corrugated sheet metal from the roof	Further described in Subsection 6.5.2	
TLS-3	Enveloping fire	Further described in Subsection 6.5.2	

Table 4.3.6

Governing Structural and Thermal Loadings for HI-STAR 190 during Short Term Operations

Loading ID	Loading type	Description	Acceptance Criterion
SSL-1	Structurally significant	The OBE strikes while the cask loaded with the canister is in the CTF cavity (see Figure 3.1.1g/h)	The cask's movement under the OBE must be limited such that it does not impact the internal shell of the CTF
TSL-1	Thermally Significant	The cask is seated in the CTF cavity which limits its heat rejection capacity (see Figure 6.4.1)	The maximum fuel cladding temperature must remain below the Short-Term Operation limit (Section 4.4)
TSL-2	Thermally significant	The CTB roof collapses while the cask is inside the CTF cavity (see Figure 6.4.1)	The maximum fuel cladding temperature must remain below the Accident condition limit (Section 4.4)



FIGURE 4.3.1: SUB-GRADE AND UNDER-GRADE SPACE NOMENCLATURE

Note 1: Space A is the lateral subgrade space in and around the VVMs which is refilled with CLSM or lean concrete after the construction of the SFP. Space B is the lateral subgrade that extends around the ISFSI. Space C is the under-grade below the SFP. Space D is the under-grade surrounding Space C. P is the distance between the outside VVMs and the edge of the ISFSI pad.

Note 2: As indicated by the title, this figure is provided to show the nomenclature for the various spaces around a HI-STORM UMAX ISFSI. This figure is not intended to provide specific dimensions or layout of the site- specific design in this SAR.

4.4. ACCEPTANCE CRITERIA FOR CASK COMPONENTS

4.4.1 Stress and Deformation Limits

In the ASME Code, plant and system operating conditions are commonly referred to as normal, upset, emergency, and faulted. Consistent with the terminology in NRC documents, this SAR utilizes the terms normal, off-normal, and accident conditions.

The ASME Code defines four service conditions in addition to the Design Limits for nuclear components. They are referred to as Level A, Level B, Level C, and Level D service limits, respectively. Their definitions are provided in Paragraph NCA-2142.4 of the ASME Code. The four levels are used in this SAR as follows:

i. Level A Service Limits are used to establish allowables for normal condition load combinations.

ii. Level B Service Limits are used to establish allowables for off-normal conditions.

iii. Level C Service Limits are not used.

iv. Level D Service Limits are used to establish allowables for certain accident conditions.

The ASME Code service limits are used in the structural analyses for definition of allowable stresses and allowable stress intensities, as applicable. Allowable stresses and stress intensities of materials required for structural analyses are tabulated in Section 4.5. These service limits are matched with normal, off-normal, and accident condition loads combinations in the following subsections.

The following definitions of terms apply to the tables on stress intensity limits; these definitions are the same as those used throughout the ASME Code:

S_m: Value of Design Stress Intensity listed in ASME Code Section II, Part D, Tables 2A, 2B and 4

S_y: Minimum yield strength at temperature

S_u: Minimum ultimate strength at temperature

The following stress limits are applicable to the SSCs at the HI-STORE CIS facility:

i. Canisters: The MPC confinement boundary is required to meet Section III, Class 1, Subsection NB stress intensity limits. Because the MPCs (canisters) are certified to loads in their native docket [1.0.6] that bound those at the HI-STORE site, it is not necessary to re-perform their stress qualifications. Accordingly, the stress intensity limits for the MPC are not presented in this SAR.

ii. HI-STORM UMAX CEC and Closure Lid: The applicable Code for stress analysis is ASME Section III, Subsection NF. Because the HI-STORM UMAX structure has been qualified to loads that uniformly bound those at the HI-STORE site, it is not necessary to re-qualify the HI-STORM UMAX structure to the site specific loads in this SAR.

iii. Load bearing ancillaries: All structurally significant ancillaries are qualified to ASME Section III Subsection NF. The stress limits for the different service conditions are listed in Table 4.4.2. Appendix 4.A provides a summary of specific stress categories extracted from the Code for NF structures

iv. Lifting and handling equipment: The applicable codes and requirements are provided in Section 4.5.

v. Special handling devices: ANSI N14.6 [1.2.4] applied. Detailed requirements are provided in Section 4.5.

4.4.2 Thermal Limits

The thermal acceptance criteria for all components are identical to the design criteria described in Section 4.3.

4.4.3 Dose Limits

The off-site dose for normal operating conditions to any real individual beyond the controlled area boundary is limited by 10CFR72.104(a) for normal conditions and 10CFR72.106 for accident conditions (including contributions from all Short-Term operations) at the HI-STORE CIS facility. Table 4.4.3 provides the numerical dose limits.

Table 4.4.1: Permissible Temperature Limits for HI-TRAC CS and CTF Materials (Note 4)

ITEM	Short Term Operations, Deg. F. (Note 1)	Accident Condition, Deg. F.	Notes
Shielding Concrete	300 (section average)	650 (local maximum)	Note 3
All steel weldments in casks and structures used at HI-STORE	600	700	Note 2; Note 3

Note 1: Short term operations include all activities in the CTB and at the ISFSI to effectuate canister transfer and onsite translocation.

Note 2: For accident conditions that involve heating of the steel structures and no mechanical loading (such as the blocked air duct accident), the permissible metal temperature of the steel parts is defined by Table 1A of ASME Section II (Part D) for Section III, Class 3 materials as 700°F

Note 3: For the ISFSI fire event, the local temperature limit of concrete is 1100°F (HI-STORM 100 FSAR Appendix 1.D [1.3.3]), and the steel structure is required to remain physically stable (i.e., so there will be no risk of structural instability such as gross buckling, the maximum temperature shall be less than 50% of the component's melting temperature and the specific temperature limits in this table do not apply). Concrete that exceeds 1100°F shall be considered unavailable for shielding of the overpack.

Note 4: The temperature limits of MPC components and its contents including fuel cladding under short-term operations are provided in Table 2.3.7 of the HI-STORM UMAX FSAR [1.0.6].

Table 4.4.2: Stress and Acceptance Limits for Different Loading Conditions for the Primary Load Bearing Structures in the Steel Weldments of Casks

(Adapted from Table 2.2.12 of HI-STORM FW FSAR [1.3.7])

STRESS CATEGORY	DESIGN + NORMAL	OFF-NORMAL	ACCIDENT
Primary Membrane, P_m	S	1.33·S	See Note 1
Primary Membrane, P_m, plus Primary Bending, P_b	1.5·S	1.995·S	
Shear Stress (Average)	0.6·S	0.6·S	

Note 1: Under accident conditions, the cask must maintain its physical integrity, the loss of solid shielding (lead, concrete, steel, as applicable) shall be minimal and the Canister must remain recoverable.

Definitions:

S = Allowable Stress Value for Table 1A, ASME Section II, Part D.
S_m = Allowable Stress Intensity Value from Table 2A, ASME Section II, Part D
S_u = Ultimate Stress

Table 4.4.3: Radiological Site Boundary Requirements from 10CFR72

(Reproduced from Table 2.3.1 of HI-STORM FW FSAR [1.3.7])

MINIMUM DISTANCE TO BOUNDARY OF CONTROLLED AREA (m)	100
NORMAL AND OFF-NORMAL CONDITIONS: -Whole Body (mrem/yr) -Thyroid (mrem/yr) -Any Other Critical Organ (mrem/yr)	 25 75 25
DESIGN BASIS ACCIDENT: -TEDE (rem) -DDE + CDE to any individual organ or tissue (other than lens of the eye) (rem) -Lens dose equivalent (rem) -Shallow dose equivalent to skin or any extremity (rem)	 5 50 15 50

Table 4.4.4
HI-STAR 190 Materials Temperature Limits

Component	Short-Term Temperature Limits[a] °C (°F)	Accident Temperature Limits[a] °C (°F)
Fuel Basket	500 (932)[b]	500 (932)[b]
DFC	570 (1058)[b]	570 (1058)[b]
Basket Shims and Solid Shim Plates	500 (932)[b]	500 (932)[b]
MPC Shell	427 (800)[b]	427 (800)[b]
MPC Lid	427 (800)[b]	427 (800)[b]
MPC Baseplate	427 (800)[b]	427 (800)[b]
Containment Shell	232 (450)[c]	371 (700)[d]
Containment Bottom and Top Forgings	232 (450)[c]	371 (700) (Structural Accidents)[d] 788 (1450) (Fire Accident[e]
Closure Lid	232 (450)[c]	371 (700) (Structural Accidents)[d] 788 (1450) (Fire Accident[e]
Remaining Cask Steel	232 (450)[c]	371 (700) (Structural accidents)[d] 788 (1450) (Fire Accident)[e]
Lid Seal	120 (248)	210 (410)
Neutron Shield	204 (400)	Note (g)
Gamma Shield	316 (600)	316 (600)[Note (h)]

4.5 LIFTING EQUIPMENT (CTB CRANE & VCT), SPECIAL LIFTING DEVICES AND MISCELLANEOUS ANCILLARIES

Ancillaries for the HI-STORE CIS are equipment, systems or devices that are needed to carry out Short Term Operations to place the canister into interim storage or to remove the loaded canister from storage. Ancillaries are differentiated from "certified" SSCs by the fact that they are not a part of the storage system and their detailed design is not subject to regulatory certification. However, as required by NUREG-1567 [1.0.3], their design criteria must be articulated in this SAR. In what follows, the design criteria for the different types of ancillaries envisaged for the HI-STORE facility are set down in sufficient detail to ensure that the resulting detailed design will fulfill their safety imperatives in full measure.

The description of principal ancillaries needed at the HI-STORE facility provided in Chapter 1 indicates that the list is quite small due to the fact that the canisters arrive in ready-to-store condition at the site and the needed operations pertain entirely to handling of the loaded canister. As a result, the ancillaries belong entirely to the class of special and standard lifting devices and certain miscellaneous equipment.

Heavy load handling device criteria summarized in the following are adopted from the HI-STORM FW FSAR [1.3.7]

4.5.1 Design Requirements Applicable to Lifting Devices and Special Lifting Devices

The lifting and handling ancillaries needed for operation of the HI-STORE CIS are classified as either "*lifting devices*" or "*special lifting devices*."

The term *special lifting device* refers to components to which ANSI N14.6 [1.2.4] applies. As stated in ANSI N14.6 (both 1978 and 1993 versions), "This standard shall apply to *special lifting devices* that transmit the load from lifting attachments, which are structural parts of a container to the hook(s) of an overhead hoisting system." Examples of *special lifting devices* are canister lift cleats, cask lift brackets, and cask lift yokes.

The term *lifting device* as used in this SAR refers to components of a lifting and handling system that are not classified as *special lifting devices*. ANSI N14.6 is not applicable to these *lifting devices.* These include non-active structural components (components that bear the primary load but are not a constituent of a moving part, e.g., gear train, hydraulic cylinder) of the system.

4.5.1.1 Stress Compliance Criteria Applicable to Lifting Devices (LDs):

Examples of *lifting devices* used with Holtec's systems include the VCT or the main girder of the gantry crane used in the transport cask receiving area of the Cask Transfer Building (CTB).

The stress compliance criteria for *lifting devices* are taken from the code applicable to the specific component. For example, slings are required to meet the guidelines of ANSI B30.9 [4.5.6], and overhead beams in a crane are required to meet the guidelines of an applicable consensus national standard selected by the designer, such as AISC, CMAA, or ASME Code (Subsection NF [4.5.1]).

The transporter used to handle the loaded transfer cask or overpack during transport operations must be engineered to provide a high integrity handling of the load, defined as a lifting/handling operation wherein the risk of an uncontrolled lowering of the heavy load is non-credible. In handling equipment, such as a transporter, high integrity handling is achieved through (a) a body and any vertical columns designed to comply with stress limits of ASME Section III, Subsection NF, Class 3, (b) an overhead beam that is single-failure-proof, and (c) redundant drop protection features. Single failure proof handling capability is achieved by ensuring that the applicable factor of safety is 200% of that required by the reference design code or national consensus standard. It is acceptable to have certain load carrying members (such as the lifting towers in a vertical cask transporter) designed with redundant devices and others (such as the transverse beam) designed to the doubled factor of safety in order to meet the criteria set above.

4.5.1.2 Stress Compliance Criteria Applicable to Special Lifting Devices (SLDs):

The stress compliance criteria for *special lifting devices* are taken directly from ANSI N14.6 [1.2.4], which requires safety factors of three against the yield strength and five times against ultimate strength. Although not required by ANSI N14.6, Holtec International requires the yield and ultimate strengths of the primary load bearing member used in the stress analysis to be at its average metal temperature (in lieu of the ambient temperature).

4.5.1.3 Single Failure Proof Criteria

In order for a *lifting device* or *special lifting device* to be considered single failure proof, the design must also follow the guidance in NUREG-0612 [1.2.7], which requires that a single failure proof device have twice the normal safety margin. This designation can be achieved by either providing redundant devices or providing twice the design safety factor as required by the applicable code. Therefore, for a *lifting device* to be considered single failure proof, the applicable code requirements should be doubled, or a redundant *lifting device* should be provided. Similarly, for a *special lifting device* to be considered single failure proof, the design safety factors in ANSI N14.6 [1.2.4] should be doubled, or a redundant *special lifting device* should be provided.

4.5.1.3 Stress Criteria and Critical Load Drop Accident

Both NUREG-0612 [1.2.7] and ANSI N14.6 [1.2.4] allow for a load drop analysis to be performed. If the consequences of that analysis are below the permissible dose rate and sub-criticality limits, the increased safety factors are not required. Performing a load drop analysis is considered a code compliance analysis, and does not mean that a drop accident is necessarily considered a credible accident. The drop analysis is used to determine the appropriate stress levels reached, and if the handling devices are designed to the correct stress limits, then the drop accident is still considered non-credible.

4.5.2 Cask Transfer Building (CTB) Crane

The CTB crane is a rail-supported (gantry) load handling device located in the Cask Transfer Building (CTB). It is the principal load handling device used to lift, upend, down-end and translocate the casks & other heavy loads used inside the CTB. It is the in-CTB counterpart to

the Vertical Cask Transporter (VCT) which principally handles the transfer cask and other heavy loads outside the CTB. The Cask Crane renders the following repetitive operations:

1. Removal of the transport cask from the railcar
2. Removal of the transport cask impact limiters
3. Movement of the transport cask in and out of the CTF
4. Movement of the transport cask (empty and loaded) inside the CTB
5. The ITS designation of the crane is provided in Table 4.2.1

4.5.2.1 Structural

The CTB Crane shall be a single failure proof load handling device designed and built in accordance with the provisions of ASME NOG-1 [3.0.1].

The applicable Design Basis dead weight and seismic loadings on the CTB Crane are set down in Table 4.5.1.

- The crane shall be designed for a load capacity specified in Table 4.5.2.
- For loading conditions that exceed the duration defined as seismic-exempt, a seismic analysis of the loaded crane shall be performed in accordance with the provisions of ASME NOG-1 [3.01].

4.5.2.2 Thermal

The CTB crane does not operate in an elevated temperature environment. The design temperature of the gantry crane is conservatively specified in Table 4.5.1 to be well above the maximum ambient temperature in the CTB.

4.5.2.3 Shielding

The CTB crane does not provide a shielding function.

4.5.2.4 Confinement

The CTB crane does not provide a confinement function.

4.5.2.5 Criticality Control

The CTB crane does not perform any criticality control function.

4.5.2.6 Operational Requirements

- The crane design shall allow interfacing with all the lifting ancillaries such as MPC Lift Extension, HI-TRAC CS Lifting Device, and HI-STAR 190 Lift Yoke.
- The crane design shall provide for the ability to upend and lift the HI-STAR from the railcar.
- The crane design shall meet the requirements per Table 4.5.1 and 4.5.2.

- The crane shall meet the operational requirements per ASME NOG-1 [3.0.1].

4.5.2.7 Environmental Conditions

The ambient conditions for the crane are identical to those for the VCT summarized in Table 4.5.3. In addition, the design of the crane shall preclude materials that may degrade under the radiation from casks during the crane's service life.

4.5.2.7 Interfaces and Media Requirements

The electrical supply requirements are specified in Table 4.5.2. The crane shall have ability to receive signals from lifted equipment in order to fulfill operational requirements described in Chapter 10.

4.5.2.8 Electric Requirements

The following requirements shall be met.

The crane shall meet the electrical requirements per ASME NOG-1 [3.0.1]

- All safety relevant functions such as interlocking mechanisms, releases, selections, acceptances, and other connections shall be established via hard wire. All other functions can be realized via PLC. The operating and display elements which have no safety implications can be linked with a bus system to the PLC. The speed and torque controllers can be linked with the PLC directly via bus system. The electrical design shall be properly configured for easy maintenance.
- Phase and voltage protection shall be provided for main power feed.
- Sufficient space shall be provided for the cable routing and buses into the electrical cabinet.
- Properly sized electrical grounding conductors shall be implemented in the cable routing of the main components.

4.5.3 Vertical Cask Transporter

The Vertical Cask Transporter (VCT) is the principal load handling device used at the HI-STORE CIS ISFSI. This Subsection provides the essential design requirements that the VCT procured for the HI-STORE facility must fulfill to comply with this SAR.

The VCT is a U-shaped, tracked vehicle (also called a tracked crawler) used for handling and on-site transport of loaded and empty HI-TRAC transfer cask. The structural characteristics of the so-called "wheeled" VCT are identical and therefore are not spelled out separately. The tracked crawler configuration has been selected for the HI-STORE site because of greater in-use experience with it in the United States. Use of a wheeled crawler at a later date will require a safety evaluation pursuant to 10CFR72.48.

The VCT is used for transferring an MPC, loaded in a HI-TRAC transfer cask, at the CTF and the HI-STORM UMAX cavity. The constituent parts of the VCT are indicated in Figure 4.5.1. As shown in Figure 4.5.1, the VCT consists of the vehicle main frame, the lifting towers, an

overhead crossbeam that connects between the lifting towers, a cask restraint system, the drive system and control system, and the cask lifting attachment. The transfer cask is supported by the lifting attachments that are connected to the overhead beam (Figure 4.5.2). The overhead beam is supported at the ends by a pair of lifting towers. The lifting towers transfer the cask weight directly to the vehicle frame. The lifting towers have an independent means of affording protection against uncontrolled lowering of the load. Figure 4.5.3 illustrates the dual-path MPC handling system utilized for Canister raising or lowering operations. In summary, used in conjunction with the special lifting devices, it provides the critical lifting and handling functions associated with the canister transfer operations. The VCT is also used to transfer HI-TRAC CS from CTB to the HI-STORM UMAX ISFSI.

The ITS designation of the VCT and its constituent components is provided in Table 4.2.1.

4.5.3.1 General Design Requirements

Prevention of a cask or canister drop is afforded by design conformance with NUREG-0612 [1.2.7] and ANSI N14.6 [1.2.4] combined with the use of automatic redundant drop protection features along with hydraulic check valves and enhanced safety margins. The automatic drop protection features shall prevent an uncontrolled lowering of the load under any potential single system failure or loss of hydraulic or electric power at any time, including travel.

The VCT vehicle frame shall be designed in accordance with applicable industry standards such as ASME Section III, Subsection NF, for Class 3, linear-type supports or equivalent such as AISC [4.5.9]. The MPC downloader system shall be fully redundant and each side shall be capable of holding the entire weight of a loaded MPC (Figure 4.5.3). Overhead beam deflection shall meet the requirements of [4.5.11]

The overhead beam, lifting attachments, and MPC downloader pulley/pins and/or other attachments shall be designed in accordance with ANSI N14.6 [1.2.4] and the applicable guidance of reference, Section 5.1.6. The safety factor shall be based on the lower of $1/6^{th}$ the yield strength or $1/10^{th}$ the ultimate strength.

Jack/Lifting Towers (including top lugs connecting to overhead beam pins and the pins connecting the Lifting Towers to the frame) shall be designed in accordance with ASME Section III, Subsection NF, for Class 3, Linear-Type Supports [4.5.1] and ASME B30.1 [4.5.8] with design safety factors consistent with the guidance of [1.2.7], Section 5.1.6 (1)(a) for the specific load lifted.

The Load Drop Protection System shall be designed to meet the applicable stress limits of ASME Section III, Subsection NF, for Class 3, Linear-Type Supports using 115% of the design basis load.

The hydraulic fluids used in jacks or other hydraulic equipment shall be appropriate for use throughout the range of service temperatures listed in Table 4.5.1. The hydraulic fluids used in the cask transporter should have a flashpoint greater than or equal to 500°F per ASTM D92 [4.5.10]. Hydraulic fluids with flashpoints lower than 500°F may be used provided they are included as combustible material in the applicable fire analyses.

The Lifting Cylinders shall meet the requirements of ASME B30.1-2009 [4.5.8].High-energy hydraulic lines shall be guarded or properly secured for personnel protection to ensure no personnel injuries from whipping of a ruptured line.

4.5.3.2 Fabrication

The VCT shall be designed, fabricated, inspected, and tested in accordance with the applicable guidance of NUREG-0612 [1.2.7]. All directly loaded tension and compression members shall be engineered to satisfy the enhanced safety criteria of paragraphs 5.1.6 (1) (a) and (b) of [1.2.7]. All welding shall comply with [4.5.3] or [4.5.4]. The VCT shall be manufactured in accordance with the provisions of [4.5.5]. Slings shall comply with the provisions of [4.5.6].

4.5.3.3 Structural

The following structural requirements apply to the components comprising the HI-STORE CIS facility VCT:

i. All materials used in the design of the overhead beam and lifting towers shall be ASTM approved or equal and shall be consistent with the ITS category of the part.

ii. Prevention of a cask or canister drop is afforded by design conformance with NUREG-0612 [1.2.7] and ANSI N14.6 [1.2.4] combined with the use of automatic redundant drop protection features along with hydraulic check valves and enhanced safety margins;

iii. The VCT vehicle frame shall be designed in accordance with applicable industry standards such as ASME Section III, Subsection NF, for Class 3, linear-type supports or equivalent, or AISC [4.5.9];

iv. The overhead beam, lifting attachments, and MPC downloader pulley/pins and/or other attachments shall be designed in accordance with ANSI N14.6 [1.2.4] and the applicable guidance of NUREG-0612 [1.2.7], Section 5.1.6. The safety factor shall be based on the lower of $1/6^{th}$ the yield strength or $1/10^{th}$ the ultimate strength;

v. Jacks shall be designed in accordance with ASME Section III, Subsection NF, for Class 3, Linear-Type Supports [4.5.1] and ASME B30.1 [4.5.8] with design safety factors consistent with the guidance of NUREG-0612 [1.2.7], Section 5.1.6 (1)(a) for the specific load lifted. Multi-stage jacks may have several rated capacities based on the extension stage. The jacks' rated capacity shall be coupled with the load based on the jack configuration for the lift of the load.

vi. The applicable Design Basis dead weight and seismic loadings on the VCT are listed in Table 4.5.3. The VCT shall be shown to not tip-over under any specified service condition. The vehicle's lateral and transverse center of gravity shall be lower than the HI-TRAC's lateral and transverse center of gravity while transporting a loaded HI-STORM. Tip-over shall assume a 7% transverse grade in all modes. A national consensus standard such as ASCE 43-05 [5.4.5] shall be used for stability evaluation. The seismic restraints and their attachment points on the VCT frame shall be designed to meet the Level D stress limits of ASME Subsection NF.

4.5.3.4 Functional Requirements

The VCT shall be operated and controlled by means of a control panel. The control panel shall be suitably positioned to allow for easy access and operator visibility during cask engagement, lifting, movement, and lowering. The control panels shall be enclosed or suitably protected from weather conditions. From the operator's chair, the operator shall be able to see all gauges and indicators necessary to accurately monitor the condition of both the power source and the hydraulic system at all times. The VCT shall be equipped with a dead man's throttle.

The VCT shall be equipped with an emergency stop switch tethered to the rear of the vehicle by means of a retractable cord reel. The emergency stop switch shall be easily and sagely carried and operated by ground personnel walking behind or to either side of the VCT.

The VCT shall be equipped with flashing movement warning lights and audible alarm with a minimum 30' range.

The VCT shall be capable of being towed and secured against movement in the event that it becomes inoperable during transit.

The design shall ensure that any electrical malfunction in the control system, motors, or power supplies will not lead to an uncontrolled lowering of the load.

Portable fire extinguisher(s) meeting the requirements of NFPA 10 [4.5.7, 4.5.12].

A catch pan or a double wall fuel tank with a hose connection to route spills away from the VCT shall be mounted beneath the fuel tank.

The VCT shall be equipped with auxiliary power receptacles. Voltage, frequency, amperage ratings, and receptacle shall be specified by Holtec to meet site specific requirements.

4.5.3.5 Thermal

The VCT does not operate in an elevated temperature environment. The design temperature of the VCT is conservatively specified in Table 4.5.3 to be well above the maximum ambient temperature in the CTB, on the VCT haul path, and the ISFSI pad.

4.5.3.6 Shielding

The VCT does not provide a shielding function.

4.5.3.7 Confinement

The VCT does not provide a confinement function.

4.5.3.8 Criticality Control

The VCT does not perform any criticality control function.

4.5.3.9 Material Failure Modes

All materials used in the design of the overhead beam and lifting towers shall be ASTM approved or equal and shall be consistent with the ITS category of the part.

The material properties and allowable stress values for all structural steel members shall be taken from the applicable national consensus standard. Acceptance criteria for the Charpy testing requirements for the overhead beam, lifting towers, cask transporter lift points and MPC downloader system load bearing components shall be per ASME Section III, Subsection NF [4.5.1] or ANSI N14.6 [1.2.4]. The lowest service temperature used for developing the test parameters for Charpy testing shall be equal to 0°F for all the components mentioned above. Lateral expansion will be per Table NF-2331(a)-3 and required Cv energies shall be extrapolated from Fig. NF-2331(a)-2 for Class 3 Materials.

Fatigue failure modes of primary structural members whose failure may result in the uncontrolled lowering of the load shall be evaluated. A minimum safety factor of 2 on the number of permissible loading cycles (1000 loading cycles) for critical members shall apply.

4.5.3.10 Environmental Conditions

The ambient conditions for the VCT are summarized in Table 4.5.3. The design of the VCT shall preclude materials that may degrade under the radiation from casks during the service life.

4.5.4 Miscellaneous Ancillaries

Miscellaneous ancillaries are those weldments that are not used in a load lifting function and do not contain or in contact with fissile material. Such ancillaries do not render a confinement or criticality function. Certain ancillaries, however, are used to reduce crew dose such as tungsten screens and lead blankets. Such non-structural ancillaries are also called “accessories” because their design is guided by ALARA, not by any regulatory regimen.

The miscellaneous ancillaries are subject to mechanical loadings under any operating modes shall meet the following design criteria:

i. The Design loads and associated applicable to the ancillary under normal and accident conditions (if any) shall be defined based on its function and application.

ii. ASME Section III Subsection NF Class 3 is designated as the governing code for purposes of stress analysis of the ancillary. Specifically, Subsection NF shall be used to demonstrate:

   a. Compliance with the Code stress limits

   b. Absence of the risk of brittle fracture at low service conditions (See Table 2.7.1)

   c. Absence of elastic instability effects such as buckling

   d. Absence of the risk of fatigue failure

iii. The load rating and maximum/minimum operating temperature for the ancillary shall be marked on the ancillary.

The stress and strength tables for common materials used in the manufacturing of ancillaries have been extracted from [1.3.3] and are provided in this sub-section.

Table 4.5.1 Design Basis Loadings on the Cask Crane inside the CTB		
Item	**Value**	**Comment**
Design Basis Dead Load	200 tons	Bounds the weight of all heavy loads lifted by the crane
Operating Basis Earthquake (OBE)	See Table 4.3.3	The seismic motion is applied at the elevation of the CTB Slab
Reference temperature	150 Deg. F.	Conservative upper bound on the maximum ambient temperature

Table 4.5.2
Design Parameters for the CTB Crane

Specification	Specification Description
Component Type per ASME NOG-1-2015 [3.0.1]	Main Hoist: Type 1 Auxiliary Hoist: Type II Gantry: Type I Trolley: Type I
Service Factor	Main Hoist, Gantry, and Trolley: To meet or exceed minimum requirements as provided in ASME NOG-01 [3.0.1]; Auxiliary Hoist: CMAA 70 [4.5.2]: CMAA Class D
Material of Construction	Carbon steel frame, commercial winch and trolley components.
Main Hoist Capacity	200 ton minimum
Auxiliary Hoist	20 tons
Hook Type	Duplex (sister) hook with pin eye
Crane Speed (reference)	45 feet /min (infinitely variable speed control with minimum 30:1 speed range)
Trolley Speed (reference)	35 feet/min (infinitely variable speed control with minimum 30:1 speed range)
Main Hoist Speed (reference)	5 feet/min (infinitely variable speed control with minimum 100:1 speed range)
Auxiliary Hoist Speed (reference)	20 feet/min (infinitely variable speed control with minimum 100:1 speed range)
Operator Controls	Radio Control – To operate on Frequencies as allowed by local codes. Pendent backup with quick disconnect and full length festoon.
Main Hoist Reeving	Single Failure Proof reeving – True Vertical Lift
Auxiliary Hoist Reeving	Single or Double reeving. If double reeving is used, ropes must be equalized using an equalizer sheave or bar.
Motor Controls	Variable Frequency Drives with infinite speed control.

Table 4.5.2
Design Parameters for the CTB Crane

Specification	Specification Description
General Additional Safety Devices	1. Overload protection for critical loads and maximum capacity of each hoist. Critical load overload protection shall be field adjustable. Approximate values are provided in this document. 2. Slack Rope protection (underload) for critical loads with over-ride for lowering of the load. Settings should be field adjustable. Approximate values are provided in this document. 3. Over Speed protection for critical loads. 4. Gantry end of travel limit switches with slowdown and stop. 5. Trolley end of travel limit switches with slow down and stop. 6. Audible alarms 7. Visual alarms (lights) 8. Fail-Safe Emergency Stop (pendant, radio control, and operating floor)
Gantry Service Platform	Walkway/Service Platform mounted to one side of the crane along the entire length of the span. An entry way to be coordinated with the crane access point is to be provided for safe personnel access to the platform. All electrical control enclosures shall be serviceable from the platform.
Trolley Service Platform	Walkway/Service Platform to allow inspection and service to hoist and trolley components. Access to the platform is to be provided from the gantry platform for safe personnel access.
Gantry Bumpers	Energy absorbing bumpers sized to decelerate and stop the while traveling without power at 40% of the rated load speed at a rate of deceleration not to exceed an average of 0.91 m/s^2 (3 ft/sec^2).
Trolley Bumpers	Energy absorbing bumpers sized to decelerate and stop the while traveling without power at 50% of the rated load speed at a rate of deceleration not to exceed an average of 1.4 m/s^2 (4.7 ft/sec^2).
Lighting	LED Gantry Crane Lighting for operators and others working under the crane.
Runway Rail and End stops	As needed by Manufacturer to meet hook coverage requirements, including all fastening hardware, splices, and end-stops.

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

Table 4.5.2 Design Parameters for the CTB Crane	
Specification	**Specification Description**
Power	3 phase, 380V, 50 Hz.
Power Disconnect	Floor Mount Power Disconnect lockable in the open position
Runway Electrification	Sliding Double Shoe Collectors and Buss Bar
Coatings	ASME NOG-01 [3.0.1]; Service Level II

Table 4.5.3 Design Basis Conditions and Loadings on the Vertical Cask Transporter		
Item	**Value**	**Comment**
Design Basis Dead Load	200 tons	Bounds the weight of the loaded HI-TRAC CS along with the associated lifting hardware
Maximum Loaded MPC	110,000 lbs	Bounding weight per HI-STORM UMAX FSAR [1.0.6] Table 3.2.1
Operating Basis Earthquake (OBE)	See Table 4.3.3	The seismic motion is applied at the elevation of the Haul Path slab
Design Temperature	150 Deg. F.	Upper bound on the maximum ambient temperature
Design Life	20 years	Normal life expectancy of the VCT
Maximum permitted service temperature	125 Deg. F	Limiting environmental temperature
Minimum permitted service temperature	0 Deg. F.	Limiting environmental temperature
Relative humidity range	0 to 100%	Design Basis Relative humidity range at the site
Maximum design basis incline or grade in the haul path	10%	Used to size the engine and transmission system of the VCT
Maximum design basis lateral grade	7%	

Table 4.5.4: Design and Level A Stress

Code: **ASME NF**
Material: **SA516, Grade 70, SA350-LF3, SA203-E**
Service Conditions: **Design and Level A**
Item: **Stress**

Temp. (Deg. F)	Classification and Value (ksi)		
	S	**Membrane Stress**	**Membrane plus Bending Stress**
-20 to 650	17.5	17.5	26.3
700	16.6	16.6	24.9

Notes:

1. S = Maximum allowable stress values from Table 1A of ASME Code, Section II, Part D.
2. Stress classification per Paragraph NF-3260.
3. Limits on values are presented in Table 4.4.2.
4. Table reproduced from [1.3.3], Table 3.1.10

Table 4.5.5: Level B Allowable Stress

Code: **ASME NF**
Material: **SA516, Grade 70, SA350-LF3, and SA203-E**
Service Conditions: **Level B**
Item: **Stress**

Temp. (Deg. F)	Classification and Value (ksi)	
	Membrane Stress	Membrane plus Bending Stress
-20 to 650	23.3	34.9
700	22.1	33.1

Notes:

1. Limits on values are presented in Table 4.4.2 with allowables from Table 4.5.4.
2. Table reproduced from [1.3.3], Table 3.1.11

Table 4.5.6: Level D Stress Intensity

Code: **ASME NF**
Material: **SA516, Grade 70**
Service Conditions: **Level D**
Item: **Stress Intensity**

Temp. (Deg. F)	Classification and Value (ksi)		
	S_m	P_m	$P_m + P_b$
-20 to 100	23.3	45.6	68.4
200	23.1	41.5	62.3
300	22.5	40.4	60.6
400	21.7	39.1	58.7
500	20.5	36.8	55.3
600	18.7	33.7	50.6
650	18.4	33.1	49.7
700	18.3	32.9	49.3

Notes:

1. Level D allowable stress intensities per Appendix F, Paragraph F-1332.
2. S_m = Stress intensity values per Table 2A of ASME, Section II, Part D.
3. Table reproduced from [1.3.3], Table 3.1.12

Table 4.5.7: Design and Level A Stress

Code: **ASME NF**
Material: **SA36**
Service Conditions: **Design and Level A**
Item: **Allowable Stress**

Temp. (Deg. F)	Classification and Value (ksi)		
	S	**Membrane Stress**	**Membrane plus Bending Stress**
-20 to 650	14.5	14.5	21.8
700	13.9	13.9	20.9

Notes:

1. S = Maximum allowable stress values from Table 1A of ASME Code, Section II, Part D.
2. Stress classification per Paragraph NF-3260.
3. Table reproduced from [1.3.3], Table 3.1.19

Table 4.5.8: Level B Allowable Stress

Code: **ASME NF**
Material: **SA36**
Service Conditions: **Level B**
Item: **Allowable Stress**

Temp. (Deg. F)	Classification and Value (ksi)	
	Membrane Stress	Membrane plus Bending Stress
-20 to 650	19.3	28.9
700	18.5	27.7

Notes:

1. Table reproduced from [1.3.6, Table 3.1.20]

Table 4.5.9: Level D Stress Intensity

Code: **ASME NF**
Material: **SA36**
Service Conditions: **Level D**
Item: **Stress Intensity**

Temp. (Deg. F)	Classification and Value (ksi)		
	S_m	P_m	$P_m + P_b$
-20 to 100	19.3	43.2	64.8
200	19.3	37.0	55.5
300	19.3	36.0	54.0
400	19.3	34.7	52.1
500	19.3	32.8	49.2
600	17.7	30.0	45.0
650	17.4	29.5	44.3
700	17.3	29.2	43.8

Notes:

1. Level D allowable stress intensities per Appendix F, Paragraph F-1332.
2. S_m = Stress intensity values per Table 2A of ASME, Section II, Part D.
3. Table reproduced from [1.3.3], Table 3.1.21



FIGURE 4.5.1: VCT MAJOR COMPONENTS



FIGURE 4.5.2: VCT CARRYING A HI-TRAC TRANSFER CASK



FIGURE 4.5.3: ILLUSTRATIVE VIEW OF THE VCT OVERHEAD BEAM AND CANISTER DOWNLOADER PULLEY SYSTEM

4.6 DESIGN CRITERIA FOR THE CASK TRANSFER BUILDING (CTB)

4.6.1 Design Features of the CTB

The Cask Transfer Building (CTB) is a NITS structure at the HI-STORE CIS facility. It serves as a weather enclosure for the cask handling equipment, facilities and structures, all of which are floor mounted. The CTB Crane, summarized in Section 4.5, is a gantry crane mounted on a set of rails founded on the CTB's slab. The layout of the equipment and ancillaries in the CTB is provided in Figure 3.1.2 of Chapter 3. Chapter 10 contains the summary of the operations that are envisaged to occur in the CTB.

The CTB is a conventional sheet metal building consisting of a thick load bearing concrete slab mentioned above and a set of knee-high concrete walls which support the steel frame that serves as the backbone for the building. Corrugated sheet metal panels are fastened to the steel frame to create the lateral enclosure system. An overhead truss provides the framework to support the roof, also made of corrugated sheet metal.

The CTB is designed to the provisions of [4.6.1] and New Mexico's state and local Building Codes. The building steel (wall and roof structures) design is informed by the load combinations and criteria in IBC-2015 [4.6.4] and ASCE 7-10 [4.6.2]. While the CTB renders no safety function, it houses safety-significant equipment. Therefore, under an extreme environmental phenomenon, such as high wind, it is necessary to postulate that its roof collapses and falls on the ITS SSCs below. Table 4.6.1 provides loading data for designing the CTB walls and roof structure; this data is used in the building collapse evaluation in Chapter 5.

4.6.2 CTB Slab

The CTB is founded on a thick reinforced concrete slab whose essential design data is summarized in Table 4.6.2.

The CTB slab is designed to the following governing dead and live loads:

(i) The live load from the railroad car wheels carrying the loaded transport cask
(ii) The live load from the CTB Crane carrying the transport or the HI-TRAC CS cask
(iii) The live load from the loaded VCT (Figure 4.5.2)

The CTB slab is designed to meet the strength requirements of ACI 318-05 [5.3.1] for the following governing load combinations:

Load Combination # 1: 1.4D

Load Combination # 2: 1.2D + 1.6L

Load Combination # 3: 1.2D + L + E

where D is the dead load of the CTB slab including long-term settlement effects, L is the live load acting on the CTB slab (including weight of VCT, CTB Crane, etc.), and E is the OBE for the site.

Table 4.6.2 provides the essential design data for the CTB slab which is used in Chapter 5 to demonstrate its compliance with ACI-318 using bounding values of loadings (live and seismic).

Table 4.6.1 Reference Design Basis Loading Data for the CTB		
Item	**Value**	**Comment**
Ultimate Design Wind Speed, V_{ult}	115 mph	Used to size the wall and roof structures in Chapter 5; based on IBC 2015 Risk Category II building classification
Nominal Design Wind Speed, V_{asd}	90 mph	
Reference Weight of a CTB Roof Truss that may fall on the ITS equipment	32,400 lb	Used in the safety analysis of the ITS equipment from collapse of the CTB in Chapter 5
Design Basis Height of the CTB Roof Truss above CTB floor	66 feet (20 meters)	Used in the safety analysis of the ITS equipment from collapse of the CTB in Chapter 5

Table 4.6.2 Reference Design Data for the CTB Slab	
Item	**Reference value**
Minimum Compressive strength of concrete	4,500 psi
Min Slab thickness	36 inches
Size of re-bars in the two orthogonal directions	#11
Re-bar nominal spacing	10 inch
Minimum concrete cover on the re-bar assembly (both faces)	3 inch
Minimum thickness of the engineered fill (or mud mat) undergirding the slab	12 inch

4.7 SUMMARY OF DESIGN CRITERIA

The Design Criteria set down in this chapter seek to ensure that during any condition of storage (normal, off-normal or accident) and during canister transfer operations, the following metrics of safety will be observed:

i. The confinement boundary is not breached.

ii. There is no risk of exceeding the neutron multiplication factor limit of 0.95 including all uncertainties and biases.

iii. The temperature of the used fuel remains below the limit set forth in ISG-11, Rev. 3 [4.0.1] which insures that the fuel will not undergo any significant degradation in storage.

iv. The stresses in the primary structural members remain within the applicable ASME code limits under every condition of storage.

v. The accreted site boundary radiation dose from the storage system meets the 72.104 & 10CFR 72.106 limits for the normal and accident conditions, respectively.

vi. The occurrence of an accidental load drop event is rendered non-credible by the *use of single failure proof* lifting and handling devices.

vii. There is no risk of brittle fracture of a primary load bearing member in the storage system under all storage scenarios.

viii. There is no risk of fatigue failure in a load bearing member under all applicable storage scenarios.

ix. There is no risk of structural instability (buckling), large deformation or similar non-linear behavior in any primary load bearing member during any (normal, off-normal and accident) condition of storage.

The above criteria are fulfilled either by reference to the HI-STORM UMAX FSAR [1.0.6] or by the safety analyses performed in support of this SAR. For the latter case, the justification for relying on the safety analysis in [1.0.6] is provided.

In particular, the information presented in this chapter shows that every loading germane to long term storage of Canisters in the HI-STORM UMAX VVM at a HI-STORM UMAX ISFSI, as described in the HI-STORM UMAX FSAR [1.0.6], either equals or bounds its site-specific counterpart for the HI-STORE CIS ISFSI. Likewise, the structural margins of safety in the short-term operations involving the HI-STAR transfer cask have been quantified in the HI-STORM UMAX FSAR for a much stronger seismic event than the Design Basis Earthquake (10,000 year return earthquake) applicable to the HI-STORE site. Finally, the Design Criteria set down in Chapter 4 of this SAR for the non- certified SSCs such as the vertical cask transporter, gantry crane and special lifting devices are identical to those specified for such components in other HI-STORM dockets [1.3.3, 1.3.7].

Therefore, the safety analyses for all aspects of safe deployment and storage of HI-STORM UMAX at the HI-STORE site, including structural, criticality, thermal and confinement are

substantially pre-empted by the qualifications in the HI-STORM UMAX FSAR making a re-evaluation for HI-STORE unnecessary. The only exceptions are:

i. The site boundary dose qualification which must be performed to demonstrate compliance with the 10CFR72.104 dose limits under the maximum fuel inventory scenario, i.e., when every storage location in the ISFSI is occupied.

ii. The temperature of the fuel within the stored canister at the HI-STORE ISFSI will meet the normal storage condition limit of ISG-11, Rev. 3. This analysis is required because the high altitude of the ISFSI (Table 2.7.1) reduces the air ventilation rate. The maximum heat load, however, is limited by the rating of the transport cask which is substantially less than the thermal capacity of HI-STORM UMAX licensed by the USNRC (Docket # 72-1040). Therefore, the ISG temperature limit is expected to be met with a large margin. Nevertheless, to support the safety case, this margin is quantified in Chapter 6.

In addition, a new transfer cask, named HI-TRAC CS has been introduced in this docket. While the design of this transfer cask is similar to the other HI-TRAC models certified in other HI-STORM dockets, viz. [1.0.6, 1.3.3, 1.3.7], there are sufficient physical differences to warrant a safety analysis of HI-TRAC CS to be performed. The applicable design criteria for such analyses are provided in this chapter.

Finally, all ancillaries must meet the design criteria presented in Section 4.5.

APPENDIX 4.A: [PROPRIETARY APPENDIX WITHHELD IN ITS ENTIRETY IN ACCORDANCE WITH 10CFR2.390]

CHAPTER 5: INSTALLATION AND STRUCTURAL EVALUATION*

5.0 INTRODUCTION

The HI-STORE CIS facility utilizes the subterranean canister storage system referred to as HI-STORM UMAX certified in NRC Docket #72-1040 [1.0.6]. As the safety determination in this chapter shows, from the structural standpoint, the HI-STORM UMAX design can be adopted in its entirety from its native docket for the HI-STORE CIS facility without the need for any modification. The basis for this adoption, as elaborated in this chapter, is supported by the existing structural qualifications of the HI-STORM UMAX system that have been previously reviewed by the NRC and which *uniformly* bound all HI-STORE CIS site-specific loadings.

However, while the safety analyses for HI-STORM UMAX can be adopted for HI-STORE, that is not the case for the ancillary systems, structures and components (SSCs) needed to operate the facility. These ancillaries are listed and their operational roles are summarized in Subsection 1.2.7. In this chapter, the structural safety qualification of each ancillary envisaged to be used at HI-STORE CIS, showing its compliance with its Design Criteria (presented in Chapter 4), is documented. The computed design margin for the ancillary SSCs under their respective design basis loads along with the safety analyses in the HI-STORM UMAX FSAR for the certified storage system underpins the safety case for the HI-STORE site.

The HI-STORM UMAX system as licensed in Docket # 72-1040 allows for a variable depth canister storage cavity to accommodate canisters of different heights. At the HI-STORE CIS site, all the storage cavities will be built to the same fixed depth, which is within the design limits of the licensed HI-STORM UMAX system. The structural qualification of HI-STORM UMAX in Docket # 72-1040 is based on the tallest and heaviest MPC-37 canisters (South Texas) because they define the bounding inertia loads. The Licensing Drawings in Section 1.5 of this SAR contain the depictions of the fixed depth HI-STORM UMAX cavity adapted from Docket #72-1040. For structural purposes, the deepest cavity to store the longest and heaviest canister defines the governing configuration. In Table 5.0.1, a comparison of the Design Basis Loads (DBLs) in its generic FSAR [1.0.6] and their site specific loading counterparts is presented to demonstrate that the Design Basis structural loads bound the site specific loads (SSLs) *in every instance.* Therefore, fresh qualifying analyses for the storage system at the HI-STORE installation, in addition to those in [5.4.7], are not necessary.

The bounding weights for the various dry cask storage components and ancillary equipment used at the HI-STORE CIS facility are listed in Table 5.0.2.

Finally, to facilitate convenient access to the referenced material, a list of sections germane to this chapter is provided in a tabular form. Table 5.0.3 provides a listing of the material adopted in this chapter by reference from other licensed dockets.

* All references are placed within square brackets in this report and are compiled in Chapter 19 of this report.

Table 5.0.1: Comparison of DBLs for HI-STORM UMAX System and Site-Specific Loads for HI-STORE CIS Facility		
Load Category	Design Basis Value	Site-Specific Value
Earthquake	Top of the Grade (Ground surface) spectra per Figure 2.4.1 of [1.0.6] with horizontal ZPA, a_H, and vertical ZPA, a_V scaled as follows: $a_H = 1.0g$ $a_V = 0.75g$ and foundation surface pad spectra per Figure 2.4.2 of [1.0.6] with horizontal ZPA, a_H, and vertical ZPA, a_V of: $a_H = 0.93g$ $a_V = 0.71g$	Top of the Grade spectra corresponding to 5% damped RG 1.60 earthquake [4.3.2] scaled to 0.25g (bounding) in three orthogonal directions (see Table 4.3.3)
Tornado	Per Table 2.3.4 of [1.0.6]	Consistent with NRC Regulatory Guide 1.76 [2.7.1], ANSI 57.9 [2.7.2], and ASCE 7-05 [4.6.1]
Flood	Floodwater depth of 125 feet.	Floodwater depth less than 1 foot
Snow Load	100 psf	See Chapter 2

Table 5.0.2: Bounding Weights for Cask Components and Ancillary Equipment	
Component	Bounding Weight, lbf
Loaded MPC	110,000
HI-TRAC CS Transfer Cask - Empty - Loaded with MPC	[PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]
HI-STAR 190 Transport Cask - Empty w/o Impact Limiters - Loaded w/o Impact Limiters - Loaded w/ Impact Limiters	 261,000 371,000 414,800
HI-TRAC CS Lift Yoke	[PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]
Transport Cask Lift Yoke	
Transport Cask Horizontal Lift Beam	
Transport Cask Tilt Frame	
MPC Lift Attachment	
MPC Lifting Device Extension	
HI-TRAC CS Lift Links (set of 2)	
VCT	
Notes: 1) All structural analyses presented in Chapter 5 use the bounding weights per this table as input. Higher values may be used for additional conservatism. 2) Assumed based on standard tracked crawler design used at various nuclear plants in U.S.	

Table 5.0.3: Material Incorporated by Reference in this Chapter			
Information Incorporated by Reference	**Source of the Information**	**Location in this SAR where Material is Incorporated**	**Technical Justification of Applicability to HI-STORM UMAX at HI-STORE CIS**
MPC-37 and MPC-89 Structural Evaluation	Section 3.4 HI-STORM FW FSAR [1.3.7]	Subsection 5.1.4	The canister is identical to the one described in the HI-STORM FW FSAR and originally approved in the referenced FSAR.
HI-STORM UMAX ISFSI Pad and SFP Structural Evaluation	Paragraph 3.4.4.1 HI-STORM UMAX FSAR [1.0.6]	Paragraph 5.3.1.4	The ISFSI Pad and SFP are identical to that described in HI-STORM UMAX FSAR and originally approved in the referenced FSAR. Also, the Design Basis Loads for the HI-STORM UMAX bound the site-specific loads applicable to the HI-STORE site as shown in Table 5.0.1.
HI-STORM UMAX VVM Structural Evaluation	Paragraph 3.4.4.1 HI-STORM UMAX FSAR [1.0.6]	Paragraph 5.4.1.4	The HI-STORM UMAX VVM is identical to that described in HI-STORM UMAX FSAR and originally approved in the referenced FSAR. Also, the Design Basis Loads for the HI-STORM UMAX bound the site-specific loads applicable to the HI-STORE site as shown in Table 5.0.1.

5.1 CONFINEMENT STRUCTURES, SYSTEMS, AND COMPONENTS

The only confinement SSC that is utilized at the HI-STORE CIS facility is the Multi-Purpose Canister (MPC). There are two types of MPCs that are permitted to be stored at the HI-STORE site, namely MPC-37 and MPC-89, both of which have been previously licensed by the NRC as part of the HI-STORM FW dry storage system (Docket # 72-1032). The structural design basis for MPC-37 and MPC-89, which are used to store PWR and BWR fuel, respectively, are described in complete detail in Chapters 2 and 3 of the HI-STORM FW FSAR [1.3.7]. A brief summary of their structural design basis is provided below.

5.1.1 Description of Structural Design

The MPC enclosure vessels are cylindrical weldments with identical and fixed outside diameters. Each MPC is an assembly consisting of a honeycomb fuel basket, a baseplate, a canister shell, a lid, and a closure ring. The number of SNF storage locations in an MPC depends on the type of fuel assembly (PWR or BWR) to be stored in it. The required characteristics of the fuel assemblies to be stored in the MPC are limited in accordance with Section 4.1 of the SAR.

The MPC enclosure vessel is a fully welded enclosure, which provides the confinement for the stored fuel and radioactive material. The MPC baseplate and shell are made of stainless steel. The lid is a two-piece construction, with the top structural portion made of Alloy X. The confinement boundary is defined by the MPC baseplate, shell, lid, port covers, and closure ring. Drawings for the MPCs are provided in Section 1.5.

The MPC-37 and MPC-89 fuel baskets are assembled using interlocking Metamic-HT panels, as shown in the Licensing Drawings in Section 1.5.

5.1.2 Design Criteria

The MPC is classified as important-to-safety. The MPC structural components include the fuel basket and the enclosure vessel. The MPC enclosure vessel is designed and fabricated as a Class 1 pressure vessel in accordance with Section III, Subsection NB of the ASME Code, with certain necessary alternatives, as discussed in Section 2.2 of [1.3.7]. The MPC fuel basket is a non-Code

Compliance with the ASME Code, with respect to the design and fabrication of the MPC, and the associated justification are discussed in Section 2.2 of [1.3.7]. The MPC design is analyzed for all design basis normal, off-normal, and postulated accident conditions, as defined in Section 2.2 of [1.3.7], which bound the conditions at the HI-STORE site.

5.1.3 Material Properties

The MPC shell, baseplate and lid are made of stainless steel (Alloy X, see Appendix 1.A of [1.3.7]). The properties for Alloy X are listed in Table 3.3.1 of the HI-STORM FW FSAR [1.3.7]. The minimum strength properties for Metamic-HT, which is used to fabricate the fuel baskets, are provided in Table 1.2.8 of the HI-STORM FW FSAR [1.3.7].

5.1.4 Structural Analyses

The structural analyses for the MPC for all design basis normal, off-normal, and postulated accident conditions are documented in Chapter 3 of the HI-STORM FW FSAR [1.3.7] and further supplemented by the seismic response analysis of the MPC inside the HI-STORM UMAX presented in Subparagraph 3.4.4.1.2 of the HI-STORM UMAX FSAR [1.0.6].

5.2 POOL AND POOL CONFINEMENT FACILITIES

There are no pools at the HI-STORE CIS facility.

5.3 REINFORCED CONCRETE STRUCTURES

The HI-STORE CIS facility includes the following reinforced concrete structures:

- HI-STORM UMAX ISFSI Pad and Support Foundation Pad (SFP)
- Cask Transfer Building (CTB) Slab
- Canister Transfer Facility (CTF) Foundation

Each of these components is discussed in more detail, including their description, design criteria, material properties, and structural analyses, in the following subsections.

5.3.1 HI-STORM UMAX ISFSI Pad and Support Foundation Pad

5.3.1.1 Description of Structural Design

The HI-STORM UMAX ISFSI pad and Support Foundation Pad (SFP) are integral parts of the HI-STORM UMAX underground dry storage system, which has already been licensed in accordance with 10CFR72 requirements under NRC Docket # 72-1040. As described in Section 1.2 of this SAR, the structural performance objectives for the ISFSI pad are to provide a riding surface for the cask transporter and to serve as a missile barrier. The SFP is the foundation mat for the HI-STORM UMAX structure, and it also serves as the resting surface for the VVM array. As shown on the Licensing Drawing in Section 1.5, the SFP is a continuous concrete pad of uniform thickness, whereas the ISFSI pad fills the interstitial space between the VVM at the top of grade level.

5.3.1.2 Design Criteria

The SFP and the ISFSI pad are categorized as important-to-safety (ITS) structures as indicated in Table 4.2.1. ACI 318-05 [5.3.1] is specified as the reference code for the design qualification of the SFP and the ISFSI pad using the load combinations specified in Table 2.4.3 of [1.0.6].

5.3.1.3 Material Properties

The ISFSI pad and SFP are reinforced concrete structures with their properties defined in Table 2.3.2 of the HI-STORM UMAX FSAR [1.0.6].

5.3.1.4 Structural Analysis

The seismic and structural qualification of the HI-STORM UMAX storage system, including the ISFSI pad and SFP, is performed in Chapter 3 of [1.0.6]. As shown in Table 5.0.1 above, the design basis loads analyzed in the HI-STORM UMAX FSAR completely bound the site-specific loads applicable to the HI-STORE site, and therefore no new structural analysis is required to qualify the ISFSI pad or the SFP for this application.

5.3.2 Cask Transfer Building Slab

5.3.2.1 Description of Structural Design

The Cask Transfer Building (CTB) slab is a reinforced concrete slab, which serves as the structural foundation for the railway and the CTB Crane, provides a riding surface for the VCT inside the CTB, and acts as laydown area for the HI-TRAC CS and other ancillary equipment. The general layout and key dimensions of the CTB slab are shown on the Licensing Drawing in Section 1.5.

5.3.2.2 Design Criteria

The structural design criteria for the CTB slab, including the governing load combinations, are provided in Subsection 4.6.2 of this SAR.

5.3.2.3 Material Properties

The material properties for the CTB slab are summarized in Table 5.3.1.

5.3.2.4 Structural Analysis

The analysis of the CTB slab is carried out using classical solutions for a slab on grade, which are obtained from [5.3.2], to determine the internal forces and moments acting on the CTB slab for the governing load combinations in Subsection 4.6.2.

The analysis of the slab considers the live loads associated with the freestanding HI-TRAC CS, the VCT, the CTB crane, the tilt frame (loaded with HI-STAR 190 with impact limiters), and the loaded rail car. The load acting on the CTB slab due to the CTB crane and the rail car are applied as concentrated forces at the wheel locations. The VCT load is applied as a uniform distributed pressure over the footprint area of its tracks/wheels. The load on the tilt frame assembly is also applied as a uniformly distributed pressure.

For the seismic load combination, the weight of each component (e.g., VCT) is amplified by the vertical ZPA for the Design Basis Earthquake (DBE), which is given in Table 4.3.3. The use of the ZPA value is justified since the DBE is a low-intensity earthquake that does not cause any of the above mentioned equipment to rock/uplift (i.e., no incipient tipping).

The calculated results for each load combination are compared with the ACI Code compliant section capacities to demonstrate the structural adequacy of the CTB slab. All calculated safety factors for the CTB slab are greater than 1.0 as shown in Table 5.3.2. The complete details of the CTB slab analysis are provided in the Structural Calculation Package [5.4.6].

5.3.3 Canister Transfer Facility Foundation

5.3.3.1 Description of Structural Design

The Canister Transfer Facility (CTF) is a below-ground structure used to carry out vertical MPC transfers from the transport cask to the HI-TRAC CS (or vice versa). The design enables a transport cask to be lowered into the CTF cavity (see Figure 3.1.1 (g)). With the transport cask in place, the HI-TRAC CS is then positioned above the CTF cavity opening and anchor bolts are installed to secure the HI-TRAC CS to the CTB slab at the CTF location, after which the MPC

can be vertically lifted from the transport cask into the HI-TRAC CS using the VCT. The general layout and key dimensions of the CTF are shown on the Licensing Drawing in Section 1.5.

At the base of the CTF cavity is a reinforced concrete slab that acts as the supporting surface for the transport cask during transfer operations. This below-grade slab is referred to as the CTF foundation, and its construction is identical to the CTB slab with respect to thickness, strength, and reinforcement details.

5.3.3.2 Design Criteria

The design criteria for the CTF foundation, which is an ITS component, are the same as the criteria for the CTB slab, which are provided in Subsection 4.6.2.

5.3.3.3 Material Properties

The material properties for the CTF foundation are identical to those for the CTB slab, which are given in Table 5.3.1.

5.3.3.4 Structural Analysis

The results for the structural analysis of the CTB slab, which are discussed above in Paragraph 5.3.2.4, are also bounding for the CTF foundation for the following reasons:

a) The construction of the CTB slab and the CTF foundation are identical in terms of their thickness, reinforcement details, and minimum strength properties.

b) The bounding weight of a loaded HI-TRAC CS (which rests vertically on the CTB slab), used in the structural evaluation [5.4.6], is greater than the bounding weight of a loaded HI-STAR 190 transport cask without impact limiters (which rests vertically on CTF foundation). See Table 5.0.2 for bounding weight comparison.

c) The contact footprint of the HI-TRAC CS alignment shield ring is smaller than that of the HI-STAR 190 bottom forging. The outer diameter is nearly equal but the alignment shield ring is an annular ring whereas the HI-STAR 190 bottom forging is a solid cylinder.

Based on the above, the minimum calculated safety factor for the CTB slab given in Table 5.3.2 is also a lower bound safety factor for the CTF foundation.

Table 5.3.1: Material Properties for CTB Slab & CTF Foundation	
Description	Value
Min. concrete compressive strength	4,500 psi
Min. rebar yield strength	60 ksi
Rebar size and spacing	See Licensing Drawing

Table 5.3.2: Key Results of CTB Slab Analysis			
Item	Max. Demand	Capacity	Safety Factor
Bending moment in CTB slab (kip-ft)	14,680	28,679	1.95
Shear force in CTB slab (kip)	2,011	3,899	1.94
Bearing load on CTB slab (kip)	304	383	1.26
Punching shear in CTB slab (kip)	304	1,093	3.60
Notes: 1) Reported values are worst-case results from all three load combinations (see Subsection 4.6.2).			

5.4 OTHER SSCs IMPORTANT TO SAFETY

The HI-STORE CIS facility includes the following other SSCs that are classified as important to safety:

- HI-STORM UMAX Vertical Ventilated Module (VVM)
- HI-TRAC CS
- Cask Transfer Building Crane
- Transport Cask Lift Yoke
- MPC Lift Attachment
- Special Lifting Devices

Each of these components is discussed in more detail, including their description, design criteria, material properties, and structural analyses, in the following subsections.

5.4.1 HI-STORM UMAX VVM

5.4.1.1 Description of Structural Aspects

The HI-STORM UMAX VVM is a central component of the HI-STORM UMAX dry storage system, which has been previously licensed in accordance with 10CFR72 requirements under NRC Docket # 72-1040. The VVM provides for storage of the MPC in a vertical configuration inside a subterranean cylindrical cavity entirely below the top-of-grade (TOG) of the ISFSI pad. The VVM is comprised of the Cavity Enclosure Container (CEC) and the Closure Lid, which are both shown on the Licensing Drawing in Section 1.5. A full description of the VVM, including its subcomponents, is provided in Section 1.2 of the HI-STORM UMAX FSAR [1.0.6]. The HI-STORM UMAX VVM is licensed as a variable height system in [1.0.6]. For the HI-STORE CIS facility, however, there will be one uniform depth for all VVMs as shown on the Licensing Drawing in Section 1.5. The HI-STORM UMAX FSAR also provides for multiple design options with respect to the seismic restraints and the closure lid design. The specific set of options selected for the HI-STORE CIS facility are shown on the Licensing Drawing in Section 1.5. This design variant of the HI-STORM UMAX, which is to be deployed at the HI-STORE CIS facility, is referred to as the HI-STORM UMAX Version C.

5.4.1.2 Design Criteria

To serve its intended function, the HI-STORM UMAX VVM, including the CEC and Closure Lid, shall ensure physical protection, biological shielding, and allow the retrieval of the MPC under all conditions of storage (10 CFR 72.122(l)). Because the VVM is an in-ground structure, drops and tip-over of the VVM are not credible events and, therefore, do not warrant analysis. The design bases and criteria for the VVM are fully defined in Chapter 2 of the HI-STORM UMAX FSAR [1.0.6]. The load cases germane to establishing the structural adequacy of the VVM pursuant to 10 CFR 72.24(c) are compiled in Table 2.4.1 of [1.0.6].

5.4.1.3 Material Properties

The material properties for the VVM are provided in Section 3.3 of the HI-STORM UMAX FSAR [1.0.6] in conjunction with the Licensing Drawing in Section 1.5.

5.4.1.4 Structural Analysis

The design basis structural analyses for the VVM for all applicable normal, off-normal, and accident loadings are presented in Chapter 3 of the HI-STORM UMAX FSAR [1.0.6]. As shown in Table 5.0.1 above, the design basis loads analyzed in the HI-STORM UMAX FSAR completely bound the site-specific loads applicable to the HI-STORE site, and therefore minimal structural analyses are required to qualify the VVM for this application.

The only loading event for the VVM that is not generically analyzed in the HI-STORM UMAX FSAR is a postulated earthquake during MPC transfer operations at the VVM, wherein the HI-TRAC CS is vertically stacked on top of the VVM and securely fastened in place at four anchor bolt locations. The analysis of this stack-up configuration is performed herein using the time history analysis method implemented in LS-DYNA [5.4.2]. The finite element model used for this analysis is shown in Figure 5.4.1.

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

5.4.2 HI-TRAC CS

5.4.2.1 Description of Structural Aspects

The HI-TRAC CS is a steel and concrete transfer cask, which is used for all on-site canister transfers. It has a cylindrical body delimited by carbon steel inner and outer shells with densified concrete occupying the space between the shells. The HI-TRAC CS has two trunnions near the top of the cask for lifting, and two rotation trunnions near its base for upending (or down ending) the cask. The bottom lid of the HI-TRAC CS, which is also referred to as the shield gate, is split into two halves such that they can be slid open in a symmetric manner to allow the MPC to pass through the opening (see Figure 1.2.3a). A complete description of the HI-TRAC CS is provided in Subsection 1.2.4.

5.4.2.2 Design Criteria

The design criteria for the HI-TRAC CS, which is an ITS component, are fully provided in Subsection 4.3.3.

The structural steel components of the HI-TRAC CS are designed to meet the stress limits of Section III, Subsection NF of the ASME Code [4.5.1] for all operating modes. The embedded trunnions for lifting and handling of the transfer cask are designed in accordance with the requirements of NUREG-0612 [1.2.7] for interfacing lift points.

Table 4.3.4 lists the loading scenarios for HI-TRAC CS for which its structural qualification must be performed.

5.4.2.3 Material Properties

The fabrication materials for the HI-TRAC CS are the same as those for the HI-STORM FW and the HI-TRAC VW. Therefore, the material properties for the HI-TRAC CS can be obtained from the summary tables in Section 3.3 of the HI-STORM FW FSAR [1.3.7], which are sourced from the Section II, Part D of ASME Code [4.6.3].

5.4.2.4 Structural Analysis

The loads on the HI-TRAC CS that are structurally significant are listed in Table 4.3.4, and the structural analysis for each of these loads is described below.

5.4.2.4.1 Lifting Analysis

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

The results for the above lifting analyses are summarized in Table 5.4.2, which shows that all calculated stresses are less than their applicable stress limits. The complete details of the HI-TRAC CS lifting analysis are provided in the Structural Calculation Package [5.4.6].

5.4.2.4.2 Seismic Analysis at CTF

The seismic analysis of the HI-TRAC CS while it is mounted atop a HI-STORM UMAX VVM is discussed in Subsection 5.4.1.4, and the results are summarized in Table 5.4.1. The anchorage design used to secure the HI-TRAC CS to the CTF is the same design used to anchor the HI-TRAC CS at a HI-STORM UMAX VVM location. The only difference between stack-up configurations at the CTF versus the HI-STORM UMAX VVM is the anchor bolts used to secure the HI-TRAC CS are longer for the latter configuration. The longer free length of the bolts introduces more flexibility into the system, which in turn may lead to larger rocking displacements and internal loads acting on the stack under seismic conditions. In light of this, plus the fact that the stack-up analysis for the HI-STORM UMAX VVM is conservatively performed using the most limiting earthquake condition (i.e., DECE), the results for the HI-TRAC CS in Table 5.4.1 are also bounding for the stack-up configuration at the CTF.

5.4.2.4.3 Tornado Missile Analysis

When the HI-TRAC CS is in use at the HI-STORE site, it is potentially exposed to tornado generated missiles. Although the threat of a tornado is relatively low at the HI-STORE site (see Section 2.3), the HI-TRAC CS is conservatively analyzed for the same tornado missiles as previously analyzed for the HI-STORM FW system and the HI-STORM UMAX system. These bounding tornado missiles are listed in Table 2.7.2.

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

The complete details of the tornado missile analysis are provided in the Structural Calculation Package [5.4.6].

5.4.2.4.4 Seismic Stability Analysis of Freestanding HI-TRAC CS

The general stability of a freestanding HI-TRAC CS (empty and fully loaded) under the SSE is evaluated for the possibility of incipient tipping and sliding, where simple dynamic equations are formulated based on force and moment equilibrium. Table 5.4.7 summarizes both the bounding parameters used as input to the seismic stability analysis and the results. As seen from the table, the cask does not uplift or slide under the SSE event. A similar analysis has also been performed for the HI-STAR 190, and the results are likewise summarized in Table 5.4.7.

5.4.2.4.5 CTB Collapse Analysis

As discussed in Section 4.6.1, the walls and roof structure of the CTB are designed to meet the requirements of IBC [4.6.4] and ASCE 7-10 [4.6.2], and they are designated as not important to safety (NITS). This means that they are not designed to withstand seismic or tornado loads. Therefore, HI-TRAC CS (as well as HI-STAR 190) has been structurally analyzed to evaluate the damage due to a potential building collapse. [

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

The complete details of the CTB collapse analysis are provided in the Structural Calculation Package [5.4.6].

5.4.2.4.6 Fatigue Evaluation

The HI-TRAC CS will be used repeatedly at the HI-STORE CIS facility to transfer canisters from arriving transport casks to VVM storage cavities. As a result, the HI-TRAC CS will be subject to both thermal and mechanical cyclic loading, which must be evaluated from a fatigue life standpoint. A fatigue life evaluation for all load bearing members of HI-TRAC CS has been performed in [5.4.6], and the results are presented in Table 5.4.8. The maximum stress in the trunnions is conservatively set at the allowable stress limit per [1.2.7] times a stress

concentration factor of 4.0 for the material. The use of stress concentration factor of 4.0 is consistent with HI-STAR 100 SAR [1.3.5]. The maximum stress in all other load bearing members of HI-TRAC CS, designed to stress limits in [4.5.1], is conservatively set at the ultimate strength of the material. The fatigue life of all load bearing materials is calculated by comparing the maximum stress value with the material cycle life curves defined in Appendix I of ASME Code [17.3.2]. A safety factor of 2.0 on the permissible loading cycles is imposed for additional conservatism per Subsection 4.5.3.9.

5.4.3 Cask Transfer Building Crane

5.4.3.1 Description of Structural Aspects

The Cask Transfer Building (CTB) Crane consists of a gantry crane, trolley, and hoist(s). The CTB Crane is electrically driven and rides on crane rails, which are mounted to the CTB slab in the Cask Receiving Area. The trolley rides on crane rails mounted to the top of the crane girders and has at least one electric wire rope hoist for load lifting. The hoist hook will be used to lift various loads and shall interface with the required rigging and below the hook lifting devices as required for the process. Figure 3.1.1 (b-c) is an illustration of the CTB Crane loading/unloading a transport package to/from a transport vehicle.

5.4.3.2 Design Criteria

The CTB Crane shall be a single failure proof load handling device designed and built in accordance with the provisions of ASME NOG-1 [3.0.1]. The design criteria and operational requirements for the CTB Crane are further discussed in Subsection 4.5.2 of this SAR.

The applicable Design Basis loadings on the CTB Crane are set down in Table 4.5.1.

5.4.3.3 Structural Analysis

The structural analysis of the CTB Crane shall demonstrate compliance with the applicable requirements of ASME NOG-1 for the specified loadings in Table 4.5.1.

5.4.4 Transport Cask Lift Yoke

5.4.4.1 Description of Structural Aspects

The Transport Cask Lifting Device is used to lift the HI-STAR 190 transport cask inside the CTB. As shown on the Licensing Drawing in Section 1.5, the Transport Cask Lifting Device has two lift arms that connect to the pair of lifting trunnions on the HI-STAR 190 and a main strongback assembly that connects to the CTB Crane hook.

5.4.4.2 Design Criteria

The design criteria that apply to lifting devices are fully described in Section 4.5. The Transport Cask Lift Yoke is a non-redundant special lifting device, which is designed to meet the increased safety factors per ANSI N14.6 [1.2.4].

5.4.4.3 Material Properties

As shown on the Licensing Drawing in Section 1.5, the major structural components of the Transport Cask Lift Yoke are the strongback plates, the lift arms, the actuator plates, the main

pins, and the actuator pins. The strongback plates, lift arms, and actuator plates are fabricated from high-strength alloy steel (A514 or equivalent). The main pins and actuator pins are fabricated from hardened nickel alloy bar material (SB-637 N07718). The minimum strength properties for these components are obtained directly from the applicable ASTM specification or from Section II, Part D of the ASME Code [4.6.3].

5.4.4.4 Structural Analysis

The load bearing members of the Transport Cask Lift Yoke are analyzed using a combination of formulae from ASME BTH-1 [5.4.3] and strength of materials principles. The lifted load considered in the analysis is equal to the bounding weight of the loaded HI-STAR 190 transport cask from Table 5.0.2. The lifted load and the self-weight of the lifting device are further amplified by 15% to account for dynamic effects in accordance with the guidance in CMAA-70 [4.5.2] for low speed lifts. The results of the structural analysis for the Transport Cask Lift Yoke are summarized in Table 5.4.4, which shows that all calculated safety factors are greater than 1.0. The complete details of the structural analysis of the Transport Cask Lift Yoke are provided in the Structural Calculation Package [5.4.6].

5.4.5 MPC Lift Attachment

5.4.5.1 Description of Structural Aspects

The MPC Lift Attachment is a one-piece lifting device (or lug) that is bolted directly to threaded anchor locations on the top surface of the MPC closure lid using a total of eight bolts (see Licensing Drawing in Section 1.5). The MPC Lift Attachment allows raising or lowering of the MPC during canister transfer operations using either the CTB Crane or the VCT.

5.4.5.2 Design Criteria

The design criteria that apply to lifting devices are fully described in Section 4.5. The MPC Lift Attachment is a non-redundant special lifting device, which is designed to meet the increased safety factors per ANSI N14.6 [1.2.4].

5.4.5.3 Material Properties

As described above, the MPC Lift Attachment consists of the lifting lug and eight attachment bolts. The lifting lug is fabricated from an alloy steel forging (A336-F6NM). The attachment bolts are fabricated from hardened nickel alloy bar material (SB-637 N07718). The minimum strength properties for these components are obtained directly from the applicable ASTM specification or from Section II, Part D of the ASME Code [4.6.3].

5.4.5.4 Structural Analysis

The load bearing members of the MPC Lift Attachment are analyzed using strength of materials principles together with formulae from ASME BTH-1 [5.4.3]. The lifted load considered in the analysis is equal to the bounding weight of a loaded MPC from Table 5.0.2. The lifted load and the self-weight of the lifting device are further amplified by 15% to account for dynamic effects in accordance with the guidance in CMAA-70 [4.5.2] for low speed lifts. The results of the structural analysis for the MPC Lift Attachment are summarized in Table 5.4.5, which shows that all calculated safety factors are greater than 1.0. The complete details of the structural analysis of the MPC Lift Attachment are provided in the Structural Calculation Package [5.4.6].

5.4.6 Other Special Lifting Devices

5.4.6.1 Description of Structural Aspects

In addition to the Transport Cask Lift Yoke and MPC Lift Attachment discussed in the preceding subsections, there are other special lifting devices that will be used to connect the cask or canister to the CTB Crane or VCT at the HI-STORE CIS facility. These other special lifting devices include:

- HI-TRAC CS Lift Yoke
- HI-TRAC CS Lift Link
- Transport Cask Horizontal Lift Beam
- MPC Lifting Device Extension

All special lifting devices that will be used at the HI-STORE CIS facility are shown on the Licensing Drawings in Section 1.5.

5.4.6.2 Design Criteria

The design criteria that apply to lifting devices are fully described in Section 4.5. Special lifting devices are designed to meet the increased safety factors per ANSI N14.6 [1.2.4].

5.4.6.3 Material Properties

The fabrication materials for the special lifting devices listed above are specified on the Licensing Drawings in Section 1.5. The minimum strength properties for these materials are obtained directly from the applicable ASTM specification or from Section II, Part D of the ASME Code [4.6.3] in accordance with the Licensing Drawings.

5.4.6.4 Structural Analysis

5.4.6.4.1 Lifting Analysis

The load bearing members of special lifting devices are analyzed using a combination of methods, including the finite element approach, formulae from ASME BTH-1 [5.4.3], and strength of materials principles. The lifted loads considered in the analyses are equal to the bounding weights of the loaded HI-STAR 190 transport cask, the loaded MPC, or the loaded HI-TRAC CS from Table 5.0.2, as applicable. The lifted load and the self-weight of the lifting device are further amplified by 15% to account for dynamic effects in accordance with the guidance in CMAA-70 [4.5.2] for low speed lifts. The minimum calculated safety factors for the special lifting devices, other than the Transport Cask Lift Yoke and the MPC Lift Attachment, are summarized in Table 5.4.6. The complete details of the structural analysis of the special lifting devices are provided in the Structural Calculation Package [5.4.6].

5.4.6.4.2 Fatigue Evaluation

The special lifting devices will be used repeatedly at the HI-STORE CIS facility to transfer canisters from arriving transport casks to VVM storage cavities. As a result, the special lifting devices will be subject to both thermal and mechanical cyclic loading, which must be evaluated from a fatigue life standpoint. A fatigue life evaluation for all special lifting devices has been

performed in [5.4.6], and the results are presented in Table 5.4.9. The maximum stress in the special lifting devices is conservatively set at the allowable stress limit per [1.2.4] times a stress concentration factor of 4.0 for the material. The use of stress concentration factor of 4.0 is consistent with HI-STAR 100 SAR [1.3.5]. The fatigue life of all load bearing materials is calculated by comparing the maximum stress value with the material cycle life curves defined in Appendix I of ASME Code [17.3.2]. A safety factor of 2.0 on the permissible loading cycles is imposed for additional conservatism per Subsection 4.5.3.9.

Table 5.4.1: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Table 5.4.2: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Table 5.4.3: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Table 5.4.4: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Table 5.4.5: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Table 5.4.6: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Table 5.4.7: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Table 5.4.8: Fatigue Life of HI-TRAC CS	
Item	Maximum Number of Loading Cycles
Lifting Trunnions (SB-637 N07718)	8,000
Lifting Trunnions (SB-637 N07718)	7,500
Inner Shell, Outer Shell and Other Load Bearing Members	6,000

Table 5.4.9: Fatigue Life of Lifting Ancillaries	
Item	Maximum Number of Loading Cycles
HI-TRAC CS Lift Yoke	3,500
Transport Cask Lift Yoke	3,500
Horizontal Lift Beam for Transport Cask	3,500
MPC Lift Attachment	3,500
MPC Lift Attachment Connector	3,500
HI-TRAC CS Lift Links	70,000

Figure 5.4.1: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 5.4.2: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 5.4.3: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 5.4.4: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 5.4.5: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 5.4.6: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

5.5 OTHER SSCs

The HI-STORE CIS facility includes the following other SSCs:

- Transport Cask Tilt Frame
- Vertical Cask Transporter
- CTB Steel Structure

Each of these components is discussed in more detail, including their description, design criteria, material properties, and structural analyses, in the following subsections.

5.5.1 Transport Cask Tilt Frame

5.5.1.1 Description of Structural Aspects

The Transport Cask Tilt Frame is used in conjunction with the CTB Crane and its special lifting devices to upend or down end the HI-STAR 190 transport cask between the vertical and horizontal orientations. The Transport Cask Tilt Frame consists of a set of trunnion support stanchions and a cask support saddle. The trunnion support stanchions engage the cask's rotation trunnions and provide a low-friction rotation point for cask tilting (see Figures 3.1.1(c-f) for illustration). The cask support saddle contacts the upper portion of the cask when the cask reaches the horizontal orientation. The trunnion support stanchion assembly is bolted to the CTB slab at its base while in use.

5.5.1.2 Design Criteria

The Transport Cask Tilt Frame is not a lifting device since it is a stationary device that provides support to the cask from below. Also, during upending or down ending operations, the cask always remains connected to the single failure proof CTB Crane via a special lifting device. Therefore, the Cask Tilt Frame is an ITS component, which is designed accordingly to meet the stress limits per ASME Section III, Subsection NF [4.5.1] for Class 3 plate- and shell-type supports.

The staging of the HI-STAR 190, without impact limiters, on the Transport Cask Tilt Frame is a short-term operation, and therefore as discussed in Subsection 4.3.6, the Transport Cask Tilt Frame is seismic-exempt. In the event that the HI-STAR 190 must remain on Transport Cask Tilt Frame for an extended period of time (i.e., more than one shift), then the impact limiters shall be re-installed on the HI-STAR 190 cask.

5.5.1.3 Material Properties

As shown on the Licensing Drawing in Section 1.5, the Transport Cask Tilt Frame is fabricated from carbon steel material (SA-516 Gr. 70, A572, A500 Gr. B). The minimum strength properties for these materials are obtained directly from the applicable ASTM specification or from Section II, Part D of the ASME Code [4.6.3].

5.5.1.4 Structural Analysis

The Transport Cask Title Frame is analyzed using the finite element code ANSYS [5.5.1] and supplemented by manual calculations using strength of materials principles. [

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

The results of the structural analysis for the Transport Cask Tilt Frame are summarized in Table 5.5.1, which shows that all of the calculated safety factors are above 1.0. The complete details of the structural analysis of the Transport Cask Tilt Frame are provided in the Structural Calculation Package [5.4.6].

5.5.2 Vertical Cask Transporter

5.5.2.1 Description of Structural Aspects

The Vertical Cask Transporter (VCT) is the principal load handling device used for MPC transfer operations at the HI-STORE CIS. Used in conjunction with the HI-TRAC CS lift links, it provides the critical lifting and handling functions associated with the canister transfer operations. It is a custom-designed equipment consisting of a set of caterpillars or multiple wheels, a diesel engine with a robust gear train and transmission housed in a rugged structural frame that also supports a set of hydraulically-actuated lifting towers. Figure 1.2.4 illustrates the general configuration of a VCT. The VCT uses the same controls and redundant drop protection features used to prevent an unplanned lowering of the critical load under a loss-of-power or hydraulic system failure as used at other ISFSIs in the United States where the VCT is used in canister transfer operations.

5.5.2.2 Design Criteria

The design criteria that apply to lifting devices, including the VCT, are fully described in Section 4.5 of this SAR. The detailed criteria that govern the design of the VCT are set down in Subsection 4.5.3.

The Design Basis loadings on the VCT are given in Table 4.5.3.

5.5.2.3 Structural Analysis

The seismic stability of the VCT (unloaded and carrying empty or fully loaded HI-TRAC CS) under the most severe DECE loading is evaluated for the possibility of incipient tipping and sliding, where simple dynamic equations are formulated based on force and moment equilibrium. [

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

The stress analysis of the VCT shall demonstrate compliance with the structural design criteria in Subsection 4.5.3 for the specified loadings in Table 4.5.3. The stress analysis of the VCT can be performed via calculations using strength of materials principles, finite element analysis, or a combination thereof.

5.5.3 CTB Steel Structure

5.5.3.1 Description of Structural Aspects

The CTB is a conventional sheet metal building consisting of a thick load bearing concrete slab and a set of knee-high concrete walls, which support the steel frame that serves as the backbone for the building. Corrugated sheet metal panels are fastened to the steel frame to create the lateral enclosure system. An overhead truss provides the framework to support the roof, which is also made of corrugated sheet metal.

Since the CTB steel structure serves as a weather enclosure, and it does not serve any safety related function, it is designated as a NITS structure. Accordingly, the HI-TRAC CS and HI-STAR 190 are analyzed in Subparagraph 5.4.2.4.5 for a hypothetical building collapse.

5.5.3.2 Design Criteria

The design criteria for the CTB, including the concrete slab and the above ground steel structure, are provided in Subsection 4.6.1.

5.5.3.3 Structural Analysis

Table 4.6.1 provides loading data for designing the CTB walls and roof structure; this data shall be used, along with the specified design criteria, to carry out the strength calculations for the CTB steel structure.

Table 5.5.1: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Table 5.5.2: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 5.5.1: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

5.6 REGULATORY COMPLIANCE

The structural compliance pursuant to the provisions of NUREG-1567 [1.0.3] for deployment of canisters certified in the HI-STORM UMAX Docket # (72-1040) has been demonstrated in this chapter. As the canisters will arrive at the HI-STORE site loaded in the transport package, the Short Term Operations on the (dry) canisters to place them in the HI-STORM UMAX VVMs and their interim storage in the HI-STORM UMAX VVMs are the subjects of safety analysis in this chapter. The information presented in this chapter confirms that:

i. The description of confinement structures, systems and components, reinforced concrete structures, and other SSCs important to safety meet the requirements of 10CFR72.24(a) and (b), 10CFR72.82(c)(2), and 10CFR72.106(a), (b), and (c).

ii. Suitable material properties for use in the design and construction of the SSCs, reinforced concrete structures, and other SSCs important to safety meet the requirements of 10CFR 72.24(c)(3).

iii. The analytical and/or test reports ensuring the structural integrity of the SSCs, reinforced concrete structures, and other SSCs important to safety meet the requirements of 10CFR72.24 (d)(1), (d)(2), and (i), and 10CFR72.122 (b)(1), (b)(2), and (b)(3), (c), (d), (f), (g), (h), (i), (j), (k), and (l).

It is therefore concluded that all applicable regulatory requirements and guidelines germane to the integrity of the stored fuel and the HI-STORM UMAX storage system have been addressed and satisfied in this chapter.

CHAPTER 6: THERMAL EVALUATION*

6.0 INTRODUCTION

HI-STORM UMAX, certified in the USNRC docket # 72-1040 is an underground vertical ventilated system with openings for air ingress and egress and internal air flow passages for ventilation cooling of loaded MPC. The licensing drawing package for the HI-STORM UMAX applicable to the HI-STORE CIS facility is provided in Section 1.5. Thermal design requirements are presented in Chapter 4.

As stated in Chapter 4, the thermal evaluation in this chapter seeks to establish that the peak fuel cladding temperature in the canisters stored in the HI-STORE CIS facility will remain below the ISG-11 Rev 3 [4.0.1] limit. Another object of the safety demonstration is that under all short-term operations summarized in Subsection 3.1.4, the peak fuel cladding temperature limit set forth in ISG-11 Rev 3 will be satisfied with robust margins.

With respect to normal storage in the HI-STORM UMAX cavities at HI-STORE, it is recognized that the maximum heat load in any canister cannot exceed the limit in the transport cask that will be used to bring the canisters to the HI-STORE CIS site. As the heat removal capacity of the ventilated HI-STORM UMAX system is substantially in excess of the (unventilated) transport cask (viz., HI-STAR 190 [1.3.6]) that will be used to transport the canisters, the ISG-11 temperature limit under the normal, off-normal and accident conditions of storage is axiomatically satisfied.

The short term operations at the HI-STORE facility involve a new transfer cask, HI-TRAC CS, which is not certified in the HI-STORM UMAX docket. As described in Subsection 1.2.4, HI-TRAC CS utilizes high density concrete (in lieu of lead, water or Holtite) to achieve enhanced structural ruggedness and for an improved dose attenuation profile. Because HI-TRAC CS is not submerged in a pool, its heat dissipation capabilities are significantly better than other HI-TRAC models that are subject to pool submergence (and hence must have a hydraulically leak-proof joint at the bottom lid suppressing the option of convective cooling of the canister). The limiting thermal scenarios with the canister in HI-TRAC CS are considered in this chapter. As described in Chapter 3, the short term operations that are performed at HI-STORE also include transfer of canisters from transportation cask (HI-STAR 190) to the HI-TRAC CS transfer cask in the Canister Transfer Facility (CTF). This thermal scenario is also considered in this chapter.

Since the Design Basis heat load is significantly lower than that in HI-STORM UMAX Docket [1.0.6] (see Table 6.3.1), the safety analyses summarized in this chapter demonstrate rather large margins to the allowable limits under all operational modes. Minor changes to the design parameters that inevitably occur during the product's life cycle and are ascertained to have an insignificant effect on the computed safety factors may not prompt a formal reanalysis and revision of the results and associated data in the tables of this chapter unless the cumulative effect of all such unquantified changes on the reduction of any of the computed safety margins cannot be deemed to be insignificant. For purposes of this determination, unconditionally safe threshold (UST) is defined as an acceptance criterion set at the smaller of 25% of the safety

* All references are in placed within square brackets in this report and are compiled in Chapter 19 of this report.

margin to the limit or 10 deg. C. for all operational modes. To ensure rigorous configuration control, the information in the Licensing Drawings in Section 1.5 should be treated as the authoritative source for safety analysis at all times.

To facilitate convenient access to the material incorporated by reference, a list of sections germane to this chapter is provided in a tabular form in Table 6.0.1. Table 6.0.1 provides a listing of the material adopted in this chapter by reference from other licensed dockets.

Table 6.0.1: Material Incorporated by Reference in this Chapter

Information Incorporated by Reference	Source of the Information	Location in this SAR where Material is Incorporated	Technical Justification of Applicability to HI-STORM UMAX at HI-STORE CIS
Thermal Properties of materials in MPC, VVM and transfer cask	Section 4.2 of HI-STORM UMAX FSAR [1.0.6]	Subsection 6.4.1	Materials used in MPC, VVM and HI-TRAC CS transfer cask are the same as those used in HI-STORM UMAX FSAR and are therefore incorporated by reference.
MPC-37 and MPC-89 Thermal Model and Methodology	Subsection 4.4.1 of HI-STORM UMAX FSAR [1.0.6]	Paragraph 6.4.2.2	The canister is identical to the one described in the HI-STORM UMAX FSAR. So the approach, general assumptions and models established for MPCs in the HI-STORM UMAX FSAR are fully applicable to the HI-STORM UMAX utilized for HI-STORE facility. Therefore, the MPC thermal models are incorporated by reference.
HI-STORM UMAX VVM Thermal Model and Methodology	Subsection 4.4.1 of HI-STORM UMAX FSAR [1.0.6]	Paragraph 6.4.2.3	The HI-STORM UMAX VVM is identical to that described in the HI-STORM UMAX FSAR with minor differences in design details like it has two fixed cavity heights instead of variable cavity height. The thermal performance is unaffected for tallest MPC and improved for shortest MPC. Additional details of the differences and technical justification for the same are provided in Paragraph 6.4.2.3. So the approach, general assumptions and models established in the HI-STORM UMAX FSAR are fully applicable to the HI-STORM UMAX utilized for HI-STORE facility.

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

Information Incorporated by Reference	Source of the Information	Location in this SAR where Material is Incorporated	Technical Justification of Applicability to HI-STORM UMAX at HI-STORE CIS
Minimum Temperatures	Subsection 4.4.4 of HI-STORM UMAX FSAR [1.0.6]	Paragraph 6.4.3.3	The minimum ambient temperature is bounded by that specified in the HI-STORM UMAX FSAR [1.0.6]. Accordingly the low-service temperature evaluation presented in HI-STORM UMAX FSAR [1.0.6] is applicable to the HI-STORM UMAX evaluated in this SAR and is therefore incorporated by reference.
Engineered Clearances	Subsection 4.4.6 of HI-STORM UMAX FSAR [1.0.6]	Paragraph 6.4.3.4	As the fuel, component temperatures and MPC cavity pressure during long-term storage in Subsection 6.4.3 are bounded by that presented in Subsection 4.4.4(i) of HI-STORM UMAX FSAR [1.0.6], the differential thermal expansions presented in Subsection 4.4.6 of the HI-STORM UMAX FSAR [1.0.6] is bounding and is therefore incorporated by reference.
Evaluation of Sustained Wind	Subsection 4.4.9 of HI-STORM UMAX FSAR [1.0.6]	Paragraph 6.4.3.5	The HI-STORM UMAX design is the same as the one described in the HI-STORM UMAX FSAR [1.0.6]. The effect of sustained wind on cask arrays evaluated under a worst case co-incidence of wind direction and speed is applicable to the HI-STORM UMAX evaluated in this SAR and is therefore incorporated by reference.
Off-Normal Environment Temperature	Paragraph 4.6.1.1 of HI-STORM UMAX FSAR [1.0.6]	Sub-section 6.5.1	The off-normal ambient temperature at the site is bounded by that specified in the HI-STORM UMAX FSAR [1.0.6] (see Table 6.3.1). So the temperatures and MPC cavity pressures presented in

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

Information Incorporated by Reference	Source of the Information	Location in this SAR where Material is Incorporated	Technical Justification of Applicability to HI-STORM UMAX at HI-STORE CIS
			HI-STORM UMAX FSAR are bounding and are therefore incorporated by reference.
Partial Blockage of Air Inlets	Paragraph 4.6.1.2 of HI-STORM UMAX FSAR [1.0.6]	Sub-section 6.5.1	Since the decay heat, fuel, component temperatures and MPC cavity pressure during long-term storage in Subsection 6.4.3 are bounded by that presented in Subsection 4.4.4(i) of HI-STORM UMAX FSAR [1.0.6], this scenario presented in Paragraph 4.6.1.2 of the HI-STORM UMAX FSAR [1.0.6] is bounding and is therefore incorporated by reference.
Extreme Environment Temperature	Paragraph 4.6.2.2 of HI-STORM UMAX FSAR [1.0.6]	Paragraph 6.5.2.4	The extreme ambient temperature at the site is the bounded by that specified in the HI-STORM UMAX FSAR [1.0.6] (see Table 6.3.1). So the temperatures and MPC cavity pressures presented in HI-STORM UMAX FSAR are bounding and is therefore incorporated by reference.
100% Blockage of Air Inlets and Outlet	Paragraph 4.6.2.3 of HI-STORM UMAX FSAR [1.0.6]	Paragraph 6.5.2.5	Since the decay heat, fuel, component temperatures and MPC cavity pressure during long-term storage in Section 6.4.3 are bounded by that presented in Section 4.4 of HI-STORM UMAX FSAR [1.0.6], this scenario presented in Paragraph 4.6.2.3 of the HI-STORM UMAX FSAR [1.0.6] is bounding.

Information Incorporated by Reference	Source of the Information	Location in this SAR where Material is Incorporated	Technical Justification of Applicability to HI-STORM UMAX at HI-STORE CIS
Flood	Paragraph 4.6.2.5 of HI-STORM UMAX FSAR [1.0.6]	Paragraph 6.5.2.6	The Design Basis Flood used to qualify the VVM in the HI-STORM UMAX FSAR (up to 5 inch) exceeds the most severe projection of flood at the ELEA site (up to 4.8 inch (see Subsection 2.4.3). Therefore, flood evaluation presented in Paragraph 4.6.2.5 of HI-STORM UMAX FSAR [1.0.6] is bounding and is therefore incorporated by reference.

6.1 DECAY HEAT REMOVAL SYSTEMS

Rejection of heat from the used nuclear fuel at the HI-STORE CIS facility occurs through three types of casks, namely:

i. The HI-STAR 190 transport cask

ii. The HI-TRAC CS transfer cask

iii. The HI-STORM UMAX vertical ventilated module

The heat dissipation mechanisms in each of the above cask systems are summarized below:

(i) The HI-STAR 190 transport cask: The HI-STAR 190 transport cask is used only during the short term operations at the HI-STORE site. The HI-STAR 190 transport cask, illustrated in Figure 6.4.1, is a metal cask whose safety analysis is summarized in the SAR [1.3.6] in NRC Docket# 71-9373. HI-STAR rejects the decay heat produced by its contents through natural convection from its external surface and by radiation. In its standard transport configuration, HI-STAR 190 is horizontally disposed. Its thermal performance in the horizontal orientation is documented in the cask's SAR [1.3.6].

(ii) At the HI-STORE facility, however, the HI-STAR cask is staged vertically inside the Canister Transfer Facility (CTF) which is a subterranean pit with a set of inlet vents located near its bottom. The heat dissipation mechanism inside the CTF is evidently different from that in the transport mode analyzed in [1.3.6]. Therefore, a thermal analysis of this configuration is required. A thermal model of this configuration is constructed and details are provided in Section 6.4.2.

(iii) The HI-TRAC CS transfer cask: The HI-TRAC is used only during the short term operations at the HI-STORE facility. The HI-TRAC CS transfer cask, illustrated in Figure 6.4.2 and described in Section 1.2, is a ventilated dual shell steel weldment with high density concrete installed in its inter-shell space for neutron and gamma shielding. HI-TRAC CS is not intended for use in fuel pool service; it is used solely for dry handling of the canisters arriving at the HI-STORE facility. As described in Chapter 3, the loaded canister is transferred to the HI-TRAC CS transfer cask in the Canister Transfer Facility (CTF) through a vertical stack up process. As shown in Figure 6.4.3, in this configuration, the canister is cooled by a direct convective action of ventilation air over a tall column of the stack. This convection effect would be much less pronounced when the canister is installed in the transfer cask and its retractable segmented shield gate is fully closed (Figure 1.2.3a). An examination of the canister loading steps outlined in Subsection 1.2.5 indicates that the limiting thermal condition involves the scenario where the canister is loaded in the transfer cask and its shield gate is closed. Figures 1.2.3a, 1.2.3b and 6.4.2 show the retractable shield gate in perspective view. As can be seen from this figure, HI-TRAC CS has a built-in ventilation feature which provides for limited ventilation even when the shield gate is fully closed. The thermal analysis in this chapter seeks to quantify the margins to the fuel cladding temperature and other material limits for this thermally limiting configuration. A thermal model of this configuration is constructed and details are provided in Section 6.4.2.

(iv) The HI-STORM UMAX VVMs: The interim storage of the canisters will occur in the HI-STORM UMAX VVMs. The thermal-hydraulic configuration of the HI-STORM UMAX VVMs at HI-STORE is essentially identical to that certified in the HI-STORM UMAX docket. Therefore, its heat rejection capacity would be virtually identical under identical conditions to that analyzed and certified in [1.0.6] under all operation modes. However, as can be inferred from Table 6.3.1, the Design Basis heat load and the ambient temperature metrics for the HI-STORE ISFSI are less challenging than those for which the system is certified in [1.0.6]. Therefore, it is concluded that the heat rejection performance of the canisters at the HI-STORE ISFSI will have even greater margins to the regulator-prescribed limit than that established in [1.0.6]. To ascertain this, long-term storage of canisters in HI-STORM UMAX with site-specific conditions from Table 6.3.1 is evaluated in this chapter. A thermal model of the HI-STORM UMAX VVM containing MPC is constructed and details are provided in Section 6.4.2.

The decay heat removal of HI-STORM UMAX VVMs under normal, off-normal and accident conditions is evaluated in this chapter. Similarly, thermal performance of HI-TRAC CS transfer cask and HI-STAR 190 cask under short-term and accident conditions are also evaluated in this chapter.

6.2 MATERIAL TEMPERATURE LIMITS

Material temperature limits are provided in Section 4.4 of Chapter 4. All material considerations including material degradation modes applicable to HI-STORM UMAX are evaluated in Chapter 17 of this SAR. If the canister arrives at HI-STORE at a date greater than 20 years from the date of first being placed on a storage pad, the canister is added to the list of canisters undergoing aging management immediately, a more detailed description of which is provided in Chapter 18 of this SAR.

6.3 THERMAL LOADS AND ENVIRONMENTAL CONDITIONS

The thermal loads and applicable environmental conditions are summarized in Table 6.3.1. This table also contains the corresponding values for which the HI-STORM UMAX system is certified in its FSAR [1.0.6]. It can be noted from this table that the site normal, off-normal and accident ambient temperatures are lower than that adopted on a generic basis in the HI-STORM UMAX FSAR [1.0.6]. The design basis normal ambient temperature used in this SAR will be exceeded only for brief periods as suggested by the ambient temperature data in Chapter 2. Inasmuch as the sole effect of the normal temperature is on the computed fuel cladding temperature to establish long-term fuel integrity, it should not lie below the time averaged yearly mean for the site. Previously licensed cask systems have employed yearly averaged normal temperatures (USNRC Dockets 72-1014, 72-1032 and 72-1040) for evaluation of long-term storage.

Table 6.3.1: Thermally Significant Parameters for the HI-STORM UMAX ISFSI at HI-STORE and Corresponding Certified Value in the System FSAR [1.0.6]

Thermally significant ISFSI parameter	Certified value from the HI-STORM UMAX FSAR and table reference		Value applicable to the HI-STORE ISFSI and reference source	
	Data	Table I.D.	Data	Source
Maximum Aggregate Heat Load for MPC-37, kW	37.06*	Table 2.1.8 of [1.0.6]	32.09	Table 4.1.1
MPC-37 Initial Helium Backfill Specification at 70°F reference temperature, psig	39 – 46	Table 4.4.6 of [1.0.6]	39 – 46	Table 4.1.3
Maximum Aggregate Heat Load for MPC-89, kW	36.72*	Table 2.1.9 of [1.0.6]	32.15	Table 4.1.2
Initial Helium Backfill Specification at 70°F reference temperature, psig	39 – 46†	Table 4.4.6 of [1.0.6]	39 – 47.5†	Table 4.1.3
Normal Ambient Temperature (See Glossary), °F	80	Table 2.3.6 of [1.0.6]	62	Table 2.7.1
Minimum Ambient Temperature (See Glossary), °F	-40	Table 2.3.6 of [1.0.6]	-11	Table 2.3.1
Off-normal Ambient Temperature (See Glossary), °F	100	Table 2.3.6 of [1.0.6]	91	Table 2.7.1
Accident Ambient Temperature (See Glossary), °F	125	Table 2.3.6 of [1.0.6]	108	Table 2.7.1

* The maximum total heat load permissible in the HI-STORM UMAX 72-1040 CoC is presented herein. The actual total heat load adopted for thermal evaluations in the HI-STORM UMAX FSAR [1.0.6] is significantly higher.

† It is recognized that the initial helium backfill specification are consistent with the limits in the transport cask [1.3.6] that will be used to bring the canisters to the HI-STORE CIS site.

6.4 APPLICABLE SYSTEMS, ANALYTICAL METHODS, MODELS AND CALCULATIONS

6.4.1 Applicable Systems

As explained in Subection 1.2.1, HI-STORM UMAX Version C is deployed at HI-STORE CIS. This design is identical to the design licensed in HI-STORM UMAX docket# 72-1040 except the following:

- The ultra-high earthquake-resistant options, referred to as MSE options, are not present.
- The storage cavity depth is made fixed (not variable, as permitted in the general certification) at two discrete dimensions and are referred to as types SL and XL (see drawing Section 1.5).

As a result of the above, the thermal performance of the system remains either unaffected or improved depending on the height of the canister being stored. The safety analysis of the HI-STORM UMAX ISFSI at HI-STORE will be bounded by the generic analysis in the HI-STORM UMAX docket [1.0.6] since the Design Basis heat load and the ambient temperature metrics for the HI-STORE ISFSI are less challenging than those for which the system is certified in [1.0.6] (see Table 6.3.1). To provide further assurance, a thermal evaluation of normal long-term storage of HI-STORM UMAX Version C VVMs under governing scenario is performed in this section to demonstrate safety compliance.

Additionally, there are two safety analyses that pertain to short term operations that warrant quantification of their safety margin. These are:

(i) The HI-STAR 190 transport cask situated in the CTF illustrated in Figure 6.4.1: The HI-STAR 190 cask is analyzed in its Part 71 docket [1.3.6] wherein its compliance with the ISG-11 Rev 3 thermal limit under transport is demonstrated. A similar demonstration for the configuration in Figure 6.4.1 is provided in Subsection 6.4.2.

(ii) HI-TRAC CS transfer cask containing a loaded canister with its shield gates closed: In this configuration, as shown in Figure 6.4.2, the canister inside the transfer cask has limited ventilation assistance. In comparison, the configuration wherein the transfer cask is mounted on top of the HI-STORM UMAX cavity or HI-STAR 190 cavity with its shield gates wide open (see Figure 6.4.3) has maximum ventilation cooling action and is therefore ruled out as a governing thermal condition. Thermal model and analysis methodology of normal onsite transfer in HI-TRAC CS is described in Subsection 6.4.2.

Table 6.4.1 provides the principal input data used in the thermal analysis performed for the above two short term operation scenarios. Thermal properties of materials used in MPC and VVM storage system are incorporated by reference from Section 4.2 of HI-STORM UMAX FSAR [1.0.6]. Materials present in HI-TRAC CS transfer cask include steel and concrete, thermal properties of which are also provided in Section 4.2 of HI-STORM UMAX FSAR [1.0.6]. Similarly properties of materials used in HI-STAR 190 cask are incorporated by reference from Section 3.3 of HI-STAR 190 SAR [1.3.6].

6.4.2 Analysis Methodology

6.4.2.1 Computer Code

The analysis vehicle for prediction of thermal performance of the systems in this SAR is the computer code FLUENT [6.4.1]. FLUENT has been benchmarked and validated for use in cask systems [6.4.2] since 1990s and has been used in the thermal qualification of every storage and transport cask developed by Holtec since 1995. A summary of pre-qualification benchmarking of FLUENT is included in Appendix 6.A herein for reference purposes. In Table 6.4.2, a listing of the licenses or license amendments issued by the USNRC and other regulatory authorities on both transport and ventilated cask types that utilize FLUENT is summarized. Several cask models listed in Table 6.4.2 have received numerous licensing amendments over the years. Thus, from this table, it can be inferred that Holtec's FLUENT models for simulating ventilated and metal casks have been repeatedly endorsed by the NRC and other national regulatory authorities.

As in all other HI-STORM dockets, the FLUENT solutions reported in this SAR have been vetted for numerical stability and grid sensitivity [6.4.3, 6.4.4] (Subsection 4.4.2 of the HI-STORM UMAX FSAR [1.0.6]).

6.4.2.2 MPC Thermal Model

The thermal analysis model of MPC is incorporated by reference from Section 4.4 of the HI-STORM UMAX FSAR [1.0.6].

6.4.2.3 HI-STORM UMAX VVM Thermal Model

The HI-STORM UMAX storage VVM used in HI-STORE CIS is slightly modified compared to the version documented in the HI-STORM UMAX FSAR [1.0.6]. A geometrically accurate 3D thermal model of the HI-STORM UMAX VVM Version C is constructed in the manner of HI-STORM UMAX in docket # 72-1040. The scenario of short MPC-37 placed in HI-STORM UMAX Version C Type SL is thermally governing for the following reasons and is therefore evaluated in this chapter:

a. As demonstrated in Section 4.4 of HI-STORM UMAX FSAR [1.0.6], thermal evaluations of MPC-89 are bounded by MPC-37. Since the heat load patterns provided in Section 4.1 of this SAR are bounded by those adopted in the generic HI-STORM UMAX FSAR [1.0.6] for both MPCs, MPC-37 is the governing canister at HI-STORE also.

b. MPC-37 with short fuel results in highest PCT and component temperatures as demonstrated in Section 4.4 of HI-STORM UMAX FSAR [1.0.6].

c. Active fuel height of short PWR fuel is lowest among short, reference and long fuel assemblies. For the same heat load, lower active height results in higher heat load density.

The thermal modeling of the HI-STORM UMAX VVM is incorporated by reference from Section 4.4 of HI-STORM UMAX FSAR [1.0.6]. The quarter symmetric model for the VVM assembly seeks to represent the essential geometry details of the physical system as depicted in the Licensing Drawings in Section 1.5 and utilizes the same conservative assumptions as summarized in Section 4.4 of [1.0.6].

Sectional and isometric views of the HI-STORM UMAX VVM quarter symmetric 3D thermal model are presented in Figures 6.4.4 and 6.4.5 respectively.

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

6.4.2.4 HI-STAR 190 Thermal Model

To accommodate all PWR and BWR canisters, the HI-STAR 190 cask is available in two discrete lengths – version SL (standard length) and version XL (extended length), as described in Chapter 1 of HI-STAR 190 SAR [1.3.6]. The HI-STAR 190 Version XL has a larger external surface area for heat dissipation than that of HI-STAR 190 Version SL. Therefore, the thermal performance of HI-STAR 190 Version XL is bounded by that of HI-STAR 190 Version SL. The thermal performance of short MPC-37 bounds that of MPC-89 for similar decay heats as has been demonstrated in Section 3.3 of HI-STAR 190 SAR [1.3.6], Sections 4.4 of the HI-STORM UMAX FSAR [1.0.6] and HI-STORM FW FSAR [1.3.7].

Based on the above justification, the shorter version SL with short MPC-37 is thermally most limiting and is therefore adopted herein. The thermal model of HI-STAR 190 is the same as that used in its native docket (10CFR71-9373 [1.3.6]). Thermal model of HI-STAR 190 placed inside the CTF has the following attributes:

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

Table 6.4.1 provides the principal input data used in the thermal analysis performed for this short term operation scenario. Sectional and isometric views of the HI-STAR 190 in CTF quarter symmetric 3D thermal model are presented in Figures 6.4.6 and 6.4.7 respectively. The computational results for this scenario are presented in Subsection 6.4.3.

6.4.2.5 HI-TRAC CS Transfer Cask Thermal Model

The HI-TRAC CS is a dry use only cask designed specifically for the HI-STORE CIS facility. HI-TRAC CS has large cavities to accommodate various heights of MPCs. As described above, short MPC-37 is the governing thermal scenario and is therefore evaluated to demonstrate safety. Its thermal model, implemented on FLUENT has the following key attributes:

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

Sectional and isometric views of the HI-TRAC quarter symmetric 3D thermal model are presented in Figures 6.4.8 and 6.4.9 respectively. The computational results for this scenario are presented in Subsection 6.4.3.

6.4.3 Calculations and Results

6.4.3.1 Maximum Temperatures

A steady state thermal analysis of the governing "thermal configurations" (meaning the combination of canister type, regionalized loading pattern and fuel type that produces highest fuel cladding temperature) was performed using the 3-D FLUENT model described in Subsection 6.4.2 to quantify the thermal margins under long term storage conditions. Thermal analyses of the MPC-37 with short fuel under heat load pattern 1 specified in Table 4.1.1 is performed.

The maximum spatial values of the computed temperatures of the fuel cladding, the fuel basket material, the divider shell, the closure lid concrete, the MPC lid, the MPC shell and the average air outlet temperature are summarized in Table 6.4.3. The following conclusions are reached from the solution data:

a. The PCT is below the temperature limit set forth in ISG-11 Rev 3 [4.0.1].

b. The maximum temperatures of all MPC and VVM constituent parts are below their respective limits set down in Section 4.4.

c. The temperatures are below the licensed temperatures obtained and presented in Chapter 4 of HI-STORM UMAX FSAR [1.0.6].

It is therefore concluded that the HI-STORM UMAX system provides a thermally acceptable storage environment for the eligible MPCs.

Thermal evaluations in Section 3.3.5 of HI-STAR 190 SAR [1.3.6] demonstrate that the predicted temperatures and cavity pressures under sub-design basis heat loads* is bounded by those under design basis maximum heat loads. Therefore, the safety conclusions made for design basis heat loads also remain applicable to sub-design basis heat loads also.

6.4.3.2 MPC Cavity Pressures

The MPC from HI-STAR 190 is already filled with dry pressurized helium. During normal storage in HI-STORM UMAX VVM and during short-term operations in HI-TRAC CS and HI-STAR 190, the gas temperature within the MPC rises to its maximum operating basis temperature. The gas pressure inside the MPC will also increase with rising temperature. The pressure rise is determined using the ideal gas law. The MPC gas pressure is also subject to substantial pressure rise under hypothetical rupture of fuel rods.

The MPC maximum gas pressure is computed for a postulated release of fission product gases from fuel rods into this free space. For these scenarios, the amounts of each of the release gas constituents in the MPC cavity are summed and the resulting total pressures determined from the ideal gas law. A concomitant effect of rod ruptures is the increased pressure and molecular weight of the cavity gases with enhanced rate of heat dissipation by internal helium convection and lower cavity temperatures. As these effects are substantial under large rod ruptures the 100% rod rupture accident is conservatively evaluated without credit for increased heat dissipation under increased pressure and molecular weight of the cavity gases. Based on fission gases release fractions (NUREG 1567 criteria), rods' net free volume and initial fill gas pressure, maximum gas pressures with 1% (normal), 10% (off-normal) and 100% (accident condition) rod rupture are given in Table 6.4.4. The maximum calculated gas pressures reported in Table 6.4.4 are all below the MPC internal design pressures for normal, off-normal and accident conditions specified in Chapter 4.

6.4.3.3 Minimum Temperatures

The minimum temperature evaluation for HI-STORM UMAX at HI-STORE is bounded by that in Subsection 4.4.4 of the HI-STORM UMAX FSAR [1.0.6] due to the following:

- The minimum ambient temperature at HI-STORE site is bounded by that defined in HI-STORM UMAX FSAR [1.0.6] (see Table 6.3.1).

Therefore, Subsection 4.4.4(ii) of the HI-STORM UMAX FSAR [1.0.6] is incorporated by reference into this document.

6.4.3.4 Engineered Clearances to Eliminate Thermal Interfaces

The differential thermal expansion between MPC and cask components for HI-STORM UMAX at HI-STORE is bounded by that in Sub-section 4.4.6 of the HI-STORM UMAX FSAR [1.0.6] due to the following:

* MPC helium initial backfill specification and sub-design basis heat load is defined in Table 4.1.4.

The MPC and VVM component temperatures at HI-STORE are lower than that presented for the same MPC presented in Section 4.4.4(i) of the HI-STORM UMAX FSAR under normal long-term storage condition [1.0.6].

Therefore, Subsection 4.4.6 of the HI-STORM UMAX FSAR [1.0.6] is incorporated by reference into this document.

6.4.3.5 Evaluation of Sustained Wind

The effect of sustained wind on HI-STORM UMAX cask arrays at HI-STORE CIS is bounded by that in Subsection 4.4.9 of the HI-STORM UMAX FSAR [1.0.6] due to the following:

- The MPC and VVM component temperatures at HI-STORE are lower than that presented for the same MPC presented in Section 4.4.4(i) of the HI-STORM UMAX FSAR under normal long-term storage condition [1.0.6].
- Wind effects at the site are bounded by those evaluated in Subsection 4.4.9 of the HI-STORM UMAX FSAR [1.0.6] due to HI-STORM UMAX evaluation under worst case combination of wind speed and direction.

Therefore, Subsection 4.4.9 of the HI-STORM UMAX FSAR [1.0.6] is incorporated by reference into this document. The effect of wind presented in Subsection 4.4.9 of the HI-STORM UMAX FSAR [1.0.6] is dwarfed by the significant margins to temperature limits for the HI-STORM UMAX at HI-STORE (see Table 6.4.3).

6.4.3.6 Evaluation of HI-STAR 190 in CTF

The calculations performed using the 3-D FLUENT model described in Subsection 6.4.2 provided steady state results that are summarized in Table 6.4.5. By comparing the results in the above tables with the acceptable limits in Chapter 4 yield the following conclusions:

i) The peak cladding temperature is considerably below the limit corresponding to short term operations.

ii) There is a large margin to the limit for the metal temperature of the steel in the cask.

iii) The temperatures of the gamma and neutron blockage materials in the transport cask have considerable margins to their respective limits.

iv) MPC cavity pressure during this short-term operation is below the design pressure limit (see Chapter 4).

In summary, the temperatures of all HI-STAR 190 components are well within their prescribed limits.

6.4.3.7 Evaluation of Normal Onsite Transfer in HI-TRAC CS

The calculations performed using the 3-D FLUENT model described in Subsection 6.4.2 provided steady state results that are summarized in Table 6.4.6. By comparing the results in the above tables with the acceptable limits in Chapter 4 yield the following conclusions:

(i) The peak cladding temperature is considerably below the limit corresponding to short term operations.

(ii) There is a large margin to the limit for the metal temperature of the steel in the cask.

(iii) The section average temperature of shielding concrete in HI-TRAC CS is also well within the permitted limit.

(iv) MPC cavity pressure during this short-term operation is below the design pressure limit (see Chapter 4).

In summary, the temperatures in every constituent part of HI-TRAC CS are well within their prescribed regulatory limits.

Table 6.4.1: Thermal Input Data for Analysis of Governing Scenarios During Short Term Operations

PARAMETER	HI-STAR 190	HI-TRAC CS
Ambient Temperature, ^{o}F (Note 1)	91	91
Ambient pressure, psia (Note 2)	12.2	12.2
Canister (Note 3)	Short MPC-37	Short MPC-37
Nominal Cask Cavity Height, inch	190.81 (Note 4)	215.25
Heat Load, kW	(Note 5)	(Note 5)
Location	Canister Transfer Building	Inside or Outside Canister Transfer Building
Configuration	Figure 6.4.1	Figure 6.4.2

Note 1: The 3-day average ambient temperature is defined in Table 2.7.1.
Note 2: The ambient pressure is assumed to be based on an altitude of 5000 feet above the Mean Sea Level [6.4.5]; the actual elevation cited in Table 2.7.1, is much lower.
Note 3: The thermal analyses reported in Section 4.1 of HI-STORM UMAX FSAR [1.0.6] shows that short MPC-37 with PWR fuel provides the most challenging thermal case.
Note 4: The cavity height of short SL version reported herein.
Note 5: The thermal analyses reported in Section 3.3 of HI-STAR 190 SAR [1.3.6] shows that Heat Load Pattern 1 specified in Appendix 7.C of HI-STAR 190 SAR [1.3.6] is the governing heat load distribution and is adopted herein for thermal evaluations.

Table 6.4.2: List of Holtec's Licensing Basis FLUENT Models Previously Used in Storage and Transport Casks			
Cask name	**Type**	**Regulator**	**Docket No.**
HI-STAR 100	Metal transport cask	USNRC	71-9261
HI-STAR 100	Metal storage cask	USNRC	72-1008
HI-STORM 100	Ventilated storage cask	USNRC	72-1014
HI-STAR 180	Metal transport cask	USNRC	71-9325
HI-STAR 60	Metal transport cask	USNRC	71-9336
HI-STAR 180D	Metal transport cask	USNRC	71-9367
HI-STORM FW	Ventilated storage cask	USNRC	72-1032
HI-STORM UMAX	Ventilated storage cask	USNRC	72-1040

Table 6.4.3: Normal Long-Term Storage Temperatures for MPC-37 in HI-STORM UMAX at HI-STORE CIS	
Component	**Temperature, °F**
Fuel Cladding	613
Fuel Basket	552
Basket Shims	435
MPC Shell	372
MPC Lid[1]	369
MPC Baseplate[1]	304
Divider Shell	273
CEC Shell	111
Closure Lid Concrete[1]	156
Average Air Outlet	153

[1] Maximum section average temperature is reported.

Table 6.4.4: MPC Cavity Pressure During Normal Long-Term Storage in HI-STORM UMAX VVM	
Component	**Pressure, psig**
Normal Condition - No Rod Rupture - 1% Rod Rupture	 88.2 89.2
Off-Normal Condition (10% Rod Rupture)	98.3
Accident Condition (100% Rod Rupture)	188.7

Table 6.4.5: Maximum Component Temperatures and MPC Cavity Pressure for HI-STAR 190 in CTF Short-Term Operation	
Component	**Temperature, °F**
Fuel Cladding	716
Fuel Basket	667
Basket Shims	558
MPC Shell	504
MPC Lid[1]	495
MPC Baseplate[1]	396
Containment Shell	385
Holtite	385
Enclosure Shell	336
Closure Lid[1]	252
Containment Bottom Forging[2]	320
Containment Top Forging[2]	264
	Pressure, psig
MPC Cavity Pressure	102.3

[1] Maximum section average temperature is reported.

[2] Bulk average temperature is reported.

Table 6.4.6: Normal On-Site Transfer Temperatures and MPC Cavity Pressure in HI-TRAC CS	
Component	**Temperature, °F**
Fuel Cladding	669
Fuel Basket	615
Basket Shims	507
MPC Shell	461
MPC Lid[1]	416
MPC Baseplate[1]	343
HI-TRAC Inner Shell	352
HI-TRAC Concrete[1]	271
HI-TRAC Outer Shell	200
	Pressure, psig
MPC Cavity Pressure	96.0

[1] Maximum section average temperature is reported.

Figure 6.4.1: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 6.4.2: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 6.4.3: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 6.4.4: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 6.4.5: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 6.4.6: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 6.4.7: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 6.4.8: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 6.4.9: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

6.5 SAFETY UNDER OFF-NORMAL AND ACCIDENT EVENTS

6.5.1 Off-Normal Events

To support evaluation of off-normal events in Section 15.2, the following off-normal events are evaluated herein:

i) Off-Normal Environment Temperature

ii) Partial Blockage of Air Inlets

iii) Off-Normal Pressure

Thermal evaluations of off-normal events (i) and (ii) are bounded by the evaluations reported in Sub-section 4.6.1 of the HI-STORM UMAX FSAR [1.0.6] since that the PCT and component temperatures of MPC stored in HI-STORM UMAX at HI-STORE are lower than that of the same MPC presented in Section 4.4.4(i) of the HI-STORM UMAX FSAR under normal long-term storage condition [1.0.6]. Therefore, Subsection 4.6.1 of the HI-STORM UMAX FSAR [1.0.6] is incorporated by reference into this document.

Thermal evaluation of off-normal event (iii) is presented in Subsection 6.4.3. The off-normal MPC cavity pressure is below the limit defined in Table 4.3.1 with positive margins.

6.5.2 Accident Events

6.5.2.1 Bounding Fire Event

(a) HI-STORM UMAX Fire Accident: The FSARs of both the HI-STORM UMAX [1.0.6] and the HI-STORM FW system [1.3.7] contain the fire consequence analysis for a 50 gallon fire at a generic ISFSI and demonstrate that all of the safety metrics of the storage system will be met. However, since a transporter with potentially larger volume of combustibles is used on site to transfer MPCs from HI-TRAC CS transfer cask to HI-STORM UMAX VVM storage module, a conservative fire event has been considered herein. The amount of combustibles is conservatively considered equal to that specified in Table 6.5.1. Thermal evaluation of an all engulfing fire of the aboveground HI-STORM FW System for the same amount of combustibles is presented in a Holtec report [6.5.3]. The results demonstrate that the fuel and MPC confinement integrity is assured under this severe fire accident. Based on this, it is safe to conclude that the MPC and its contents are also safe in HI-STORM UMAX at HI-STORE under transporter fire accident due to the following:

- The initial PCT and component temperatures of MPC stored in HI-STORM UMAX at HI-STORE are lower than that of the same MPC in the HI-STORM FW system [6.5.3].
- MPC decay heat is significantly lower in HI-STORM UMAX.
- HI-STORM UMAX system has much lesser surface directly exposed to fire than that of above-ground system.

Consequently, the conclusion that PCT and components' temperatures and MPC pressure are below temperature and pressure limits for transporter fire event drawn in Holtec report [6.5.3] remain valid for the HI-STORM UMAX system at HI-STORE site.

(b) HI-TRAC CS Fire Accident: The case of fire in the Cask Transfer Building (CTB) where the HI-TRAC CS cask is used to handle the arriving canister, however, is not addressed in the above referenced FSARs. While the probability of a fire event in the CTB is quite low due to the lack of combustible materials, except the fuel in the Vertical Cask Transporter's tank (procedurally limited to 50 gallons), a conservative fire event has been assumed herein and analyzed. Under a postulated fuel tank fire, the outer layers of HI-TRAC CS cask will be heated for the duration of fire by the incident thermal radiation and forced convection heat fluxes.

To make the fire event even more severe, the quantity of combustible fluid in the VCT has been conservatively increased to as adopted in Table 6.5.1. The fuel tank fire is conservatively assumed to surround the HI-TRAC CS cask thus exposing the entire external to heating by radiation and convection heat transfer. Following the 10 CFR 71 guidelines [1.3.2], the following fire parameters are assumed:

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

The results of the fire and post-fire events are reported in Table 6.5.2. These results demonstrate the following:

- The fire event has a minor effect on the fuel cladding temperature. The peak cladding temperature remains below the applicable ISG-11 Rev 3 [4.0.1] limit.
- The internal pressure in the canister remains below its accident condition limit.
- Localized regions of shielding concrete in the body of HI-TRAC CS up to less than 0.25 inch depth are exposed to temperatures in excess of accident temperature limit set forth in Chapter 4, Table 4.4.1. The bulk of the concrete remains well below the accident temperature limit.
- The metal temperature of the steel weldment of the HI-TRAC CS cask is also well within the applicable limit in Table 4.4.1.

It is thus concluded that the suitability of the HI-TRAC CS cask to render its canister transfer function will remain essentially unimpaired after the bounding fire event postulated in the foregoing.

(c) HI-STAR 190 Fire Accident: All loading/lifting operations related to HI-STAR 190 transport cask after arriving at the facility is performed using CTB crane (see Section 10.3). The CTB crane does not have sources of combustibles to cause a potential fire hazard. The HI-TRAC CS transfer cask is also operated using the crane and placed on the CTF alignment plate for MPC transfer from HI-STAR 190 to HI-TRAC CS. The transporter is only used for transfer operations with HI-TRAC CS, which is always distant from the CTF or HI-STAR 190 cask. Any potential hazard from transporter fire is bounded by the 30 minute fire evaluation in Section 3.4 of the HI-STAR 190 SAR [1.3.6] and is therefore incorporated by reference.

(d) Potential Fire Hazards: Site survey in Subsection 2.1.2 yields potential hazards which are evaluated herein. These are the presence of an oil recovery facility and underground run natural gas pipelines at the facility. There are no active oil wells on the site and there are no plans to use any of the plugged and abandoned wells on site. This section reviews the potential fire hazards from these sources that could affect spent fuel storage operations at storage pad and/or cask transfer operations along the haul path. The identified hazards from oil well and natural gas pipelines are evaluated for credibility and severity.

As stated in Table 2.1.4, the oil recovery facility or oil well is at a substantial distance from any cask structure either on the storage pad or haul path to cause a significant impact on fuel cladding temperature or cask structures. In an unlikely event oil well catches fire, emergency response plans are in place to mitigate the fire. If the oil well catches fire during transfer of MPC in HI-TRAC CS on the haul path, transfer cask shall be moved either to the storage pad or the cask transfer building.

The temporary flexible pipelines that run aboveground through the center of the site will be moved prior to or during the early construction phases of the CIS facility, as described in Subsection 2.1.2. Therefore, they do not present a fire hazard. The natural gas pipelines that run underground along the north-south axis to the east of the site do not present a real fire hazard.

6.5.2.2 Explosion Event

There are no credible internal explosive events at the HI-STORE ISFSI since all materials are compatible with the various operating environments, as discussed in Chapter 17, or appropriate preventive measures are taken to preclude internal explosive events (see Table 4.3.1). The canister is composed of non-explosive materials and maintains an inert gas environment. Thus explosion during long term storage is not credible. Likewise, the mandatory use of the protective measures at the HI-STORE site to prevent fires and explosions and the absence of any need for an explosive material during loading and unloading operations eliminates the scenario of an explosion as a credible event. Furthermore, because the MPC is internally pressurized, any short-term external pressure from explosion will act to reduce the tensile state of stress in the enclosure vessel. Nevertheless, a design basis external pressure (Table 4.3.1) has been defined as a design basis loading event wherein the internal pressure is non-mechanistically assumed to be absent. The ability of the canister to withstand loads due to an explosion event is evaluated in Chapter 3 of HI-STORM FW FSAR [1.3.7].

6.5.2.3 Burial under Debris

(a) Burial of HI-STORM UMAX VVM

There are no structures that loom over the HI-STORE HI-STORM UMAX ISFSI whose collapse could bury the VVMs in debris. A substantial distance from the ISFSI to the nearest ISFSI security fence (see Drawing in Section 1.5) precludes the close proximity of substantial amount of vegetation (native vegetation is low lying scrub). Thus, there is no credible mechanism for the HI-STORM UMAX system to become completely buried under debris.

(b) Collapse of the CTB

The CTB is a non-load bearing Butler building made of corrugated aluminum. The building does not support any crane or other loads and is designed to withstand the maximum wind applicable to the HI-STORE site. It is nevertheless assumed that the roof of the CTB will fall and cover the canister bearing casks that are in use within the CTB. The governing burial scenarios are shown in Figures 6.4.1 and 6.4.2 that involve the HI-STAR 190 metal cask (unventilated) and the HI-TRAC CS cask (ventilated), respectively. Because of the corrugated shape of the debris and the physical restrictions, it is assumed that the debris restricts the exiting air flow to only 10% of the unobstructed (normal) condition. A FLUENT analysis of the restricted flow in Figures 6.4.1 and 6.4.2 is performed. The steady state results for this accident on HI-TRAC CS and HI-STAR 190 when it is in the CTF are summarized in Tables 6.5.3 and 6.5.4. The results demonstrate integrity on fuel cladding and MPC confinement boundary are assured under a postulated CTB collapse accident.

6.5.2.4 Extreme Environmental Temperature

The extreme environmental accident evaluation for HI-STORM UMAX at HI-STORE is bounded by that in Paragraph 4.6.2.2 of the HI-STORM UMAX FSAR [1.0.6] due to the following:

- The PCT and component temperatures of MPC stored in HI-STORM UMAX at HI-STORE are lower than that of the same MPC presented in Section 4.4.4(i) of the HI-STORM UMAX FSAR under normal long-term storage condition [1.0.6].

- The extreme environment temperature at HI-STORE site is lower than that defined in HI-STORM UMAX FSAR [1.0.6] (see Table 6.3.1).

Therefore, Paragraph 4.6.2.2 of the HI-STORM UMAX FSAR [1.0.6] is incorporated by reference into this document.

6.5.2.5 100% Blockage of Air Vents

Thermal evaluation of 100% blockage of air vents accident event is bounded by that in Paragraph 4.6.2.3 of the HI-STORM UMAX FSAR [1.0.6] due to the following:

- The initial condition of the PCT and component temperatures of MPC stored in HI-STORM UMAX at HI-STORE is lower than that of the same MPC presented in Section 4.4.4(i) of the HI-STORM UMAX FSAR under normal long-term storage condition [1.0.6].
- Design basis heat load is lower in HI-STORM UMAX at HI-STORE (see Table 6.3.1) which results in lower heat-up rate.

Therefore, Paragraph 4.6.2.3 of the HI-STORM UMAX FSAR [1.0.6] is incorporated by reference into this document. The amount of heat removed from the MPC external surfaces by natural circulation of air is reduced to less than 1% of that under normal conditions (i.e. when inlet and outlet vents completely unblocked). Therefore, in an event of complete blockage of both inlet and outlet vents, that small additional heat removal capability by air through outlet vents is also lost. This will result in a small temperature rise compared to the large available temperature margins established from the transient study of complete inlet vents blockage in Paragraph 4.6.2.3 of the HI-STORM UMAX FSAR [1.0.6]. This accident condition is, however, a short duration event that is identified and corrected through scheduled periodic surveillance. The periodic surveillance time requirement is adopted the same as that in HI-STORM UMAX FSAR [1.0.6].

6.5.2.6 Flood

The flood accident evaluation is bounded by that in Paragraph 4.6.2.5 of the HI-STORM UMAX FSAR [1.0.6] due to the following:

- The Design Basis Flood used to qualify the VVM in the HI-STORM UMAX FSAR [1.0.6] (up to 5 inch) exceeds the most severe projection of flood at the ELEA site i.e. up to 4.8 inch (see Subsection 2.4.3).
- The initial condition of the PCT and component temperatures of MPC stored in HI-STORM UMAX at HI-STORE is lower than that of the same MPC presented in Section 4.4.4(i) of the HI-STORM UMAX FSAR under normal long-term storage condition [1.0.6].

Therefore, Paragraph 4.6.2.5 of the HI-STORM UMAX FSAR [1.0.6] is incorporated by reference into this document.

6.5.3 SSCs Important to Safety Guidance for Fire Protection Program

There are no combustible or explosive materials associated with the HI-STORM UMAX System. Combustible materials will not be stored within an ISFSI. However, for conservatism, a

hypothetical fire accident has been analyzed as a bounding condition for HI-STORM UMAX System. The evaluation of the HI-STORM UMAX System fire accident is discussed in Subsection 6.5.2. Similarly, there are no credible internal explosive events at the HI-STORE ISFSI since all materials are compatible with the operating environments, or appropriate preventive measures are taken to preclude explosions. The canister is composed of non-explosive materials and maintains an inert gas environment. Thus explosion during long term storage is not credible. Likewise, the mandatory use of the protective measures at the HI-STORE site to prevent fires and explosions and the absence of any need for an explosive material during loading and unloading operations eliminates the scenario of an explosion as a credible event. An emergency response plan is in place as described in emergency response plan report [10.5.1]. The Holtec CISF Emergency Response Plan [10.5.1] evaluates and describes the necessary and sufficient emergency response capabilities for managing fire emergency conditions associated with the operation of the HI-STORE facility. The plan meets all requirements of 10CFR72.32 (a).

Measures for fire prevention, fire detection, fire suppression, and fire containment for the protection of the spent fuel assemblies and cask structures important to safety are provided in emergency response plan [10.5.1]. The fire detection and suppression systems are contained within the Canister Transfer Building. The construction materials of the Canister Transfer Building do not support combustion, and the fire-prone materials are limited to diesel fuel. Fires are analyzed for all casks in Subsection 6.5.2 of this SAR. The area surrounding the storage pads and Canister Transfer Building includes a gravel-covered fire break with vegetation control to limit potential fuel for fires. The nonflammable nature of the materials of construction, other passive design features, and the limited fuel sources at the Facility lead to the conclusion that the fire detection and suppression systems are correctly classified as not important to safety.

The design of the Facility is such that all structures, systems, and components are located within a region covered with crushed rock. Therefore, there is no credible wildfire load on structures, systems, and components important to safety. A range of onsite fire scenarios has been evaluated. Bounding fire events are based on the volume of combustibles in the transporter, as given in Table 6.5.1. Operational restrictions are in place to ensure that these levels are not exceeded. The cask structures are designed so that they can continue to perform their safety functions under credible fire and explosion exposure conditions. Additionally, the cask structures containing spent fuel are located at significant distances from potential fire hazards identified on site.

Table 6.5.1: Cask Transporter Combustible Quantities and Fire Duration	
Description	**Value**
Volume of Combustibles, gallon	430
Fuel Area around HI-TRAC CS Cask, ft^2	291.6
Depth of Combustibles, inch	2.366
Fuel consumption rate, in/min [6.5.1]	0.15
Fire Duration, seconds	946 (Note 1)
Note 1: Thermal evaluations of HI-TRAC CS fire conservatively performed for a larger duration.	

Table 6.5.2: HI-TRAC CS Fire and Post-Fire Accident Results		
Component	**Temperature, °F**	
	End of Fire	**Post-Fire[Note 1]**
Fuel Cladding	670	701
Fuel Basket	615	650
Basket Shims	508	537
MPC Shell	512	512
MPC Lid[1]	474	474
MPC Baseplate[1]	426	527
HI-TRAC Inner Shell	886	886
HI-TRAC Concrete	1380 (Note 2)	1380 (Note 2)
HI-TRAC Outer Shell[2]	1092	1092
	Pressure, psig	
MPC Cavity Pressure	100.2	

Note 1: Maximum temperatures are reported during the fire event.
Note 2: An extremely small area of concrete skin towards the top of the HI-TRAC is unavailable for shielding since it exceeds the temperature limit specified in Table 4.4.1.

[1] Maximum section average temperature is reported.

[2] Bulk temperature is reported.

Table 6.5.3: HI-TRAC CS Maximum Temperatures due to Cask Blockage from Debris (CTB Collapse Accident)	
Component	**Temperature, ^{o}F**
Fuel Cladding	918
Fuel Basket	869
Basket Shims	757
MPC Shell	718
MPC Lid[1]	649
MPC Baseplate[1]	642
HI-TRAC Inner Shell	642
HI-TRAC Concrete	640
HI-TRAC Outer Shell	351
	Pressure, psig
MPC Cavity Pressure	125.8

[1] Maximum section average temperature is reported.

Table 6.5.4: Maximum Temperatures of HI-STAR 190 when Placed in CTF during CTB Collapse Accident	
Component	**Temperature, ^{o}F**
Fuel Cladding	862
Fuel Basket	813
Basket Shims	709
MPC Shell	664
MPC Lid[1]	630
MPC Baseplate[1]	531
Containment Shell	592
Enclosure Shell	550
Closure Lid[1]	475
	Pressure, psig
MPC Cavity Pressure	118.6

[1] Maximum section average temperature is reported.

6.6 REGULATORY COMPLIANCE

The thermal compliance pursuant to the provisions of NUREG-1567 [1/0/3] and ISG-11 [4.0.1] for deployment of canisters certified in the HI-STORM UMAX docket number (72-1040) has been demonstrated in this chapter. As the canisters will arrive at the HI-STORE site loaded in the transport package, the Short Term Operations on the (dry) canisters to place them in the HI-STORM UMAX VVMs and their interim storage in the VVMs are the subjects of safety analysis in this chapter.

Following the guidance of ISG-11 [4.0.1], the fuel cladding temperature at the beginning of dry storage at HI-STORE will be below the anticipated damage-threshold temperatures for normal conditions of storage for the licensed life of the HI-STORM UMAX System. Maximum fuel cladding temperatures for long-term storage conditions are reported in Section 6.4. The large margin to the ISG-11 limit for the fuel cladding temperature at the HI-STORE ISFSI provides added assurance that the breach of fuel cladding in storage is extremely unlikely.

Following the guidance of NUREG-1567, the system is passively cooled. All heat rejection mechanisms described in this chapter, including conduction, natural convection, and thermal radiation, are completely passive.

During Short Term Operations, the ISG-11 requirement to ensure that maximum cladding temperatures be below 400°C (752°F) for high burnup fuel and below 570°C (1058°F) for moderate burnup fuel is satisfied with ample margin.

Events of extremely low probability such as an enveloping fire and an extreme environmental phenomenon leading to burial of the transfer or transport cask in debris have been analyzed for their compliance with the temperature limits set down for fuel cladding, structural weldments and shielding materials. The results show ample margins of safety against regulatory limits.

It is therefore concluded that all applicable regulatory requirements and guidelines germane to the integrity of the stored fuel and the HI-STORM UMAX storage system have been addressed and satisfied in this chapter.

APPENDIX 6A: [PROPRIETARY APPENDIX WITHHELD IN ITS ENTIRETY IN ACCORDANCE WITH 10CFR2.390]

CHAPTER 7: SHIELDING EVALUATION*

7.0 INTRODUCTION

The shielding evaluations for the HI-STORE CIS Facility are presented in this chapter, including dose and dose rate calculations to show that the facility is in compliance with the applicable regulatory requirements.

Specifically, evaluations and calculations are presented here for the following conditions and configurations:

- Owner Controlled Area boundary, with dose rates and annual dose for the location closest to the ISFSI. An ISFSI with 500 loaded HI-STORM UMAX VVMs, consistent with the description in Section 1.1, is used for the evaluations, and conservative assumptions on the content of each canister.
- Occupational dose rates at the surface and 1 meter from a single HI-STORM UMAX.
- Occupational dose rates at the surface, 0.5 meters, 1 meter, and 2 meters from the HI-TRAC CS

The HI-STORE CIS Facility utilizes the HI-STORM UMAX storage system (Docket #72-1040), and only canisters approved for that system and listed in Table 1.0.3 are permitted for storage in the facility. Therefore, the principal calculational approach, including principal assumptions and methodologies, are directly taken from the HI-STORM UMAX FSAR, and are incorporated by reference. Table 7.0.1 lists all sections from the HI-STORM UMAX FSAR that are incorporated by reference, together with a technical justification. However, some additional shielding evaluation that is different from that in the HI-STORM UMAX FSAR is required specifically for the HI-STORE CIS Facility, due to site-specific considerations. These additional shielding evaluations are clearly identified in the following sections. In brief, they contain the following:

- The dose analyses in the HI-STORM UMAX FSAR focus on dose rates around a single VVM, and only a few hypothetical ISFSI configurations were analyzed. In the evaluations presented here, the full ISFSI as described in Section 1.1 is used as the basis of the evaluation.
- The HI-STORM UMAX storage VVM used here is slightly modified compared to the version documents in the HI-STORM UMAX FSAR [1.0.6], with lower doses and other improvements not related to the shielding analyses. General details of this version are presented in Section 1.2. This is considered in the dose evaluations presented here.
- The HI-STORM UMAX FSAR assumes the use of a generic transfer cask (HI-TRAC VW) suitable for canister loading in a spent fuel pool. Since wet loading of canisters is not part of the operation of the HI-STORE CIS facility, a different HI-TRAC, termed HI-TRAC CS, with improved shielding and improved operational characteristics is used.

* All references are in placed within square brackets in this report and are compiled in Chapter 19 (References)

Details of this HI-TRAC CS are presented in Section 1.2. Dose rate evaluations for this transfer cask are presented in this chapter.

- The dose estimates for loading operations consider the operational sequence for canister loading at the HI-STORE facility, which includes the unloading of the transport cask, stackup operation between the transport cask and the HI-TRAC CS, transfer movement to the HI-STORM UMAX VVM ISFSI, and downloading of the canister into the HI-STORM UMAX VVM.

Table 7.0.1: Material Incorporated by Reference in this Chapter				
Information Incorporated by Reference	**Source of the Information**	**NRC Approval of Material Incorporated by Reference**	**Location in this SAR where Material is Incorporated**	**Technical Justification of Applicability to HI-STORM UMAX**
HI-STORM UMAX Evaluation Methodologies	Sections 5.1, 5.2, 5.3, and 5.4; Reference [1.0.6]	SER HI-STORM UMAX Amendments 0, 1, and 2 References [7.0.1, 7.0.2, 7.0.3]	Sections 7.1, 7.2, and 7.4	The general HI-STORM UMAX design is the same from a shielding perspective as the one described in the HI-STORM UMAX FSAR with minor differences in design details, so the approaches, general assumptions and methods established in the HI-STORM UMAX FSAR are fully applicable to the HI-STORM UMAX utilized for the HI-STORE facility. Note that the HI-STORM UMAX FSAR includes references to the HI-STORM FW FSAR, since both share the same canister models. However, since the HI-STORM UMAX FSAR includes relevant excerpts from the HI-STORM FW FSAR, no part of the HI-STORM FW FSAR needs to be incorporated by reference into the HI-STORE SAR in this chapter.

7.1 CONTAINED RADIATION SOURCES

7.1.1 General Specification and Approach for Neutron and Gamma Sources

The HI-STORE CIS Facility is designed for spent fuel and associated hardware in sealed canisters. The principal description of the source terms for the fuel, together with the calculations methodologies, is presented in Section 5.2 of the HI-STORM UMAX FSAR [1.0.6], which is incorporated here by reference. The only additional discussion needed here is the justification of the design basis assembly assumption presented below.

7.1.2 Design Basis Assemblies

The design basis assemblies in [1.0.6] are industry standard 17x17 PWR assemblies, with a burnup, enrichment and cooling time combination specified in Table 5.0.1 of [1.0.6]. These parameters while conservative for HI-STORM UMAX systems loaded on ISFSIs at Nuclear Power Plant sites, far exceed the allowable heat load of the HI-STAR 190 (Table 7.C.7 of Reference [1.3.6]) and other transportation casks that would be used to transport canisters to the HI-STORE CIS Facility. Therefore, a conservative but more realistic set of burnup, cooling time, and initial enrichment parameters as shown in Table 7.1.1 that have a heat load comparable to Table 4.1.1 are used for site-specific HI-STORE CIS Facility shielding calculations.

A number of conservative assumptions are applied throughout the HI-STORE CIS Facility shielding calculations. These assumptions assure that actual dose rates will always be below the calculated dose rates, and below regulatory limits. Selected key assumptions are:

[

PROPRIETARY INFORMATION WITHHELD PER 10CFR2.390

]

- Assemblies with higher burnups
    - Those would also have correspondingly higher cooling times to meet transport requirements
- PWR fuel assemblies that differ from HI-STORM UMAX FSAR [1.0.6] design basis fuel assemblies
- The MPC-89 canister with BWR fuel.
    - Calculations for the HI-STORM FW [1.3.7] show that the results for the MPC-37 and MPC-89 are comparable

Table 7.1.1: Design Basis Fuel Burnup, Cooling Time, and Enrichment for Dose Evaluation			
MPC TYPE	**BURN- UP (GWD/MTU)**	**COOLING TIME (YEARS)**	**ENRICHMENT (Wt % U-235)**
MPC-37	45	8	3.2

7.2 STORAGE AND TRANSFER SYSTEMS

7.2.1 Design Criteria

The design criteria, namely the relevant regulatory dose and dose rate, and ALARA requirements are presented in Chapter 4.

7.2.2 Design Features

7.2.2.1 Storage System

The version of the HI-STORM UMAX storage system used here is slightly different from that described in [1.0.6]. However, the differences are minor, and do not affect the principal design features of the system. A discussion of the shielding design features of the storage system see Subsection 5.1.1 in [1.0.6]. This Subsection is incorporated here by reference.

The storage system design is based on a metal canister that is sealed by welding for spent fuel confinement, preventing release of radionuclides from inside the canister. Radioactive effluents are thus precluded by design. This meets the intent of 10CFR72.24(e) and 10CFR72.126(d) [1.0.5], which requires that the ISFSI design provide means to limit the release of radioactive materials in effluents during normal operations to levels that are ALARA. There are no radioactive effluents released from the CIS Facility during normal operations. This passive system design also requires minimum maintenance and surveillance requirements by personnel.

7.2.2.2 Transfer Cask HI-TRAC CS

As discussed before, the HI-STORE facility uses a different transfer cask, HI-TRAC CS, than used in the operation of the generic HI-STORM UMAX and HI-STORM FW system. Instead of lead and steel for gamma shielding, and water for neutron shielding, it uses steel and concrete for both gamma and neutron shielding, and has an integrated bottom door for operational purposes. A detailed description of the HI-TRAC CS design is presented in Subsection 1.2.4. With its higher weight and integrated bottom shield gates, it provides significant advantages in dose rates and operational doses compared to the lead and water design.

7.3 SHIELDING COMPOSITION AND DETAILS

7.3.1 Composition and Material Properties

The composition and material properties for the concrete and soil used in the MCNP model of the HI-STORM UMAX System is provided in Table 7.3.1. The material compositions and material properties of the storage system are provided in Subsection 5.3.2 and Table 5.3.2 in [1.0.6]. This section and table are incorporated by reference into this document.

The material compositions and properties for the materials used for the HI-TRAC CS are the same as those for the corresponding materials in Table 5.3.2 in [1.0.6], except for the concrete in the transfer cask body, which is specified in Table 7.3.1 at the end of this subsection.

7.3.2 Shielding Details

For shielding details of the canisters see Section 5.3 in [1.0.6]. This section is incorporated by reference into this document.

Chapter 1 provides the drawings that describe the HI-STORM UMAX System including the HI-TRAC CS transfer cask. These drawings, using nominal dimensions, were used to create the MCNP models used in the radiation transport calculations for the transfer cask. Figure 7.4.1 shows a cross sectional view of the HI-TRAC CS with the MPC-37. Figure 7.4.2 shows the HI-STORM UMAX Version C as modeled in MCNP. These figures were created in the visual editor provided with MCNP, and are drawn to scale.

Conservatively the walls of the HI-TRAC CS are shorter than the dimensions shown in Section 1.5 Licensing Drawings and the optional Annulus Shield Ring is not credited.

Table 7.3.1 Composition of Concrete and Soil

Component	Density (g/cm^3)	Elements	Mass Fraction (%)
HI-TRAC CS Concrete	Normal Conditions 3.05 Accident Conditions 2.40 Ground 2.30	O	53.2
		Si	33.7
		Ca	4.4
		Al	3.4
		Na	2.9
		Fe	1.4
		H	1.0
HI-STORM UMAX Concrete	Lid 2.40 C.E.C Plenum Shield 2.16 ISFSI Pad 2.16 Support Foundation Pad 1.92	O	53.2
		Si	33.7
		Ca	4.4
		Al	3.4
		Na	2.9
		Fe	1.4
		H	1.0
Soil	Ground 1.92 Beneath VVM 1.7	H	0.962
		O	54.361
		Al	12.859
		Si	31.818

7.4 SHIELDING ANALYSES METHODS AND RESULTS

7.4.1 Computational Methods and Data

Computational methods and associated data is provided in Section 5.4 in [1.0.6]. This section is incorporated by reference into this document.

For doses and does rates from the entire ISFSI, the contribution from each individual VVM is calculated, considering the distance of the VVM to the selected dose location, and then the results for all VVMs are added.

7.4.2 Dose and Dose Rate Estimates

7.4.2.1 Normal Conditions

Dose rates around a HI-TRAC CS and around a single HI-STORM UMAX storage module, loaded with the MPC-37 and design basis fuel, are presented in Table 7.4.1 and 7.4.2 respectively. It can be concluded from the shielding analysis and results that the HI-TRAC CS and HI-STORM UMAX provide suitable shielding in accordance with 10CFR72.128(a)(2) [1.0.5].

Dose rates, and annual dose from 500 loaded HI-STORM UMAX VVMs at the ISFSI for various distances are presented in Table 7.4.3. Figure 7.4.3 shows ISFSI dose rates as a function of distance.

The maximum controlled area boundary dose rate (assuming an occupancy of 2,000 hours per year) is below the 25 mrem annual dose limit of 10CFR72.104 [1.0.5].

The nearest residence is 1.5 miles from the HI-STORE CIS Facility. The dose calculations conservatively assume a full-time resident (8760 hours/year) is only 1000 meters from the nearest loaded HI-STORM UMAX VVM. In the case of this nearest residence, the dose is calculated to be below the 25 mrem annual dose limit prescribed in 10CFR72.104 [1.0.5].

Operations inside the Canister Transfer Building would not contribute significantly to dose rates at the Controlled Area Boundary since the loaded canisters are shielded at all times by a shipping or transfer cask. The operational steps to load a single storage module, together with the estimated duration and dose rate for each step, and the cumulative crew dose for the entire operation, is presented in Chapter 11 (Radiation Protection).

Occupational doses to individuals are administratively controlled to ensure that they are maintained below 10CFR20.1201(a)(1) annual limits [7.4.1] i.e. the more limiting of:

i. The total effective dose equivalent being equal to 5 rem (0.05 Sv); or

ii. The sum deep-dose equivalent and the committed dose equivalent to any individual organ or tissue other than the lens of the eye being equal to 50 rem (0.5 Sv).

Operational controls ensure the total effective dose equivalent to individual members of the public from the licensed operation does not exceed 0.1 rem (1 mSv) in accordance with 10CFR20.1301(a)(1) [7.4.1] and that the dose in any unrestricted area from external sources does not exceed 2 mrem (0.02 mSv) in any one hour 10CFR20.1301(a)(2) [7.4.1].

TLDs are located at the Restricted Area fence and at the Controlled Area Boundary in accordance with 10CFR20.1302 [7.4.1] to show compliance with the annual dose limit in 10CFR20.1301 [7.4.1].

7.4.2.2 Off-Normal and Accident Conditions

The only off-normal or accident condition applicable to the HI-STORM UMAX storage system is the missile impact during construction next to a loaded canister. This condition is analyzed and modeled in Section 5.1 and 5.3 of the HI-STORM UMAX FSAR [1.0.6]. The evaluation of this missile impact event shows that the regulatory dose limits are met for this condition. The respective sections are hereby incorporated by reference into this document.

The HI-TRAC CS is always carried with single failure proof equipment when loaded with a canister, hence any drop accident that could result in an increase in does rates is not credible. Further, unlike the HI-TRAC VW used in the HI-STORM UMAX FSAR, the HI-TRAC CS does not contain any water as neutron absorber. A loss of water accident is therefore not possible. However, under the fire accident condition, the outside of the cask would heat up significantly, and while the outer steel shell would assure the overall integrity of the cask, and hence prevent any significant loss of shielding function, the outer area of the shielding concrete may experience some degradation. To model this in an analysis, shielding calculations are performed in which the density of the HI-TRAC CS concrete is assumed to be substantially degraded as shown in Table 7.3.1. Results of the analyses are presented in Table 7.4.4, with the resulting accident dose (assuming a 30 day accident duration) at 100 m from the cask showing compliance with the requirements of 10CFR72.106 [1.0.5].

Table 7.4.1: Dose Rates from the HI-TRAC CS MPC-37 Design Basis Fuel 45,000 MWD/MTU and 8-Year Cooling			
Dose Point Location[1]	**Gamma Dose Rate[2] (mrem/hr)**	**Neutron Dose Rate (mrem/hr)**	**Total Dose Rate (mrem/hr)**
Surface of HI-TRAC CS			
Bottom Duct	58	54	**111**
60 inches below Mid-Height	57	2	**58**
Mid-Height	58	2	**60**
60 inches above Mid-Height	48	1	**48**
Center of Top Lid	867	156	**1023**
0.5 meters from HI-TRAC CS			
Bottom Duct	24	10	**35**
60 inches below Mid-Height	35	2	**36**
Mid-Height	37	1	**38**
60 inches above Mid-Height	27	1	**27**
1 meter from HI-TRAC CS			
Bottom Duct	18	6	**24**
60 inches below Mid-Height	24	2	**25**
Mid-Height	27	1	**27**
60 inches above Mid-Height	18	1	**19**
2 meters from HI-TRAC CS			
Bottom Duct	14	3	**17**
60 inches below Mid-Height	14	1	**15**
Mid-Height	17	1	**17**
60 inches above Mid-Height	11	1	**12**

[1] Refer to Figure 7.4.1.
[2] Dose rate from gammas include gammas generated by neutron capture, fuel gammas, Co-60 gammas and BPRA gammas.

Table 7.4.2: Dose Rates Adjacent to and 1 Meter from the HI-STORM UMAX Module for Normal Conditions MPC-37 Design Basis Zircaloy Clad Fuel			
Dose Point Location[1]	**Gamma Dose Rate[2] (mrem/hr)**	**Neutron Dose Rate (mrem/hr)**	**Total Dose Rate (mrem/hr)**
Surface of Closure Lid			
1	10.70	2.47	13.17
2	3.19	1.45	4.64
3	2.67	0.74	3.41
4	4.34	1.53	5.87
5	13.72	3.40	17.12
One Meter from Closure Lid			
1	0.40	0.30	0.70
2	0.36	0.22	0.59
3	0.90	0.35	1.24
4	1.03	0.29	1.32
5	0.31	0.19	0.50

[1] Refer to Figure 7.4.2 for dose point locations.
[2] Dose rate from gammas include gammas generated by neutron capture, fuel gammas, Co-60 gammas, and BPRA gammas.

Table 7.4.3: Dose Rates as a Function of Distance from 500 Loaded HI-STORM UMAX VVMs for Fuel Assemblies with a Burnup of 45,000 MWD/MTU, an Initial U-235 Enrichment of 3.2 wt%, and a Cooling Time of 8 Years

Distance (m)	Total Dose Rate (mrem/hr)	2000 hour/year Occupancy	8760 hour/year Occupancy
		Total Dose (mrem/yr)	Total Dose (mrem/yr)
10	5.84E-01	1.17E+03	5.11E+03
20	3.91E-01	7.82E+02	3.43E+03
30	2.88E-01	5.77E+02	2.53E+03
40	2.21E-01	4.41E+02	1.93E+03
50	1.73E-01	3.46E+02	1.51E+03
75	9.99E-02	2.00E+02	8.75E+02
100	6.17E-02	1.23E+02	5.40E+02
150	2.65E-02	5.29E+01	2.32E+02
200	1.24E-02	2.49E+01	1.09E+02
250	6.19E-03	1.24E+01	5.42E+01
300	3.22E-03	6.43E+00	2.82E+01
350	1.73E-03	3.46E+00	1.52E+01
400	9.63E-04	1.93E+00	8.44E+00
450	5.53E-04	1.11E+00	4.85E+00
500	3.27E-04	6.53E-01	2.86E+00
600	1.24E-04	2.47E-01	1.08E+00
700	5.42E-05	1.08E-01	4.75E-01
800	2.55E-05	5.10E-02	2.23E-01
900	1.28E-05	2.56E-02	1.12E-01
1000	9.68E-06	1.94E-02	8.48E-02

Table 7.4.4 Dose at 100 Meters from a Single HI-TRAC CS with MPC-37 Loaded with Design Basis Fuel for Accident Condition[1]
Dose (Rem)
0.083

[1] Accident duration is assumed to be 30 days.

Figure 7.4.1 [PROPRIETARY INFORMATION WITHHELD PER 10CFR2.390]

Figure 7.4.2. [PROPRIETARY INFORMATION WITHHELD PER 10CFR2.390]

Figure 7.4.2. [PROPRIETARY INFORMATION WITHHELD PER 10CFR2.390]



Figure 7.4.3. HI-STORE CIS Facility HI-STORM UMAX VVM ISFSI Dose Rates as a Function of Distance (500 loaded HI-STORM UMAX VVMs)

7.5 SUMMARY

In summary, the design of the facility satisfies all regulatory criteria and limits for radiological protection, and provides acceptable means for limiting the exposure of the public to direct and scattered radiation.

CHAPTER 8: CRITICALITY EVALUATION*

8.0 INTRODUCTION

The criticality safety qualification of the canisters for installation at the HI-STORE CIS facility is considered in this chapter. An essential commitment in this SAR is that only those canisters that have been certified and loaded under the HI-STORM UMAX docket (#72-1040) may be stored at the HI-STORE facility. Reactivity of the stored fuel in a canister depends foremost on the configuration of the fuel basket and to a lesser extent on the circumscribing Enclosure Vessel around the basket. Because the canister shipped from the originating site has already been designed, built, loaded and certified to an NRC-issued Technical Specification, the subcriticality of the canister is pre-established. Thus, for example, for the canisters denoted as MPC-37 and MPC-89, the substantiating criticality safety demonstration is in the HI-STORM FW FSAR [1.3.7]. This qualification as also been utilized in the regulatory review and certification for storage in the HI-STORM UMAX system in docket # 72-1040. Since the same HI-STORM UMAX system is proposed to be deployed at HI-STORE, the criticality safety determination by the NRC in docket # 72-1040 remains applicable. This axiomatic qualification of the canisters will remain valid unless the canister and its fuel basket are physically altered during their transport or handling to the HI-STORE facility which will summarily disqualify them from storage under the HI-STORE CIS docket.

* All references are placed within square brackets in this report and are compiled in Chapter 19 (last chapter)

Table 8.0.1: Material Incorporated by Reference in this Chapter				
Information Incorporated by Reference	**Source of the Information**	**NRC Approval of Material Incorporated by Reference**	**Location in this SAR where Material is Incorporated**	**Technical Justification of Applicability to HI-STORM UMAX**
MPC-37 and MPC-89 Criticality Evaluation	Sections 6.1, 6.2, 6.3, 6.4, and 6.5; Appendices 6.A and 6.B of Reference [1.3.7]	SER HI-STORM FW Amendments 0, 1, and 2 References [8.0.1, 8.0.2, and 8.0.3]	Sections 8.1, 8.3, and 8.4	The canister is the same as the one described in the FW FSAR and originally approved in the referenced SER. There is no change to the fuel basket, and canister integrity is ensured by the acceptance test criteria established in this SAR.
Applicability of HI-STORM FW criticality evaluation to HI-STORM UMAX system	Section 6.2 of Reference [1.0.6]	SER HI-STORM UMAX Amendments 0, 1, and 2 References [7.0.1, 7.0.2, 7.0.3]	Sections 8.3, and 8.4	The HI-STORM UMAX design is the same from a criticality perspective as the one described in the HI-STORM UMAX FSAR and so the conclusions established therein that the HI-STORM FW criticality analysis is fully applicable to the HI-STORM UMAX, remain unchanged in this SAR.

8.1 CRITICALITY DESIGN CRITERIA AND FEATURES

8.1.1 Criteria

The acceptance criteria for criticality evaluations for the HI-STORM UMAX system utilized at the HI-STORE facility are presented in Chapter 4 of this SAR.

8.1.2 Features

Section 6.1 of the HI-STORM FW FSAR [1.3.7] is incorporated by reference into this SAR, and describes all the criticality design features of the canisters which maintain the stored fuel in a sub-critical condition.

8.2 STORED MATERIAL SPECIFICATIONS

The fuel assemblies allowable for storage in the HI-STORM UMAX VVMs at the HI-STORE facility are described in Section 4.1.

8.3 EVALUATION

During storage conditions in the HI-STORM UMAX system, the maximum k_{eff} will be significantly below the limiting maximum k_{eff} since the MPC is internally dry. Under this condition, the configuration is very similar in all other HI-STORM models, which consists of an internally dry MPC, an air gap between the MPC and the overpack, a steel shell or shells and concrete (above-ground) or soil (underground). Results for the HI-STORM UMAX VVM would therefore be practically identical to the results listed for storage conditions in Chapter 6 of the canister's native FSAR (such as the HI-STORM FW FSAR [1.3.7] for the canisters subsequently certified under the HI-STORM UMAX FSAR [1.0.6], which are now included in this site-specific license. Any small differences in results would not affect the principal conclusions, since the maximum k_{eff} under storage conditions (dry inert environment) is substantially below the regulatory limit. It should be noted that the analysis for the canisters in the various HI-STORM models conservatively assumes that the gap between the canister and the HI-STORM is flooded with water, thus increasing the neutron reflection compared to a dry cavity [8.0.1, Section 7]. Flooding under accident conditions of the HI-STORM UMAX is therefore also covered by the calculations for the HI-STORM FW (see also Subsection 8.3.2 below). All other normal, off-normal and accident conditions in the HI-STORM UMAX system at HI-STORE are identical to or less severe than invoked for certification in the generic dockets (such as HI-STORM FW) which consider bounding loadings for the entire continental United States.

In summary, the limiting condition for storage of the canisters certified in the generic docket for HI-STORM UMAX (Docket # 72-1040) is identical to their storage in HI-STORM UMAX at HI-STORE from a criticality perspective, and all other normal, off-normal and accident conditions are identical or equivalent between the two dockets from a criticality perspective. Therefore, the criticality safety of the canisters certified in docket # 72-1040 is *a priori* ensured for storing those canisters at HI-STORE. No additional calculations to demonstrate criticality safety are required for storing such canisters in the HI-STORM UMAX system at HI-STORE.

8.3.1 Model Configuration

The model configuration including material properties for the criticality analysis is incorporated by reference from Section 6.3 of [1.3.7], as described in Table 8.0.1 of this SAR.

8.3.2 Accidental Criticality

10CFR72.124(a) requires that at least two unlikely events (changes) must occur before a criticality accident is possible. The HI-STORM UMAX implementation at the HI-STORE facility would in fact require three such events before an accident is possible, and is therefore in compliance with the abovementioned regulation. The three unlikely events applicable to the facility are as follows

- The site is in a dry area with no flood plains (see [1.0.4], Subsection 3.5.4). Even the 100,000 year flood is estimated to be only 4.8 inches (see [1.0.4], Subsection 4.5.3), and at that level the design of the systems would prevent any flooding of the CECs, since the lowest points of the air inlets or outlets are higher above the ground than this value. Further, the pads are designed and constructed so that rainwater will run off and not accumulate. A water spray was performed on the first HI-STORM UMAX systems installed at a site to demonstrate this

after installation. Based on this, a flooding of the CECs is unlikely, in fact considered not credible.

- However, even if a CEC would be flooded, the internal cavity of the canister with the basket and fuel would remain dry, and hence the reactivity would remain very low. The canister is seal-welded, and the integrity of the canister is verified during the acceptance tests when it enters the site. For the initially licensed period of each canister, this gives assurance that a leak of the canister that would allow ingress of water is unlikely. For longer storage times beyond the initially licensed period, an aging management program is applied, designed to detect and mitigate any such leaks, making water inleakage also an unlikely event.
- Finally, the fact that canisters are not loaded on-site, but always be delivered to the site in a 10CFR71 approved transportation cask, together with the acceptance tests for each transport cask, presents the third barrier, which would prevent a criticality accident even in the unlikely event that both the CEC and the canister would be flooded:
    - The transport regulations require that the package remains subcritical under normal conditions when flooded with pure water.
        - For BWR fuel that is essentially met by default, since canisters are loaded in a pool with fresh water
        - For PWR fuel, the requirements for transportation in the HI-STAR 190 require burnup credit so that the same requirement is met, i.e. subcriticality when flooded with fresh water
    - The transportation cask to be used for the approved canisters (HI-STAR 190) will also be qualified for High Burnup Fuel, where fuel damage is possible. In that case, the criticality safety evaluation for the package does not assume flooding of the canister. However, the acceptance tests for the acceptance of the canister on site excludes canisters from transports that have undergone any accident condition, as described in the Facility Technical Specifications. This scenario is therefore not applicable here.

  Based on this, even for a flooded canister, accidental criticality is unlikey.

Overall, at least three unlikely (or non-credible) events would be required before accidental criticality could be possible at the HI-STORE facility. The facility is therefore in compliance with 10CFR72.124(a).

8.4 APPLICANT CRITICALITY ANALYSIS

The criticality analysis for the MPC-37 and MPC-89 is incorporated by reference from Section 6.4 of [1.3.7], as described in Table 8.0.1 of this SAR, including the computer program utilized, multiplication factor, and benchmark comparison. The discussion of how these HI-STORM FW results apply to the HI-STORM UMAX system is incorporated by reference from Section 6.2 of [1.0.6]. The configuration and confinement of the canisters are unchanged based on the discussion in Chapter 9, so the existing analysis is fully applicable to the HI-STORE CIS Facility.

8.5 CRITICALITY MONITORING

10CFR72.124(c) requires criticality monitoring during operations unless the fuel is already packaged in the storage configuration. At the HI-STORE facility, no wet fuel operations are performed, and fuel will always be in the dry and sealed canisters, i.e. in the storage configuration. Hence criticality monitoring per 10CFR72.124(c) is not required.

CHAPTER 9: CONFINEMENT EVALUATION*

9.0 INTRODUCTION

The confinement safety of the HI-STORE CIS facility is considered in this chapter. In accordance with NUREG-1567 [1.0.3] the following areas are addressed

- Potential of the release of radioactive material
- Monitoring systems
- Protection of stored materials from degradation

The evaluation of any potential release considers both the storage systems and the operational activities.

Additionally, for the storage systems, aspects of receipt inspections for systems delivered to the site, and long term aging are briefly addressed, with full details presented in other chapters of this SAR and referenced appropriately.

With respect to the storage systems themselves, only radioactive materials in seal-welded canisters are accepted and placed into storage in this facility. Further, this is limited to those canisters that are certified for storage in the HI-STORM UMAX docket (Docket #72-1040). Hence this chapter contains references to sections of the FSAR of the HI-STORM UMAX. The sections that are included by reference from the HI-STORM UMAX FSAR are listed in Table 9.0.1.

* All references are in placed within square brackets in this report and are compiled in Chapter 19 (last chapter)

Table 9.0.1: Material Incorporated by Reference in this Chapter				
Information Incorporated by Reference	**Source of the Information**	**NRC Approval of Material Incorporated by Reference**	**Location in this SAR where Material is Incorporated**	**Technical Justification of Applicability to HI-STORM UMAX**
HI-STORM UMAX Confinement Evaluation	Chapter 7 of [1.0.6]	SER HI-STORM UMAX Amendments 0, 1, and 2 References [7.0.1, 7.0.2, 7.0.3]	Section 9.2.1	Only canisters approved for use in HI-STORM UMAX under its certificate are permitted for storage in the HI-STORE facility. Further, the HI-STORM UMAX storage system used for storage if the canisters are principally the same as that in the HI-STORM UMAX FSAR. Additionally, the conditions, namely the environmental temperatures, and canisters heat loads, for the HI-STORE facility are bounded by the values the canisters are qualified for in the HI-STORM UMAX FSAR. Hence the containment evaluation in the HI-STORM UMAX FSAR is fully applicable to the HI-STORM UMAX utilized for the HI-STORE facility. Note that the HI-STORM UMAX FSAR includes references to the HI-STORM FW FSAR, since both share the same canister models. However, since the HI-STORM UMAX FSAR includes relevant excerpts from the HI-STORM FW FSAR, no part of the HI-STORM FW FSAR needs to be incorporated by reference into the HI-STORE SAR in this chapter.

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

9.1 ACCEPTANCE CRITERIA

The acceptance criteria for confinement evaluations for are presented in Chapter 4 of this SAR.

9.2 CONFINEMENT OF RADIOACTIVE MATERIALS

9.2.1 Storage Systems

Continued Storage

Only canisters approved for use in HI-STORM UMAX under its certificate are permitted for storage in the HI-STORE facility. Chapter 7 of the HI-STORM UMAX FSAR is therefore included here by reference. For a justification see Table 9.0.1. Further details on the canisters and the applicability of the containment evaluations from the HI-STORM UMAX FSAR to the HI-STORE facility are discussed below

Confinement of all radioactive materials in all HI-STORM vertical ventilated modules is provided by the canister's Enclosure Vessel which has no mechanical joints, flanges, gaskets and the like that may be subject to leakage. The confinement boundary as defined in Paragraph 2.3.3.4 in the HI-STORM UMAX FSAR[1.0.6] consists of the MPC shell, MPC baseplate, MPC lid, port cover plates, closure ring, and associated welds. The pressure boundary of the canister consists of radiographed weld seams and ultrasonically tested plate and forging stock. Only high ductility stainless steel alloy with excellent fracture strength properties at low service temperatures are used in the manufacture of the canisters eligible for storage at HI-STORE.

All normal, off-normal and accident conditions relevant to confinement integrity for which the canister is certified in the HI-STORM UMAX docket are equal to less severe at the HI-STORE facility. Therefore, there are no new conditions for the HI-STORE CIS facility that would require additional confinement analyses. With respect to the applicability of the containment evaluation from the HI-STORM UMAX note that the continued confinement integrity of a canister is influenced by the stress field that exists in its Enclosure vessel during its storage state and by the occurrence of any stress-inducing mechanical loading event. These are discussed below:

- The stresses that the canister will experience at the HI-STORE facility will be bounded by those for which it is certified in the HI-STORM UMAX docket because:
    - The Design Basis Heat load (see Table 4.1.1) for all canisters eligible for storage in HI-STORE is lower than that for the canisters certified in Docket # 72-1040 (see Table 2.1.8 in the HI-STORM UMAX FSAR[1.0.6]). It follows that the internal gas temperature in the former will be less than the latter. Therefore, it follows that the pressure in the canisters and hence any pressure-induced stresses will be lower in HI-STORE canisters than their certification-basis in the HI-STORM UMAX FSAR.
    - The canisters in the HI-STORM UMAX docket are certified for the entire range of ambient temperatures that exist in the lower 48 states in the United States. Therefore, the licensing-basis ambient temperature range applicable to the canister's general certification in the HI-STORM UMAX docket bounds the conditions at the HI-STORE site.
- As in the HI-STORM UMAX FSAR, all lifting and handling operations involving canisters at the HI-STORM facility are performed with single failure proof equipment. Hence there are no additional mechanical loading events that would affect the confinement function of the canisters

In summary, the storage conditions at the HI-STORE site are identical to, or more benign (less challenging) than the certification-basis conditions for the canisters in the generic HI-STORM UMAX docket (# 72-1040). Therefore, the safety conclusions reached with respect to the system confinement integrity in the HI-STORM UMAX FSAR [1.0.6] also apply to the canisters stored at HI-STORE.

Confinement safety of the canisters in this docket is therefore demonstrated by reference to confinement determination reached in the HI-STORM UMAX FSAR [1.0.6].

Receipt Inspection

The canister must meet the following criteria that pertain to its continued condition of no-credible-leakage upon arrival at the HI-STORE facility:

- The canister was not subject to any incident beyond the normal conditions which the package has been qualified to pursuant to 10CFR71.71.
- The canister passes the leak test and other receipt inspections set forth in this Chapter 10 of this FSAR at the HI-STORE receiving area.

A canister that meets the above conditions is deemed to continue to meet the no-credible-leakage criteria to which it has been certified in the HI-STORM UMAX docket (# 72-1040). Although the HI-STORM UMAX confinement boundary includes the MPC lid to shell weld, this weld is covered with a redundant closure ring. Therefore, the leak testing described tests performed only on that redundant closure ring of the confinement boundary. However, due to the restrictions on no transport incident and the fact that the storage conditions have been demonstrated to pose no challenge to the confinement boundary, confirmation that the closure ring is intact provides reasonable assurance that the inner lid-to-shell weld remains a fully qualified confinement boundary.

Long Term Storage and Aging Management

While a canister is still within its originally licensed period in accordance with the certificate it was originally approved to, no further confinement considerations are necessary, since the canister retains its no-credible-leakage status based on the original confinement evaluation and the receipt inspection discussed above. However, it is expected that canisters will be stored at the HI-STORE CIS facility beyond this initial period. Any canister where the storage life exceeds 20 years will need to comply with the aging management requirements outlined in Chapter 18 of this SAR. Compliance with these requirements will ensure that any conditions that could be detrimental to the confinement function of the canister and identified, and, if necessary, mitigated.

9.2.2 Operational Activities

With respect to the confinement of the radioactive material, the operational activities can be grouped into the following three steps/conditions

- MPC is still inside the intact containment boundary of the transportation cask that its delivered in
- Receipt inspection activities on each canister, and, if the inspection criteria are met, opening of the transport cask containment boundary.

- Operational activities to place the accepted canister into storage

These steps are discussed in further detail below.

While the canister is still inside the transportation cask, the canister is still considered the confinement boundary for the material. However, the receipt inspections need to be passed to confirm that the confinement boundary has not degraded during the transport phase. Until this is concluded, the containment boundary of the transportation cask serves as additional measure to assure the confinement of the material in the canisters.

During the receipt inspection and opening of each transportation cask containing, the activities that are performed, and the possibility (or lack thereof) of any release of radioactive material is as follows:

- One of the vent/drain ports of the transportation cask is opened to allow access to the small free volume between the canister and the cask. For this activity the port is covered by appropriate means, so that in the unlikely event that the volume would contain any radioactive material, such would not be released into the local work area (transfer building), but appropriately collected.
- A gas sample is taken from this volume and tested for the presence of fission products, namely Krypton-85.
    - If any fission products are detected, the port will be resealed, and the cask will be classified as “not acceptable”. All gas samples containing fission products will be collected and tracked in accordance with Subsection 10.3.3 For further processing of casks that are not acceptable see Subsection 10.3.3.
    - Full details of the receipt inspection test including instrumentation and acceptance criteria are outlined in Chapter 10.
    - If the acceptance criteria outlined in Chapter 10 are not met the transportation cask is not opened and is not accepted at the HI-STORE facility
- If no fission products are detected, the free volume is evacuated, flushed with nitrogen and then tested for traces of helium that could be the indication of any leakage of the helium-filled canister in the cask (see Paragraph 10.3.3.2 for details). The gas extracted from the volume during the evacuation and helium testing is also collected and tested for any fission products before being released.
    - If the tightness of the canister cannot be ascertained, or if fission products are detected, the port will be resealed, and the cask will be classified as “not acceptable”. All gas samples containing fission products will be collected and tracked in accordance with Subsection 10.3.3 For further processing of casks that are not acceptable see Subsection 10.3.3

From this step, even in the unlikely event that fission products were detected, these would only be small amounts from the small free space between the cask and the canisters, and the process is designed to ensure that those are collected. A release into the building or the environment is therefore not considered credible.

As discussed in Subsection 9.2.1 above, all radioactive material is stored and handled in seal welded canisters, and as presented in Chapter 1, all handling operations are performed either with single-failure-proof cranes, or using suitable impact limiters. Hence once the canisters have passed the receipt inspection, also discussed in Subsection 9.2.1, there is no credible normal or accident situation that could challenge the integrity of the canister confinement integrity and result in a release of any radioactivity.

Overall, from all operational activities, no credible events are identified that would result in a release of any radioactive materials into the work areas or the environment.

9.3 POOL AND WASTE MANAGEMENT FACILITIES

9.3.1 Pool Facilities

HI-STORE CIS contains no pool or any other water-based storage or handling facility.

9.3.2 Waste Management Facilities

No specific facilities are needed for the management of radioactive waste at the HI-STORE facility, since no, or only insignificant amounts of, radioactive waste is generated in the facility, as discussed in the following:

- All fuel is handled in seal-welded canisters with no credible leakage, and all activities and operations with the canisters are designed to maintain this condition
- The transportation casks received with the canisters at the site would almost certainly have been loaded with canisters in a dry facility, hence contamination of the casks are not expected.
    - Nevertheless, transport casks are checked for contamination and during processing and extraction of the canisters, and in the unlikely event that any contamination would be detected, this would be removed with standard methods, and any materials related to this operation would be separately collected, and transported off-site for appropriate disposal.
- Small gas samples are taken during the receipt inspection of the canisters. The samples will be kept in closed containers until the measurements have confirmed the absence of any fission gases. In the unlikely event that fission gases would be detected, the gas samples will be transported off-site for appropriate disposal.
- There is no other radioactive material that is being handled openly throughout the facility.

9.4 CONFINEMENT MONITORING

9.4.1 Storage Confinement Systems

9.4.1.1 Closure Seal Monitoring System

All radioactive material is stored in seal-welded canisters, and consistent with its operation an approval under the initial certificate that those canisters are loaded under, no monitoring of the closure seals are required for the initial licensing period. The continuous confinement of the canisters beyond their initial licensing period is addressed in the Aging Management Program in Chapter 18, which uses a Canister Aging Management Program to inspect and monitor, as described in Section 18.5.

9.4.1.2 Continuous Monitoring System

All material at the ISFSI is stored in seal welded canisters, qualified to have no credible leakage per ISG-18. Hence no monitoring of airborne radiation is needed in and around the storage area.

For the canister transfer inside the CTB, there is also no expectation that any release of radioactivity would occur, so no monitoring of airborne radiation is required. Nevertheless, radiation detectors able to detect airborne radiation may be used in the CTB as additional measure.

9.4.2 Effluents

The HI-STORE CIS facility does not generate any radioactive effluent, hence no effluent monitoring system is required.

Additionally, in the absence of any effluent, there is no potential for transport of radioactive materials to the environment through any aquifer under the site.

9.5 PROTECTION OF STORED MATERIALS FROM DEGRADATION

9.5.1 Confinement Casks or Systems

All radioactive material is stored in seal-welded canisters, in an inert atmosphere, and consistent with its operation an approval under the initial certificate that those canisters are loaded under, no degradation of its content is to be expected. Any potential degradation beyond their initial licensing period is addressed in the Aging Management Program in Chapter 18.

9.5.2 Pool and Waste Management Systems

HI-STORE CIS contains no pool or any other water-based storage or handling facility.

9.6 SUMMARY

In summary,

- This chapter describes confinement structures, systems and components, and their evaluation and effectiveness.
- The confinement of all radioactive material is provided by seal-welded canisters, loaded and closed under their original certificates.
- The operation of the HI-STORE CIS facility generates no radioactive effluents. There is no potential for transport of radioactive materials to the environment through any aquifer.
- No release of any radioactive material is expected from the facility and its operation, hence no additional dose from released material is considered in the evaluations in Chapter 11.
- No radiation monitoring system is required.
- The stored material is protected against degradation due to its storage in an inert atmosphere.
- The confinement systems will reasonably maintain confinement under normal, off-normal and accident conditions.

CHAPTER 10: CONDUCT OF OPERATIONS EVALUATION*

10.0 INTRODUCTION

This chapter discusses the organization and procedures established by Holtec International (Holtec) for the operation and decommissioning of an Independent Spent Fuel Storage Installation (ISFSI) at the HI-STORE CIS site. Included are descriptions of organizational structure, testing, training programs, normal operations, emergency planning, and security safeguards.

* All references are placed within square brackets in this report and are compiled in Chapter 19 of this report.

10.1 ORGANIZATIONAL STRUCTURE

This section describes the organization that is responsible for long term storage of spent nuclear fuel at the HI-STORE CIS facility. Lines of authority, responsibility, and communication shall be defined and established throughout highest management levels, intermediate levels, and all operating organization positions. These relationships shall be documented and updated, as appropriate, in organizational charts, functional descriptions of departmental responsibilities and relationships, and job descriptions for key personnel positions, or in equivalent forms of documentation. This chapter is included in this SAR to fulfill the requirements in 10CFR72.24(h) and 72.28(c).

10.1.1 Corporate and On-Site Organization

The Holtec Corporate Executive responsible for the HI-STORE CIS facility (hereafter referred to as the Corporate Executive) has overall responsibility for safe operation of the site.

The Holtec HI-STORE CIS Site Manager (hereafter referred to as the Site Manager) reports to the Corporate Executive. The Site Manager is responsible for safe operation of the site, maintaining personnel trained and qualified in accordance with the HI-STORE Site Specialist Training Program [10.1.1], day-to-day implementation of the Holtec Quality Assurance Manual [12.0.1], and operation of all HI-STORE CIS facility structures, systems and components that are important to safety. This position provides direction for the safe operation, maintenance, radiation protection, training and qualification, and security of the site and personnel.

To assure continuity of operation and organizational responsiveness to off-normal situations, a normal order of succession and delegation of authority will be established. The Site Manager will designate, in writing, personnel who are qualified to act in his/her absence.

The organization charts shown in Figures 10.4.1 and 10.4.2 represent the planned organizational relationships throughout the life of the facility.

10.1.2 Support Staff (ISFSI Specialists)

Support staff will be available by either corporate staff, on-site staff or contract personnel to provide support and expertise to the Site Manager in the following areas:

- Quality Assurance: Responsible for the implementation of the requirements of the Holtec Quality Assurance Manual [12.0.1], including the maintenance of appropriate records. The staff will ensure that the appropriate steps are added to site procedures for operation and maintenance to ensure that all activities are performed in accordance with the site license;
- Engineering: The site nuclear compliance engineer is responsible for the oversight of the facility modifications. Engineering support staff, either on or off-site, is provided to support the site nuclear engineer.
- Radiation Protection: Responsible for the planning and direction of the facility radiation protection and ALARA programs and procedures, as well as the operation of the health physics laboratory.

- Maintenance: Responsible for mechanical, electrical and instrument maintenance for buildings, fencing, mechanical equipment and all other site equipment. Also provide operations coverage for those periods of time in which loaded canisters are handled and routine site maintenance and surveillance when canisters are not being handled. May also provide maintenance as needed for operation of railroad locomotives from the railroad mainline. Shall be responsible for ensuring that appropriate records are maintained in accordance with Subsection 10.3.2 of this Chapter and the site licensing requirements.
- Security: Responsible to maintain the security of special nuclear materials that are within the physical confines of the site, including providing initial responses to security intrusions as described in the Site Security Plan [3.1.1].
- Records: Responsible for the maintenance of records in accordance with Subsection 10.3.2 of this Chapter and the site licensing requirements.
- Site Administrative: Responsible for site administrative functions, including the maintenance of records in accordance with Subsection 10.3.2 of this Chapter and the site licensing requirements, as well as site business records and contracts. Also responsible for ensuring appropriate hiring standards are followed in the selection of staff members.

The Site Manager and Specialists are qualified as described in Table 10.1.1.

Table 10.1.1: Staffing Qualifications and Operation Organization	
Site Manager	The Site Manager, at the time of appointment to the position, shall have a minimum of five years of nuclear power plant or comparable experience, with relevant experience in the management of nuclear facility operations. The ISFSI Manager will be trained and certified in accordance with the HI-STORE CISF Specialist Training Program [10.1.1], and shall meet or exceed the minimum qualifications of ANSI N18.1-1971 [10.1.2] for a comparable position. In addition to the above specified requirements, the Site Manager will also be required to be qualified as an Independent Safety Reviewer (ISR) as described below.
Specialists	The ISFSI Specialists, at the time of appointment to the position, shall have a High School diploma or successfully completed the General Education Development (GED) test. Operation of equipment and controls that are identified as important to safety shall be limited to personnel who are trained and certified in accordance with the Certified ISFSI Specialist Training Program[10.1.1] or personnel who are under the direct visual supervision of a person who is trained and certified in accordance with the Certified ISFSI Specialist Training Program. Specialists will be trained and certified in accordance with the Holtec Certified ISFSI Specialist Training Program and the Holtec HI-STORE Site Security Plan training and qualification requirements, and shall meet or exceed the minimum qualifications of ANSI N18.1-1971 for a comparable position. At the time of completion of training and appointment to the position, the Certified ISFSI Specialist shall have a minimum of two years of nuclear facility experience.
Independent Safety Reviewers	The Independent Safety Reviewer (ISR) shall be an individual not having direct involvement in the performance of the activities under review, but who may be from the same functionally cognizant organization as the individuals performing the original work. The ISR shall have five years of professional level experience and either A Bachelor's Degree in Engineering or the Physical Sciences or equivalent in accordance with ANSI/ANS-3.1-1981. The Holtec Corporate Executive shall designate the qualified ISRs in writing.

10.2 PREOPERATIONAL TESTING AND STARTUP OPERATIONS

Prior to operation of the HI-STORE CIS facility, a preoperational test, a startup test, and other tests and inspections will be performed to verify that the storage system satisfied the design criteria described in this SAR. Tests and inspections will also be completed prior to initial loading of the ISFSI to ensure that the storage system handling equipment satisfied the design criteria stated in Chapter 4. The results of such tests and inspections will be maintained in accordance with regulatory recordkeeping requirements and will be available at the ISFSI site.

Several of the tests and inspections of equipment involved with loading the storage system will be performed (e.g., load testing the CTB crane). These tests and inspections are not pre-operational or startup tests of the storage system, but are discussed below due to their importance to the safe loading and operation of the storage system.

10.2.1 Administrative Procedures for Conducting the Test Program

The development, approval, and performance of pre-operational and startup test procedures will will meet the requirements of the Holtec Quality Assurance Manual [12.0.1]. The procedures that govern testing will specify how the test results will be evaluated, documented, and approved. Test results must be shown to be within the acceptance criteria specified in test procedures.

The procedure that governs testing will specify the process for identifying needed system modifications that are recognized during testing. Also, the procedure will require evaluation of whether retesting is required after a needed modification has been implemented.

10.2.2 Preoperational Testing Plan

The test program is divided into two parts: preoperational testing and startup testing. Other tests and inspections which are not pre-operational or startup tests, are also briefly discussed in this section because of their importance to the proper operation and integrity of the storage system and handling equipment. The preoperational, startup, and other tests are described in this section and a summary is provided in Table 10.2.1.

The VVM storage system uses passive cooling, and therefore has no “operating” systems, other than the optional air outlet temperature monitoring system, to test prior to the loading of spent nuclear fuel (i.e., pre-operational testing). However, the other tests and inspections described below are performed to ensure the storage system will function in accordance with the design.

Startup testing is performed for each VVM after loading with a spent nuclear fuel canister. Startup testing confirms that the actual dose rates are less than the maximum expected dose rates determined in Chapter 11 of this SAR, such that estimated personnel exposures are bounded by the safety analyses.

In addition to the tests and inspections described in this section, all safety significant equipment will be inspected prior to use to ensure that these components are fabricated in accordance with the design drawings. Materials used specifically for shielding will be tested for shielding effectiveness. Steel properties will be verified by review of appropriate test reports. Structural and shielding adequacy of concrete will be determined by testing during construction.

10.2.2.1 Pre-Operational Testing of Equipment

The operations associated with the physical transfer of an MPC from receipt to installation in the VVM will be completed and verified using a full size, full weight dummy MPC. In addition to evaluating component function, pre-operational tests will also evaluate adequacy of procedural controls, communication, personnel safety and all other processes and controls that affect operations. Relevant operations include the following:

1. Receipt of the loaded HI-STAR transport cask
2. Removal of the loaded HI-STAR from the shipping railcar;
3. Canister integrity testing
4. Preparation of the loaded HI-STAR for unloading, including upending and placement in the CTF;
5. Removal of the HI-STAR closure lid;
6. Installation of the CTF alignment plate;
7. Installation of rigging and lifting apparatus on the MPC;
8. Installation and alignment of the HI-TRAC transfer cask;
9. Loading of the dummy MPC into the HI-TRAC, and associated tasks for preparation for transfer to the VVM;
10. Transfer of the dummy MPC into the VVM;
11. Installation of the VVM closure lid and other associated components.

10.2.2.2 Startup Testing

A startup testing will consist of the measurement of external radiation dose rates for each VVM after it is loaded with spent nuclear fuel to confirm that the actual dose rates are less than the maximum expected dose rates defined in Chapter 11 of this SAR. This will confirm that the estimates of personnel exposures are bounded by the safety analysis.

10.2.2.3 Other Testing

Load tests: The following components are loaded test prior to pre-operational testing as part of fabrication acceptance requirements:

1. CTB crane
2. VCT lift brackets and structure
3. HI-STAR lifting trunnions
4. Lift yoke for HI-STAR 190
5. Tilt frame
6. Transport cask horizontal lift beam

7. HI-TRAC lifting trunnions
8. HI-TRAC lower shield gates
9. Lift yoke for HI-TRAC
10. MPC lift attachment
11. MPC lifting device extension
12. HI-TRAC CS lift links

Functional testing of HI-TRAC: The efficient and dependable operation of the HI-TRAC cask is paramount to achieving ALARA operations while transferring the MPC from its transport cask to its VVM storage location. Before pre-operational testing, post-fabrication operational testing of the HI-TRAC shield gates will be performed to ensure the gates repeatedly function as designed, both prior to and after repeated application of a load representative of the worst-case MPC weight that will be transported by the HI-TRAC.

Leak test equipment validation: Equipment used for sampling the HI-STAR transport cask annulus will be calibrated using a suitable reference concentration of Krypton-85 gas. Equipment will be functionally tested to both ensure repeatable operation and evaluate, and improve, the efficiency of the sampling operations.

RTD monitoring system tests: Acceptance testing of the optional RTD monitoring system will be performed prior to pre-operational tests to ensure proper performance of the system. Prior to the installation of an MPC into each VVM, operational tests of each RTD monitoring component relevant to its VVM will be checked against an appropriate standard temperature source.

10.2.3 Evaluation of Tests

The tests will be deemed successful if the acceptance criteria provided in the test procedures are achieved safely and without damage to any of the components or associated equipment.

10.2.4 Corrective Actions

Modifications to equipment or components will be performed, should they become necessary, to ensure that the acceptance criteria are achieved. The modified equipment or components will be retested to confirm that the modification is sufficient. If required, pre-operational test procedure changes will be incorporated into the appropriate operating procedures.

Table 10.2.1
Pre-Operational, Startup, and Other Tests

Component	Type	Test Purpose / Objective(s)
Railcar transfer into CTB	Pre-Op	Operational clearances are confirmed and sequence/efficiency of operational steps is evaluated.
CTB crane test	Other	Receipt inspection and testing per requirements of ASME NOG-01[3.0.1]
Load test of HI-TRAC horizontal lift beam	Other	Load test in accordance with requirements of ANSI N14.6 [1.2.4]. Verify fitup and clearance of all associated lift equipment.
Transfer of HI-STAR from railcar to tilting frame	Pre-Op	Check clearances and interferences of components. Evaluate sequence/efficiency of operational steps. Confirm alignment of tilting frame
Removal of HI-STAR impact limiters	Pre-Op	Evaluate efficiency of rigging operations. Check clearances and interferences
HI-STAR cask cavity sampling	Pre-Op	Evaluate functionality of equipment. Optimize sampling process. Verify calibration of equipment.
HI-STAR cask cavity evacuation and backfill	Pre-Op	Optimize procedure. Evaluate time and steps required for backfill.
MPC leak test in HI-STAR cavity	Pre-Op	Evaluate functionality of equipment. Optimize sampling process. Verify calibration of equipment.
CTF preparations	Pre-Op	Check fitup of alignment fixture on CTF
Load test of HI-STAR lift yoke	Other	Load test in accordance with requirements of ANSI 14.6 [1.2.4]. Verify fitup and clearance of all associated lift equipment.
Transfer of HI-STAR to CTF	Pre-Op	Check clearances and operational steps. Evaluate efficiency of rigging operations
HI-STAR closure lid removal in CTF	Pre-Op	Evaluate ergonomics of rigging/removal.
Load test of MPC lift attachment	Other	Load test to demonstrate ability to safely lift a fully loaded MPC in accordance with requirements of ANSI 14.6 [1.2.4]. Verify fitup and clearance of all associated lift equipment.

Table 10.2.1
Pre-Operational, Startup, and Other Tests

Component	Type	Test Purpose / Objective(s)
Installation of MPC lift attachment	Pre-Op	Check fit up with MPC lid and CTF.
Acceptance test of HI-TRAC shield gates	Other	Demonstrate proper operation of gates after supporting the weight equivalent to 150% of design load.
Installation of CTF Adapter Plate	Pre-Op	Check fit up with transport cask and CTF.
Installation of HI-TRAC on CTF	Pre-Op	Check fit up with transport cask and CTF adapter plate.
Transfer Cask lifting trunnions	Other	300% load test to demonstrate ability to safely lift a loaded Transfer Cask.
Load test of HI-TRAC CS Lift Yoke	Other	Check fit up with Transfer Cask and crane. 150% load test to demonstrate ability to safely lift a loaded Transfer Cask.
Transfer of MPC into HI-TRAC	Pre-Op	Check for interferences. Evaluate operation and seating of MPC on HI-TRAC shield gates.
Transfer of HI-TRAC (with MPC) to ISFSI site	Pre-Op	Evaluate ability to maneuver haul path, review operational steps for efficiency,
Mating of HI-TRAC with HI-STORM UMAX VVM	Pre-Op	Check fit up and alignment. Evaluated procedure for installation of tie-down studs.
Transfer of MPC into HI-STORM UMAX VVM	Pre-Op	Check for interferences. Evaluate operation of VCT and HI-TRAC.
VVM air outlet temperature monitoring system components	Pre-op	Demonstrate proper operation of the temperature monitoring system components prior to placing a loaded MPC into the VVM
Installation of CEC closure lid	Other	Check fit up and lifting/handling operations.

10.3 NORMAL OPERATION

This section describes the administrative controls and conduct of operations associated with activities considered important to safety. Also described in this section is the management system for maintaining records related to the operation of the ISFSI.

10.3.1 Procedures

Activities affecting quality are accomplished in accordance with approved and documented instructions, procedures, or drawings. Written procedures will be used for site operations, maintenance, and testing activities that are quality-related as defined in the Holtec Quality Assurance Manual [12.0.1]. Procedures will be used to implement the Fire Protection Program and training and certification of personnel. The review and approval process for procedures, and changes thereto, will be procedurally controlled. The Site Manager or his designee will approve procedures and changes prior to implementation. Temporary changes to procedures are allowed if the intent of the existing procedure is not altered and the change is approved by the Site Manager or his/her designee.

Site procedures will require that any changes to facilities, equipment or procedures will be reviewed for safety impact to ensure that the proposed change does not require prior NRC approval pursuant to 10CFR72.48.

10.3.2 Records

Administrative procedures will be established and maintained to ensure quality assurance records are identifiable and retrievable. In addition to quality assurance records, the following records will also be maintained in accordance with 10CFR72.174:

1. Operating records, including maintenance and modifications.
2. Records of off-normal occurrences.
3. Events associated with radioactive releases.
4. Environmental survey records.
5. Personnel Training and Qualification Records.
6. Records of ISFSI design changes made pursuant to 10CFR72.48.
7. Records showing the receipt, inventory (including location), disposal, acquisition, and transfer of spent fuel and related nuclear material as required by 10CFR72.72(a).
8. Records of material control and inventory procedures to account for material in storage as required by 10CFR72.72.

Records of site procedure changes, and tests and experiments, conducted pursuant to 10CFR72.48 will be maintained in accordance with 10CFR72.48. Storage of the above records will be in accordance with the requirements of the Holtec Quality Assurance Manual [12.0.1].

Security records, including security training and qualification records, will be maintained in accordance with the HI-STORE Site Security Plan [3.1.1].

10.3.3 Conduct of Operations

The information presented in this section will be used to develop detailed operating procedures for the receipt of MPC transport casks and the safe transfer of the MPCs to their storage location at the HI-STORE site. In preparing the procedures, the user must consult the conditions of the Technical Specifications, equipment-specific operating instructions, and the HI-STORE site's working procedures as well as the information in this chapter to ensure that the short-term operations shall be carried out with utmost safety and ALARA.

The following generic criteria shall be used to determine whether the HI-STORE site operating procedures developed pursuant to the guidance in this chapter are acceptable for use:

- All heavy load handling instructions are in keeping with the guidance in industry standards and Holtec-provided instructions.
- The procedures are in conformance with this SAR and its Technical Specifications.
- The procedures are in conformance with the HI-STORM UMAX FSAR [1.0.6] and HI-STORM FW System FSAR [1.3.7] where applicable.
- The operational steps are ALARA.
- The procedures contain provisions for documenting successful execution of all safety significant steps for archival reference.
- Procedures contain provisions for classroom and hands-on training and for a Holtec-approved personnel qualification process to ensure that all operations personnel are adequately trained.
- The procedures are sufficiently detailed and articulated to enable craft labor to execute them in literal compliance with their content.

Independent safety reviews will be performed and documented by qualified Independent Safety Reviewers (ISR) prior the performance of any operations. The independent safety reviews shall confirm that changes to the facility, changes to operating procedures, and the performance of tests and experiments not described in the Safety Analysis Report are safe and do not require prior NRC approval pursuant to 10CFR72.48.

10.3.3.1 Receipt and Inspection of Transportation Cask and Canister

The following operational steps are used to receive and inspect the transportation cask in the HI-STORE CTB. The steps also include

1. The HI-STAR packaging is visually receipt inspected to verify that there are no outward visual indications of impaired physical conditions except for superficial marks and dents. Any issues are identified to site management. Any road dirt is washed off and any foreign material is removed.
2. The HI-STAR transportation package is moved into the CTB building security trap, where it is inspected by HI-STORE site security personnel to ensure no unauthorized devices enter the CTB building.

3. The HI-STAR transportation package is moved into the CTB.
4. The personnel barrier, if used, is removed and the security seal installed on the top impact limiter is inspected to verify there was no tampering and that it matches the corresponding shipping documents.
5. The HI-STAR shipment personnel barrier and tie-downs are removed. The radial spacers are removed from the top and bottom of the cask.
6. Radiological surveys are performed in accordance with 49CFR173.443 [10.3.1] and 10CFR20.1906 [7.4.1]. Any issues are identified to site management. If necessary, the overpack is decontaminated as directed by site radiation protection. Appropriate notifications are made as detailed in the surveillance requirements.
7. The HI-STAR is rigged and transferred to the tilt frame using the CTB building crane.

ALARA Warning:
Dose rates around the bottom end of the HI-STAR cask may be higher that other locations around the cask. After the impact limiter is removed, the cask should be upended promptly. Personnel should remain clear of the bottom of the unshielded cask and exercise other appropriate ALARA controls.

8. The HI-STAR impact limiters are rigged and removed using the CTB crane and a second visual inspection to verify that there are no outward visual indications of impaired physical condition is performed.
9. The neutron shield relief devices are inspected to confirm that they are installed, intact, and not covered by tape or any other covering.
10. As a safety precaution, the HI-STAR closure lid access port cover is removed and sampling equipment is attached to test for the presence of Krypton-85. The cask cavity gas sample is handled in accordance with Radiation Protection directions by qualified personnel. Testing is performed per pre-approved procedure, using appropriately calibrated equipment, to confirm that the sample meets the acceptance criteria of Table 10.3.3. In the unlikely event that the Krypton-85 concentration exceeds the acceptance criteria, the canister transfer operations are terminated and site management is informed for disposition.

Operational Limit:
Prior to performing evacuation, flushing, and leak testing of the MPC within the HI-STAR cask, an evaluation based on the specific transportation cask conditions, canister conditions (including heat load), and leak test conditions shall be performed to establish a canister-specific time limit for all operations performed without helium in the cask annulus. A previously performed bounding evaluation may also be utilized. Process steps shall be stopped before reaching the thermal time limit, and the helium backfill shall be re-established per the requirements of Table 10.3.4 before continuing.

11. The sampling equipment is removed, and the HI-STAR annulus space is evacuated and flushed with nitrogen using the sampling equipment connector. This process may be repeated several times to flush the residual helium from the annulus space. Refer to Table 10.3.4 for process pressure limits.
12. The mass spectrometer leak test apparatus is attached to the sampling equipment connector and a leak test of the MPC is performed. Leakage rate testing is performed per procedures written and approved in accordance with the requirements of ANSI N14.5-2014 [10.3.3]. All testing is performed by qualified personnel in accordance with the Holtec QA program. The written and approved test procedures shall clearly define the test equipment arrangement. The applicable recommended guidelines of SNT-TC-1A [10.3.2] shall be considered as minimum requirements.
13. The CTF is inspected and prepared for receipt of the HI-STAR transportation cask.
14. The HI-STAR is upended, removed from the tilting frame and transferred to the CTF using a lift yoke attached to the cask trunnions and the CTB crane.

10.3.3.2 Transfer of Canister from Transportation Cask to HI-TRAC

1. Using the CTB crane, the HI-TRAC alignment plate is installed on the CTF over the HI-TRAC cask.
2. The HI-STAR closure lid bolts are removed and the closure lid is removed using the CTB crane.

ALARA Warning:
Personnel should remain clear of the open end of the unshielded cask and exercise other appropriate ALARA controls. Dose rates around open end of the HI-STAR cask may be higher that other locations around the cask. Temporary shielding may be installed to reduce worker dose ALARA.

3. A cask seal surface protector is installed on the closure lid sealing surface to protect it

from damage.

4. The MPC lifting attachment is connected to the threaded holes on the MPC closure lid. The lifting attachment bolts are tightened hand-tight.
5. Using the CTB crane, the HI-TRAC is placed on the HI-TRAC alignment plate with the shield gates open. The CTF studs are secured to the HI-TRAC and the nuts are tightened wrench- tight.
6. The MPC lifting extension is attached to the CTB crane, lowered through the HI-TRAC body, and engaged with the MPC lift attachment.
7. Using the CTB crane, the MPC is lifted into the HI-TRAC.
8. The HI-TRAC shield gates are closed, and the MPC is lowered to rest on the gates.
9. The MPC lifting extension is disconnected and removed using the CTB crane.
10. The HI-TRAC lift yoke is connected to CTB crane and the HI-TRAC lift trunnions.
11. The CTF stud nuts are removed.
12. The HI-TRAC is lifted using the CTB crane and placed in a location of the CTB floor that is accessible to the VCT.

10.3.3.4 Preparation of VVM for Receipt of MPC

1. Prior to receipt of the MPC, install or confirm installation of the appropriate divider shell in the appropriate VVM for the planned MPC. Installation and verification shall be procedurally controlled and reviewed to ensure correct VVM component designs are specified so that licensing requirements are met.
2. If not already removed, remove the closure lid using a crane or other equivalent lifting device.
3. Install the HI-TRAC restraint studs in the VVM threaded anchors.

Operations Note:

In addition to securing the HI-TRAC to the VVM, the restraint studs also provide alignment while positioning the HI-TRAC on the VVM.

10.3.3.5 Placement of Canisters in the CEC

1. Position the VCT over the loaded HI-TRAC.
13. Attach the HI-TRAC CS lift links to the HI-TRAC and lift the HI-TRAC several inches off the ground, as needed for transport to the ISFSI.

Operations Note:

If required for transport of the loaded HI-TRAC to the designated VVM, the outlet air vent extensions for previously loaded or unloaded VVMs may be temporarily removed (if installed) to minimize the required lift height for the HI-TRAC. For previously loaded VVMs, the outlet air vent extensions shall be expeditiously re-installed to restore the VVMs to its normal condition of storage.

2. Using the VCT, transport the loaded HI-TRAC to the ISFSI and place the loaded HI-TRAC on the VVM, using the HI-TRAC restraint studs (previously installed) to ensure proper alignment.

14. Disconnect the HI-TRAC CS lift links from the HI-TRAC and rig the MPC lifting attachment to the VCT using the MPC lifting extension.

3. Raise the MPC slightly to remove the weight of the MPC from the HI-TRAC Shield Gate.

ALARA Warning:

Temporary shielding may be used to reduce personnel dose during MPC transfer operations. If used, temporary shielding must not restrict air flow into CEC inlet vent openings. If ALARA considerations dictate that temporary shielding not be used, personnel must remain clear of the immediate area around the HI-TRAC Shield Gates during MPC downloading.

4. Open the HI-TRAC Shield Gate. At the user's discretion, install temporary shielding to cover the potential streaming paths around the HI-TRAC Shield Gates.

5. Lower the MPC into the VVM.

6. Verify that the MPC is fully seated in the VVM.

Caution:

Operations steps that occur with the MPC in the VVM with the HI-TRAC Shield Gate closed must be performed in an expeditious manner to avoid excessive heating of the MPC and fuel. The Mating Device must be removed or the drawer opened to establish air cooling within the time limits described in Section 4.5. In the event of equipment malfunction that results in the blockage of air flow, corrective actions must occur within the time limits of the 100% blocked duct accident condition.

7. Disconnect the MPC lifting attachment from the MPC and remove using the lifting extension and the VCT.

8. Remove any temporary shielding and close the HI-TRAC Shield Gates.

ALARA Warning:

Personnel should remain clear (to the maximum extent practicable) of the VVM annulus when HI-TRAC is being removed to comply with ALARA requirements.

9. Remove the HI-TRAC transfer cask from the top of the VVM.
10. Install plugs in the empty MPC bolt holes.

Guidance:

The VVM closure lid shall be preferably kept less than 2 feet above the top surface of the VVM while over the MPC. This lift limit action is purely a defense-in-depth measure because the Closure Lid cannot fall and impact the MPC because of geometric constraints.

11. Install the VVM closure lid. Check that the rigging (in its specific configuration) is rated to lift the load (rated to lift two times the load per NUREG 0612).
12. Remove the VVM closure lid rigging equipment and re-install the outlet vent cover (if previously removed).
13. Install the VVM temperature monitoring elements (if used).
14. Ensure records showing the receipt, inventory (including location), disposal, acquisition, and transfer of the canister, as required by 10CFR72.72(a), are complete.

10.3.3.6 Removal of Canisters from the CEC

If necessary, canisters are recovered from the HI-STORM UMAX VVM and returned to the transport cask in accordance with the steps described in this Section, except that the order is basically reversed.

10.3.4 Maintenance Program for the HI-STORM UMAX VVM & HI-TRAC CS

An ongoing maintenance program shall be defined and incorporated into the HI-STORM UMAX system Operations and Maintenance Manual for the HI-STORE CIS facility. This document shall delineate the detailed inspections, testing, and parts replacement necessary to ensure continued structural, thermal performance, and radiological safety in accordance with 10CFR72 regulations, the conditions in the Technical Specifications, and the design requirements and criteria contained in this SAR.

The HI-STORM UMAX system is totally passive by design and requires minimal preventive maintenance to ensure that it will render its intended design functions satisfactorily. Periodic surveillance (via temperature monitoring or visual or camera-aided inspection of air passages) is required to ensure that the air passage in the VVM is not blocked. Preventive or remedial painting of the exposed steel surfaces as part of the user's preventive maintenance program is recommended to mitigate corrosion.

In-service inspection for long-term interior and below-grade degradation shall be performed by

visual inspection of accessible areas of the HI-STORM UMAX VVM. The frequency of this visual in-service inspection should be in performed in accordance with Table 10.3.1.

Additional in-service inspection activities will include more thorough inspections for foreign material accumulation, corrosion (CEC wall thinning) and insulation degradation. A VVM with a loaded MPC may be inspected using remote devices such as a boroscope. The oldest VVM or VVM considered to be most vulnerable to corrosion degradation shall be selected for inspection.

Among the QA commitments are performance of maintenance by trained personnel by written procedures and written documentation of the maintenance work performed and of the results obtained. Table 10.3.2 provides a listing of the minimum maintenance activities on the HI-STORM UMAX VVM.

In summary, the HI-STORM UMAX System is totally passive by design: There are no active components or monitoring systems required to assure the performance of its safety functions. As a result, only minimal maintenance will be required over its lifetime, and this maintenance would primarily result from the effects of weather. Typical of such maintenance would be the reapplication of corrosion inhibiting materials on accessible external surfaces. Visual inspection of the vent screens is required to ensure the air flow passages are free from obstruction

Maintenance activities shall be performed under Holtec's NRC-approved quality assurance program. Maintenance activities shall be administratively controlled and the results documented.

10.3.4.1 Structural Capacity Verification

Prior to each MPC loading, a visual examination in accordance with a written procedure shall be required of the Closure Lid lift lugs and the HI-TRAC trunnions, bottom lid bolts, and bolt holes. The examination shall inspect for indications of overstress such as cracks, deformation, wear marks, corrosion, etc. Repairs in accordance with written and approved procedures shall be required if an unacceptable condition is identified.

10.3.4.2 Shielding Capacity

The gamma and neutron shielding materials in HI-TRAC CS are not subject to measurable degradation over time or as a result of usage. The radiation shielding capacity of the HI-STORM UMAX System is expected to remain undiminished over time. Therefore, unless the VVM is subjected to an extreme environmental event that imparts stresses or temperatures beyond-the-design-basis limits for the system (i.e., prolonged fire or impact from a beyond-the-design basis large energetic projectile) with the plausible potential to degrade the shielding effectiveness of the VVM, no shielding effectiveness tests beyond that required by the HI-STORE's Radiation Protection Program are required over the life of the AFR facility.

Radiation monitoring of the ISFSI in accordance with 10CFR72.104(c) will provide ongoing evidence and confirmation of shielding integrity and performance. If increased radiation doses are indicated by the facility monitoring program, additional surveys of the ISFSI shall be performed to determine the cause of the increased dose rates.

10.3.4.3 Thermal Capacity

In order to assure that the HI-STORM UMAX System continues to provide effective thermal performance during storage operations, surveillance of the air vents (or alternatively, by temperature monitoring) shall be performed in accordance with written procedures.

10.3.5 Maintenance Program for the Canister

The canister is an all-welded stainless steel pressure vessel that does not require an in-service maintenance unless a disruptive occurrence such as deposition of flood-borne foreign materials on the canister's surface occurs. Because submergence from flood has been rules out as a credible occurrence at the HI-STORE ISFSI, no routine in-service maintenance activity on the stored canister is expected. The Aging Management Program described in Chapter 18, however, will require monitoring and inspection activities, and possibly remedial actions, if so determined.

Table 10.3.1
HI-STORM UMAX System Maintenance Program Schedule

Task	Frequency
VVM cavity visual inspection	Prior to MPC loading
Divider shell visual inspection	Prior to MPC loading
Closure Lid visual inspection	Prior to MPC loading
VVM external surface (accessible) visual examination	Annually, during storage operation
VVM inlet and outlet vent screen visual inspection for damage, holes, etc.	Monthly
VVM inlet and outlet vent inspection for blockage	Daily unless monitoring is performed using temperature monitoring equipment
HI-TRAC cavity visual inspection	Prior to each handling campaign
HI-TRAC TAL visual inspection	Prior to each handling campaign
HI-TRAC bottom lid bolts and bolt holes	Prior to each handling campaign
VVM visual inspection of identification markings	Annually
VVM inlet plenum inspection for accumulation of foreign materials.	Every five years or following a severe weather event that may introduce significant foreign materials material.

Table 10.3.2
Maintenance Activities for the HI-STORM UMAX VVM

	Activity	Frequency	Comment
1.	CEC cavity is visually inspected	Prior to MPC installation	To ensure that VVM internal components are properly aligned, the surface preservatives on all exposed surfaces are undamaged, the insulation on the Divider Shell is undamaged and the cavity is free of visible foreign material.
2.	Lid Examination	Prior to MPC installation	Ensure that the preservatives on the external surfaces are in good condition and the lid is free of dents and rust stains.
3.	Screen Inspection	Prior to installation of the flanged screen assembly and monthly when in use	Ensure that the screen is present and undamaged.
4.	ISFSI pad	Annually	Ensure that the ISFSI Pad (raised areas near the VVM) is free of visible cracks or repaired as appropriate, the interface between the ISFSI Pad and the CEC Flange is grouted (or caulked) if necessary, the ISFSI drain system is functional, the ground water collection and removal system (if used) is in working order. Ensure that the subgrade settlement is minimal and unsightly surface cracks in the ISFSI pad have not developed. Implement counter measures to prevent the opening of surface cracks and excessive pad settlement, if observed.
5.	Shielding Effectiveness Test	As required by the Radiation Protection Program	—

Table 10.3.2 (continued)
Maintenance Activities for the HI-STORM UMAX VVM

	Activity	Frequency	Comment
6.	ISFSI Settlement	Every five years	Confirm that the VVM settlement is within the range of its design basis
7.	VVM Air Temperature Monitoring System (if used)	Per Licensee's QA Program and manufacturer's recommendations	—
8.	VVM In-Service Inspection	Annually	Ensure that the vent screen assembly fasteners or weldments remain coated with preservative, the screen is present and undamaged, all visible external surfaces are free from significant corrosion, and the air passages are not degraded.
10.	Additional VVM In-Service Inspection for Long-Term Interior and Below-grade Degradation: a) Visual inspection of accessible areas for long-term degradation. b) Additional in-service inspection activities include inspection for foreign material accumulation, corrosion (CEC thinning) and insulation degradation	a) Monthly visual inspection of accessible areas. b) Frequencies for additional in-service inspections are determined on a site-specific basis.	Inspection activities shall be commensurate with site-specific conditions. Under site conditions existing at most ISFSI sites, visual inspection of accessible areas is sufficient to determine the general condition of the system.

Table 10.3.3 Acceptance Criteria for Testing of Shipping Cask Gas Sample	
Radionuclide	**Concentration Limit (Note 1)**
Krypton-85	10^{-4} μCi/cc (Note 2)

Note 1: Concentration measurement is performed using equipment specifically designed to detect gamma emission from Krypton-85 in the gas sample. Equipment shall be suitably designed and calibrated to correlate the rate of Krypton-85 radioisotope disintegration to volumetric concentration.

Note 2: Acceptance criteria based on occupational derived air concentration limits for Krypton-85 of Appendix B to 10 CFR Part 20 [7.4.1].

Table 10.3.4 Transport Cask Flushing/Backfill Requirements		
Process	**Gas**	**Limit**
Cask Backfill	99.9% Helium (recommended)	41 kPa (6 psig) to 103 kPa (15 psig)
Cask Flushing (Note 1)	99.7% Nitrogen (or greater)	≤ 103 kPa (15psig)

Note 1: Requirements applicable only for transport cask in horizontal orientation, on tilt frame.

10.4 PERSONNEL SELECTION, TRAINING, AND CERTIFICATION

10.4.1 Personnel Organization

The personnel organization is shown in the organization charts in Figures 10.4.1 and 10.4.2.

10.4.2 Selection and Training of Operating Personnel

The main objective of the training program is to provide personnel with the specialized training necessary to operate and maintain the site in a safe manner.

Individuals requiring unescorted access to the site will receive training in the following areas: Radiation Protection, Security, Radiological Emergency Plan, Quality Assurance, Fire Protection, Chemical Safety, OSHA compliance, and the Policy statement on worker responsibility for safe operation of the ISFSI. Individuals requiring continued unescorted access will receive refresher training on these topics annually.

Individuals performing quality-related activities in support of the site will receive training on the QA Program, QA policies, and if applicable, site procedures and organization as necessary to ensure that suitable proficiency is maintained.

Operation of equipment and controls that are identified as important to safety for the ISFSI shall be limited to personnel who are trained and certified in accordance with the HI-STORE Specialist Training Program [10.1.1] or personnel who are under the direct visual supervision of a person who is trained and certified in accordance with the HI-STORE Specialist Training Program [10.1.1].

On-site workers will receive radiation protection training commensurate with their responsibilities in accordance with 10 CFR 19, "Notices, Instructions and Reports to Workers: Inspection and Investigations." [11.1.1]

Records will be maintained on the status of trained personnel, training of new employees, and refresher training of present personnel.

10.4.3 Selection and Training of Security Guards

Security training will be provided in accordance with the training and qualification requirements outlined in the HI-STORE Site Security Plan [3.1.1].



Figure 10.4.1: Holtec Corporate Organization



Figure 10.4.2: HI-STORE Site Organization

10.5 EMERGENCY PLANNING

The Holtec CISF Emergency Response Plan [10.5.1] evaluates and describes the necessary and sufficient emergency response capabilities for managing all reasonably anticipated emergency conditions associated with the operation of the HI-STORE facility. The plan meets all requirements of 10CFR72.32(a).

10.6 PHYSICAL SECURITY AND SAFEGUARDS CONTINGENCY PLANS

The HI-STORE Site Security Plan [3.1.1] contains a detailed plan for security measures for physical protection of the site. In addition, this plan contains contingencies for responding to threats and potential radiological sabotage. This plan complies with the requirements of 10CFR72, Subpart H, "Physical Protection."

10.7 SUMMARY

The conduct of operations described in this chapter fulfills the requirements of NUREG-1567 [1.0.3], Section 10, by providing the following information:

1 A plan for conduct of operations at the HI-STORE CIS site in compliance with 10CFR72.24(h).

2 Detailed description of the HI-STORM UMAX storage system operations which, based on successful previous experience, is concluded to be largely demonstrated and in compliance with 10CFR72.24(i).

3 Detailed description of the program covering preoperational testing and initial operations, in compliance with 10CFR72.24(p).

4 The provision of acceptable technical qualifications, including training and experience, for personnel who will be engaged in the proposed activities, in compliance with 10CFR72.28(a).

5 A description of a personnel training program to comply with 10CFR72,Subpart I.

6 A description of the operating organization, delegations of responsibility and authority, and the minimum skills and experience qualifications relevant to the various levels of responsibility and authority, in compliance with 10CFR72.28(c).

7 A commitment to maintain an adequate complement of trained and certified installation personnel before receipt of spent fuel or high-level radioactive waste for storage, in compliance with 10CFR72.28(d).

8 Assurance of qualification by reason of training and experience to conduct the operations covered by the regulations in 10 CFR 72, in compliance with 10CFR72.40(a)(4).

9 Assurance with regard to the management, organization, and planning for preoperational testing and initial operations that the activities authorized by the license can be conducted without endangering the health and safety of the public, in compliance with 10CFR72.40(a)(13).

CHAPTER 11: RADIATION PROTECTION EVALUATION*

11.0 INTRODUCTION

11.0.1 Ensuring Occupational Radiation Exposures are As Low As is Reasonably Achievable

The objective for the Centralized Interim Storage (CIS) Facility Radiation Protection Program is to keep radiation exposures to facility workers and the general public as low as is reasonably achievable (ALARA). Subsection 11.1.1 describes the policy and procedures that ensure that ALARA occupational exposures are achieved. Subsection 11.1.2 describes the ALARA design considerations and Subsection 11.1.3, the ALARA operational considerations.

The HI-STORE CIS Facility utilizes the HI-STORM UMAX storage system (Docket #72-1040) [1.0.6], and only canisters approved for that system and listed in Table 1.0.3 are permitted for storage in the facility. Therefore, the principal radiation protection evaluation is directly taken from the HI-STORM UMAX FSAR, and is incorporated by reference. Table 11.0.1 lists all sections from the HI-STORM UMAX FSAR that are incorporated by reference, together with a technical justification. However, some additional radiation protection evaluation that is different from that in the HI-STORM UMAX FSAR is required specifically for the HI-STORE CIS Facility, due to site-specific considerations. These additional radiation protection evaluations are clearly identified in the following sections.

* All references are in placed within square brackets in this report and are compiled in Chapter 19 (References)

Table 11.0.1: Material Incorporated by Reference in this Chapter (Sheet 1 of 2)

Information Incorporated by Reference	Source of the Information	NRC Approval of Material Incorporated by Reference	Location in this SAR where Material is Incorporated	Technical Justification of Applicability to HI-STORM UMAX
Ensuring that Occupational Radiation Exposures are As-Low-As-Reasonably-Achievable (ALARA)	Section 11.1 of Reference [1.0.6]	SER HI-STORM UMAX Amendments 0, 1, and 2, References [7.0.1, 7.0.2, and 7.0.3]	Section 11.1	From the radiation protection perspective, the HI-STORM UMAX system at the HI-STORE CIS Facility is the same as the one described in the HI-STORM UMAX FSAR and originally approved in the referenced SER. The generic radiation protection policy considerations, radiation exposure criteria, operational considerations, and auxiliary/temporary shielding measures established in this SAR are also applicable for the site-specific HI-STORE CIS Facility license.
Radiation Protection Features in the HI-STORM UMAX System Design	Section 11.2 of Reference [1.0.6]	SER HI-STORM UMAX Amendments 0, 1, and 2, References [7.0.1, 7.0.2, and 7.0.3]	Section 11.2	The HI-STORM UMAX radiation protection design features are the same as described in the HI-STORM UMAX FSAR and therefore the conclusions established therein that the radiation protection features ensure that the occupational dose as well as off-site dose from the ISFSI will be ALARA, remain unchanged in this SAR.
Estimated On-Site Cumulative Dose Assessment - Excavation Activities and accident site boundary dose limits.	Subsection 11.3.2 of Reference [1.0.6]	SER HI-STORM UMAX Amendments 0, 1, and 2, References [7.0.1, 7.0.2, and 7.0.3]	Subsection 11.3.1	In the event it is desired to expand the HI-STORE CIS Facility's HI-STORM UMAX VVM ISFSI, radiation protection of the excavation activities is achieved on a site-specific level using the same prescription as in the generic case (i.e. prescribing a minimum distance between the excavation area and the loaded VVMs, as well as radiological monitoring of the excavation area. The shielding design basis accident dose presented in the HI-STORM UMAX FSAR for the HI-STORM UMAX system demonstrates compliance with 10CFR72.106 [1.0.5] for the HI-STORE CIS Facility.

Table 11.0.1: Material Incorporated by Reference in this Chapter (Sheet 2 of 2)

Information Incorporated by Reference	Source of the Information	NRC Approval of Material Incorporated by Reference	Location in this SAR where Material is Incorporated	Technical Justification of Applicability to HI-STORM UMAX
Estimated Exposures for Surveillance and Maintenance	Subsection 11.3.4 of Reference [1.0.6]	SER HI-STORM UMAX Amendment 0, 1, and 2, Reference [7.0.1, 7.0.2, and 7.0.3]	Subsection 11.3.1	Security surveillance and maintenance activities for the HI-STORM UMAX ISFSI are addressed in the HI-STORM UMAX FSAR. The HI-STORM UMAX ISFSI at the HI-STORE CIS Facility utilizes electronic temperature monitoring of the HI-STORM UMAX modules, which significantly lowers personnel dose accumulated from security and surveillance measures.

11.1 AS LOW AS REASONABLY ACHIEVABLE CONSIDERATIONS

11.1.1 ALARA Policies and Programs

A Radiation Protection Program is implemented at the CIS Facility in accordance with requirements of 10CFR72.126, 10CFR20.1101, and 10CFR19.12 [1.0.5], [7.4.1], and [11.1.1]. The program draws upon the experience and expertise of programs and personnel of Holtec International and utilities that plan to transport radioactive waste to the CIS Facility.

Section 11.1 of the HI-STORM UMAX FSAR [1.0.6] is incorporated by reference into this SAR, and describes radiation protection policy considerations, radiation exposure criteria, operational considerations, and auxiliary/temporary shielding measures applicable to the HI-STORE CIS Facility, as described in Table 11.0.1 of this SAR.

The primary goal of the Radiation Protection Program is to minimize exposure to radiation such that the individual and collective exposure to personnel in all phases of operation and maintenance are kept ALARA. This is accomplished by integrating ALARA concepts into design, construction, and operation of the facility.

Trained personnel develop and conduct the Radiation Protection Program and will assure that procedures are followed to meet CIS Facility and regulatory requirements. Training programs in the basics of radiation protection and exposure control is provided to all facility personnel whose duties require working in radiation areas.

Basic objectives of the ALARA program are:

1 Protection of personnel, including surveillance and control over internal and external radiation exposure to maintain individual exposures within permissible limits and ALARA, and to keep the annual integrated (collective) dose to facility personnel ALARA.

2 Protection of the public, including surveillance and control over all conditions and operations that may affect the health and safety of the public.

The radiation protection staff is responsible for and has the appropriate authority to maintain occupational exposures as far below the specified limits as reasonably achievable. Ongoing reviews are performed to determine how exposures might be reduced. The program ensures that CIS Facility personnel receive sufficient training and that radiation protection personnel have sufficient authority to enforce safe facility operation. Periodic training and exercises are conducted for management, radiation workers, and other site employees in radiation protection principles and procedures, protective measures, and emergency responses. Revisions to operating and maintenance procedures and modifications to CIS Facility equipment and facilities are made when the proposed revisions will substantially reduce exposures at a reasonable cost. The program also ensures that adequate equipment and supplies for radiation protection work are provided.

The CIS Facility is committed to a strong ALARA program. The ALARA program follows the guidelines of Regulatory Guides 8.8 [11.1.2] and 8.10 [11.1.3] and the requirements of 10 CFR 20 [7.4.1]. Management is committed to compliance with regulatory requirements regarding control of personnel exposures and establishes and maintain a comprehensive program at the CIS

Facility to keep individual and collective doses ALARA. Management will assure that each staff member integrates appropriate radiation protection controls into work activities. CIS Facility personnel are trained and updated on ALARA practices and dose reduction techniques to assure that each individual understands and follows procedures to maintain his/her radiation dose ALARA. Design, operation, and maintenance activities are reviewed to ensure ALARA criteria are met.

The ALARA program ensures that:

1 An effective ALARA program is administered at the CIS Facility that appropriately integrates management philosophy and NRC regulatory requirements and guidance.

2 CIS Facility design features, operating procedures, and maintenance practices are in accordance with ALARA program guidelines. Formal periodic reviews of the Radiation Protection Program will assure that objectives of the ALARA program are attained.

3 Pertinent information concerning radiation exposure of personnel is reflected in design and operation.

4 Appropriate experience gained during the operation of nuclear power stations relative to radiation control is factored into procedures, and revisions of procedures, to assure that the procedures continually meet the objectives of the ALARA program.

5 Necessary assistance is provided to ensure that operations, maintenance, and decommissioning activities are planned and accomplished in accordance with ALARA objectives.

6 Trends in CIS Facility personnel and job exposures are reviewed to permit corrective actions to be taken with respect to adverse trends.

7 When it is not practicable to apply process controls or other engineering controls, dose reduction techniques such as access control, limitation of exposure times, and other controls in accordance with 10CFR20.1702 [7.4.1] may be used.

CIS Facility personnel are responsible for ensuring that activities are planned and accomplished in accordance with the objectives of the ALARA program. Staff will ensure that procedures and their revisions are implemented in accordance with the objectives of the ALARA program, and that radiation protection staff is consulted as necessary for assistance in meeting ALARA program objectives. Individual radiation doses, and collective doses associated with tasks controlled by radiation work permits, are tracked to identify trends and support development of alternative procedures that result in lower doses.

11.1.2 Design Considerations

ALARA considerations have been incorporated into the CIS Facility design, in accordance with 10CFR72.126(a) [1.0.5], based upon the layout of the CIS Facility area and the type of spent fuel storage system selected. The following summarizes the design considerations:

- The HI-STORM UMAX ISFSI is located at least 400 meters (1312 feet) to the controlled area boundary. This provides an acceptable distance from radiation sources to offsite personnel to ensure dose rates at the controlled area boundary are minimized and maintained within specified limits.

- The HI-STORM UMAX ISFSI has been sized to allow adequate spacing between Vertically Ventilated Modules (VVMs) to permit workers to function efficiently during loading/unloading operations at the ISFSI and during performance of maintenance (e.g. clearing blockage from the inlet ducts and surveillances. Adequate work space helps to minimize time spent by workers in the vicinity of storage casks, limiting worker dose.
- The storage system design is based on a metal canister that is sealed by welding for spent fuel confinement, preventing release of radionuclides from inside the canister. Radioactive effluents are thus precluded by design. This meets the intent of 10CFR72.24(e)(l) and 10CFR72.126(d) [1.0.5], which requires that the ISFSI design provide means to limit the release of radioactive materials in effluents during normal operations to levels that are ALARA. There are no radioactive effluents released from the CIS Facility during normal operations. This passive system design also requires minimum maintenance and surveillance requirements by personnel.
- The data acquisition of the VVM temperature monitoring system enables remote readout of temperatures representative of cask thermal performance, avoiding time spent by CIS staff to perform daily walkdowns, or take measurements, or read instrumentation in the vicinity of the HI-STORM UMAX ISFSI.
- Holtec International, the vendor of the spent fuel storage system, has incorporated a number of design features to provide ALARA conditions during transportation, handling, and storage as described in its HI-STORM UMAX Final Safety Analysis Report [1.0.6].
- Where practical, power operated wrenches are used to reduce the times associated with tasks involving bolt insertion and removal during transport cask receipt and canister transfer operations. This minimizes times spent in radiation fields. Temporary shielding is used where it is determined to be effective in reducing total dose for a task (considering doses to personnel involved in its installation and removal).

Regulatory Position 2 of Regulatory Guide 8.8 [11.1.2] is incorporated into design considerations, as described below:

- Regulatory Position 2a on access control is met by use of a fence with a locked gate that surrounds the HI-STORM UMAX ISFSI and prevents unauthorized access.
- Regulatory Position 2b on radiation shielding is met by the heavy shielding of the shipping, storage, and transfer casks, which minimizes personnel exposures during transport cask reception, canister transfer, canister storage, and offsite shipment operations. The designs of the storage cask air inlet and outlet ducts prevent direct radiation streaming. The Canister Transfer Building is positioned a substantial distance (as shown in Figure 2.1.4) from the HI-STORM UMAX ISFSI to minimize dose from the ISFSI to personnel during operations taking place in the Canister Transfer Building. The designs of the shipping, storage, transfer casks and auxiliary equipment assure adequate shielding for personnel inside the Cask Transfer Building.
- The Security and Administrative Buildings is also positioned a substantial distance (as shown in Figure 2.1.4) from the HI-STORM UMAX ISFSI to minimize dose from the ISFSI to personnel residing in this building.

- Regulatory Position 2c on process instrumentation is met since the cask temperature monitoring system utilizes a data acquisition system to record cask temperature instrumentation readings, avoiding time spent by CIS Facility staff to make daily cask vent blockage surveillances and to read instrumentation in the vicinity of the storage casks.
- Regulatory Position 2d on control of airborne contaminants is not applicable because gaseous releases are precluded by the sealed canister design. No significant surface contamination is expected on the outer surfaces of the canister since process controls are maintained during fuel loading into the canister at the originating nuclear power plants. Additionally, the nuclear power plant shipping the cask is required to demonstrate compliance with 49CFR173.443 [10.3.1], which places strict controls on non-fixed contamination.
- Regulatory Position 2e on crud control is not applicable to the CIS Facility because there are no systems at the CIS Facility that could produce crud.
- Regulatory Position 2f on decontamination is met because the internal surfaces of shipping, transfer, and storage casks have hard surfaces that lend themselves to decontamination by wiping. Interior surfaces of the Canister Transfer Building are painted with a special paint that is easily decontaminated.
- Regulatory Position 2g on radiation monitoring is met with the use of area radiation monitors in the Canister Transfer Building for monitoring general area dose rates from the casks and canisters during canister transfer operations, and with thermoluminescent dosimeters (TLDs) along the perimeters of the RA and OCA to provide information on radiation doses. Continuous air monitors, if deemed necessary, are located in the exhaust of the Canister Transfer Building (Subsection 11.2.5) and/or available as portable air samplers.
- Regulatory Position 2h on resin treatment systems is not applicable to the CIS Facility because there are not any radioactive systems containing resins.
- Applicable portions of Regulatory Position 2i concerning other miscellaneous ALARA items is met because CIS Facility features provide a favorable working environment and promote efficiency (Paragraph 2i(13)) [11.1.2]. These include:
    - Adequate lighting in the Canister Transfer Building, and HI-STORM UMAX ISFSI; adequate ventilation in the Canister Transfer Building;
    - Adequate working space in the Canister Transfer Building and at the HI-STORM UMAX ISFSI; and accessibility – with platforms or scaffolding and ladders that facilitate ready access to the tops of the transport casks and storage casks and to the transfer cask doors where operators need to perform tasks during canister transfer operations.
    - Regulatory Position 2i(15) is met because the emergency lighting system is adequate to permit prompt egress from any high radiation areas that could possibly exist in the vicinity of the canister/casks during canister transfer operations.

11.1.3 Operational Considerations

Specific CIS Facility operational considerations to achieve ALARA conditions are as follows:

- Fuel loading operations take place at the originating nuclear power plants, away from the CIS Facility. There are no assembly handling operations at the CIS Facility.
- No significant surface contamination is expected on the canisters as the result of controls applied during the fuel loading operations at the originating nuclear power plants. Workers therefore are not exposed to significant surface contamination or airborne contamination during canister transfer operations.
- Canister transfer between the transport cask and the HI-STORM UMAX VVM will take place within a shielded transfer cask.
- Prior to canister transfer operations, "dry runs" are performed to train personnel on canister transfer procedures, discuss methods to minimize exposures, and refine procedures to achieve minimum probable exposures.
- The CIS Facility procedures and work practices reflect ALARA lessons learned from other ISFSIs that use VVMs, as applicable.
- Operations research is performed to determine types of tools, portable shielding, and equipment that helps to minimize exposures to workers involved in canister transfer operations.
- The gantry crane located in the Canister Transfer Building is single-failure proof and is designed to withstand the design basis ground motion, as described in Chapter 5. The gantry crane, whose range of travel covers the length and width of the Canister Transfer Building, handles the transport casks and moves the transport casks from a horizontal orientation on the inbound rail car to a vertical orientation where it can be placed in the Canister Transfer Facility (indoor pit).
- The Vertical Cask Transporter (VCT) is used to move the HI-TRAC CS (transfer cask) from the Canister Transfer Building to the HI-STORM UMAX ISFSI. The VCT requires minimum personnel and allows for quick and accurate placement of a storage cask.
- The storage systems do not require any systems that process liquids or gases or contain, collect, store, or transport radioactive liquids. Therefore, there are no such systems to be maintained or operated.

Regulatory Position 4 of Regulatory Guide 8.8 is met with the use of area radiation monitors in the Canister Transfer Building and TLDs around the Restricted Area fence and the Controlled Area boundary. In addition, radiation protection personnel use portable monitors during transport cask receipt, inspection, and canister transfer operations, and the operating staff will have personal dosimetry (Subsection 11.4.2). The access control point is at the Security Building, as described in Subsection 11.4.2.

Protective equipment, that may include anti-contamination clothing and respirators, is available in the Security Building and controlled by radiation protection personnel. Airborne monitoring is performed using portable monitors as needed.

Regulatory Guide 8.10 [11.1.3] is incorporated into the CIS Facility operational considerations as described below:

1 Facility personnel are made aware of management's commitment to keep occupational exposures ALARA.

2 Ongoing reviews are performed to determine how exposures might be lowered.

3 There is a well-supervised radiation protection capability with specific, defined responsibilities.

4 Facility workers receive sufficient training.

5 Sufficient authority to enforce safe facility operation is provided to radiation protection personnel.

6 Modification to operating and maintenance procedures and to equipment and facilities are made where they substantially reduce exposures at a reasonable cost.

7 The radiation protection staff understands the origins of radiation exposures in the facility and seeks ways to reduce exposures.

8 Adequate equipment and supplies for radiation protection work are provided.

11.2 RADIATION PROTECTION DESIGN FEATURES

The HI-STORM UMAX radiation protection design features are incorporated by reference from Section 11.2 of [1.0.6], as described in Table 11.0.1 of this SAR.

11.2.1 Installation Design Features

A description of the CIS Facility layout and design is provided in Section 2.1. The CIS Facility layout and design are in accordance with the facility and equipment design features identified in Position 2 of Regulatory Guide 8.8 [11.1.2], as described in Subsection 11.1.2.

The CIS Facility has the following design features that ensure that exposures are ALARA:

- The site is located far from population centers [1.0.4].
- The nearest resident is 1.5 miles (2.41 km) north of the site, as shown in Table 1.0.1.
- The only sources of radiation at the CIS Facility are the sealed canisters containing spent fuel assemblies. These canisters are always shielded by shipping, storage, or by transfer casks during canister transfer operations.
- Measures are taken at the originating nuclear power plants to prevent loose surface contamination levels on the exterior of the canisters. Controls assure that canisters are not transported to the CIS Facility unless contamination levels are within specified limits.
- The canisters are sealed by welding, eliminating the potential for release of radioactive gases or particles.
- The canisters are never opened, nor will spent fuel assemblies be unloaded at the CIS Facility.
- The fuel assemblies are stored dry inside the canisters, so that no radioactive liquid is available for release.
- The shipping, transfer, and HI-STORM UMAX VVMs are heavily shielded to minimize external dose rates.
- The CIS Facility site layout provides substantial distance between the HI-STORM UMAX ISFSI and the Controlled Area boundary, as shown in Table 1.0.1, minimizing radiation exposures to individuals outside the controlled area boundary and assuring offsite dose rates are below the 10CFR72.104 [1.0.5] criteria.
- The location of the Canister Transfer Building inside the Restricted Area (RA) minimizes the route between the Canister Transfer Building and the HI-STORM UMAX ISFSI, provides for minimal other traffic on the route, and maintains substantial distance from the Controlled Area boundary.
- There are no radioactive liquid wastes associated with the CIS Facility.

The CIS Facility building ventilation systems are not designed for any special radiological considerations since there is no credible scenario for which a significant radioactive release would occur. Shielding of the canister is provided by the HI-STORM UMAX systems and by the shipping and transfer casks during canister receipt, transfer, and offsite shipping operations.

The general area inside the RA fence is a Restricted Area, as defined by 10CFR20 [7.4.1], and is controlled in accordance with applicable requirements of 10CFR20, with personnel dosimetry required. Certain areas within the Restricted Area are designated as Radiation Areas, and specific locations within the RA have the potential to be High Radiation Areas, and are posted and controlled in accordance with applicable requirements of 10CFR20 [7.4.1]. The cask load/unload bay, crane bay, cask transporter bay, and canister transfer cells inside the Canister Transfer Building are designated as Radiation Areas whenever loaded canisters are present in these areas, since the potential exists for dose rates to exceed 5 mrem/hr in these areas. Upon removal of the impact limiters from the transport casks in the Canister Transfer Building, the potential exists for dose rates in the vicinity of the top and or bottom of the casks to exceed 100 mrem/hr in localized areas, and these localized areas will be posted as High Radiation Areas, with necessary controls applied. Due to distances from the transport casks when their impact limiters are removed, dose rates outside the Canister Transfer Building are well below 100 mrem/hr.

11.2.2 Access Control

The CIS Facility is designed to provide access control in accordance with 10CFR72. Access control to the RA is provided for both personnel radiological protection and facility physical protection. The physical protection program is covered in the Security Plan, which is classified and submitted as part of the License Application under separate cover.

The access control boundary for the restricted area are established along the security fence lines (see Figure 2.1.4). The RA is that space which is controlled for purposes of protecting individuals from exposure to radiation or radioactive materials and for providing facility physical security. Operational controls ensure the total effective dose equivalent to individual members of the public from the licensed operation does not exceed 0.1 rem in accordance with 10CFR20.1301(a)(1) [7.4.1]. The boundary for the RA is the security fence where the dose rate is less than 2 mrem/hr, in accordance with 10CFR20.1301(a)(2) [7.4.1]. The controlled area is the area inside the site boundary. The dose rate beyond the controlled area is less than 25 mrem/year, in accordance with 10CFR72.104 [1.0.5].

Access to the RA is controlled through a single access point in the Security Building (See Figure 2.1.4). Personal dosimetry is issued and controlled in this building to individuals entering the Restricted Area (RA). Provisions exist in this building for donning and removing personal protective equipment, such as anti-contamination clothing and/or respirators if deemed necessary, in the event of contamination in the Canister Transfer Building as a result of off-normal or accident conditions. Provisions for personnel decontamination are also contained in the Security Building. The Restricted Area also includes the cask storage area and Canister Transfer Building. In accordance with the CIS Facility Radiation Protection Program (Section 11.4), radiation protection personnel monitor radiation levels in the RA and establish access requirements as needed.

11.2.3 Radiation Shielding

The HI-STORM UMAX VVMs are designed to maintain radiation exposures ALARA. No low-level radioactive waste (LLW) materials are expected to be generated on site, and there are no special design provisions for low-level radioactive waste materials are not required.

In the unlikely event that low level waste is generated on site such as for smears, disposable clothing, tape, blotter paper, rags, and related health physics material, this material will be processed and temporarily stored on-site while awaiting removal to a licensed LLW disposal facility. The material will be packaged and stored in sealed LLW containers. The LLW containers provide necessary shielding, and dose rates on the outside surfaces of the drums are expected to be negligible. In the unlikely event that LLW materials are stored on-site with significant activity levels, temporarily located shielding may be used to maintain dose rates in the area ALARA, as determined by radiation protection personnel.

11.2.3.1 Shielding Configurations

Chapter 5 of the HI-STORM UMAX FSAR [1.0.6] identifies the shielding materials and geometries of the HI-STORM UMAX system and describes the codes used to model shielding and assess cask dose rates. Further descriptions of site specific shielding configurations are provided in Chapter 7 of this SAR.

11.2.4 Confinement and Ventilation

10CFR72.122(h)(3) [1.0.5] requires that ventilation systems and off-gas systems be provided where necessary to ensure the confinement of airborne radioactive particulate materials during normal or off-normal conditions. However, there are no special ventilation systems installed at the CIS Facility buildings. There are no credible scenarios that would require installation of ventilation systems to protect against off-gas or particulate filtration.

11.2.5 Area Radiation and Airborne Radioactivity Monitoring Instrumentation

10CFR72.122(h)(4) [1.0.5] requires the capability for continuous monitoring of the storage system to enable the licensee to determine when corrective action needs to be taken to maintain safe storage conditions. This is not applicable to the CIS Facility because the canisters are sealed by welding and with the canisters in HI-STORM UMAX systems, there are no credible events that could result in releases of radioactive material from within the canisters or unacceptable increases in direct radiation levels, as described in Chapter 9. Area radiation and airborne radioactivity monitors are therefore not needed at the storage pads. However, TLDs are used to record dose rates in the Restricted Area and along the Controlled Area boundary. TLDs provide a passive means for continuous monitoring of radiation levels and provide a basis for assessing the potential impact on the environment.

TLDs are located at the Restricted Area fence and at the Controlled Area Boundary in accordance with 10CFR20.1302 [7.4.1]. Additionally, TLDs are located at strategic locations inside the Canister Transfer Building, Security Building, and Administration Building where personnel are normally working. These TLDs serve as a backup for monitoring personnel radiation exposure and maintaining this exposure ALARA. For redundancy, each TLD location mentioned above house a set of two TLDs. The TLDs are retrieved and processed quarterly. The TLDs primarily detect gamma radiation and have a lower limit of sensitivity of (0.02 mrem). The storage system design is based on a metal canister that is sealed by welding for spent fuel confinement, preventing release of radionuclides from inside the canister. Radioactive effluents are thus precluded by design.

Local radiation monitors with audible alarms are installed in the Canister Transfer Building. These provide warning to personnel involved in the canister transfer operation of abnormal radiation levels that could possibly occur during transfer operations. Because of measures taken at the originating nuclear power plants to minimize loose surface contamination levels on the exterior of the canisters during fuel loading operations, as discussed in Subsection 11.1.3, it is unlikely that canister transfer operations would generate significant levels of airborne contaminants. Local continuous air monitors include alarms to warn operating personnel in the unlikely event of an airborne release, remote alarm in the Security Building alarm station to ensure coverage at all times, and charting capability to provide data necessary to quantify any release. The radiological alarm systems are designed with provisions for calibration and operability testing. There are no liquid or gaseous effluent releases from the CIS Facility. This satisfies the requirements of 10CFR72.24(e)(l) and 10CFR72.126(b)(c) [1.0.5].

11.3 DOSE ASSESSMENT

11.3.1 Onsite Dose

The shipping, transfer, and storage casks are designed to limit dose rates to ALARA levels for operators, inspectors, maintenance, and radiation protection personnel when the canisters are being transferred from the shipping to the transfer casks, when the transfer cask is being moved to the ISFSI, and while the canisters are transferred from the transfer cask to the HI-STORM UMAX VVMs.

HI-TRAC CS dose rates at the surface, 0.5 meter, 1 meter, and 2 meter distances are presented in Table 7.4.1. HI-STORM UMAX Version C dose rates at the surface and at 1 meter are presented in Table 7.4.2.

Table 11.3.1 shows the estimated occupational exposures to CIS Facility personnel during receipt of the transport cask and transfer of the canister from the transport cask to the HI-STORM UMAX using the HI-TRAC CS transfer cask. The operational sequence for these operations is also described in Chapter 3.

Dose rate values include both gamma and neutron flux components, and are based on design basis PWR fuel as shown in Table 7.1.1. Fuel with these characteristics is considered to conservatively represent fuel assemblies that are contained in canisters handled at the CIS Facility, and dose estimates based on fuel with these characteristics are considered to be realistic and reflect expected personnel exposures.

Occupational doses to individuals are administratively controlled to ensure that they are maintained below 10 CFR 20.1201 limits. Temporarily positioned shielding is used during transfer operations to reduce dose rates from streaming paths or relatively high radiation areas where its use results in a net reduction in worker exposures. Conservatively, the effects of temporarily positioned shielding are not considered in the Table 11.3.1 dose estimates for canister transfer operations. It is expected the actual crew dose per loading would be significantly less than what is presented in Table 11.3.1, and operational experience gained with each loading also has been shown to lower crew dose on subsequent loadings.

The shielding design basis accident dose analysis for the HI-STORM UMAX system presented in Subsection 11.3.2 of Reference [1.0.6] is incorporated by reference as described in Table 11.0.1. Additionally, in the event it is desired to expand the HI-STORE CIS Facility's HI-STORM UMAX VVM ISFSI, radiation protection of excavation activities is incorporated by reference from Section 11.3.2 of Reference [1.0.6] as described in Table 11.0.1.

Occupational exposures are also estimated to security personnel and CIS Facility personnel that conduct inspections, surveillances, and maintain the storage systems. Subsection 11.3.4 of the HI-STORM UMAX FSAR [1.0.6], which addresses estimated exposures for security surveillance and maintenance, is incorporated by reference into this SAR as described in Table 11.0.1.

11.3.2 Offsite Dose

The offsite dose evaluation is provided in Section 7.4, with results in Table 7.4.3 and Table 7.4.4.

Table 11.3.1: Estimated Personnel Exposures for Loading Operations of One Canister at the HI-STORE CIS Facility

(Sheet 1 of 2)

OPERATION	NUMBER OF PERSONNEL	DURATION (MINS)	OCCUPANCY FACTOR (%)	DOSE RATE (mrem/hour)	CREW DOSE (mrem)
RECEIVE HI-STAR 190	2	120	20	50	40.0
PERFORM HI-STAR 190 INSPECTION	2	30	50	50	25.0
REMOVE PERSONNEL BARRIER	2	20	50	10	3.3
REMOVE TIE-DOWN	2	20	70	10	4.7
ATTACH HORIZONTAL LIFT BEAM	2	25	30	50	12.5
MOVE HI-STAR 190 TO TILT FRAME	2	25	70	10	5.8
REMOVE IMPACT LIMITERS	2	30	90	10	9.0
PERFORM ANNULUS SAMPLE	2	60	20	200	80.0
REMOVE LID BOLTS	2	80	90	10	24.0
ATTACH LIFT YOKE TO HI-STAR 190	1	20	30	10	1.0
TILT HI-STAR 190 TO VERTICAL	2	10	80	10	2.7
PLACE HI-STAR 190 IN CTF	2	20	80	10	5.3
REMOVE HI-STAR 190 CLOSURE LID	2	20	70	50	23.3
INSTALL SEAL SURFACE PROTECTOR	2	10	80	256	68.2
INSTALL MPC LIFTING ATTACHMENT	2	20	90	256	153.5
PLACE ALIGNMENT PLATE ON HI-STAR 190	2	25	80	51	34.1
PLACE HI-TRAC ON CTF	2	20	90	17	10.0
GRAPPLE MPC LIFTING ATTACHMENT	1	15	100	17	4.2
RAISE MPC INTO HI-TRAC	2	5	100	17	2.8
CLOSE HI-TRAC SHIELD GATES	2	5	100	35	5.8

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

Table 11.3.1: Estimated Personnel Exposures for Loading Operations of One Canister at the HI-STORE CIS Facility

(Sheet 2 of 2)

OPERATION	NUMBER OF PERSONNEL	DURATION (MINS)	OCCUPANCY FACTOR (%)	DOSE RATE (mrem/hour)	CREW DOSE (mrem)
MOVE HI-TRAC TO VCT PICK UP AREA	2	30	90	17	15.1
CONNECT VCT TO HI-TRAC	3	20	100	17	16.7
REMOVE CEC LID	3	120	50	2.0	6.0
INSTALL DIVIDER SHELL	3	120	50	2.0	6.0
TRANSPORT HI-TRAC TO CEC	2	120	100	17	69.2
PLACE HI-TRAC ON CEC	3	20	100	17	17.3
CONNECT MPC LIFTING EXTENSION TO MPC LIFTING ATTACHMENT	1	15	100	17	4.3
OPEN HI-TRAC SHIELD GATES	2	5	100	35	5.8
LOWER MPC INTO CEC	1	10	100	17	2.9
DISCONNECT MPC LIFTING EXTENSION	1	5	100	17	1.4
REMOVE HI-TRAC FROM CEC	3	60	90	17	46.7
REMOVE MPC LIFTING ATTACHMENT	2	15	40	512	102.3
INSTALL CEC LID	2	60	100	2.69	5.4
TOTAL					814.2

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

11.4 RADIATION PROTECTION PROGRAM

11.4.1 Organizational Structure

The CIS Facility Radiation Protection Manager reports to the Site Manager (Figure 10.4.2) and is responsible for administering the radiation protection program and for the radiation safety of the facility. Minimum qualification requirements are set forth in Chapter 10.

Responsibilities of the CIS Facility Radiation Protection Manager include the following:

- Administer the Radiation Protection program policies and procedures
- Review and approve radiation protection procedures
- Coordinate radiation protection group activities with operations and maintenance personnel
- Ensure adequate staffing, facilities, and equipment are available to perform the functions assigned to radiation protection personnel
- Establish goals for the Radiation Protection program
- Initiate and implement exposure control program that factors dosimetry results into operational planning
- Issue or rescind "stop work" orders as appropriate
- Ensure that locations, operations, and/or conditions that have potential for causing significant exposures to radiation are identified and controlled
- Review and approve training programs related to work in radiological areas or involving radioactive material
- Administer shipments (if necessary) of solid radioactive waste offsite for disposal
- Review root causes and corrective actions for incidents and deficiencies associated with Radiation Protection
- Ensure an effective ALARA program is maintained, in accordance with the guidance provided in Regulatory Guides 8.8 [11.1.2] and 8.10 [11.1.3]
- Supervise the collection, analysis and evaluation of data obtained from radiological surveys and monitoring activities in accordance with 10CFR20.1501 [7.4.1]
- Participate in the event of an emergency, as required

Radiation protection technicians report to the Radiation Protection Manager. Responsibilities of the radiation protection technicians include the following:

- Conduct radiation, contamination, and airborne surveys and prepare complete and accurate records
- Prepare Radiation Work Permits to control access to and activities in radiologically controlled areas

- Identify and post radiation, contamination, hot particle, airborne and radioactive material areas in accordance with 10 CFR 20 [7.4.1] requirements
- Monitor CIS Facility operations to assure good radiological work practices
- Implement ALARA program requirements
- Maintain and calibrate portable monitoring instruments
- Issue "stop work" orders whenever activities have the potential to jeopardize the health and safety of workers, visitors, or the general public
- Verify proper packaging of any radioactive material
- Participate in the event of an emergency, as required

11.4.2 Equipment, Instrumentation, and Facilities

A sufficient inventory and variety of operable and calibrated portable and fixed radiological instrumentation is maintained to allow for effective measurement and control of radiation exposure and radioactive material and to provide back-up capability for inoperable equipment. Equipment is ensured to be appropriate to enable the assessment of sources of gamma, neutron, beta, and alpha radiation, including the capability to measure dose rates and radioactivity concentrations expected. Radiation protection procedures govern instrument calibration, instrument inventory and control, and instrument operation.

Portable survey and personnel monitoring instrumentation, if deemed necessary during normal, off-normal, or accident conditions, will include, but not be limited to, the following:

- Low-level contamination meters
- Beta/gamma portable survey meters
- Alarming beta/gamma personnel friskers
- Portable air samplers

Area radiation monitors are utilized in the Canister Transfer Building since the operations performed in this building (transport cask receipt, inspection, and canister transfer operations) pose the greatest risk to the operating staff for radiation exposure. These monitors have audible alarms to warn operating personnel of abnormal radiation levels. Area radiation monitors are not utilized outside the Canister Transfer Building since these areas have relatively low area radiation levels and there are no operations performed in these areas which could result in rapid change in radiation level and pose a risk for over-exposure of personnel.

The Restricted Area is surrounded by a chain link security fence and an outer chain link nuisance fence with an isolation zone and intrusion detection system between the two fences. Access to the Restricted Area is controlled through a single access point in the Security Building (see Figure 2.1.4). Personal dosimetry is issued and controlled in this building to individuals entering the Restricted Area. External radiation dose monitoring is accomplished through the use of thermoluminescent dosimeters (TLDs) and self-reading dosimeters (SRDs) or digital alarming dosimeters (DADs). During transfer operations inside the Canister Transfer Building alarming dosimeters shall be used to warn of excessively high direct radiation to maintain exposures

ALARA, thereby providing assurance that occupational exposures do not exceed the limits of 10 CFR Part 20. The official record of external dose to beta and gamma radiations is normally obtained from the TLDs with SRDs or DADs used as a means for tracking dose between TLD processing periods as a backup to TLDs. Self-reading dosimeters are administered in accordance with the guidance in Regulatory Guide 8.4 [11.4.1].

Provisions exist in the Security Building for donning and removing personal protective equipment, such as anti-contamination clothing, which could be necessary in the event of contamination in the Canister Transfer Building due to off-normal or accident conditions. A respiratory protection program, if deemed necessary, will be established in accordance with 10 CFR 20 and consistent with the guidance of NUREG-0041 [11.4.2].

Provisions for personnel decontamination are contained in the Security Building. Contamination of equipment or personnel is not expected to occur under normal conditions of operation. In accordance with the CIS Facility policy of preventing generation of liquid radioactive waste, any necessary decontamination of equipment and personnel will be conducted using methods that produce only solid radioactive waste. Decontamination methods would typically include wiping the contaminated item with rags or paper wipes.

Drain sumps are provided in the cask load/unload bay of the Canister Transfer Building which catch and collect water that drips from transport casks (e.g. from melting snow) onto the floor. Water collected in the cask load/unload bay drain sumps is sampled and analyzed to verify it is not contaminated prior to its release. In the event contaminated water is detected, it will be collected in a suitable container, solidified by the addition of an agent such as cement or "Aquaset" so that it qualifies as solid waste, staged on-site while awaiting shipment offsite, and transported to a LLW disposal facility, in accordance with Radiation Protection procedures.

No process or effluent monitors are necessary because of the design of the CIS Facility storage system, in which spent fuel assemblies are stored in welded canisters. During routine storage operations at the CIS Facility, the only radiological instrumentation in use in the storage area are the TLDs, as described in Subsection 11.2.5. Routine radiological surveys use instruments that are controlled by the Radiation Protection Program and governed by existing procedures. Calibration procedures for radiological instrumentation are established and applied to instruments used at the CIS Facility.

11.4.3 Policies and Procedures

Radiation protection requirements for all radiological work at the CIS Facility are governed by radiation protection procedures. Radiation protection practices for cask loading and unloading operations, canister transfer, canister storage, and monitoring are also based on these procedures, as well as on anticipated conditions when the task is to be performed. These procedures, if deemed necessary, include, but are not limited to, the following:

- Procedure for performing badging functions for access authorization to the Restricted Area.
- Procedure for issuing personnel dosimetry, and monitoring, recording, and tracking individual exposures.
- Procedure for performing radiological safety training and refresher training.

- Procedure for performing ALARA reviews of plant procedures and monitoring of operations.
- Procedure for determining radiation doses on a periodic basis at the Restricted Area and Controlled Area boundaries using TLDs.
- Procedure for issuing, revising, and terminating radiation work permits and standing radiation work permits.
- Procedure for roping off, barricading, and posting radiation control zones.
- Procedure for decontaminating personnel, equipment, and areas.
- Procedure for performing radiation surveys in accordance with 10CFR20.1501.
- Procedure for smear swab sampling, counting, and calculation.
- Procedure for calibrating detection, monitoring, and dosimetry instruments.
- Procedure for quantifying airborne radioactivity.
- Procedure for maintaining records of the radiation protection program, including audits and other reviews of program content and implementation; radiation surveys; instrument calibrations; individual monitoring results; and records required for decommissioning.

Implementation of the Radiation Protection Program procedures ensures that occupational doses are below the limits required by 10 CFR 20.1201 [7.4.1]. Area radiation monitors in the Canister Transfer Building have audible alarms and warn operating personnel of abnormal radiation levels. While area radiation monitors are not installed in the Restricted Area, measures are in place to ensure personnel in the Restricted Area do not exceed dose limits. Process and engineering controls at the HI-STORE CIS Facility ensures that contamination is non-existent or minimized, that controls are in place to ensure air concentrations of radioactive material is non-existent or insignificantly low, and that there is no or minimal generation of radioactive waste on-site in accordance with 10CFR20.1406 and 10CFR20.1701 [7.4.1].

As discussed in Subsection 11.2.2, access to the Restricted Area is controlled through a single access point in the Security Building where personal dosimetry is issued to individuals entering the Restricted Area. Periodic radiation surveys are conducted of areas inside the Restricted Area and maps are generated showing the radiation levels in all areas. Radiation work permits (RWPs) are completed by qualified radiation protection personnel prior to any entry and serve to identify normal and unusual radiation readings. Workers are required to read, understand and sign that they are aware of the conditions or unknowns. Personnel are trained to use the appropriate radiation detection instruments or are required to have a qualified radiation protection technician with them at all times while in the areas. Training includes responses to unusual readings and off-scale conditions. The Radiation Protection program will provide for the immediate reading of any individual's TLD if an unusual reading or off-scale condition occurs.

11.5 REGULATORY COMPLIANCE

The HI-STORM UMAX System at the HI-STORE CIS Facility provides radiation shielding and confinement features that are sufficient to meet the requirements of 10CFR72.104 and 10CFR72.106 [1.0.5].

Occupational radiation exposures satisfy the limits of 10CFR20 [7.4.1] and meet the objective of maintaining exposures ALARA.

The design of the HI-STORM UMAX System is in compliance with 10CFR72 [1.0.5] and applicable design and acceptance criteria have been satisfied. The radiation protection system design provides reasonable assurance that the HI-STORM UMAX System at the HI-STORE CIS Facility allows safe storage of spent fuel.

CHAPTER 12: QUALITY ASSURANCE PROGRAM*

12.0 INTRODUCTION

12.0.1 Overview

This chapter provides a summary of the quality assurance program implemented by Holtec International for activities related to the design, qualification analyses, material procurement, fabrication, assembly, testing and use of structures, systems, and components of the Company's dry storage/transport systems including the HI-STORM UMAX System and other equipment at the HI-STORE CIS facility. This chapter is included in this SAR to fulfill the requirements in 10CFR72.140(c)(2) as elaborated in NUREG-1567[1.0.3].

Important-to-safety activities related to construction and deployment of the HI-STORM UMAX System and other equipment at the HI-STORE CIS Facility are controlled under the NRC-approved Holtec Quality Assurance Program. The Holtec QA program manual [12.0.1]† is approved by the NRC under Docket 71-0784. The Holtec QA program satisfies the requirements of 10CFR72, Subpart G and 10CFR71, Subpart H. In accordance with 10CFR72.140(d), this approved 10CFR71 QA program will be applied to spent fuel storage cask activities at HI-STORE under 10CFR72. The additional recordkeeping requirements of 10CFR72.174 are addressed in the Holtec QA program manual and must also be complied with.

The Holtec QA program is implemented through a hierarchy of procedures and documentation, listed below.

1. Holtec Quality Assurance Program Manual [12.0.1]
2. Holtec Quality Assurance Procedures
3. Miscellaneous Documents including, but not limited to:
    a. Holtec Standard Procedures
    b. Holtec Project Procedures
    c. Project Specifications
    d. Drawing packages
    e. Project Bill-of-Materials
    f. Inspection and testing procedures
    g. Welding procedure Specifications
    h. Calculation packages
    i. Technical Reports (generic and project specific)
    j. Position Papers and Technical Memos

* All references are in placed within square brackets in this report and are compiled in Chapter 19 of this report
† Holtec QA manual [12.0.1] is incorporated by reference in its entirety in this chapter. Format and content of QA manual is in accordance with NUREG 1567 [1.0.3] and Regulatory Guide 3.50 [1.0.2].

k. Corporate Documents that include Corporate Governance, Safety and other manuals

l. A series of databases including the Lessons Learned database

Quality activities performed by others on behalf of Holtec are governed by the supplier's quality assurance program or Holtec's QA program extended to the supplier. The type and extent of Holtec QA control and oversight is specified in the procurement documents for the specific item or service being procured. The fundamental goal of the supplier oversight portion of Holtec's QA program is to provide the assurance that activities performed in support of the supply of safety-significant items and services are performed correctly and in compliance with the procurement documents.

12.0.2 Graded Approach to Quality Assurance

Holtec International uses a graded approach to quality assurance on all safety-related or important-to-safety projects. This graded approach is controlled by Holtec Quality Assurance (QA) program documents as described in Subsection 12.0.1.

NUREG/CR-6407 [1.2.2] provides descriptions of quality categories A, B and C. Using the guidance in NUREG/CR-6407, Holtec International assigns a quality category to each individual, important-to-safety component of the HI-STORM UMAX System and HI-TRAC transfer cask. The ITS categories assigned to the HI-STORM UMAX cask components and for other equipment deployed at the HI-STORE CIS Facility, and equipment needed to deploy the HI-STORM UMAX System at HI-STORE CIS are provided in Chapter 4 using the guidelines of NUREG/CR-6407 [1.2.2].

Activities affecting quality will be defined by Holtec's Purchase Specifications and/or written instructions/procedures for use of the HI-STORM UMAX System under the license provisions of 10CFR72, Subpart C at the HI-STORE CIS independent spent fuel storage installation (ISFSI). These activities include any or all of the following: design, procurement, fabrication, handling, shipping, storing, cleaning, assembly, inspection, testing, operation, maintenance, repair, monitoring and aging management of HI-STORM UMAX and other HI-STORE CIS Facility equipment structures, systems, and components (SSCs) that are important-to-safety.

The quality assurance program described in the Holtec QA Program Manual fully complies with the requirements of 10CFR72 Subpart G and the intent of NUREG-1567 [1.0.3]. However, NUREG-1567 does not explicitly address incorporation of a QA program manual by reference. Therefore, invoking the NRC-approved QA program in this SAR constitutes a literal deviation from NUREG-1567. This deviation is acceptable since important-to-safety activities are implemented in accordance with the latest revision of the Holtec QA program manual and implementing procedures. Further, incorporating the QA Program Manual by reference in this SAR avoids duplication of information between the implementing documents and the SAR and any discrepancies that may arise from simultaneous maintenance to the two program descriptions governing the same activities. The Holtec Quality Assurance Manual has been included as one of the documents incorporated by reference in this SAR (Table 1.0.3).

12.1 REGULATORY COMPLIANCE

The chapter complies with the quality assurance requirements of 10CFR72. As indicated in Table 1.0.3, Holtec's NRC-approved QA program, is adopted herein for 10CFR72 activities performed at the HI-STORE CIS Facility. The QA program applies to the dockets listed in Table 1.3.1 of this SAR. The QA program covers activities affecting important to safety components identified in this report for the HI-STORE CIS Facility.

The format and content of the Quality Assurance Program Manual [12.0.1] is in accordance with NUREG-1567 [1.0.3] and Regulatory Guide 3.50 [1.0.2].

CHAPTER 13: DECOMMISSIONING EVALUATION*

13.0 INTRODUCTION

This chapter contains the information for the design and operational features of the HI-STORE CIS Facility that will allow for eventual decontamination and decommissioning of the site. Also, described in this chapter is the financial assurance mechanisms that will fund the decommissioning effort.

* All references are in placed within square brackets in this report and are compiled in Chapter 19 of this report.

Table 13.0.1: Material Incorporated By Reference				
Information Incorporated by Reference	**Source of the Information**	**NRC Approval of Material Incorporated by Reference**	**Location in this SAR where Material is Incorporated**	**Technical Justification of Applicability to HI-STORM UMAX**
HI-STORM UMAX Decommissioning Considerations	HI-STORM UMAX FSAR Chapter 2.11 [1.0.6]	SER HI-STORM UMAX Amendments 0, 1, and 2 [7.0.1, 7.0.2, 7.0.3]	Section 13.1	The ISFSI structure is the same as the one described in the HI-STORM UMAX FSAR and the same Decommissioning Considerations would apply at the HI-STORE CIS Facility.

13.1 DESIGN FEATURES

Section 2.11 of the HI-STORM UMAX FSAR [1.0.6] is incorporated by reference into this SAR, and describes all the design features of the ISFSI which are considered for the decommissioning of the Site. The CTF and other auxiliary SSCs, as described in Chapter 4, support decommissioning processes similar to those used for the HI-STORM UMAX VVM structures.

13.2 OPERATIONAL FEATURES

The layout and design of the HI-STORE CIS Facility will facilitate rapid, safe, and economical decommissioning of the Site. As described in Chapter 2 of the HI-STORM UMAX FSAR [1.0.6], the VVM components are designed to allow the retrieval of the MPC under all conditions of storage. The MPC, which holds the SNF assemblies, is engineered to be suitable as a waste package for permanent internment in a deep Mined Geological Disposal System (MGDS). Towards that end, the loaded MPC has been designed with the objective to transport it in a transportation cask, which is an *a priori* assumption for receipt of the canisters at the Site.

The HI-STORE CIS Facility will be operated as a "clean" facility. All components of the facility including the transport casks and storage canisters are designed to minimize the potential for any contamination. Canisters are already welded shut and sealed to prevent leaks at the generator facility. All procedures controlling handling and storage operations of the canisters will emphasize minimizing any potential contamination at the Site. Dose rate surveys will be performed throughout the operations for site receiving and loading of canisters as discussed in Chapter 3 of this SAR. The dose requirements for these surveys are discussed in Chapter 7 of this SAR.

Pursuant to 10 CFR 72.30(f), records of importance to the decommissioning of the HI-STORE CIS Facility will be maintained until the site is released for unrestricted use. Records will include:

- Records of spills or other unusual occurrences involving the spread of contamination in and around the facility, equipment, or site.
- Records on contamination that may have spread to inaccessible areas.
- As-built drawings and modifications of structures and equipment used in the storage of radioactive materials.
- A list containing all areas designated as a restricted area.
- The decommissioning funding plan, cost estimate, and records of the funding method used for assuring funds are available for decommissioning.

13.3 DECOMMISSIONING PLAN

13.3.1 General Provisions

A Preliminary Decommissioning Plan for the HI-STORE CIS Facility is provided in Holtec Report HI-2177558 [13.3.1]. A summary of this preliminary plan and is presented below.

The objective of decommissioning activities at the HI-STORE CIS Facility is to verify that any potential radioactive contamination is below established release limits, and in the unlikely event of contamination, to identify and remove radioactive contamination that is above the NRC release limits, so that the site may be released for unrestricted use and the NRC license terminated.

Residual radioactive contamination is not anticipated at the HI-STORE CIS Facility for several reasons:

- Canisters are surveyed and decontaminated at the generator facility, prior to shipment, to ensure the outer surfaces are clean. This is repeated at the HI-STORE CIS Facility to ensure dose rate and contamination requirements are met.
- Canisters are welded shut and sealed to prevent leaks.
- Canisters will not be opened during transportation to the Site or during transfer, handling, or storage operations at any time.
- Radiological activation of the VVM and concrete pad materials is expected to be insignificant with radiation levels below the applicable NRC criteria for unrestricted release.

An insignificant amount of radioactive wastes are expected to be generated at the HI-STORE CIS Facility from normal operations of the Site. Conventional decontamination techniques will be used to minimize the volume of waste generated. Any waste generated will be sent to a licensed facility for disposal. Gaseous and liquid wastes are not generated at the HI-STORE CIS Facility. Small volumes of solid radioactive waste may be produced from routine operations involving contamination surveys and decontamination activities involving incoming and outgoing transportation casks and equipment. Potential solid waste streams are collected and temporarily stored at the Site until offsite shipping, processing, and disposal methods are available.

A Final Decommissioning Plan detailing activities and procedures for decommissioning will be provided once all of the canisters are removed from the facility. The Final Decommissioning Plan will address final status survey of the site and termination of the license. The final plan will evaluate NRC criteria for decommissioning to ensure all requirements are satisfied. Decommissioning activities will be planned using ALARA principles and in a manner that protects the public and environment during the process.

13.3.2 Cost Estimate

Pursuant to 10 CFR 72.30, a decommissioning cost estimate was prepared and is presented in Holtec Report HI-2177565 [13.3.2]. This report discusses the decommissioning cost estimate and financial funding assurance per 10 CFR 72.30(b)(2). The decommissioning cost estimate follows

the guidance of NUREG-1757 [13.3.3, 13.3.4] for activities that will allow the NRC license to be terminated and the remaining facility and site may be released for unrestricted use.

The cost estimating method used for developing the overall decommissioning cost estimate is based on resource costing. The resource costing is based on the resources and duration to estimate the costs associated with radiological surveys and decontamination activities. The estimated labor costs are based on an R.S. Means 2017 [13.3.5] that will allow an independent third party to assume the responsibility and carry out the decommissioning project. Non-labor costs include equipment and security.

The decommissioning cost estimate is based on the following key assumptions:

- All costs associated with removing the canisters from the site is not included.
- Four crews will be used to perform the radiological survey within a one year time frame.
- No subsurface material is assumed to require remediation regarding radionuclides.
- No canisters will be opened at the CIS Facility
- Nuclear activation of the VVMs and concrete pads are anticipated to be below the release limits, however for the purposes of the cost estimate, it is assumed that removal and remediation of the VVMs will be necessary
- There is no subsurface soil containing residual radioactivity that will require remediation.
- The decommissioning tasks are assumed to be completed in a two year time frame.
- All costs used in the estimates were current on January 2017.

The decommissioning cost estimate will be updated a minimum of every three years, adjusting the estimated cost for current prices of services, inflation (as necessary), and approach. The key assumptions will be also be revisited and adjusted as warranted.

13.3.3 Financial Assurance Mechanism

The method of financial assurance as specified in 10 CFR 72.30(e)(3) will be met by Holtec International. Expected decommissioning costs for Phase 1 of the HI-STORE CIS Facility are presented in Holtec Report HI-2177565 [13.3.2]. A decommissioning fund will be established by setting aside a fixed dollar amount per MTU stored at the HI-STORE facility. These funds, plus earnings on such funds calculated at a fixed rate of return over the life of the facility, will cover the estimated cost to complete decommissioning.

13.4 REGULATORY COMPLIANCE

Pursuant to the guidance provided in NUREG-1567 [1.0.3], the foregoing material in this Chapter provides:

i. A complete description of the Design Features of the Site which facilitate decommissioning as mandated by 10CFR72.24, 72.30, and 72.130;

ii. A complete description of the Operational Features of the Site which facilitate decommissioning as mandated by 10CFR72.24, 72.30, and 72.130;

iii. A complete description of the Decommissioning Plan for the Site including the Decommissioning Cost Estimate and Decommissioning Funding Plan as mandated by 10CFR72.24, 72.30, and 72.130;

Therefore, it can be concluded that this SAR provides adequate information to assure that decommissioning issues for the ISFSI facility have been adequately characterized, so that the site will ultimately be available for unrestricted use for any private or public purpose. Additionally, it can be concluded that this SAR provides adequate information to estimate the costs of decommissioning activities as well as sufficient financial assurance mechanisms to provide reasonable assurance that adequate funds will be available to decommission the facility so that the site will ultimately be available for unrestricted use for any private or public purpose.

CHAPTER 14: WASTE CONFINEMENT AND MANAGEMENT EVALUATION*

14.0 INTRODUCTION

Radioactive wastes are not generated as a result of handling and storage operations for spent fuel or high-level waste (HLW) at the HI-STORE CIS site. The canisters bearing SNF and other approved contents for storage in HI-STORM UMAX systems at the HI-STORE CIS serves as the confinement system during storage and related operations, as noted in Chapter 9 of this report. There is no breaching or opening of the confinement canister during storage operations. The integrity of the confinement system has been proven via analysis to be maintained during normal, off-normal and hypothetical accident conditions as discussed in Chapters 9 and 15 of this report.

* All references are in placed within square brackets in this report and are compiled in Chapter 19 of this report.

14.1 WASTE SOURCES

Radioactive wastes typically generated during operations at an ISFSI fall into the categories (a and b) below. However, as discussed in Sections 14.3, 14.4 and 14.5, the HI-STORE CIS does not generate radioactive wastes in any form during operations. Therefore, implicitly, the HI-STORE CIS complies with the radioactive wastes and radiological impact criteria in 10CFR20 and 10CFR72, as they pertain to the waste generated onsite.

a) Effluents (gaseous and liquid), and

b) Wastes (solid or solidified)

In addition to the radioactive waste types above, NUREG-1567 [1.0.3] also recommends evaluation of exposure of radioactive wastes to non-radioactive wastes such as combustion products and chemical wastes.

Combustion Products

An explosion within the protected area of the ISFSI is unlikely, since explosive materials are generally prohibited within the site boundary. However, an explosion as a result of combustible fluid contained in the VCT is possible (Subsection 6.5.2). Due to the quantity of combustible fluid and the structurally robust construction materials of the HI-TRAC transfer cask, HI-STORM UMAX VVM and the canister, the effects of a fire is minimal, and the confinement boundary of the canister is not compromised (Subsection 6.5.2). The canister is in the HI-TRAC during transfer by the VCT to the HI-STORM UMAX VVM, which provides protection to the canister during an explosion. The effect of an explosion on the canister is further reduced after loading into a HI-STORM UMAX. Canisters in a HI-STORM UMAX system are protected from an explosion by the robust lid of the HI-STORM UMAX, the ISFSI pad, the subgrade and HI-STORM UMAX VVM. Thus explosions due to combustion products will not compromise canisterized wastes being transferred to the VVM or in the VVM, and therefore have no radiological impact. There is also no credible mechanism through which radioactive wastes will come into contact with the fuel prior to or after loading into the VCT, which could potentially result in unplanned releases as exhausts effluents from the VCT's engine during operations.

Chemical Wastes

There are no chemical wastes generated at the HI-STORE CIS Facility.

14.2 OFF-GAS TREATMENT AND VENTILATION

The HI-STORE CIS is not a waste treatment facility. Canisters loaded and welded shut at the waste site of origin remain closed during transfer operations and storage at the HI-STORE CIS. The canister confinement boundary is not procedurally opened during operations upon arrival at the HI-STORE CIS. Furthermore, upon arrival at the HI-STORE CIS and prior to opening the transport cask containment boundary, the transport cask and the loaded canister are leak tested to ANSI N14.5 (Subsection 10.3.3) "leaktight" criteria to ensure the confinement boundary of the canister was not compromised during transport to the HI-STORE CIS. If a breach of the loaded canister is detected during the leakage test, the loaded transport cask is transported off-site to a facility authorized to perform contents unloading operations or transported back to the site of origin of the radioactive wastes without opening its transport cask containment boundary.

Therefore, since a) breach of the confinement canisters is deemed non-credible under analyzed conditions, b) opening of the confinement boundary of canisters is procedurally prohibited at the HI-STORE CIS, and c) the HI-STORE CIS is not a waste treatment facility, the generation or presence of gaseous effluents, either due to contamination cleanup or other activities is non-credible, and negates the need for off-gas treatment and ventilation systems.

14.3 LIQUID WASTE TREATMENT AND RETENTION

The HI-STORE CIS is designed for passive storage of HI-STORM UMAX Systems that require no further handling once canisters are loaded into the VVM. Liquid wastes, radioactive or non-radioactive, are not generated at the HI-STORE CIS during handling and or storage operations. Therefore treatment and retention systems for liquid wastes are not required.

Fuel and HLW loaded canisters are inspected prior to transport to the HI-STORE CIS. Upon arrival at the HI-STORE CIS, the transport cask or overpack is inspected for damage and is also leak tested along with the loaded canister. In the unlikely scenario that leakage is detected or damage is observed to a degree that may compromise the long term integrity of the canister, the transport cask with the loaded canister is returned to the waste site of origin or other authorized facility for decontamination, which may involve a washdown, followed by canister unloading. Washdowns or decontamination activities of the transport cask and canisters, if required, will not occur at the HI-STORE CIS. This prevents generation of liquid radioactive or non-radioactive wastes at the CIS. Furthermore, the CIS has no labs or other facilities that may produce liquid wastes, that may become susceptible to contamination, radiologically or otherwise.

Furthermore, the ISFSI pads are designed to ensure drainage of rain water or other spilled liquids away from the HI-STORM UMAX VVMs. Radioactive contamination of drained liquids from the ISFSI pad is unlikely since all radioactive wastes onsite are in canisters. The canister design, as approved by the NRC, precludes a breach of its steel weldment construction under all analyzed conditions (Chapters 9 and 15) during storage in the HI-STORM UMAX systems. Therefore leakage of radioactive material from the canisters is or non-credible.

14.4 SOLID WASTES

As explained in Subsection 14.3, the liquid waste (radioactive or non-radioactive) is not generated as a result of facility normal operations and off-normal events as defined in Chapters 9 and 15 of this report. As such, solidified wastes – generated from liquid waste stream(s) – are not generated at the HI-STORE CIS, and there isn't a need for a packaging system or storage facility for solidified wastes.

Solid radioactive wastes, are not generated at the HI-STORE CIS as a result of facility operations. SNF and HLW stored at the CIS arrives in a canister that is transferred to the HI-STORM UMAX VVM following inspection that ensures the integrity of the canister weldment is uncompromised. At no time during storage and transfer operations at the CIS is the canister opened and waste handled or treated. If breach of the canister is detected during leak testing of the transport cask and loaded canister, the package is transported back to the site of origin or other site authorized to handle the radioactive contents of the package for unloading and other remediation activities. Therefore no solid radioactive wastes are generated as a result of CIS facility operations, and no packaging and storage system is needed.

14.5 RADIOLOGICAL IMPACT OF NORMAL OPERATIONS

There are no radioactive wastes generated during normal operations of the HI-STORE CIS Facility. The radiological impact of the HI-STORE CIS Facility is provided in Chapter 11 of this report, and is in compliance with 10CFR20 [7.4.1] and 10CFR72 [1.0.5] effluents and dose criteria.

14.6 REGULATORY COMPLIANCE

In accordance with NUREG-1567 [1.0.3], this chapter should comply with 10CFR20 Appendix B Table 2, 10CFR72.24(l) and (f), 10CFR72.40(a)(13), 10 CFR72.104, 72.122(h), 10 CFR 72.126(c) and (d), and 10CFR72.128(a)(5) and (b).

10CFR20 Appendix B, Table 2 gaseous or liquid effluents radionuclide concentration limits shall not be exceeded at the HI-STORE CIS Facility.

10CFR72.24(f) requires this report to include features of the ISFSI design and operating modes that reduce to the extent practicable radioactive waste volumes generated at the installation.

10CFR72.24(l) requires description of instruments that maintain control over radioactive materials in gaseous and liquid effluents produced during normal operations and expected operational occurrences.

10CFR72.40(a)(13) requires that this report provide reasonable assurance that (i) the activities authorized by the license can be conducted without endangering the health and safety of the public, and (ii) the activities be conducted in compliance with applicable regulations of this chapter.

10CFR72.104 doses shall not be exceeded.

10CFR72.122(h)(3) requires that ventilation systems and off-gas systems must be provided where necessary to ensure the confinement of airborne radioactive particulate materials during normal or off-normal conditions.

10CFR72.126(c) requires as appropriate for handling and storage systems that effluent monitoring system be provided, and direct radiation monitoring system be provided in and around areas containing radioactive materials.

10CFR72.126(d) requires the ISFSI be designed to provide means to limit as low as reasonably achievable the release of radioactive materials in effluents during normal operations; and control the release of radioactive materials under accident conditions. Show via analysis that releases to the environment will be within the exposure limits given in 10 CFR 72.104 for normal conditions and 10 CFR 72.106 for design basis accident conditions.

10CFR72.128(a)(5) requires spent fuel and other radioactive wastes handling and storage systems must be designed to minimize the quantity of radioactive wastes generated.

10CFR 72.128(b) radioactive waste treatment facilities must be provided. Provisions must be made for the packing of site-generated low-levels wastes in a form suitable for storage onsite awaiting transfer to disposal sites.

This chapter ensures that the HI-STORE CIS Facilities complies with the applicable waste confinement and management regulatory requirements of 10 CFR 20 and 72. The HI-STORE CIS Facility is designed to receive welded canisters containing SNF and related hardware. No radioactive wastes (gaseous or liquid effluents) will be generated at the ISFSI site, and the canisters will arrive welded and remain welded throughout the storage duration at the HI-STORE CIS ISFSI. The canisters are classified as “leaktight” in accordance with ANSI N14.5 (Subsection 10.3.3), and release to the environment or impact on public health and safety is

considered non credible or negligible. Therefore no effluents monitoring system are provided. Radiation monitoring equipment are provided at the HI-STORE CIS Facility as discussed in the Radiation Protection chapter (11).

As noted in Section 2.2 of this report, four nuclear facilities exist or are planned to be built within 50 miles of the proposed site for the HI-STORE CIS Facility. The closest nuclear facility is located 16 miles southwest of the proposed site for the HI-STORE CIS Facility. As such, there is no concern of the cumulative impact from operation of the HI-STORE CIS Facility and nearby facilities on the public. The environmental impacts of other nuclear facilities are in impact statements in Section 2.2 of this report.

CHAPTER 15: ACCIDENT ANALYSIS[1]

15.0 INTRODUCTION

This chapter is focused on the safety evaluation of all off-normal and accident events germane to the HI-STORE CIS facility. For each postulated event, the event cause, means of detection, consequences, and corrective actions, as applicable, are discussed and evaluated. For other miscellaneous events (i.e., those not categorized as either design basis off-normal or accident condition events), a similar outline for safety analysis is followed. As applicable, the evaluation of consequences includes the impact on the structural, thermal, shielding, criticality, confinement, and radiation protection performance of the system due to each postulated event.

As the HI-STORE facility deploys the NRC licensed HI-STORM UMAX System for long term storage of spent fuel the applicable off-normal and accident events addressed in the HI-STORM UMAX FSAR [1.0.6] are incorporated herein by reference. A roadmap of applicable HI-STORM UMAX material is tabulated in Table 15.0.1.

The structural, thermal, shielding, criticality, and confinement features and performance of the HI-STORM UMAX system under the short-term operations and various conditions of storage are discussed in Chapters 5, 6, 7, 8 and 9. The evaluations provided in this chapter are based on the safety analyses reported therein. The accidents considered in this chapter follow guidance in NUREG-1567 [1.0.3] and NUREG-1536 [15.3.1].

[1] All references are in placed within square brackets in this report and are compiled in Chapter 19 (last chapter).

Table 15.0.1: Material Incorporated by Reference in this Chapter				
Information Incorporated by Reference	**Source of the Information**	**NRC Approval of Material Incorporated by Reference**	**Location in this SAR where Material is Incorporated**	**Technical Justification of Applicability to HI-STORM UMAX**
Off-Normal Events	Section 12.1, Reference [1.0.6]	SER HI-STORM UMAX Amendments 0,1,2 References [7.0.1, 7.0.2, 7.0.3]	Section 15.2	See Note 1
Accident Events	Sections 12.2 and 12.3, Reference [1.0.6]	SER HI-STORM UMAX Amendments 0,1,2 References [7.0.1, 7.0.2, 7.0.3]	Section 15.3	See Note 1
Note 1: As the HI-STORM UMAX Version C System is essentially the same as the version approved for use in the HI-STORM UMAX Docket[2] and the severity of events are no greater than off-normal and accident events evaluated in the HI-STORM UMAX FSAR [1.0.6] it follows that the consequences evaluated in it are bounding.				

[2] Minor changes introduced in Version C have no adverse effect on the analyses performed for the generic license version.

15.1 ACCEPTANCE CRITERIA

15.1.1 Off-Normal Events

Criticality

In accordance with 10CFR72.124(a) regulations spent fuel sub-criticality must be maintained with k_{eff} equal to or less than 0.95.

Confinement

In accordance with 10CFR72.128(a)(3) regulations systems important to safety must be evaluated to reasonably ensure radioactive material remains confined under off-normal and accident events.

Retrievability

In accordance with 10CFR72.122(l) storage systems must allow safe retrieval of the stored spent fuel without endangering public health and safety or undue exposure to workers.

Instrumentation

In accordance with 10 CFR72.122(i) and 72.128(a)(1) the SAR must identify all instruments and control systems required to remain operational under accident conditions.

15.1.2 Accident Events

In addition to Subsection 15.1.1 criteria, dose rates to individuals located at or beyond controlled area boundary must meet 10CFR72.106(b) limits under design basis accidents.

15.2 OFF-NORMAL EVENTS

In this section, design events pertaining to off-normal operation under expected operational occurrences are considered and evaluated.

The following off-normal events are applicable to the HI-STORE CIS facility:

- Off-Normal Pressure
- Off-Normal Environmental Temperature
- Leakage of One MPC Seal
- Partial Blockage of Air Inlet and Outlet Ducts
- Hypothetical Non-Quiescent Wind[3]
- Cask Drop Less Than Design Allowable Height
- Off-Normal Events Associated with Pool Facilities

15.2.1 Off-Normal Pressure

The sole pressure boundary in the HI-STORM UMAX storage System is the MPC enclosure vessel. The off-normal pressure condition is specified in Section 6.4 and evaluated in Section 6.5. The off-normal pressure for the MPC internal cavity is a function of the initial helium fill pressure and the steady state temperature reached within the MPC cavity under normal ambient temperature. The MPC internal pressure under the off-normal condition is evaluated with 10% of the fuel rods ruptured and with 100% of ruptured rods fill gas and 30% of ruptured rods fission gases released to the cavity.

15.2.1.1 Postulated Cause of Off-Normal Pressure

Fuel rods rupture is a non-mechanistic event postulated as a defense-in-depth measure and evaluated.

15.2.1.2 Detection of Off-Normal Pressure

The HI-STORM UMAX system is designed to withstand the MPC off-normal internal pressure without any effects on its ability to meet its safety requirements. There is no requirement or safety imperative for detection of off-normal pressure and, therefore, no monitoring is required.

15.2.1.3 Analysis of Effects and Consequences of Off-Normal Pressure

The MPC off-normal internal pressure is analyzed in Section 6.4. The analysis shows that the MPC pressure remains below Off-Normal limit.

i. Structural

Structural integrity of the MPC enclosure vessel is not affected as the pressure computed under this event remains below the MPC Off-Normal pressure limit as qualified by the

[3] Hypothetical non-quiescent wind intends to evaluate HI-STORM UMAX under a sustained persistent wind of a constant magnitude and direction to maximize disruption of the thermal performance.

structural design of the MPC in Section 3.1 of the HI-STORM UMAX FSAR [1.0.6] and incorporated herein by reference.

ii. Thermal

The MPC internal pressure under off-normal conditions is evaluated in Section 6.5. The computed pressure remains below Off-Normal pressure limit.

iii. Shielding

There is no effect on the shielding performance of the system as a result of this off-normal event.

iv. Criticality

There is no effect on the criticality control features of the system as a result of this off-normal event.

v. Confinement

There is no effect on the confinement function of the MPC as a result of this off-normal event. As discussed in the structural evaluation above, all pressure boundary stresses remain within allowable ASME Code values, assuring Confinement Boundary integrity.

vi. Radiation Protection

As shielding and confinement functions are not affected as evaluated above, there is no adverse effect on occupational or public exposures as a result of this off-normal event.

15.2.1.4 Corrective Action for Off-Normal Pressure

The HI-STORM UMAX system is designed to withstand the off-normal pressure without any effects on its ability to maintain safe storage conditions. Therefore, there is no corrective action requirement for off-normal pressure.

15.2.1.5 Radiological Impact of Off-Normal Pressure

The event of off-normal pressure has no radiological impact because the confinement barrier and shielding integrity are not affected.

15.2.1.6 Conclusion

Based on this evaluation, it is concluded that the off-normal pressure does not affect the safe operation of the HI-STORM UMAX system.

15.2.2 Off-Normal Environmental Temperature

As evaluated in Subsection 6.5.1 this event is bounded by HI-STORM UMAX FSAR [1.0.6]. Event evaluation incorporated by reference. See Table 15.0.1 and HI-STORM UMAX FSAR Subsection 12.1.2 [1.0.6].

15.2.3 Leakage of one MPC seal

The MPC confinement boundary is defined by MPC shell, baseplate, lid, vent and drain port covers, closure ring and associated welds. Leakage of an MPC seal weld evaluated in HI-STORM UMAX FSAR Subsection 12.1.3 [1.0.6] is incorporated by reference.

15.2.4 Partial Blockage of the Air Inlet and Outlet Ducts

As evaluated in Subsection 6.5.1 this event is bounded by HI-STORM UMAX FSAR [1.0.6]. Event evaluation incorporated by reference. See Table 15.0.1 and HI-STORM UMAX FSAR Subsection 12.1.4 [1.0.6].

15.2.5 Hypothetical Non-Quiescent Wind

As evaluated in Subsection 6.4.3 this event is bounded by HI-STORM UMAX FSAR [1.0.6]. Event evaluation incorporated by reference. See Table 15.0.1 and HI-STORM UMAX FSAR Subsection 12.1.5 [1.0.6].

15.2.6 Cask Drop Less Than Design Allowable Height

HI-STORM UMAX VVM

Not applicable as HI-STORM UMAX VVM is a permanently installed underground structure.

HI-TRAC CS

HI-TRAC CS drop not credible as heavy load handling requires redundant drop protection. See Chapter 4, Subsections 4.5.1, 4.5.2 and 4.5.3.

HI-STAR 190

HI-STAR 190 drop not credible as heavy load handling requires redundant drop protection. See Chapter 4, Subsections 4.5.1, 4.5.2 and 4.5.3.

15.2.7 Off-Normal Events Associated with Pool Facilities

Not applicable to HI-STORE CIS facility as pool facilities not required to support operations.

15.2.8 Safety Evaluation

Off-Normal event analyses support the conclusion that HI-STORM UMAX robustly withstands impact of off-normal events and complies with Section 15.1 Acceptance Criteria and Chapter 4 Design Limits.

15.3 ACCIDENTS

Accidents, in accordance with ANSI/ANS-57.9 [2.7.2], are either infrequent events that could reasonably be expected to occur during the lifetime of the cask or events postulated because their consequences may affect public health and safety. Accidents germane to the safety evaluation of HI-STORM UMAX system are considered and evaluated herein.

The following accident events are applicable to the HI-STORE CIS facility:

- Fire Accident
- Partial Blockage of MPC Basket Vent Holes
- Tornado Missiles
- Flood
- Earthquake
- 100% Fuel Rods Rupture
- Confinement Boundary Leakage
- Explosion
- Lightning
- 100% Blockage of Air Inlet and Outlet Ducts
- Burial Under Debris
- Extreme Environmental Temperature
- Cask Tipover
- Cask Drop
- Loss of Shielding
- Adiabatic Heatup
- Accidents at Nearby Sites
- Accidents Associated with Pool Facilities
- Building Structural Failure onto SSCs
- 100% Rod Rupture Accident Coincident with Accident Events

15.3.1 Fire Accident

The potential of a fire accident is extremely remote by ensuring that there are no significant combustible materials in the area. The only credible concern is related to a transport vehicle fuel tank fire engulfing a loaded HI-STORM UMAX VVM or a HI-TRAC CS transfer cask. Fire accident involving the HI-STORM UMAX VVM, HI-TRAC CS or HI-STAR 190 fire is evaluated in the following.

15.3.1.1 Fire Analysis

(a) HI-STORM UMAX VVM Fire

The analysis for the fire accident including the methodology is articulated in Subsection 6.5.2. The transport vehicle fuel tank fire is analyzed to evaluate the storage overpack heating by the incident thermal radiation and forced convection heat fluxes and fuel cladding and MPC temperatures.

i. Structural

As evaluated in Subsection 6.5.2 there are no structural consequences of the fire accident condition as the short-term temperature limit on great majority of the concrete is not exceeded and component temperatures remain within Chapter 4 temperature limits. The MPC structural boundary remains within normal condition internal pressure and temperature limits.

ii. Thermal

Based on a conservative analysis articulated in Subsection 6.5.2 and computed response under the hypothetical event, it is concluded that the fire event does not affect the temperature of the MPC or contained fuel. Furthermore, the ability of the HI-STORM UMAX System to maintain cooling of the spent nuclear fuel within temperature limits during and after fire is not compromised.

iii. Shielding

With respect to limited damage to the outer layers of concrete subject to direct fire flux, NUREG-1536 (4.0,V,5.b) states: “the loss of a small amount of shielding material is not expected to cause a storage system to exceed the regulatory requirements in 10 CFR 72.106 and, therefore, need not be estimated or evaluated in the FSAR.”

iv. Criticality

There is no effect on the criticality control features of the system as a result of this event.

v. Confinement

There is no effect on the confinement function of the MPC as a result of this event as the structural integrity of the confinement boundary is unaffected.

vi. Radiation Protection

As there is minimal reduction, if any, in shielding and no effect on the confinement capabilities as discussed above, there is no effect on occupational or public exposures as a result of this accident event.

As supported by evaluation above, it is concluded that the design basis fire does not affect the safe operation of the HI-STORM UMAX System.

(b) HI-TRAC CS Fire

The HI-TRAC CS must withstand elevated temperatures under the Design Basis Fire event defined Chapter 6. The acceptance criteria for the fire accident are specified in Design Criteria Chapter 4.

i. Structural

The effect of the fire accident on the HI-TRAC CS is an increase in fuel cladding and system component temperatures and MPC internal pressure and thus an increase in MPC pressure boundary stresses. The resultant temperatures and pressures are below the accident design limits as evaluated below. The MPC pressures resulting from the fire accident event are be bounded by the applicable pressure boundary limits; therefore, there is no effect on structural function.

ii. Thermal

As evaluated in Section 6.5, the effect of the fire does not result in any system component or the contained fuel to exceed temperature limits set in this SAR. The Design Basis Fire has a minor impact on MPC pressure. The temperatures and pressures resulting from the fire accident event are to be bounded by the applicable system temperature and pressure limits; therefore, there is no deleterious effect on the system's thermal function. With respect to limited damage to the outer layers of concrete subject to direct fire flux, NUREG-1536 (4.0,V,5.b) states: "the loss of a small amount of shielding material is not expected to cause a storage system to exceed the regulatory requirements in 10 CFR 72.106 and, therefore, need not be estimated or evaluated in the FSAR."

iii. Shielding

Under the fire accident condition, the outside of the cask would heat up significantly, and while the outer steel shell would assure the overall integrity of the cask, and hence prevent any significant loss of shielding function, the outer area of the shielding concrete may experience some degradation. To model this in an analysis, shielding calculations are performed in which the density of the HI-TRAC CS concrete is substantially degraded as shown in Table 7.3.1. Results of the analyses are presented in Table 7.4.4, demonstrating compliance with 10CFR72.106.

iv Criticality

There is no effect on the criticality control features of the system as a result of this event.

v. Confinement

There is no effect on the confinement function of the MPC as a result of this event as the structural integrity of the confinement boundary is unaffected.

vi. Radiation Protection

There is no effect on the confinement capabilities as evaluated above, and the site boundary shielding accident dose limits in 10CFR72.106 are not exceeded thereby ensuring occupational and public safety.

(c) HI-STAR 190 Fire

As evaluated in Subsection 6.5.2 HI-STAR 190 fire accident under HI-STORE CIS deployment is bounded by the HI-STAR 190 SAR transport fire accident [1.3.6]. The accident Section 3.4 is incorporated by reference.

15.3.1.2 Fire Accident Corrective Actions

Upon detection of a fire appropriate fire protection actions are initiated in accordance with facility Emergency Response Plan [10.5.1] to extinguish the fire. Following the termination of the fire, a visual and radiological inspection of the equipment shall be performed.

If damage to HI-STORM UMAX VVM, HI-TRAC CS or HI-STAR 190 warrant, and/or radiological conditions require (based on dose rate measurements), the MPC shall be transferred to HI-TRAC CS in accordance with procedures set down in Chapter 3. The HI-STORM UMAX VVM, HI-TRAC CS or HI-STAR 190 may be returned to service after appropriate restoration (reapplication of coatings, etc.) and if there is no significant increase in the measured dose rates (i.e., the shielding effectiveness of overpack is confirmed) and if visual inspection is satisfactory.

15.3.1.3 Conclusion

Based on the above evaluation, it is concluded that the Design Basis Fire accident does not affect the safe operation of the HI-STORM UMAX, HI-TRAC CS and HI-STAR 190 casks.

15.3.2 Partial Blockage of MPC Basket Vent Holes

Event evaluation incorporated by reference. See Table 15.0.1 and UMAX FSAR Subsection 12.2.2.

15.3.3 Tornado Missiles

<u>HI-STORM UMAX VVM</u>

Site specific tornado hazards are identified in Chapter 2, Section 2.3. These hazards are bounded by HI-STORM UMAX FSAR [1.0.6] as justified in Chapter 4, Table 4.3.1. Accordingly, HI-STORM UMAX FSAR tornado accident Subsection 12.2.3 [1.0.6] is incorporated by reference.

<u>HI-TRAC CS</u>

See discussion below.

<u>HI-STAR 190</u>

HI-STAR 190 damage from tornado missile impacts are bounded by the more onerous 1-meter puncture drop accident evaluated in the HI-STAR 190 SAR [1.3.6].

15.3.3.1 Cause

Tornado and high winds are principally caused by the uneven heating of the earth's atmosphere, coupled with gravitational forces and the rotation of the earth. The HI-TRAC CS involves deployment in an open area environment and thus will be subject to extreme environmental conditions throughout the storage period.

15.3.3.2 Tornado Analysis

A tornado event is characterized by high wind velocities and tornado-generated missiles. The reference missiles considered in this SAR are of three sizes: small, medium, and large. A small projectile, upon collision with a cask, would tend to penetrate it. A large projectile, such as an automobile, on the other hand, would tend to cause deformation.

The tornado analysis for a HI-TRAC CS transfer cask is evaluated in Chapter 5. The evaluation is summarized below.

i. Structural

There is no effect on the structural function of HI-TRAC CS as a result of this accident event.

ii. Thermal

There is no effect on the function of HI-TRAC CS heat transfer features as a result of this accident event. Tornado borne missile may cause localized damage. Global heat dissipation characteristics are unaffected.

iii. Shielding

Tornado borne missile may cause localized damage. Dose consequences of the localized damage are bounded by accident analysis in Shielding Chapter 7

iv. Criticality

There is no effect on the criticality control features of the MPC as a result of this accident event.

v. Confinement

There is no effect on the confinement function of the MPC as a result of this accident event.

15.3.3.3 Radiation Protection and Consequences

There is no adverse effect on confinement functions. Controlled area boundary accident dose limits in 10CFR72.106 are not exceeded.

15.3.3.4 Tornado Accident Corrective Action

Following a tornado accident visual and radiological inspection shall be performed in accordance with site Emergency Response Plan and appropriate restoration measures undertaken if localized damage results in a significant increase in measured dose.

15.3.3.5 Conclusion

Based on the above evaluation, it is concluded that the Design Basis tornado accident will not affect the safe operation of the HI-STORM UMAX, HI-TRAC CS and HI-STAR 190 casks.

15.3.4 Flood

Site specific flood hazards are identified in Chapter 2, Section 2.4.3. These hazards are bounded by HI-STORM UMAX FSAR [1.0.6] as justified in Chapter 4, Table 4.3.1. Moderator exclusion under flood accident is evaluated in Chapter 8. HI-STORM UMAX FSAR flood accident Subsection 12.2.4 [1.0.6] is incorporated by reference.

15.3.5 Earthquake

HI-STORM UMAX

Site specific earthquake hazards are identified in Chapter 4, Subsection 4.3.2. These hazards are bounded by HI-STORM UMAX FSAR [1.0.6] as justified in Chapter 4, Table 4.3.1. HI-STORM UMAX FSAR earthquake accident Subsection 12.2.5 [1.0.6] is incorporated by reference.

HI-TRAC CS

See discussion below.

HI-STAR 190

HI-STAR 190 g-loads under earthquake events are reasonably bounded by the 10CFR Part 71 10-meter drop accident evaluated in the HI-STAR 190 SAR [1.3.6]. In addition, the seismic stability of freestanding HI-STAR 190 under site specific earthquake is evaluated in Chapter 5.

15.3.5.1 Cause of Event

Earthquake is a terrestrial instability event cause by relative movements in the mantle of the earth. The only concern is under a stack up of HI-TRAC CS in the CTB during canister transfer operations. This event is analyzed under site earthquake loading in Chapter 5 and evaluated below.

15.3.5.2 Analysis of the Effect of Site-Specific Earthquake

i. Structural

The stack-up scenario of the HI-TRAC CS has been fully evaluated in Chapter 5. Due to the robust configuration of the HI-TRAC CS and its earthquake resistant bolting design, it has been demonstrated that there are no structural concerns with the HI-TRAC CS under an earthquake event.

ii. Thermal

There is no effect on the function of HI-TRAC CS heat transfer features as a result of this accident event because no constriction of the air flow passages within the system is computed to occur and vertical configuration is not compromised as evaluated in the structural analysis above. Thus, the cooling effectiveness of the HI-TRAC CS remains undiminished in under an earthquake event.

iii. Shielding

There is no adverse effect on the function of shielding features of the system as a result of this accident event.

iv. Criticality

There is no effect on the criticality control features of the MPC as a result of this accident event.

v. Confinement

There is no effect on the confinement function of the MPC as a result of this accident event. Structural evaluation shows stresses remain within design criteria, assuring confinement boundary integrity.

vi. Radiation Protection and Consequences

As there is no effect on shielding or confinement functions as evaluated above, there is no radiological consequence (from effluents and direct radiation) as a result of this accident event. A minor increase to occupational exposures for the performance of corrective actions is expected.

15.3.5.3 Earthquake Accident Corrective Action

Following a seismic event HI-TRAC CS must be inspected for localized damage. Visual inspection shall be performed as follows:

- Visual inspection to confirm the extent of damage (if any) to the MPC shell is negligible.
- Visual inspection to verity the extent of damage (if any) to HI-TRAC CS components important-to-safety is negligible.
- Visual inspection to confirm air flow passages are clear of obstructions.

Corrective actions shall be implemented based on the results of the inspection.

15.3.5.4 Conclusion

Based on the above evaluation, it is concluded that the Design Basis Earthquake will not affect the safe operation of HI-TRAC CS. Corrective actions may be necessary to restore the system to the pre-seismic condition.

15.3.6 100% Fuel Rods Rupture

The rupture of every fuel rod inside the Canister is postulated as a *non-mechanistic event* in NUREG -1536 [15.3.1]. In other words, simultaneous failure of all fuel rods in a Canister is a counter-factual event whose actuation mechanism cannot be articulated but it is nevertheless postulated to ascertain the robustness of the Confinement boundary. (A similar non-credible event requiring safety assessment in NUREG-1536 is the "non-mechanistic tip-over" of above-ground storage casks). Because the rods are assumed to have failed *a' priori,* the 100% rod rupture event does not require satisfaction of a specific fuel cladding temperature limit. Rather, the acceptance criterion focuses on demonstrating the integrity of the Confinement Boundary. This accident is analyzed in Subsection 6.4.3 and integrity of the Canister's pressure boundary evaluated to ensure the internal pressure in the Canister remains below the Chapter 4 accident design pressure.

From a thermal perspective 100% percent rod rupture event is not adverse to heat transfer because internal convection heat transfer in the Canister is significantly boosted by the release of the plenum gases in the rods (due to their rupture), thus spatial temperature field in the Canister is moderated (reduced in magnitude).

15.3.7 Confinement Boundary Leakage

Event evaluation incorporated by reference. See Table 15.0.1 and HI-STORM UMAX FSAR Subsection 12.2.7 [1.0.6].

15.3.8 Explosion

Accident event is bounded by HI-STORM UMAX FSAR [1.0.6]. See site specific explosion evaluation in Chapter 4, Table 4.3.1 and Chapter 6, Subsection 6.5.2. HI-STORM UMAX FSAR explosion accident Subsection 12.2.8 [1.0.6] is incorporated by reference.

15.3.9 Lightning

Event evaluation incorporated by reference. See Table 15.0.1 and HI-STORM UMAX FSAR Subsection 12.2.9 [1.0.6].

15.3.10 100% Blockage of Air Inlets

Event evaluation incorporated by reference. See Table 15.0.1 and HI-STORM UMAX FSAR Subsection 12.2.10 [1.0.6].

15.3.11 Burial Under Debris

HI-STORM UMAX

As evaluated in Chapter 6, Subsection 6.5.2 burial accident is not credible.

HI-TRAC CS

See Subsection 15.3.19.

15.3.12 Extreme Environmental Temperature

This event is bounded by the HI-STORM UMAX FSAR [1.0.6] as the site extreme ambient temperature and cask heat loads are bounded by HI-STORM UMAX (See Table 6.3.1). Accordingly the event evaluation is incorporated by reference. See Table 15.0.1 and HI-STORM UMAX FSAR Subsection 12.2.12 [1.0.6].

15.3.13 Tip-over

Because the HI-STORM UMAX VVM is situated underground, a tip-over event is not a credible accident for this design. See Table 4.3.1.

HI-TRAC CS cask and HI-STAR 190 cask tip-over is not credible as demonstrated in Chapter 5.

15.3.14 Cask Drop

HI-STORM UMAX VVM

Not applicable as HI-STORM UMAX VVM is a permanently installed underground structure.

HI-TRAC CS

HI-TRAC CS drop not credible as heavy load handling requires redundant drop protection. See Chapter 4, Subsections 4.5.1, 4.5.2 and 4.5.3.

HI-STAR 190

HI-STAR 190 drop not credible as heavy load handling requires redundant drop protection. See Chapter 4, Subsections 4.5.1, 4.5.2 and 4.5.3.

15.3.15 Loss of Shielding

Loss of shielding rendered not-credible under an array of challenging off-normal and accident events wherein shielding function is concluded to result in *no-impact*.

15.3.16 Adiabatic Heat-up

Accident not credible as this requires a counter-factual postulate choking all means of heat dissipation including conduction, convection and radiation.

15.3.17 Accidents at Nearby Sites

To ensure HI-STORE CIS facility is not under undue risk from off-site facilities the surrounding area must be assessed for potential hazards such as military installations, gas and oil processing or storage facilities, oil or gas pipelines, chemicals, fireworks or explosives factories.

A survey of surrounding areas evaluated in Sections 2.1 and 2.2 yields one fire hazard that warrants attention. The fire hazard is evaluated in Section 6.5 concluding no adverse effect on the HI-STORM UMAX storage casks or on-site transfer operations involving the HI-TRAC CS and HI-STAR 190.

15.3.18 Accidents Associated with Pool Facilities

Not applicable to HI-STORE CIS as pool facilities not required to support operations.

15.3.19 Building Structural Failure onto SSCs

15.3.19.1 Cause of Building Collapse

This accident is defined as a postulated structural collapse of CTB building roof and burial under it of canister bearing HI-TRAC CS and HI-STAR 190 casks. The event is analyzed in Section 5.4 and Section 6.5, for structural and thermal considerations, respectively.

15.3.19.2 Building Collapse Analysis

Burial of casks under debris adversely affects ventilation cooling because debris will block the inflow of air. A thermal analysis is undertaken in Section 6.5 to compute steady state maximum cask temperatures and co-incident MPC pressures. The results are evaluated below.

i. Structural

The effect of burial under collapsed debris on the MPC is an increase in component and fuel cladding temperatures and internal pressure and thus an increase in pressure boundary stresses. The resultant temperatures and pressures obtained in Subsection 6.5.2 remain below accident limits. In addition, the HI-TRAC CS and HI-STAR 190 casks are structurally analyzed to evaluate the damage due to a potential building collapse in Section 5.4.

ii. Thermal

The fuel cladding and MPC integrity is evaluated in Section 6.5. The evaluation supports the conclusion that fuel cladding and confinement function of the MPC is not compromised.

iii. Shielding

HI-TRAC CS

The thermal results support the conclusion there is no material loss in the shielding capacity of the HI-TRAC CS cask.

HI-STAR 190

Limited reduction in shielding effectiveness is possible as Holtite neutron shield temperature limits are nominally exceeded. These effects are reasonably bounded by Holtite loss under the 10CFR Part 71 fire accident evaluated in HI-STAR 190 SAR [1.3.6].

iv. Criticality

Criticality control function is not affected under this event.

v. Confinement

Confinement function is not affected under this event.

vi. Radiation Protection and Consequences

As shielding and confinement functions as evaluated above are not affected, there is no radiological consequence. A negligible-to-minor increase to occupational exposures for the performance of corrective actions is expected.

15.3.19.3 Corrective Action

Analysis of building collapse accident shows that fuel, components and MPC pressures remain below accident limits. Under building collapse accident, operator shall remove the debris from around loaded casks in accordance with facility Emergency Response Plan [10.5.1]. Upon debris removal flow passages shall be visually inspected to verify air flow path is free of obstructions. The site's emergency action plan shall include provisions for the implementation of this corrective action.

15.3.19.4 Conclusion

Based on the above evaluation, it is concluded that the burial-under-debris accident event does not affect the safe operation of canister bearing casks in the CTB.

15.3.20 100% Rod Rupture Accident Coincident with Accident Events

The rupture of every fuel rod inside the Canister is postulated as a *non-mechanistic event* in NUREG -1536 [15.3.1]. In other words, simultaneous failure of all fuel rods in a Canister is a counter-factual event whose actuation mechanism cannot be articulated but it is nevertheless postulated to ascertain the robustness of the Confinement boundary. (A similar non-credible event requiring safety assessment in NUREG-1536 is the "non-mechanistic tip-over" of above-

ground storage casks). Because the rods are assumed to have failed *a' priori,* the 100% rod rupture event does not require satisfaction of a specific fuel cladding temperature limit. Rather, the acceptance criterion focuses on demonstrating the integrity of the Confinement Boundary. The integrity of the Canister's pressure boundary is satisfied if the internal pressure in the Canister remains below the Chapter 4 accident design pressure.

From a thermal perspective 100% percent rod rupture event is not adverse to heat transfer because internal convection heat transfer in the Canister is significantly boosted by the release of the plenum gases in the rods (due to their rupture), thus spatial temperature field in the Canister is moderated (reduced in magnitude).

Because the 100% rod rupture is a hypothetical postulate, the standard safety analysis practice as licensed in the Part 72 dockets (viz 72-1008, 72-1014, 72-1032, 72-1040) is to treat it as a stand-alone event, not to be combined with any accident such as fire near the HI-STORM UMAX ISFSI. The above position is supported by quote from the NRC Safety Evaluation Report as shown in the text highlighted below for emphasis:

HI-STORM 100 SER[4]:

"The HI-STORM 100 Cask System postulated accidents are described in Chapter 11 of the proposed FSAR and include:

1. HI-TRAC Transfer Cask Handling Accident
2. HI-STORM 100 Overpack Handling Accidents
3. Tip Over
4. Fire Accident
5. Partial Blockage of MPC Basket Vent Holes
6. Tornado
7. Flood
8. Earthquake
9. **100% Fuel Rod Rupture**
10. Confinement Boundary Leakage
11. Lightning
12. Explosion
13. 100% Blockage of Air Inlets
14. Burial Under Debris
15. Extreme Environmental Temperature
16. SCS Failure"

[4] "Final Safety Evaluation Report Docket No. 72-1014 Holtec International HI-STORM 100 Cask System Certificate of Compliance No. 1014 Amendment No. 5", pp. 11-2 & 11-3.

15.4 OTHER NON-SPECIFIED ACCIDENTS

This section addresses miscellaneous events, which are placed in the category of "other events" since they cannot be categorized as off-normal or accident events. The following "other events" are discussed in this chapter:

- Hazards during Construction Proximate to existing VVMs

This situation will arise if the facility owner decides to expand storage capacity by adding VVMs adjacent to operating VVMs. Evaluation of this event is incorporated by reference to HI-STORM UMAX FSAR Subsection 12.3.1 [1.0.6]. See Table 15.0.1. The results of the evaluations demonstrate that loaded HI-STORM UMAX VVMs can withstand the effects of "other events" without affecting safety function.

15.5 I&C SYSTEMS

The HI-STORM UMAX System does not rely on instruments or control systems for safety limits compliance under accident conditions.

15.6 REGULATORY COMPLIANCE

The accident compliance pursuant to the provisions of NUREG-1567 for deployment of canisters certified in the HI-STORM UMAX docket (#72-1040) has been demonstrated in this chapter.

As required by 10CFR72.124(a) the spent fuel sub-criticality is maintained under all design basis off-normal and accident events.

As required by 10CFR72.128(a)(3) confinement barrier integrity is maintained under all design basis off-normal and accident events.

As required by 10CFR72.122(l) spent fuel retrievability defined as the capability of returning stored radioactive material to a safe condition without endangering public health and safety is not compromised under all design basis off-normal and accident conditions.

As required by 10CFR72.106(b) regulations dose rates to individuals located at or beyond controlled area boundaries do not exceed specified accident limits under all design basis accidents.

In accordance with 10CFR72.122(i) and 72.128(a)(1) regulations instruments and control systems required to be operational under accident conditions are identified herein.

CHAPTER 16: TECHNICAL SPECIFICATIONS*

16.0 INTRODUCTION†

This chapter defines the operating controls and limits (i.e., Technical Specifications) including their supporting bases for deployment and storage of approved MPCs in a HI-STORM UMAX VVM at the HI-STORE CIS Facility ISFSI. The technical specifications define the conditions that are deemed necessary and sufficient for safe ISFSI use, and are in Appendix A to the HI-STORE CIS Facility license (No. SNM-1051) [16.0.2]. The technical specifications are required by 10CFR72.44(c) to include functional/operating limits, monitoring instruments, limiting control settings, limiting conditions, surveillance requirements, design features, and administrative controls. Technical specifications for a Part 72 storage facility, specifically the HI-STORE CIS Facility, shall be necessary to maintain subcriticality, confinement, shielding, heat removal, and structural integrity under normal, off-normal, and accident conditions. The technical specifications for the HI-STORE CIS Facility, contained herein, are supported by analyses. However, since the HI-STORE CIS Facility is designed for dry storage of MPCs loaded and shipped from a licensed 10CFR72 or 10CFR50 facility, and MPCs are not opened at the HI-STORE CIS Facility, technical specifications LCOs and their bases outside the scope of this SAR, but related to fuel loading and unloading of the MPC, including drying operations and criticality control and surface contamination surveys, shall be complied with prior to transport and storage at the HI-STORE CIS Facility in a HI-STORM UMAX System.

Table 16.0.1 contains material incorporated by reference from the HI-STORM UMAX FSAR and CoC that are applicable to the HI-STORE CIS Facility.

* All references are in placed within square brackets in this report and are compiled in Chapter 19 of this report.
† This chapter is based on the format and content of NUREG 1567 [1.0.3] and Regulatory Guide 3.50, Rev. 2 [1.0.2].

Table 16.0.1 : Material Incorporated by Reference in this chapter				
Information Incorporated by Reference	**Source of the Information**	**NRC Approval of Material Incorporated by Reference**	**Location in this SAR where Material is Incorporated**	**Technical Justification of Applicability to HI-STORM UMAX**
MPCs 37 and 89 Confinement Analysis	Section 7.0 of Reference [1.0.6]	HI-STORM UMAX SER Amendments 0, 1 and 2 of Reference [7.0.1, 7.0.2, 7.0.3]	Section 16.6 of this chapter	The canister was originally qualified for the HI-STORM FW and incorporated by reference into the HI-STORM UMAX FSAR and subsequently this HI-STORE SAR by reference. See Table 1.0.3 of this SAR.
MPC Design Codes and Standards (including alternatives)	HI-STORM UMAX CoC, Appendix B (Section 3.3), Amendment 0,1 and 2, Reference [16.0.1]	HI-STORM UMAX SER Amendments 0, 1 and 2, Reference [7.0.1, 7.0.2, 7.0.3]	Section 16.4 of this chapter	MPC deign codes and standards (including alternatives) approved by NRC in the generic CoC (No. 1040) for the HI-STORM UMAX System are unchanged in this application and therefore are applicable during deployment of the HI-STORM UMAX System at the HI-STORE CIS facility.

16.1 FUNCTIONAL/OPERATING LIMITS, MONITORING INSTRUMENTS, AND LIMITING CONTROL SETTINGS

This section provides a discussion of the operating controls and limits, monitoring instruments, and limiting control settings for the HI-STORM UMAX system to assure long-term performance consistent with the conditions analyzed in this SAR.

Functional and operating limits, monitoring instruments, and limiting control settings include limits placed on fuel, waste handling, and storage conditions to protect the integrity of the fuel and MPC, to maintain radiation workers exposure to radiation at the storage facility ALARA, and to guard against the uncontrolled release of radioactive materials.

As discussed in Section 16.0, loading and unloading of MPC contents occurs at a 10CFR72 license facility or a Part 50 license facility, in accordance with QA'd program procedures, prior to shipment to the HI-STORE CIS Facility. Therefore fuel loadings are verified and records maintained. Waste handling (fuel loading and MPC handling) at the site of origin is performed by individuals appropriately trained and qualified. Upon arrival at the HI-STORE CIS Facility, MPC handling shall be performed by personnel trained under the HI-STORE CIS Facility QA program. The controls and limits apply to operating parameters and conditions which are observable, detectable, and/or measurable. The HI-STORM UMAX system is completely passive during storage and requires no monitoring instruments. A temperature monitoring system or visual inspection of the vent screens to verify operability of the VVM heat removal system may be employed in accordance with Technical Specification Limiting Condition for Operation (LCO) 3.1.1 (Appendix 16.A) .

16.2 LIMITING CONDITIONS

Limiting Conditions for Operation (LCO) specify the minimum capability or level of performance that is required to assure that the HI-STORM UMAX system at the HI-STORE CIS can fulfill its safety functions. Limiting Conditions are supported by analyses in this SAR (Chapters 5 – 9) and provided in Appendix A of the proposed license (No. SNM-1051 Rev. 0), and their bases are contained herein Appendix 16.A to this chapter.

16.3 SURVEILLANCE REQUIREMENTS

The analyses in this SAR show that the HI-STORE CIS Facility fulfills its safety functions, provided that the Technical Specifications in Appendix A of the proposed license (No. SNM-1051 Rev. 0) are met. Surveillance requirements during storage operations at the HI-STORE CIS Facility are provided in the Technical Specifications. Surveillance is required to ensure LCOs are not violated.

16.4 DESIGN FEATURES

This subsection describes design features at the HI-STORE CIS Facility that are Important to Safety. These features require design controls and fabrication controls. The design features, detailed in this SAR and in Section 4.0 of Appendix A to the Proposed HI-STORE CIS Facility license (No. SNM-1051), are established in specifications and drawings which are controlled through the quality assurance program. Fabrication controls and inspections are in place to ensure that the HI-STORE CIS Facility and important to safety systems are fabricated or constructed in accordance with the licensing drawings in Section 1.5.

The HI-STORE and HI-STORM UMAX system and its components, as appropriate, have been analyzed for specified normal, off-normal, and accident conditions, including extreme environmental conditions. Analysis has shown that no credible condition or event prevents the important to safety systems at from performing their function. As a result, there is no threat to public health and safety from any postulated accident condition or analyzed event. When all equipment are tested and placed into service in accordance with procedures developed for the ISFSI, no failure of the system to perform its safety function is expected to occur.

Design codes and standards for the MPC, including alternatives, are incorporated by reference in Section 3.3 of the NRC issued HI-STORM UMAX CoC No. 1040 Amendments 0, 1 and 2 . Criticality control features of the MPC are referenced from Section 3.2 of the HI-STORM UMAX CoC No. 1040 Amendments 0, 1 and 2. Design codes and standards, and criticality control features are incorporated by reference into this chapter in accordance with Table 16.0.1.

Criteria and analyses (as applicable) for design features, including important to safety components of drawings in Section 1.5 and ancillaries in Subsection 1.2.7, are provided in Chapters 4 – 9 of this SAR.

16.5 ADMINISTRATIVE CONTROLS

Administrative control is established through the development of organizational and management procedures, recordkeeping, review and audit systems, and reporting necessary to ensure that the HI-STORE CIS Facility is managed in a safe and reliable manner. Administrative action, in accordance with written procedures, shall be taken in the event of non-compliance.

Administrative controls for the HI-STORE CIS Facility in Appendix A to proposed HI-STORE license No. SNM-1051 Rev. 0 is in alignment with Conduct of Operations in Chapter 10 of this Safety Analysis Report.

16.6 REGULATORY COMPLIANCE

This chapter ensures regulatory compliance with 10CFR72.24, 72.26 and 72.44(a)(c) and (d).

10CFR72.24(g) requires identification and justification for the selection of those subjects that will be probable license conditions and technical specifications

10CFR72.26 requires that each application under this part include proposed technical specifications.

10CFR72.44(a) requires that each license includes license conditions

10CFR72.44(c) requires that each license includes technical specifications that must include requirements in the following categories:

1. Functional and operating limits and monitoring instruments and limiting control settings.
2. Limiting conditions.
3. Surveillance requirements.
4. Design features
5. Administrative Controls

10CFR72.44(d) states that each license must include an annual report that specifies the quantity of each of the principal radionuclides released to the environment.

This chapter discusses the technical specifications and LCO bases as applicable for the HI-STORE CIS Facility or incorporated by reference. The Technical Specifications are license conditions. Therefore, compliance with 10CFR72.44(c) is by extension compliance with 10CFR72.24(g) and 10CFR72.26. Technical specifications noted in 10CFR72.44(a) and (c) are discussed in this chapter. 10CFR72.44(d) requirement for an annual report that specifies the quantity of each of the principal radionuclides released to the environment is not discussed in the chapter and not required for the HI-STORE CIS Facility. Analysis (Table 16.0.1) of the MPCs confirms it remains intact and welds are not breached under normal, off-normal and accident conditions. Since the MPC meets the ANSI N14.5 leaktight criteria (Subsection 10.3.3), release of effluents from MPCs are on an order of magnitude to be considered negligible and with no impact on public health and safety.

HI-STORE CIS Facility SAR

APPENDIX 16.A

TECHNICAL SPECIFICATION (LCOs) BASES

FOR THE HOLTEC HI-STORE CIS Facility

BASES TABLE OF CONTENTS

B 3.0 LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY 16.A-3
B 3.0 SURVEILLANCE REQUIREMENT (SR) APPLICABILITY 16.A-6

B 3.1 SFSC INTEGRITY 16.A-11
B 3.1.2 SFSC Heat Removal System 16.A-11

B 3.0 LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY

BASES

LCOs	LCO 3.0.1, 3.0.2, 3.0.4, and 3.0.5 establish the general requirements applicable to all Specifications and apply at all times, unless otherwise stated.
LCO 3.0.1	LCO 3.0.1 establishes the Applicability statement within each individual Specification as the requirement for when the LCO is required to be met (i.e., when the facility is in the specified conditions of the Applicability statement of each Specification).
LCO 3.0.2	LCO 3.0.2 establishes that upon discovery of a failure to meet an LCO, the associated ACTIONS shall be met. The Completion Time of each Required Action for an ACTIONS Condition is applicable from the point in time that an ACTIONS Condition is entered. The Required Actions establish those remedial measures that must be taken within specified Completion Times when the requirements of an LCO are not met. This Specification establishes that: a. Completion of the Required Actions within the specified Completion Times constitutes compliance with a Specification; and b. Completion of the Required Actions is not required when an LCO is met within the specified Completion Time, unless otherwise specified. There are two basic types of Required Actions. The first type of Required Action specifies a time limit in which the LCO must be met. This time limit is the Completion Time to restore a system or component or to restore variables to within specified limits. Whether stated as a Required Action or not, correction of the entered Condition is an action that may always be considered upon entering ACTIONS. The second type of Required Action specifies the remedial measures that permit continued operation that is not further restricted by the Completion Time. In this case, compliance with the Required Actions provides an acceptable level of safety for continued operation.

(continued)

BASES

LCO 3.0.2 (continued)	Completing the Required Actions is not required when an LCO is met or is no longer applicable, unless otherwise stated in the individual Specifications. The Completion Times of the Required Actions are also applicable when a system or component is removed from service intentionally. The reasons for intentionally relying on the ACTIONS include, but are not limited to, performance of Surveillances, preventive maintenance, corrective maintenance, or investigation of operational problems. Entering ACTIONS for these reasons must be done in a manner that does not compromise safety. Intentional entry into ACTIONS should not be made for operational convenience.
LCO 3.0.3	This specification is not applicable to a dry storage cask system because it describes conditions under which a power reactor must be shut down when an LCO is not met and an associated ACTION is not met or provided. The placeholder is retained for consistency with the power reactor technical specifications.
LCO 3.0.4	LCO 3.0.4 establishes limitations on changes in specified conditions in the Applicability when an LCO is not met. It precludes placing the HI-STORM UMAX System in a specified condition stated in that Applicability (e.g., Applicability desired to be entered) when the following exist: a. Facility conditions are such that the requirements of the LCO would not be met in the Applicability desired to be entered; and b. Continued noncompliance with the LCO requirements, if the Applicability were entered, would result in being required to exit the Applicability desired to be entered to comply with the Required Actions. Compliance with Required Actions that permit continuing with dry fuel storage activities for an unlimited period of time in a specified condition provides an acceptable level of safety for continued operation. This is without regard to the status of the dry storage system. Therefore, in such cases, entry into a specified condition in the Applicability may be made in accordance with the provisions of the Required Actions. The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components before entering an associated specified condition in the Applicability.

(continued)

BASES	
LCO 3.0.4 (continued)	The provisions of LCO 3.0.4 shall not prevent changes in specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of LCO 3.0.4 shall not prevent changes in specified conditions in the Applicability that are related to the unloading of an SFSC. Exceptions to LCO 3.0.4 are stated in the individual Specifications. Exceptions may apply to all the ACTIONS or to a specific Required Action of a Specification.
LCO 3.0.5	LCO 3.0.5 establishes the allowance for restoring equipment to service under administrative controls when it has been removed from service or determined to not meet the LCO to comply with the ACTIONS. The sole purpose of this Specification is to provide an exception to LCO 3.0.2 (e.g., to not comply with the applicable Required Action(s)) to allow the performance of testing to demonstrate: The equipment being returned to service meets the LCO; or Other equipment meets the applicable LCOs. The administrative controls ensure the time the equipment is returned to service in conflict with the requirements of the ACTIONS is limited to the time absolutely necessary to perform the allowed testing. This Specification does not provide time to perform any other preventive or corrective maintenance.

B 3.0 SURVEILLANCE REQUIREMENT (SR) APPLICABILITY

BASES

SRs	SR 3.0.1 through SR 3.0.4 establish the general requirements applicable to all Specifications and apply at all times, unless otherwise stated.
SR 3.0.1	SR 3.0.1 establishes the requirement that SRs must be met during the specified conditions in the Applicability for which the requirements of the LCO apply, unless otherwise specified in the individual SRs. This Specification is to ensure that Surveillances are performed to verify that systems and components meet the LCO and variables are within specified limits. Failure to meet a Surveillance within the specified Frequency, in accordance with SR 3.0.2, constitutes a failure to meet an LCO. Systems and components are assumed to meet the LCO when the associated SRs have been met. Nothing in this Specification, however, is to be construed as implying that systems or components meet the associated LCO when: a. The systems or components are known to not meet the LCO, although still meeting the SRs; or b. The requirements of the Surveillance(s) are known to be not met between required Surveillance performances. Surveillances do not have to be performed when the HI-STORM UMAX System is in a specified condition for which the requirements of the associated LCO are not applicable, unless otherwise specified. Surveillances, including Surveillances invoked by Required Actions, do not have to be performed on equipment that has been determined to not meet the LCO because the ACTIONS define the remedial measures that apply. Surveillances have to be met and performed in accordance with SR 3.0.2, prior to returning equipment to service. Upon completion of maintenance, appropriate post-maintenance testing is required. This includes ensuring applicable Surveillances are not failed and their most recent performance is in accordance with SR 3.0.2. Post maintenance testing may not be possible in the current specified conditions in the Applicability due to the necessary dry storage cask system parameters not having been established. In these situations, the equipment may be considered to meet the LCO provided testing has been satisfactorily completed to the extent possible and the equipment is not otherwise believed to be incapable of performing its function. This will allow dry fuel storage activities to proceed to a specified condition where other necessary post maintenance tests can be completed.

(continued)

BASES

SR 3.0.2

SR 3.0.2 establishes the requirements for meeting the specified Frequency for Surveillances and any Required Action with a Completion Time that requires the periodic performance of the Required Action on a "once per..." interval.

SR 3.0.2 permits a 25% extension of the interval specified in the Frequency. This extension facilitates Surveillance scheduling and considers facility conditions that may not be suitable for conducting the Surveillance (e.g., transient conditions or other ongoing Surveillance or maintenance activities).

The 25% extension does not significantly degrade the reliability that results from performing the Surveillance at its specified Frequency. This is based on the recognition that the most probable result of any particular Surveillance being performed is the verification of conformance with the SRs. The exceptions to SR 3.0.2 are those Surveillances for which the 25% extension of the interval specified in the Frequency does not apply. These exceptions are stated in the individual Specifications as a Note in the Frequency stating, "SR 3.0.2 is not applicable."

As stated in SR 3.0.2, the 25% extension also does not apply to the initial portion of a periodic Completion Time that requires performance on a "once per..." basis. The 25% extension applies to each performance after the initial performance. The initial performance of the Required Action, whether it is a particular Surveillance or some other remedial action, is considered a single action with a single Completion Time. One reason for not allowing the 25% extension to this Completion Time is that such an action usually verifies that no loss of function has occurred by checking the status of redundant or diverse components or accomplishes the function of the affected equipment in an alternative manner.

The provisions of SR 3.0.2 are not intended to be used repeatedly merely as an operational convenience to extend Surveillance intervals or periodic Completion Time intervals beyond those specified.

(continued)

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

BASES

SR 3.0.3

SR 3.0.3 establishes the flexibility to defer declaring affected equipment as not meeting the LCO or an affected variable outside the specified limits when a Surveillance has not been completed within the specified Frequency. A delay period of up to 24 hours or up to the limit of the specified Frequency, whichever is less, applies from the point in time that it is discovered that the Surveillance has not been performed in accordance with SR 3.0.2, and not at the time that the specified Frequency was not met.

This delay period provides adequate time to complete Surveillances that have been missed. This delay period permits the completion of a Surveillance before complying with Required Actions or other remedial measures that might preclude completion of the Surveillance.

The basis for this delay period includes consideration of HI-STORM UMAX System conditions, adequate planning, availability of personnel, the time required to perform the Surveillance, the safety significance of the delay in completing the required Surveillance, and the recognition that the most probable result of any particular Surveillance being performed is the verification of conformance with the requirements. When a Surveillance with a Frequency based not on time intervals, but upon specified facility conditions, is discovered not to have been performed when specified, SR 3.0.3 allows the full delay period of 24 hours to perform the Surveillance.

SR 3.0.3 also provides a time limit for completion of Surveillances that become applicable as a consequence of changes in the specified conditions in the Applicability imposed by the Required Actions.

Failure to comply with specified Frequencies for SRs is expected to be an infrequent occurrence. Use of the delay period established by SR 3.0.3 is a flexibility which is not intended to be used as an operational convenience to extend Surveillance intervals.

(continued)

BASES

SR 3.0.3 (continued)	If a Surveillance is not completed within the allowed delay period, then the equipment is considered to not meet the LCO or the variable is considered outside the specified limits and the Completion Times of the Required Actions for the applicable LCO Conditions begin immediately upon expiration of the delay period. If a Surveillance is failed within the delay period, then the equipment does not meet the LCO, or the variable is outside the specified limits and the Completion Times of the Required Actions for the applicable LCO Conditions begin immediately upon the failure of the Surveillance. Completion of the Surveillance within the delay period allowed by this Specification, or within the Completion Time of the ACTIONS, restores compliance with SR 3.0.1.
SR 3.0.4	SR 3.0.4 establishes the requirement that all applicable SRs must be met before entry into a specified condition in the Applicability. This Specification ensures that system and component requirements and variable limits are met before entry into specified conditions in the Applicability for which these systems and components ensure safe conduct of dry fuel storage activities. The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components before entering an associated specified condition in the Applicability. However, in certain circumstances, failing to meet an SR will not result in SR 3.0.4 restricting a change in specified condition. When a system, subsystem, division, component, device, or variable is outside its specified limits, the associated SR(s) are not required to be performed per SR 3.0.1, which states that Surveillances do not have to be performed on equipment that has been determined to not meet the LCO. When equipment does not meet the LCO, SR 3.0.4 does not apply to the associated SR(s) since the requirement for the SR(s) to be performed is removed. Therefore, failing to perform the Surveillance(s) within the specified Frequency does not result in an SR 3.0.4 restriction to changing specified conditions of the Applicability. However, since the LCO is not met in this instance, LCO 3.0.4 will govern any restrictions that may (or may not) apply to specified condition changes.

(continued)

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

BASES

SR 3.0.4 (continued)

The provisions of SR 3.0.4 shall not prevent changes in specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of LCO 3.0.4 shall not prevent changes in specified conditions in the Applicability that are related to the unloading of an SFSC.

The precise requirements for performance of SRs are specified such that exceptions to SR 3.0.4 are not necessary. The specific time frames and conditions necessary for meeting the SRs are specified in the Frequency, in the Surveillance, or both. This allows performance of Surveillances when the prerequisite condition(s) specified in a Surveillance procedure require entry into the specified condition in the Applicability of the associated LCO prior to the performance or completion of a Surveillance. A Surveillance that could not be performed until after entering the LCO Applicability would have its Frequency specified such that it is not "due" until the specific conditions needed are met. Alternately, the Surveillance may be stated in the form of a Note as not required (to be met or performed) until a particular event, condition, or time has been reached. Further discussion of the specific formats of SRs' annotation is found in Section 1.4, Frequency.

HOLTEC INTERNATIONAL COPYRIGHTED MATERIAL

B 3.1 SFSC Integrity

B 3.1.1 SFSC Heat Removal System

BASES	
BACKGROUND	The SFSC Heat Removal System is a passive, air-cooled, convective heat transfer system that ensures heat from the MPC canister is transferred to the environs by the chimney effect. Air is drawn into the inlet ducts and travels down the space between the Cavity Enclosure Container (CEC) and the Divider Shell, through the cut-outs at the bottom of the Divider Shell, up the space between the Divider Shell and the MPC, and out through the outlet duct. The MPC transfers its heat from its surface to the air via natural convection. The buoyancy created by the heating of the air creates a chimney effect.
APPLICABLE SAFETY ANALYSIS	The thermal analyses of the SFSC take credit for the decay heat from the spent fuel assemblies being ultimately transferred to the ambient environment surrounding the VVM. Transfer of heat away from the fuel assemblies ensures that the fuel cladding and other SFSC component temperatures do not exceed applicable limits. Under normal storage conditions, the inlet and outlet duct screens are unobstructed and full air flow occurs. Analyses have been performed for half and complete obstruction of the inlet duct screens. Blockage of half of the inlet ducts reduces air flow through the VVM and decreases heat transfer from the MPC. Under this off-normal condition, no SFSC components exceed the short term temperature limits. The complete blockage of all inlet air ducts stops normal air cooling of the MPC. The MPC will continue to radiate heat to the relatively cooler subgrade. With the loss of normal air cooling, the SFSC component temperatures will increase toward their respective short-term temperature limits. None of the components reach their temperature limits over the duration of the analyzed event.
	(continued)

BASES	
LCO	The SFSC Heat Removal System must be verified to be operable to preserve the assumptions of the thermal analyses. Operability is defined as 50% or more of the inlet vent duct areas are unblocked and available for flow. Operability of the heat removal system ensures that the decay heat generated by the stored fuel assemblies is transferred to the environs at a sufficient rate to maintain fuel cladding and other SFSC component temperatures within design limits. The intent of this LCO is to address those occurrences of air duct screen blockage that can be reasonably anticipated to occur from time to time at the ISFSI (i.e., Design Event I and II class events per ANSI/ANS-57.9). These events are of the type where corrective actions can usually be accomplished within one 8-hour operating shift to restore the heat removal system to operable status (e.g., removal of loose debris). This LCO is not intended to address low frequency, unexpected Design Event III and IV class events (ANSI/ANS-57.9) such as design basis accidents and extreme environmental phenomena that could potentially block one or more of the air ducts for an extended period of time (i.e., longer than the total Completion Time of the LCO). This class of events is addressed site-specifically as required by Section 4.2.4 of Appendix A to the license (SNM-1051).
APPLICABILITY	The LCO is applicable during STORAGE OPERATIONS. Once a VVM containing an MPC loaded with spent fuel has been placed in storage, the heat removal system must be operable to ensure adequate dissipation of the decay heat from the fuel assemblies.
ACTIONS	A note has been added to the ACTIONS which states that, for this LCO, separate Condition entry is allowed for each SFSC. This is acceptable since the Required Actions for each Condition provide appropriate compensatory measures for each SFSC not meeting the LCO. Subsequent SFSCs that don't meet the LCO are governed by subsequent Condition entry and application of associated Required Actions.
	(continued)

BASES

ACTIONS (continued)

A.1

Although the heat removal system remains operable, the blockage should be cleared expeditiously.

B.1

If the heat removal system has been determined to be inoperable, it must be restored to operable status within eight hours. Eight hours is a reasonable period of time to take action to remove the obstructions in the air flow path.

C.1

If the heat removal system cannot be restored to operable status within eight hours, the VVM and the fuel may experience elevated temperatures. Therefore, dose rates are required to be measured to verify the effectiveness of the radiation shielding provided by the concrete. This Action must be performed immediately and repeated every twelve hours thereafter to provide timely and continued evaluation of the effectiveness of the concrete shielding. As necessary, the system user shall provide additional radiation protection measures such as temporary shielding. The Completion Time is reasonable considering the expected slow rate of deterioration, if any, of the concrete under elevated temperatures.

C.2.1

In addition to Required Action C.1, efforts must continue to restore cooling to the SFSC. Efforts must continue to restore the heat removal system to operable status by removing the air flow obstruction(s) unless optional Required Action C.2.2 is being implemented.

This Required Action must be complete in 24 hours. The Completion Time is consistent with the thermal analyses of this event, which show that all component temperatures remain below their short-term temperature limits up to 32 hours after event initiation.

(continued)

BASES	
ACTIONS (continued)	C.2.1 (continued) The Completion Time reflects the 8 hours to complete Required Action B.1 and the appropriate balance of time consistent with the applicable analysis results. The event is assumed to begin at the time the SFSC heat removal system is declared inoperable. This is reasonable considering the low probability of all inlet ducts becoming simultaneously blocked. C.2.2 In lieu of implementing Required Action C.2.1, transfer of the MPC into a TRANSFER CASK will place the MPC in an analyzed condition and ensure adequate fuel cooling until actions to correct the heat removal system inoperability can be completed. Transfer of the MPC into a TRANSFER CASK removes the SFSC from the LCO Applicability since STORAGE OPERATIONS does not include times when the MPC resides in the TRANSFER CASK. An engineering evaluation must be performed to determine if any deterioration which prevents the VVM from performing its design function. If the evaluation is successful and the air inlet duct screens have been cleared, the VVM heat removal system may be considered operable and the MPC transferred back into the VVM. Compliance with LCO 3.1.1 is then restored. If the evaluation is unsuccessful, the user must transfer the MPC into a different, fully qualified VVM to resume STORAGE OPERATIONS and restore compliance with LCO 3.1.1 In lieu of performing the engineering evaluation, the user may opt to proceed directly to transferring the MPC into a different, fully qualified VVM. The Completion Time of 24 hours reflects the Completion Time from Required Action C.2.1 to ensure component temperatures remain below their short-term temperature limits for the respective decay heat loads.
	(continued)

BASES	
SURVEILLANCE REQUIREMENTS	SR 3.1.2 The long-term integrity of the stored fuel is dependent on the ability of the SFSC to reject heat from the MPC to the environment. There are two options for implementing SR 3.1.1, either of which is acceptable for demonstrating that the heat removal system is OPERABLE. Visual observation that all air inlet duct screens are unobstructed ensures that the SFSC is operable. If greater than 50% of the air inlet duct screens are blocked the heat removal system is inoperable and this LCO is not met. While 50% or less blockage of the total air inlet duct screen area does not constitute inoperability of the heat removal system, corrective actions should be taken promptly to remove the obstruction and restore full flow. Visual observation of air outlet duct screen blockage does not constitute inoperability of the heat removal system; however, corrective action should be taken to promptly remove the obstruction. As an alternative, for VVMs with air temperature monitoring instrumentation installed in the air outlets, the temperature difference between the outlet air and the ambient air may be monitored to verify operability of the heat removal system. Blocked air inlet duct screens will reduce air flow and increase the outlet duct air temperature. Based on the analyses, if the temperature difference between the ambient air and the outlet duct air meets the criteria in the LCO, adequate air flow is occurring to provide assurance of long term fuel cladding integrity. The reference ambient temperature used to perform this Surveillance shall be measured at the ISFSI facility. The Frequency of 24 hours is reasonable based on the time necessary for SFSC components to heat up to unacceptable temperatures assuming design basis heat loads, and allowing for corrective actions to take place upon discovery of blockage of air ducts.
REFERENCES	1. SAR Chapter 6 2. ANSI/ANS 57.9-1992

CHAPTER 17: MATERIAL EVALUATION

17.0 INTRODUCTION

This chapter presents an assessment of the materials selected for use in the HI-STORM UMAX system [1.0.6] components that are envisaged to be deployed at the HI-STORE CIS facility. The assessment of the materials selected for use in the MPCs is provided in the previously licensed HI-STORM FW system FSAR [1.3.7]. The fuel loading, dewatering, drying and welding of the canister occur at the nuclear plant site, the material selection decisions for the canister are comprehensively covered in [1.3.7]. The canisters will arrive at the HI-STORE site in *ready-to-store* condition; no material selection decision vis-à-vis the canisters will be made at the HI-STORE site. Because the environmental conditions and design criteria for the MPCs for use at HI-STORE are completely bounded by those in the HI-STORM FW (and HI-STORM UMAX) dockets, reference is made to the material selection considerations for the MPCs (canisters) in their native docket (HI-STORM FW FSAR). The information on the suitability of the MPC for the local environmental conditions at HI-STORE CIS, however, underpins the Aging Management program presented in Chapter 18.

The HI-STORM UMAX components must withstand the environmental conditions experienced during normal operation, off-normal conditions, and accident conditions for the entire service life of the interim storage facility (please see Table 17.0.1).

Chapter 1 provides a general description of the HI-STORM UMAX System including information on materials of construction. The ITS categories of the principal materials of construction in the HI-STORM UMAX VVM and ISFSI system are identified in the drawing package provided in Section 1.5.

Nevertheless, for completeness, it is necessary that the material considerations applicable to HI-STORM UMAX be independently evaluated for compliance with the ISG-15 [17.0.1] which contains the latest NRC position in this matter. The principal purpose of ISG-15 is to evaluate the dry cask storage system to ensure adequate material performance of components deemed to be important-to-safety at an independent spent fuel storage installation (ISFSI) under normal, off-normal, and accident conditions.

ISG-15 sets down the following general acceptance criteria for material evaluation:

- The safety analysis report should describe all materials used for dry spent fuel storage components important-to-safety, and should consider the suitability of those materials for their intended functions in sufficient detail to evaluate their effectiveness in relation to all safety functions.
- The dry spent fuel storage system should employ materials that are compatible with wet and dry spent fuel loading and unloading operations and facilities. These materials should not degrade to the extent that a safety concern is created.

* All references are in placed within square brackets in this report and are compiled in Chapter 19 of this report.

The information compiled in this chapter seeks to address the above acceptance criteria in full measure for the HI-STORM UMAX VVM and ISFSI. To perform the material suitability evaluation, it is necessary to characterize the following for each component: (i) the applicable environment, (ii) potential degradation modes and (iii) potential hazards to continued effectiveness of the selected material.

The material evaluation presented in this chapter is intended to be complete, even though *a' priori* conclusion of the adequacy of the materials can be made on the basis of the following facts:

i. The materials used in HI-STORM UMAX VVM are identical to those used in the widely deployed HI-STORM 100 System (Docket No. 72-1014) [1.3.3] including its underground VVM denoted as HI-STORM 100U and the HI-STORM FW system (Docket No. 72-1032) [1.3.7].

ii. As can be ascertained from Table 2.7.1, the thermal environment in the HI-STORM UMAX system at the HI-STORE site is bounded by the design basis for its generic certification in the HI-STORM UMAX docket [1.0.6].

In this chapter , the significant mechanical, thermal, radiological, and metallurgical properties of materials identified for use in the components of the HI-STORM UMAX System and ISFSI are presented. The material evaluation effort is directed towards the interim storage at HI-STORE CS for its intended service life and its consequences to the system's continued safety. Table 17.0.1 provides the expected licensing, design and service life data for the HI-STORE CIS facility.

Because the materials designated to be used at the HI-STORE CIS facility have a long pedigree of usage in other HI-STORM dockets, their mechanical and thermos-physical properties are well documented in the prior FSARs approved by the NRC. The identification of such sections/appendices/tables that are adopted by reference herein is summarized in Table 17.0.2.

Table 17.0.1; Target License, Design and Service Life of the HI-STORE CIS Facility		
Item	**Definition**	**Value in Years**
License Life	The period for which the NRC is expected to grant the initial license	40
Design Life	A conservative estimate of the useable life of the system in full compliance with the regulations and ALARA expectations	80
Service Life	The expected life of the facility for which it will continued to meet all safety requirements if the aging management program described in this SAR is implemented without limitation	120

Table 17.0.2:Material Incorporated By Reference

Information Incorporated by Reference	Source of the Information	NRC Approval of Material Incorporated by Reference	Location in this SAR where Material is Incorporated	Technical Justification of Applicability to HI-STORE
Mechanical Properties of materials	Section 3.3 of [1.0.6]	SER HI-STORM UMAX Amendments 0, 1, and 2 References [7.0.1, 7.0.2,7.0.3]	Subsection 17.4.1	The materials used in the canisters and components at the HI-STORE CIS Facility are identical to those used in the HI-STORM UMAX Generic License FSAR.
Summary of Thermal Properties of materials	Section 4.2 of [1.0.6]	SER HI-STORM UMAX Amendments 0, 1, and 2 References [7.0.1, 7.0.2,7.0.3]	Subsection 17.4.2	The materials used in the canisters and components at the HI-STORE CIS Facility are identical to those used in the HI-STORM UMAX Generic License FSAR.
Alloy X Description	Appendix 1.A of [1.3.7]	SER HI-STORM FW Amendments 0, 1, and 2 References [8.0.1, 8.0.2,8.0.3]	Sub-section 17.4.3	The materials used in the canisters and components at the HI-STORE CIS Facility are identical to those used in the HI-STORM UMAX Generic License FSAR.
MPC Material Selection Information	Section 8.2 of [1.3.7]	SER HI-STORM FW Amendments 0, 1, and 2 References [8.0.1, 8.0.2, 8.0.3]	Section 17.2	The MPCs are identical to those loaded under the HI-STORM UMAX and FW generic licenses, and therefore the same material selection criteria apply.
Metamic-HT	Paragraph 1.2.1.4 of [1.3.7]	SER HI-STORM FW Amendments 0, 1, and 2 References [8.0.1, 8.0.2, 8.0.3]	Section 17.9	The materials used in the canisters and components at the HI-STORE CIS Facility are identical to those used in the HI-STORM UMAX Generic License FSAR.
Fuel Integrity Evaluation	Section 8.13 of [1.3.7]	SER HI-STORM FW Amendments 0, 1, and 2 References [8.0.1, 8.0.2, 8.0.3]	Section 17.12	The fuel remains in seal welded canisters, with lower temperatures and pressures than originally licensed, therefore the fuel integrity evaluation is still applicable.

Table 17.0.2:Material Incorporated By Reference				
Information Incorporated by Reference	**Source of the Information**	**NRC Approval of Material Incorporated by Reference**	**Location in this SAR where Material is Incorporated**	**Technical Justification of Applicability to HI-STORE**
Examination and Testing	Section 8.13 of [1.0.6],	SER HI-STORM UMAX Amendments 0, 1, and 2 References [7.0.1, 7.0.2, 7.0.3]	Section 17.12	The canisters to be stored at the HI-STORE facility must fully meet the fabrication examination and testing requirements that are in the HI-STORM UMAX FSAR.

17.1 MATERIAL DEGRADATION MODES

Tables 17.1.1 and 17.1.2 provide a summary of the environmental states, potential degradation modes, and hazards applicable to the HI-STORM UMAX modules. Table 17.1.3 provides the listing of material types that are important to safety and are subject to the ambient environmental of the HI-STORE Facility.

To provide a proper context for the subsequent evaluations, the potential degradation mechanisms applicable to the ventilated systems are summarized in Table 17.1.4. The degradation mechanisms listed in Table 17.1.4 are considered in the suitability evaluation presented in this chapter.

Table 17.1.1: Considerations Germane to Performance of Materials used in the MPCs in Long Term Storage in HI-STORM UMAX	
Consideration	**Environment**
Environment	MPC's internal environment is hot (≤ 752°F), inertized and dry. Temperature of the MPC internals cycles vary gradually due to changes in the environmental temperature.
Potential degradation modes	Corrosion of the external surfaces of the MPC (stress, corrosion, cracking, pitting, etc.).
Potential hazards to effective performance	Blockage of ventilation ducts under an extreme environmental phenomenon leading to a rapid heat-up of the MPC internals.

Table 17.1.2: Considerations Germane to the HI-STORM UMAX VVM Material Performance	
Consideration	**Performance Data**
Environment	Cool ambient air is progressively (but marginally) heated as it flows up the annulus between the Divider Shell and the MPC heating the inside surface of the cask and cooling the outside surface of the MPC. The heated air has reduced relative humidity the warmer it gets. As a result, the bottom external surface of the Closure Lid is heated and the top external surfaces are in contact with ambient air, rain, and snow, as applicable. The exterior surfaces of the CEC are in contact with either engineered fill or concrete (concrete encasement or “free-flow “concrete).
Potential degradation modes	Peeling or perforation of surface preservatives on steel surfaces and corrosion of exposed steel surfaces.
Potential hazards to effective performance	Blockage of ducts by debris leading to overheating of the concrete in the ISFSI pad, scorching of the cask by proximate fire, lightning.

Table 17.1.3:* Material Types in the HI-STORM UMAX System Components Exposed to the Long-Term Ambient Environment		
	Material Type	**Components and Their Surfaces Exposed to Ambient Environment**
1.	Low carbon steel	• All surfaces of the closure lid • Internal surfaces of the CEC (expose to air) • External surfaces of the CEC (exposed to CLSM) or subgrade • Internal and External surfaces of the Divider shell
2.	Shielding concrete	• The outside surface of the ISFSI pad
3.	Alloy X Austenitic Stainless Steel (Defined in Appendix 1A of the HI-STORM 100 FSAR [1.3.3] and used in all HI-STORM dockets.	• External surfaces of the stored MPC • MPC Guides and MPC support surfaces inside the CEC. • Surfaces of the closure lid • Internal surfaces of the CEC • External surfaces of the CEC Internal External surfaces of the Divider shell (optional per Section 1.5)
4.	Elastomeric Gasket	• Closure Lid Seal • Divider Shell Seal

* Specific material grades used at the HI-STORE ISFSI will comply with the requirements set forth in Subsection 8.2.3 of [1.3.7] which provides the conditions to establish material equivalence.

Table 17.1.4: Failure and Degradation Mechanisms*				
	Mechanism	**Area of Performance Affected**	**Vulnerable Parts**	**Location of Discussion**
1.	General Corrosion	Structural Integrity	All carbon steel parts	Section 18.3
2.	Stress Corrosion Cracking	Structural Integrity	Austenitic Stainless Steel	Section 18.3
3.	Galling	Equipment handling and deployment	Threaded Fasteners	Section 17.6
4.	Fatigue	Structural Integrity	Fuel Cladding & Bolting	Section 18.3
5.	Brittle Fracture	Structural Integrity	Thick Steel Parts	Section 17.4.3
6.	Boron Depletion	Criticality Control	Neutron Absorber	Section 18.3

* This table lists all potential (generic) mechanisms, whether they are credible for the HI-STORM UMAX System or not. The viability of each failure mechanism is discussed later in this chapter and/or chapter 18.

17.2 MATERIAL SELECTION

The acceptance criteria for the materials subject to long-term storage conditions in HI-STORM UMAX are extracted from ISG-15 [17.0.1] as follows:

a. The material properties of a dry spent fuel storage component should meet its service requirements in the proposed cask system for the duration of the licensing period.

b. The materials that comprise the dry spent fuel storage should maintain their physical and mechanical properties during all conditions of operations. The spent fuel should be readily retrievable without posing operational safety problems.

c. Over the range of temperatures expected prior to and during the storage period, any ductile-to-brittle transition of the dry spent fuel storage materials, used for structural and nonstructural components, should be evaluated for its effects on safety.

d. Dry spent fuel storage gamma shielding materials should not experience slumping or loss of shielding effectiveness to an extent that compromises safety. The shield should perform its intended function throughout the licensed service period.

e. Dry spent fuel storage materials used for neutron absorption should be designed to perform their safety function.

f. Dry spent fuel storage protective coatings should remain intact and adherent during all loading and unloading operations within wet or dry spent fuel facilities, and during long-term storage.

The qualification of the materials used in the MPC types is documented in Section 8.2 of the HI-STORM FW FSAR [1.3.7] incorporated herein by reference. The material selection opportunities for the HI-STORM UMAX system, therefore, are limited to the HI-TRAC CS and the VVM module assembly components and the reinforced concrete structures that support or surround them.

However, to obviate the need for any new material qualification effort, the materials permitted for the HI-STORM UMAX system are limited to those certified in other HI-STORM 100 and HI-STORM FW dockets. The material qualification information presented in this chapter is accordingly adapted from Docket Number 72-1032 [1.3.7].

17.2.1 Structural Materials

17.2.1.1 Cask Components and Their Constituent Materials

The major structural material that is used in the HI-STORM UMAX VVM is steel. The concrete in the VVM Closure Lid does not play a major structural role but is present in large quantity for the main purpose of shielding. The major structural materials in the ISFSI structures are the concrete and rebars in the Support Foundation Pad, the ISFSI Pad and the Self-hardening Engineered Subgrade in the inter-CEC space.

17.2.1.2 Synopsis of Structural Materials

i. Carbon Steel, Low-Alloy Steel

Materials for the HI-STORM UMAX VVM are selected to preclude brittle fracture. Details of discussions are provided in Section 17.4 herein.

ii. Reinforced Concrete

All reinforced concrete load bearing structures (concrete and rebar) in the HI-STORM UMAX ISFSI will conform to stress criteria of ACI-318(2005) [5.3.1]. Section 3.3 in the HI-STORM UMAX FSAR [1.0.6] provides properties for reinforced concrete to be used for the HI-STORM UMAX interfacing ISFSI structures. The service life of the ISFSI structures is specified to be the same as that of the HI-STORM UMAX VVM.

iii. Self-hardening Engineered Subgrade

The SES material (i.e., lean concrete or CLSM) used in the HI-STORM UMAX ISFSI will conform to the stress criteria of ACI-318(2005) or ACI-229(1999). Tables 2.3.2 and 3.3.4 in the HI-STORM UMAX FSAR [1.0.6] provide the critical properties for the SES material used for HI-STORM UMAX ISFSI safety analyses. In the interest of a reliably robust design and long service life, additional performance properties of CLSM are listed in table below. The service life for the SES is the same as that of the VVM and ISFSI reinforced concrete.

iv. Austenitic Stainless Steel

Austenitic stainless steel may be used for certain components of the HI-STORM UMAX VVM. Chapter 5 provides the structural evaluation for the HI-STORM UMAX VVM using the governing structural materials. Since stainless steel materials do not undergo a ductile-to-brittle transition in the minimum permissible service temperature range of the HI-STORM UMAX System, brittle fracture is not a concern for stainless steel components. It is recognized that austenitic stainless steels are qualified for use with other HI-STORM UMAX System components (namely Alloy X for the MPC) by the HI-STORM FW FSAR.

Chapter 5 discusses the structural evaluations of the HI-STORM UMAX System components and ISFSI structures. It is demonstrated that the structural steel components of the HI-STORM UMAX VVM and the SFP concrete meet the allowable stress limits for normal, off-normal, and accident loading conditions as applicable. The analyses documented in Chapter 5 also demonstrate that the SES remains stable under the Design Basis Earthquake condition and provides sufficient protection to the stored MPC even if any side of the self- hardening sub-grade (SES) is fully exposed during excavation for ISFSI expansion.

17.2.2 Non-Structural Materials

i. Plain Concrete

Plain concrete is specified for the VVM Closure Lid for its shielding properties and also as an encasement around the exterior of the VVM CEC shell, if required, for its corrosion mitigation properties. The requirements on the shielding concrete are specified in Table 4.3.3.

The shielding performance of the plain concrete is maintained by ensuring that the minimum concrete density is met during construction and the allowable concrete temperature limits are not exceeded. The durability and thermal analyses for normal and off-normal conditions are carried out in this SAR to ensure that the plain concrete does not exceed the allowable long term temperature limit provided in Chapter 4. The strength analysis is carried out in Chapter 5 of this SAR.

ii. Insulation

The Divider Shell is lined with insulation on its outer surface to prevent excessive heating of the ISFSI pad. The insulation selected shall be suitable for high temperature and high humidity operation and shall be foil faced, jacketed, or otherwise made water-resistant to ensure the required thermal resistance is maintained in accordance with Chapter 6. The high zinc content present in the coating of the Divider Shell provides protection for the jacketing or foil from the potential of galvanic corrosion. To ensure adequate radiation resistance, the insulation blanket does not contain any organic binders. The damage threshold for ceramics is known to be approximately $1x10^{10}$ Rads. Chloride corrosion is not a concern since chloride leachables are limited and sufficiently low. Stress corrosion cracking of the foil or jacketing, whether made from stainless steel or other material, is not an applicable corrosion mechanism due to minimal stresses derived from self-weight. The foil or jacketing and attachment hardware shall either have sufficient corrosion resistance (e.g., stainless steel, aluminum, or galvanized steel) or shall be protected with a suitable surface preservative. The insulation is adequately secured to prevent blockage of the ventilation passages in case of failure of a single attachment (strap, clamp, bolt or other attachment hardware). Table 17.2.2 provides the acceptance criteria for the selection of insulation material for the VVM assembly and ranks them in order of importance.

Table 17.2.1: Additional CLSM Performance Properties*		
Performance Property	**Test Property**	**Nominal Value**
Corrosive Resistance	pH Resistivity Permeability	7.5 – 11.5 > 279000 ohm-cm < 10^{-5} cm/sec
Flowability	Flow	6” – 8” (ASTM D 6103)
Excavatability	Unconfined Compressive Strength	Not excavatable since compressive strength is greater than 300 psi
Permeability	Water Permeability	< 10^{-5} cm/sec
Strength	Penetration Resistance	> 650
Acidity/Alkalinity	pH	7.5 – 11.5
Note: * These properties are not used in HI-STORM UMAX safety analyses; nominal values obtained from References [17.2.1], [17.2.2], and [17.2.3] are tabulated for information only.		

Table 17.2.2: Acceptance Criteria for the Selection of the Insulation Material[Note 1]	
Rank	**Criteria**
1	Adequate thermal resistance
2	Adequate high temperature resistance
3	Adequate humidity resistance
4	Adequate radiation resistance
5	Adequate resistance to the ambient environment
6	Sufficiently low chloride leachables
7	Adequate integrity and resistance to degradation and corrosion during long-term storage

Note 1: Kaowool® ceramic fiber insulation [17.2.1] is selected as one that satisfies the acceptance criteria to the maximum degree. The Kaowool® insulation material provides excellent resistance to chemical attack and is not degraded by oil or water. It has been used in all HI-STORM UMAX ISFSIs thus far. Equivalent materials that meet the above criteria are also commercially available.

17.3 APPLICABLE CODES AND STANDARDS

The design, material selection, manufacturing, inspection and testing of the SSCs for the HI-STORM UMAX system are undergirded by national codes and consensus standards to ensure the longest possible service life. The principal codes and standards applied to the HI-STORM UMAX System components are the ASME Code Section II [17.3.1], the ACI code [5.3.1], the ASTM Standards, and the ANSI standards.

The Codes and standards for the ISFSI pad are discussed in Chapter 5.

Allowable stresses and stress intensities for various materials for the HI-STORM UMAX structures are extracted from ASME Section III Subsection NF for various service conditions. "NF" is also invoked to establish fracture toughness test requirements for low service temperature conditions. Mechanical properties of materials are extracted from applicable ASME sections [17.3.1], [17.3.2] and are tabulated for various materials used in HI-STORM UMAX System. Concrete properties are from ACI 318-2005 [5.3.1] code.

In order to meet the requirements of the codes and standards the materials must conform to the minimum acceptable physical strengths and chemical compositions and the fabrication procedures must satisfy the prescribed requirements of the applicable codes.

Additional codes and standards applicable to welding are discussed in Section 17.5 and those for the bolts and fasteners are discussed in Section 17.6.

Review of the above shows that the identified codes and standards are appropriate for the material control of major components. Additional material control is identified in material specifications. Material selections are appropriate for environmental conditions to be encountered during loading, unloading, transfer, and storage operations. The materials and fabrication of major components are suitable based on the applicable codes of record.

17.4 MATERIAL PROPERTIES

This section provides discussions on material properties that mainly include mechanical and thermal properties. The material properties used in the design and analysis of the HI-STORM UMAX System are obtained from established industry sources such as the ASME Boiler and Pressure Vessel Code [17.3.1], ASTM publications, handbooks, textbooks, other NRC-reviewed SARs, and government publications, as appropriate.

17.4.1 Mechanical Properties

Section 3.3 of the HI-STORM UMAX FSAR [1.0.6], incorporated herein by reference, provides mechanical properties of all ITS materials used in the HI-STORM UMAX System at HI-STORE. The structural materials include Alloy X, carbon steel, low-alloy and nickel-alloy steel, bolting materials, and weld materials. The properties include yield stress, mean coefficient of thermal expansion, ultimate stress, and Young's modulus of these materials and their variations with temperature. Certain mechanical properties are also provided for nonstructural materials such as concrete used for shielding.

The discussion on mechanical properties of materials in Chapter 3 of [1.0.6] provides reasonable assurance that the class and grade of the structural materials are acceptable under the applicable construction code of record. Selected parameters such as the temperature dependent values of stress allowables, modulus of elasticity, Poisson's ratio, density, thermal conductivity, and thermal expansion have been appropriately defined in conjunction with other disciplines. The material properties of all code materials are guaranteed by procuring materials from Holtec-approved vendors through the so-called "material dedication" process*, if necessary.

17.4.2 Thermal Properties

Section 4.2 of [1.0.6], incorporated herein by reference, presents thermal properties of materials used in the MPC such as Alloy X, Metamic-HT, aluminum shims and helium gas; materials present in HI-STORM UMAX such as carbon steel, stainless steel and concrete; and materials present in HI-TRAC transfer cask that include carbon steel and plain concrete. The properties include density, thermal conductivity, heat capacity, and surface emissivity/absorptivity. Variations of these properties with temperature are also provided in tabular forms.

The thermal properties of fuel (UO_2) and fuel cladding are also reported in Section 4.2 of [1.0.6]. Thermal properties are obtained from standard handbooks or established text books.

17.4.3 Protection Against Brittle Fracture of Ferritic Steel Parts

The risk of brittle fracture in the HI-STORM UMAX components is eliminated by utilizing materials that maintain high fracture toughness under "cold" conditions (-40 degrees F).

The MPC canister is constructed from a menu of stainless steels termed Alloy X (Appendix 1A of HI-STORM 100 FSAR, incorporated herein by reference]. These stainless steel materials do not undergo a ductile-to-brittle transition in the minimum service temperature range of the HI-STORM UMAX system. Therefore, brittle fracture is not a concern for the MPC components.

* Dedication is a term of art in nuclear quality assurance.

Such an assertion cannot be made *a' priori* for the HI-STORM UMAX VVM and HI-TRAC CS transfer cask that contain ferritic steel parts. In general, the impact testing requirement for the VVM and the transfer cask is a function of two parameters: the Lowest Service Temperature (LST)* and the normal stress level. The significance of these two parameters, as they relate to impact testing of the VVM is discussed below.

In normal storage mode, the LST of the VVM structural members may reach the minimum ambient temperature in the limiting condition wherein the spent nuclear fuel (SNF) in the contained MPCs emits no (or negligible) heat. The minimum service temperature of the storage VVM and HI-TRAC CS steel components is conservatively set at a temperature that is 10 degrees F below the 24-hour average for any day at the HI-STORE site recorded for the site in the previous year. This temperature restriction also applies to the heavy load handling operations at an ISFSI. All load bearing parts are deemed to have the necessary level of protection against brittle fracture if the NDT (nil ductility transition) temperature of the part meets ASME Section III Subsection NF requirements.

It is well known that the NDT temperature of steel is a strong function of its composition, manufacturing process (viz., fine grain vs. coarse grain practice), thickness, and heat treatment. For example, it is well known that increasing the carbon content in carbon steels from 0.1% to 0.8% leads to the change in NDT from -50°F to approximately 120°F. Likewise, lowering of the normalizing temperature in the ferritic steels from 1200°C to 900°C may lower the NDT from 10°C to -50°C. It therefore follows that the fracture toughness of steels can be varied significantly within the confines of the ASME Code material specification set forth in Section II of the Code. For example, SA516 Gr. 70 can have a maximum carbon content of up to 0.3% in plates up to four inches thick. Section II further permits normalizing or quenching followed by tempering to enhance fracture toughness. Manufacturing processes that have a profound effect on fracture toughness, but little effect on tensile or yield strength of the material, are also not specified with the degree of specificity in the ASME Code to guarantee a well-defined fracture toughness. In fact, the Code relies on actual coupon testing of the part to ensure the desired level of protection against brittle fracture. For Section III, Subsection NF Class 3 parts, the desired level of protection is considered to exist if the lowest service temperature is equal to or greater than the NDT temperature (per NF 2311(b)(10)).

17.4.4 Protection Against Creep

Creep, a visco-elastic and visco-plastic effect in metals, manifests itself as a monotonically increasing deformation if the metal part is subjected to stress under elevated temperature. Since certain parts of the HI-STORM UMAX system, notably the fuel basket, operate at relatively high temperatures, creep resistance of the fuel basket is an important property. Creep resistance of the MPC internals is discussed in the HI-STORM FW FSAR [1.3.7]. Creep is not a concern in the Enclosure Vessel, the HI-STORM UMAX, or the HI-TRAC steel weldment because of the operating metal temperatures, stress levels and material properties. Steels used in ASME Code pressure vessels have a high threshold temperature at which creep becomes a factor in the equipment design. The ASME Code Section II material properties provide the acceptable upper temperature limit for metals and alloys acceptable for pressure vessel service. In the selection of

* LST (Lowest Service Temperature) is defined as the daily average for the host ISFSI site

steels for the HI-STORM UMAX system, a critical criterion is to ensure that the sustained (normal) metal temperature of the part made of the particular steel type shall be less than the Code permissible temperature for pressure vessel service. This criterion guarantees that excessive creep deformation will not occur in the steels used in the HI-STORM UMAX system.

17.5 WELDING MATERIAL AND WELDING SPECIFICATION

No welding operations are expected to occur on the system components at the HI-STORE CIS site. Nevertheless, the requirements on welding are set down in this section to ensure that the SSCs manufactured at a remote fabrication plant (such as Holtec's plants in Camden, NJ, Orrville, OH or Pittsburgh, PA) comply with the essential provisions specified below.

Welds in the HI-STORM UMAX system are divided into two broad categories:

i. Structural welds

ii. Non-structural welds

Structural welds are those that are essential to withstand mechanical and inertial loads exerted on the component under normal storage and handling.

Non-structural welds are those that are subject to minor stress levels and are not critical to the safety function of the part. Non-structural welds are typically located in the redundant parts of the structure. The guidance in the ASME Code Section NF-1215 for secondary members may be used to determine whether the stress level in a weld qualifies it to be categorized as non-structural.

Both structural and non-structural welds must satisfy the material considerations listed in Tables 8.1.1 and 8.1.2 of [1.0.6] for the MPC and the HI-STORM UMAX VVM, respectively. In addition, the welds must not be susceptible to any of the applicable failure modes listed in Table 17.1.4.

The welding material and welding specification considerations for the MPC and HI-TRAC are discussed in Section 8.5 of the HI-STORM FW FSAR [1.3.7].

To ensure that all structural welds in the HI-STORM UMAX system shall render their intended function, the following requirements are observed:

i. The welding procedure specifications comply with ASME Section IX for every Code material used in the system.

ii. The quality assurance requirements applied to the welding process correspond to the highest ITS classification of the parts being joined.

iii. The non-destructive examination of every weld is carried out using quality procedures that comply with ASME Section V.

The welding operations are performed in accordance with the requirements of codes and standards depending on the design and functional requirements of the components.

The selection of the weld wire, welding process, range of essential and non-essential variables*, and the configuration of the weld geometry has been carried out to ensure that each weld will have:

i. Greater mechanical strength than the parent metal.

* Please refer to Section IX of the ASME Code for the definition and delineation of essential and non-essential variables.

ii. Acceptable ductility, toughness, and fracture resistance.

iii. Corrosion resistance properties comparable to the parent metal.

iv. No risk of crack propagation under the applicable stress levels.

The welding procedures implemented in the manufacturing of HI-STORM UMAX components are intended to fulfill the above performance expectations.

The weld filler material shall comply with requirements set forth in the applicable Welding Procedure Specifications qualified to ASME Section IX at the manufacturer's facility. Only those Welding Procedures that have been qualified to the Code are permitted in the manufacturing of HI-STORM UMAX components.

The weld procedure qualification record specifies the requirements for fracture control (e.g., post weld heat treatment). The HI-STORM UMAX module assembly does not require any post weld heat treatment due to the material combinations and provisions in the applicable codes and standards.

Non-structural welds shall meet the following requirements:

1. The welding procedure shall comply with Section IX of the ASME Code or AWS D1.1.
2. The welder shall be qualified, at minimum, to the commercial code such as ASME Section VIII, Div.1, or AWS D1.1.
3. The weld shall be visually examined by the weld operator or a Q.C. inspector qualified to Level 1 (or above) per ASNT designation.

17.6 BOLTS AND FASTENERS

The HI-STORM UMAX VVM assembly does not employ any ITS bolts or fasteners. However, during the MPC transfer into the HI-STORM UMAX, the HI-TRAC is attached to the VVM assembly to prevent tip-over during a seismic event. Likewise, the HI-TRAC CS cask is bolted to the CTF (located in the Cask Transfer Building) during the canister transfer operation. These bolts used to secure the HI-TRAC against tip-over, the bolts and anchor location material are classified as ITS and are procured in accordance with the Holtec QA program. Bolt and anchor location material must meet either an ASME or ASTM specification.

The only bolts employed in the HI-STORM UMAX VVM system are those used to secure the vent flue to the inlet and outlet plenums. All bolts and fasteners are made of alloy materials which are not expected to experience any significant corrosion and/or SCC in the operating environment. The ISFSI operation and maintenance program shall call for coating of bolts and fasteners if the ambient environment is aggressive.

All threaded surfaces are treated with a preservative to prevent corrosion. The O&M program for the storage system calls for all bolts to be monitored for corrosion damage and replaced, as necessary.

The coefficient of thermal expansion (CTE) describes how the size of an object changes with a change in temperature. Bolts and fasteners used in HI-STORE CIS systems, used only for short term operations, will have a CTE that is similar to the CTE of the materials being bolted together. In case of dissimilar material bolting, the temperature gradient is not high enough to alter the size of the bolts, and it is not credible that the bolts will lose their intended functions.

17.7 COATINGS AND CORROSION MITIGATION

In order to provide reasonable assurance that the VVM will meet its intended Design Life (Table 17.0.1) and perform its intended safety function(s), chemical and galvanic reactions and other potentially degrading mechanisms must be accounted for in its design and construction.

It should be noted that, although the CEC is a buried steel structure it is substantially sequestered from the native soil through two engineered features:

a. A thick reinforced concrete Enclosure Wall surrounds the VVM array and, along with the Support Foundation pad, provides a physical separation (water intrusion protection) to the CECs.

b. The subgrade in contact with the CECs is either a "free flow" concrete or an engineered fill selected to provide a non-aggressive environment around the CECs.

The above engineered features provide an environmentally benign condition for the CECs. The above said, although the CEC is not a part of the MPC confinement boundary, it should not corrode to the extent where localized in-leakage of water occurs or where gross general corrosion prevents the component from performing its primary safety function. In the following, considerations in the VVM's design and construction consistent with the applicable guidance provided in ISG-15 [17.0.1] are summarized.

All VVM components are protected from galvanic corrosion by appropriate designs. Except for the CEC exterior surfaces (exterior CEC surface coating requirements discussed separately), all carbon steel surfaces of the VVM are lined and coated with the same or equivalent surface preservative that is used in the aboveground HI-STORM FW and HI-STORM 100 overpacks. The pre-approved surface preservative is a proven zinc-rich inorganic/metallic (may also be an organic zinc rich coating) material that protects galvanically and has self-healing characteristics for added protection. All exposed surfaces interior to the VVM are accessible for the reapplication of surface preservative, if necessary.

The native soil excavated at the ISFSI site shall not be used as subgrade at the HI-STORE CIS ISFSI. Instead, CLSM will be used to provide corrosion protection and enhanced shielding.

17.7.1 Exterior Coating

The CEC exterior shall be coated with a radiation resistant surface preservative designed for below-grade and/or immersion service. Inorganic and/or metallic coatings are sufficiently radiation-resistant for this application; therefore, radiation testing is not required. Organic coatings such as epoxy, however, must have proven radiation resistance or must be tested without failure to at least 10^7 Rad. Radiation testing shall be performed in accordance with ASTM D 4082 [17.7.4] or equivalent. The coating should be conservatively treated as a Service Level II coating as described in Reg. Guide 1.54 [17.7.1]. As such, the coating shall be subjected to appropriate quality assurance in accordance with the applicable guidance provided by ASTM D 3843-00 [17.7.2]. The coating should preferably be shop-applied in accordance with manufacturer's instructions and, if appropriate, applicable guidance from ANSI C 210-03 [17.7.3]. The following table provides the acceptance criteria for the selection of coatings for the exterior surfaces of the CEC and ranks them in order of importance.

Acceptance Criteria for the Selection of Coatings	
Rank	**Criteria**
1	suitable for immersion and/or below grade service
2a	compatible with the ICCPS (if used) • adequate dielectric strength • adequate resistance to cathodic disbondment
2b	compatible with concrete encasement (if used) • adequate resistance to high alkalinity
3	adequate radiation resistance
4	adequate adhesion to steel
5	adequate bendability/ductility/cracking resistance/abrasion resistance
6	adequate strength to resist handling abuse and substrate stress

The Keeler & Long polyamide-epoxy coating is selected as one that satisfies the acceptance criteria to the maximum degree. Alternatively, a Holtec-approved equivalent that meets the acceptance criteria set forth in the table above may be used.

17.8 GAMMA AND NEUTRON SHIELDING MATERIALS

Gamma and neutron shield materials in the HI-STORM UMAX VVM system are discussed in Section 1.2. The primary shielding materials used in the HI-STORM UMAX VVM system, as listed in Table 17.1.3, are plain concrete, reinforced concrete, and steel.

The plain concrete provides the main shielding function in the HI-STORM UMAX lids to minimize sky shine.

17.8.1 Plain Concrete

Unlike the above ground HI-STORM models, the use of plain concrete for shielding purposes in the underground VVMs is limited to the VVM Closure Lid. The critical characteristics of concrete used in the Closure Lid are its density and compressive strength. Table 2.3.2 in the HI-STORM UMAX FSAR provides reference properties of plain concrete used in the Closure Lid.

The density of plain concrete within the HI-STORM UMAX VVM is subject to a minor decrease due to long-term exposure to elevated temperatures. The reduction in density occurs primarily due to liberation of unbonded water by evaporation.

17.9 NEUTRON ABSORBING MATERIALS

The neutron absorber material is permanently installed inside the Canisters for reactivity control. Metamic-HT is the neutron absorber material utilized the MPC-37 and MPC-89 -Canisters initially certified in the HI-STORM FW docket (#72-1032). The properties of Metamic-HT are fully characterized in the HI-STORM FW FSAR [1.3.7] in Paragraph 1.2.1.4 which is incorporated herein by reference [see Table 17.0.2].

Because Metamic-HT is enclosed in a helium environment and is subject to no interaction with the environment, its service life is not subject to attrition in storage.

17.10 SEALS

The HI-STORM UMAX VVM assembly does not utilize any gaskets that seal against a large pressure differential.

The only external gasket used in the system is the soft gasket at the Closure lid-CEC Flange interface that helps prevent the ingress of moisture and insects (through the small crack that may exist due to weld distortion in the fabrication of interfacing fabricated steel weldment surfaces) into the module cavity space.

The Divider shell is sealed against the Closure lid using a pliable, non-organic seal material that is suitable for long-term ambient air application up to 300 degree F.

BISCO® BF-1000 Extra Soft Cellular Silicone gasket material [17.10.1] is selected as one that satisfies the acceptance criteria to the maximum degree. The seal/gasket material provides excellent compressibility, softness, and durability to adapt to various environments, making it an ideal choice for sealing Closure Lid. It has been used in all HI-STORM UMAX ISFSIs thus far. Equivalent materials that meet the above criteria are also commercially available.

17.11 CHEMICAL AND GALVANIC REACTIONS

The materials used in the HI-STORM UMAX System are examined to establish that these materials do not participate in any chemical or galvanic reactions when exposed to the various environments during all normal operating conditions and off-normal and accident events. Chemical and galvanic reactions related to the MPC are discussed in Section 8.12 of the HI-STORM FW FSAR.

The following acceptance criteria for chemical and galvanic reactions are extracted from ISG-15 [17.0.1] for use in HI-STORM UMAX VVM components.

a. The DCSS should prevent the spread of radioactive material and maintain safety control functions using, as appropriate, noncombustible and heat resistant materials.

b. A review of the DCSS, its components, and operating environments (wet or dry) should confirm that no operation (e.g., short-term loading/unloading or long-term storage) will produce adverse chemical and/or galvanic reactions, which could impact the safe use of the storage cask.

c. Components of the DCSS should not react with one another, or with the cover gas or spent fuel, in a manner that may adversely affect safety. Additionally, corrosion of components inside the containment vessel should be effectively prevented.

d. Potential problems from general corrosion, pitting, stress corrosion cracking, or other types of corrosion, should be evaluated for the environmental conditions and dynamic loading effects that are specific to the component.

The materials and their ITS pedigree are listed in the drawing package provided in Section 1.5. The compatibility of the selected materials with the operating environment and to each other for potential galvanic reactions is discussed in this section.

- External atmosphere – During long-term storage the casks are exposed to outside atmosphere, air with temperature variations, solar radiation, rain, snow, ice, etc.

As discussed herein, the components of the HI-STORM UMAX System have been engineered to ensure that the environmental conditions expected to exist at nuclear power plant installations do not prevent the cask components from rendering their respective intended functions.

The principal operational considerations that bear on the adequacy of the VVM for the service life are addressed as follows:

<u>Exposure to Environmental Effects</u>

All exposed surfaces of the HI-STORM UMAX VVM components are made from stainless steels or ferritic steels that are readily painted. Concrete, which serves strictly as a shielding material in the VVM Closure Lid, is encased in steel. Therefore, the potential of environmental vagaries such as spalling of concrete are ruled out for HI-STORM UMAX VVM. Under normal storage conditions, the bulk temperature of the HI-STORM UMAX storage overpack will change very gradually with time because of its large thermal inertia. Therefore, material degradation from rapid thermal ramping conditions is not credible for the HI-STORM UMAX VVM. Similarly, corrosion of structural steel embedded in the concrete structures due to salinity in the

environment at coastal sites is not a concern for HI-STORM UMAX VVM because it does not rely on rebars (indeed, it contains no rebars). The configuration of the storage VVM assures resistance to freeze-thaw degradation. In addition, the storage system is specifically designed for a full range of enveloping design basis natural phenomena that could occur over the service life of the storage system as catalogued in Section 2.2 and evaluated in Chapter 15.

The ISFSI pad, which is exposed to the elements, shall be subject to a surveillance program to monitor its potential degradation, as discussed in Chapter 10.

Material Degradation

The relatively low neutron flux to which the VVM is subjected cannot produce measurable degradation of the cask's material properties and impair its intended safety function. Exposed carbon steel components are coated to prevent corrosion. The ambient environment of the ISFSI storage pad mitigates damage due to exposure to corrosive and aggressive chemicals that may be produced at other industrial plants in the surrounding area.

Maintenance and Inspection Provisions

The requirements for periodic inspection and maintenance of the VVM throughout its service life are defined in Chapter 10. These requirements include provisions for routine inspection of the exterior and periodic visual verification that the ventilation flow paths are free and clear of debris. ISFSIs located in areas subject to atmospheric conditions that may degrade the storage cask or canister should be evaluated by the licensee on a site-specific basis to determine the frequency for such inspections to assure long-term performance. In addition, the HI-STORM UMAX system is designed for easy retrieval of the MPC from the VVM should it become necessary to perform more detailed inspections and repairs on the storage system.

The above findings are consistent with those of the NRC's Continued Storage of Spent Nuclear Fuel Decision [17.11.1], which concluded that dry storage systems designed, fabricated, inspected, and operated in accordance with such requirements are adequate for the design and service life expectations set down in Table 17.0.1.

17.12 FUEL CLADDING INTEGRITY

The discussion related to the fuel cladding integrity during short term operations is incorporated by reference from Section 8.13 of the HI-STORM FW FSAR and is not repeated here.

17.13 EXAMINATION AND TESTING

Examination and testing are integral parts of manufacturing of the HI-STORM UMAX System components, these requirements are incorporated by reference from HI-STORM UMAX FSAR [1.0.6], Section 8.13.

Post-fabrication inspections are discussed in Chapter 10 of this SAR as part of the HI-STORM UMAX VVM System maintenance program. Inspections are conducted prior to fuel loading or prior to each fuel handling campaign. Other periodic inspections are conducted during storage.

The HI-STORM UMAX VVM is a passive device with no moving parts. The vent screens are inspected on scheduled intervals for damage, holes, etc. The VVM's external surface, including identification markings, is visually examined on a periodic basis in accordance with the ISFSI's surveillance plan. The temperature monitoring system, if used, is inspected per the licensee's QA program and manufacturer's recommendations.

17.14 REGULATORY COMPLIANCE

The preceding sections describe the materials used in important-to-safety SSCs and the suitability of those materials for their intended functions in the HI-STORM UMAX System at the HI-STORE CIS facility.

The requirements of 10CFR72.122(a) are met: The material properties of SSCs important to safety conform to quality standards commensurate with their safety functions.

The requirements of 10CFR72.104(a), 106(b), 124, and 128(a)(2) are met: Materials used for shielding are adequately designed and specified to perform their intended function.

The requirements of 10CFR72.122(h)(1) are met: The design of the DCSS and the selection of materials adequately protect the spent fuel cladding against degradation that might otherwise lead to gross rupture of the cladding by ensuring that the cladding temperature remains below the ISG-11 Rev 3 limits..

The requirements of 10CFR72.122(l) are met: The material properties of SSCs important-to-safety will be maintained during normal, off-normal, and accident conditions of operation as well as short-term operations so the spent fuel can be readily retrieved without posing operational safety problems.

The requirements of 10CFR72.122(f) are met: The material properties of SSCs important-to-safety will be maintained during all conditions of operation so the spent fuel can be safely stored for the specified service life and maintenance can be conducted as required.

The requirements of 10CFR72.1226(b) are met: The HI-STORM UMAX System employs materials that are not vulnerable to degradation over time or react with one another during long-term storage.

CHAPTER 18: AGING MANAGEMENT PROGRAM*

18.0 INTRODUCTION

This chapter contains the essentials of the Aging Management Programs (AMP) for the HI-STORE CIS ISFSI which is intended to possess a long Service life (Table 17.0.1). An effective AMP is considered an imperative for an ISFSI that may ultimately house thousands of canisters containing spent nuclear fuel. For such a facility, a well-construed program to thwart gradual weakening of the safety margins associated with aging of the facility with potentially adverse consequences to important-to-safety structures, systems and components (SSCs) is a necessity. AMPs monitor and control the degradation of storage system's SSCs, so that the aging effects will not result in loss of their safety-significant function during their service life in interim storage. An effective AMP prevents, mitigates, or detects the aging effects and provides for the prediction of the extent of the effects of aging and timely corrective actions before there is a loss of intended function.

It is recognized that the HI-STORE ISFSI will store canisters most of whom have been previously stored at an ISFSI at an operating or shuttered nuclear plant site. An AMP has not been required as a part of the initial licensing cycle of an ISFSI which has historically been 20 years. An acceptable AMP is required, however, at the end of the initial licensed life as a regulatory predicate for life extension of the storage license. At HI-STORE CIS, Holtec International plans to implement a state-of-the-art AMP that incorporates certain innovative approaches pioneered by the Company which are founded on the fundamentals of material degradation mechanisms. The architecture of the Program is informed by the published regulatory and industry literature as synopsized below.

NUREG-1927 [18.0.1] sets down an AMP containing 10 elements to manage the effects of aging. This document emphasizes the operating experience of all operating units to be documented and reviewed. Periodic future reviews of operating experience are required to confirm the effectiveness of AMP, or identify a need to enhance/modify the AMP. Managing aging mechanisms and effects in a "learning" manner articulated in [18.0.1] means ISFSI owners would monitor both the known SSC degradation mechanisms and the symptoms that would be indicators of a potential unknown SSC degradation mechanism.

The AMP set down in this chapter consists of four major components, namely

- Monitoring for emerging signs of potential degradation
- Periodic inspection and testing to uncover onset of the SSC's degradation
- Implementation of preventive measures (barriers) to arrest degradation
- Recovery and remedial measures if all barriers were to fail

Each of the above constituents of the AMP is summarized in the following sections.

* All references are in placed within square brackets in this report and are compiled in Chapter 19 (last chapter)

Nuclear Energy Institute (NEI) publication #14-03, Revision 1 [18.0.2] elaborates on [18.0.1] providing an explicit set of expectations from a well implemented AMP. The NEI espoused program calls for the AMP to have the following attributes:

- safety-focused
- operations-based
- implemented within existing corrective action and operating experience programs
- qualitatively risk-informed based on relevant failure modes and effects
- forward-looking
- proactive
- responsive to condition-based monitoring.

NEI 14-03 [18.0.2] provides a framework for AMP through the use of tollgates, defined as periodic points within the period of extended operation when licensees would be required to evaluate aggregate feedback and perform and document a safety assessment that confirms the safe storage of spent fuel. Tollgates are an additional set of in-service assessments beyond the normal continual assessment of operating experience, research, monitoring, and inspections on component performance that is part of normal ISFSI operations for licensees during the initial license period as well as the renewal period.

The concept of operations-based aging management is to manage aging mechanisms and timeframes (duration to loss of intended function) that are either not known or not well understood. Known aging mechanisms will be managed using existing corrective action and operating experience programs with the objective of preventing loss of intended safety functions due to aging effects. Because some postulated aging mechanisms and/or timeframes for in-scope SSCs are not well-characterized by operating data, aging management should be implemented in a manner that feeds information back in a timely fashion to the licensees. This feedback will be used to perform corrective actions on components to preclude the loss of safety function over the renewed operating period.

Operations-based aging management programs should include the following attributes for the known and unknown degradation mechanisms and time frames:

- recognition and evaluation (key technical issues)
- storage system inspections
- monitoring and operational inspections
- analysis and assessment
- tollgate assessment
- feedback and corrective actions (mitigation/repair and/or analysis).

The AMP outlined in this chapter incorporates the above elements of [18.0.1 and 18.0.2] and is termed a "progressively enhanced plan" (PEP) that is shaped and guided by fundamental technical principles and ongoing operating experience.

All the important-to-safety (ITS) SSCs scoped for aging management were granted a 20 year initial license under the HI-STORM UMAX license. HI-STORE SAR will be requesting a 40 year license. To ensure an uninterrupted performance of these ITS SSCs and their intended functions through the 40 year license period, all such ITS SSCs will be inspected and monitored per their respective AMP, and a concern-free service life of those SSCs will be established. Additional AMPs are also included for those SSCs that are not part of the HI-STORM UMAX generic license. Typical aging mechanisms and quantitative and/or qualitative analyses are discussed in Section 18.3 below.

18.1 SCOPING EVALUATION AND SEVERITY INDEX

The HI-STORE CIS ISFSI consists of (i) the MPC, (ii) the VVM, and (iii) other support SSCs. These components were evaluated using the two scoping criteria in NUREG-1927 [18.0.1]. In summary, these criteria are (1) an SSC that is Important to Safety (ITS) or (2) an SSC that supports SSC safety functions.

Because the canister provides the confinement protection and reactivity control, its AMP is the most critical activity and is accordingly the central focus of the program. The VVM which includes the top pad (ISFSI pad) is the other critical component. As a steel and concrete structure that is limited to providing dose attenuation, the aging management demands on the VVM are different in nature from those on the MPC and are also somewhat less severe. Furthermore, the top lid (Closure Lid) of the VVMs is a removable item which can be replaced with a new lid, if needed, making the aging management demands on it less consequential. (The VVM body is integral to the ISFSI and cannot be replaced). The HI-TRAC CS transfer cask is used only during loading operations; it does not store any used Fuel. The AMP for the Transfer cask is accordingly informed by its functional requirement. An assessment of the VVM, MPCs, HI-TRAC CS Transfer Cask, ISFSI pad, and other SSCs is documented in [1.2.1] which identifies the necessary inspection and monitoring activities to provide reasonable assurance that the SSCs will perform their intended functions for the duration of their License life. A summary of the SSCs that warrant an AMP along with the severity of the consequence of each SSC's degradation is provided in Table 18.1.1 (partially adapted from [1.2.1]). The Severity index is essentially a graded approach to defining AMP requirements: A Severity Index of 3 is the highest, 2 means moderate severity, 1 is minor impact on SSC, and 0 means the SSC is not subject to an AMP.

Table 18.1.1: Summary of SSCs Requiring Aging Management & Their Severity Index

SSC	Scoping Results		In-Scope SSC	Severity of the consequence of degradation (3 most severe, 2 moderately severe, 1 Minor; 0 not severe and not-included)
	Criterion 1[1]	Criterion 2[2]		
MPC	Yes	N/A	Yes	3
HI-TRAC CS Transfer Cask	Yes	N/A	Yes	1
VVM	Yes	N/A	Yes	2
Fuel Assembly	Yes	N/A	Yes	3
ISFSI Pad	Yes	No	Yes	2
SFP	Yes	No	Yes	1
CTB Crane	Yes	No	Yes	1
CTB Slab	Yes	No	Yes	1
CTF	Yes	No	Yes	1
HI-TRAC CS Lifting Device (Lift Yoke)	Yes	No	Yes	1
MPC Lift Attachment	Yes	No	Yes	1
MPC Lifting Device Extension	Yes	No	Yes	1
VCT	Yes	No	Yes	1
Special Lifting Devices	Yes	No	Yes	1
CLSM	No	No	No	0
CTB	No	No	No	0
CTF Adapter Plate	No	No	No	0
ISFSI Security Equipment	No	No	No	0

Notes:
(1) SSC is Important to Safety (ITS)
(2) SSC is Not Important to Safety (NITS), but its failure could prevent an ITS function from being fulfilled

18.2 MAINTENANCE PROGRAM FOR THE HI-STORM UMAX VVM & HI-TRAC CS

The maintenance program is an essential element of a comprehensive AMP. The essentials of the maintenance program for the HI-STORE ISFSI SSCs are summarized in Chapter 10. The relationship of aging management to the maintenance program is discussed in Section 18.12.

18.3 MECHANISMS FOR AGING OF SSCS

In this section, the fundamental mechanisms that underlie aging of a dry storage SSC are summarized to serve as the guide in evolving an effective aging management program. The principal effects that can cause aging of an SSC are:

i. Cyclic fatigue from thermal and pressure transients

ii. Creep

iii. Erosion

iv. General Corrosion

v. Boron depletion (of neutron absorbing or shielding materials)

vi. Crack propagation

vii. Repetitive mechanical loading (of trunnions and threaded anchor locations)

viii. Stress corrosion cracking (SCC)

Each mechanism is discussed below in the context of its potential role in aging of the HI-STORE SSCs.

i. Cyclic Fatigue:

Cyclic fatigue is caused by thermal or pressure transients in a SSC. The necessary condition for fatigue expenditure in metals is a rapid pulsation of large amplitude stress which is only possible in the dry storage SSCs if the environmental conditions were to change drastically (hundreds of °F change) in a matter of seconds and such changes were to occur repeatedly (thousands of cycles). Because such cyclic conditions are not realistic for any terrestrial environment, cyclic fatigue of dry storage components and structures is not a credible mechanism for their degradation.

Quantitative analysis of long term fatigue on HI-TRAC CS and other lifting ancillaries is discussed in Chapter 5 in this SAR.

It summarizes a cyclic loading fatigue evaluation of the HI-TRAC CS Transfer Cask and other lifting ancillaries which concludes that stresses are well below the endurance limit of the trunnion material. Thus, trunnion fatigue is not an issue during the aging management period. It is conservatively assumed that the HI-TRAC CS and other lifting ancillaries are utilized for all lifts of the ISFSI MPCs. However, the allowable number of lifting cycles far exceeds the number of lifts that will be needed. Therefore, no additional aging management plan is needed to address fatigue failure of the HI-TRAC CS and other lifting ancillaries.

ii. Creep:

Creep is a time-dependent effect that produces ever-increasing deformation under a sustained load. Creep is a factor in components that operate at a high temperature and are subject to an elevated state of stress. Creep effects are negligible in most metals at moderate temperature (below 600°F) and stress levels (less than half of the material's Yield Strength). Creep, therefore, is a concern only for the fuel assembly rods inside the canisters. Because the fuel rods are thin

walled pressurized tubes and operate at elevated temperatures, the incidence of damage from creep cannot be ruled out. In this respect, the high thermal capacity of the HI-STORM UMAX system provides an effective protection against creep. A quantitative estimate of the benefit accrued by HI-STORM UMAX to the canisters brought in at a substantially lower heat load (Section 4.1) can be obtained by using the creep rate equation for fuel cladding from [18.3.1]:

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

The creep rate corresponding to the maximum heat load in HI-STORM UMAX to that if the fuel rod were at the ISG-11 Rev 3 limit temperature can be obtained by assuming the cladding hoop stress is directly proportional to the absolute temperature of the cladding material. Using the cladding temperature result from Table 18.3.1, the ratio is determined and presented in Table 18.3.1. As can be seen from this result, the high thermal capacity of the HI-STORM VVMs has the effect of reducing the creep rate by several orders of magnitude.

Of course, as the canister ages, its heat load decreases, causing a corresponding decrease in the creep rate, reaching vanishing small values after a few years. Therefore, the threat of creep damage to the fuel recedes to a negligible range as the canisters will age in interim storage at HI-STORE.

Appendix D of NUREG-1927 [18.0.1] provides supplemental guidance for the use of a demonstration program as a surveillance tool for confirmation of integrity of High Burnup Fuel (HBF) during the period of extended operation. The technical discussion and guidance provided by the demonstration program will be used for learning purposes and the results obtained from the program will be analyzed. All appropriate actions shall be taken at the HI-STORE facility, as needed, based on the demonstration program results.

iii. Erosion:

Erosion is a mechanical action wherein the impinging particles carried by a fluid medium on a surface causes the target surface to release fine surface matter. Erosion requires a high fluid velocity to cause noticeable material loss. Contemporary design practice in tubular heat exchanger thermal design holds that the incident velocity must be high enough so that E defined

by $\rho v^2 > 500$, where ρ is density of the fluid carrier in lb/cubic feet, and v is the flow velocity orthogonal to the target surface in feet/sec.

The evident area on the canister's surface potentially vulnerable to erosion would be the surface facing the inlet ducts through which ventilation air enters. The value of in-duct air velocity from the FLUENT analysis is used for comparison purposes. The key computed data is summarized in the unnumbered table below which shows that the minimum required threshold value is orders of magnitude larger than the actual value.

Empirical correlation for the rate of erosion states that the rate varies as 4.5 power of velocity. Using this correlation gives the computed factor of safety against the onset of erosion on the canister's surface.

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

Therefore, erosion is ruled out as an actuating mechanism to cause damage to the stored canister at the HI-STORE facility.

iv. General Corrosion & Spalling of the ISFSI concrete surface:

General corrosion of painted carbon steel surfaces in the HI-STORM UMAX ISFSI is expected and dealt with in the maintenance program described in the foregoing. Because the ambient air is relatively dry, the incidence of peeling of the coating is expected to be much more subdued.

Likewise spalling of the ISFSI concrete surface around the VVM is prevented by keeping the surface coating in good condition through preventive maintenance.

v. Boron depletion:

The theoretical risk of boron depletion applies to the neutron absorber panels in the canister's Fuel Basket wherein the B-10 isotope in the material serves to capture thermalized neutrons produced by the radioactive decay of the used fuel. Calculations performed on a typical canister show that the fraction of boron atoms consumed during the service life of the MPC (Table 17.0.1) will be a small fraction of boron available in the Fuel Basket.

A quantitative analysis on Boron depletion has been discussed in Section 3.4.8 of HI-STORM FW FSAR [1.3.7]. The analysis demonstrates that the Boron depletion in Metamic-HT material is negligible over a 60 year duration. Thus, sufficient levels of Boron are present in the fuel

basket neutron absorbing material to maintain criticality safety functions over the license life of the MPC.

Therefore, aging management of the canister to insure adequate boron-10 isotope in the Fuel Basket is not necessary; the canister does not run a credible risk of boron depletion below the needed level to maintain subcriticality.

vi. Crack propagation:

Every material has flaws at microscopic level. Those components whose load bearing materials are volumetrically examined are less apt to have hidden flaws but the existence of imperfections that can propagate over time can't be entirely ruled out. In order to ensure that any pre-existing flaw will not propagate and lead to sudden failure, the following design measures will be implemented in the design and manufacturing of the SSCs for HI-STORE:

- In high strength materials, such as those used in lift rigs, the maximum primary stress in the material during lifting and handling operations is required to be less than 1/6th of the material Yield Strength which is generally considered to be the limit at which a pre-existing crack may propagate.
- In high ductility materials, such as austenitic stainless steel (used in the canister), the maximum stress is required to meet the limit in Reg Guide 3.61. Furthermore, the primary stress in the canister under normal storage condition is required to meet the limit for ASME Section III Class 1 components.

Observing the above restrictions eliminates the threat of crack propagation in critical equipment at the HI-STORM ISFSI and hence the need for any prophylactic measures to avoid their occurrence.

vii. Repetitive Mechanical Loading:

The design measure employed by Holtec requires the maximum primary stress in a trunnion or threaded anchor location under the maximum lifted load to be below the “endurance strength” of the material. Observing the endurance limit criterion eliminates the threat of cyclic fatigue failure *a’ priori.* Quantitative analysis of long term fatigue on lifting ancillaries is discussed in Chapter 5 in the SAR.

viii. Stress Corrosion Cracking (SCC):

Unique to austenitic and duplex stainless steels, SCC causes cracking at the intergranular or transgranular level in the material. It is a serious threat to the canister's confinement boundary which is exposed to the ambient environment at the ISFSI. The incidence of SCC requires three essential conditions to be present concurrently:

a. Significant tensile stress at the surface exposed to the environment, and
b. Halides in the environment, and
c. Relative humidity in excess of 20%

At the HI-STORE site, the halide content in the air is negligible as mentioned in Chapter 2, therefore an essential requirement for SCC is not satisfied and the incidence of SSC becomes a remote possibility. Nevertheless, the risk of SCC cannot be entirely ruled out and the AMP must

provide for a way to anticipate it. Accordingly, the monitoring method for the canister proposed in this SAR assumes that the threat of SCC is real and possible.

Table 18.3.1: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Property	Value
Bounding Cladding Stress (σ_{max})	144.7 MPa @ T_{ref} = 387°C [1]
Baseline Cladding Temperature (T_{cb})	400°C
Max. Cladding Temperature under HI-STORM UMAX Storage (T_{cs})	330°C [2]
Cladding Stress (σ_b) @ T_{cb} (σ_{max} * (T_{cb} + 273)/ (T_{ref} + 273))	147.6 MPa
Cladding Stress (σ_s) @ T_{cs} (σ_{max} * (T_{cs} + 273)/ (T_{ref} + 273))	132.2 MPa
Creep Rate Ratio (φ @ T_{cs} / φ @ T_{cb})	0.04

[1] Data adopted from Appendix 4.A for bounding PWR fuel rods [18.3.1]
[2] Data adopted from Chapter 6, Section 6.4 of the HI-STORE SAR.

18.4 UNIQUE ASPECTS OF THE HI-STORE CIS WITH NEXUS TO ITS AMP

The following aspects of the HI-STORE ISFSI are relevant to developing a sound AMP for the site:

i. Because the storage system is subterranean, the extent of the exposed metal surface of the VVM is quite small compared to the above-ground storage systems.

ii. The relatively thin wall of the exposed surface of the canister (the canister's shell which is made of austenitic stainless steel) is disposed vertically which, as expected, discourages the deposition of aggressive species from accumulating on the shell surface. (An EPRI/Holtec measurement program at Diablo Canyon and Salem/Hope Creek ISFSIs showed that the deposition on the shell surface is significantly less than that on the horizontal surface [18.4.1]). It is well known that the deposition of solutes on the surface of stainless steel directly correlates with the risk of generation of nucleation sites where stress corrosion cracking (SCC) may initiate. Reduced deposition rate on the thin wall of the canister is a positive feature for an extended service life.

iii. As described in Chapter 2, the ambient environment at the HI-STORE site has minuscule amount of salts and other airborne particulates known to be injurious to stainless steel. The minuscule concentration of halides in the air starves the canister's surface of an essential ingredient for initiating SCC.

iv. There is no location for contaminant hide-out (such as crevice or gouge) on the surface of the vertically arrayed canister (in contrast to the condition where the canister is horizontally stored), where halide-bearing particles may concentrate enabling SCC to take hold.

v. The settling of moisture on the canister's shell during cool hours followed by warm hours causing the moisture to evaporate leaving behind the particulate residue is the principal means for salts to accumulate on the canister's surface. In the high desert of south-eastern New Mexico, the relative humidity in the air is low, making the delivery of salts to the canister's surface less effective.

In light of the above, it is reasonable to expect that the canisters stored at HI-STORE CIS will have a substantially longer service life than that projected in Table 17.0.1. Nevertheless, a progressively enhanced plan for Aging Management has been adopted in this SAR as explained in this Chapter.

18.5 CANISTER AGING MANAGEMENT PROGRAM

18.5.1 Visual Examination

The canister AMP involves monitoring the exterior surface of a MPC, including visual inspection of the MPC surface for signs of degradation. The canisters with the highest susceptibility for SCC should be selected for inspection. The selection criteria include oldest and coldest canisters with a potential for accumulation and deliquescence of deposited salts that may promote localized corrosion and/or SCC. The selection criteria for inspection of the installed canisters at the site will be re-evaluated as and when additional canisters are installed. The visual inspection frequency has been outlined per Table 18.6.1.

The monitored conditions include, but are not limited to:

- Localized corrosion pits, stress corrosion cracking, etching, or deposits
- Discrete colored corrosion products, especially those adjacent to welds and weld heat affected zones
- Linear appearance of corrosion products parallel to or traversing welds or weld heat affected zones
- Red-orange colored corrosion products combined with deposit accumulations in any location
- Red-orange colored corrosion tubercles of any size

18.5.2 Accelerated Coupon Testing

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

[

PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390

]

Figure 18.5.1: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

Figure 18.5.2: [PROPRIETARY INFORMATION WITHHELD IN ACCORDANCE WITH 10CFR2.390]

18.6 HI-TRAC CS TRANSFER CASK AGING MANAGEMENT PROGRAM

The HI-TRAC CS Transfer Cask Aging Management Program utilizes inspections to ensure that the transfer cask maintains its intended function throughout its Service Life by performing a visual inspection for degradation of the external surfaces of the Transfer Cask and trunnions. This inspection is performed prior to use of the Transfer Cask per Table 18.6.1.

The visual inspection will include the following:

- All painted surfaces for corrosion and paint integrity
- All surfaces for dents, scratches, gouges, or other damage
- Lifting trunnions for deformation, cracks, damage, corrosion, and galling

Table 18.6.1: Periodic Inspection Frequency of HI-STORE CIS ISFSI Components

Components	Periodic Inspection Frequency
MPC	Every 5 years
HI-TRAC CS Transfer Cask	Pre-Use and Once every year while in use
VVM	Every 5 years
ISFSI Pad and SFP	Once every year
CTB Crane	Pre-Use and Once every year while in use
CTB Slab	Once every year
Lifting Devices (HI-TRAC CS Lift Yoke, VCT, MPC Lift Attachment, MPC Lifting Device Extension)	Pre-Use and Once every year while in use
CTF	Pre-Use and Once every year while in use

18.7 VVM AGING MANAGEMENT PROGRAM

The Vertical Ventilated Module (VVM) AMP utilizes condition monitoring to manage aging effects of the Cavity Enclosure Container (CEC), Divider Shell, and the Closure Lid as set down in the maintenance program in the foregoing. The initial frequency of inspection is set down in Table 18.6.1 which is subject to change depending on the 'tollgate" protocol explained in Section 18.11.

The visual inspection of the steel components and structures will include the following:

- All internal surfaces for corrosion and integrity
- All other surfaces for dents scratches, gouges, or other damage.

18.8 REINFORCED CONCRETE AGING MANAGEMENT PROGRAM

The ISFSI pad, SFP and Cask Transfer Building (CTB) slab are examples of reinforced concrete structures at the HI-STORE CIS facility. The AMP includes periodic visual inspections by personnel qualified to monitor reinforced concrete for applicable aging effects, and evaluate identified aging effects against acceptance criteria derived from the design bases. The initial frequency of inspection is set down in Table 18.6.1.

The program also includes periodic sampling and testing of groundwater, and the need to assess the impact of any changes in its chemistry on the concrete structures underground. Additional activities may include periodic inspections to ensure the air convection vents are not blocked.

The inspection of the reinforced concrete structures will include the following:

- All accessible surfaces for cracking, loss of material, permeability and integrity
- Groundwater chemistry monitoring to identify conditions conducive to underground aging mechanisms such as corrosion of steel and degradation due to chemical attack.

18.9 HBF AGING MANAGEMENT PROGRAM

This is a program that monitors and assesses data and other information regarding HBF performance, to confirm that the design-bases HBF configuration is maintained during the period of extended operation. The HBF AMP relies on a surrogate demonstration program to provide data on HBF performance. Guidance to support HBF AMP is given in Appendix D of NUREG-1927.

The aging management review is not expected to identify any aging effects that could lead to fuel reconfiguration, as long as the HBF is stored in a dry inert environment, temperature limits are maintained, and thermal cycling is limited. Short term testing and scientific analyses examining the performance of HBF have provided a foundation for the technical basis that storage of HBF in the period of extended operation may be performed safely and in compliance with regulations. However, there has been relatively little operating experience, to date, with dry storage of HBF.

Therefore, the purpose of HBF AMP is to monitor and assess data and other information regarding HBF performance to confirm there is no degradation of HBF that would result in an unanalyzed configuration during the period of extended operation.

The parameters (maximum assembly-average burnup, cladding type, peak cladding temperatures) of the demonstration program are applicable to the design-bases HBF at HI-STORE.

18.10 LIFTING DEVICE AGING MANAGEMENT PROGRAM

Ancillaries for the HI-STORE CIS are equipment, systems or devices that are needed to carry out Short Term Operations to place the canister into interim storage or to remove the loaded canister from storage. The lifting and handling ancillaries needed for operation of the HI-STORE CIS are classified as either "lifting devices" or "special lifting devices". The design requirements and stress compliance criteria applicable for such devices are located in Section 4.5 of this SAR.

The term *lifting device* as used in this SAR refers to components of a lifting and handling system that are not classified as *special lifting devices*. ANSI N14.6 is not applicable to these *lifting devices.* Examples of *lifting devices* used with Holtec's systems include the VCT used in the transport cask receiving area of the Cask Transfer Building (CTB).

The term *special lifting device* refers to components to which ANSI N14.6 [1.2.4] applies. As stated in ANSI N14.6 (both 1978 and 1993 versions), "This standard shall apply to *special lifting devices* that transmit the load from lifting attachments, which are structural parts of a container to the hook(s) of an overhead hoisting system." Examples of *special lifting devices* are canister lift cleats, cask lift brackets, and HI-TRAC CS Lifting Device (Lift Yoke).

The Lifting Device AMP utilizes condition monitoring to manage aging effects of the Cask Transfer Building (CTB) Crane, Canister Transfer Facility (CTF), Vertical Cask Transporter (VCT), MPC Lift Attachment, MPC Lifting Device Extension, HI-TRAC CS Lift Yoke and Special Lifting Device as set down in the maintenance program in the foregoing. The initial frequency of inspection is set down in Table 18.6.1 which is subject to change depending on the 'tollgate" protocol explained below.

The visual inspection of the steel components and structures will include the following:

- All internal surfaces for corrosion and integrity
- All other surfaces for dents scratches, gouges, or other damage.

18.11 LEARNING BASED AMP

The "tollgate" approach is based on NEI's report [18.0.2]. Tollgates are established to evaluate aging management feedback and perform a safety assessment that confirms the safe storage of spent nuclear fuel. The impact of the aggregate feedback will be assessed as it pertains to components at the ISFSI and actions taken as necessary, such as:

- Adjustment of aging-related degradation monitoring and inspection programs in AMPs described in the foregoing
- Modification of testing frequency based on operating experience
- Performance of mitigation activities

Each tollgate assessment should address the following elements:

- Utilize the performance criteria outlined below to evaluate the aging management program
- Correlate the performance criteria in the license application with one or more of the applicable ten program elements. It is not necessary to evaluate all ten elements; however, particular attention should be focused on the detection of aging effects (element 4), corrective action (element 7), and operating experience (element 10) as a minimum
- Perform a review of plant-specific and industry operating experience to confirm the effectiveness of aging management programs, utilizing the INPO database described below
- Use the following criteria to arrive at a conclusion regarding "effective"
    - Aging management program implementing activities are completed as scheduled
    - Industry and site-specific operating experience is routinely evaluated and program adjustments are made as necessary
    - Self-assessments are conducted and program adjustments are made as necessary.
    - No significant findings are identified from external assessments or internal audits.
- Ineffective programs or ineffective elements of programs would be addressed in the site's corrective action program
- Document the results of the effectiveness reviews, summarize in a tollgate assessment, and maintain as records available for audit and NRC inspection.

ISFSI's tollgates are shown in Table 18.11.1. Note that the implementation of these tollgates does not infer that ISFSI will wait until one of these designated times to evaluate information. ISFSI will continue to follow existing processes for addressing emergent issues, including the use of the corrective action program on site. These tollgates are specific times where an aggregate of information will be evaluated as a whole.

Table 18.11.1: Tollgate Assessments for HI-STORE ISFSI

Tollgate	Year	Assessment
1	See Note [1]	Perform an assessment of the AMP effectiveness considering the criteria in the license renewal application. It is not necessary to evaluate all ten elements; however, particular attention should be focused on the detection of aging effects (element 4), corrective action (element 7), and operating experience (element 10) as a minimum. This assessment should include information from the INPO AMID.
2	Tollgate 1 Year + 5	Evaluate additional information gained from the AMID and subsequent AMP inspections to update the assessment listed in Tollgate 1, to ensure continued AMP effectiveness.
3	Tollgate 2 Year + 5	Evaluate additional information gained from the AMID and subsequent AMP inspections to update the assessment listed in Tollgate 2, to ensure continued AMP effectiveness.
4	Tollgate 3 Year + 5	Evaluate additional information gained from the AMID and subsequent AMP inspections to update the assessment listed in Tollgate 3, to ensure continued AMP effectiveness.
5	Tollgate 4 Year + 5	Evaluate additional information gained from the AMID and subsequent AMP inspections to update the assessment listed in Tollgate 4, to ensure continued AMP effectiveness.
6	Tollgate 5 Year + 5	Evaluate additional information gained from the AMID and subsequent AMP inspections to update the assessment listed in Tollgate 5, to ensure continued AMP effectiveness.
7	Tollgate 6 Year + 5	Evaluate additional information gained from the AMID and subsequent AMP inspections to update the assessment listed in Tollgate 6, to ensure continued AMP effectiveness.
8	Tollgate 7 Year + 5	Evaluate additional information gained from the AMID and subsequent AMP inspections to update the assessment listed in Tollgate 7, to ensure continued AMP effectiveness.

Notes:
(1) The calendar year when the first MPC (37 or 89) completes 20 years of service life. If the first canister at HI-STORE already exceeds 20 years of service life, then the calendar year is the year of first canister placed in a VVM at HI-STORE.

18.12 TIMING OF AGING MANAGEMENT IMPLEMENTATION

18.12.1 Canisters

Based on the fact that canisters will be arriving at the HI-STORE CIS that may have been stored for extended period of time at other sites, it is important to identify when aging management will be performed. Regardless of when aging management begins, the canisters will still be required to undergo the acceptance testing described in Chapters 3 and 10.

Canister Age Less than 20 Years

If the canister arrives at HI-STORE at a date less than 20 years from the date of first being placed on a storage pad, aging management is not required. Once the canister reaches 20 years from first being placed on a storage pad, the aging management activities described in this chapter are implemented. The canister is added to all other canisters undergoing aging management and the selection criteria given in this chapter are utilized to determine which canisters need to be inspected.

Canister Age Greater than 20 Years

If the canister arrives at HI-STORE at a date greater than 20 years from the date of first being placed on a storage pad, the canister is added to the list of canisters undergoing aging management immediately. The selection criteria given in this chapter are utilized to determine which canisters need to be inspected.

18.12.2 All Other SSCs

For all other SSCs, which are constructed exclusively for the HI-STORE facility, the aging management activities described in this chapter are implemented once the SSC reaches 20 years from use for first loading. These may be separate dates for groups of HI-STORM UMAX VVMs, as the construction of HI-STORE is designed to be performed in stages.

Chapter 10 of HI-STORE SAR discusses the operations and maintenance procedures established for the equipment and lifting ancillaries used at HI-STORE CIS facility. The preoperational and startup testing programs, and other tests and inspections of ISFSI equipment are located in Section 10.2.2, and the normal operations and maintenance procedures are located in Section 10.3 of Chapter 10. Maintenance activities will be performed on brand new equipment and devices for 20 years prior to introduction of aging management, and it will be a combination of maintenance and aging management from thereon.

As mentioned earlier, maintenance activities at the ISFSI will be carried out on dates of different frequency. Overlapping of maintenance activity and aging management program may be expected at a future date. Hence, if aging management is scheduled within 1 year of a maintenance program, certain inspection activities may not need to be repeated, but the conditions of the SSC/device will have to meet the acceptance criteria per AMP.

18.13 AMELIORATING THE RISK OF CANISTER DEGRADATION OVER A LONG-TERM STORAGE DURATION

Industry data on SSC attack on austenitic stainless steels indicates that wet surfaces are more vulnerable to attack than dry surfaces. Maintaining the proximate air's relative humidity below 20%, as noted above, helps mitigate the risk of SCC. Noting that the canister's internal heat generation rate will decrease exponentially with the passage of time, its surface will get progressively cooler. After a long period in storage, the canister's surface may cool off sufficiently to allow moisture to reside on it. From the SCC perspective, this is not a welcome situation. To address this perverse effect of canister cool down, Holtec proposes to seek a license amendment at a later date that will permit the inlet and/or outlet ventilation passages to be progressively constricted so that the canister's surface remains warm and moisture free.

This approach is a part of the long-term AMP (many decades from now) that Holtec International expects to formalize and submit to the NRC for review.

18.14 RECOVERY PLAN

The AMP described in this chapter has been configured to provide an advance warning of the potential of loss of Confinement integrity in a loaded canister. The accelerated coupon testing and, if the coupon testing indicates onset of nucleation on the canister surface, then a comprehensive canister wall integrity determination using eddy current testing provide a reliable strategy to predict the risk of leakage well before such a problem would materialize.

Nevertheless, it is deemed prudent to have the ability to isolate an at-risk canister before leakage occurs. Towards this end, Holtec will insure that a HI-STAR 190 transport cask can be brought to the HI-STORE CIS site within 30 days after the site's Emergency Response organization identifies such a need.

Finally, it should be noted that there is adequate cross sectional and vertical space available in the VVM cavity to accommodate a highly conductive sequestration canister with a gasketed lid that can be used to isolate a leaking canister from the environment. Such a sequestration canister can be installed using the canister Transfer Facility using a set of steps that are ALARA. This sequestration canister will provide a defense-in-depth measure (in addition to the transport cask which provides a high integrity containment boundary) for dealing with an extenuating situation involving the likelihood of an impending canister leak at the HI-STORE CIS site.

CHAPTER 19: CONSOLIDATED REFERENCES

References cited throughout this SAR are compiled in this chapter. Each reference may be cited multiple times in multiple chapters. The context of the citation delineates the extent of reliance in this SAR on any particular reference. No reference, unless so stated, is invoked in its entirety. Each reference is identified by a decimal system (its native chapter. Section, and numeric sequence) and is enclosed in square brackets throughout this document. All Holtec origin documents are proprietary subject to 10CFR2.390 protection from dissemination except for Safety Analysis Reports which are available in redacted version in the Public Document Room. The unabridged version of any referenced Holtec document is shared with the USNRC upon request.

[1.0.1] Report to the Secretary of Energy, "Blue Ribbon Commission on America's Nuclear Future", January 2012. (https://energy.gov/sites/prod/files/2013/04/f0/brc_finalreport_jan2012.pdf)

[1.0.2] USNRC Regulatory Guide 3.50 "Standard Format and Content for a Specific License Application for an Independent Spent Fuel Storage Installation or Monitored Retrievable Storage Facility", Revision 2, September 2014.

[1.0.3] USNRC NUREG-1567, "Standard Review Plan for Spent Fuel Dry Storage Facilities", March 2000.

[1.0.4] "Environmental Report on The HI-STORE CIS Facility", Holtec Report 2167521, dated March 2017

[1.0.5] 10 CFR Part 72, "Licensing Requirements for the Independent Storage of Spent Nuclear Fuel, High-level Radioactive Waste, and Reactor-Related Greater than Class C Waste", Title 10 of the Code of Federal Regulations- Energy, Office of the Federal Register, Washington, D.C.

[1.0.6] USNRC Docket 72-1040, "Final Safety Analysis Report on The HI-STORM UMAX Canister Storage System", Holtec Report No. HI-2115090, Revision 3. Submitted with Holtec Letter 5021032 (ML16193A336), dated June 30, 3016

[1.2.1] "Aging Assessment and Management Program for HI-STORE CIS", Holtec Report 2167378, Revision 0, dated March 2017

[1.2.2] NUREG/CR-6407, "Classification of Transportation Packaging and Dry Spent Fuel Storage System Components According to Importance to Safety", U.S. Nuclear Regulatory Commission, February 1996.

[1.2.3] ANSI/NSF Standard 61, "Drinking Water System Components – Health Effects", 2013.

[1.2.4] ANSI N14.6-1993, "American National Standard for Radioactive Materials - Special Lifting Devices for Shipping Containers Weighing 10,000 Pounds (4,500 Kg) or More", American National Standards Institute, Inc., Washington D.C., June 1993.

[1.2.5] Interim Staff Guidance (ISG) – 2, "Fuel Retrievability", Revision 1, February 22, 2010.

[1.2.6] Interim Staff Guidance (ISG) – 3, "Post Accident Recovery and Compliance with 10 CFR 72.122(l)"

[1.2.7] NUREG 0612, "Control of Heavy Loads at Nuclear Power Plants", U.S. Nuclear Regulatory Commission, Washington, D.C., July 1980.

[1.3.1] 10 CFR Part 50, "Domestic Licensing of Production and Utilization Facilities", Title 10 of the Code of Federal Regulations, Office of the Federal Register, Washington, D.C.

[1.3.2] 10CFR Part 71, "Packaging and Transportation of Radioactive Material", Title 10 of the Code of Federal Regulations, Office of the Federal Register, Washington, D.C.

[1.3.3] USNRC Docket 72-1014, "Final Safety Analysis Report for the HI-STORM 100 Cask System", Holtec Report No. HI-2002444, Revision 14.

[1.3.4] USNRC Docket 72-1008, "Final Safety Analysis Report for the HI-STAR 100 Cask System", Holtec Report No. HI-2012610, Revision 3.

[1.3.5] USNRC Docket 71-9261, "Safety Analysis Report on the HI-STAR 100 Cask System", Holtec Report No. 951251, Revision 15.

[1.3.6] USNRC Docket 71-9373, "Safety Analysis Report on the HI-STAR 190 Package", Holtec Report No. 2146214, Revision 0.D.

[1.3.7] USNRC Docket 72-1032, "Final Safety Analysis Report on the HI-STORM FW System", Holtec Report No. HI-2114830, Revision 4.

[2.1.1] Eddy-Lea Energy Alliance. *Memorandum of Agreement with Holtec International*. April 2016.

[2.1.2] New Mexico Board of Finance. "Action Taken: Board of Finance Meeting." Governor's Cabinet Room – Fourth Floor, State Capitol Building – Santa Fe, New Mexico. July 19, 2016.

[2.1.3] Eddy-Lea Energy Alliance. *GNEP Siting Study*. 2007. (https://curie.ornl.gov/system/files/EDDY_LEA_Siting_Study_ML102440738.pdf)

[2.1.4] United States Department of Agriculture, Natural Resources Conservation Service (USDA/NRCS). 2016. Soil Survey Geographic (SSURGO) Database for Lea County, New Mexico. Soil Survey Staff, Natural Resources Conservation Service, United States Department of Agriculture. Available at: http://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx , Accessed September 30, 2016.

[2.1.5] Dick-Peddie, W.A., W.H. Moir, and R. Spellberg. New Mexico Vegetation: Past, Present and Future. Albuquerque, NM: University of New Mexico Press.

[2.1.6] Federal Emergency Management Agency (FEMA). Flood Insurance Study, Lea County, New Mexico and Incorporated Areas. December 16, 2008.

[2.1.7] FEMA. FEMA Flood Map Service Center. Available at: http://msc.fema.gov/portal/search?AddressQuery=Lea%20County%2C%20new%20mexico#searchresultsanchor. Accessed October 2016.

[2.1.8] Holtec International. *Data Call for the CISF Environmental Report*. September 2016.

[2.1.9] U.S. Census Bureau (USCB). Table B01003, Total Population, American Community Survey 5-Year Estimates. Available at: http://factfinder.census.gov/bkmk/Table/1.0/en/ACS/11_5YR/B01003/0400000US35|0400000US48|0500000US35015|0500000US35025|0500000US48003|0500000US48165. Accessed on October 19, 2016.

[2.1.10] New Mexico Department of Workforce Solutions (NMDWS). New Mexico Annual Social and Economic Indicator, Statistical Abstract for Data Users, 2015. Available at: https://www.dws.state.nm.us/Portals/0/DM/LMI/ASEI_2015.pdf.

[2.1.11] Texas Demographic Center (Texas). Texas Population Projections. Available at: http://txsdc.utsa.edu/data/TPEPP/Projections/Index. Accessed on October 19, 2016.

[2.1.12] U.S. Census Bureau (USCB). Table GCT-PH1, Population, Housing Units, Area, and Density: 2010 – County, 2010 Census Summary File 1. Available at: http://factfinder.census.gov/bkmk/Table/1.0/en/DEC/10_SF1/GCTPH1.CY07/0500000US35015|0500000US35025|0500000US48003|0500000US48165.

[2.1.13] Environmental Justice Screen (EJSCREEN). EPA's Environmental Justice Screening and Mapping Tool (Version 2016). Location with 50-mile buffer. Available at: https://ejscreen.epa.gov/mapper/. Accessed on October 14, 2016.

[2.1.14] International Isotopes Fluorine Products, Inc. (IIFP). Fluorine Extraction Process & Depleted Uranium De-conversion Plant (FEP/DUP) Environmental Report. December 27, 2009.

[2.1.15] CEHMM. "Holtec HI-Store Facility Area GIS Conflict Analysis." October 7, 2016.

[2.2.1] Department of Energy (DOE). *Waste Isolation Pilot Plant Disposal Phase Final Supplemental Environmental Impact Statement.* DOE/EIS-0026-S2. September. Available at: http://energy.gov/nepa/eis-0026-s2-waste-isolation-pilot-plant-disposal-phase-carlsbad-new-mexico.

[2.2.2] DOE. *Waste Isolation Pilot Plant Annual Site Environmental Report for 2014.* DOE/WIPP-15-8866. September 2015.

[2.2.3] NRC. *Environmental Impact Statement for the Proposed National Enrichment Facility in Lea County, New Mexico*. NUREG-1790. June 2005.

[2.2.4] NRC. *Environmental Impact Statement for the Proposed Fluorine Extraction Process and Depleted Uranium Deconversion Plant in Lea County, New Mexico.* NUREG-2113. August 2012.

[2.2.5] Waste Control Specialists. "WCS Consolidated Interim Spent Fuel Storage Facility Environmental Report." May 2016. (Compiled from ADAMS Numbers: ML16133A137, ML16133A161, ML16133A158, ML16133A139, ML16133A162, ML16133A153, ML16133A151, ML16133A146, ML16133A145, ML16133A144, ML16133A143, ML16133A142, ML16133A099)

[2.3.1] Western Regional Climate Center Hobbs, Lea County Airport data. Available at: http://www.wrcc.dri.edu/cgi-bin/cliMAIN.pl?nm4028. Accessed on October 14, 2016.

[2.3.2] Holzworth, G.C. Mixing Heights, Wind Speeds, and Potential for Urban Air Pollution Throughout The Contiguous United States. January 1972.

[2.3.3] Greer. American Meteorological Society. Glossary of Weather and Climate. 1996.

[2.3.4] National Oceanic and Atmospheric Administration (NOAA). Enhanced F Scale for Tornado Damage. Available at: http://www.spc.noaa.gov/faq/tornado/ef-scale.html. Accessed on October 14, 2016.

[2.3.5] Tornado history. Available at: http://www.tornadohistoryproject.com/tornado/New-Mexico/. October 14, 2016.

[2.4.1] NRC. Safety Evaluation Report for the International Isotopes Fluorine Products, Inc. Fluorine Extraction Process and Depleted Uranium Deconversion Plant in Lea County, New Mexico. NUREG-2116. May 2012.

[2.4.2] Bonnin, M., D. Martin, B. Lin, T. Parzybok, M. Yekta, and D. Riley, "Precipitation Frequency Atlas of the United States: NOAA Atlas 14, Volume 1: Semiarid Southwest (Arizona, Southeast California, Nevada, New Mexico, Utah)," Version 5.0, Silver Spring, MD: U.S. Department of Commerce, National Oceanic and Atmospheric Administration, National Weather Service, 2011.

[2.5.1] New Mexico Office of the State Engineer (NMOSE). Declared Underground Water Basins Map. Available at: http://www.ose.state.nm.us/GIS/maps.php. Accessed October 2016.

[2.5.2] Nicholson, Alexander Jr. and Alfred Clebsch, Jr. 1963. Ground-water Report 6, Geology and Ground-water Condition in Southern Lea County, New Mexico. State Bureau of Mines and Mineral Resources, New Mexico Institute of Mining and Technology. 1963.

[2.6.1] Powers, D. W., Lambert, S. J., Shaffer, S. E., Hill, L. R., and Weart, W. D., eds., 1978, Geological Characterization Report for the Waste Isolation Pilot Plant (WIPP) Site,

Southeastern New Mexico. SAND78-1596, Vols. I and II. Sandia National Laboratories.

[2.6.2] Nuclear Regulatory Commission (NRC). Safety Evaluation Report for the National Enrichment Facility in Lea County, New Mexico, Louisiana Energy Services (NUREG-1827), Available at: http://www.nrc.gov/reading-rm/doc-collections/nuregs/staff/sr1827/, Accessed October 28, 2016.

[2.6.3] United States Geological Survey (USGS). Earthquake Archive Search. Available at: http://earthquake.usgs.gov/earthquakes/search/. Accessed on September 29, 2016.

[2.6.4] USGS. Earthquake Probability Mapping, 2009 PSHA Model. United States Geological Survey. Available at: http://geohazards.usgs.gov/eqprob/2009/. Accessed on October 13, 2016.

[2.6.5] Sanford A., Balch, R., and Delap S., 1993, Report 68: A Review of the Seismicity and Seismic Risk at the WIPP Site, Geoscience Department and Geophysical Research Center, New Mexico Tech. Available at: https://www.ees.nmt.edu/images/ees/Geop/nmquakes/R68/R68.HTM Accessed October 24, 2016.

[2.6.6] Safety Evaluation Report for Approval of DOE/WIPP 07-3372, Waste Isolation Pilot Plant Documented Safety Analysis, Revision 5 and DOE/WIPP 07-3373, Waste Isolation Pilot Plant Technical Safety Requirements, Revision 5

[2.6.7] USGS. Quaternary Faults in Google Earth. Available at: http://earthquake.usgs.gov/hazards/qfaults/google.php . Accessed on September 29, 2016.

[2.6.8] USGS. Geologic Hazards Map. Available at: http://geohazards.usgs.gov/hazards/apps/cmaps/ . Accessed September on 30, 2016.

[2.6.9] Mineral Lease Relinquishment Agreement between Intrepid Potash and Holtec International, October 5, 2016.

[2.6.10] 10 CFR Part 100, “Reactor Site Criteria”, Title 10 of the Code of Federal Regulations, Office of the Federal Register, Washington, D.C.

[2.7.1] Regulatory Guide 1.76, “Design Basis Tornado and Tornado Missiles for Nuclear Power Plants,” United States Nuclear Regulatory Commission, March 2007.

[2.7.2] ANSI/ANS 57.9-1992, "Design Criteria for an Independent Spent Fuel Storage Installation (Dry Type)", American Nuclear Society, LaGrange Park, IL, May 1992.

[3.0.1] ASME NOG-1, Rules for Construction of Overhead and Gantry Cranes (Top Running Bridge, Multiple Girder), American Society of Mechanical Engineers, New York, 2015.

[3.1.1] Holtec International & Eddy Lea Energy Alliance (ELEA) Underground Consolidated Interim Storage Facility – Physical Security Plan, Holtec Report HI-2177559, Latest Revision.

[3.1.2] 49 CFR 171, "General Information, Regulations, and Definitions," Title 49 of the Code of Federal Regulations – Transportation, Office of the Federal Register, Washington, D.C.

[3.1.3] 49 CFR 172, "Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, Training Requirements, and Security Plans," Title 49 of the Code of Federal Regulations – Transportation, Office of the Federal Register, Washington, D.C.

[3.1.4] 49 CFR 174, "Carriage by Rail," Title 49 of the Code of Federal Regulations – Transportation, Office of the Federal Register, Washington, D.C.

[3.1.5] 49 CFR 177, "Carriage by Public Highway," Title 49 of the Code of Federal Regulations – Transportation, Office of the Federal Register, Washington, D.C.

[4.0.1] ISG-11, "Cladding Considerations for the Transport and Storage of Spent Fuel," USNRC, Washington, DC, Revision 3, November 17, 2003.

[4.2.1] Holtec Position Paper DS-381, "Guidelines for Specifying ITS Categories," Revision 0, dated October 8, 2012

[4.2.2] Holtec Standard Procedure HSP 345, Important-to-Safety Classification Procedure.

[4.3.1] ASLB Hearings, Private Fuel Storage, LLC, Docket # 72-22-ISFSI, ASLBP 97-732-02-ISFSI, February 2005.

[4.3.2] U.S. Nuclear Regulatory Commission, Regulatory Guide 1.60, "Design Response Spectra for Seismic Design of Nuclear Power Plants," Revision 1, 1973.

[4.3.3] U.S. Nuclear Regulatory Commission, Regulatory Guide 1.92, "Combining Modal Responses and Spatial Components in Seismic Response Analysis," Revision 2, 2006.

[4.5.1] ASME Boiler and Pressure Vessel Code, Section III, Division 1, Subsection NF - Supports, 2010.

[4.5.2] Crane Manufacturer's Association of America (CMAA), Specification #70, 1988, Section 3.3.

[4.5.3] ASME Boiler and Pressure Vessel Code, Welding, Section IX, 2010.

[4.5.4] AWS D1.1:2006 Structural Welding Code – Steel, 2008.

[4.5.5] ISO 9001:2008, Quality Management Systems.

[4.5.6] American Society of Mechanical Engineers, American National Standard, Safety Standards, "Slings", ASME B30.9, 1971

[4.5.7] National Fire Protection Association (NFPA), NFPA 70, "National Electric Code".

[4.5.8] American Society of Mechanical Engineers, American National Standard, Safety Standards, "Jacks", ASME B30.1-2009.

[4.5.9] American Institute for Steel Construction (AISC), Specification for Structural Steel Buildings, Allowable Stress Design and Plastic Design, 13th Edition.

[4.5.10] ASTM D92, "Standard Test Method for Flash and Fire Points".

[4.5.11] American National Standard Institute, "Overhead and Gantry Cranes (Top Running Bridge, Single or Multiple Girder, Top Running Trolley Hoist)", ANSI B30.2, 1976.

[4.5.12] National Fire Protection Association NFPA 10-2013 Standard for Portable Fire Extinguishers.

[4.6.1] ANSI/ASCE 7-05 (formerly ANSI A58.1), "Minimum Design Loads for Buildings and Other Structures," American Society of Civil Engineers, 2006.

[4.6.2] ASCE 7-10, "Minimum Design Loads for Building and Other Structures," American Society of Civil Engineers, 2013.

[4.6.3] ASME Boiler and Pressure Vessel Code, Section II, Part D, Properties, 2010.

[4.6.4] International Building Code (IBC), International Code Council, 2015.

[5.3.1] ACI-318 (2005), Building Code Requirements for Structural Concrete (ACI 318-05) and Commentary (ACI 318R-05), American Concrete Institute, 2005.

[5.3.2] Boresi, A. et al., Advanced Mechanics of Materials, John Wiley and Sons, Third Edition.

[5.4.1] U.S. Nuclear Regulatory Commission, "Standard Review Plan Chapter 3.7.1 – Seismic Design Parameters", Revision 3, March 2007.

[5.4.2] LS-DYNA, Version 971, Livermore Software Technology, 2012.

[5.4.3] ASME BTH-1-2011, Design of Below-the-Hook Lifting Devices, January 2012.

[5.4.4] "Regulatory Guide 1.60 Time Histories Using EZ-FRISK", Holtec Report HI-2146083, Revision 2.

[5.4.5] ASCE/SEI 43-05, Seismic Design Criteria for Structures, Systems, and Components in Nuclear Facilities, American Society of Civil Engineers, 2005.

[5.4.6] "Structural Calculation Package for HI-STORE CIS Facility", Holtec Report HI-2177585, Revision 0.

[5.4.7] "Structural Calculation Package for the HI-STORM UMAX System", Holtec Report HI-2125228, Revision 9.

[5.5.1] ANSYS (Versions up to 17.1), SAS IP, Inc., 2016.

[6.4.1] FLUENT Computational Fluid Dynamics Software, Fluent, Inc., Centerra Resource Park, 10 Cavendish Court, Lebanon, NH 03766.

[6.4.2] "Topical Report on the HI-STAR/HI-STORM Thermal Model and its Benchmarking with Full-Size Cask Test Data," Holtec Report HI-992252, Revision 1, Holtec International, Marlton, NJ, 08053.

[6.4.3] "Standard for Verification and Validation in Computational Fluid Dynamics and Heat Transfer", ASME V&V 20-2009.

[6.4.4] "Procedure for Estimating and Reporting of Uncertainty due to Discretization in CFD Applications", I.B. Celik, U. Ghia, P.J. Roache and C.J. Freitas (Journal of Fluids Engineering Editorial Policy on the Control of Numerical Accuracy).

[6.4.5] Perry, Robert.H., Perry's Chemical Engineers' Handbook, Sixth Edition, Texas: McGraw-Hill, pg. 3-167, 1984.

[6.4.6] "Fuel, Weather and Considerations", United States Department of Agriculture, Forest Service Southern Region, February 1989; Technical Publication R8-TP 11.

[6.5.1] Gregory, J.J. et. al., "Thermal Measurements in a Series of Large Pool Fires", SAND85-1096, Sandia National Laboratories, (August 1987).

[6.5.2] Jakob, M. and Hawkins, G.A., "Elements of Heat Transfer," John Wiley & Sons, New York, (1957).

[6.5.3] "Evaluation of Effects of Tracked VCT Fire on HI-STORM FW System", Holtec Report HI-2135677, Latest Revision.

[6.5.4] "Thermal Analysis of HI-TRAC CS Transfer Cask", Holtec Report HI-2177553, Revision 0.

[6A.1] Darr, J.H., and S.P. Vanka, "Separated flow in a driven trapezoidal cavity", Physics Fluids A, 3, 3, 385-392, (March 1991).

[6A.2] Young, D.F. and F.Y. Tsai, "Flow characteristics in models of arterial stenoses-I steady flow", Journal of Biomechanics, 6, 395-410, (1973).

[6A.3] Coutanceau, M. and J.R. Defaye, "Circular cylinder wake configurations - A flow visualization survey", Applied Mechanics Review, 44, 6, (June 1991).

[6A.4] Braza, M.P. Chassaing and H.H. Minh, "Numerical study and physical analysis of the pressure and velocity fields in the near wake of a circular cylinder", Journal of Fluid Mechanics, 165, 79-130, (1986).

[6A.5] Hayes, R.E., K. Nandkumar and H. Nasr-El-Din, "Steady laminar flow in a 90 degree planar branch", Computers and Fluids, 17, 4, 537-553, (1989).

[6A.6] Kuehn, T.H. and R.J. Goldstein, "An experimental study of natural convection heat transfer in concentric and eccentric horizontal cylinder annuli", Journal of Heat Transfer, 100, 635-640, (1978).

[6A.7] Yucel, A., S. Acharya and M.L. Williams, "Natural convection and radiation in a square enclosure", Numerical Heat Transfer, Part A, 15, 261-278, (1989).

[6A.8] Sorensen, J.N. and T.P. Loc, "Higher-order axisymmetric Navier-Stokes Code: Description and evolution of boundary conditions", International Journal for Numerical Methods in Fluids, 9, 1517-1537, (1989).

[6A.9] Michelsen, J.A., "Modelling of laminar incompressible rotating fluid flow", AFM 86-05, Ph.D. dissertation, Department of fluid mechanics, Technical University of Denmark, (1986).

[6A.10] Eidelman, S., P. Collela and R.P. Shreeve, "Application of the Godunov method and its second-order extension to cascade flow modelling", AIAA Journal, 22, 1609-1615, (1984).

[6A.11] Karki, K.C., "A calculational procedure for viscous flows at all speeds in complex geometries", Ph.D. Thesis, U. of Minnesota, (1986).

[6A.12] Vogel, J.C. and J.K. Eaton, "Combined heat transfer and fluid dynamic measurements downstream of a backward facing step", Journal of Heat Transfer, 107, 922-929, (1985).

[6A.13] Antonopoulos, K.A., "The prediction of turbulent inclined flow in rod bundles", Computers and Fluids, 14, 4, 361-378, (1986).

[6A.14] Humphrey, T.A.C., A.M.K. Taylor and J.H. Whitelaw, "Laminar flow in a square duct of strong curvature", Journal of Fluid Mechanics, 83, 509-527, (1977).

[6A.15] Rogers, S.E., D. Kwak and C. Kiris, "Steady and Unsteady Solutions of the Incompressible Navier-Stokes Equations", AIAA Journal, 29, 4, 603-610, (April 1991).

[6A.16] Yeo, R.N., P.E. Wood and A.N. Hrymak, "A numerical study of laminar 90-degree bend duct flow with different discretization schemes", Journal of Fluid Engineering, 113, 563-568, (December 1991).

[6A.17] Bradley, D., L.A. Kwa, A.K.C. Lau, M. Missaghi and S.B. Chin, "Laminar Flamelet modelling of recirculating premixed methane and propane-air combustion", Combustion and Flame, 71, 109-122, (1988).

[6A.18] Kakac, S., R.K. Shah and W. Aung, "Handbook of single-phase convective heat transfer", Wiley interscience, NY, (1987).

[6A.19] Stanitz, J.D., W.M. Osborn and Mizisin, "An experimental investigation of secondary flow in an accelerating rectangular elbow with 90 degree turning", NACA-TN-30150, (1953).

[6A.20] EPRI, "The TN-24P PWR Spent Fuel Storage Cask: Testing and Analyses, EPRI ND-5128, April 1987.

[6A.21] "Topical Report on the HI-STAR/HI-STORM Thermal Model and its Benchmarking with Full-Size Cask Test Data", Holtec Report HI-992252, Revision 1.

[7.0.1] Safety Evaluation Report for the HI-STORM UMAX System, Amendment 0, dated April 2, 2015, ML15093A510.

[7.0.2] Safety Evaluation Report for the HI-STORM UMAX System, Amendment 1, dated September 8, 2015, ML15252A423.

[7.0.3] Safety Evaluation Report for the HI-STORM UMAX System, Amendment 2, dated January 6, 2017, ML16341B129.

[7.4.1] 10 CFR Part 20 "Standards for Protection Against Radiation," Title 10, of the Code of Federal Regulations – Energy, Office of the Federal Register, Washington, D.C.

[8.0.1] Safety Evaluation Report for the HI-STORM FW System, Amendment 0, dated July 14, 2011, ML111950325.

[8.0.2] Safety Evaluation Report for the HI-STORM FW System, Amendment 1, dated December 17, 2014, ML14351A475.

[8.0.3] Safety Evaluation Report for the HI-STORM FW System, Amendment 2, dated October 25, 2016, ML16280A302.

[10.1.1] HI-STORE CISF Specialist Training Program.

[10.1.2] ANSI N18.1. "Selection and Training of Nuclear Power Plant Personnel", American National Standards Institute, Inc., Washington D.C., 1971.

[10.3.1] 49 CFR 173, "Shippers – General Requirements for Shipments and Packagings," Title 49 of the Code of Federal Regulations – Transportation, Office of the Federal Register, Washington, D.C.

[10.3.2] American Society for Nondestructive Testing, "Personnel Qualification and Certification in Nondestructive Testing," Recommended Practice No. SNT-TC-1A, December 1992.

[10.3.3] ANSI N14.5, American National Standard for Radioactive Materials – Leakage Tests on Packages for Shipment, 2014.

[10.5.1] Holtec CISF Emergency Response Plan, Holtec Report HI-2177535, dated March 2017.

[11.1.1] *U.S. Code of Federal Regulations,* Title 10, "Energy" Part 19 "Notices, Instructions and Reports to Workers: Inspection and Investigations".

[11.1.2] U.S. Nuclear Regulatory Commission "Information Relevant to Ensuring that Occupational Radiation Exposures at Nuclear Power at Nuclear Power Stations will be As Low As Reasonably Achievable", Regulatory Guide 8.8, June 1978.

[11.1.3] U.S. Nuclear Regulatory Commission, "Operating Philosophy for Maintaining Occupational and Public Radiation Exposures As Low As is Reasonably Achievable", Regulatory Guide 8.10, Revision 2, August 2016.

[11.4.1] U.S. Nuclear Regulatory Commission "Personnel Monitoring Device – Direct-Reading Pocket Dosimeters" Regulatory Guide 8.4, Revision 1. June 2011.

[11.4.2] NUREG/CR-0041, "Manual of Respiratory Protection Against Airborne Radioactive Material" U.S. Nuclear Regulatory Commission, Revision 1. January 2001.

[12.0.1] Holtec International Quality Assurance Program, Latest Approved Revision on Docket 71-0784.

[13.3.1] Holtec Report HI-2177558, "Holtec International & Eddy Lea Energy Alliance (ELEA) Underground Consolidated Interim Storage Facility - Decommissioning Plan," dated March 2017

[13.3.2] Holtec Report HI-2177565, "Holtec International & Eddy Lea Energy Alliance (ELEA) CIS Facility - Decommissioning Cost Estimate and Funding Plan".

[13.3.3] NUREG-1757 Volume 1, "Consolidated Decommissioning Guidance".

[13.3.4] NUREG-1757 Volume 3, "Consolidated Decommissioning Guidance, Financial Assurance, Recordkeeping and Timeliness".

[13.3.5] R.S. Means, Construction Cost Data, 2017.

[15.3.1] NUREG-1536, "Standard Review Plan for Spent Fuel Dry Storage Systems at a General License Facility", Rev 1, U.S. Nuclear Regulatory Commission, Washington, DC.

[16.0.1] HI-STORM UMAX CoC, Amendments 0, 1, 2, Issued April 6, 2015, September 8, 2015 and January 9, 2017 respectively.

[16.0.2] Proposed HI-STORE CIS Facility License SNM-1051, Appendix A (Technical Specifications), Revision 0, March 31, 2017.

[17.0.1] ISG-15, "Materials Evaluation," USNRC, Washington D.C., dated January 10, 2001

[17.2.1] Morgan Thermal Ceramics Inc., Product Data Sheet for Blanket Products (Kaowool® Blanket).

[17.2.2] "Properties, Behavior and Construction Use of Controlled Low Strength Material (CLSM) (U)," Engineering Studies Research Report K-ESG-G-00004, Revision 1.0, September 2002, Geotechnical Engineering Group.

[17.2.3] "Guide Specification for Controlled Low Strength Materials (CLSM)", National Ready Mixed Concrete Association, Silver Spring, MD.

[17.3.1] ASME Boiler and Pressure Vessel Code, Section II, Part A – Ferrous Material Specifications," American Society of Mechanical Engineers, New York, NY, 2010 Edition.

[17.3.2] ASME Boiler and Pressure Vessel Code, Section III, Appendices, 2010 Edition.

[17.7.1] Reg. Guide 1.54, "Service Level I, II, and III Protective Coatings Applied to Nuclear Power Plants", Revision 2, US Nuclear Regulatory Commission, Washington, DC.

[17.7.2] ASTM D 3843-00, "Standard Practice for Quality Assurance for Protective Coatings Applied to Nuclear Facilities", ASTM International, West Conshohocken, PA.

[17.7.3] ANSI C 210-03, "Liquid Epoxy Coating Systems for the Interior and Exterior of Steel Water Pipes".

[17.7.4] ASTM D4082-10, "Standard Test Method for Effects of Gamma Radiation on Coatings for use in Nuclear Power Plants", ASTM International, West Conshohocken, PA.

[17.10.1] Rogers Corporation, Product Data Sheet for BISCO® Silicones (BF-1000 – Extra Soft Cellular Silicone).

[17.11.1] SECY-14-0072, "Final Rule: Continued Storage of Spent Nuclear Fuel," dated July 14, 2014, as supported by NUREG-2157, "Generic Environmental Impact Statement for Continued Storage of Spent Nuclear Fuel".

[18.0.1] NUREG-1927, "Standard Review Plan for Renewal of Specific Licenses and Certificates of Compliance for Dry Storage of Spent Nuclear Fuel" Revision 1 – USNRC 2016 ADAMS # ML16179A148.

[18.0.2] NEI 14-03, "Format, Content and Implementation Guidance for Dry Cask Storage Operations-Based Aging Management for Dry Cask Storage" Revision 1 – NEI 2015 ADAMS # ML15272A329.

[18.3.1] USNRC Docket 72-1014, "Final Safety Analysis Report on the HI-STORM 100 Cask System", Holtec Report No. HI-2002444, Revision 1.

[18.4.1] "MPC Surface Inspection of Diablo Canyon Power Plant", Holtec Report No. HI-2146301, Revision 2.

[18.5.1] ASTM G 30, "Standard Practice for Making and Using U-Bend Stress Corrosion Test Specimens", ASTM ,100 Barr Harbor Drive, W Conshohocken, PA 19428-2959, 1997.

[18.5.2] ASTM G 1, "Standard Practice for Preparing, Cleaning, and Evaluating Corrosion Test Specimens", ASTM 100 Barr Harbor Drive, W Conshohocken, PA 19428, 2011.

[18.5.3] ASME Section V, "Nondestructive Examination", Two Park Avenue, New York, NY 10016, 2015.