

**CERTIFICATE OF COMPLIANCE
FOR SPENT FUEL STORAGE CASKS**

The U.S. Nuclear Regulatory Commission is issuing this certificate of compliance pursuant to Title 10 of the *Code of Federal Regulations*, Part 72, "Licensing Requirements for Independent Storage of Spent Nuclear Fuel and High-Level Radioactive Waste" (10 CFR Part 72). This certificate is issued in accordance with 10 CFR 72.238, certifying that the storage design and contents described below meet the applicable safety standards set forth in 10 CFR Part 72, Subpart L, and on the basis of the Final Safety Analysis Report (FSAR) of the cask design. This certificate is conditional upon fulfilling the requirements of 10 CFR Part 72, as applicable, and the conditions specified below.

Certificate No. 1004	Effective Date (Certificate) 1/23/95	Expiration Date 1/23/2015	Docket No. 72-1004	Amendment No. 4	Amendment Effective Date 2/12/2002	Package Identification No. USA/72-1004
	Renewed Effective Date TBD	Renewed Expiration Date 1/23/2055		Revision No 1	Revision Effective Date 4/25/2017	

Issued To: (Name/Address)

TN Americas LLC
7135 Minstrel Way, Suite 300
Columbia, MD 21045

Safety Analysis Report Title

Transnuclear West, Inc., "Final Safety Analysis Report for the Standardized NUHOMS® Horizontal Modular Storage System for Irradiated Nuclear Fuel"

CONDITIONS

1. Casks authorized by this certificate are hereby approved for use by holders of 10 CFR Part 50 and 10 CFR Part 52 licenses for nuclear power reactors at reactor sites under the general license issued pursuant to 10 CFR 72.210 subject to the conditions specified by 10 CFR 72.212 and the attached technical specifications.
2. The holder of this certificate who desires to change the certificate or technical specifications shall submit an application for amendment of the certificate or technical specifications.
3. CASK:
 - a. Model Nos. Standardized NUHOMS®-24P, NUHOMS®-52B, and NUHOMS®-61BT

The two digits refer to the number of fuel assemblies stored in the dry shielded canister (DSC), the character P for pressurized water reactor (PWR) or B for boiling water reactor (BWR) is to designate the type of fuel stored, and T is to designate that the DSC is intended for transportation in a 10 CFR Part 71 approved package

b. Description

The Standardized NUHOMS® System is certified as described in the final safety analysis report (FSAR) and in the NRC's safety evaluation report (SER). The Standardized NUHOMS® System is a horizontal canister system composed of a steel dry shielded canister (DSC), a reinforced concrete horizontal storage module (HSM), and a transfer cask (TC). The welded DSC provides confinement and criticality control for the storage and transfer of irradiated fuel. The concrete module provides radiation shielding while allowing cooling of the DSC and fuel by natural convection during storage. The TC is used for transferring the DSC from/to the Spent Fuel Pool Building to/from the HSM.

**CERTIFICATE OF COMPLIANCE
FOR SPENT FUEL STORAGE CASKS**
Supplemental SheetCertificate No. 1004
Amendment No. 4, Rev. 1
Renewed Yes
Page 2 of 4

The principal component subassemblies of the DSC are the shell with integral bottom cover plate and shield plug and ram/grapple ring, top shield plug, top cover plate, and basket assembly. The shell length is fuel-specific. The internal basket assembly is composed of guide sleeves, support rods, and spacer disks. This assembly is designed to hold 24 PWR fuel assemblies, 52 BWR assemblies. An alternate basket assembly configuration consisting of assemblies of stainless steel fuel compartments held in place by basket rails and a holdown ring is designed to hold 61 BWR assemblies. The basket assembly aids in the insertion of the fuel assemblies, enhances subcriticality during loading operations, and provides structural support during a hypothetical drop accident. The DSC is designed to slide from the transfer cask into the HSM and back without undue galling, scratching, gouging, or other damage to the sliding surfaces.

The HSM is a reinforced concrete unit with penetrations located at the top and bottom of the side walls for air flow. The penetrations are protected from debris intrusions by wire mesh screens during storage operation. The DSC Support Structure, a structural steel frame with rails, is installed within the HSM module to provide for sliding the DSC in and out of the HSM and to support the DSC within the HSM.

The TC is designed and fabricated as a lifting device to meet NUREG-0612 and ANSI N14.6 requirements. It is used for transfer operations within the Spent Fuel Pool Building and for transfer operations to/from the HSM. The TC is a cylindrical vessel with a bottom end closure assembly and a bolted top cover plate. Two upper lifting trunnions are located near the top of the cask for downending/uprighting and lifting of the cask in the Spent Fuel Pool Building. The lower trunnions, located near the base of the cask, serve as the axis of rotation during downending/uprighting operations and as supports during transport to/from the Independent Spent Fuel Storage Installation (ISFSI).

With the exception of the TC, fuel transfer and auxiliary equipment necessary for ISFSI operations are not included as a part of the Standardized NUHOMS[®] System to be reviewed for a Certificate of Compliance under 10 CFR Part 72, Subpart L. Such equipment may include, but is not limited to, special lifting devices, the transfer trailer, and the skid positioning system.

c. Drawings

The drawings for the Standardized NUHOMS[®] System are contained in Appendix E and Appendix K of the FSAR.

d. Basic Components

The basic components of the Standardized NUHOMS[®] System that are important to safety are the DSC, HSM, and TC. These components are described in Section 4.2 and Appendix K, Table K.2-8 of the FSAR.

4. Fabrication activities shall be conducted in accordance with a quality assurance program as described in Section 11.0 of the FSAR.

**CERTIFICATE OF COMPLIANCE
FOR SPENT FUEL STORAGE CASKS**
Supplemental SheetCertificate No. 1004
Amendment No. 4, Rev. 1
Renewed Yes
Page 3 of 4

5. Notification of fabrication schedules shall be made in accordance with the requirements of 10 CFR 72.232(d).
6. All Standardized NUHOMS® Systems must be fabricated and used in accordance with CoC No. 1004, Amendment No. 4. Standardized NUHOMS® Systems that were previously fabricated and put into operation by general licensees in accordance with the original CoC, or Amendment Nos. 1, 2, and 3 may continue to be used under the appropriate CoC or Amendment.
7. CONTINUED USE OF PREVIOUS VERSION OF AMENDMENT NO. 4

A general licensee may continue to use the previous version of this certificate, Amendment No. 4, dated February 12, 2002, until October 22, 2017. By October 22, 2017, general licensees using Amendment No. 4, dated February 12, 2002, must have implemented the changes authorized by this revision and completed the evaluation described below.

The general licensee shall perform written evaluations before use and before applying the changes authorized by this revised certificate which establish that the cask, once loaded with spent fuel or once the changes authorized by this revised certificate have been applied will conform to the terms, conditions, and specifications of this revised certificate. The results of this review shall be documented in accordance with 10 CFR 72.212(b)(5) no later than October 22, 2017.

In applying the changes authorized by this revised certificate, the general licensee shall register each such cask with the Nuclear Regulatory Commission no later than 30 days after applying the changes authorized by the revised certificate. The registration shall include the information required by 10 CFR 72.212(b)(2).

8. FSAR UPDATE FOR RENEWED COC

The CoC holder shall submit an updated FSAR to the Commission, in accordance with 10 CFR 72.4, within 90 days of the effective date of the renewal. The updated FSAR shall reflect the changes and CoC holder commitments resulting from the review and approval of the renewal of the CoC. The CoC holder shall continue to update the FSAR pursuant to the requirements of 10 CFR 72.248.

9. 72.212 EVALUATIONS FOR RENEWED COC USE

Any general licensee that initiates spent fuel dry storage operations with the Standardized NUHOMS® Horizontal Modular Storage System after the effective date of the renewal of the CoC and any general licensee operating a Standardized NUHOMS® Horizontal Modular Storage System as of the effective date of the renewal of the CoC, including those that put additional storage systems into service after that date, shall:

- a. as part of the evaluations required by 10 CFR 72.212(b)(5), include evaluations related to the terms, conditions, and specifications of this CoC amendment as modified (i.e., changed or added) as a result of the renewal of the CoC;
- b. as part of the document review required by 10 CFR 72.212(b)(6), include a review of the FSAR changes resulting from the renewal of the CoC and the NRC Safety Evaluation Report related to the renewal of the CoC; and

**CERTIFICATE OF COMPLIANCE
FOR SPENT FUEL STORAGE CASKS**
Supplemental Sheet

Certificate No. 1004
Amendment No. 4, Rev. 1
Renewed Yes
Page 4 of 4


c. ensure that the evaluations required by 10 CFR 72.212(b)(7) and (8) capture the evaluations and review described in (a.) and (b.) of this CoC condition.

10. AMENDMENTS AND REVISIONS FOR RENEWED COC

All future amendments and revisions to this CoC shall include evaluations of the impacts to aging management activities (i.e. time-limited aging analyses and aging management programs) to assure they remain adequate for any changes to SSCs within the scope of renewal.

FOR THE NUCLEAR REGULATORY COMMISSION

John McKirgan, Chief
Spent Fuel Licensing Branch
Division of Spent Fuel Management
Office of Nuclear Material Safety
and Safeguards



Attachment: A. Technical Specifications

Dated: