



**Kraftwerk Union**

REAKTORTECHNIK

---

GKM II - M - Condensation Tests

Hand out  
for the Meeting in Bethesda  
February, 1980

8004080662

### GKM II-M Test Matrix

Test Number	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20		
Break Size (mm)	Ø 210 (RCL)		*	*																		
	Ø 190 (MSL)				*	*	*	*	*	*	*											
	Ø 110 (1/3 MSL)											*	*									
	Ø 80 (1/6 MSL)													*	*	*	*	*	*	*	*	*
Pool Temperature	24°C (75 F)				*	*							*	*								
	32°C (90 F)		*	*			*	*	*	*		*	*			*	*	*	*			
	55°C (130 F)									*	*									*	*	
Drywell Air Content	100 %		*	*	*	*	*	*	*	*	*	*	*	*	*	*	*			*	*	
	85 % (approx.)							*	*									*	*			
Repeat Test		*		*		*		*		*		*		*		*		*		*		

# TEST PERFORMANCE AND TEST RESULTS TO DATE

## 1. DESCRIPTION OF THE TEST FACILITY AND TEST PERFORMANCE

- 1.1 MSL BREAKS
- 1.2 RCL BREAKS

## 2. INSTRUMENTATION

- 2.1 OPERATING
- 2.2 TEST

## 3. MATRIX OVERVIEW

## 4. TRANSIENT TIME HISTORIES OF THE MAIN PARAMETERS

- 4.1 STEAM MASS FLUX
- 4.2 AIR CONTENT
- 4.3 DRYWELL & WETWELL PRESSURE TIME HISTORIES
- 4.4 POOL TEMPERATURES

## 5. DYNAMIC POOL PRESSURES


- 5.1 COMPRESSED PRESSURE TIME HISTORIES
- 5.2 EVALUATION PROCEDURE
- 5.3 FREQUENCY DISTRIBUTIONS
- 5.4 MEAN AND MAXIMUM VALUES
- 5.5 MAIN PARAMETRIC INFLUENCES

## 6. BRACING LATERAL LOADS

- 6.1 EVALUATION PROCEDURE
- 6.2 FREQUENCY DISTRIBUTIONS
- 6.3 MEAN AND MAXIMUM VALUES
- 6.4 DIRECTION DISTRIBUTIONS


## 7. FILM

- 7.1 VENT CLEARING
- 7.2 CONDENSATION



**GKM II-M-Condensation Tests**  
**Test Stand Schematic Diagram**

Kraftwerk Union



## GKM II-M-Condensation Tests

Test Tank

\* Normal Water Level


Fixed Parameters	SSES Single Cell	GKM II-M Test Vessel
Drywell Volume including Vents <sup>1)</sup>	77.9 m <sup>3</sup>	75.6 m <sup>3</sup>
Wetwell Free Air Volume <sup>1)</sup>	48.4 m <sup>3</sup>	47.0 m <sup>3</sup>
Drywell/Wetwell Air Volume Ratio <sup>1)</sup>	1.61	1.61
Pool Area		
small cell at containment wall	3.7 m <sup>2</sup>	3.7 m <sup>2</sup>
mean value	5.8 m <sup>2</sup>	-
Downcomer Dimensions		
Length	13.86 m	13.76 m
O. D.	0.6096 m	0.6096 m
Wall Thickness	9.5 mm	10 mm
Downcomer Submergence <sup>1)</sup>	3.66 m	3.66 m
Downcomer Clearance (exit to pool bottom)	3.35 to 3.54 m	3.63 m <sup>2)</sup>

1) at high water level (12'/3.66 m submergence)

2) at the deepest point

Comparison of fixed Parameters

Legend: P Pressure transducer  
 T Temperature transducer  
 L Water Level  
 OR Oxygen Rate




## GKM II-M-Condensation Tests


Test Instrumentation

\* Normal Water Level

- Legend: P Pressure transducer  
 T Thermocouple  
 DG Displacement Gage  
 LP Level Probe  
 LC Load Cell  
 SG Strain Gage  
 AF Air Fraction  
 AG Accelerometer Gage



Section A-B





## GKM II - M - Condensation Tests

### Test Instrumentation


\*Normal Water Level





	geprüft	ausgegeben	empfohlen
Allg.	R 523	R 523	P 141
Techn.			
Abw. G.			

R 523 - 6 - 11 - 1598	
BRMB-M	Kandrohrliebe
Druck über Aufzugsblech	R 523 - 6 - 11 - 1598
R 523	



GKM II-M-Condensation Tests

Bracing Configuration

# GKM IIM TESTING - SUSQUEHANNA SES

200 FRAMES PER SECOND

24" DOWNCOMER DIAMETER

TIME MAGNIFICATION: 8

PART I VENT CLEARING TEST NUMBER 3  
INITIAL MASS FLUX:  $250 \text{ Kg}/(\text{m}^2\text{s})$   
INITIAL POOL TEMP:  $24^\circ\text{C}$

PART I VENT CLEARING TEST NUMBER 18  
INITIAL MASS FLUX:  $40 \text{ Kg}/(\text{m}^2\text{s})$   
INITIAL POOL TEMP:  $33^\circ\text{C}$

PART II CONDENSATION TEST NUMBER 15  
TIME: 200 SECONDS AFTER TEST START  
STEAM MASS FLUX:  $16 \text{ Kg}/(\text{m}^2\text{s})$   
POOL TEMPERATURE:  $60^\circ\text{C}$

PART III CONDENSATION TEST NUMBER 15  
TIME: 300 SECONDS AFTER TEST START  
STEAM MASS FLUX:  $9 \text{ Kg}/(\text{m}^2\text{s})$   
POOL TEMPERATURE:  $65^\circ\text{C}$

GKM II M - TEST EVALUATION TO DATE  
WITH RESPECT TO SSES POOL BOUNDARY LOADS

1. INTRODUCTORY REMARKS
2. MAIN PHYSICAL PHENOMENA OBSERVED IN THE TESTS

GLOBAL BLOWDOWN HISTORY AND PARAMETERS  
PRESSURE EVENTS IN THE POOL  
OSCILLATION FREQUENCIES

3. DISCUSSION OF MULTI-VENT SYSTEM WITH RESPECT TO TEST EVALUATION
4. EVALUATION OF TESTS No. 3 TO 10 AND SELECTION OF REPRESENTATIVE PRESSURE TRACES

EVALUATION METHOD  
PRESSURE AMPLITUDES AND FREQUENCIES  
SELECTION OF TRACES

5. PRELIMINARY SYMMETRICAL POOL BOUNDARY LOADS FOR SSES
6. ANALYTICAL JUSTIFICATION OF THE LOADS AND CORRECTION OF AMPLITUDE FACTORS

# AGENDA

## SUSQUEHANNA INPLANT SUPPRESSION POOL LOAD TESTS

- INTRODUCTION - PP & L
  - TEST PLAN
  - TEST MATRIX
  - TEST RESULTS
- } DR. A. HASHEMI, SRI
- BOUNDARY PRESSURE LOADS
  - SUBMERGED STRUCTURE LOADS

## SUBMERGED STRUCTURES METHODOLOGY FOR STEAM CONDENSATION LOADINGS

- PURPOSE
  - CALCULATION PROCEDURE
  - CONCLUSION
- } T. LUM, BECHTEL

## IN-PLANT SUPPRESSION POOL LOAD TESTS

- PRESENT QUENCHER LOAD DEFINITION FOR BOTH POOL BOUNDARY AND SUBMERGED STRUCTURES CONSIDERED VERY CONSERVATIVE
  - o BUBBLES OSCILLATION "IN-PHASE"
  - o BOUNDING APPROACH TO PRESSURE AMPLITUDES AND FREQUENCIES
    - CONSERVATIVE MULTIPLIERS
- EVALUATION OF POTENTIAL LOAD REDUCTION EFFORT SHOWED THAT ACTUAL IN-PLANT TEST DATA WOULD BE REQUIRED.
- SRI DEVELOPED A MECHANISM FOR SIMULATING THE BUBBLE LOADS RESULTING FROM SRV DISCHARGE
  - o AMPLITUDE AND FREQUENCY COULD BE VARIED
  - o ONCE A GIVEN SOURCE WAS CHOSEN IT COULD READILY BE REPRODUCED
- THE SAME SOURCE COULD THEN BE USED IN KARLSTEIN UNIT CELL AND SUSQUEHANNA SUPPRESSION POOL
- WE BELIEVE THAT THE TEST DATA PROVIDES AN EXCELLENT BASIS FOR PURSUING LOAD REDUCTION
- FINAL DECISION ON OUR PURSUING THAT LOAD REDUCTION IS YET TO BE MADE