

REGULATOR INFORMATION DISTRIBUTION SYSTEM (RIDS)

ACCESSION NBR: 8207080199      DOC. DATE: 82/07/06      NOTARIZED: NO      DOCKET #  
 FACIL: 50-387 Susquehanna Steam Electric Station, Unit 1, Pennsylv      05000387  
 50-388 Susquehanna Steam Electric Station, Unit 2, Pennsylv      05000388  
 AUTH. NAME      AUTHOR AFFILIATION  
 CURTIS, N.W.      Pennsylvania Power & Light Co.  
 RECIPIENT NAME      RECIPIENT AFFILIATION  
 SCHWENCER, A.      Licensing Branch 2

SUBJECT: Submits change to draft Tech Spec 4.6.5.3, "Standby Gas treatment Sys." Marked-up Tech Specs encl.

DISTRIBUTION CODE: B001S      COPIES RECEIVED: LTR 1 ENCL 1      SIZE: 4  
 TITLE: PSAR/FSAR AMDTS and Related Correspondence

NOTES:

	RECIPIENT ID CODE/NAME	COPIES LTTR ENCL	RECIPIENT ID CODE/NAME	COPIES LTTR ENCL
	A/D LICENSNG	1 0	LIC BR #2 BC	1 0
	LIC BR #2 LA	1 0	PERCH, R. 01	1 1
INTERNAL:	ELD/HDS4	1 0	IE FILE	1 1
	IE/DEP EPDS 35	1 1	IE/DEP/EPLB 36	3 3
	MPA	1 0	NRR/DE/CEB 11	1 1
	NRR/DE/EQB 13	3 3	NRR/DE/GB 28	2 2
	NRR/DE/HGEB 30	2 2	NRR/DE/MEB 18	1 1
	NRR/DE/MTEB 17	1 1	NRR/DE/QAB 21	1 1
	NRR/DE/SAB 24	1 1	NRR/DE/SEB 25	1 1
	NRR/DHFS/HFEB40	1 1	NRR/DHFS/LQB 32	1 1
	NRR/DHFS/OLB 34	1 1	NRR/DHFS/PTRB20	1 1
	NRR/DSI/AEB 26	1 1	NRR/DSI/ASB 27	1 1
	NRR/DSI/CPB 10	1 1	NRR/DSI/CSB 09	1 1
	NRR/DSI/ETSB 12	1 1	NRR/DSI/ICSB 16	1 1
	NRR/DSI/PSB 19	1 1	NRR/DSI/RAB 22	1 1
	NRR/DSI/RSB 23	1 1	NRR/DST/LGB 33	1 1
	<u>REG FILE</u> 04	1 1	RGN1	2 2
EXTERNAL:	ACRS 41	10 10	BNL (AMDTS ONLY)	1 1
	DMB/DSS (AMDTS)	1 1	FEMA-REP DIV 39	1 1
	LPDR 03	2 2	NRC PDR 02	1 1
	NSIC 05	1 1	NTIS	1 1



[Faint, illegible text, possibly a header or introductory paragraph.]

[A vertical column of faint, illegible text, possibly a list or a specific section of the document.]

[Faint, illegible text at the bottom of the page, possibly a footer or concluding paragraph.]



Pennsylvania Power & Light Company

Two North Ninth Street • Allentown, PA 18101 • 215 / 770-5151

Norman W. Curtis  
Vice President-Engineering & Construction-Nuclear  
215 / 770-5381

July 6, 1982

Mr. A. Schwencer, Chief  
Licensing Branch No., 2  
U.S. Nuclear Regulatory Commission  
Washington, D.C. 20555

SUSQUEHANNA STEAM ELECTRIC STATION  
SGTS TECH SPEC  
ER 100450  
PLA-1171

FILE 841-2

Docket Nos. 50-387  
50-388

Dear Mr. Schwencer:

It is requested that the following change be made to the draft Technical Specifications for incorporation into the Operating License for Susquehanna Steam Electric Station, Unit 1:

Specification 4.6.5.3, Standby Gas Treatment System  
Pages 3/4 6-35 and 3/4 6-36

- Change test flowrate from 10,500 cfm,  $\pm 10\%$  to 10,100 cfm  $\pm 10\%$  as shown on Attachment 1A

Justification

The safety related flow requirement for SGTS is established by the capability to draw down the Reactor Building to 1/4" water vacuum in less than 60 seconds and to maintain that negative pressure against Reactor Building in leakage. This requirement is significantly less than the design capability of approximately 10,500 cfm which supports the containment purge function. Since it is possible for the fans to operate near the maximum capability, it is important to perform the operability tests at this value.

13001

8207080199 820706  
PDR ADOCK 05000387  
A PDR





.

.

.

.

.

.

.

0

1

9

00

1

2

3

4

5

6

7

8

9

0

1

2

3

4

5

6


7

8

9

However, actual preoperational test results show that the maximum flowrate attainable with clean filters installed is only about 10,100 cfm. The requested change reflects actual equipment capability without compromising any safety requirements.

Very Truly yours,

A handwritten signature in cursive script that reads "David P. Meyer". The signature is written in dark ink and is positioned above the typed name.


N. W. Curtis

Vice President - Engineering & Construction - Nuclear

RRS

Attachments

cc: R. L. Perch - NRC  
R. R. Bottimore - NRC



CONTAINMENT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- b. At least once per 18 months or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) following painting, fire or chemical release in any ventilation zone communicating with the subsystem by:
  - 1. Verifying that the subsystem satisfies the in-place testing acceptance criteria and uses the test procedures of Regulatory Positions C.5.a, C.5.c and C.5.d of Regulatory Guide 1.52, Revision 2, March 1978, and the system flow rate is ~~10,500~~ <sup>10,100</sup> cfm ± 10%.
  - 2. Verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978.
  - 3. Verifying a subsystem flow rate of ~~10,500~~ <sup>10,100</sup> cfm ± 10% during system operation when tested in accordance with ANSI N510-1975.
  
- c. After every 720 hours of charcoal adsorber operation by verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978.
  
- d. At least once per 18 months by:
  - 1. Verifying that the pressure drop across the combined HEPA filters and charcoal adsorber banks is less than 13 inches Water Gauge while operating the filter train at a flow rate of ~~10,500~~ <sup>10,100</sup> cfm ± 10%.
  - 2. Verifying that the filter train starts and associated dampers open on each of the following test signals:
    - a. Manual initiation from the control room, and
    - b. Simulated automatic initiation signal.
  - 3. Verifying that the filter cooling bypass and outside air dampers open and the fan start on filter cooling initiation.
  - 4. Verifying that the temperature differential across each heating coil is ≥ 17°F when tested in accordance with ANSI N510-1975.





PROOF & REVIEW COPY

CONTAINMENT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- e. After each complete or partial replacement of a HEPA filter bank by verifying that the HEPA filter banks remove greater than or equal to 99.95% of the DOP when they are tested in-place in accordance with ANSI N510-1975 while operating the system at a flow rate of ~~10,500~~ <sup>10,100</sup> cfm. ± 10%.
- f. After each complete or partial replacement of a charcoal adsorber bank by verifying that the charcoal adsorbers remove greater than 99.95% of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1975 while operating the system at a flow rate of ~~10,500~~ <sup>10,100</sup> cfm ± 10%.



*[Faint, illegible handwritten text]*