


PLANT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

1. Verifying that the subsystem satisfies the in-place penetration and bypass leakage testing acceptance criteria of less than 0.05% and uses the test procedures of Regulatory Positions C.5.a, C.5.c and C.5.d of Regulatory Guide 1.52, Revision 2, March 1978, and the system flow rate is 5810 cfm \pm 10%. 16 | 3.
 2. Verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978, for a methyl iodide penetration of less than 0.175%; and 16 | 35
 3. Verifying a subsystem flow rate of 5810 cfm \pm 10% during subsystem operation when tested in accordance with ANSI N510-1975. 16
- c. After every 720 hours of charcoal adsorber operation by verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978, for a methyl iodide penetration of less than 0.175%. 35
- d. At least once per 18 months by:
1. Verifying that the pressure drop across the combined prefilter, upstream and downstream HEPA filters and charcoal adsorber banks is less than 9.1 inches Water Gauge while operating the subsystem at a flow rate of 5810 cfm \pm 10%.
 2. Verifying that on ~~each of the below isolation mode actuation test signals~~, the subsystem automatically switches to the isolation mode of operation and the isolation dampers close within 8 seconds:
 - a) Outside air intake chlorine - high,
 - ~~b) Outside air intake radiation - high, and~~
 - ~~c) Reactor Building isolation.~~
 3. Verifying that on each of the below pressurization mode actuation test signals, the subsystem automatically switches to the pressurization mode of operation and the control structure is maintained at a positive pressure of 1/8 inch W.G. relative to the outside atmosphere during subsystem operation at a flow rate less than or equal to 5810 cfm:
 - a) Reactor Building isolation, and
 - b) Outside air intake radiation - high.
 4. Verifying that the heaters dissipate 30 \pm 3.0 Kw when tested in accordance with ANSI N510-1975.



PLANT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

1. Verifying that the subsystem satisfies the in-place penetration and bypass leakage testing acceptance criteria of less than 0.05% and uses the test procedures of Regulatory Positions C.5.a, C.5.c, and C.5.d of Regulatory Guide 1.52, Revision 2, March 1978, and the system flow rate is 5810 cfm \pm 10%.
 2. Verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978, for a methyl iodide penetration of less than 0.175%; and
 3. Verifying a subsystem flow rate of 5810 cfm \pm 10% during subsystem operation when tested in accordance with ANSI N510-1975.
- c. After every 720 hours of charcoal adsorber operation by verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978, for a methyl iodide penetration of less than 0.75%.
- d. At least once per 18 months by:
1. Verifying that the pressure drop across the combined prefilter, upstream and downstream HEPA filters and charcoal adsorber banks is less than 9.1 inches Water Gauge while operating the subsystem at a flow rate of 5810 cfm \pm 10%.
 2. Verifying that ^{on}~~on each of~~ the below isolation mode actuation test signals, the subsystem automatically switches to the isolation mode of operation and the isolation dampers close within 8 seconds:
 - a) Outside air intake chlorine - high.
 - ~~b) Outside air intake radiation - high, and~~
 - ~~c) Reactor Building isolation.~~
 3. Verifying that on each of the below pressurization mode actuation test signals, the subsystem automatically switches to the pressurization mode of operation and the control structure is maintained at a positive pressure of 1/8 inch W.G. relative to the outside atmosphere during subsystem operation at a flow rate less than or equal to 5810 cfm:
 - a) Reactor Building isolation, and
 - b) Outside air intake radiation - high.
 4. Verifying that the heaters dissipate 30 \pm 3.0 Kw when tested in accordance with ANSI N510-1975.

