

MANUAL HARD COPY DISTRIBUTION
DOCUMENT TRANSMITTAL 2017-9571

USER INFORMATION:

GERLACH*ROSEY M EEMPL#:028401 CA#: 0363

Address: NUCSA2

Phone#: 542-3194

TRANSMITTAL INFORMATION:

TO: GERLACH*ROSEY M 06/01/2017

LOCATION: USNRC

FROM: NUCLEAR RECORDS DOCUMENT CONTROL CENTER (NUCSA-2)

THE FOLLOWING CHANGES HAVE OCCURRED TO THE HARDCOPY OR ELECTRONIC MANUAL ASSIGNED TO YOU. HARDCOPY USERS MUST ENSURE THE DOCUMENTS PROVIDED MATCH THE INFORMATION ON THIS TRANSMITTAL. WHEN REPLACING THIS MATERIAL IN YOUR HARDCOPY MANUAL, ENSURE THE UPDATE DOCUMENT ID IS THE SAME DOCUMENT ID YOU'RE REMOVING FROM YOUR MANUAL. TOOLS FROM THE HUMAN PERFORMANCE TOOL BAG SHOULD BE UTILIZED TO ELIMINATE THE CHANCE OF ERRORS.

ATTENTION: "REPLACE" directions do not affect the Table of Contents, Therefore no OC will be issued with the updated material.

TSB1 - TECHNICAL SPECIFICATION BASES UNIT 1 MANUAL

REMOVE MANUAL TABLE OF CONTENTS DATE: 05/25/2017

ADD MANUAL TABLE OF CONTENTS DATE: 05/31/2017

CATEGORY: DOCUMENTS TYPE: TSB1

ID: TEXT 3.5.3

REMOVE: REV:4

ADD: REV: 5

*ADD
NRR*

CATEGORY: DOCUMENTS TYPE: TSB1
ID: TEXT LOES
REMOVE: REV:125

ADD: REV: 126

ANY DISCREPANCIES WITH THE MATERIAL PROVIDED, CONTACT DCS @ X3107 OR X3171 FOR ASSISTANCE. UPDATES FOR HARDCOPY MANUALS WILL BE DISTRIBUTED WITHIN 3 DAYS IN ACCORDANCE WITH DEPARTMENT PROCEDURES. PLEASE MAKE ALL CHANGES AND ACKNOWLEDGE COMPLETE IN YOUR NIMS INBOX UPON COMPLETION OF UPDATES. FOR ELECTRONIC MANUAL USERS, ELECTRONICALLY REVIEW THE APPROPRIATE DOCUMENTS AND ACKNOWLEDGE COMPLETE IN YOUR NIMS INBOX.

SSES MANUAL

Manual Name: TSBI

Manual Title: TECHNICAL SPECIFICATION BASES UNIT 1 MANUAL

Table Of Contents

Issue Date: 05/31/2017

<u>Procedure Name</u>	<u>Rev</u>	<u>Issue Date</u>	<u>Change ID</u>	<u>Change Number</u>
TEXT LOES Title: LIST OF EFFECTIVE SECTIONS	126	05/31/2017		
TEXT TOC Title: TABLE OF CONTENTS	23	07/02/2014		
TEXT 2.1.1 Title: SAFETY LIMITS (SLS) REACTOR CORE SLS	6	01/22/2015		
TEXT 2.1.2 Title: SAFETY LIMITS (SLS) REACTOR COOLANT SYSTEM (RCS) PRESSURE S	1	10/04/2007		
TEXT 3.0 Title: LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY	3	08/20/2009		
TEXT 3.1.1 Title: REACTIVITY CONTROL SYSTEMS SHUTDOWN MARGIN (SDM)	1	04/18/2006		
TEXT 3.1.2 Title: REACTIVITY CONTROL SYSTEMS REACTIVITY ANOMALIES	0	11/15/2002		
TEXT 3.1.3 Title: REACTIVITY CONTROL SYSTEMS CONTROL ROD OPERABILITY	3	11/16/2016		
TEXT 3.1.4 Title: REACTIVITY CONTROL SYSTEMS CONTROL ROD SCRAM TIMES	5	11/16/2016		
TEXT 3.1.5 Title: REACTIVITY CONTROL SYSTEMS CONTROL ROD SCRAM ACCUMULATORS	2	11/16/2016		
TEXT 3.1.6 Title: REACTIVITY CONTROL SYSTEMS ROD PATTERN CONTROL	4	11/16/2016		

SSES MANUAL

Manual Name: TSB1

Manual Title: TECHNICAL SPECIFICATION BASES UNIT 1 MANUAL

TEXT 3.1.7 4 11/16/2016
Title: REACTIVITY CONTROL SYSTEMS STANDBY LIQUID CONTROL (SLC) SYSTEM

TEXT 3.1.8 4 11/16/2016
Title: REACTIVITY CONTROL SYSTEMS SCRAM DISCHARGE VOLUME (SDV) VENT AND DRAIN VALVES

TEXT 3.2.1 3 11/16/2016
Title: POWER DISTRIBUTION LIMITS AVERAGE PLANAR LINEAR HEAT GENERATION RATE (APLHGR)

TEXT 3.2.2 4 11/16/2016
Title: POWER DISTRIBUTION LIMITS MINIMUM CRITICAL POWER RATIO (MCPR)

TEXT 3.2.3 3 11/16/2016
Title: POWER DISTRIBUTION LIMITS LINEAR HEAT GENERATION RATE (LHGR)

TEXT 3.3.1.1 7 11/16/2016
Title: INSTRUMENTATION REACTOR PROTECTION SYSTEM (RPS) INSTRUMENTATION

TEXT 3.3.1.2 3 11/16/2016
Title: INSTRUMENTATION SOURCE RANGE MONITOR (SRM) INSTRUMENTATION

TEXT 3.3.2.1 5 11/16/2016
Title: INSTRUMENTATION CONTROL ROD BLOCK INSTRUMENTATION

TEXT 3.3.2.2 3 11/16/2016
Title: INSTRUMENTATION FEEDWATER MAIN TURBINE HIGH WATER LEVEL TRIP INSTRUMENTATION

TEXT 3.3.3.1 10 11/16/2016
Title: INSTRUMENTATION POST ACCIDENT MONITORING (PAM) INSTRUMENTATION

TEXT 3.3.3.2 2 11/16/2016
Title: INSTRUMENTATION REMOTE SHUTDOWN SYSTEM

TEXT 3.3.4.1 3 11/16/2016
Title: INSTRUMENTATION END OF CYCLE RECIRCULATION PUMP TRIP (EOC-RPT) INSTRUMENTATION

SSES MANUAL

Manual Name: TSB1

Manual Title: TECHNICAL SPECIFICATION BASES UNIT 1 MANUAL

TEXT 3.3.4.2 1 11/16/2016
Title: INSTRUMENTATION ANTICIPATED TRANSIENT WITHOUT SCRAM RECIRCULATION PUMP TRIP (ATWS-RPT) INSTRUMENTATION

TEXT 3.3.5.1 4 11/16/2016
Title: INSTRUMENTATION EMERGENCY CORE COOLING SYSTEM (ECCS) INSTRUMENTATION

TEXT 3.3.5.2 1 11/16/2016
Title: INSTRUMENTATION REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM INSTRUMENTATION

TEXT 3.3.6.1 8 11/16/2016
Title: INSTRUMENTATION PRIMARY CONTAINMENT ISOLATION INSTRUMENTATION

TEXT 3.3.6.2 5 11/16/2016
Title: INSTRUMENTATION SECONDARY CONTAINMENT ISOLATION INSTRUMENTATION

TEXT 3.3.7.1 3 11/16/2016
Title: INSTRUMENTATION CONTROL ROOM EMERGENCY OUTSIDE AIR SUPPLY (CREOAS) SYSTEM INSTRUMENTATION

TEXT 3.3.8.1 3 11/16/2016
Title: INSTRUMENTATION LOSS OF POWER (LOP) INSTRUMENTATION

TEXT 3.3.8.2 1 11/16/2016
Title: INSTRUMENTATION REACTOR PROTECTION SYSTEM (RPS) ELECTRIC POWER MONITORING

TEXT 3.4.1 5 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RECIRCULATION LOOPS OPERATING

TEXT 3.4.2 4 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) JET PUMPS

TEXT 3.4.3 3 01/13/2012
Title: REACTOR COOLANT SYSTEM RCS SAFETY RELIEF VALVES S/RVS

TEXT 3.4.4 1 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RCS OPERATIONAL LEAKAGE

SSES MANUAL

Manual Name: TSB1

Manual Title: TECHNICAL SPECIFICATION BASES UNIT 1 MANUAL

TEXT 3.4.5	2	04/13/2016
Title: REACTOR COOLANT SYSTEM (RCS) RCS PRESSURE ISOLATION VALVE (PIV) LEAKAGE		
TEXT 3.4.6	5	11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RCS LEAKAGE DETECTION INSTRUMENTATION		
TEXT 3.4.7	3	11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RCS SPECIFIC ACTIVITY		
TEXT 3.4.8	3	11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RESIDUAL HEAT REMOVAL (RHR) SHUTDOWN COOLING SYSTEM - HOT SHUTDOWN		
TEXT 3.4.9	2	11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RESIDUAL HEAT REMOVAL (RHR) SHUTDOWN COOLING SYSTEM - COLD SHUTDOWN		
TEXT 3.4.10	5	11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RCS PRESSURE AND TEMPERATURE (P/T) LIMITS		
TEXT 3.4.11	1	11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) REACTOR STEAM DOME PRESSURE		
TEXT 3.5.1	5	11/16/2016
Title: EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM ECCS - OPERATING		
TEXT 3.5.2	1	11/16/2016
Title: EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM ECCS - SHUTDOWN		
TEXT 3.5.3	5	05/31/2017
Title: EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM RCIC SYSTEM		
TEXT 3.6.1.1	6	11/16/2016
Title: PRIMARY CONTAINMENT		
TEXT 3.6.1.2	2	11/16/2016
Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT AIR LOCK		

SSES MANUAL

Manual Name: TSBI

Manual Title: TECHNICAL SPECIFICATION BASES UNIT 1 MANUAL

TEXT 3.6.1.3	13	11/16/2016	Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT ISOLATION VALVES (PCIVS)
TEXT 3.6.1.4	2	11/16/2016	Title: CONTAINMENT SYSTEMS CONTAINMENT PRESSURE
TEXT 3.6.1.5	2	11/16/2016	Title: CONTAINMENT SYSTEMS DRYWELL AIR TEMPERATURE
TEXT 3.6.1.6	1	11/16/2016	Title: CONTAINMENT SYSTEMS SUPPRESSION CHAMBER-TO-DRYWELL VACUUM BREAKERS
TEXT 3.6.2.1	3	11/16/2016	Title: CONTAINMENT SYSTEMS SUPPRESSION POOL AVERAGE TEMPERATURE
TEXT 3.6.2.2	1	11/16/2016	Title: CONTAINMENT SYSTEMS SUPPRESSION POOL WATER LEVEL
TEXT 3.6.2.3	2	11/16/2016	Title: CONTAINMENT SYSTEMS RESIDUAL HEAT REMOVAL (RHR) SUPPRESSION POOL COOLING
TEXT 3.6.2.4	1	11/16/2016	Title: CONTAINMENT SYSTEMS RESIDUAL HEAT REMOVAL (RHR) SUPPRESSION POOL SPRAY
TEXT 3.6.3.1	2	06/13/2006	Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT HYDROGEN RECOMBINERS
TEXT 3.6.3.2	2	11/16/2016	Title: CONTAINMENT SYSTEMS DRYWELL AIR FLOW SYSTEM
TEXT 3.6.3.3	2	11/16/2016	Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT OXYGEN CONCENTRATION
TEXT 3.6.4.1	13	04/19/2017	Title: CONTAINMENT SYSTEMS SECONDARY CONTAINMENT

SSES MANUAL

Manual Name: TSB1

Manual Title: TECHNICAL SPECIFICATION BASES UNIT 1 MANUAL

TEXT 3.6.4.2	12	04/19/2017	Title: CONTAINMENT SYSTEMS SECONDARY CONTAINMENT ISOLATION VALVES (SCIVS)
TEXT 3.6.4.3	5	11/16/2016	Title: CONTAINMENT SYSTEMS STANDBY GAS TREATMENT (SGT) SYSTEM
TEXT 3.7.1	5	11/16/2016	Title: PLANT SYSTEMS RESIDUAL HEAT REMOVAL SERVICE WATER (RHRSW) SYSTEM AND THE ULTIMATE HEAT SINK (UHS)
TEXT 3.7.2	3	11/16/2016	Title: PLANT SYSTEMS EMERGENCY SERVICE WATER (ESW) SYSTEM
TEXT 3.7.3	2	11/16/2016	Title: PLANT SYSTEMS CONTROL ROOM EMERGENCY OUTSIDE AIR SUPPLY (CREOAS) SYSTEM
TEXT 3.7.4	1	11/16/2016	Title: PLANT SYSTEMS CONTROL ROOM FLOOR COOLING SYSTEM
TEXT 3.7.5	2	11/16/2016	Title: PLANT SYSTEMS MAIN CONDENSER OFFGAS
TEXT 3.7.6	3	11/16/2016	Title: PLANT SYSTEMS MAIN TURBINE BYPASS SYSTEM
TEXT 3.7.7	2	11/16/2016	Title: PLANT SYSTEMS SPENT FUEL STORAGE POOL WATER LEVEL
TEXT 3.7.8	1	11/16/2016	Title: PLANT SYSTEMS
TEXT 3.8.1	8	11/16/2016	Title: ELECTRICAL POWER SYSTEMS AC SOURCES - OPERATING
TEXT 3.8.2	0	11/15/2002	Title: ELECTRICAL POWER SYSTEMS AC SOURCES - SHUTDOWN

SSES MANUAL

Manual Name: TSB1

Manual Title: TECHNICAL SPECIFICATION BASES UNIT 1 MANUAL

TEXT 3.8.3	5	11/16/2016	Title: ELECTRICAL POWER SYSTEMS DIESEL FUEL OIL, LUBE OIL, AND STARTING AIR
TEXT 3.8.4	4	11/16/2016	Title: ELECTRICAL POWER SYSTEMS DC SOURCES - OPERATING
TEXT 3.8.5	1	12/14/2006	Title: ELECTRICAL POWER SYSTEMS DC SOURCES - SHUTDOWN
TEXT 3.8.6	2	11/16/2016	Title: ELECTRICAL POWER SYSTEMS BATTERY CELL PARAMETERS
TEXT 3.8.7	2	11/16/2016	Title: ELECTRICAL POWER SYSTEMS DISTRIBUTION SYSTEMS - OPERATING
TEXT 3.8.8	1	11/16/2016	Title: ELECTRICAL POWER SYSTEMS DISTRIBUTION SYSTEMS - SHUTDOWN
TEXT 3.9.1	1	11/16/2016	Title: REFUELING OPERATIONS REFUELING EQUIPMENT INTERLOCKS
TEXT 3.9.2	2	11/16/2016	Title: REFUELING OPERATIONS REFUEL POSITION ONE-ROD-OUT INTERLOCK
TEXT 3.9.3	1	11/16/2016	Title: REFUELING OPERATIONS CONTROL ROD POSITION
TEXT 3.9.4	0	11/15/2002	Title: REFUELING OPERATIONS CONTROL ROD POSITION INDICATION
TEXT 3.9.5	1	11/16/2016	Title: REFUELING OPERATIONS CONTROL ROD OPERABILITY - REFUELING
TEXT 3.9.6	2	11/16/2016	Title: REFUELING OPERATIONS REACTOR PRESSURE VESSEL (RPV) WATER LEVEL

SSES MANUAL

Manual Name: TSBI

Manual Title: TECHNICAL SPECIFICATION BASES UNIT 1 MANUAL

TEXT 3.9.7 1 11/16/2016
Title: REFUELING OPERATIONS RESIDUAL HEAT REMOVAL (RHR) - HIGH WATER LEVEL

TEXT 3.9.8 1 11/16/2016
Title: REFUELING OPERATIONS RESIDUAL HEAT REMOVAL (RHR) - LOW WATER LEVEL

TEXT 3.10.1 1 01/23/2008
Title: SPECIAL OPERATIONS INSERVICE LEAK AND HYDROSTATIC TESTING OPERATION

TEXT 3.10.2 1 11/16/2016
Title: SPECIAL OPERATIONS REACTOR MODE SWITCH INTERLOCK TESTING

TEXT 3.10.3 1 11/16/2016
Title: SPECIAL OPERATIONS SINGLE CONTROL ROD WITHDRAWAL - HOT SHUTDOWN

TEXT 3.10.4 1 11/16/2016
Title: SPECIAL OPERATIONS SINGLE CONTROL ROD WITHDRAWAL - COLD SHUTDOWN

TEXT 3.10.5 1 11/16/2016
Title: SPECIAL OPERATIONS SINGLE CONTROL ROD DRIVE (CRD) REMOVAL - REFUELING

TEXT 3.10.6 1 11/16/2016
Title: SPECIAL OPERATIONS MULTIPLE CONTROL ROD WITHDRAWAL - REFUELING

TEXT 3.10.7 1 04/18/2006
Title: SPECIAL OPERATIONS CONTROL ROD TESTING - OPERATING

TEXT 3.10.8 2 11/16/2016
Title: SPECIAL OPERATIONS SHUTDOWN MARGIN (SDM) TEST - REFUELING

SUSQUEHANNA STEAM ELECTRIC STATION
LIST OF EFFECTIVE SECTIONS (TECHNICAL SPECIFICATIONS BASES)

<u>Section</u>	<u>Title</u>	<u>Revision</u>
TOC	Table of Contents.....	23
B 2.0	SAFETY LIMITS BASES	
B2.1.1	Reactor Core SLs	6
B2.1.2	Reactor Coolant System (RCS) Pressure SL.....	1
B 3.0	LCO AND SR APPLICABILITY BASES	3
B 3.1	REACTIVITY CONTROL BASES	
B3.1.1	Shutdown Margin (SDM)	2
B3.1.2	Reactivity Anomalies	1
B3.1.3	Control Rod OPERABILITY	3
B3.1.4	Control Rod Scram Times	5
B3.1.5	Control Rod Scram Accumulators.....	2
B3.1.6	Rod Pattern Control.....	4
B3.1.7	Standby Liquid Control (SLC) System	4
B3.1.8	Scram Discharge Volume (SDV) Vent and Drain Valves	4
B 3.2	POWER DISTRIBUTION LIMITS BASES	
B3.2.1	Average Planar Linear Heat Generation Rate (APLHGR).....	3
B3.2.2	Minimum Critical Power Ratio (MCPR).....	4
B3.2.3	Linear Heat Generation Rate (LHGR).....	3
B 3.3	INSTRUMENTATION	
B3.3.1.1	Reactor Protection System (RPS) Instrumentation	7
B3.3.1.2	Source Range Monitor (SRM) Instrumentation	3
B3.3.2.1	Control Rod Block Instrumentation	5
B3.3.2.2	Feedwater – Main Turbine High Water Level Trip Instrumentation	3
B3.3.3.1	Post Accident Monitoring (PAM) Instrumentation.....	10
B3.3.3.2	Remote Shutdown System	2
B3.3.4.1	End of Cycle Recirculation Pump Trip (EOC-RPT) Instrumentation.....	3
B3.3.4.2	Anticipated Transient Without Scram Recirculation Pump Trip (ATWS-RPT) Instrumentation.....	1
B3.3.5.1	Emergency Core Cooling System (ECCS) Instrumentation	4
B3.3.5.2	Reactor Core Isolation Cooling (RCIC) System Instrumentation	1
B3.3.6.1	Primary Containment Isolation Instrumentation	8
B3.3.6.2	Secondary Containment Isolation Instrumentation.....	5
B3.3.7.1	Control Room Emergency Outside Air Supply (CREOAS)	3
B3.3.8.1	Loss of Power (LOP) Instrumentation	3
B3.3.8.2	Reactor Protection System (RPS) Electric Power Monitoring.....	1

SUSQUEHANNA STEAM ELECTRIC STATION
LIST OF EFFECTIVE SECTIONS (TECHNICAL SPECIFICATIONS BASES)

<u>Section</u>	<u>Title</u>	<u>Revision</u>
B 3.4	REACTOR COOLANT SYSTEM BASES	
B3.4.1	Recirculation Loops Operating.....	5
B3.4.2	Jet Pumps	4
B3.4.3	Safety/Relief Valves (S/RVs).....	3
B3.4.4	RCS Operational LEAKAGE	1
B3.4.5	RCS Pressure Isolation Valve (PIV) Leakage.....	2
B3.4.6	RCS Leakage Detection Instrumentation.....	5
B3.4.7	RCS Specific Activity	3
B3.4.8	Residual Heat Removal (RHR) Shutdown Cooling System – Hot Shutdown	3
B3.4.9	Residual Heat Removal (RHR) Shutdown Cooling System – Cold Shutdown	2
B3.4.10	RCS Pressure and Temperature (P/T) Limits	5
B3.4.11	Reactor Steam Dome Pressure.....	1
B3.5	ECCS AND RCIC BASES	
B3.5.1	ECCS – Operating.....	5
B3.5.2	ECCS – Shutdown.....	1
B3.5.3	RCIC System.....	5
B3.6	CONTAINMENT SYSTEMS BASES	
B3.6.1.1	Primary Containment.....	6
B3.6.1.2	Primary Containment Air Lock	2
B3.6.1.3	Primary Containment Isolation Valves (PCIVs).....	13
B3.6.1.4	Containment Pressure.....	2
B3.6.1.5	Drywell Air Temperature	2
B3.6.1.6	Suppression Chamber-to-Drywell Vacuum Breakers	1
B3.6.2.1	Suppression Pool Average Temperature	3
B3.6.2.2	Suppression Pool Water Level.....	1
B3.6.2.3	Residual Heat Removal (RHR) Suppression Pool Cooling	2
B3.6.2.4	Residual Heat Removal (RHR) Suppression Pool Spray	1
B3.6.3.1	Not Used	2
B3.6.3.2	Drywell Air Flow System	2
B3.6.3.3	Primary Containment Oxygen Concentration.....	2
B3.6.4.1	Secondary Containment.....	13
B3.6.4.2	Secondary Containment Isolation Valves (SCIVs)	12
B3.6.4.3	Standby Gas Treatment (SGT) System	5

SUSQUEHANNA STEAM ELECTRIC STATION
LIST OF EFFECTIVE SECTIONS (TECHNICAL SPECIFICATIONS BASES)

<u>Section</u>	<u>Title</u>	<u>Revision</u>
B3.7	PLANT SYSTEMS BASES	
B3.7.1	Residual Heat Removal Service Water (RHRSW) System and the Ultimate Heat Sink (UHS)	5
B3.7.2	Emergency Service Water (ESW) System	3
B3.7.3	Control Room Emergency Outside Air Supply (CREOAS) System	2
B3.7.4	Control Room Floor Cooling System.....	1
B3.7.5	Main Condenser Offgas.....	2
B3.7.6	Main Turbine Bypass System	3
B3.7.7	Spent Fuel Storage Pool Water Level.....	2
B3.7.8	Main Turbine Pressure Regulation System.....	1
B3.8	ELECTRICAL POWER SYSTEMS BASES	
B3.8.1	AC Sources – Operating	8
B3.8.2	AC Sources – Shutdown.....	0
B3.8.3	Diesel Fuel Oil, Lube Oil, and Starting Air.....	5
B3.8.4	DC Sources – Operating.....	4
B3.8.5	DC Sources – Shutdown	1
B3.8.6	Battery Cell Parameters.....	2
B3.8.7	Distribution Systems – Operating	2
B3.8.8	Distribution Systems – Shutdown	1
B3.9	REFUELING OPERATIONS BASES	
B3.9.1	Refueling Equipment Interlocks	1
B3.9.2	Refuel Position One-Rod-Out Interlock.....	1
B3.9.3	Control Rod Position.....	1
B3.9.4	Control Rod Position Indication.....	0
B3.9.5	Control Rod OPERABILITY – Refueling	1
B3.9.6	Reactor Pressure Vessel (RPV) Water Level.....	2
B3.9.7	Residual Heat Removal (RHR) – High Water Level	1
B3.9.8	Residual Heat Removal (RHR) – Low Water Level.....	1
B3.10	SPECIAL OPERATIONS BASES	
B3.10.1	Inservice Leak and Hydrostatic Testing Operation.....	1
B3.10.2	Reactor Mode Switch Interlock Testing.....	1
B3.10.3	Single Control Rod Withdrawal – Hot Shutdown	1
B3.10.4	Single Control Rod Withdrawal – Cold Shutdown	1
B3.10.5	Single Control Rod Drive (CRD) Removal – Refueling	1
B3.10.6	Multiple Control Rod Withdrawal – Refueling.....	1
B3.10.7	Control Rod Testing – Operating	1
B3.10.8	Shutdown Margin (SDM) Test – Refueling.....	2

B 3.5 EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM

B 3.5.3 RCIC System

BASES

BACKGROUND The RCIC System is not part of the ECCS; however, the RCIC System is included with the ECCS section because of their similar functions.

The RCIC System is designed to operate either automatically or manually following reactor pressure vessel (RPV) isolation accompanied by a loss of coolant flow from the feedwater system to provide adequate core cooling and control of the RPV water level. Under these conditions, the High Pressure Coolant Injection (HPCI) and RCIC systems perform similar functions. The RCIC System design requirements ensure that the criteria of Reference 1 are satisfied.

The RCIC System (Ref. 2) consists of a steam driven turbine pump unit, piping, and valves to provide steam to the turbine, as well as piping and valves to transfer water from the suction source to the core via the feedwater system line, where the coolant is distributed within the RPV through the feedwater sparger. Suction piping is provided from the condensate storage tank (CST) and the suppression pool. Pump suction is normally aligned to the CST to minimize injection of suppression pool water into the RPV. However, if the CST water supply is low, an automatic transfer to the suppression pool water source ensures an adequate suction head for the pump and an uninterrupted water supply for continuous operation of the RCIC System. The steam supply to the turbine is piped from a main steam line upstream of the associated inboard main steam line isolation valve.

The RCIC System is designed to provide core cooling for a wide range of reactor pressures (165 psia to 1225 psia). Upon receipt of an initiation signal, the RCIC turbine accelerates to a specified speed. As the RCIC flow increases, the turbine control valve is automatically adjusted to maintain design flow. Exhaust steam from the RCIC turbine is discharged to the suppression pool. A full flow test line is provided to route water to the CST to allow testing of the RCIC System during normal operation without injecting water into the RPV.

(continued)

BASES

BACKGROUND
(continued) The RCIC pump is provided with a minimum flow bypass line, which discharges to the suppression pool. The valve in this line automatically opens to prevent pump damage due to overheating when other discharge line valves are closed. To ensure rapid delivery of water to the RPV and to minimize water hammer effects, the RCIC System discharge piping is kept full of water. The RCIC System is normally aligned to the CST. The RCIC discharge line is kept full of water using a "keep fill" system supplied by the condensate transfer system.

APPLICABLE SAFETY ANALSES The function of the RCIC System is to respond to transient events by providing makeup coolant to the reactor. The RCIC System is not an Engineered Safety Feature System and no credit is taken in the safety analyses for RCIC System operation. Based on its contribution to the reduction of overall plant risk, however, the system is included in the Technical Specifications, as required by the NRC Policy Statement (Ref. 4).

LCO The OPERABILITY of the RCIC System provides adequate core cooling such that actuation of any of the low pressure ECCS subsystems is not required in the even of RPV isolation accompanied by a loss of feedwater flow. The RCIC System has sufficient capacity for maintaining RPV inventory during an isolation event.

APPLICABILITY The RCIC System is required to be OPERABLE during MODE 1, and MODES 2 and 3 with reactor steam dome pressure > 150 psig, since RCIC is the primary non-ECCS water source for core cooling when the reactor is isolated and pressurized. In MODES 2 and 3 with reactor steam dome pressure ≤ 150 psig, and in MODES 4 and 5, RCIC is not required to be OPERABLE since the low pressure ECCS injection/spray subsystems can provide sufficient flow to the RPV.

ACTIONS A Note prohibits the application of LCO 3.0.4.b to an inoperable RCIC system. There is an increased risk associated with entering a MODE or other specified condition in the Applicability with an inoperable RCIC system and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

(continued)

BASES

ACTIONS
(continued)

A.1 and A.2

If the RCIC is inoperable during MODE 1, or MODE 2 or 3 with reactor steam dome pressure > 150 psig, and the HPCI System is verified to be OPERABLE, the RCIC System must be restored to OPERABLE status within 14 days. In this Condition, loss of the RCIC System will not affect the overall plant capability to provide makeup inventory at high reactor pressure since the HPCI System is the only high pressure system assumed to function during a loss of coolant accident (LOCA). OPERABILITY of HPCI is therefore verified immediately when the RCIC System is inoperable. This may be performed as an administrative check, by examining logs or other information, to determine if HPCI is out of service for maintenance or other reasons. It does not mean it is necessary to perform the Surveillances needed to demonstrate the OPERABILITY of the HPCI System. If the OPERABILITY of the HPCI System cannot be verified, however, Condition B must be immediately entered. For transients and certain abnormal events with no LOCA, RCIC (as opposed to HPCI) is the preferred source of makeup coolant because of its relatively small capacity, which allows easier control of the RPV water level. Therefore, a limited time is allowed to restore the inoperable RCIC to OPERABLE status.

The 14 day Completion Time is based on a reliability study (Ref. 3) that evaluated the impact on ECCS availability, assuming various components and subsystems were taken out of service. The results were used to calculate the average availability of ECCS equipment needed to mitigate the consequences of a LOCA as a function of allowed outage times (AOTs). Because of similar functions of HPCI and RCIC, the AOTs (i.e., Completion Times) determined for HPCI are also applied to RCIC.

B.1 and B.2

If the RCIC System cannot be restored to OPERABLE status within the associated Completion Time, or if the HPCI System is simultaneously inoperable, the plant must be brought to a condition in which the LCO does not apply. To achieve this status, the plant must be brought to at least MODE 3 within 12 hours and reactor steam dome pressure reduced to ≤ 150 psig within 36 hours. The allowed Completion Times

(continued)

BASES

ACTIONS

B.1 and B.2 (continued)

are reasonable, based on operating experience, to reach the required plant conditions from full power conditions in a orderly manner and without challenging plant systems.

SURVEILLANCE
REQUIREMENTS

SR 3.5.3.1

The flow path piping has the potential to develop voids and pockets of entrained air. Maintaining the pump discharge line of the RCIC System full of water ensures that the system will perform properly, injecting its full capacity into the Reactor Coolant System upon demand. This will also prevent a water hammer following an initiation signal. One acceptable method of ensuring the line is full is to vent at the high points. The Surveillance Frequency is controlled under the Surveillance Frequency Control Program.

SR 3.5.3.2

Verifying the correct alignment for manual, power operated, and automatic valves in the RCIC flow path provides assurance that the proper flow path will exist for RCIC operation. The SR does not apply to valves that are locked, sealed, or otherwise secured in position since these valves were verified to be in the correct position prior to locking, sealing, or securing. A valve that receives an initiation signal is allowed to be in a nonaccident position provided the valve will automatically reposition in the proper stroke time. This SR does not require any testing or valve manipulation; rather, it involves verification that those valves capable of potentially being mispositioned are in the correct position. This SR does not apply to valves that cannot be inadvertently misaligned, such as check valves. For the RCIC System, this SR also includes the steam flow path for the turbine and the flow controller position.

The Surveillance Frequency is controlled under the Surveillance Frequency Control Program.

(continued)

BASES

SURVEILLANCE
REQUIREMENTS

SR 3.5.3.3 and SR 3.5.3.4

The RCIC pump flow rates ensure that the system can maintain reactor coolant inventory during pressurized conditions with the RPV isolated. The flow tests for the RCIC System are performed at two different pressure ranges such that system capability to provide rated flow is tested both at the higher and lower operating ranges of the system. Additionally, adequate steam flow must be passing through the main turbine or turbine bypass valves to continue to control reactor pressure when the RCIC System diverts steam flow. Reactor steam pressure is considered adequate when ≥ 920 psig to perform SR 3.5.3.3 and ≥ 150 psig to perform SR 3.5.3.4. However, the requirements of SR 3.5.3.4 are met by a successful performance at any pressure ≤ 165 psig. Adequate steam flow is represented by at least 1.25 turbine bypass valves open. Therefore, sufficient time is allowed after adequate pressure and flow are achieved to perform these SRs. Reactor startup is allowed prior to performing the low pressure Surveillance because the reactor pressure is low and the time allowed to satisfactorily perform the Surveillance is short. The reactor pressure is allowed to be increased to normal operating pressure since it is assumed that the low pressure Surveillance has been satisfactorily completed and there is no indication or reason to believe that RCIC is inoperable. Therefore, these SRs are modified by Notes that state the Surveillances are not required to be performed until 12 hours after the reactor steam pressure and flow are adequate to perform the test.

The Surveillance Frequency is controlled under the Surveillance Frequency Control Program.

(continued)

BASES

SURVEILLANCE
REQUIREMENTS

SR 3.5.3.5

The RCIC System is required to actuate automatically in order to verify its design function satisfactorily. This Surveillance verifies that, with a required system initiation signal (actual or simulated), the automatic initiation logic of the RCIC System will cause the system to operate as designed, including actuation of the system throughout its emergency operating sequence; that is, automatic pump startup and actuation of all automatic valves to their required positions. This test also ensures the RCIC System will automatically restart on an RPV low water level (Level 2) signal received subsequent to an RPV high water level (Level 8) trip and that the suction is automatically transferred from the CST to the suppression pool. The LOGIC SYSTEM FUNCTIONAL TEST performed in LCO 3.3.5.2 overlaps this Surveillance to provide complete testing of the assumed safety function.

The Surveillance Frequency is controlled under the Surveillance Frequency Control Program.

This SR is modified by a Note that excludes vessel injection during the Surveillance. Since all active components are testable and full flow can be demonstrated by recirculation through the test line, coolant injection into the RPV is not required during the Surveillance.

-
- REFERENCES
1. 10 CFR 50, Appendix A, GDC 33.
 2. FSAR, Section 5.4.6.

(continued)

BASES

REFERENCES
(continued)

3. Memorandum from R. L. Baer (NRC) to V. Stello, Jr. (NRC),
"Recommended Interim Revisions to LCOs for ECCS Components,"
December 1, 1975.
 4. Final Policy Statement on Technical Specifications Improvements,
July 22, 1993 (58 FR 39132).
-