

REACTOR COOLANT SYSTEM

PORV BLOCK VALVES

LIMITING CONDITION FOR OPERATION

3.4.12 Each Power Operator Relief Valve (PORV) Block Valve shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTION:

With one or more block valve(s) inoperable, within 1 hour either restore the block valve(s) to OPERABLE status or close the block valve(s) and remove power from the block valve(s)*; otherwise, be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.4.12 Each block valve shall be demonstrated OPERABLE at least once per 92 days by operating the valve through one complete cycle of full travel.

* In lieu of closing and removing power to the block valve, the PORV may be deenergized in the closed position such that it is incapable of being opened.

REACTOR COOLANT SYSTEM

BASES

3/4.4.12 PORV BLOCK VALVES

The opening of the Power Operated Relief Valves fulfills no safety related function. The electronic controls of the PORVs must be maintained OPERABLE to ensure satisfaction of Specifications 4.5.1.d.1 and 4.5.2.d.1. Since it is impractical and undesirable to actually open the PORVs to demonstrate reclosing, it becomes necessary to verify operability of the PORV Block Valves to ensure the capability to isolate a malfunctioning PORV, or to ensure that the PORV will not be capable of malfunctioning.


STATE OF FLORIDA)
)
COUNTY OF DADE)

ss.

Robert E. Uhrig, being first duly sworn, deposes and says:

That he is a Vice President of Florida Power & Light Company,
the Licensee herein;


That he has executed the foregoing document; that the state-
ments made in this said document are true and correct to the
best of his knowledge, information, and belief, and that he
is authorized to execute the document on behalf of said
Licensee.



Robert E. Uhrig

Subscribed and sworn to before me this

3 day of August, 1981



NOTARY PUBLIC, in and for the county of Dade,
State of Florida

Notary Public, State of Florida at Large
My Commission Expires October 30, 1983
Bonded thru Maynard Bonding Agency

My commission expires: _____

