

UNITED STATES NUCLEAR REGULATORY COMMISSION

WASHINGTON, D.C. 20555-0001

FLORIDA POWER & LIGHT COMPANY

ORLANDO UTILITIES COMMISSION OF

THE CITY OF ORLANDO, FLORIDA

AND

FLORIDA MUNICIPAL POWER AGENCY

DOCKET NO. 50-389

ST. LUCIE PLANT UNIT NO. 2

AMENDMENT TO FACILITY OPERATING LICENSE

Amendment No. 81 License No. NPF-16

1. The Nuclear Regulatory Commission (the Commission) has found that:

- Α. The application for amendment by Florida Power & Light Company, et al. (the licensee), dated August 16, 1995, complies with the standards and requirements of the Atomic Energy Act of 1954, as amended (the Act) and the Commission's rules and regulations set forth in 10 CFR Chapter I:
- Β. The facility will operate in conformity with the application, the provisions of the Act, and the rules and regulations of the Commission;
- С. There is reasonable assurance (i) that the activities authorized by this amendment can be conducted without endangering the health and safety of the public, and (ii) that such activities will be conducted in compliance with the Commission's regulations;
- D. The issuance of this amendment will not be inimical to the common defense and security or to the health and safety of the public; and
- Ε. The issuance of this amendment is in accordance with 10 CFR Part 51 of the Commission's regulations and all applicable requirements have been satisfied.

960320

0389 PDR

.

н Н Н · · · * * * * x ł

1 N 7

•





2. Accordingly, Facility Operating License No. NPF-16 is amended by changes to the Technical Specifications as indicated in the attachment to this license amendment, and by amending paragraph 2.C.2 to read as follows:

2 -

2. <u>Technical Specifications</u>

The Technical Specifications contained in Appendices A and B, as revised through Amendment No. 81, are hereby incorporated in the license. The licensee shall operate the facility in accordance with the Technical Specifications.

3. This license amendment is effective as of its date of issuance and shall be implemented within 30 days.

FOR THE NUCLEAR REGULATORY COMMISSION

EV Ambro

Eugene V. Imbro, Director Project Directorate II-1 Division of Reactor Projects - I/II Office of Nuclear Reactor Regulation

Attachment: Changes to the Technical Specifications

Date of Issuance: March 20, 1996

· · •

•

ATTACHMENT TO LICENSE AMENDMENT NO. 81

TO FACILITY OPERATING LICENSE NO. NPF-16

DOCKET NO. 50-389

Replace the following page of the Appendix "A" Technical Specifications with the enclosed page. The revised page is identified by amendment number and contains a vertical line indicating the area of change. The corresponding overleaf page is also provided to maintain document completeness.

<u>Remove Page</u>	•	<u>Insert Page</u>
3/4 6-27		3/4 6-27

۹ ۹ ۹ ۹ ۹ ۹ ۹ ۹

,



SHIELD BUILDING VENTILATION SYSTEM (SBVS)

LIMITING CONDITION FOR OPERATION

3.6.6.1 Two independent Shield Building Ventilation Systems shall be OPERABLE.

APPLICABILITY: At all times in MODES 1, 2, 3, and 4. In addition, during movement of irradiated fuel assemblies or during crane operations with loads over irradiated fuel assemblies in the Spent Fuel Storage Pool in MODES 5 and 6.

ACTION:

- a. With the SBVS inoperable <u>solely</u> due to loss of the SBVS capability to provide design basis filtered air evacuation from the Spent Fuel Pool area, only ACTION-c is required. If the SBVS is inoperable for any other reason, concurrently implement ACTION-b and ACTION-c.
- b. (1) With one SBVS inoperable in MODE 1, 2, 3, or 4, restore the inoperable system to OPERABLE status within 7 days; otherwise, be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.
 - (2) With both SBVS inoperable in MODE 1, 2, 3, or 4, immediately enter LCO 3.0.3.
- c. (1) With one SBVS inoperable in any MODE, restore the inoperable system to OPERABLE status within 7 days; otherwise, suspend movement of irradiated fuel assemblies within the Spent Fuel Storage Pool and crane operations with loads over irradiated fuel in the Spent Fuel Storage Pool.
 - (2) With both SBVS inoperable in any MODE, immediately suspend movement of irradiated fuel assemblies within the Spent Fuel Storage Pool and crane operations with loads over irradiated fuel in the Spent Fuel Storage Pool.

SURVEILLANCE REQUIREMENTS

- 4.6.6.1 Each Shield Building Ventilation System shall be demonstrated OPERABLE:
 - a. At least once per 31 days on a STAGGERED TEST BASIS by initiating, from the control room, flow through the HEPA filters and charcoal adsorbers and verifying that the system operates for at least 10 hours with the heaters on.
 - b. At least once per 18 months or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) following painting, fire, or chemical release in any ventilation zone communicating with the system by:
 - 1. Performing a visual examination of SBVS in accordance with ANSI N-510-1980.

١

ب د

CONTAINMENT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- 2. Performing airflow distribution to HEPA filters and charcoal adsorbers in accordance with ANSI N-510-1980. The distribution shall be \pm 20% of the average flow per unit.
- 3. Verifying that the charcoal adsorbers remove \geq 99% of a halogenated hydrocarbon refrigerant test gas when they are tested in place in accordance with ANSI N-510-1980 while operating the system at a flow rate of 6000 cfm ± 10%.
- 4. Verifying that the HEPA filter banks remove \geq 99.825% of the DOP when they are tested in place in accordance with ANSI N-510-1980 while operating the system at a flow rate of 6000 cfm ± 10%.
- 5. Verifying a system flow rate of 6000 cfm ± 10% during system operation when tested in accordance with ANSI N-510-1980.
- c. After every 720 hours of charcoal adsorber operation by verifying within 31 days after removal that a 2-inch laboratory sample from the installed sample canisters demonstrates a removal efficiency of \geq 90% for radioactive methyl iodine and \geq 99% for radioactive elemental iodine when tested in accordance with ANSI N-510-1980 (130°C, 95% R.H.).
- d. At least once per 18 months by:
 - Verifying that the pressure drop across the demisters, electric heaters, HEPA filters, and charcoal adsorber banks is less than 8.5 inches Water Gauge (WG) while operating the system at a flow rate of 6000 cfm + 10%.
 - 2. Verifying that the system starts on a Unit 2 containment isolation signal and on a fuel pool high radiation signal.
 - 3. Verifying that the filter cooling makeup and cross connection valves can be manually opened.
 - 4. Verifying that each system produces a negative pressure of greater than or equal to 2.0 inches WG in the annulus within 99 seconds after a start signal.
 - 5. Verifying that the main heaters dissipate 30 ± 3 kW and the auxiliary heaters dissipate 1.5 ± 0.25 kW when tested in accordance with ANSI N-510-1980.

• • 1 · · ·

15

3

, , L

· • * •

•

. .

i · · · · · · ۰. ۲ ۰, 1

•