

ACCELERATED DOCUMENT DISTRIBUTION SYSTEM

REGULATOR INFORMATION DISTRIBUTION SYSTEM (RIDS)

ACCESSION NBR: 9305170162 DOC.DATE: 93/05/07 NOTARIZED: NO DOCKET #
 FACIL: 50-244 Robert Emmet Ginna Nuclear Plant, Unit 1, Rochester G 05000244
 AUTH.NAME AUTHOR AFFILIATION
 MECREY, R.C. Rochester Gas & Electric Corp.
 RECIPIENT NAME RECIPIENT AFFILIATION
 JOHNSON, A.R. Project Directorate I-3

SUBJECT: Provides addl info in support of 930420 Relief Request 23 re hydrostatic pressure test alternatives for AFW sys recirculation check valve V-4023. Operability test performed during 1993 refueling outage post-installation testing.

DISTRIBUTION CODE: A047D COPIES RECEIVED: LTR 1 ENCL 0 SIZE: 2
 TITLE: OR Submittal: Inservice/Testing/Relief from ASME Code

NOTES: License Exp date in accordance with 10CFR2,2.109(9/19/72). 05000244

	RECIPIENT		COPIES			RECIPIENT		COPIES		
	ID CODE/NAME		LTR	ENCL		ID CODE/NAME		LTR	ENCL	
	PD1-3 LA		1	0		PD1-3 PD		1	1	
	JOHNSON, A		2	2						
INTERNAL:	NRR/DE/EMEB		1	1		NUDOCS-ABSTRACT		1	1	
	OC/EMEB		1	0		OGC/HDS1		1	0	
	<u>REG. FILE</u> 01		1	1		RES MILLMAN, G		1	1	
	RES/DSIR/EIB		1	1						
EXTERNAL:	EG&G BROWN, B		1	1		EG&G RANSOME, C		1	1	
	NRC PDR		1	1		NSIC		1	1	

*Cont no
p23784683-9*

NOTE TO ALL "RIDS" RECIPIENTS:

PLEASE HELP US TO REDUCE WASTE! CONTACT THE DOCUMENT CONTROL DESK, ROOM P1-37 (EXT. 504-2065) TO ELIMINATE YOUR NAME FROM DISTRIBUTION LISTS FOR DOCUMENTS YOU DON'T NEED!

TOTAL NUMBER OF COPIES REQUIRED: LTR 15 ENCL 12



ROCHESTER GAS AND ELECTRIC CORPORATION • 89 EAST AVENUE, ROCHESTER N.Y. 14649-0001



ROBERT C. MECREDDY
Vice President
Ginna Nuclear Production

May 7, 1993

TELEPHONE
AREA CODE 716 546-2700

U.S. Nuclear Regulatory Commission
Document Control Desk
Attn: Allen R. Johnson
Project Directorate I-3
Washington, D.C. 20555

Subject: Ginna Nuclear Power Plant Inservice Inspection
Quality Assurance Manual, Appendix B
ASME Section XI Required Examinations
Relief Request #23
R.E. Ginna Nuclear Power Plant
Docket No. 50-244

Ref. (a): Letter from R. C. Mecreddy (RG&E), to A. R. Johnson (NRC),
Subject: Ginna Nuclear Power Plant, Quality Assurance
Manual, Appendix B, ASME Section XI Required
Examinations, dated April 20, 1993

Dear Mr. Johnson:

This letter provides additional information in support of the hydrostatic pressure test alternatives for the Auxiliary Feedwater System recirculation check valve V-4023 welds described in Relief Request No. 23 as referenced above.

Although the pump shutoff head from the head-capacity curve is about 1620 psi, the maximum running pressure that the check valve is subjected to in service is approximately 1425 psig. This occurs during quarterly operability testing of the downstream minimum flow recirculation valve 4291 (see P&ID 33013-1237, UFSAR Figure 10.5-1). During post installation testing for the V-4023 replacement during the 1993 refueling outage, this operability test was performed. The test included performing an ASME Section XI VT-2 examination as documented in the installation work package for SM.

We believe that this information is consistent with the information exchanged during the telecons between RG&E and Allen Johnson and Don Naujock of the NRC on April 29, 1993 and May 3, 1993.

Very truly yours,

Robert C. Mecreddy
Robert C. Mecreddy

*Cont No
P237846839*

170077

*1047
1/0*


9305170162 930507
PDR ADDCK 05000244
PDR

REJ/283
Attachment

xc: Mr. Allen R. Johnson (Mail Stop 14D1)
Project Directorate I-3
Washington, D.C. 20555

U.S. Nuclear Regulatory Commission
Region I
475 Allendale Road
King of Prussia, PA 19406

Ginna Senior Resident Inspector



f