

3/4.8 ELECTRICAL POWER SYSTEMS

3/4.8.1 A.C. SOURCES

A.C. SOURCES - OPERATING.

LIMITING CONDITION FOR OPERATION

3.8.1.1 As a minimum, the following A.C. electrical power sources shall be OPERABLE:

- a. Two physically independent circuits between the offsite transmission network and the onsite Class IE distribution system, and
- b. Three separate and independent diesel generators, each with:
 1. Separate day fuel tanks containing a minimum of 1400 gallons of fuel,
 2. A separate fuel storage system containing a minimum of 53,000 gallons of fuel for diesel generator 1 (DG-1) and 53,000 gallons of fuel for diesel generator 2 (DG-2), and 33,000 gallons of fuel for diesel generator 3 (DG-3).
 3. A separate fuel transfer pump.

APPLICABILITY: OPERATIONAL CONDITIONS 1, 2, and 3.

ACTION:


Within 1 hour

- a. With either one offsite circuit or DG-1 or DG-2 of the above required A.C. electrical power sources inoperable, demonstrate the OPERABILITY of the remaining A.C. sources by performing Surveillance Requirements 4.8.1.1.1.a and 4.8.1.1.2.a.4, for one diesel generator at a time, within 4 hours and at least once per 8 hours thereafter; restore at least two offsite circuits and DG-1 and DG-2 to OPERABLE status within 72 hours or be in at least HOT SHUTDOWN within the next 12 hours and in COLD SHUTDOWN within the following 24 hours.

Within 1 hour

- b. With one offsite circuit and DG-1 or DG-2 of the above required A.C. electrical power sources inoperable, demonstrate the OPERABILITY of the remaining A.C. sources by performing Surveillance Requirements 4.8.1.1.1.a and 4.8.1.1.2.a.4, for one diesel generator at a time, within 4 hours and at least once per 8 hours thereafter; restore at least one of the inoperable A.C. sources to OPERABLE status within 12 hours or be in at least HOT SHUTDOWN within the next 12 hours and in COLD SHUTDOWN within the following 24 hours. Restore at least two offsite circuits and DG-1 and DG-2 to OPERABLE status within 72 hours from time of initial loss or be in at least HOT SHUTDOWN within the next 12 hours and in COLD SHUTDOWN within the following 24 hours.

8312200553 831213
PDR ADCK 05000397
A PDR



ELECTRICAL POWER SYSTEMS

LIMITING CONDITION FOR OPERATION (Continued)

ACTION (Continued)

- c. With DG-3 of the above required A.C. electrical power sources inoperable, demonstrate the OPERABILITY of the remaining A.C. sources by performing Surveillance Requirements 4.8.1.1.1.a and 4.8.1.1.2.a.4, for one diesel generator at a time, within ~~8~~ ⁴ hours and at least once per 8 hours thereafter; restore the inoperable DG-3 to OPERABLE status within 72 hours or declare the HPCS system inoperable and take the ACTION required by Specification 3.5.1. *within 1 hour*
- d. With DG-1, DG-2, or DG-3 of the above required A.C. electrical power sources inoperable, in addition to ACTION a., b., or c., as applicable, verify within 2 hours that all required systems, subsystems, trains, components, and devices that depend on the remaining OPERABLE diesel generators as a source of emergency power are also OPERABLE; otherwise, be in at least HOT SHUTDOWN within the next 12 hours and in COLD SHUTDOWN within the following 24 hours.
- e. With two of the above required offsite circuits inoperable, demonstrate the OPERABILITY of three diesel generators by performing Surveillance Requirement 4.8.1.1.2.a.4 for one diesel generator at a time, within ~~4~~ ¹ hour and at least once per 8 hours thereafter, unless the diesel generators are already operating; restore at least one of the inoperable offsite circuits to OPERABLE status within 24 hours or be in at least HOT SHUTDOWN within the next 12 hours. With only one offsite circuit restored to OPERABLE status, restore at least two offsite circuits to OPERABLE status within 72 hours from time of initial loss or be in at least HOT SHUTDOWN within the next 12 hours and in COLD SHUTDOWN within the following 24 hours.
- f. With DG-1 and DG-2 of the above required A.C. electrical power sources inoperable, demonstrate the OPERABILITY of the remaining A.C. sources by performing Surveillance Requirements 4.8.1.1.1.a and 4.8.1.1.2.a.4 ² within ~~8~~ ² hours and at least once per 8 hours thereafter; restore at least one of the inoperable DG-1 and DG-2 to OPERABLE status within 2 hours or be in at least HOT SHUTDOWN within the next 12 hours and in COLD SHUTDOWN within the following 24 hours. Restore both DG-1 and DG-2 to OPERABLE status within 72 hours from time of initial loss or be in at least HOT SHUTDOWN within the next 12 hours and in COLD SHUTDOWN within the following 24 hours.

ELECTRICAL POWER SYSTEMS

SURVEILLANCE REQUIREMENTS

4.8.1.1.1 Each of the above required independent circuits between the offsite transmission network and the onsite Class 1E distribution system shall be:

- a. Determined OPERABLE at least once per 7 days by verifying correct breaker alignments and indicated power availability, and
- b. Demonstrated OPERABLE at least once per 18 months during shutdown by transferring, manually and automatically, unit power supply from the normal circuit to the alternate circuit.

4.8.1.1.2 Each of the above required diesel generators shall be demonstrated OPERABLE:

- a. In accordance with the frequency specified in Table 4.8.1.1.2-1 on a STAGGERED TEST BASIS by:
 - 1. Verifying the fuel level in the day fuel tank.
 - 2. Verifying the fuel level in the fuel storage tank.
 - 3. Verifying the fuel transfer pump starts and transfers fuel from the storage system to the day fuel tank.
 - 4. Verifying the diesel starts from ambient condition and accelerates to at least 900 rpm (60 Hz) in less than or equal to 10 seconds* for DG-1 and DG-2 and 13 seconds* for DG-3. The generator voltage and frequency shall be 4160 ± 420 volts and 60 ± 3.0 Hz within 10 seconds* for DG-1 and DG-2 and 13 seconds* for DG-3 after the start signal. The diesel generator shall be started for this test by using one of the following signals:
 - a) Manual.
 - b) Simulated loss-of-offsite power by itself.
 - c) Simulated loss-of-offsite power in conjunction with an ESF actuation test signal.
 - d) An ESF actuation test signal by itself.
 - 5. Verifying the diesel generator is synchronized, loaded to greater than or equal to 4400 kW for DG-1 and DG-2 and 2600 kW for DG-3 in less than or equal to 60 seconds*, and operates with these loads for at least 60 minutes.
 - 6. Verifying the diesel generator is aligned to provide standby power to the associated emergency busses.
 - 7. Verifying the pressure in all diesel generator air start receivers to be greater than or equal to 230 psig for DG-1 and DG-2 and 200 psig for DG-3.

- b. At least once per 31 days and after each operation of the diesel where the period of operation was greater than or equal to 1 hour by checking for and removing accumulated water from the day fuel tanks.

*

These Diesel Generator starts from ambient conditions shall be performed only once per 184 days in the surveillance test and all other engine starts for the purpose of this surveillance testing shall be preceded by an engine pre-lube period and/or other warmup procedures recommended by the manufacturer so that mechanical stress and D/G wear is minimized.

TABLE 4.8.1.1.2-1

DIESEL GENERATOR TEST SCHEDULE

<u>Number of Failures in Last 100 Valid Tests*</u>	<u>Test Frequency</u>
≤ 1	At least once per 31 days
2	At least once per 14 days
3	At least once per 7 days
≥ 4	At least once per 3 days

*Criteria for determining number of failures and number of valid tests shall be in accordance with Regulatory Position C.2.e of Regulatory Guide 1.108, Revision 1, August 1977, where the last 100 tests are determined on a per nuclear unit basis. For the purposes of this test schedule, only valid tests conducted after the OL issuance date shall be included in the computation of the "last 100 valid tests." Entry into this test schedule shall be made at the 31 day test frequency. *With the exception of the semi-annual fast start, no starting time requirements are required to meet the valid test requirements of RG 1.108.*