

SURVEILLANCE REQUIREMENTS (Continued)

- 4.7.1.2 Each auxiliary feedwater pump shall be demonstrated OPERABLE: ~~when tested pursuant to Specification 4.0.5 by:~~  
*when tested pursuant to Specification 4.0.5 by*
- a. *1* Verifying that each motor driven auxiliary feedwater pump's developed head at the test flow point is greater than or equal to the required developed head.  
*when tested pursuant to Specification 4.0.5 by*
  - b. Verifying that the turbine driven auxiliary feedwater pump's developed head at the test flow point is greater than or equal to the required developed head when the secondary steam supply pressure is greater than 310 psig. The provisions of Specification 4.0.4 are not applicable for entry into MODE 3.
  - c. *By* Verifying *at least once per 31 days* that each non-automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in its correct position.
  - d. *By* Verifying *at least once per 31 days* that each automatic valve in the flow path is in the fully open position whenever the auxiliary feedwater system is placed in automatic control or when above 10% RATED THERMAL POWER. This requirement is not applicable for those portions of the auxiliary feedwater system being used intermittently to maintain steam generator water level.
  - e. *By* Verifying at least once per 18 months during shutdown that each automatic valve in the flow path actuates to its correct position upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
  - f. *By* Verifying at least once per 18 months during shutdown that each auxiliary feedwater pump starts as designed automatically upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
  - g. *By* Verifying at least once per 18 months during shutdown that the unit cross-tie valves can cycle full travel. Following cycling, the valves will be verified to be in their closed positions.

REFUELING OPERATIONS

STORAGE POOL VENTILATION SYSTEM\*\*

LIMITING CONDITION FOR OPERATION

---

3.9.12 The spent fuel storage pool exhaust ventilation system shall be OPERABLE.

APPLICABILITY:. Whenever irradiated fuel is in the storage pool.

ACTION:

- a. With no fuel storage pool exhaust ventilation system OPERABLE, suspend all operations involving movement of fuel within the storage pool or crane operation with loads over the storage pool until at least one spent fuel storage pool exhaust ventilation system is restored to OPERABLE status.\*
- b. The provisions of Specifications 3.0.3 and 3.0.4 are not applicable.

SURVEILLANCE REQUIREMENTS

---

4.9.12 The above required fuel storage pool ventilation system shall be demonstrated OPERABLE:

- a. At least once per 31 days by initiating flow through the HEPA filter and charcoal adsorber train and verifying that the train operates for at least 15 minutes.
- b. At least once per 18 months or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) following painting, fire or chemical release in any ventilation zone communicating with the system, by:
  1. Deleted.
  2. Verifying that the charcoal adsorbers remove  $\geq 99\%$  of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1980 while operating the exhaust ventilation system at a flow rate of 30,000 cfm  $\pm 10\%$ .

\* The crane bay roll-up door and the drumming room roll-up door may be opened under administrative control during movement of fuel within the storage pool or crane operation with loads over the storage pool.

\*\* Shared system with D. C. COOK - UNIT 2.

~~This does not include the main load block. For purposes of this specification, a deenergized main load block need not be considered a load.~~

REACTOR COOLANT SYSTEM

SPECIFIC ACTIVITY

LIMITING CONDITION FOR OPERATION

3.4.8 The specific activity of the primary coolant shall be limited to:

- a. Less than or equal to 1 microCurie per gram DOSE EQUIVALENT I-131, and
- b. Less than or equal to  $100/\bar{E}$  microCuries per gram of gross radioactivity.

APPLICABILITY: MODES 1, 2, 3, 4 and 5

ACTION:

MODES 1, 2 and 3\*

- a. With the specific activity of the reactor coolant greater than 1 microCurie per gram DOSE EQUIVALENT I-131 for more than 48 hours during one continuous time interval ~~for~~ exceeding the limit line shown on Figure 3.4-1, be in HOT STANDBY with  $T_{avg}$  less than  $500^{\circ}\text{F}$  within 6 hours.
- b. With the specific activity of the reactor coolant greater than  $100/\bar{E}$  microCuries per gram, be in HOT STANDBY with  $T_{avg}$  less than  $500^{\circ}\text{F}$  within 6 hours.

MODES 1, 2, 3, 4 and 5

- a. With the specific activity of the reactor coolant greater than 1 microCurie per gram DOSE EQUIVALENT I-131 or greater than  $100/\bar{E}$  microCuries per gram, perform the sampling and analysis requirements of item 4a of Table 4.4-4 until the specific activity of the reactor coolant is restored to within its limits.

SURVEILLANCE REQUIREMENTS

4.4.8 The specific activity of the reactor coolant shall be determined to be within the limits by performance of the sampling and analysis program of Table 4.4-4.

\*With  $T_{avg}$  greater than or equal to  $500^{\circ}\text{F}$ .



2  
3

SURVEILLANCE REQUIREMENTS

4.7.1.2 Each auxiliary feedwater pump shall be demonstrated OPERABLE; ~~when tested pursuant to Specification 4.0.5 by:~~

- when tested pursuant to Specification 4.0.5 by*
- a. *1*  Verifying that each motor driven auxiliary feed pump's developed head at the test flow point is greater than or equal to the required developed head.
  - b.  Verifying that the turbine driven auxiliary feedwater pump's developed head at the test flow point is greater than or equal to the required developed head when the secondary steam supply pressure is greater than 310 psig. The provisions of Specification 4.0.4 are not applicable for entry into MODE 3.
  - c. *at least once per 31 days*  
 By Verifying that each non-automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in its correct position.
  - d. *at least once per 31 days*  
 By Verifying that each automatic valve in the flow path is in the fully open position whenever the auxiliary feedwater system is placed in automatic control or when above 10% RATED THERMAL POWER. This requirement is not applicable for those portions of the auxiliary feedwater system being used intermittently to maintain steam generator level.
  - e.  By Verifying at least once per 18 months during shutdown that each automatic valve in the flow path actuates to its correct position upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
  - f.  By Verifying at least once per 18 months during shutdown that each auxiliary feedwater pump starts as designed automatically upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
  - g.  By Verifying at least once per 18 months during shutdown that the unit cross-tie valves can cycle full travel. Following cycling, the valves will be verified to be in their closed positions.

REFUELING OPERATIONS

STORAGE POOL VENTILATION SYSTEM\*\*

LIMITING CONDITION FOR OPERATION

---

3.9.12 The spent fuel storage pool exhaust ventilation system shall be OPERABLE.

APPLICABILITY: Whenever irradiated fuel is in the storage pool.

ACTION:

- a. With no fuel storage pool exhaust ventilation system OPERABLE, suspend all operations involving movement of fuel within the storage pool or crane operation with loads over the storage pool<sup>A</sup> until at least one spent fuel storage pool exhaust ventilation system is restored to OPERABLE status.\*
- b. The provisions of Specifications 3.0.3 and 3.0.4 are not applicable.

SURVEILLANCE REQUIREMENTS

---

4.9.12 The above required fuel storage pool ventilation system shall be demonstrated OPERABLE:

- a. At least once per 31 days by initiating flow through the HEPA filter and charcoal adsorber train and verifying that the train operates for at least 15 minutes.
- b. At least once per 18 months or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) following painting, fire or chemical release in any ventilation zone communicating with the system, by:
  1. Deleted.
  2. Verifying that the charcoal adsorbers remove  $\geq 99\%$  of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1980 while operating the exhaust ventilation system at a flow rate of 30,000 cfm  $\pm 10\%$ .

\* The crane bay roll-up door and the drumming room roll-up door may be opened under administrative control during movement of fuel within the storage pool or crane operation with loads over the storage pool.

\*\* Shared system with D. C. COOK - UNIT 1.

~~This does not include the main load block. For purposes of this specification, a deenergized main load block need not be considered a load.~~

ATTACHMENT 3 TO AEP:NRC:0433P  
PROPOSED TECHNICAL SPECIFICATION PAGES



32

SURVEILLANCE REQUIREMENTS (Continued)

- 4.7.1.2 Each auxiliary feedwater pump shall be demonstrated OPERABLE:
- a. When tested pursuant to Specification 4.0.5 by verifying that each motor driven auxiliary feedwater pump's developed head at the test flow point is greater than or equal to the required developed head.
  - b. When tested pursuant to Specification 4.0.5 by verifying that the turbine driven auxiliary feedwater pump's developed head at the test flow point is greater than or equal to the required developed head when the secondary steam supply pressure is greater than 310 psig. The provisions of Specification 4.0.4 are not applicable for entry into MODE 3.
  - c. By verifying at least once per 31 days that each non-automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in its correct position.
  - d. By verifying at least once per 31 days that each automatic valve in the flow path is in the fully open position whenever the auxiliary feedwater system is placed in automatic control or when above 10% RATED THERMAL POWER. This requirement is not applicable for those portions of the auxiliary feedwater system being used intermittently to maintain steam generator water level.
  - e. By verifying at least once per 18 months during shutdown that each automatic valve in the flow path actuates to its correct position upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
  - f. By verifying at least once per 18 months during shutdown that each auxiliary feedwater pump starts as designed automatically upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
  - g. By verifying at least once per 18 months during shutdown that the unit cross-tie valves can cycle full travel. Following cycling, the valves will be verified to be in their closed positions.

STORAGE POOL VENTILATION SYSTEM\*\*

LIMITING CONDITION FOR OPERATION

3.9.12 The spent fuel storage pool exhaust ventilation system shall be OPERABLE.

APPLICABILITY: Whenever irradiated fuel is in the storage pool.

ACTION:

- a. With no fuel storage pool exhaust ventilation system OPERABLE, suspend all operations involving movement of fuel within the storage pool or crane operation with loads over the storage pool until at least one spent fuel storage pool exhaust ventilation system is restored to OPERABLE status.\*
- b. The provisions of Specifications 3.0.3 and 3.0.4 are not applicable.

SURVEILLANCE REQUIREMENTS

4.9.12 The above required fuel storage pool ventilation system shall be demonstrated OPERABLE:

- a. At least once per 31 days by initiating flow through the HEPA filter and charcoal adsorber train and verifying that the train operates for at least 15 minutes.
- b. At least once per 18 months or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) following painting, fire or chemical release in any ventilation zone communicating with the system, by:
  1. Deleted.
  2. Verifying that the charcoal adsorbers remove  $\geq 99\%$  of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1980 while operating the exhaust ventilation system at a flow rate of 30,000 cfm  $\pm 10\%$ .

---

\* The crane bay roll-up door and the drumming room roll-up door may be opened under administrative control during movement of fuel within the storage pool or crane operation with loads over the storage pool.

\*\* Shared system with Cook Nuclear Plant - Unit 2.



12

3

100

3/4 LIMITING CONDITIONS FOR OPERATION AND SURVEILLANCE REQUIREMENTS  
3/4.4 REACTOR COOLANT SYSTEM

---

SPECIFIC ACTIVITY

LIMITING CONDITION FOR OPERATION

3.4.8 The specific activity of the primary coolant shall be limited to:

- a. Less than or equal to 1 microCurie per gram DOSE EQUIVALENT I-131, and
- b. Less than or equal to  $100/\bar{E}$  microCuries per gram of gross radioactivity.

APPLICABILITY: MODES 1, 2, 3, 4 and 5

ACTION:

MODES 1, 2 and 3\*

- a. With the specific activity of the reactor coolant greater than 1 microCurie per gram DOSE EQUIVALENT I-131 for more than 48 hours during one continuous time interval or exceeding the limit line shown on Figure 3.4-1, be in HOT STANDBY with  $T_{avg}$  less than 500°F within 6 hours.
- b. With the specific activity of the reactor coolant greater than  $100/\bar{E}$  microCuries per gram, be in HOT STANDBY with  $T_{avg}$  less than 500°F within 6 hours.

MODES 1, 2, 3, 4 and 5

- a. With the specific activity of the reactor coolant greater than 1 microCurie per gram DOSE EQUIVALENT I-131 or greater than  $100/\bar{E}$  microCuries per gram, perform the sampling and analysis requirements of item 4a of Table 4.4-4 until the specific activity of the reactor coolant is restored to within its limits.

SURVEILLANCE REQUIREMENTS

4.4.8 The specific activity of the reactor coolant shall be determined to be within the limits by performance of the sampling and analysis program of Table 4.4-4.

---

\*With  $T_{avg}$  greater than or equal to 500°F.

SURVEILLANCE REQUIREMENTS

- 4.7.1.2 Each auxiliary feedwater pump shall be demonstrated OPERABLE:
- a. When tested pursuant to Specification 4.0.5 by verifying that each motor driven auxiliary feed pump's developed head at the test flow point is greater than or equal to the required developed head.
  - b. When tested pursuant to Specification 4.0.5 by verifying that the turbine driven auxiliary feedwater pump's developed head at the test flow point is greater than or equal to the required developed head when the secondary steam supply pressure is greater than 310 psig. The provisions of Specification 4.0.4 are not applicable for entry into MODE 3.
  - c. By verifying at least once per 31 days that each non-automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in its correct position.
  - d. By verifying at least once per 31 days that each automatic valve in the flow path is in the fully open position whenever the auxiliary feedwater system is placed in automatic control or when above 10% RATED THERMAL POWER. This requirement is not applicable for those portions of the auxiliary feedwater system being used intermittently to maintain steam generator level.
  - e. By verifying at least once per 18 months during shutdown that each automatic valve in the flow path actuates to its correct position upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
  - f. By verifying at least once per 18 months during shutdown that each auxiliary feedwater pump starts as designed automatically upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
  - g. By verifying at least once per 18 months during shutdown that the unit cross-tie valves can cycle full travel. Following cycling, the valves will be verified to be in their closed positions.

3/4 LIMITING CONDITIONS FOR OPERATION AND SURVEILLANCE REQUIREMENTS  
3/4.9 REFUELING OPERATIONS

---

STORAGE POOL VENTILATION SYSTEM\*\*

LIMITING CONDITION FOR OPERATION

3.9.12 The spent fuel storage pool exhaust ventilation system shall be OPERABLE.

APPLICABILITY: Whenever irradiated fuel is in the storage pool.

ACTION:

- a. With no fuel storage pool exhaust ventilation system OPERABLE, suspend all operations involving movement of fuel within the storage pool or crane operation with loads over the storage pool until at least one spent fuel storage pool exhaust ventilation system is restored to OPERABLE status.\*
- b. The provisions of Specifications 3.0.3 and 3.0.4 are not applicable.

SURVEILLANCE REQUIREMENTS

4.9.12 The above required fuel storage pool ventilation system shall be demonstrated OPERABLE:

- a. At least once per 31 days by initiating flow through the HEPA filter and charcoal adsorber train and verifying that the train operates for at least 15 minutes.
- b. At least once per 18 months or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) following painting, fire or chemical release in any ventilation zone communicating with the system, by:
  1. Deleted.
  2. Verifying that the charcoal adsorbers remove  $\geq 99\%$  of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1980 while operating the exhaust ventilation system at a flow rate of 30,000 cfm  $\pm 10\%$ .

---

\* The crane bay roll-up door and the drumming room roll-up door may be opened under administrative control during movement of fuel within the storage pool or crane operation with loads over the storage pool.

\*\* Shared system with D. C. Cook - Unit 1.

