

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>C. <u>-----NOTES-----</u>  <u>1. Not applicable during installation of the Unit 2 Division 2 CSCS isolation valve during Unit 2 Refueling 17 while Unit 2 is in MODE 4, 5, or defueled.</u>   <u>2. Not applicable during installation of the Unit 1 Division 2 CSCS isolation valve during Unit 1 Refueling 19 while Unit 1 is in MODE 4, 5, or defueled.</u>  <u>-----</u></p> <p>Required Division 3 DG inoperable.</p> <p><u>OR</u></p> <p>One required Division 1, 2, or 3 DG inoperable and the required opposite unit Division 2 DG inoperable.</p>	<p>C.1 Perform SR 3.8.1.1 for OPERABLE required offsite circuit(s).</p> <p><u>AND</u></p> <p>C.2 Declare required feature(s), supported by the inoperable DG(s), inoperable when the redundant required feature(s) are inoperable.</p> <p><u>AND</u></p> <p>C.3.1 Determine OPERABLE DG(s) are not inoperable due to common cause failure.</p> <p><u>OR</u></p> <p>C.3.2 Perform SR 3.8.1.2 for OPERABLE DG(s).</p> <p><u>AND</u></p> <p>C.4 Restore required DG(s) to OPERABLE status.</p>	<p>1 hour</p> <p><u>AND</u></p> <p>Once per 8 hours thereafter</p> <p>4 hours from discovery of Condition C concurrent with inoperability of redundant required feature(s)</p> <p>24 hours</p> <p>24 hours</p> <p>72 hours</p> <p><u>AND</u></p> <p>17 days from discovery of failure to meet LCO 3.8.1.a or b</p>

(continued)

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>F. <u>-----NOTES-----</u>  <u>1. Not applicable during installation of the Unit 2 Division 2 CSCS isolation valve during Unit 2 Refueling 17 while Unit 2 is in MODE 4, 5, or defueled.</u>   <u>2. Not applicable during installation of the Unit 1 Division 2 CSCS isolation valve during Unit 1 Refueling 19 while Unit 1 is in MODE 4, 5, or defueled.</u>   <u>-----</u></p> <p>Two required Division 1, 2, or 3 DGs inoperable.</p> <p><u>OR</u></p> <p>Division 2 DG and the required opposite unit Division 2 DG inoperable.</p>	<p>F.1 Restore one required DG to OPERABLE status.</p>	<p>2 hours</p> <p><u>OR</u></p> <p>72 hours if Division 3 DG is inoperable</p>

(continued)

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p><u>G.</u> -----NOTES-----  <u>1. Only applicable during installation of the Unit 2 Division 2 CSCS isolation valve during Unit 2 Refueling 17 while Unit 2 is in MODE 4,5, or defueled.</u>   <u>2. Only applicable during installation of the Unit 1 Division 2 CSCS isolation valve during Unit 1 Refueling 19 while Unit 1 is in MODE 4,5, or defueled.</u>            -----   <u>Division 2 DG and the required opposite unit Division 2 DG inoperable.</u></p>	<p><u>G.1</u> <u>Restore required Division 2 DG to OPERABLE status.</u></p>	<p><u>7 days</u></p>
<p><u>H.</u> Required Action and associated Completion Time of Condition A, B, C, D, E, <u>F or G</u> not met.</p>	<p><u>H.1</u> Be in MODE 3.</p>	<p>12 hours</p>
<p><u>I.</u> Three or more required AC sources inoperable.</p>	<p><u>I.1</u> Enter LCO 3.0.3.</p>	<p>Immediately</p>