

ENCLOSURE

NOTICE OF VIOLATION

Florida Power and Light Company
Turkey Point

Docket Nos. 50-250 and 50-251
License Nos. DPR-31 and DPR-41

The following violations were identified during an inspection conducted on March 11 - April 8, 1985. The Severity Levels were assigned in accordance with the NRC Enforcement Policy (10 CFR Part 2, Appendix C).

1. Technical Specification (TS) 4.1, Table 4.1-1, requires that each power range nuclear instrument (NI) channel be calibrated quarterly. TS 1.7.3 requires that a channel calibration encompass the entire channel.

Contrary to the above, as of April 1, 1985, quarterly calibrations of the Power Range NI channels did not encompass the entire channel in that the Power Range NI output signal from each instrument's lower detector was not verified to supply an input to the over temperature delta temperature (OTDT) and over power delta temperature (OPDT) protective circuits.

This is a Severity Level IV violation (Supplement I).


2. TS 4.15.2.a.5 requires that each testable valve in the fire protection water system be cycled annually. TS 4.15.2.a.3 requires that each valve in the fire protection water system flow path be verified to be in its correct position monthly. TS 4.18.1 requires a monthly fire suppression water system walkdown to verify that each accessible valve is in its correct position.

Contrary to the above, prior to April 1, 1985, four accessible and testable valves in the fire protection (suppression) water system were neither cycled annually nor verified monthly to be in their correct positions.

This is a Severity Level IV violation (Supplement I).

Pursuant to 10 CFR 2.201, you are required to submit to this office within 30 days of the date of this Notice, a written statement or explanation in reply, including: (1) admission or denial of the alleged violations; (2) the reasons for the violations if admitted; (3) the corrective steps which have been taken and the results achieved; (4) corrective steps which will be taken to avoid further violations; and (5) the date when full compliance will be achieved.

8506210262 850507
PDR ADOCK 05000250
Q PDR



Florida Power and Light Company
Turkey Point Units 1 and 2

2

Docket Nos. 50-250 and 50-251
License Nos. DPR-31 and DPR-41

Security or safeguards information should be submitted as an enclosure to facilitate withholding it from public disclosure as required by 10 CFR 2.790(d) or 10 CFR 73.21.

MAY 07 1985

Date: _____

11



2001 10 10

