FORM 21-100M



Central I ile
50.400
(G) DV 400
403

November 21, 1979

Mr. Harold D. Thornburg, Director Division of Reactor Construction Inspection United States Nuclear Regulatory Commission Office of Inspection and Enforcement Washington, D.C. 20555

SHEARON HARRIS NUCLEAR POWER PLANT UNIT NOS. 1, 2, 3 AND 4
DOCKET NOS. 50-400, 50-401, 50-402, AND 50-403
SUPPLEMENTAL RESPONSE TO IE BULLETIN 79-15

Dear Mr. Thornburg:

Carolina Power & Light Company (CP&L) provided an initial response to IE Bulletin 79-15 on September 10, 1979. In that letter, we provided general information on deep draft pumps as required by Items 1, 2 and 3 of the bulletin. We further indicated we were not able to provide the startup, operational, and maintenance information required by Items 4, 5 and 6 of the bulletin since the pumps had not yet been received on site for installation.

The purpose of this supplemental response is to inform you that inspections will be performed at the manufacturer's facility prior to shipment to confirm that specified clearances have been maintained and that dimensions for mechanical parts are within specified tolerances. Assembly procedures will specify bolt torques for critical bolts. Threaded connections will be inspected to verify that no galling has occurred. Additionally, CP&L will accumulate the on-site information for inspection requested by the bulletin as it become available.

Yours very truly,

ORIGINAL SIGNED BY

M. A. McDuffie Senior Vice President Engineering & Construction

MAM/jcb

cc: Mr. James P. O'Reilly, Director Region II United States Nuclear Regulatory Commission 101 Marietta Street, N.W. Atlanta, Georgia 30303

> 198322 OFFICIAL COPY

AOII

7912170

142

. • . . * • ,