

MANUAL HARD COPY DISTRIBUTION
DOCUMENT TRANSMITTAL 2018-1836

USER INFORMATION:

GERLACH*ROSEY M EMPL#:028401 CA#: 0363

Address: NUCSA2

Phone#: 542-3194

TRANSMITTAL INFORMATION:

TO: GERLACH*ROSEY M 01/24/2018

LOCATION: USNRC

FROM: NUCLEAR RECORDS DOCUMENT CONTROL CENTER (NUCSA-2)

THE FOLLOWING CHANGES HAVE OCCURRED TO THE HARDCOPY OR ELECTRONIC MANUAL ASSIGNED TO YOU. HARDCOPY USERS MUST ENSURE THE DOCUMENTS PROVIDED MATCH THE INFORMATION ON THIS TRANSMITTAL. WHEN REPLACING THIS MATERIAL IN YOUR HARDCOPY MANUAL, ENSURE THE UPDATE DOCUMENT ID IS THE SAME DOCUMENT ID YOU'RE REMOVING FROM YOUR MANUAL. TOOLS FROM THE HUMAN PERFORMANCE TOOL BAG SHOULD BE UTILIZED TO ELIMINATE THE CHANCE OF ERRORS.

ATTENTION: "REPLACE" directions do not affect the Table of Contents, Therefore no C will be issued with the updated material.

TSB2 - TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

REMOVE MANUAL TABLE OF CONTENTS DATE: 01/04/2018

ADD MANUAL TABLE OF CONTENTS DATE: 01/23/2018

CATEGORY: DOCUMENTS TYPE: TSB2

ID: TEXT 3.3.1.2

ADD: REV: 4

REMOVE: REV:3

A001
NRR

CATEGORY: DOCUMENTS TYPE: TSB2
ID: TEXT LOES
ADD: REV: 134

REMOVE: REV:133

ANY DISCREPANCIES WITH THE MATERIAL PROVIDED, CONTACT DCS @ X3107 OR X3171 FOR ASSISTANCE. UPDATES FOR HARDCOPY MANUALS WILL BE DISTRIBUTED WITHIN 3 DAYS IN ACCORDANCE WITH DEPARTMENT PROCEDURES. PLEASE MAKE ALL CHANGES AND ACKNOWLEDGE COMPLETE IN YOUR NIMS INBOX UPON COMPLETION OF UPDATES. FOR ELECTRONIC MANUAL USERS, ELECTRONICALLY REVIEW THE APPROPRIATE DOCUMENTS AND ACKNOWLEDGE COMPLETE IN YOUR NIMS INBOX.

SSES MANUAL

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

Table Of Contents

Issue Date: 01/23/2018

<u>Procedure Name</u>	<u>Rev</u>	<u>Issue Date</u>	<u>Change ID</u>	<u>Change Number</u>
TEXT LOES	134	01/23/2018		
Title: LIST OF EFFECTIVE SECTIONS				
TEXT TOC	23	03/01/2017		
Title: TABLE OF CONTENTS				
TEXT 2.1.1	5	01/22/2015		
Title: SAFETY LIMITS (SLS) REACTOR CORE SLS				
TEXT 2.1.2	1	10/04/2007		
Title: SAFETY LIMITS (SLS) REACTOR COOLANT SYSTEM (RCS) PRESSURE SL				
TEXT 3.0	3	08/20/2009		
Title: LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY				
TEXT 3.1.1	1	03/24/2005		
Title: REACTIVITY CONTROL SYSTEMS SHUTDOWN MARGIN (SDM)				
TEXT 3.1.2	0	11/18/2002		
Title: REACTIVITY CONTROL SYSTEMS REACTIVITY ANOMALIES				
TEXT 3.1.3	3	11/16/2016		
Title: REACTIVITY CONTROL SYSTEMS CONTROL ROD OPERABILITY				
TEXT 3.1.4	5	11/16/2016		
Title: REACTIVITY CONTROL SYSTEMS CONTROL ROD SCRAM TIMES				
TEXT 3.1.5	2	11/16/2016		
Title: REACTIVITY CONTROL SYSTEMS CONTROL ROD SCRAM ACCUMULATORS				
TEXT 3.1.6	4	11/16/2016		
Title: REACTIVITY CONTROL SYSTEMS ROD PATTERN CONTROL				

SSES MANUAL

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.1.7 4 11/16/2016
Title: REACTIVITY CONTROL SYSTEMS STANDBY LIQUID CONTROL (SLC) SYSTEM

TEXT 3.1.8 4 11/16/2016
Title: REACTIVITY CONTROL SYSTEMS SCRAM DISCHARGE VOLUME (SDV) VENT AND DRAIN VALVES

TEXT 3.2.1 5 11/16/2016
Title: POWER DISTRIBUTION LIMITS AVERAGE PLANAR LINEAR HEAT GENERATION RATE (APLHGR)

TEXT 3.2.2 4 11/16/2016
Title: POWER DISTRIBUTION LIMITS MINIMUM CRITICAL POWER RATIO (MCPR)

TEXT 3.2.3 3 11/16/2016
Title: POWER DISTRIBUTION LIMITS LINEAR HEAT GENERATION RATE LHGR

TEXT 3.3.1.1 6 11/16/2016
Title: INSTRUMENTATION REACTOR PROTECTION SYSTEM (RPS) INSTRUMENTATION

TEXT 3.3.1.2 4 01/23/2018
Title: INSTRUMENTATION SOURCE RANGE MONITOR (SRM) INSTRUMENTATION

TEXT 3.3.2.1 4 11/16/2016
Title: INSTRUMENTATION CONTROL ROD BLOCK INSTRUMENTATION

TEXT 3.3.2.2 3 11/16/2016
Title: INSTRUMENTATION FEEDWATER - MAIN TURBINE HIGH WATER LEVEL TRIP INSTRUMENTATION

TEXT 3.3.3.1 9 11/16/2016
Title: INSTRUMENTATION POST ACCIDENT MONITORING (PAM) INSTRUMENTATION

TEXT 3.3.3.2 2 11/16/2016
Title: INSTRUMENTATION REMOTE SHUTDOWN SYSTEM

TEXT 3.3.4.1 2 11/16/2016
Title: INSTRUMENTATION END OF CYCLE RECIRCULATION PUMP TRIP (EOC-RPT) INSTRUMENTATION

SSES MANUAL

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.3.4.2 1 11/16/2016
Title: INSTRUMENTATION ANTICIPATED TRANSIENT WITHOUT SCRAM RECIRCULATION PUMP TRIP (ATWS-RPT) INSTRUMENTATION

TEXT 3.3.5.1 6 11/16/2016
Title: INSTRUMENTATION EMERGENCY CORE COOLING SYSTEM (ECCS) INSTRUMENTATION

TEXT 3.3.5.2 1 11/16/2016
Title: INSTRUMENTATION REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM INSTRUMENTATION

TEXT 3.3.6.1 8 11/16/2016
Title: INSTRUMENTATION PRIMARY CONTAINMENT ISOLATION INSTRUMENTATION

TEXT 3.3.6.2 5 11/16/2016
Title: INSTRUMENTATION SECONDARY CONTAINMENT ISOLATION INSTRUMENTATION

TEXT 3.3.7.1 3 11/16/2016
Title: INSTRUMENTATION CONTROL ROOM EMERGENCY OUTSIDE AIR SUPPLY (CREOAS) SYSTEM INSTRUMENTATION

TEXT 3.3.8.1 4 11/16/2016
Title: INSTRUMENTATION LOSS OF POWER (LOP) INSTRUMENTATION

TEXT 3.3.8.2 1 11/16/2016
Title: INSTRUMENTATION REACTOR PROTECTION SYSTEM (RPS) ELECTRIC POWER MONITORING

TEXT 3.4.1 5 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RECIRCULATION LOOPS OPERATING

TEXT 3.4.2 4 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) JET PUMPS

TEXT 3.4.3 3 01/13/2012
Title: REACTOR COOLANT SYSTEM (RCS) SAFETY/RELIEF VALVES (S/RVS)

TEXT 3.4.4 1 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RCS OPERATIONAL LEAKAGE

SSES MANUAL

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.4.5 3 03/10/2010
Title: REACTOR COOLANT SYSTEM (RCS) RCS PRESSURE ISOLATION VALVE (PIV) LEAKAGE

TEXT 3.4.6 5 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RCS LEAKAGE DETECTION INSTRUMENTATION

TEXT 3.4.7 3 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RCS SPECIFIC ACTIVITY

TEXT 3.4.8 3 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RESIDUAL HEAT REMOVAL (RHR) SHUTDOWN COOLING SYSTEM
- HOT SHUTDOWN

TEXT 3.4.9 2 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RESIDUAL HEAT REMOVAL (RHR) SHUTDOWN COOLING SYSTEM
- COLD SHUTDOWN

TEXT 3.4.10 5 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) RCS PRESSURE AND TEMPERATURE (P/T) LIMITS

TEXT 3.4.11 1 11/16/2016
Title: REACTOR COOLANT SYSTEM (RCS) REACTOR STEAM DOME PRESSURE

TEXT 3.5.1 5 11/16/2016
Title: EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC)
SYSTEM ECCS - OPERATING

TEXT 3.5.2 3 11/16/2016
Title: EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC)
SYSTEM ECCS - SHUTDOWN

TEXT 3.5.3 5 05/31/2017
Title: EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC)
SYSTEM RCIC SYSTEM

TEXT 3.6.1.1 6 11/16/2016
Title: PRIMARY CONTAINMENT

TEXT 3.6.1.2 2 11/16/2016
Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT AIR LOCK

SSES MANUAL

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.6.1.3 16 04/19/2017
Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT ISOLATION VALVES (PCIVS)

TEXT 3.6.1.4 2 11/16/2016
Title: CONTAINMENT SYSTEMS CONTAINMENT PRESSURE

TEXT 3.6.1.5 2 11/16/2016
Title: CONTAINMENT SYSTEMS DRYWELL AIR TEMPERATURE

TEXT 3.6.1.6 1 11/16/2016
Title: CONTAINMENT SYSTEMS SUPPRESSION CHAMBER-TO-DRYWELL VACUUM BREAKERS

TEXT 3.6.2.1 3 11/16/2016
Title: CONTAINMENT SYSTEMS SUPPRESSION POOL AVERAGE TEMPERATURE

TEXT 3.6.2.2 1 11/16/2016
Title: CONTAINMENT SYSTEMS SUPPRESSION POOL WATER LEVEL

TEXT 3.6.2.3 2 11/16/2016
Title: CONTAINMENT SYSTEMS RESIDUAL HEAT REMOVAL (RHR) SUPPRESSION POOL COOLING

TEXT 3.6.2.4 1 11/16/2016
Title: CONTAINMENT SYSTEMS RESIDUAL HEAT REMOVAL (RHR) SUPPRESSION POOL SPRAY

TEXT 3.6.3.1 2 06/13/2006
Title: CONTAINMENT SYSTEMS INTENTIONALLY LEFT BLANK

TEXT 3.6.3.2 3 09/29/2017
Title: CONTAINMENT SYSTEMS DRYWELL AIR FLOW SYSTEM

LDCN 5297

TEXT 3.6.3.3 3 09/29/2017
Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT OXYGEN CONCENTRATION

TEXT 3.6.4.1 14 04/19/2017
Title: CONTAINMENT SYSTEMS SECONDARY CONTAINMENT

SSES MANUAL

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.6.4.2 12 04/19/2017
Title: CONTAINMENT SYSTEMS SECONDARY CONTAINMENT ISOLATION VALVES (SCIVS)

TEXT 3.6.4.3 6 09/15/2017
Title: CONTAINMENT SYSTEMS STANDBY GAS TREATMENT (SGT) SYSTEM

TEXT 3.7.1 7 03/01/2017
Title: PLANT SYSTEMS RESIDUAL HEAT REMOVAL SERVICE WATER (RHRSW) SYSTEM AND THE
ULTIMATE HEAT SINK (UHS)

TEXT 3.7.2 3 11/16/2016
Title: PLANT SYSTEMS EMERGENCY SERVICE WATER (ESW) SYSTEM

TEXT 3.7.3 3 09/15/2017
Title: PLANT SYSTEMS CONTROL ROOM EMERGENCY OUTSIDE AIR SUPPLY (CREOAS) SYSTEM

TEXT 3.7.4 1 11/16/2016
Title: PLANT SYSTEMS CONTROL ROOM FLOOR COOLING SYSTEM

TEXT 3.7.5 2 11/16/2016
Title: PLANT SYSTEMS MAIN CONDENSER OFFGAS

TEXT 3.7.6 4 11/16/2016
Title: PLANT SYSTEMS MAIN TURBINE BYPASS SYSTEM

TEXT 3.7.7 2 11/16/2016
Title: PLANT SYSTEMS SPENT FUEL STORAGE POOL WATER LEVEL

TEXT 3.7.8 1 11/16/2016
Title: MAINE TURBINE PRESSURE REGULATION SYSTEM

TEXT 3.8.1 10 11/16/2016
Title: ELECTRICAL POWER SYSTEMS AC SOURCES - OPERATING

TEXT 3.8.2 0 11/18/2002
Title: ELECTRICAL POWER SYSTEMS AC SOURCES - SHUTDOWN

SSES MANUAL

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.8.3 6 12/14/2017
Title: ELECTRICAL POWER SYSTEMS DIESEL FUEL OIL LUBE OIL AND STARTING AIR

TEXT 3.8.4 4 11/16/2016
Title: ELECTRICAL POWER SYSTEMS DC SOURCES - OPERATING

TEXT 3.8.5 1 12/14/2006
Title: ELECTRICAL POWER SYSTEMS DC SOURCES - SHUTDOWN

TEXT 3.8.6 2 11/16/2016
Title: ELECTRICAL POWER SYSTEMS BATTERY CELL PARAMETERS

TEXT 3.8.7 6 03/01/2017
Title: ELECTRICAL POWER SYSTEMS DISTRIBUTION SYSTEMS - OPERATING

TEXT 3.8.8 1 11/16/2016
Title: ELECTRICAL POWER SYSTEMS DISTRIBUTION SYSTEMS - SHUTDOWN

TEXT 3.9.1 1 11/16/2016
Title: REFUELING OPERATIONS REFUELING EQUIPMENT INTERLOCKS

TEXT 3.9.2 2 11/16/2016
Title: REFUELING OPERATIONS REFUEL POSITION ONE-ROD-OUT INTERLOCK

TEXT 3.9.3 1 11/16/2016
Title: REFUELING OPERATIONS CONTROL ROD POSITION

TEXT 3.9.4 0 11/18/2002
Title: REFUELING OPERATIONS CONTROL ROD POSITION INDICATION

TEXT 3.9.5 1 11/16/2016
Title: REFUELING OPERATIONS CONTROL ROD OPERABILITY - REFUELING

TEXT 3.9.6 2 11/16/2016
Title: REFUELING OPERATIONS REACTOR PRESSURE VESSEL (RPV) WATER LEVEL

SSES MANUAL

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.9.7 1 11/16/2016
Title: REFUELING OPERATIONS RESIDUAL HEAT REMOVAL (RHR) - HIGH WATER LEVEL

TEXT 3.9.8 1 11/16/2016
Title: REFUELING OPERATIONS RESIDUAL HEAT REMOVAL (RHR) - LOW WATER LEVEL

TEXT 3.10.1 1 01/23/2008
Title: SPECIAL OPERATIONS INSERVICE LEAK AND HYDROSTATIC TESTING OPERATION

TEXT 3.10.2 1 11/16/2016
Title: SPECIAL OPERATIONS REACTOR MODE SWITCH INTERLOCK TESTING

TEXT 3.10.3 1 11/16/2016
Title: SPECIAL OPERATIONS SINGLE CONTROL ROD WITHDRAWAL - HOT SHUTDOWN

TEXT 3.10.4 1 11/16/2016
Title: SPECIAL OPERATIONS SINGLE CONTROL ROD WITHDRAWAL - COLD SHUTDOWN

TEXT 3.10.5 1 11/16/2016
Title: SPECIAL OPERATIONS SINGLE CONTROL ROD DRIVE (CRD) REMOVAL - REFUELING

TEXT 3.10.6 1 11/16/2016
Title: SPECIAL OPERATIONS MULTIPLE CONTROL ROD WITHDRAWAL - REFUELING

TEXT 3.10.7 1 03/24/2005
Title: SPECIAL OPERATIONS CONTROL ROD TESTING - OPERATING

TEXT 3.10.8 3 11/16/2016
Title: SPECIAL OPERATIONS SHUTDOWN MARGIN (SDM) TEST - REFUELING

SUSQUEHANNA STEAM ELECTRIC STATION
LIST OF EFFECTIVE SECTIONS (TECHNICAL SPECIFICATIONS BASES)

<u>Section</u>	<u>Title</u>	<u>Revision</u>
TOC	Table of Contents	23
B 2.0	SAFETY LIMITS (SLs)	
B2.1.1	Reactor Core SLs	5
B2.1.2	Reactor Coolant System (RCS) Pressure SL.....	1
B 3.0	LCO AND SR APPLICABILITY BASES	3
B 3.1	REACTIVITY CONTROL SYSTEMS	
B3.1.1	Shutdown Margin (SDM).....	2
B3.1.2	Reactivity Anomalies	1
B3.1.3	Control Rod OPERABILITY	3
B3.1.4	Control Rod Scram Times.....	5
B3.1.5	Control Rod Scram Accumulators.....	2
B3.1.6	Rod Pattern Control.....	4
B3.1.7	Standby Liquid Control (SLC) System.....	3
B3.1.8	Scram Discharge Volume (SDV) Vent and Drain Valves.....	4
B 3.2	POWER DISTRIBUTION LIMITS	
B3.2.1	Average Planar Linear Heat Generation Rate (APLHGR).....	5
B3.2.2	Minimum Critical Power Ratio (MCPR)	4
B3.2.3	Linear Heat Generation Rate (LHGR).....	3
B 3.3	INSTRUMENTATION	
B3.3.1.1	Reactor Protection System (RPS) Instrumentation	6
B3.3.1.2	Source Range Monitor (SRM) Instrumentation	4
B3.3.2.1	Control Rod Block Instrumentation	4
B3.3.2.2	Feedwater – Main Turbine High Water Level Trip Instrumentation	3
B3.3.3.1	Post Accident Monitoring (PAM) Instrumentation.....	9
B3.3.3.2	Remote Shutdown System	2
B3.3.4.1	End of Cycle Recirculation Pump Trip (EOC-RPT) Instrumentation	2
B3.3.4.2	Anticipated Transient Without Scram Recirculation Pump Trip (ATWS-RPT) Instrumentation.....	1
B3.3.5.1	Emergency Core Cooling System (ECCS) Instrumentation.....	6
B3.3.5.2	Reactor Core Isolation Cooling (RCIC) System Instrumentation	1
B3.3.6.1	Primary Containment Isolation Instrumentation.....	8
B3.3.6.2	Secondary Containment Isolation Instrumentation.....	5
B3.3.7.1	Control Room Emergency Outside Air Supply (CREOAS) System Instrumentation.....	3
B3.3.8.1	Loss of Power (LOP) Instrumentation	4
B3.3.8.2	Reactor Protection System (RPS) Electric Power Monitoring.....	1

SUSQUEHANNA STEAM ELECTRIC STATION
LIST OF EFFECTIVE SECTIONS (TECHNICAL SPECIFICATIONS BASES)

<u>Section</u>	<u>Title</u>	<u>Revision</u>
B 3.4	REACTOR COOLANT SYSTEM (RCS)	
B3.4.1	Recirculation Loops Operating.....	5
B3.4.2	Jet Pumps	4
B3.4.3	Safety/Relief Valves (S/RVs)	4
B3.4.4	RCS Operational LEAKAGE.....	1
B3.4.5	RCS Pressure Isolation Valve (PIV) Leakage	4
B3.4.6	RCS Leakage Detection Instrumentation	5
B3.4.7	RCS Specific Activity	3
B3.4.8	Residual Heat Removal (RHR) Shutdown Cooling System – Hot Shutdown	3
B3.4.9	Residual Heat Removal (RHR) Shutdown Cooling System – Cold Shutdown.....	2
B3.4.10	RCS Pressure and Temperature (P/T) Limits.....	5
B3.4.11	Reactor Steam Dome Pressure	1
B 3.5	EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM	
B3.5.1	ECCS – Operating.....	5
B3.5.2	ECCS – Shutdown.....	3
B3.5.3	RCIC System.....	5
B 3.6	CONTAINMENT SYSTEMS	
B3.6.1.1	Primary Containment.....	6
B3.6.1.2	Primary Containment Air Lock	2
B3.6.1.3	Primary Containment Isolation Valves (PCIVs)	16
B3.6.1.4	Containment Pressure	2
B3.6.1.5	Drywell Air Temperature	2
B3.6.1.6	Suppression Chamber-to-Drywell Vacuum Breakers	1
B3.6.2.1	Suppression Pool Average Temperature	3
B3.6.2.2	Suppression Pool Water Level.....	1
B3.6.2.3	Residual Heat Removal (RHR) Suppression Pool Cooling.....	2
B3.6.2.4	Residual Heat Removal (RHR) Suppression Pool Spray	1
B3.6.3.1	Not Used	2
B3.6.3.2	Drywell Air Flow System	3
B3.6.3.3	Primary Containment Oxygen Concentration.....	3
B3.6.4.1	Secondary Containment	14
B3.6.4.2	Secondary Containment Isolation Valves (SCIVs)	12
B3.6.4.3	Standby Gas Treatment (SGT) System	6

SUSQUEHANNA STEAM ELECTRIC STATION
LIST OF EFFECTIVE SECTIONS (TECHNICAL SPECIFICATIONS BASES)

<u>Section</u>	<u>Title</u>	<u>Revision</u>
B 3.7	PLANT SYSTEMS	
B3.7.1	Residual Heat Removal Service Water (RHRSW) System and the Ultimate Heat Sink (UHS)	7
B3.7.2	Emergency Service Water (ESW) System	3
B3.7.3	Control Room Emergency Outside Air Supply (CREOAS) System	3
B3.7.4	Control Room Floor Cooling System.....	1
B3.7.5	Main Condenser Offgas.....	2
B3.7.6	Main Turbine Bypass System	4
B3.7.7	Spent Fuel Storage Pool Water Level.....	2
B3.7.8	Main Turbine Pressure Regulation System.....	1
B 3.8	ELECTRICAL POWER SYSTEM	
B3.8.1	AC Sources – Operating.....	10
B3.8.2	AC Sources – Shutdown.....	0
B3.8.3	Diesel Fuel Oil, Lube Oil, and Starting Air.....	6
B3.8.4	DC Sources – Operating.....	4
B3.8.5	DC Sources – Shutdown.....	1
B3.8.6	Battery Cell Parameters.....	2
B3.8.7	Distribution Systems – Operating.....	6
B3.8.8	Distribution Systems – Shutdown	1
B 3.9	REFUELING OPERATIONS	
B3.9.1	Refueling Equipment Interlocks	1
B3.9.2	Refuel Position One-Rod-Out Interlock.....	1
B3.9.3	Control Rod Position.....	1
B3.9.4	Control Rod Position Indication.....	0
B3.9.5	Control Rod OPERABILITY – Refueling	1
B3.9.6	Reactor Pressure Vessel (RPV) Water Level.....	2
B3.9.7	Residual Heat Removal (RHR) – High Water Level	1
B3.9.8	Residual Heat Removal (RHR) – Low Water Level.....	1
B 3.10	SPECIAL OPERATIONS	
B3.10.1	Inservice Leak and Hydrostatic Testing Operation.....	1
B3.10.2	Reactor Mode Switch Interlock Testing.....	1
B3.10.3	Single Control Rod Withdrawal – Hot Shutdown	1
B3.10.4	Single Control Rod Withdrawal – Cold Shutdown	1
B3.10.5	Single Control Rod Drive (CRD) Removal – Refueling.....	1
B3.10.6	Multiple Control Rod Withdrawal – Refueling	1
B3.10.7	Control Rod Testing – Operating	1
B3.10.8	SHUTDOWN MARGIN (SDM) Test – Refueling.....	3

B 3.3 INSTRUMENTATION

B 3.3.1.2 Source Range Monitor (SRM) Instrumentation

BASES

BACKGROUND

The SRMs provide the operator with information relative to the neutron flux level at startup and low flux levels in the core. As such, the SRM indication is used by the operator to monitor the approach to criticality and determine when criticality is achieved. The SRMs are not fully withdrawn from the core until the SRM to intermediate range monitor (IRM) overlap is demonstrated (as required by SR 3.3.1.1.6), when the SRMs are normally fully withdrawn from the core.

The SRM subsystem of the Neutron Monitoring System (NMS) consists of four channels. Each of the SRM channels can be bypassed, but only one at any given time, by the operation of a bypass switch. Each channel includes one detector that can be physically positioned in the core. Each detector assembly consists of a miniature fission chamber with associated cabling, signal conditioning equipment, and electronics associated with the various SRM functions. The signal conditioning equipment converts the current pulses from the fission chamber to analog DC currents that correspond to the count rate. Each channel also includes indication, alarm, and control rod blocks. However, this LCO specifies OPERABILITY requirements only for the monitoring and indication functions of the SRMs.

During refueling, shutdown, and low power operations, the primary indication of neutron flux levels is provided by the SRMs or special movable detectors connected to the normal SRM circuits. The SRMs provide monitoring of reactivity changes during fuel or control rod movement and give the control room operator early indication of unexpected subcritical multiplication that could be indicative of an approach to criticality.

APPLICABLE

SAFETY ANALYSES

Prevention and mitigation of prompt reactivity excursions during refueling and low power operation is provided by LCO 3.9.1, "Refueling Equipment Interlocks"; LCO 3.1.1, "SHUTDOWN MARGIN (SDM)"; LCO 3.3.1.1, "Reactor Protection System (RPS) Instrumentation"; IRM Neutron Flux—High and Average Power Range Monitor (APRM) Neutron Flux—High

(continued)

BASES

APPLICABLE
SAFETY ANALYSES
(continued)

(Setdown) Functions; and LCO 3.3.2.1, "Control Rod Block Instrumentation."

The SRMs have no safety function and are not assumed to function during any FSAR design basis accident or transient analysis. However, the SRMs provide the only on-scale monitoring of neutron flux levels during startup and refueling. Therefore, they are being retained in Technical Specifications.

LCO

During startup in MODE 2, three of the four SRM channels are required to be OPERABLE to monitor the reactor flux level prior to and during control rod withdrawal, subcritical multiplication and reactor criticality, and neutron flux level and reactor period until the flux level is sufficient to maintain the IRMs on Range 3 or above. All but one of the channels are required in order to provide a representation of the overall core response during those periods when reactivity changes are occurring throughout the core.

In MODES 3 and 4, with the reactor shut down, two SRM channels provide redundant monitoring of flux levels in the core.

In MODE 5, during a spiral offload or reload, an SRM outside the fueled region will no longer be required to be OPERABLE, since it is not capable of monitoring neutron flux in the fueled region of the core. Fueled region is a continuous area with fuel. Thus, CORE ALTERATIONS are allowed in a quadrant with no OPERABLE SRM in an adjacent quadrant provided the Table 3.3.1.2-1, footnote (b), requirement that the bundles being spiral reloaded or spiral offloaded are all in a single fueled region containing at least one OPERABLE SRM is met. Spiral reloading and offloading encompass reloading or offloading a cell on the edge of a continuous fueled region (the cell can be reloaded or offloaded in any sequence).

In nonspiral routine operations, two SRMs are required to be OPERABLE to provide redundant monitoring of reactivity changes occurring in the reactor core. Because of the local nature of reactivity changes during refueling, adequate coverage is provided by requiring one SRM to be OPERABLE in

(continued)

BASES

LCO
(continued)

the quadrant of the reactor core where CORE ALTERATIONS are being performed, and the other SRM to be OPERABLE in an adjacent quadrant containing fuel. These requirements ensure that the reactivity of the core will be continuously monitored during CORE ALTERATIONS.

Special movable detectors, according to footnote (c) of Table 3.3.1.2-1, may be used during CORE ALTERATIONS in place of the normal SRM nuclear detectors. These special detectors must be connected to the normal SRM circuits in the NMS, such that the applicable neutron flux indication can be generated. These special detectors provide more flexibility in monitoring reactivity changes during fuel loading, since they can be positioned anywhere within the core during refueling. They must still meet the location requirements of SR 3.3.1.2.2 and all other required SRs for SRMs.

For an SRM channel to be considered OPERABLE, it must be providing neutron flux monitoring indication.

APPLICABILITY

The SRMs are required to be OPERABLE in MODES 2, 3, 4, and 5 prior to the IRMs being on scale on Range 3 to provide for neutron monitoring. In MODE 1, the APRMs provide adequate monitoring of reactivity changes in the core; therefore, the SRMs are not required. In MODE 2, with IRMs on Range 3 or above, the IRMs provide adequate monitoring and the SRMs are not required.

ACTIONS

A.1 and B.1

In MODE 2, with the IRMs on Range 2 or below, SRMs provide the means of monitoring core reactivity and criticality. With any number of the required SRMs inoperable, the ability to monitor neutron flux is degraded. Therefore, a limited time is allowed to restore the inoperable channels to OPERABLE status.

Provided at least one SRM remains OPERABLE, Required Action A.1 allows 4 hours to restore the required SRMs to OPERABLE status. This time is reasonable because there is adequate capability remaining to monitor the core, there is

(continued)

BASES

ACTIONS

A.1 and B.1 (continued)

limited risk of an event during this time, and there is sufficient time to take corrective actions to restore the required SRMs to OPERABLE status or to establish alternate IRM monitoring capability. During this time, control rod withdrawal and power increase is not precluded by this Required Action. Having the ability to monitor the core with at least one SRM, proceeding to IRM Range 3 or greater (with overlap required by SR 3.3.1.1.6), and thereby exiting the Applicability of this LCO, is acceptable for ensuring adequate core monitoring and allowing continued operation.

With three required SRMs inoperable, Required Action B.1 allows no positive changes in reactivity (control rod withdrawal must be immediately suspended) due to inability to monitor the changes. Required Action A.1 still applies and allows 4 hours to restore monitoring capability prior to requiring control rod insertion. This allowance is based on the limited risk of an event during this time, provided that no control rod withdrawals are allowed, and the desire to concentrate efforts on repair, rather than to immediately shut down, with no SRMs OPERABLE.

C.1

In MODE 2, if the required number of SRMs is not restored to OPERABLE status within the allowed Completion Time, the reactor shall be placed in MODE 3. With all control rods fully inserted, the core is in its least reactive state with the most margin to criticality. The allowed Completion Time of 12 hours is reasonable, based on operating experience, to reach MODE 3 from full power conditions in an orderly manner and without challenging plant systems.

D.1 and D.2

With one or more required SRMs inoperable in MODE 3 or 4, the neutron flux monitoring capability is degraded or nonexistent. The requirement to fully insert all insertable control rods ensures that the reactor will be at its minimum reactivity level while no neutron monitoring capability is available. Placing the reactor mode switch in the shutdown position prevents subsequent control rod withdrawal by

(continued)

BASES

ACTIONS

D.1 and D.2 (continued)

maintaining a control rod block. The allowed Completion Time of 1 hour is sufficient to accomplish the Required Action, and takes into account the low probability of an event requiring the SRM occurring during this interval.

E.1 and E.2

With one or more required SRM inoperable in MODE 5, the ability to detect local reactivity changes in the core during refueling is degraded. CORE ALTERATIONS must be immediately suspended and action must be immediately initiated to fully insert all insertable control rods in core cells containing one or more fuel assemblies. Suspending CORE ALTERATIONS prevents the two most probable causes of reactivity changes, fuel loading and control rod withdrawal, from occurring. Inserting all insertable control rods ensures that the reactor will be at its minimum reactivity given that fuel is present in the core. Suspension of CORE ALTERATIONS shall not preclude completion of the movement of a component to a safe, conservative position.

Action (once required to be initiated) to insert control rods must continue until all insertable rods in core cells containing one or more fuel assemblies are inserted.

SURVEILLANCE
REQUIREMENTS

The SRs for each SRM Applicable MODE or other specified conditions are found in the SRs column of Table 3.3.1.2-1.

SR 3.3.1.2.1 and SR 3.3.1.2.3

Performance of the CHANNEL CHECK ensures that a gross failure of instrumentation has not occurred. A CHANNEL CHECK is normally a comparison of the parameter indicated on one channel to a similar parameter on another channel. It is based on the assumption that instrument channels monitoring the same parameter should read approximately the same value. Significant deviations between the instrument channels could be an indication of excessive instrument drift in one of the channels or something even more serious. A CHANNEL CHECK will detect gross channel failure; thus, it

(continued)

BASES

SURVEILLANCE
REQUIREMENTS

SR 3.3.1.2.1 and SR 3.3.1.2.3 (continued)

is key to verifying the instrumentation continues to operate properly between each CHANNEL CALIBRATION.

Agreement criteria which are determined by the plant staff based on an investigation of a combination of the channel instrument uncertainties may be used to support this parameter comparison and include indication and readability. If a channel is outside the criteria, it may be an indication that the instrument has drifted outside its limit, and does not necessarily indicate the channel is Inoperable.

The Surveillance Frequency is controlled under the Surveillance Frequency Control Program. The CHANNEL CHECK supplements less formal checks of channels during normal operational use of the displays associated with the channels required by the LCO.

SR 3.3.1.2.2

To provide adequate coverage of potential reactivity changes in the core, a maximum of two SRMs are required to be OPERABLE. One SRM is required to be OPERABLE in the quadrant where CORE ALTERATIONS are being performed, and the other OPERABLE SRM must be in an adjacent quadrant containing fuel. However, in accordance with Table 3.3.1.2-1, only one SRM is required during a spiral reload until the fueled region is large enough to encompass a second installed SRM. Note 1 states that the SR is required to be met only during CORE ALTERATIONS. It is not required to be met at other times in MODE 5 since core reactivity changes are not occurring. This Surveillance consists of a review of plant logs to ensure that SRMs required to be OPERABLE for given CORE ALTERATIONS are, in fact, OPERABLE. In the event that only one SRM is required to be OPERABLE, per Table 3.3.1.2-1, footnote (b), only the a. portion of this SR is required. Note 2 clarifies that more than one of the three requirements can be met by the same OPERABLE SRM. The Surveillance Frequency is controlled under the Surveillance Frequency Control Program.

(continued)

BASES

SURVEILLANCE
REQUIREMENTS

SR 3.3.1.2.4

This Surveillance consists of a verification of the SRM instrument readout to ensure that the SRM reading is greater than a specified minimum count rate, which ensures that the detectors are indicating count rates indicative of neutron flux levels within the core. The signal-to-noise ratio shown in Figure 3.3.1.2-1 is the SRM count rate at which there is a 95% probability that the SRM signal indicates the presence of neutrons and only a 5% probability that the SRM signal is a result of noise (Ref. 1). With few fuel assemblies loaded, the SRMs will not have a high enough count rate to satisfy the SR. Therefore, allowances are made for loading sufficient "source" material, in the form of irradiated fuel assemblies, to establish the minimum count rate.

To accomplish this, the SR is modified by a Note that states that the count rate is not required to be met on an SRM that has less than or equal to four fuel assemblies adjacent to the SRM and no other fuel assemblies are in the associated core quadrant. With four or less fuel assemblies loaded around each SRM and no other fuel assemblies in the associated core quadrant, even with a control rod withdrawn, the configuration will not be critical.

The Surveillance Frequency is controlled under the Surveillance Frequency Control Program.

SR 3.3.1.2.5 and SR 3.3.1.2.6

Performance of a CHANNEL FUNCTIONAL TEST demonstrates the associated channel will function properly. SR 3.3.1.2.5 is

(continued)

BASES

SURVEILLANCE
REQUIREMENTS

SR 3.3.1.2.5 and SR 3.3.1.2.6 (continued)

required in MODE 5, and ensures that the channels are OPERABLE while core reactivity changes could be in progress. The Surveillance Frequency is controlled under the Surveillance Frequency Control Program.

SR 3.3.1.2.6 is required in MODE 2 with IRMs on Range 2 or below, and in MODES 3 and 4. The Surveillance Frequency is controlled under the Surveillance Frequency Control Program.

Verification of the signal to noise ratio also ensures that the detectors are inserted to an acceptable operating level. In a fully withdrawn condition, the detectors are sufficiently removed from the fueled region of the core to essentially eliminate neutrons from reaching the detector. Any count rate obtained while the detectors are fully withdrawn is assumed to be "noise" only.

The Note to the Surveillance allows the Surveillance to be delayed until entry into the specified condition of the Applicability (THERMAL POWER decreased to IRM Range 2 or below). The SR must be performed within 12 hours after IRMs are on Range 2 or below. The allowance to enter the Applicability with the Frequency not met is reasonable, based on the limited time of 12 hours allowed after entering the Applicability and the inability to perform the Surveillance while at higher power levels. Although the Surveillance could be performed while on IRM Range 3, the plant would not be expected to maintain steady state operation at this power level. In this event, the 12 hour Frequency is reasonable, based on the SRMs being otherwise verified to be OPERABLE (i.e., satisfactorily performing the CHANNEL CHECK) and the time required to perform the Surveillances.

(continued)

BASES

SURVEILLANCE
REQUIREMENTS
(continued)

SR 3.3.1.2.7

Performance of a CHANNEL CALIBRATION verifies the performance of the SRM detectors and associated circuitry. The Frequency considers the plant conditions required to perform the test, the ease of performing the test, and the likelihood of a change in the system or component status. The Surveillance Frequency is controlled under the Surveillance Frequency Control Program. The neutron detectors are excluded from the CHANNEL CALIBRATION because they cannot readily be adjusted. The detectors are fission chambers that are designed to have a relatively constant sensitivity over the range and with an accuracy specified for a fixed useful life.

Note 2 to the Surveillance allows the Surveillance to be delayed until entry into the specified condition of the Applicability. The SR must be performed in MODE 2 within 12 hours of entering MODE 2 with IRMs on Range 2 or below. The allowance to enter the Applicability with the Frequency not met is reasonable, based on the limited time of 12 hours allowed after entering the Applicability and the inability to perform the Surveillance while at higher power levels. Although the Surveillance could be performed while on IRM Range 3, the plant would not be expected to maintain steady state operation at this power level. In this event, the 12 hour Frequency is reasonable, based on the SRMs being otherwise verified to be OPERABLE (i.e., satisfactorily performing the CHANNEL CHECK) and the time required to perform the Surveillances.

REFERENCES

1. General Electric Service Information Letter (SIL) 478 "SRM Minimum Count Rate" dated December 16, 1988.
-