

ENCLOSURE 2

REVISED PAGES - UNIT NO. 1

8905120019 890505
PDR ADDCK 05000272
P PDC

SURVEILLANCE REQUIREMENTS (Continued)

In addition to the regular sample, snubbers which failed the previous functional test shall be retested during the next test period. If a spare snubber has been installed in place of a failed snubber, then both the failed snubber (if it is repaired and installed in another position) and the spare snubber shall be retested. Test results of these snubbers may not be included for the re-sampling.

If any snubber selected for functional testing either fails to lockup or fails to move, i.e., frozen in place, the cause will be evaluated and if caused by manufacturer or design deficiency all snubbers of the same design subject to the same defect shall be functionally tested. This testing requirement shall be independent of the requirements stated above for snubbers not meeting the functional test acceptance criteria.

For the snubber(s) found inoperable, an engineering evaluation shall be performed on the components which are supported by the snubber(s). The purpose of this engineering evaluation shall be to determine if the components supported by the snubber(s) were adversely affected by the inoperability of the snubber(s) in order to ensure that the supported component remains capable of meeting the designed service.

d. Hydraulic Snubbers Functional Test Acceptance Criteria

The hydraulic snubber functional test shall verify that:

1. Activation (restraining action) is achieved within the specified range of velocity or acceleration in both tension and compression.
2. Snubber bleed, or release rate, where required, is within the specified range in compression or tension. For snubbers specifically required to not displace under continuous load, the ability of the snubber to withstand load without displacement shall be verified.

e. Mechanical Snubbers Functional Acceptance Criteria

The mechanical snubber functional test shall verify that:

1. The force that initiates free movement of the snubber rod in either tension or compression is less than the specified maximum drag force.
2. Activation (restraining action) is achieved within the specified range of velocity or acceleration in both tension and compression.

REVISED PAGES - UNIT NO. 2

PLANT SYSTEMS
SURVEILLANCE REQUIREMENTS (Continued)

In addition to the regular sample, snubbers which failed the previous functional test shall be retested during the next test period. If a spare snubber has been installed in place of a failed snubber, then both the failed snubber (if it is repaired and installed in another position) and the spare snubber shall be retested. Test results of these snubbers may not be included for the re-sampling.

If any snubber selected for functional testing either fails to lockup or fails to move, i.e., frozen in place, the cause will be evaluated and if caused by manufacturer or design deficiency all snubbers of the same design subject to the same defect shall be functionally tested. This testing requirement shall be independent of the requirements stated above for snubbers not meeting the functional test acceptance criteria.

For the snubber(s) found inoperable, an engineering evaluation shall be performed on the components which are supported by the snubber(s). The purpose of this engineering evaluation shall be to determine if the components supported by the snubber(s) were adversely affected by the inoperability of the snubber(s) in order to ensure that the supported component remains capable of meeting the designed service.

d. Hydraulic Snubbers Functional Test Acceptance Criteria

The hydraulic snubber functional test shall verify that:

1. Activation (restraining action) is achieved within the specified range of velocity or acceleration in both tension and compression.
2. Snubber bleed, or release rate, where required, is within the specified range in compression or tension. For snubbers specifically required to not displace under continuous load, the ability of the snubber to withstand load without displacement shall be verified.

e. Mechanical Snubbers Functional Acceptance Criteria

The mechanical snubber functional test shall verify that:

1. The force that initiates free movement of the snubber rod in either tension or compression is less than the specified maximum drag force.
2. Activation (restraining action) is achieved within the specified range of velocity or acceleration in both tension and compression.