

4.4 CONTAINMENT TESTSApplicability

Applies to containment leakage testing.

Objective

To assure that leakage of the primary reactor containment and associated systems is held within allowable leakage rate limits; and to assure that periodic surveillance is performed to assure proper maintenance and leak repair during the service life of the containment.

Specification

- A. Periodic and post-operational integrated leakage rate tests of the containment shall be performed in accordance with the requirements of 10 CFR 50, Appendix J, "Reactor Containment Leakage Testing for Water Cooled Power Reactors."
- B. Containment Leakage Rate Testing Requirements

1. The containment and containment penetrations leakage rate shall be demonstrated by performing leakage rate testing as required by 10 CFR 50 Appendix J, Option B, as modified by approved exemptions, and in accordance with the guidelines contained in Regulatory Guide 1.163, dated September, 1995. Leakage rate acceptance criteria are as follows:

- a. An overall integrated leakage rate of less than or equal to L_a , 0.1 percent by weight of containment air per 24 hours, at calculated peak pressure (Pa).
- b. A combined leakage rate of less than or equal to $0.60 L_a$ for all penetrations and valves subject to Type B and C testing when pressurized to Pa.

Prior to entering an operating condition where containment integrity is required the as-left Type A leakage rate shall not exceed $0.75 L_a$ and the combined leakage rate of all penetrations subject to Type B and C testing shall not exceed $0.6 L_a$.

2. The provisions of Specification 4.0.2 are not applicable.

Basis

The leak tightness testing of all liner welds was performed during construction by welding a structural steel test channel over each weld seam and performing soap bubble and halogen leak tests.

Amendment Nos.

9603190300 960314
PDR ADOCK 05000280
P PDR