

September 13, 1978  
L-78-297

Office of Nuclear Reactor Regulation  
Attention: Mr. Victor Stello, Director  
Division of Operating Reactors  
U. S. Nuclear Regulatory Commission  
Washington, D. C. 20555

09/20/78

Dear Mr. Stello:

Re: Turkey Point Units 3 and 4  
Docket Nos. 50-250 and 50-251  
Proposed Amendment to Facility Operating Licenses  
DPR-31 and DPR-41  
Additional Information

On August 9, 1978, Florida Power & Light Company requested an amendment to Facility Operating Licenses DPR-31 and DPR-41 as a result of a reevaluation of ECCS cooling performance (FPL letter L-78-264). This revised ECCS evaluation was performed by Westinghouse using an evaluation model approved in the internal NRC memorandum, Safety Evaluation Report on Revised Westinghouse ECCS Evaluation Model dated August 23, 1978 for D. B. Vassallo, Assistant Director for Light Water Reactors, from D. F. Ross, Assistant Director for Reactor Safety.

Attached as Attachment 1 are the results of 18 case analyses which were performed for the remainder of Turkey Point 3, Cycle 5, (present burnup over 4000 MWD/MTU) and for the upcoming Turkey Point 4, Cycle 5. These results are being forwarded to you in accordance with a request by a member of your staff.

Attachment 2 provides information concerning our planned test program to be performed following the current refueling outage. This information was requested by a member of your staff.

Attachment 3 revises Table 3 from the Turkey Point Unit 4, Cycle 5 Reload Safety Evaluation, which was submitted to you on June 19, 1978.

Very truly yours,

*Robert E. Uhrig*  
Robert E. Uhrig  
Vice President

REU/GDW/npb

780720262

Asst  
9/13





FIGURE 1

Turkey Point Unit 3 -- Cycle 5  
 Maximum [F<sub>0</sub> - Pre] vs. Axial Height  
 During Normal Operation from  
 1000 MWD/MTU Cycle 5 Burnup to EOL

MAX [F<sub>0</sub> - PRE]



0 1 2 3 4 5 6 7 8 9 10 11 12  
 BOTTOM CORE HEIGHT (FT) TOP

461510

10 X 10 TO THE CENTIMETER 10 X 10 CM.  
 KALUFEL & LESSER CO. MADE IN U.S.A.





FIGURE 2

Turkey Point Unit 4 - Cycle 5

Maximum  $[F_0 - P_{rel}]$  vs. Axial Height  
During Normal Operation



MAX. [F0 - P REL]

BOTTOM

CORE HEIGHT (FT)

TOP

KEUFFEL & ESSER CO. MADE IN U.S.A.




24

## Attachment 2

TABLE 3

TURKEY POINT 4 - CYCLE 4 AND 5  
SHUTDOWN REQUIREMENTS AND MARGINS

	<u>CYCLE 4</u>		<u>CYCLE 5</u>	
	<u>BOC</u>	<u>EOC</u>	<u>BOC</u>	<u>EOC</u>
<u>Control Rod Worth (%<math>\Delta\rho</math>)</u>				
All Rods Inserted Less Worst Stuck Rod	5.64	5.89	6.51	6.54
(1) Less 10%	5.08	5.30	5.86	5.89
<u>Control Rod Requirements (%<math>\Delta\rho</math>)</u>				
Reactivity Defects (Doppler, $T_{avg}$ , Void, Redistribution)	1.76	2.69	2.13	2.70
Rod Insertion Allowance	.70	.70	.50	.50
(2) Total Requirements	2.46	3.39	2.63	3.20
Shutdown Margin [(1)-(2)] % $\Delta\rho$	2.62	1.91	3.23	2.69
Required Shutdown Margin (% $\Delta\rho$ )	1.00	1.77	1.36	1.77





Attachment 3

UNIT 4 CYCLE 5  
STARTUP PHYSICS TESTS

1. Control Rod Worth

Acceptance criteria for total measured rod worth is +10% of design. If the measured rod worth does not meet the criteria, a calculation of shutdown margin will be made. If shutdown margin cannot be attained, the cause will be determined and corrective action taken before power escalation begins.

2. Temperature Coefficient

Acceptance criteria: Temperature coefficient is proven negative. If the temperature coefficient is not negative with ARO, a maximum boron will be specified below which the temperature coefficient is negative.

3. HZP Flux Map and 75% Power Flux Map

Acceptance criteria: A calculation of peaking factors shall be made to determine the maximum allowable power level. Values for maximum  $F_{\Delta H}$  and  $F_0$  must be less than those specified in the Technical Specifications to ensure that the assumptions used in the analysis for establishing DNB margin, Linear Heat Rate, and thermal margins remain valid during operations.

4. ARO Boron Concentration HZP

The HZP, ARO boron concentration acceptance criteria is +100 ppm of the design value. If the acceptance criteria cannot be met the cause shall be determined and appropriate action taken to find the deviation.

5. Power Defect

The acceptance criteria for the measurement is +10% of the design value. If this cannot be met the shutdown boron concentrations shall be adjusted for Hot and Cold Shutdown to ensure adequate shutdown margin.



10-1-78