

**SECTIONS**

<b>1.1</b>	<b>INTRODUCTION .....</b>	<b>1.1-1</b>
	1.1.1 GENERAL.....	1.1-1
	1.1.2 LICENSING HISTORY.....	1.1-1
<b>1.2</b>	<b>GENERAL PLANT DESCRIPTION.....</b>	<b>1.2-1</b>
	1.2.1 PLANT SITE .....	1.2-1
	1.2.2 PLANT ARRANGEMENT .....	1.2-1
	1.2.3 CONTAINMENT.....	1.2-2
	1.2.4 NUCLEAR STEAM SUPPLY SYSTEM (NSSS) .....	1.2-3
	1.2.5 TURBINE GENERATOR .....	1.2-10
<b>1.3</b>	<b>IDENTIFICATION OF CONTRACTORS .....</b>	<b>1.3-1</b>
<b>1.4</b>	<b>PRINCIPAL DESIGN CRITERIA.....</b>	<b>1.4-1</b>
	1.4.1 STATION DESIGN.....	1.4-1
	1.4.2 REACTOR .....	1.4-1
	1.4.3 PRIMARY COOLANT AND AUXILIARY SYSTEMS .....	1.4-2
	1.4.4 CONTAINMENT SYSTEM .....	1.4-3
	1.4.5 ENGINEERED SAFEGUARDS .....	1.4-3
	1.4.6 INSTRUMENTATION AND CONTROL .....	1.4-4
	1.4.7 ELECTRICAL SYSTEMS .....	1.4-4
	1.4.8 RADIOACTIVE WASTES AND RADIATION PROTECTION .....	1.4-4
	1.4.9 FUEL HANDLING AND STORAGE .....	1.4-4
	1.4.10 FIRE PROTECTION .....	1.4-4
	1.4.11 CIRCULATING WATER SYSTEM.....	1.4-5
	1.4.12 SECURITY .....	1.4-5
	1.4.13 EMERGENCY PLANNING .....	1.4-5
	1.4.14 PLANT OPERATION .....	1.4-5
	1.4.15 STRUCTURES.....	1.4-6
	1.4.16 SINGLE FAILURE CRITERIA .....	1.4-6
	1.4.16.1 Licensing Basis.....	1.4-6
	1.4.16.2 Active And Passive Failures .....	1.4-7
	1.4.16.3 Current Design Considerations .....	1.4-8

1.5	MAJOR PLANT MODIFICATIONS (DESIGN/CONSTRUCTION) .....	1.5-1
1.6	INSERVICE INSPECTION .....	1.6-1
1.6.1	HISTORICAL BACKGROUND .....	1.6-1
1.6.2	GENERAL.....	1.6-1
1.7	RESEARCH AND DEVELOPMENT REQUIREMENTS.....	1.7-1
1.7.1	FLOW MIXING AND FLOW DISTRIBUTION .....	1.7-1
1.7.2	CONTROL ROD TESTS .....	1.7-1
1.7.3	CONTROL ROD DRIVE MECHANISMS .....	1.7-1
1.7.4	FUEL BUNDLE DESIGN .....	1.7-2
1.7.5	REACTOR VESSEL FLOW TESTS .....	1.7-2
1.8	SPECIAL MAJOR PROGRAMS.....	1.8-1
1.8.1	SYSTEMATIC EVALUATION PROGRAM .....	1.8-1
1.8.1.1	Description of Program.....	1.8-1
1.8.1.2	SEP Reviews Confirmed Safety of Palisades Design.....	1.8-3
1.8.1.3	Continuing Applicability and Interpretation of SEP Information .....	1.8-4
1.8.2	TMI ACTION ITEMS (NUREG-0737).....	1.8-5
1.8.3	PIPE SUPPORT BASEPLATE DESIGNS USING CONCRETE EXPANSION ANCHOR BOLTS (IE BULLETIN 79-02) .....	1.8-5
1.8.4	SEISMIC ANALYSIS FOR AS-BUILT SAFETY-RELATED PIPING SYSTEMS (IE BULLETIN 79-14).....	1.8-6
1.8.5	UNRESOLVED SAFETY ISSUES (NUREG-0410).....	1.8-7
1.8.6	ENVIRONMENTAL QUALIFICATION OF "SAFETY-RELATED" ELECTRICAL EQUIPMENT (EEQ) (NUREG-0588) (USI A-24).....	1.8-8
1.8.7	CONTROL ROOM HABITABILITY (NUREG-0696) .....	1.8-8
1.8.8	EFFECTS OF PIPE RUPTURE (SEP TOPICS III.5.A AND B)....	1.8-8
1.8.9	STATION BLACKOUT (10 CFR 50.63) (USI A-44).....	1.8-9
1.8.10	SAFE SHUTDOWN .....	1.8-9
1.8.11	HEAVY LOADS .....	1.8-10

1.9	RENEWED FACILITY OPERATING LICENSE .....	1.9-1
1.9.1	SUMMARY DESCRIPTIONS OF AGING MANAGEMENT PROGRAMS .....	1.9-1
1.9.1.1	Nickel Alloy Program .....	1.9-2
1.9.1.2	ASME Section XI, Subsections IWB, IWC, IWD, IWF Inservice Inspection Program .....	1.9-3
1.9.1.3	Bolting Integrity Program .....	1.9-3
1.9.1.4	Boric Acid Corrosion Program.....	1.9-3
1.9.1.5	Buried Services Corrosion Monitoring Program ..	1.9-4
1.9.1.6	Closed Cycle Cooling Water Program .....	1.9-4
1.9.1.7	Containment Inservice Inspection Program .....	1.9-4
1.9.1.8	Containment Leakage Testing Program.....	1.9-5
1.9.1.9	Diesel Fuel Monitoring and Storage Program.....	1.9-5
1.9.1.10	Fire Protection Program .....	1.9-6
1.9.1.11	Flow Accelerated Corrosion Program .....	1.9-6
1.9.1.12	Non-EQ Electrical Commodities Condition Monitoring Program .....	1.9-7
1.9.1.13	One-Time Inspection Program .....	1.9-7
1.9.1.14	Open Cycle Cooling Water Program.....	1.9-9
1.9.1.15	Overhead Load Handling Systems Inspection Program.....	1.9-9
1.9.1.16	Reactor Vessel Integrity Surveillance Program..	1.9-10
1.9.1.17	Reactor Vessel Internals Inspection Program ....	1.9-10
1.9.1.18	Steam Generator Tube Integrity Program .....	1.9-11
1.9.1.19	Structural Monitoring Program .....	1.9-12
1.9.1.20	System Monitoring Program .....	1.9-12
1.9.1.21	Water Chemistry Program .....	1.9-13
1.9.1.22	Inspections of Opportunity for Internal Surfaces Of Selected Components and Corrosion Under Insulation .....	1.9-13
1.9.1.23	Compressed Air Monitoring Program.....	1.9-14

---

1.9.1.24	Oil Sampling and Analysis .....	1.9-14
1.9.1.25	Electrical Equipment Qualification Program.....	1.9-15
1.9.1.26	Fatigue Monitoring Program .....	1.9-15
1.9.2	<b>SUMMARY DESCRIPTIONS OF TIME-LIMITED AGING ANALYSES.....</b>	<b>1.9-15</b>
1.9.2.1	Reactor Vessel Neutron Embrittlement.....	1.9-16
1.9.2.2	Metal Fatigue .....	1.9-19
1.9.2.3	Environmental Qualification of Electrical Equipment.....	1.9-38
1.9.2.4	Containment Liner Plate, Metal Containments And Penetrations Fatigue Analysis .....	1.9-40
1.9.2.5	Other Plant-Specific Time-Limited Aging Analyses.....	1.9-42
1.9.3	<b>NEWLY IDENTIFIED STRUCTURES, SYSTEMS, AND COMPONENTS .....</b>	<b>1.9-47</b>
	<b>REFERENCES .....</b>	<b>1-1</b>

**LIST OF TABLES**

1-1	Chronological Licensing Events
1-2	Palisades Design Characteristics (Nominal Values)
1-3	Systematic Evaluation Program (SEP) and Integrated Assessment Program (IAP), Palisades Plant - NUREG-0820
1-4	Post-TMI Requirements for Consumers Power Company's, Palisades Plant - NUREG-0737
1-5	Unresolved Safety Issues
1-6	Estimated Use on March 24, 2031
1-7	Estimated RT <sub>PTS</sub> on March 24, 2031
1-8	Summary of Fatigue Usage Factors at NUREG/CR-6260 Sample Locations Applicable to Palisades
1-9	Long-Term Commitments for License Renewal of Palisades Nuclear Plant
1-10	Listing of Newly Identified Systems, Structures, and Components per 10 CFR 50.37(b)

**LIST OF FIGURES**

1-1 Sh 1	Plant Site Plan
1-1 Sh 2	Plant Area Plan
1-2	Equipment Location - Reactor Building, Plan of Elevation 570'-0"
1-3	Equipment Location - Auxiliary Building, Radwaste Modifications Plan of Elevation 590'-0"
1-4	Equipment Location - Auxiliary and Reactor Building, Radwaste Modifications Plan of Elevation 607'-6"
1-5	Equipment Location - Auxiliary and Reactor Building, Radwaste Modifications Plan of Elevation 625'-0"
1-6	Equipment Location - Auxiliary Building, Radwaste Modifications Plan of Elevation 649'-0"
1-7	Equipment Location - Reactor Building, Sections A-A, B-B, C-C, D-D and E-E
1-8	Equipment Location - Auxiliary Building, Radwaste Modifications Section F-F
1-9	Equipment Location - Reactor Building, Section G-G
1-10	Equipment Location - Reactor Building, Plan of Elevation 602'-0" and Sections H-H, J-J and K-K
1-11	Equipment Location - Reactor Building, Plan of Elevation 700'-0"
1-12 Sh 1	Equipment Location - Turbine Building, Plan of Elevation 590'-0"
1-12 Sh 2	Equipment Location - Turbine Building, Pump Structure Plan of Elevation 590'-0"
1-13	Equipment Location - Turbine Building, Plan of Elevation 607'-6"
1-14	Equipment Location - Turbine Building, Plan of Elevation 625'-0"
1-15	Equipment Location - Turbine Building, Sections
1-16	Equipment Location - Turbine Building, Sections
1-17	Equipment Location - Auxiliary Building, Radwaste Modifications Sections
1-18	General Arrangement - Condensate and Makeup Demin Building

**SECTIONS**

<b>2.1</b>	<b>LOCATION.....</b>	<b>2.1-2</b>
	<b>2.1.1 TOPOGRAPHY AND LAND USAGE.....</b>	<b>2.1-2</b>
	<b>2.1.2 POPULATION .....</b>	<b>2.1-3</b>
	<b>2.1.3 NEARBY INDUSTRIAL, TRANSPORTATION AND MILITARY FACILITIES .....</b>	<b>2.1-5</b>
<b>2.2</b>	<b>HYDROLOGY .....</b>	<b>2.2-1</b>
	<b>2.2.1 GROUNDWATER.....</b>	<b>2.2-1</b>
	<b>2.2.2 GENERAL LAKE HYDROLOGY.....</b>	<b>2.2-4</b>
<b>2.3</b>	<b>GEOLOGY .....</b>	<b>2.3-1</b>
	<b>2.3.1 PREGLACIAL GEOLOGY .....</b>	<b>2.3-1</b>
	<b>2.3.2 GLACIAL GEOLOGY.....</b>	<b>2.3-2</b>
	<b>2.3.3 FAULTS.....</b>	<b>2.3-3</b>
	<b>2.3.4 ENGINEERING GEOLOGY.....</b>	<b>2.3-3</b>
	<b>2.3.5 CONCLUSIONS .....</b>	<b>2.3-5</b>
<b>2.4</b>	<b>SEISMICITY .....</b>	<b>2.4-1</b>
	<b>2.4.1 SITE GEOLOGY.....</b>	<b>2.4-1</b>
	<b>2.4.2 SEISMIC HISTORY .....</b>	<b>2.4-2</b>
	<b>2.4.3 DISCUSSION .....</b>	<b>2.4-3</b>
	<b>2.4.4 CONCLUSIONS .....</b>	<b>2.4-4</b>
<b>2.5</b>	<b>METEOROLOGY .....</b>	<b>2.5-1</b>
	<b>2.5.1 GENERAL CLIMATOLOGY OF PALISADES PLANT AREA.....</b>	<b>2.5-1</b>
	<b>2.5.2 METEOROLOGICAL PROGRAM HISTORY .....</b>	<b>2.5-3</b>
	<b>2.5.2.1 Preoperational Program.....</b>	<b>2.5-3</b>
	<b>2.5.2.2 Interim Program.....</b>	<b>2.5-4</b>
	<b>2.5.2.3 Present Program .....</b>	<b>2.5-4</b>

2.5.3	DISCUSSION OF EXISTING 1977/1978 DATA .....	2.5-5
2.5.3.1	Wind Frequency Distributions .....	2.5-5
2.5.3.2	Stability Wind Roses .....	2.5-6
2.5.3.3	Persistence .....	2.5-6
2.5.3.4	Hourly Data .....	2.5-7
2.5.3.5	Data Recovery .....	2.5-8
2.5.4	DIFFUSION CLIMATOLOGY .....	2.5-8
2.5.4.1	Turbulence and Diffusion Regimes .....	2.5-8
2.5.4.2	Shoreline Influences .....	2.5-9
2.5.5	SHORT-TERM DISPERSION PARAMETERS .....	2.5-9
2.5.5.1	X/Q Determination for TID Analyses.....	2.5-9
2.5.5.2	X/Q Determination for AST Analyses.....	2.5-10
2.5.5.2.1	Offsite X/Q Determination.....	2.5-11
2.5.5.2.2	Control Room X/Q Determination.....	2.5-12
2.5.6	LONG-TERM DISPERSION PARAMETERS .....	2.5-12
2.6	ENVIRONMENTAL SURVEILLANCE.....	2.6-1
2.6.1	SAMPLE SENSITIVITY .....	2.6-2
2.6.2	SAMPLE TYPE AND FREQUENCY .....	2.6-2
2.6.3	SAMPLING STATIONS.....	2.6-2
2.6.4	SAMPLE TYPES .....	2.6-3
2.6.5	SUMMARY OF PREOPERATIONAL RESULTS .....	2.6-3
2.6.6	ADJUSTMENTS TO THE ENVIRONMENTAL SURVEY .....	2.6-5
	REFERENCES .....	2-1

**LIST OF TABLES**

2-1	Agricultural Statistics
2-2	Population Related to Selected Land Use Categories
2-3	People per Dwelling by Township and City
2-4	Permanent Resident Population Distribution
2-5	Transient Population Related to Educational Facilities Within 10 Miles of Palisades
2-6	Major Employer's Work Force Distribution Within 10 Miles of the Palisades Plant
2-7	Motels and Cottages Within 10 Miles of Palisades Plant
2-8	Campsites Within 10 Miles of Palisades Plant
2-9	Maximum Probable Population for All Categories
2-10	Population Growth and Density by County
2-11	Field Permeability Test Results
2-12	Analyses of Soil Samples
2-13	Epicenter Distance From Site Versus Reported Intensity
2-14	Stability Class Comparison by Wind Sector
2-15	Meteorological Data Recovery Rates
2-16	Physical Characteristics of the Routine Release Points for the Palisades Nuclear Plant
2-17	Relative Dispersion (X/Q) Values ( $s/m^3$ ) Versus Averaging Time, Turbine Building Vent - Ground Level Release Exclusion Area Boundary
2-18	Relative Dispersion (X/Q) Values ( $s/m^3$ ) Versus Averaging Time, Turbine Building Vent - Ground Level Release Low Population Zone
2-19	Annual Average X/Q ( $sec/m^3$ ) Values, Turbine Building Vent - Ground Level Release
2-20	Detection Capabilities for Environmental Sample Analysis
2-21	X/Q Values ( $s/m^3$ ) – Ground Level Release – Exclusion Area Boundary
2-22	X/Q Values ( $s/m^3$ ) – Ground Level Release – Low Population Zone



**LIST OF FIGURES**

2-1	Population Centers - 1990 Census Over 10,000, 0 to 50 Miles
2-2	Site Layout
2-3	Site Topography, Boring Locations, and Seismic Profiles
2-4	Topography Cross Sections
2-5	Selected Land Use Categories
2-6	Population Centers - 1990 Census Over 1,000, 0 to 50 Miles
2-7	Permanent Residential Population Breakdown (1990)
2-8	Population Distribution (1990), 10 to 50 Miles
2-9	Groundwater Elevations and Area Gradients
2-10	Geologic Map and Cross Section
2-11	1966 Drilling Program, Drill Hole and Cross Section Locations
2-12	1966 Drilling Program, Drill Logs and Soil Penetration Test Results
2-13	1966 Drilling Program, Subsurface Sections
2-14	Regional Structures, Bedrock Geology, Major Faulting and Epicenters
2-15	Compressional (P)Wave Velocities From Seismic Survey
2-16	Seismic Regionalization: Zones of Probable Maximum Intensity (MM)
2-17	Meteorological Tower Locations
2-18	10 Meter Wind Frequency Distribution - Palisades Site, December 1, 1977 through February 28, 1978
2-19	60 Meter Wind Frequency Distribution - Palisades Site, December 1, 1977 through February 28, 1978
2-20	10 Meter Wind Frequency Distribution - Palisades Site, March 1 through May 31, 1978
2-21	60 Meter Wind Frequency Distribution - Palisades Site, March 1 through May 31, 1978
2-22	10 Meter Wind Frequency Distribution - Palisades Site, June 1 through August 31, 1978
2-23	60 Meter Wind Frequency Distribution - Palisades Site, June 1 through August 31, 1978
2-24	10 Meter Wind Frequency Distribution - Palisades Site, September 1 through November 30, 1978
2-25	60 Meter Wind Frequency Distribution - Palisades Site, September 1 through November 30, 1978
2-26	10 Meter Wind Frequency Distribution - Palisades Site, December 1, 1977 through November 30, 1978
2-27	60 Meter Wind Frequency Distribution - Palisades Site, December 1, 1977 through November 30 1978

**SECTIONS**

<b>3.1</b>	<b>INTRODUCTION .....</b>	<b>3.1-1</b>
<b>3.2</b>	<b>DESIGN BASES .....</b>	<b>3.2-1</b>
	<b>3.2.1 PERFORMANCE OBJECTIVES .....</b>	<b>3.2-1</b>
	<b>3.2.2 DESIGN OBJECTIVES .....</b>	<b>3.2-1</b>
	<b>3.2.3 DESIGN LIMITS .....</b>	<b>3.2-2</b>
<b>3.3</b>	<b>REACTOR DESIGN .....</b>	<b>3.3-1</b>
	<b>3.3.1 GENERAL SUMMARY .....</b>	<b>3.3-1</b>
	<b>3.3.2 NUCLEAR DESIGN AND EVALUATION.....</b>	<b>3.3-2</b>
	<b>3.3.2.1 Reactivity and Control Requirements.....</b>	<b>3.3-2</b>
	<b>3.3.2.2 Reactivity Coefficients .....</b>	<b>3.3-4</b>
	<b>3.3.2.3 Control Blade Worths.....</b>	<b>3.3-6</b>
	<b>3.3.2.4 Reactivity Insertion Rates.....</b>	<b>3.3-7</b>
	<b>3.3.2.5 Power Distribution and Power Escalation Rates..</b>	<b>3.3-7</b>
	<b>3.3.2.6 Neutron Fluence on Pressure Vessel .....</b>	<b>3.3-9</b>
	<b>3.3.2.7 Nuclear Evaluation .....</b>	<b>3.3-10</b>
	<b>3.3.2.8 Reactor Stability .....</b>	<b>3.3-10</b>
	<b>3.3.3 THERMAL-HYDRAULIC DESIGN AND EVALUATION .....</b>	<b>3.3-14</b>
	<b>3.3.3.1 Thermal-Hydraulic Design Criteria .....</b>	<b>3.3-14</b>
	<b>3.3.3.2 Plant Parameter Variations.....</b>	<b>3.3-15</b>
	<b>3.3.3.3 Core Flow Distribution.....</b>	<b>3.3-15</b>
	<b>3.3.3.4 Trip Set Points .....</b>	<b>3.3-16</b>
	<b>3.3.4 MECHANICAL DESIGN AND EVALUATION .....</b>	<b>3.3-17</b>
	<b>3.3.4.1 Reactor Internals .....</b>	<b>3.3-17</b>
	<b>3.3.4.2 Control Rod Drive Mechanism .....</b>	<b>3.3-22</b>
	<b>3.3.4.3 Core Mechanical Design .....</b>	<b>3.3-28</b>
	<b>REFERENCES .....</b>	<b>3-1</b>

**LIST OF TABLES**

- 3-1 Primary Stress Limits for Critical Reactor Vessel Internal Structures
- 3-2 Fuel Bundle Component Description

**LIST OF FIGURES**

- 3-1 Reactor Arrangement
- 3-2 Position of Fuel Assemblies and Control Rod Groups in the Palisades Core
- 3-3 Control Rod Insertion Limits
- 3-4 Reactivity Difference Between Fundamental and Excited States of a Bare Cylindrical Reactor
- 3-5 Thermal Neutron Flux at the Center of the Core vs Time
- 3-6 Damping Coefficient vs Reactivity Difference Between Fundamental and Excited State
- 3-7 End of Life Axial Oscillations With Doppler Feedback, Full Power (2-Hour Time Steps)
- 3-8 Split Detector Response to Axial Power Profiles in the Core
- 3-9 Reactor Core Cross Section
- 3-10 Reactor Arrangement
- 3-11 Upper Guide Structure Assembly
- 3-12 Hold Down Ring
- 3-13 Control Rod Drive Mechanism
- 3-14 Fuel Bundle Assembly, Sheet 1 of 2
- 3-15 Fuel Bundle Assembly, Sheet 2 of 2
- 3-16 Deleted
- 3-17 Spacer Assembly, HTP
- 3-18 UO<sub>2</sub> Fuel Rod Assembly
- 3-19 Fuel Rod Assembly, Gadolinia Bearing
- 3-20 Control Rod

**SECTIONS**

<b>4.1</b>	<b>INTRODUCTION .....</b>	<b>4.1-1</b>
<b>4.2</b>	<b>DESIGN BASIS .....</b>	<b>4.2-1</b>
	<b>4.2.1 PERFORMANCE OBJECTIVES AND PARAMETERS FOR NORMAL CONDITIONS .....</b>	<b>4.2-1</b>
	<b>4.2.2 DESIGN CYCLIC LOADS .....</b>	<b>4.2-1</b>
	<b>4.2.3 DESIGN SERVICE LIFE CONSIDERATIONS .....</b>	<b>4.2-2</b>
	<b>4.2.4 CODES ADHERED TO AND COMPONENT CLASSIFICATION...4.2-3</b>	
	<b>4.2.5 SAFETY CONSIDERATIONS OF DESIGN PARAMETERS.....4.2-3</b>	
	<b>4.2.6 PRIMARY COOLANT SYSTEM ASYMMETRIC LOADS .....</b>	<b>4.2-4</b>
<b>4.3</b>	<b>SYSTEM DESIGN AND OPERATION .....</b>	<b>4.3-1</b>
	<b>4.3.1 GENERAL DESCRIPTION.....4.3-1</b>	
	<b>4.3.2 INTERFACES WITH OTHER SYSTEMS .....</b>	<b>4.3-2</b>
	<b>4.3.3 REACTOR VESSEL .....</b>	<b>4.3-3</b>
	<b>4.3.4 STEAM GENERATOR .....</b>	<b>4.3-5</b>
	<b>4.3.4.1 Steam Generator Tube Degradation .....</b>	<b>4.3-8</b>
	<b>4.3.4.2 Steam Generator Replacement .....</b>	<b>4.3-8</b>
	<b>4.3.5 PRIMARY COOLANT PUMPS.....4.3-9</b>	
	<b>4.3.6 PRIMARY COOLANT PIPING .....</b>	<b>4.3-11</b>
	<b>4.3.7 PRESSURIZER .....</b>	<b>4.3-13</b>
	<b>4.3.8 QUENCH TANK .....</b>	<b>4.3-19</b>
	<b>4.3.9 VALVES .....</b>	<b>4.3-20</b>
	<b>4.3.9.1 General Criteria .....</b>	<b>4.3-20</b>
	<b>4.3.9.2 Pressurizer Throttling (Spray) Control Valves ....4.3-21</b>	
	<b>4.3.9.3 Power-Operated Relief Valves (PORV) and Block Valves .....</b>	<b>4.3-22</b>
	<b>4.3.9.4 Spring-Actuated Primary Safety Valves .....</b>	<b>4.3-23</b>
	<b>4.3.10 ENVIRONMENTAL PROTECTION .....</b>	<b>4.3-24</b>
	<b>4.3.11 MATERIALS EXPOSED TO COOLANT .....</b>	<b>4.3-24</b>
	<b>4.3.12 INSULATION.....4.3-24</b>	
	<b>4.3.13 SYSTEM CHEMICAL TREATMENT .....</b>	<b>4.3-25</b>

---

<b>4.4</b>	<b>SYSTEM DESIGN EVALUATION.....</b>	<b>4.4-1</b>
	4.4.1 DESIGN MARGIN .....	4.4-1
	4.4.2 PREVENTION OF BRITTLE FRACTURE.....	4.4-2
<b>4.5</b>	<b>TESTS AND INSPECTIONS .....</b>	<b>4.5-1</b>
	4.5.1 GENERAL .....	4.5-1
	4.5.2 NIL DUCTILITY TRANSITION TEMPERATURE DETERMINATION.....	4.5-1
	4.5.3 SURVEILLANCE PROGRAM .....	4.5-2
	4.5.4 NONDESTRUCTIVE TESTS .....	4.5-7
	4.5.5 ADDITIONAL TESTS .....	4.5-9
	4.5.6 INSERVICE INSPECTION.....	4.5-10
	4.5.7 NDTT OF OTHER PRIMARY SYSTEM COMPONENTS .....	4.5-13
	4.5.8 NONDESTRUCTIVE TESTS OF OTHER PRIMARY SYSTEM COMPONENTS.....	4.5-13
<b>4.6</b>	<b>OPERATING LIMITATIONS .....</b>	<b>4.6-1</b>
<b>4.7</b>	<b>PRIMARY COOLANT PRESSURE BOUNDARY LEAKAGE DETECTION.....</b>	<b>4.7-1</b>
	4.7.1 LEAK DETECTION .....	4.7-1
	4.7.2 OPERATOR ACTION FOLLOWING LEAK DETECTION.....	4.7-2
<b>4.8</b>	<b>PRIMARY COOLANT GAS VENT SYSTEM .....</b>	<b>4.8-1</b>
	<b>REFERENCES .....</b>	<b>4-1</b>

**LIST OF TABLES**

4-1	Primary Coolant System Parameters
4-2	Primary Coolant System Code Requirements
4-3	Reactor Vessel Parameters
4-4	Steam Generator Parameters
4-5	Secondary Safety Valve Parameters
4-6	Primary Coolant Pump Parameters
4-7	Piping List
4-8	Pressurizer Parameters
4-9	Pressurizer Normal Level Control Program/Pressurizer Backup Level Control Program
4-10	Pressurizer Safety Valve Parameters
4-11	Quench Tank Parameters
4-12	Actuator-Operated Throttling Valve Parameters
4-13	Actuator-Operated Block Valve Parameters
4-14	Pressurizer Power-Operated Relief Valve Parameters
4-15	Materials Exposed to Coolant
4-16	Primary Coolant Chemistry
4-17	Summary of Specimens Provided for Each Exposure Location / Summary of Specimens Provided for Each Supplemental Surveillance Capsule
4-18	Primary Coolant System Preservice Quality Assurance Program
4-19	Primary Coolant System Inspection CE Requirements
4-20	Reactor Vessel Surveillance Coupon Removal Schedule

**LIST OF FIGURES**

4-1 Sh 1	Piping and Instrumentation Diagram, Primary Coolant System
4-1 Sh 2	Piping and Instrumentation Diagram, Primary Coolant System
4-2	Reactor Vessel
4-3	Steam Generator
4-4	Primary Coolant Circulating Pump
4-5	Deleted
4-6	Enlarged View of Pump Seal Area
4-7	Primary Coolant Pump Characteristics Curve
4-8	Pressurizer
4-9	Temperature Control Program
4-10	Pressurizer Level Set Point vs $T_{AVG}$
4-11	Location of Surveillance Capsule Assemblies
4-12	Typical Surveillance Capsule Assembly
4-13	Typical Charpy Impact Compartment Assembly
4-14	Typical Tensile - Monitor Compartment Assembly
4-15	Variable LTOP Setpoints

**SECTIONS**

<b>5.1</b>	<b>GENERAL DESIGN CRITERIA .....</b>	<b>5.1-1</b>
5.1.1	INTRODUCTION .....	5.1-1
5.1.2	<b>GROUP I: OVERALL REQUIREMENTS (CRITERIA 1-5).....</b>	<b>5.1-2</b>
5.1.2.1	Criterion 1 - Quality Standards and Records.....	5.1-2
5.1.2.2	Criterion 2 - Design Bases for Protection Against Natural Phenomena .....	5.1-3
5.1.2.3	Criterion 3 - Fire Protection.....	5.1-3
5.1.2.4	Criterion 4 - Environmental and Missile Design Bases .....	5.1-4
5.1.2.5	Criterion 5 - Sharing of Structures, Systems and Components.....	5.1-5
5.1.2.6	Conclusions .....	5.1-5
5.1.3	<b>GROUP II: PROTECTION BY MULTIPLE FISSION PRODUCT BARRIERS (CRITERIA 10-19) .....</b>	<b>5.1-5</b>
5.1.3.1	Criterion 10 - Reactor Design.....	5.1-5
5.1.3.2	Criterion 11 - Reactor Inherent Protection.....	5.1-6
5.1.3.3	Criterion 12 - Suppression of Reactor Power Oscillations.....	5.1-6
5.1.3.4	Criterion 13 - Instrumentation and Control.....	5.1-7
5.1.3.5	Criterion 14 - Reactor Coolant Pressure Boundary .....	5.1-8
5.1.3.6	Criterion 15 - Reactor Coolant System Design.....	5.1-8
5.1.3.7	Criterion 16 - Containment Design .....	5.1-9
5.1.3.8	Criterion 17 - Electrical Power Systems.....	5.1-9
5.1.3.9	Criterion 18 - Inspection and Testing of Electrical Power Systems.....	5.1-11
5.1.3.10	Criterion 19 - Control Room .....	5.1-12
5.1.3.11	Conclusions .....	5.1-13
5.1.4	<b>GROUP III: PROTECTION AND REACTIVITY CONTROL SYSTEMS (CRITERIA 20-29).....</b>	<b>5.1-13</b>
5.1.4.1	Criterion 20 - Protection System Functions .....	5.1-13
5.1.4.2	Criterion 21 - Protection System Reliability and Testability.....	5.1-14
5.1.4.3	Criterion 22 - Protection System Independence.....	5.1-15
5.1.4.4	Criterion 23 - Protection System Failure Modes.....	5.1-16
5.1.4.5	Criterion 24 - Separation of Protection and Control Systems .....	5.1-16
5.1.4.6	Criterion 25 - Protection System Requirements for Reactivity Control Malfunctions.....	5.1-17
5.1.4.7	Criterion 26 - Reactivity Control System Redundancy and Capability .....	5.1-17
5.1.4.8	Criterion 27 - Combined Reactivity Control Systems Capability .....	5.1-18
5.1.4.9	Criterion 28 - Reactivity Limits .....	5.1-18



	5.1.4.10	Criterion 29 - Protection Against Anticipated Operational Occurrences .....	5.1-19
	5.1.4.11	Conclusions .....	5.1-19
5.1.5	<b>GROUP IV: FLUID SYSTEMS (CRITERIA 30-46)</b> .....		5.1-20
	5.1.5.1	Criterion 30 - Quality of Reactor Coolant Pressure Boundary .....	5.1-20
	5.1.5.2	Criterion 31 - Fracture Prevention of Reactor Coolant Pressure Boundary.....	5.1-21
	5.1.5.3	Criterion 32 - Inspection of Reactor Coolant Pressure Boundary .....	5.1-22
	5.1.5.4	Criterion 33 - Reactor Coolant Makeup .....	5.1-22
	5.1.5.5	Criterion 34 - Residual Heat Removal .....	5.1-23
	5.1.5.6	Criterion 35 - Emergency Core Cooling .....	5.1-24
	5.1.5.7	Criterion 36 - Inspection of Emergency Core Cooling System .....	5.1-25
	5.1.5.8	Criterion 37 - Testing of Emergency Core Cooling System .....	5.1-25
	5.1.5.9	Criterion 38 - Containment Heat Removal .....	5.1-26
	5.1.5.10	Criterion 39 - Inspection of Containment Heat Removal System .....	5.1-27
	5.1.5.11	Criterion 40 - Testing of Containment Heat Removal System .....	5.1-27
	5.1.5.12	Criterion 41 - Containment Atmosphere Cleanup.....	5.1-28
	5.1.5.13	Criterion 42 - Inspection of Containment Atmosphere Cleanup Systems .....	5.1-28
	5.1.5.14	Criterion 43 - Testing of Containment Atmosphere Cleanup Systems .....	5.1-29
	5.1.5.15	Criterion 44 - Cooling Water.....	5.1-29
	5.1.5.16	Criterion 45 - Inspection of Cooling Water System and Criterion 46 - Testing of Cooling Water System .....	5.1-30
	5.1.5.17	Conclusions .....	5.1-30
5.1.6	<b>GROUP V: REACTOR CONTAINMENT (CRITERIA 50-57)</b> .....		5.1-31
	5.1.6.1	Criterion 50 - Containment Design Basis.....	5.1-31
	5.1.6.2	Criterion 51 - Fracture Prevention of Containment Pressure Boundary .....	5.1-32
	5.1.6.3	Criterion 52 - Capability for Containment Leakage Rate Testing .....	5.1-32
	5.1.6.4	Criterion 53 - Provisions for Containment Testing and Inspection .....	5.1-33
	5.1.6.5	Criterion 54 - Piping Systems Penetrating Containment.....	5.1-33
	5.1.6.6	Criterion 55 - Primary Coolant Pressure Boundary Penetrating Containment.....	5.1-34
	5.1.6.7	Criterion 56 - Primary Containment Isolation .....	5.1-35
	5.1.6.8	Criterion 57 - Closed System Isolation Valves.....	5.1-36
	5.1.6.9	Conclusions .....	5.1-38

5.1.7	<b>GROUP VI: FUEL AND RADIOACTIVITY CONTROL</b>	
	<b>(CRITERIA 60-64)</b> .....	<b>5.1-39</b>
5.1.7.1	<b>Criterion 60 - Control of Releases of</b>	
	<b>Radioactive Materials to the Environment</b> .....	<b>5.1-39</b>
5.1.7.2	<b>Criterion 61 - Fuel Storage and Handling and</b>	
	<b>Radioactivity Control</b> .....	<b>5.1-40</b>
5.1.7.3	<b>Criterion 62 - Prevention of Criticality in Fuel</b>	
	<b>Storage and Handling</b> .....	<b>5.1-41</b>
5.1.7.4	<b>Criterion 63 - Monitoring Fuel and Waste</b>	
	<b>Storage</b> .....	<b>5.1-42</b>
5.1.7.5	<b>Criterion 64 - Monitoring Radioactivity</b>	
	<b>Releases</b> .....	<b>5.1-42</b>
5.1.7.6	<b>Conclusions</b> .....	<b>5.1-43</b>
5.1.8	<b>OVERALL CONCLUSION</b> .....	<b>5.1-43</b>
5.2	<b>CLASSIFICATION OF STRUCTURES, SYSTEMS AND COMPONENTS</b> ....	<b>5.2-1</b>
5.2.1	<b>BACKGROUND INFORMATION</b> .....	<b>5.2-1</b>
	5.2.1.1 <b>Classification Overview</b> .....	<b>5.2-1</b>
	5.2.1.2 <b>Original Palisades Design Review</b> .....	<b>5.2-2</b>
5.2.2	<b>CONSUMERS DESIGN CLASSIFICATIONS</b> .....	<b>5.2-3</b>
	5.2.2.1 <b>Design - Class 1</b> .....	<b>5.2-3</b>
	5.2.2.2 <b>Design - Class 2</b> .....	<b>5.2-4</b>
	5.2.2.3 <b>Design - Class 3</b> .....	<b>5.2-4</b>
	5.2.2.4 <b>Design - Palisades Modifications</b> .....	<b>5.2-4</b>
	5.2.2.5 <b>Inservice Inspection</b> .....	<b>5.2-5</b>
	5.2.2.6 <b>Service Quality Group Classification</b> .....	<b>5.2-5</b>
	5.2.2.7 <b>Service - Electrical and Instrumentation and</b>	
	<b>Controls Equipment Classification</b> .....	<b>5.2-5</b>
	5.2.2.8 <b>Safety-Related Classification</b> .....	<b>5.2-6</b>
	5.2.2.8.1 <b>Safety-Related</b> .....	<b>5.2-6</b>
	5.2.2.8.2 <b>Important to Safety</b> .....	<b>5.2-6</b>
	<b>REFERENCES</b> .....	<b>5.2-7</b>
5.3	<b>WIND AND TORNADO LOADINGS</b> .....	<b>5.3-1</b>
5.3.1	<b>WIND</b> .....	<b>5.3-1</b>
	5.3.1.1 <b>Design Parameters</b> .....	<b>5.3-1</b>
	5.3.1.2 <b>Forces on Structures</b> .....	<b>5.3-1</b>
5.3.2	<b>TORNADO</b> .....	<b>5.3-2</b>
	5.3.2.1 <b>Design Parameters</b> .....	<b>5.3-2</b>
	5.3.2.2 <b>Forces on Structures</b> .....	<b>5.3-2</b>
5.3.3	<b>PLANT REEVALUATION</b> .....	<b>5.3-3</b>
	<b>REFERENCES</b> .....	<b>5.3-4</b>

<b>5.4</b>	<b>WATER LEVEL DESIGN .....</b>	<b>5.4-1</b>
5.4.1	<b>FLOODING FROM NATURAL SOURCES .....</b>	<b>5.4-1</b>
5.4.1.1	<b>Description of Events .....</b>	<b>5.4-1</b>
5.4.1.2	<b>Effects on Consumers Design Class 1 Structures and Safety-Related Equipment .....</b>	<b>5.4-1</b>
5.4.2	<b>FLOODING AND WETTING FROM PLANT SOURCES .....</b>	<b>5.4-2</b>
	<b>REFERENCES .....</b>	<b>5.4-4</b>
<b>5.5</b>	<b>MISSILE PROTECTION.....</b>	<b>5.5-1</b>
5.5.1	<b>TORNADO MISSILES.....</b>	<b>5.5-1</b>
5.5.1.1	<b>Design Parameters.....</b>	<b>5.5-1</b>
5.5.1.1.1	<b>Containment Structure, Auxiliary Building (including Radwaste Addition), Turbine Building.....</b>	<b>5.5-1</b>
5.5.1.1.2	<b>Auxiliary Building TSC/EER/HVAC Addition .....</b>	<b>5.5-1</b>
5.5.1.1.3	<b>Diesel Fuel Oil Storage Tank Housing.....</b>	<b>5.5-1</b>
5.5.1.1.4	<b>Condensate Storage Tank .....</b>	<b>5.5-2</b>
5.5.1.1.5	<b>Equipment Hatch .....</b>	<b>5.5-3</b>
5.5.1.2	<b>Structural Considerations .....</b>	<b>5.5-4</b>
5.5.1.3	<b>Plant Reevaluation .....</b>	<b>5.5-4</b>
5.5.1.3.1	<b>Review Parameters .....</b>	<b>5.5-4</b>
5.5.1.3.2	<b>Summary .....</b>	<b>5.5-4</b>
5.5.2	<b>TURBINE MISSILES.....</b>	<b>5.5-5</b>
5.5.2.1	<b>Background .....</b>	<b>5.5-5</b>
5.5.2.2	<b>High-Pressure Turbine Missiles .....</b>	<b>5.5-5</b>
5.5.2.3	<b>Low-Pressure Turbine Missiles .....</b>	<b>5.5-6</b>
5.5.2.4	<b>Turbine Overspeed Protection System.....</b>	<b>5.5-7</b>
5.5.3	<b>INTERNALLY GENERATED MISSILES.....</b>	<b>5.5-7</b>
5.5.3.1	<b>Containment Missiles .....</b>	<b>5.5-7</b>
5.5.3.2	<b>Plant Reevaluation .....</b>	<b>5.5-8</b>
5.5.4	<b>SITE PROXIMITY MISSILES .....</b>	<b>5.5-9</b>
	<b>REFERENCES .....</b>	<b>5.5-11</b>
<b>5.6</b>	<b>DYNAMIC EFFECTS OF PIPE RUPTURE .....</b>	<b>5.6-1</b>
5.6.1	<b>DEFINITIONS.....</b>	<b>5.6-1</b>
5.6.2	<b>DESIGN BASES .....</b>	<b>5.6-2</b>
5.6.2.1	<b>Systems in Which Design Basis Failures Occur..</b>	<b>5.6-2</b>
5.6.2.2	<b>Identification of Essential Systems and Components .....</b>	<b>5.6-2</b>
5.6.2.3	<b>Limiting Conditions .....</b>	<b>5.6-3</b>
5.6.2.4	<b>Safety Evaluation .....</b>	<b>5.6-4</b>
5.6.3	<b>CRITERIA USED TO DEFINE BREAKS .....</b>	<b>5.6-5</b>
5.6.3.1	<b>ASME Section III, Class 1 Piping .....</b>	<b>5.6-5</b>
5.6.3.2	<b>ASME Section III Class 2 and 3 Piping (other than between containment isolation valves) .....</b>	<b>5.6-6</b>
5.6.3.3	<b>Non-nuclear Class Piping.....</b>	<b>5.6-7</b>
5.6.3.4	<b>Piping Penetrating Containment.....</b>	<b>5.6-8</b>

5.6.4	PROTECTIVE MEASURES .....	5.6-9
5.6.5	JET IMPINGEMENT.....	5.6-10
5.6.6	PLANT MODIFICATION LINE-BREAK ANALYSIS .....	5.6-11
5.6.6.1	Plant Modifications Involving High- or Moderate-Energy Piping.....	5.6-11
5.6.6.2	Plant Modifications Involving Essential Systems and Components .....	5.6-11
5.6.7	HISTORY OF PALISADES HIGH-ENERGY LINE-BREAK ANALYSIS .....	5.6-11
5.6.7.1	High-Energy Line Breaks Outside Containment .....	5.6-11
5.6.7.2	High-Energy Line Breaks Inside Containment ...	5.6-15
5.6.7.3	Moderate-Energy System Pipe-Break Evaluation .....	5.6-16
	REFERENCES .....	5.6-18
5.7	SEISMIC DESIGN .....	5.7-1
5.7.1	SEISMIC INPUT .....	5.7-1
5.7.1.1	Design Bases .....	5.7-1
5.7.1.2	Ground Design Response Spectra.....	5.7-2
5.7.1.3	Floor Design Response Spectra.....	5.7-2
5.7.1.4	Damping Values .....	5.7-3
5.7.2	SEISMIC ANALYSIS OF MAJOR CP CO DESIGN CLASS 1 STRUCTURES .....	5.7-4
5.7.2.1	Containment Building.....	5.7-5
5.7.2.2	Auxiliary Building.....	5.7-6
5.7.3	SEISMIC ANALYSIS OF OTHER CP CO DESIGN CLASS 1 STRUCTURES .....	5.7-7
5.7.3.1	Turbine Building.....	5.7-7
5.7.3.1.1	CP Co Design Class 1 Portion.....	5.7-7
5.7.3.1.2	CP Co Design Class 3 Portion.....	5.7-7
5.7.3.2	Intake Structure.....	5.7-9
5.7.3.3	Auxiliary Building Radwaste Addition .....	5.7-9
5.7.3.4	Auxiliary Building TSC/EER Addition.....	5.7-10
5.7.3.5	Other Auxiliary Building Additions.....	5.7-12
5.7.3.6	CP Co Design Class 1 Tank Foundations .....	5.7-12
5.7.3.7	Miscellaneous Frames and Trusses .....	5.7-12

5.7.4	SEISMIC ANALYSIS OF CP CO DESIGN CLASS 1 PIPING .....	5.7-13
5.7.5	SEISMIC ANALYSIS OF MAJOR CP CO DESIGN CLASS 1 SYSTEM AND COMPONENTS .....	5.7-16
5.7.5.1	Primary Coolant System.....	5.7-16
5.7.5.1.1	Reactor Vessel Assembly.....	5.7-17
5.7.5.1.2	Steam Generators .....	5.7-17
5.7.5.1.3	Primary Coolant Pumps.....	5.7-17
5.7.5.1.4	Pressurizer.....	5.7-17
5.7.5.1.5	Primary Coolant System Piping.....	5.7-18
5.7.5.1.6	Pressurizer Quench Tank .....	5.7-18
5.7.5.1.7	Pressurizer Safety and Power-Operated Relief Valves .....	5.7-18
5.7.5.2	Other Major CP Co Design Class 1 Systems and Components .....	5.7-18
5.7.6	SEISMIC ANALYSIS OF SPENT FUEL STORAGE RACKS .....	5.7-19
5.7.6.1	Region 1 Racks .....	5.7-19
5.7.6.2	Region 2 Racks (See Section 9.11).....	5.7-21
5.7.7	SEISMIC ANALYSIS AND TESTING OF OTHER CP CO DESIGN CLASS 1 COMPONENTS .....	5.7-22
5.7.7.1	Electrical Equipment and Instrumentation .....	5.7-24
5.7.7.2	Tanks.....	5.7-24
5.7.7.3	Appendages to CP Co Design Class 1 Components .....	5.7-24
5.7.7.4	Overhead Cranes .....	5.7-25
5.7.7.5	Containment Air Locks.....	5.7-25
5.7.8	SEISMIC ANALYSIS OF BURIED STRUCTURES AND COMPONENTS.....	5.7-25
5.7.9	SEISMIC INSTRUMENTATION .....	5.7-25
	REFERENCES .....	5.7-26
5.8	CONTAINMENT STRUCTURE .....	5.8-1
5.8.1	DESIGN BASIS.....	5.8-1
5.8.2	GENERAL DESCRIPTION .....	5.8-2
5.8.3	LOADS AND LOAD COMBINATIONS .....	5.8-6
5.8.3.1	Containment Structure Concrete.....	5.8-6
5.8.3.1.1	Construction Condition .....	5.8-6
5.8.3.1.2	Working Stress Condition .....	5.8-6
5.8.3.1.3	Yield Strength Condition .....	5.8-7
5.8.3.2	Liner Plate System.....	5.8-9
5.8.3.2.1	Liner Plate .....	5.8-9
5.8.3.2.2	Liner Plate Anchors .....	5.8-9
5.8.3.3	Penetrations .....	5.8-10

<b>5.8.4</b>	<b>ANALYSIS</b> .....	<b>5.8-10</b>
5.8.4.1	Containment Structure Concrete.....	5.8-10
5.8.4.1.1	General.....	5.8-10
5.8.4.1.2	Axisymmetric Loads .....	5.8-11
5.8.4.1.3	Nonaxisymmetric Loads.....	5.8-15
5.8.4.2	Prestressing System.....	5.8-15
5.8.4.2.1	Tendon Anchorage Zones .....	5.8-15
5.8.4.3	Liner Plate System.....	5.8-19
5.8.4.3.1	Liner Plate.....	5.8-19
5.8.4.3.2	Liner Plate Anchors .....	5.8-19
5.8.4.4	Penetrations .....	5.8-20
<b>5.8.5</b>	<b>DESIGN</b> .....	<b>5.8-21</b>
5.8.5.1	Design Basis .....	5.8-21
5.8.5.2	Containment Structure Concrete.....	5.8-23
5.8.5.2.1	General Criteria .....	5.8-23
5.8.5.2.2	Construction Condition .....	5.8-24
5.8.5.2.3	Working Stress Condition .....	5.8-25
5.8.5.2.4	Yield Strength Condition .....	5.8-26
5.8.5.2.5	Results .....	5.8-31
5.8.5.3	Prestressing System.....	5.8-31
5.8.5.3.1	Tendons .....	5.8-31
5.8.5.3.2	Tendon Anchorage Zones.....	5.8-33
5.8.5.4	Liner Plate System.....	5.8-34
5.8.5.4.1	General.....	5.8-34
5.8.5.4.2	Liner Plate.....	5.8-35
5.8.5.4.3	Liner Plate Anchors .....	5.8-36
5.8.5.4.4	Brackets .....	5.8-38
5.8.5.5	Penetrations .....	5.8-38
<b>5.8.6</b>	<b>PENETRATIONS</b> .....	<b>5.8-39</b>
5.8.6.1	Design Basis .....	5.8-39
5.8.6.2	General Description .....	5.8-39
5.8.6.2.1	Personnel and Equipment Openings.....	5.8-40
5.8.6.2.2	Other Openings .....	5.8-41
5.8.6.3	Design Criteria .....	5.8-42
5.8.6.3.1	Concrete Openings .....	5.8-42
5.8.6.3.2	Steel Penetrations .....	5.8-42
5.8.6.4	Analysis and Design .....	5.8-45
5.8.6.4.1	Small Penetrations .....	5.8-46
5.8.6.4.2	Large Penetrations.....	5.8-48
5.8.6.4.3	Other Design Details .....	5.8-51

5.8.7	<b>CONSTRUCTION</b> .....	5.8-52
5.8.7.1	<b>Materials</b> .....	5.8-52
5.8.7.1.1	<b>Concrete</b> .....	5.8-52
5.8.7.1.2	<b>Reinforcing Steel</b> .....	5.8-53
5.8.7.1.3	<b>Prestressing Tendons and Hardware</b> .....	5.8-54
5.8.7.1.4	<b>Liner Plate</b> .....	5.8-54
5.8.7.1.5	<b>Steel Penetrations</b> .....	5.8-54
5.8.7.1.6	<b>Sheathing Filler</b> .....	5.8-55
5.8.7.2	<b>Quality Control</b> .....	5.8-55
5.8.7.2.1	<b>Concrete Mix Design</b> .....	5.8-55
5.8.7.2.2	<b>Concrete Materials</b> .....	5.8-56
5.8.7.2.3	<b>Concrete</b> .....	5.8-57
5.8.7.2.4	<b>Reinforcing Steel and CADWELD</b> <b>Splices</b> .....	5.8-57
5.8.7.2.5	<b>Prestressing Tendons and Hardware</b> .....	5.8-58
5.8.7.2.6	<b>Liner Plate</b> .....	5.8-59
5.8.7.2.7	<b>Steel Penetrations</b> .....	5.8-60
5.8.7.2.8	<b>Sheathing Filler</b> .....	5.8-60
5.8.7.3	<b>Construction Methods</b> .....	5.8-60
5.8.7.3.1	<b>Governing Codes</b> .....	5.8-60
5.8.7.3.2	<b>Concrete</b> .....	5.8-61
5.8.7.3.3	<b>Reinforcing Steel and CADWELD</b> <b>Splices</b> .....	5.8-61
5.8.7.3.4	<b>Prestressing System</b> .....	5.8-62
5.8.7.3.5	<b>Liner Plate</b> .....	5.8-63
5.8.7.4	<b>Construction Problems</b> .....	5.8-64
5.8.7.4.1	<b>Cracking at Welds in Containment</b> <b>Liner Plate</b> .....	5.8-64
5.8.8	<b>CONTAINMENT STRUCTURE TESTING</b> .....	5.8-68
5.8.8.1	<b>Integrated Leak Rate Testing</b> .....	5.8-68
5.8.8.1.1	<b>Historical Summary</b> .....	5.8-68
5.8.8.1.2	<b>Regulatory Basis for Current Program</b> .....	5.8-70
5.8.8.1.3	<b>Type A Test Performance Under</b> <b>Option B</b> .....	5.8-71
5.8.8.2	<b>Local Leakage Rate Testing</b> .....	5.8-71
5.8.8.2.1	<b>Historical Summary</b> .....	5.8-72
5.8.8.2.2	<b>Regulatory Basis for Current Program</b> .....	5.8-73
5.8.8.2.3	<b>Scope of the Type B and C</b> <b>Testing Program</b> .....	5.8-73
5.8.8.2.4	<b>Performance Based Type B and C</b> <b>Program Overview</b> .....	5.8-74
5.8.8.3	<b>Prestressing System Surveillance</b> .....	5.8-75
5.8.8.3.1	<b>Basis for Program</b> .....	5.8-75
5.8.8.3.2	<b>Surveillance Period</b> .....	5.8-76
5.8.8.3.3	<b>Surveillance Guidelines</b> .....	5.8-76
5.8.8.3.4	<b>Acceptance Criteria</b> .....	5.8-79
5.8.8.3.5	<b>Historical Summary</b> .....	5.8-80

5.8.8.4	Structural Integrity Test.....	5.8-84
5.8.8.4.1	Basis for Test.....	5.8-84
5.8.8.4.2	Test Guidelines.....	5.8-85
5.8.8.4.3	Objectives .....	5.8-85
5.8.8.4.4	Test Data and Results.....	5.8-86
5.8.8.4.5	Summary .....	5.8-88
5.8.8.5	Liner Plate and Penetration Surveillance Program .....	5.8-89
5.8.8.5.1	Basis for Program .....	5.8-89
5.8.8.5.2	Surveillance Period .....	5.8-89
5.8.8.5.3	Details of Program .....	5.8-90
5.8.8.5.4	Summary .....	5.8-90
5.8.8.6	End Anchorage Concrete Surveillance .....	5.8-91
5.8.8.6.1	Basis for Program .....	5.8-91
5.8.8.6.2	Surveillance Period .....	5.8-91
5.8.8.6.3	Surveillance Locations .....	5.8-92
5.8.8.6.4	Details and Results .....	5.8-92
5.8.8.6.5	Summary .....	5.8-93
5.8.9	<b>STEAM GENERATOR REPLACEMENT CONSTRUCTION</b>	
	<b>OPENING .....</b>	<b>5.8-93</b>
5.8.9.1	General Description .....	5.8-93
5.8.9.2	Containment Reevaluation.....	5.8-94
5.8.9.3	Materials .....	5.8-96
5.8.9.3.1	Concrete.....	5.8-96
5.8.9.3.2	Reinforcing Steel.....	5.8-97
5.8.9.3.3	Prestressing Tendons and Hardware .....	5.8-98
5.8.9.3.4	Liner Plate and Hardware .....	5.8-98
5.8.9.3.5	Sheathing Filler .....	5.8-98
5.8.9.4	Quality Control .....	5.8-98
5.8.9.4.1	Concrete Mix Design.....	5.8-98
5.8.9.4.2	Concrete Materials .....	5.8-99
5.8.9.4.3	Concrete.....	5.8-100
5.8.9.4.4	Reinforcing Steel and CADWELD Splices.....	5.8-100
5.8.9.4.5	Prestressing Tendons.....	5.8-101
5.8.9.4.6	Liner Plate.....	5.8-101
5.8.9.4.7	Sheathing Filler .....	5.8-102
5.8.9.5	Construction Methods .....	5.8-102
5.8.9.5.1	Governing Codes .....	5.8-102
5.8.9.5.2	Concrete.....	5.8-102
5.8.9.5.3	Reinforcing Steel and CADWELD Splices.....	5.8-102
5.8.9.5.4	Prestressing System.....	5.8-103
5.8.9.6	Containment Testing .....	5.8-103
5.8.9.6.1	Integrated Leak Rate Testing .....	5.8-103
5.8.9.6.2	Structural Integrity Test.....	5.8-103



5.8.10	CONTAINMENT STRUCTURAL INTEGRITY SURVEILLANCE PROGRAM.....	5.8-104
5.8.10.1	Requirement for Metal Containment Examinations.....	5.8-104
5.8.10.2	Requirements for Concrete Containment Examinations.....	5.8-104
5.8.10.2.1	Surveillance of Unbonded Post-Tensioning System .....	5.8-104
5.8.10.2.2	Surveillance of Containment Structural Concrete .....	5.8-104
	REFERENCES .....	5.8-105
5.9	OTHER STRUCTURES .....	5.9-1
5.9.1	DESIGN CRITERIA.....	5.9-1
5.9.1.1	CP Co Design Class 1 Structures .....	5.9-1
5.9.1.1.1	Design Methods.....	5.9-1
5.9.1.1.2	Loads and Load Combinations .....	5.9-2
5.9.1.2	CP Co Design Class 2 Structures .....	5.9-4
5.9.1.3	CP Co Design Class 3 Structures .....	5.9-4
5.9.1.4	Loads Common to All Structures .....	5.9-5
5.9.2	CONTAINMENT INTERIOR STRUCTURES .....	5.9-5
5.9.2.1	General Description.....	5.9-5
5.9.2.2	Loads .....	5.9-6
5.9.2.3	Analysis and Design .....	5.9-8
5.9.2.4	Materials of Construction.....	5.9-10
5.9.3	AUXILIARY BUILDING .....	5.9-10
5.9.3.1	General Description .....	5.9-10
5.9.3.2	Loads .....	5.9-11
5.9.3.3	Analysis and Design .....	5.9-12
5.9.3.4	Materials of Construction.....	5.9-13
5.9.4	TURBINE BUILDING AND INTAKE STRUCTURE .....	5.9-13
5.9.4.1	General.....	5.9-13
5.9.5	AUXILIARY BUILDING RADWASTE ADDITION .....	5.9-13
5.9.5.1	General Description .....	5.9-13
5.9.5.2	Analysis and Design .....	5.9-14
5.9.5.3	Materials of Construction.....	5.9-14
5.9.6	AUXILIARY BUILDING TSC/EER/HVAC ADDITION .....	5.9-14
5.9.6.1	General Description .....	5.9-14
5.9.6.2	Loads and Load Combinations.....	5.9-15
5.9.6.2.1	Loads.....	5.9-15
5.9.6.2.2	Load Combinations.....	5.9-16
5.9.6.3	Analysis and Design .....	5.9-17
5.9.6.4	Materials of Construction.....	5.9-18
	REFERENCES .....	5.9-19

5.10	SYSTEMS AND COMPONENTS .....	5.10-1
5.10.1	DESIGN CRITERIA FOR CP CO DESIGN CLASS 1 SYSTEMS AND COMPONENTS .....	5.10-1
5.10.1.1	CP Co Design Class 1 Piping.....	5.10-1
5.10.1.2	CP Co Design Class 1 Pipe Supports.....	5.10-3
5.10.1.3	Other CP Co Design Class 1 Systems and Components .....	5.10-5
5.10.1.4	Interim Operability Criteria.....	5.10-6
5.10.2	DESIGN CRITERIA FOR CP CO DESIGN CLASS 2 AND CLASS 3 SYSTEMS AND COMPONENTS .....	5.10-6
5.10.2.1	CP Co Design Class 2.....	5.10-6
5.10.2.2	CP Co Design Class 3.....	5.10-6
5.10.3	ANCHORAGE MODIFICATIONS FOR SAFETY-RELATED SYSTEMS AND COMPONENTS .....	5.10-7
5.10.3.1	Piping Systems .....	5.10-7
5.10.3.1.1	1974 Review .....	5.10-7
5.10.3.1.2	1979 Reanalysis.....	5.10-7
5.10.3.1.3	Revision of Seismic Piping Criteria - ASME Section III, Code Case N-411 .....	5.10-8
5.10.3.1.4	Inspection and Enforcement Bulletins .....	5.10-9
5.10.3.2	Masonry Walls .....	5.10-11
5.10.3.2.1	History.....	5.10-11
5.10.3.2.2	Identification .....	5.10-11
5.10.3.2.3	Reevaluation .....	5.10-11
5.10.3.2.4	Modifications .....	5.10-11
5.10.3.3	Electrical Equipment.....	5.10-12
5.10.3.3.1	History.....	5.10-12
5.10.3.3.2	Identification.....	5.10-12
5.10.3.3.3	Evaluation and Modifications .....	5.10-13
5.10.4	QUALITY CONTROL .....	5.10-13
5.10.4.1	Shop Welding .....	5.10-13
5.10.4.2	Field Welding.....	5.10-14
5.10.4.3	Inspection of Piping.....	5.10-15
5.10.4.4	Field Inspection of Mechanical Components, Electrical Components and Instrumentation....	5.10-16
	REFERENCES .....	5.10-17

**LIST OF TABLES**

5.2-1	Palisades System of Classification for Structures/Systems/Components
5.2-2	Structures Classification
5.2-3	Mechanical System/Component Classification
5.2-4	Electrical Systems/Component Classification
5.2-5	Instrumentation and Control/Component Classification
5.3-1	Tornado Design Pressures
5.4-1	Safety-Related Equipment That Requires Protection From Flooding Due to Failures of Nonclass 1 Systems
5.5-1	Class 1 Structures Wall and Roof Thickness
5.5-2	Burst Probability for Each LP Rotor and Total Unit at 120% Rated Speed
5.6-1	High-Energy Pipe Failures Outside Containment - Summary of Operating Stresses - Main Steam
5.6-2	High-Energy Pipe Failures Outside Containment - Summary of Operating Stresses - Feedwater
5.6-3	High-Energy Pipe Failures Outside Containment - Summary of Operating Stresses - Main Steam Dump
5.6-4	Summary of Eliminated Hardware Resulting from Application of Generic Letter 87-11, "Relaxation of Arbitrary Pipe Rupture Requirements"
5.7-1	List of Computer Codes
5.7-2	Material Damping Values for Various Materials and Types of Construction
5.7-3	Material Damping Values for Various Class 1 Structures
5.7-4	Auxiliary Building TSC/EER Addition Summary of Modal Parameters Flexible Base Analysis
5.7-5	Comparison of Specifications for Seismic Requirements
5.7-6	Major Class 1 Components Seismic Loads
5.7-7	Class 1E Electrical Equipment and Instrumentation Seismic Loads
5.7-8	Class 1 Tanks Seismic Loads
5.7-9	Safety-Related Hydraulic Shock Suppressors (Snubbers)
5.7-10	Safety-Related Mechanical Shock Suppressors (Snubbers)
5.8-1	Containment Structure Summary of Concrete and Reinforcing Steel Stresses
5.8-2	Containment Structure Tendon Anchorage Zone Reinforcement Stresses
5.8-3	Containment Structure Liner Plate Anchor Analysis
5.8-4	Containment Penetrations and Appendix J Test Requirements
5.9-1	Major Equipment Supports, Materials of Construction
5.10-1	Class 1 Systems or Portions Thereof Included in the 1974 Review of As-Built Pipe Supports
5.10-2	Systems Containing Safety-Related Piping

**LIST OF FIGURES**

5.5-1	Deleted
5.5-2	Deleted
5.7-1	OBE Horizontal Design Ground Response Spectrum (Housner)
5.7-2	Taft Ground Response Spectrum Versus Housner Ground Response Spectrum (SSE), 4% Damping
5.7-3	Taft Ground Response Spectrum Versus Housner Ground Response Spectrum (SSE), 7-1/2% Damping
5.7-4	Containment Building Dynamic Model
5.7-5	Containment Shell Maximum Seismic Responses (OBE) Comparison of Responses for Fixed Base and Coupled Models
5.7-6	Auxiliary Building, N-S Mathematical Model
5.7-7	Auxiliary Building, E-W Mathematical Model
5.7-8	Electrical Penetration Enclosure, N-S and E-W Dynamic Models and Maximum Seismic Responses (OBE)
5.7-9	Turbine Building, E-W Dynamic Models
5.7-10	Turbine Building, E-W Fundamental Modeshapes, Outside Walls
5.7-11	Turbine Building, E-W Direction, Maximum Seismic Responses (SSE)
5.7-12	Auxiliary Building Radwaste Addition, Dynamic Models
5.7-13	Auxiliary Building TSC/EER Addition, Dynamic Model
5.7-14	Auxiliary Building TSC/EER Addition, Maximum Seismic Responses (OBE)
5.8-1 Sh 1	Containment Structure, Typical Cross Section
5.8-1 Sh 2	Containment Structure, Typical Cross Section
5.8-2	Containment Structure, Typical Piping Penetrations
5.8-3	Containment Structure, Typical Electrical Penetrations
5.8-4	Containment Structure, Reinforcing and Tendon Plan Adjacent to Equipment Hatch
5.8-5 Sh 1	Containment Structure, Tendon Hardware Assembly, Horizontal and Dome Tendons, Shop Buttonheaded End
5.8-5 Sh 2	Containment Structure, Tendon Hardware Assembly, Horizontal and Dome Tendons, Field Buttonheaded End
5.8-5 Sh 3	Containment Structure, Tendon Hardware Assembly, Vertical Tendons, Shop Buttonheaded End
5.8-5 Sh 4	Containment Structure, Tendon Hardware Assembly, Vertical Tendons, Field Buttonheaded End
5.8-6	Containment Structure, Personnel Air Lock
5.8-7	Containment Structure, Escape Air Lock
5.8-8	Containment Structure, Equipment Hatch Door
5.8-9	Containment Structure, Finite Element Mesh
5.8-10	Containment Structure, DBA Thermal Gradients Across Containment Wall, No Insulation

5.8-11 Sh 1	Containment Structure, Isostress Plot, Dome and Wall, $D + F_i$
5.8-11 Sh 2	Containment Structure, Isostress Plot, Dome and Wall, $D + F_f + 1.15P$
5.8-11 Sh 3	Containment Structure, Isostress Plot, Dome and Wall, $D + F_f + 1.5P + T_a$
5.8-11 Sh 4	Containment Structure, Isostress Plot, Dome and Wall, $D + F_f + T_a$
5.8-12 Sh 1	Containment Structure, Isostress Plot, Wall and Base Slab, $D + F_i$
5.8-12 Sh 2	Containment Structure, Isostress Plot, Wall and Base Slab, $D + F_f + 1.15P$
5.8-12 Sh 3	Containment Structure, Isostress Plot, Wall and Base Slab, $D + F_f + 1.5P + T_a$
5.8-12 Sh 4	Containment Structure, Isostress Plot, Wall and Base Slab, $D + F_f + T_a$
5.8-13 Sh 1	Containment Structure, Stress Resultants, Dead Load (D)
5.8-13 Sh 2	Containment Structure, Stress Resultants, Final Prestress ( $F_f$ )
5.8-13 Sh 3	Containment Structure, Stress Resultants, DBA Pressure (P)
5.8-13 Sh 4	Containment Structure, Stress Resultants, DBA Temperature ( $T_a$ )
5.8-14	Containment Structure, Finite Element Mesh for Buttress, Plane Strain Analysis
5.8-15 Sh 1	Containment Structure, Buttress Isostress Plot, Maximum Compressive Stresses
5.8-15 Sh 2	Containment Structure, Buttress Isostress Plot, Minimum Compressive or Maximum Tensile Stresses
5.8-16 Sh 1	Containment Structure, Model for Liner Plate Analysis
5.8-16 Sh 2	Containment Structure, Model for Liner Plate Analysis
5.8-17	Containment Structure, Results From Tests on Liner Plate Anchors
5.8-18	Containment Structure, Thermal Gradient at Main Steam Penetration
5.8-19	Containment Structure, Loads on Pipe Penetrations
5.8-20	Containment Structure, Stress Concentrations at Equipment Hatch Opening
5.8-21	Containment Structure, Liner Plate, Weld Cracking at Backing Strip Discontinuities
5.8-22 Sh 1	Containment Structure, Liner Plate Test Sample, Elevation 600'0", Azimuth 113°
5.8-22 Sh 2	Containment Structure, Liner Plate Test Sample, Elevation 600'0", Azimuth 275°
5.8-23 Sh 1	Containment Structure, Liner Plate, Inspection and Method of Repair, Elevation 583' 6"
5.8-23 Sh 2	Containment Structure, Liner Plate, Inspection and Method of Repair, Elevation 588' 6"
5.8-23 Sh 3	Containment Structure, Liner Plate, Inspection and Method of Repair, Elevation 590' 0"
5.8-24	Containment Structure, Location and Identification of Eleven Surveillance Tendons for One- and Three-Year Surveillances

---

5.8-25 Sh 1	Containment Structure, Structural Integrity Test Inside Hoop Strain Profiles, Typical Section
5.8-25 Sh 2	Containment Structure, Structural Integrity Test Outside Meridional Strain Profiles, Typical Section
5.8-26	Containment Structure, Pressure Test Displacement Profiles
5.8-27 Sh 1	Containment Structure, Pressure Test Tendon Load Change
5.8-27 Sh 2	Containment Structure, Pressure Test Tendon Load Change
5.8-28	Containment Structure, End Anchorage Surveillance Program, Crack Surveillance Locations
5.8-29	Construction Opening Plan, Elevations, and Sections
5.8-30	Construction Opening Tendon Detensioning and Post Tensioning Sequence
5.8-31	Miscellaneous Gas Supply Systems
5.9-1	Containment Structure, Interior Construction

SECTIONS

6.1	<b>SAFETY INJECTION SYSTEM</b> .....	6.1-1
6.1.1	<b>DESIGN BASES</b> .....	6.1-1
6.1.2	<b>SYSTEM DESCRIPTION AND OPERATION</b> .....	6.1-5
6.1.2.1	General Description .....	6.1-5
6.1.2.2	Component Design .....	6.1-8
6.1.2.3	Operation .....	6.1-16
6.1.3	<b>TESTING</b> .....	6.1-20
6.1.3.1	Operational Testing .....	6.1-20
6.1.3.2	Environmental Testing .....	6.1-21
6.1.4	<b>DESIGN ANALYSIS</b> .....	6.1-21
6.2	<b>CONTAINMENT SPRAY SYSTEM</b> .....	6.2-1
6.2.1	<b>DESIGN BASIS</b> .....	6.2-1
6.2.2	<b>SYSTEM DESCRIPTION AND OPERATION</b> .....	6.2-2
6.2.2.1	General Description .....	6.2-2
6.2.2.2	Component Description .....	6.2-2
6.2.2.3	System Operation .....	6.2-3
6.2.3	<b>DESIGN ANALYSIS</b> .....	6.2-4
6.2.3.1	Margins of Safety .....	6.2-4
6.2.3.2	Margins of Capacity .....	6.2-4
6.2.3.3	Testing .....	6.2-4
6.3	<b>CONTAINMENT AIR COOLERS</b> .....	6.3-1
6.3.1	<b>DESIGN BASES</b> .....	6.3-1
6.3.2	<b>SYSTEM DESCRIPTION AND OPERATION</b> .....	6.3-1
6.3.2.1	General Description .....	6.3-1
6.3.2.2	System Operation .....	6.3-3
6.3.3	<b>DESIGN ANALYSIS</b> .....	6.3-4
6.3.4	<b>COMPONENT TESTING</b> .....	6.3-5
6.3.4.1	Coils .....	6.3-5
6.3.4.2	Fans.....	6.3-6
6.3.4.3	Testing .....	6.3-6
6.4	<b>CONTAINMENT SUMP pH CONTROL</b> .....	6.4-1
6.4.1	<b>DESIGN BASIS</b> .....	6.4-1
6.4.2.1	General Description .....	6.4-1
6.4.2.2	Operation .....	6.4-1
6.4.2.3	Materials .....	6.4-2
6.4.2.4	Paint .....	6.4-3
6.5	<b>CONTAINMENT VENTING CHARCOAL FILTER</b> .....	6.5-1
6.5.1	<b>GENERAL</b> .....	6.5-1
6.6	<b>DELETED</b>	

<b>6.7</b>	<b>CONTAINMENT ISOLATION SYSTEM.....</b>	<b>6.7-1</b>
	<b>6.7.1 DESIGN BASIS.....</b>	<b>6.7-1</b>
	<b>6.7.2 SYSTEM DESCRIPTION AND OPERATION .....</b>	<b>6.7-1</b>
	<b>6.7.2.1 System Description.....</b>	<b>6.7-1</b>
	<b>6.7.2.2 Component Description .....</b>	<b>6.7-4</b>
	<b>6.7.2.3 System Operation .....</b>	<b>6.7-4</b>
	<b>6.7.3 DESIGN ANALYSIS .....</b>	<b>6.7-6</b>
	<b>6.7.3.1 System Reliability - Margins of Safety .....</b>	<b>6.7-6</b>
	<b>6.7.3.2 Provisions for Testing and Inspection.....</b>	<b>6.7-6</b>
<b>6.8</b>	<b>REACTOR CAVITY FLOODING SYSTEM.....</b>	<b>6.8-1</b>
	<b>6.8.1 SYSTEM OPERATION .....</b>	<b>6.8-1</b>
<b>6.9</b>	<b>INSERVICE INSPECTION OF ASME CLASSES 1, 2 AND 3 SYSTEMS</b>	
	<b>AND COMPONENTS.....</b>	<b>6.9-1</b>
	<b>6.9.1 STRUCTURAL INTEGRITY EXAMINATION.....</b>	<b>6.9-2</b>
	<b>6.9.2 PUMP AND VALVE TESTING PROGRAM .....</b>	<b>6.9-3</b>
	<b>6.9.2.1 Pump Testing Program.....</b>	<b>6.9-3</b>
	<b>6.9.2.2 Valve Testing Program .....</b>	<b>6.9-3</b>
<b>6.10</b>	<b>CONTROL ROOM HABITABILITY .....</b>	<b>6.10-1</b>
	<b>6.10.1 DESIGN BASIS.....</b>	<b>6.10-1</b>
	<b>6.10.2 SYSTEM DESIGN .....</b>	<b>6.10-1</b>
	<b>6.10.3 DESIGN ANALYSIS.....</b>	<b>6.10-2</b>
	<b>REFERENCES.....</b>	<b>6-1</b>

**LIST OF TABLES**

6-1	Safety Injection and Refueling Water Tank Design Parameters
6-2	Low Pressure Safety Injection Pump Data Summary
6-3	High Pressure Safety Injection Pump Data Summary
6-4	Shutdown Cooling Heat Exchanger Data Summary
6-5	Safety Injection Tank Design Parameters
6-6	Containment Spray System Component Description
6-7	Containment Air Cooler Component Description
6-8	Containment Air Coolers Performance Data for Normal Operation
6-9	Containment Air Coolers Performance Data for Post-DBA Conditions
6-10	ECCS Component Systems
6-11	Deleted
6-12	ISI Major Components and/or Systems List
6-13	Inservice Pump Test Program Summary
6-14	Technical Specification 3.6.3, "Containment Isolation Valves," Applicability



**LIST OF FIGURES**

6-1 Sh 1	Piping & Instrument Diagram, Safety Injection Containment Spray and Shutdown Cooling System
6-1 Sh 2	Piping & Instrument Diagram, Safety Injection Containment Spray and Shutdown Cooling System
6-2 Sh 1	Piping & Instrument Diagram, Safety Injection Containment Spray and Shutdown Cooling System
6-2 Sh 1A	Piping & Instrument Diagram, Safety Injection Containment Spray and Shutdown Cooling System
6-2 Sh 1B	Piping & Instrument Diagram, Safety Injection Containment Spray
6-3	Containment Air Coolers Relief Panel & Condensate Drain
6-4	Containment Vent Filter
6-5 Sh 1	Containment Penetrations
6-5 Sh 2	Containment Penetrations
6-5 Sh 2A	Containment Penetrations
6-5 Sh 3	Containment Penetrations
6-6	Reactor Cavity Flooding System
6-7	Capacity Curve 1713A Nozzle

**SECTIONS**

<b>7.1</b>	<b>INTRODUCTION.....</b>	<b>7.1-1</b>
<b>7.2</b>	<b>REACTOR PROTECTIVE SYSTEM .....</b>	<b>7.2-1</b>
7.2.1	GENERAL.....	7.2-1
7.2.2	DESIGN BASES .....	7.2-2
7.2.3	REACTOR PROTECTIVE SYSTEM ACTIONS .....	7.2-4
7.2.3.1	High Rate-of-Change of Power .....	7.2-4
7.2.3.2	Variable High Power .....	7.2-5
7.2.3.3	Low Primary Coolant Flow .....	7.2-6
7.2.3.4	High Pressurizer Pressure .....	7.2-7
7.2.3.5	Thermal Margin/Low Pressure.....	7.2-8
7.2.3.6	Loss of Load.....	7.2-9
7.2.3.7	Low Steam Generator Water Level.....	7.2-9
7.2.3.8	Low Steam Generator Pressure.....	7.2-9
7.2.3.9	Containment High Pressure.....	7.2-10
7.2.3.10	Manual Trip.....	7.2-10
7.2.4	SIGNAL GENERATION .....	7.2-11
7.2.5	LOGIC OPERATION.....	7.2-12
7.2.5.1	Trip Logic (See Figure 7-2).....	7.2-12
7.2.5.2	Trip Bypass Logic.....	7.2-12
7.2.5.3	CRDM Clutch Power Circuitry (See Figure 7-1)..	7.2-14
7.2.6	TESTING.....	7.2-15
7.2.7	EFFECTS OF FAILURES .....	7.2-16
7.2.8	POWER SOURCES .....	7.2-18
7.2.9	PHYSICAL SEPARATION AND ELECTRICAL ISOLATION .....	7.2-19
7.2.9.1	Physical Separation .....	7.2-19
7.2.9.2	Electrical Isolation .....	7.2-19
7.2.10	REACTOR TRIP AND PRETRIP SET POINTS .....	7.2-21
<b>7.3</b>	<b>ENGINEERED SAFEGUARDS CONTROLS .....</b>	<b>7.3-1</b>
7.3.1	INTRODUCTION.....	7.3-1
7.3.2	SAFETY INJECTION SYSTEM CONTROL CIRCUITS AND EQUIPMENT INITIATION .....	7.3-2
7.3.2.1	Design Basis .....	7.3-2
7.3.2.2	Description and Operation .....	7.3-2
7.3.2.3	Design Analysis .....	7.3-4
7.3.3	CONTAINMENT HIGH PRESSURE AND HIGH RADIATION .....	7.3-5
7.3.3.1	Design Basis .....	7.3-5
7.3.3.2	Description and Operation .....	7.3-5
7.3.3.3	Design Analysis .....	7.3-8

7.3.4	<b>SAFETY INJECTION AND REFUELING WATER TANK</b>	
	LOW LEVEL .....	7.3-9
7.3.4.1	Design Basis .....	7.3-9
7.3.4.2	Description and Operation .....	7.3-10
7.3.4.3	Design Analysis .....	7.3-11
7.3.5	<b>ENGINEERED SAFEGUARDS TESTING</b> .....	7.3-11
7.3.5.1	Design Bases .....	7.3-11
7.3.5.2	Testing Description.....	7.3-12
7.4	<b>OTHER SAFETY RELATED PROTECTION, CONTROL AND DISPLAY SYSTEMS.....</b>	<b>7.4-1</b>
7.4.1	<b>REACTOR SHUTDOWN CONTROLS.....</b>	<b>7.4-1</b>
7.4.2	<b>PRIMARY COOLANT BOUNDARIES PROTECTION.....</b>	<b>7.4-1</b>
7.4.2.1	Primary Coolant Overpressure Protection System .....	7.4-1
7.4.2.2	Other Primary Coolant Boundaries Protection ....	7.4-5
7.4.3	<b>AUXILIARY FEEDWATER CONTROLS .....</b>	<b>7.4-6</b>
7.4.3.1	Auxiliary Feedwater Initiation .....	7.4-6
7.4.3.2	Auxiliary Feedwater Flow Controls and Isolation.....	7.4-12
7.4.4	<b>CONTAINMENT HYDROGEN CONTROLS .....</b>	<b>7.4-15</b>
7.4.4.1	Design Basis .....	7.4-15
7.4.5	<b>VENTILATION AND EFFLUENT RELEASES CONTROLS .....</b>	<b>7.4-16</b>
7.4.5.1	Control Room .....	7.4-16
7.4.5.2	Engineered Safeguards Pump Rooms .....	7.4-16
7.4.5.3	Radwaste Area .....	7.4-16
7.4.5.4	Fuel Handling Areas .....	7.4-16
7.4.5.5	Waste Gas Decay Tank.....	7.4-16
7.4.6	<b>OTHER SAFETY RELATED DISPLAY SYSTEMS .....</b>	<b>7.4-17</b>
7.4.6.1	Subcooled Margin Monitor.....	7.4-17
7.4.6.2	Wide-Range Containment Pressure, Temperature and Water Level.....	7.4-18
7.4.6.3	Reactor Vessel Level Monitoring System .....	7.4-19
7.4.6.4	Core Exit Thermocouple (CET) System .....	7.4-21
7.5	<b>NONSAFETY-RELATED REGULATING CONTROLS .....</b>	<b>7.5-1</b>
7.5.1	<b>DESIGN BASES .....</b>	<b>7.5-1</b>
7.5.1.1	Reactor Regulating .....	7.5-1
7.5.1.2	Primary Pressure Regulating.....	7.5-2
7.5.1.3	Feedwater Regulating.....	7.5-2
7.5.1.4	Pressurizer Level Regulating.....	7.5-3
7.5.1.5	Steam Dump and Bypass .....	7.5-3
7.5.1.6	Turbine Runback.....	7.5-4
7.5.1.7	Turbine Generator Controls .....	7.5-4

7.5.2	SYSTEM DESIGN .....	7.5-4
7.5.2.1	Reactor Regulating .....	7.5-4
7.5.2.2	Primary Pressure Regulating .....	7.5-7
7.5.2.3	Feedwater Regulating .....	7.5-8
7.5.2.4	Pressurizer Level Regulating .....	7.5-9
7.5.2.5	Steam Dump and Bypass .....	7.5-9
7.5.2.6	Turbine Generator Controls .....	7.5-11
7.5.3	SYSTEM EVALUATION .....	7.5-12
7.5.3.1	Rod Drive Control System .....	7.5-12
7.5.3.2	Primary Pressure Regulating .....	7.5-13
7.5.3.3	Feedwater Regulating .....	7.5-13
7.5.3.4	Pressurizer Level Regulating .....	7.5-14
7.5.3.5	Steam Dump and Bypass .....	7.5-16
7.5.3.6	Turbine Generator Controls .....	7.5-17
7.6	NUCLEAR STEAM SUPPLY SYSTEM INSTRUMENTATION .....	7.6-1
7.6.1	DESIGN BASES .....	7.6-1
7.6.1.1	Process Instrumentation .....	7.6-1
7.6.1.2	Nuclear Instrumentation .....	7.6-2
7.6.1.3	Control Rod Position Instrumentation .....	7.6-2
7.6.1.4	Incore Instrumentation .....	7.6-3
7.6.1.5	Palisades Plant Computer (PPC) .....	7.6-4
7.6.2	SYSTEM DESCRIPTION .....	7.6-5
7.6.2.1	Process Instrumentation .....	7.6-5
7.6.2.2	Nuclear Instrumentation .....	7.6-11
7.6.2.3	Control Rod Position Instrumentation .....	7.6-15
7.6.2.4	Incore Instrumentation .....	7.6-17
7.6.2.5	Palisades Plant Computer .....	7.6-19
7.7	OPERATING CONTROL STATIONS .....	7.7-1
7.7.1	GENERAL LAYOUT .....	7.7-1
7.7.2	CONTROL ROOM .....	7.7-1
7.7.3	ENGINEERED SAFEGUARDS AUXILIARY PANEL (C-33) .....	7.7-4
7.7.4	AUXILIARY HOT SHUTDOWN CONTROL PANELS (C-150/C-150A) .....	7.7-5
7.7.5	RADWASTE SYSTEM LOCAL CONTROL PANEL .....	7.7-7
7.7.6	MISCELLANEOUS LOCAL CONTROL STATIONS .....	7.7-7
7.7.7	FEATURES WHICH ENHANCE SAFE OPERATION .....	7.7-7
7.7.8	IN-PLANT COMMUNICATION SYSTEM .....	7.7-7
7.7.9	OUT-OF-PLANT COMMUNICATION SYSTEM .....	7.7-8

<b>7.8</b>	<b>QUALITY CONTROL.....</b>	<b>7.8-1</b>
	<b>7.8.1 SPECIFICATIONS .....</b>	<b>7.8-1</b>
	<b>7.8.2 SUPPLIER'S QUALITY CONTROL.....</b>	<b>7.8-2</b>
	<b>7.8.3 REACTOR PROTECTIVE SYSTEM SHOP TEST.....</b>	<b>7.8-2</b>
	<b>7.8.4 SHIPPING AND STORAGE.....</b>	<b>7.8-3</b>
	<b>7.8.5 RELIABILITY .....</b>	<b>7.8-3</b>
	<b>7.8.6 RECORDS AND CERTIFICATION .....</b>	<b>7.8-4</b>
	<b>7.8.7 FIELD QUALITY CONTROL.....</b>	<b>7.8-4</b>
	<b>REFERENCES.....</b>	<b>7-1</b>

**APPENDICES**

Appendix 7A, "Engineered Safeguard Testing  
Appendix 7C, "Regulatory Guide 1.97 Rev 3, Parameter Summary Table"

**LIST OF TABLES**

7-1	Reactor Protective System Relays
7-2	Regulating Rods Withdrawal Interlocks
7-3	Source/Wide-Range Nuclear Instrument Channel Trip Unit Actions
7-4	Power-Range Safety Channel Trip Unit Actions
7-5	Control Rod Position Light Matrix

**LIST OF FIGURES**

7-1	Reactor Protective System Block Diagram
7-2	Reactor Protective System Functional Diagram
7-3	Typical Measurement Channel Functional Diagram
7-4	Schematic Diagram, Pressurizer Pressure ATWS
7-5	Schematic Diagram, Pressurizer Pressure ATWS
7-6	Low Flow Protective System Functional Diagram
7-7	Logic for Thermal Margin Monitor
7-8	Neutron Flux Monitoring System Start-Up and Logarithmic Range Channels
7-9	Neutron Flux Monitoring System Power Range Channels
7-10	Power Rate-of-Change Trip and Pretrip Interface With RPS
7-11	Zero Power Mode Bypass
7-12	Reactor Protective System Interfaces
7-13	Logic Diagram, Safety Injection Initiation
7-14 Sh 1	Logic Diagram, Main Generator Protection
7-14 Sh 2	Logic Diagram, Turbine-Generator Trips and Fast Transfer
7-14 Sh 3	Logic Diagram, 2400 Volt Load Shed
7-14 Sh 4	Logic Diagram, Diesel Start (CPCo)
7-14 Sh 5	Logic Diagram, Diesel Engine Control, Trips and Alarms
7-14 Sh 6	Logic Diagram, Diesel Generator Breakers
7-14 Sh 7	Logic Diagram, Bus 1C and 1D Incoming Breakers
7-14 Sh 8	Logic Diagram, Power to Bus 1E, 1F and 1G Incoming Breakers
7-14 Sh 9	Logic Diagram, Bus 1A & 1B Incoming Breakers

7-14 Sh 10	Logic Diagram, Generator Breaker and M.O.D. Control
7-14 Sh 11	Logic Diagram, Start-Up XFMR. Protection
7-14 Sh 12	Logic Diagram, Safeguard Transformer 1-1
7-14 Sh 13	Logic Diagram, Circuit Breaker Operation
7-15	Schematic Diagram, Safety Injection Signal Auxiliary Circuits
7-16	Schematic Diagram, Safety Injection Signal Auxiliary Circuits
7-17	Schematic Diagram, Safety Injection and Sequence Loading Circuits
7-18	Schematic Diagram, Safety Injection and Sequence Loading Circuits
7-19	Schematic Diagram, Safety Injection and Sequence Loading Circuits
7-20	Schematic Diagram, Safety Injection and Sequence Loading Circuits
7-21	Schematic Diagram, Safety Injection and Sequence Loading Test Circuit
7-22	Schematic Diagram, Safety Injection and Sequence Loading Test Circuit
7-23	Schematic Diagram, Safety Injection and Sequence Loading Test Circuit
7-24	Logic Diagram, Containment High Pressure Signal
7-25	Logic Diagram, Containment High Radiation
7-26	Schematic Diagram, Containment High Pressure, High Radiation and SIRW Tank Low Level
7-27	Schematic Diagram, Containment High Pressure, High Radiation and SIRW Tank Low Level
7-28	Schematic Diagram, Containment Isolation on High Pressure or High Radiation
7-29	Schematic Diagram, Containment Isolation on High Pressure or High Radiation
7-30	Logic Diagram, SIS Test and RAS
7-31	Schematic Diagram, SIRW Tank and Containment Sump Valves
7-32	Schematic Diagram, SIRW Tank and Containment Sump Valves
7-33	Logic Diagram, Legend and Notes
7-34	Logic Diagram, Legend and Notes
7-35	Logic Diagram, Legend and Notes
7-36	Schematic Diagram, Steam Generator Level Instrumentation
7-37	Logic Diagram, Auxiliary Feedwater Actuation System
7-38	Logic Diagram, Motor Driven Auxiliary Feedwater Pump P-8A
7-39	Logic Diagram, Motor Driven Auxiliary Feedwater Pump P-8C
7-40 Sh 1	Logic Diagram, Turbine Driven Auxiliary Feedwater Pump P-8B
7-40 Sh 2	Logic Diagram, Turbine Driven Auxiliary Feedwater Pump P-8B
7-41	Interface Loop Diagram, Pump Low Suction Pressure Trip
7-41 Sh 1	Logic Diagram Turbine Driven Auxiliary Feedwater Pump P-8B
7-41 Sh 2	Logic Diagram Turbine Driven Auxiliary Feedwater Pump P-8B
7-42	Logic Diagram, Auxiliary Feedwater Pumps Low Suction Pressure Trip
7-43	Interface Loop Diagram, Flow Control
7-44	Interface Loop Diagram, Flow Control
7-45	Interface Loop Diagram, Flow and Pressure Indication
7-46	Logic Diagram, Aux Feedwater Flow Control and Pump Test Logic
7-47	Logic Diagram, Auxiliary Feedwater Flow Control and Pump Test Logic
7-48	Logic Diagram, Auxiliary Feedwater Actuation System
7-49	Logic Diagram, Auxiliary Feedwater - Steam Generator Isolation Valves
7-50	Logic Diagram, Auxiliary Feedwater - Steam Generator Isolation Valves
7-51	Logic Diagram, AFAS-FOGG Remote Display and Annunciator Assignment
7-52	Logic Diagram, AFAS-FOGG Remote Display and Annunciator Assignment

7-53	Reactor Shutdown Controls
7-54	Reactor Regulating System Block Diagram
7-55	Rod Drive Control System Schematic Diagram
7-56	Rod Position Set Points
7-57	Pressure Control Program
7-58	Block Diagram, Steam Dump and Bypass System
7-59	Pressurizer Level Control System Failures Study - Mode "A" Failure
7-60	Piping Drawing, Nuclear Detector Wells
7-61	Block Diagram, Critical Functions Monitor System

**SECTIONS**

<b>8.1</b>	<b>INTRODUCTION .....</b>	<b>8.1-1</b>
	8.1.1 DESIGN BASIS .....	8.1-1
	8.1.2 DESCRIPTION AND OPERATION .....	8.1-3
	8.1.3 ENVIRONMENTAL QUALIFICATION OF ELECTRICAL EQUIPMENT.....	8.1-4
	8.1.4 SEISMIC QUALIFICATION OF ELECTRICAL EQUIPMENT .....	8.1-6
	8.1.5 STATION BLACKOUT .....	8.1-6
<b>8.2</b>	<b>NETWORK INTERCONNECTION .....</b>	<b>8.2-1</b>
	8.2.1 DESIGN BASIS .....	8.2-1
	8.2.2 DESCRIPTION AND OPERATION .....	8.2-1
	8.2.3 DESIGN ANALYSIS .....	8.2-3
	8.2.4 TRANSMISSION SYSTEM OWNERSHIP.....	8.2-5
<b>8.3</b>	<b>STATION DISTRIBUTION .....</b>	<b>8.3-1</b>
	8.3.1 4,160 VOLT SYSTEM.....	8.3-1
	8.3.1.1 Design Basis.....	8.3-1
	8.3.1.2 Description and Operation .....	8.3-1
	8.3.1.3 Design Analysis.....	8.3-3
	8.3.2 2,400 VOLT SYSTEM.....	8.3-3
	8.3.2.1 Design Basis.....	8.3-3
	8.3.2.2 Description and Operation .....	8.3-3
	8.3.2.3 Design Analysis.....	8.3-7
	8.3.3 480 VOLT SYSTEM.....	8.3-7
	8.3.3.1 Design Basis.....	8.3-7
	8.3.3.2 Description and Operation .....	8.3-8
	8.3.3.3 Design Analysis.....	8.3-10
	8.3.4 CONTROL ROD DRIVE POWER.....	8.3-10
	8.3.4.1 Design Basis.....	8.3-10
	8.3.4.2 Description and Operation .....	8.3-11
	8.3.4.3 Design Analysis.....	8.3-11



8.3.5	DC AND PREFERRED AC SYSTEMS.....	8.3-11
8.3.5.1	Design Basis.....	8.3-11
8.3.5.2	Description and Operation .....	8.3-11
8.3.5.3	Design Analysis.....	8.3-17
8.3.6	INSTRUMENT AC SYSTEM .....	8.3-18
8.3.6.1	Design Basis.....	8.3-18
8.3.6.2	Description and Operation .....	8.3-18
8.3.6.3	Design Analysis.....	8.3-18
8.4	EMERGENCY POWER SOURCES .....	8.4-1
8.4.1	EMERGENCY GENERATORS.....	8.4-1
8.4.1.1	Design Basis.....	8.4-1
8.4.1.2	Description and Operation .....	8.4-1
8.4.1.3	Design Analysis.....	8.4-4
8.4.2	STATION BATTERIES.....	8.4-7
8.4.2.1	Design Basis.....	8.4-7
8.4.2.2	Description and Operation .....	8.4-8
8.4.2.3	Design Analysis.....	8.4-9
8.4.2.4	Dedicated Battery Supply to Address Fire Scenarios.....	8.4.9
8.4.3	TURBINE GENERATOR COASTDOWN .....	8.4-9
8.4.3.1	Design Basis.....	8.4-9
8.4.3.2	Description and Operation .....	8.4-10
8.4.4	EMERGENCY POWER SUPPLY FOR PRESSURIZER HEATERS .....	8.4-10
8.4.4.1	Design Basis.....	8.4-10
8.4.4.2	Description and Operation .....	8.4-10
8.4.5	SUPPLEMENTAL 2400 VOLT POWER SUPPLY .....	8.4-11
8.4.5.1	Design Basis.....	8.4-11
8.4.5.2	Description and Operation .....	8.4-11

---

<b>8.5</b>	<b>RACEWAY AND CABLING SYSTEM .....</b>	<b>8.5-1</b>
<b>8.5.1</b>	<b>DESIGN BASIS .....</b>	<b>8.5-1</b>
<b>8.5.1.1</b>	<b>Fire Protection Features .....</b>	<b>8.5-1</b>
<b>8.5.1.2</b>	<b>Electrical Penetrations of Reactor Containment ..</b>	<b>8.5-1</b>
<b>8.5.2</b>	<b>DESIGN DESCRIPTION.....</b>	<b>8.5-1</b>
<b>8.5.3</b>	<b>DESIGN EVALUATION.....</b>	<b>8.5-3</b>
<b>8.5.3.1</b>	<b>Compliance With Regulatory Guide 1.75.....</b>	<b>8.5-3</b>
<b>8.5.3.2</b>	<b>Raceway and Cabling Separation Criteria.....</b>	<b>8.5-4</b>
<b>8.5.3.3</b>	<b>Raceway and Cabling Fire Barriers .....</b>	<b>8.5-7</b>
<b>8.5.3.4</b>	<b>Cable Spreading Room Protection Design .....</b>	<b>8.5-7</b>
<b>8.5.3.5</b>	<b>Cable Penetration Rooms Protection Design .....</b>	<b>8.5-8</b>
<b>8.5.3.6</b>	<b>Raceway Runs Protection Design .....</b>	<b>8.5-9</b>
<b>8.5.3.7</b>	<b>Safety-Related Cabling Routing Via Nonsafety-Related Areas .....</b>	<b>8.5-9</b>
<b>8.5.3.8</b>	<b>Containment Building Routing Protection .....</b>	<b>8.5-10</b>
<b>8.5.3.9</b>	<b>Other Areas Routing Protection.....</b>	<b>8.5-10</b>
<b>8.6</b>	<b>AUTOMATIC TRANSFER, VOLTAGE PROTECTION AND LOAD SHEDDING CONTROLS .....</b>	<b>8.6-1</b>
<b>8.6.1</b>	<b>DESIGN BASIS .....</b>	<b>8.6-1</b>
<b>8.6.2</b>	<b>DESCRIPTION AND OPERATION .....</b>	<b>8.6-2</b>
<b>8.6.3</b>	<b>DESIGN ANALYSIS .....</b>	<b>8.6-5</b>
<b>8.6.3.1</b>	<b>Automatic Transfer System.....</b>	<b>8.6-5</b>
<b>8.6.3.2</b>	<b>Voltage Protection and Load Shedding Systems .</b>	<b>8.6-6</b>

**8.7 PHYSICAL SEPARATION, ELECTRICAL ISOLATION AND SUPPORT SYSTEMS .....8.7-1**  
**8.7.1 ELECTRICAL ISOLATION (SEE FIGURE 8-1) .....8.7-1**  
**8.7.2 PHYSICAL SEPARATION .....8.7-2**  
**8.7.2.1 General .....8.7-2**  
**8.7.2.2 Transformers .....8.7-3**  
**8.7.2.3 Protection Against Water Damage.....8.7-3**  
**8.7.2.4 Smoke Control .....8.7-4**  
**8.7.2.5 Switchgear Rooms Protection .....8.7-4**  
**8.7.2.6 Emergency Generators Rooms Protection .....8.7-5**  
**8.7.2.7 Battery Rooms Protection .....8.7-6**  
**8.7.3 SUPPORT SYSTEMS .....8.7-7**  
**8.7.3.1 Ventilation .....8.7-7**

**8.8 MOTOR OPERATED VALVES .....8.8-1**

**8.9 LIGHTING SYSTEMS .....8.9-1**

**8.10 QUALITY CONTROL .....8.10-1**

**REFERENCES .....8-1**

**LIST OF TABLES**

8-1 Switchyard System Ratings and Construction of Components  
8-2 4,160 Volt System Ratings and Construction of Components  
8-3 2,400 Volt System Ratings and Construction of Components  
8-4 480 Volt System Ratings and Construction of Components  
8-5 DC and Preferred AC Systems Ratings and Construction of Components  
8-6 Diesel 1-1 Sequence Start  
8-7 Diesel 1-2 Sequence Start

**LIST OF FIGURES**

8-1 Sh 1	Single Line Meter & Relay Diagram, 480 Volt Motor Control Center - Warehouse
8-1 Sh 2	Plant Single Line Diagram
8-1 Sh 3	Plant Single Line Diagram
8-2	Substation
8-3 Sh 1	Single Line Meter & Relay Diagram, Generator & 4160 V System
8-3 Sh 2	Single Line Meter & Relay Diagram, Cooling Tower Systems
8-4	Single Line Meter & Relay Diagram, 2400 Volt System
8-5 Sh 1	Single Line Meter & Relay Diagram, 480 Volt Load Centers
8-5 Sh 2	Single Line Meter & Relay Diagram, 480 Volt Load Centers
8-5 Sh 3	Single Line Meter & Relay Diagram, Cooling Tower Systems
8-6 Sh 1	Single Line Meter & Relay Diagram, 480 Volt Motor Control Centers
8-6 Sh 2	Single Line Meter & Relay Diagram, 480 Volt Motor Control Centers
8-6 Sh 3	Single Line Meter & Relay Diagram, 480 Volt Motor Control Centers
8-6 Sh 4	Single Line Meter & Relay Diagram, Radwaste System
8-7 Sh 1	Single Line Meter & Relay Diagram, 125V DC, 120V Instrument & Preferred AC System
8-7 Sh 2	Single Line Meter & Relay Diagram, 125V DC, 120V Instrument & Preferred AC System
8-8	125V DC System, Auxiliary Shutdown Layout
8-9	Substation 120/240V AC & 125V DC Power Distribution Center
8-10	Voltage Protection Sensors Location
8-11	Piping & Instrument Diagram, Lube Oil, Fuel Oil and Diesel Generator Systems
8-12	Battery Supply for Alternate Controls Credited in Fire Scenario

SECTIONS

9.1	SERVICE WATER SYSTEM.....	9.1-1
9.1.1	DESIGN BASIS.....	9.1-1
9.1.2	SYSTEM DESCRIPTION AND OPERATION .....	9.1-1
9.1.2.1	System Description.....	9.1-1
9.1.2.2	Component Description .....	9.1-2
9.1.2.3	System Operation .....	9.1-3
9.1.3	DESIGN ANALYSIS.....	9.1-5
9.1.3.1	Margins of Safety .....	9.1-5
9.1.3.2	Provisions for Testing and Inspection .....	9.1-6
9.1.3.3	Discharge Line Rupture Analysis .....	9.1-6
9.1.3.4	Generic Letter 96-06 Waterhammer Analysis .....	9.1-8
9.2	REACTOR PRIMARY SHIELD COOLING SYSTEM.....	9.2-1
9.2.1	DESIGN BASIS.....	9.2-1
9.2.2	SYSTEM DESCRIPTION AND OPERATION .....	9.2-1
9.2.2.1	System Description.....	9.2-1
9.2.2.2	Component Description .....	9.2-1
9.2.2.3	System Operation .....	9.2-2
9.2.3	DESIGN ANALYSIS.....	9.2-3
9.2.3.1	Margins of Safety .....	9.2-3
9.3	COMPONENT COOLING SYSTEM .....	9.3-1
9.3.1	DESIGN BASIS.....	9.3-1
9.3.2	SYSTEM DESCRIPTION AND OPERATION .....	9.3-1
9.3.2.1	System Description.....	9.3-1
9.3.2.2	Component Description .....	9.3-2
9.3.2.3	System Operation .....	9.3-2
9.3.3	DESIGN ANALYSIS.....	9.3-6
9.3.3.1	Margins of Safety .....	9.3-6
9.3.3.2	Provisions for Testing and Inspection .....	9.3-7
9.4	SPENT FUEL POOL COOLING SYSTEM .....	9.4-1
9.4.1	DESIGN BASIS.....	9.4-1
9.4.2	SYSTEM DESCRIPTION AND OPERATION .....	9.4-1
9.4.2.1	System Description.....	9.4-1
9.4.2.2	Component Description .....	9.4-2
9.4.2.3	System Operation .....	9.4-2
9.4.3	DESIGN ANALYSIS.....	9.4-3
9.4.3.1	Margins of Safety .....	9.4-3
9.4.3.2	Provisions for Testing .....	9.4-4

9.5	COMPRESSED AIR SYSTEMS .....	9.5-1
9.5.1	INSTRUMENT AIR SYSTEM .....	9.5-1
9.5.1.1	Design Basis .....	9.5-1
9.5.1.2	System Description.....	9.5-1
9.5.1.3	Component Description .....	9.5-1
9.5.1.4	System Operation .....	9.5-2
9.5.1.5	Design Analysis .....	9.5-3
9.5.2	HIGH PRESSURE AIR SYSTEM .....	9.5-4
9.5.2.1	Design Basis .....	9.5-4
9.5.2.2	System Description.....	9.5-4
9.5.2.3	Component Description .....	9.5-4
9.5.2.4	System Operation .....	9.5-5
9.5.2.5	Design Analysis .....	9.5-5
9.5.3	BACKUP SYSTEMS .....	9.5-6
9.5.3.1	Design Basis .....	9.5-6
9.5.3.2	System Description.....	9.5-7
9.5.3.3	Component Description .....	9.5-7
9.5.3.4	System Operation .....	9.5-7
9.5.3.5	Design Analysis .....	9.5-8
9.5.4	FEEDWATER PURITY AIR SYSTEM .....	9.5-8
9.5.4.1	Design Basis .....	9.5-8
9.5.4.2	System Description.....	9.5-8
9.5.4.3	Component Description .....	9.5-8
9.5.4.4	System Operation .....	9.5-8
9.5.5	RADWASTE AREA COMPRESSOR .....	9.5-9
9.6	FIRE PROTECTION .....	9.6-1
9.6.1	DESIGN BASIS.....	9.6-1
9.6.2	SYSTEM DESCRIPTION AND OPERATION .....	9.6-2
9.6.2.1	System Description.....	9.6-2
9.6.2.2	Component Description .....	9.6-3
9.6.2.3	System Operation .....	9.6-4
9.6.3	DESIGN ANALYSIS .....	9.6-5
9.6.4	FIRE PROTECTION PROGRAM.....	9.6-5
9.7	AUXILIARY FEEDWATER SYSTEM.....	9.7-1
9.7.1	DESIGN BASIS.....	9.7-1
9.7.2	SYSTEM DESCRIPTION AND OPERATION .....	9.7-1
9.7.2.1	System Description.....	9.7-1
9.7.2.2	Component Description .....	9.7-2
9.7.2.3	System Operation .....	9.7-2
9.7.3	DESIGN ANALYSIS.....	9.7-4
9.7.4	SYSTEM RELIABILITY.....	9.7-5
9.7.5	TESTS AND INSPECTION .....	9.7-5

9.8	HEATING, VENTILATION AND AIR-CONDITIONING SYSTEM .....	9.8-1
9.8.1	DESIGN BASIS.....	9.8-1
9.8.2	SYSTEM DESCRIPTION AND OPERATION .....	9.8-2
9.8.2.1	System Description.....	9.8-2
9.8.2.2	Component Description .....	9.8-4
9.8.2.3	Codes .....	9.8-6
9.8.2.4	Operation .....	9.8-7
9.8.3	TESTS AND INSPECTIONS .....	9.8-22
9.8.4	LOSS OF INSTRUMENT AIR TO VENTILATION DAMPERS.....	9.8-23
9.8.5	SAFETY EVALUATION .....	9.8-24
9.8.5.1	Introduction .....	9.8-24
9.8.5.2	Evaluation.....	9.8-24
9.9	SAMPLING SYSTEM.....	9.9-1
9.9.1	DESIGN BASIS.....	9.9-1
9.9.2	SYSTEM DESCRIPTION AND OPERATION .....	9.9-1
9.9.3	SYSTEM EVALUATION .....	9.9-2
9.10	CHEMICAL AND VOLUME CONTROL SYSTEM .....	9.10-1
9.10.1	DESIGN BASIS.....	9.10-1
9.10.2	SYSTEM DESCRIPTION AND OPERATION .....	9.10-1
9.10.2.1	General.....	9.10-1
9.10.2.2	Volume Control .....	9.10-2
9.10.2.3	Chemical Control .....	9.10-3
9.10.2.4	Reactivity Control .....	9.10-4
9.10.2.5	Pressure-Leakage Test System .....	9.10-5
9.10.2.6	Component Functional Description .....	9.10-5
9.10.3	OPERATIONS.....	9.10-8
9.10.3.1	Start-Up.....	9.10-8
9.10.3.2	Normal Operations.....	9.10-9
9.10.3.3	Shutdown.....	9.10-10
9.10.3.4	Emergency Operations.....	9.10-11
9.10.4	DESIGN ANALYSIS.....	9.10-11
9.10.5	TESTING AND INSPECTION .....	9.10-12
9.10.6	REGENERATIVE HEAT EXCHANGER.....	9.10-12
9.11	FUEL HANDLING AND STORAGE SYSTEMS .....	9.11-1
9.11.1	INTRODUCTION .....	9.11-1
9.11.2	NEW FUEL STORAGE .....	9.11-1
9.11.3	SPENT FUEL STORAGE .....	9.11-2
9.11.3.1	Original Design .....	9.11-2
9.11.3.2	Modified Spent Fuel Storage.....	9.11-3
9.11.3.3	Structural Analysis .....	9.11-5

9.11.3.4	Prevention of Criticality During Transfer and Storage .....	9.11-6
9.11.3.5	Radiological Considerations.....	9.11-10
9.11.3.5.1	Radiation Shielding.....	9.11-10
9.11.3.5.2	Pool Surface Dose.....	9.11-10
9.11.3.5.3	Airborne Doses.....	9.11-11
9.11.3.5.4	General Area Doses .....	9.11-12
9.11.3.5.5	Protection Against Radioactivity Release.....	9.11-12
9.11.4	FUEL HANDLING SYSTEM.....	9.11-14
9.11.4.1	General.....	9.11-14
9.11.4.2	Fuel Handling Structures .....	9.11-15
9.11.4.3	Major Fuel Handling Equipment .....	9.11-15
9.11.4.4	System Evaluation .....	9.11-28
9.11.4.5	Test Program.....	9.11-29
9.11.5	SPENT FUEL STORAGE AT AN INDEPENDENT SPENT FUEL STORAGE INSTALLATION .....	9.11-30
9.11.5.1	Description Of 10CFR72 License Items Which Interface With The 10CFR50 License.....	9.11-31
9.11.5.1.1	Multi-Assembly Sealed Basket And Transfer Cask .....	9.11-31
9.11.5.1.2	Transnuclear 32PT-S125 DSC, 24 PTH-S125 DSC and OS-197 Transfer Cask .....	9.11-32
9.11.5.1.3	HI-STORM FW MPC and Transfer Cask..	9.11-32
9.11.5.1.4	Impact Limiting Pads.....	9.11-32
9.11.5.1.5	Security For The Independent Spent Fuel Storage Installation.....	9.11-33
9.11.5.1.6	Lifting Equipment.....	9.11-33
9.11.5.1.7	Spent Fuel Pool Boron and Temperature Limits.....	9.11-34
9.12	ULTIMATE HEAT SINK.....	9.12-1
9.12.1	DESIGN BASIS.....	9.12-1
9.12.2	SYSTEM DESCRIPTION AND OPERATION .....	9.12-1
9.12.2.1	System Description.....	9.12-1
9.12.2.2	System Operation .....	9.12-3
9.12.3	DESIGN ANALYSIS.....	9.12-3
9.12.3.1	Margin of Safety .....	9.12-3
9.12.3.2	Provisions for Testing and Inspection .....	9.12-4
9.12.3.3	Heat Sink At Hot Shutdown Conditions .....	9.12-4
	REFERENCES.....	9-1



**LIST OF TABLES**

9-1	Service Water System Flow Requirements
9-2	Service Water System Design Ratings and Construction of Components
9-3	Reactor Primary Shield Cooling System Design Ratings and Construction of Components
9-4	Component Cooling System Heat Loads
9-5	Component Cooling Water System Design Ratings and Construction of Components
9-6	Component Cooling System Required Flow Rates
9-7	Spent Fuel Pool Cooling System Design Ratings and Construction of Components
9-8	Instrument Air System Design Ratings and Construction of Components
9-9	Effect of Loss of Air to Air-Operated Valves
9-10	Fire Detection Instrumentation
9-11	Fire Protection System Design Ratings and Construction of Components
9-12	Auxiliary Feedwater System Design Ratings and Construction of Components
9-13	Design Basis Ambient Conditions
9-14	Control Room HVAC System Major Component Design Data
9-15	Ventilation Dampers: Functions and Positions for Various Modes of Plant Operation
9-16	Sampling Stations
9-17	Sample Point Summary
9-18	Chemical and Volume Control System Design Parameters
9-19	Fuel Handling Data
9-20	Fuel Building Crane

**LIST OF FIGURES**

9-1 Sh 1	System Diagram, Service Water System
9-1 Sh 1A	P&ID, Service Water System
9-1 Sh 1B	P&ID, Service Water System
9-1 Sh 2	P&ID, Service Water Screen Structure, and Chlorinator
9-2	P&ID, Shield Cooling System
9-3	Nominal Operating Conditions Cooling Coil Centerline
9-4	Nominal Operating Conditions Mid-Span of Two Cooling Coils
9-5	Bounding Design Cooling Coil Centerline
9-6	Bounding Design Conditions and Mid-Span of Two Cooling Coils
9-7 Sh 1	P&ID, Component Cooling System
9-7 Sh 2	P&ID, Component Cooling System
9-7 Sh 3	P&ID, Component Cooling System
9-8	P&ID, Spent Fuel Pool Cooling System
9-9 Sh 1	P&ID, Service and Instrument Air Systems
9-9 Sh 2	P&ID, Miscellaneous Gas Supply Systems
9-10 Sh 1	P&ID, High Pressure Air Operated Valves
9-10 Sh 1A	P&ID High Pressure Air Operated Valves
9-10 Sh 2	P&ID, High Pressure Air Operated Valves
9-11 Sh 1	P&ID, Fire Protection System
9-11 Sh 2	P&ID, Fire Protection System
9-11 Sh 3	P&ID, Fire Protection System
9-12	P&ID, Auxiliary Feedwater System
9-13	P&ID, Auxiliary Feedwater Steam Supply
9-14 Sh 1	P&ID, Heating, Ventilation and Air Conditioning, Switchgear and Cable Spreading Rooms
9-14 Sh 2	P&ID, Heating, Ventilation and Air Conditioning, Containment Building
9-14 Sh 3	P&ID, Heating, Ventilation and Air Conditioning, Radwaste Area
9-14 Sh 4	P&ID, Heating, Ventilation and Air Conditioning, Miscellaneous Buildings
9-14 Sh 5	P&ID, Heating, Ventilation and Air Conditioning, Control Room
9-14 Sh 6	P&ID, Heating, Ventilation and Air Conditioning, Control Room
9-14 Sh 7	P&ID, Heating, Ventilation and Air Conditioning, Control Room
9-14 Sh 8	Heating and Ventilation Air Flow Diagram
9-14 Sh 9	P&ID, Heating, Ventilating and Cooling Auxiliary Building Addition
9-15	P&ID, Fluid System Diagram Post Accident Sample Monitor System
9-16	P&ID, Gas Analyzing Systems (Containment Hydrogen)
9-17	Monitoring and Sampling Systems (Radwaste Addition)
9-18 Sh 1	P&ID, Chemical and Volume Control System
9-18 Sh 1A	P&ID, Chemical and Volume Control System
9-18 Sh 1B	P&ID, Chemical and Volume Control System
9-19	Boron Concentration vs Core Lifetime
9-20	Palisades Plant Spent Fuel Storage Rack Arrangement

**SECTIONS**

10.1 DESIGN BASIS..... 10.1-1

10.2 SYSTEM DESCRIPTION AND OPERATION ..... 10.2-1

10.2.1 SYSTEM GENERAL DESCRIPTION..... 10.2-1

10.2.2 SYSTEM TURBINE..... 10.2-5

10.2.2.1 High-Pressure Turbine ..... 10.2-5

10.2.2.2 Low-Pressure Turbine ..... 10.2-6

10.2.2.3 Electrical Generator..... 10.2-8

10.2.2.4 Exciter..... 10.2-8

10.2.3 CONDENSATE AND FEEDWATER..... 10.2-9

10.2.3.1 Condensate System..... 10.2-9

10.2.3.2 Condensate Demineralizer System..... 10.2-10

10.2.3.3 Feedwater Regulating System..... 10.2-11

10.2.4 CIRCULATING WATER SYSTEM..... 10.2-13

10.2.4.1 Cooling Towers..... 10.2-13

10.2.4.2 Makeup and Blowdown..... 10.2-14

10.2.4.3 Dilution..... 10.2-14

10.2.5 CODES AND STANDARDS..... 10.2-14

10.3 SYSTEM ANALYSIS..... 10.3-1

10.3.1 REACTOR AND/OR TURBINE TRIP..... 10.3-1

10.4 TESTS AND INSPECTIONS..... 10.4-1

10.4.1 PIPE WALL THINNING INSPECTION PROGRAM..... 10.4-1

REFERENCES.....None

**LIST OF TABLES**

10-1 Turbine Casing Properties

10-2 Stud Mechanical Properties

10-3 Signal System Operating Conditions

10-4 Cooling Tower Design Summary

10-5 Cooling Tower Pumps

**LIST OF FIGURES**

10-1 System Diagram, Main Steam, Main and Auxiliary Turbine Systems

10-2 System Diagram, Extractions, Heaters Vents and Drain Systems

10-3 Sh 1 Piping and Instrument Diagram, Steam Generator Blowdown Modification

10-3 Sh 2 Piping and Instrument Diagram, Steam Generator Blowdown Modification

10-3 Sh 3 Piping and Instrument Diagram, Steam Generator Blowdown Modification

10-4 System Diagram, Feedwater and Condensate System

10-5 General Assembly Electrical Generator

10-6 System Diagram, Cooling Tower System

**TABLE OF CONTENTS**

---

**SECTIONS**

<b>11.1</b>	<b>SOURCE TERMS .....</b>	<b>11.1-1</b>
<b>11.2</b>	<b>LIQUID RADIOACTIVE WASTE SYSTEM.....</b>	<b>11.2-1</b>
	<b>11.2.1 DESIGN BASES .....</b>	<b>11.2-1</b>
	11.2.1.1 Design Objective.....	11.2-1
	11.2.1.2 Design Criteria .....	11.2-1
	11.2.1.3 Codes .....	11.2-1
	<b>11.2.2 SYSTEM DESCRIPTION .....</b>	<b>11.2-2</b>
	11.2.2.1 Clean Waste Section.....	11.2-2
	11.2.2.2 Dirty Waste Section .....	11.2-4
	11.2.2.3 Laundry Waste Section .....	11.2-4
	<b>11.2.3 RADIOACTIVE RELEASES.....</b>	<b>11.2-5</b>
	11.2.3.1 Clean Waste Section.....	11.2-5
	11.2.3.2 Dirty Waste Section .....	11.2-8
	11.2.3.3 Laundry Waste Section .....	11.2-8
	<b>11.2.4 BALANCE OF PLANT (BOP) INTERFACE.....</b>	<b>11.2-8</b>
	11.2.4.1 Clean Waste Section.....	11.2-8
	11.2.4.2 Dirty Waste Section .....	11.2-8
	11.2.4.3 Laundry Waste Section .....	11.2-9
	11.2.4.4 Alternate Radwaste Processing System.....	11.2-9
<b>11.2.5</b>	<b>SYSTEM EVALUATION .....</b>	<b>11.2-9</b>
<b>11.3</b>	<b>GASEOUS RADIOACTIVE WASTE SYSTEM.....</b>	<b>11.3-1</b>
	<b>11.3.1 DESIGN BASIS.....</b>	<b>11.3-1</b>
	<b>11.3.2 SYSTEM DESCRIPTION .....</b>	<b>11.3-1</b>
	11.3.2.1 Gas Collection Header.....	11.3-1
	11.3.2.2 Waste Gas Processing System.....	11.3-2
	<b>11.3.3 RADIOACTIVE RELEASES.....</b>	<b>11.3-2</b>
	<b>11.3.4 BOP INTERFACE .....</b>	<b>11.3-3</b>
	<b>11.3.5 SYSTEM EVALUATION .....</b>	<b>11.3-3</b>
<b>11.4</b>	<b>SOLID WASTE MANAGEMENT SYSTEM.....</b>	<b>11.4-1</b>
	<b>11.4.1 DESIGN BASIS.....</b>	<b>11.4-1</b>
	<b>11.4.2 SYSTEM DESCRIPTION .....</b>	<b>11.4-2</b>
	11.4.2.1 System Modifications .....	11.4-2
	11.4.2.2 Radioactive Waste Storage Facilities.....	11.4-3
	11.4.2.3 Alternate Radwaste Processing Standard Dewatering System .....	11.4-8
	<b>11.4.3 RADIOACTIVE RELEASES.....</b>	<b>11.4-8</b>
	<b>11.4.4 BOP INTERFACE .....</b>	<b>11.4-9</b>
	<b>11.4.5 SYSTEM EVALUATION .....</b>	<b>11.4-9</b>
	<b>11.4.6 REQUEST TO RETAIN SOIL IN ACCORDANCE     WITH 10CFR20.302 .....</b>	<b>11.4-9</b>

TABLE OF CONTENTS

---

11.5	PROCESS AND EFFLUENT RADIOLOGICAL MONITORING AND SAMPLING SYSTEM.....	11.5-1
	11.5.1 DESIGN BASIS.....	11.5-1
	11.5.2 SYSTEM DESCRIPTION .....	11.5-1
	11.5.3 EFFLUENT MONITORING AND SAMPLING .....	11.5-2
	11.5.4 SYSTEM EVALUATION .....	11.5-3
11.6	RADIATION PROTECTION.....	11.6-1
	11.6.1 GENERAL.....	11.6-1
	11.6.1.1 Radiation Exposure of Personnel.....	11.6-1
	11.6.1.2 Radiation Exposure of Materials and Components.....	11.6-1
	11.6.2 RADIATION ZONING AND ACCESS CONTROL .....	11.6-2
	11.6.3 GENERAL DESIGN CONSIDERATIONS .....	11.6-3
	11.6.3.1 Specific Design Values.....	11.6-3
	11.6.3.2 Reactor Core Data.....	11.6-3
	11.6.4 SHIELDING DESIGN .....	11.6-4
	11.6.4.1 Containment Building Shell .....	11.6-4
	11.6.4.2 Containment Building Interior .....	11.6-4
	11.6.4.3 Auxiliary Building (Including Radwaste Building Addition).....	11.6-5
	11.6.4.4 Turbine Building .....	11.6-7
	11.6.4.5 General Plant Yard Areas .....	11.6-7
	11.6.4.6 Other Buildings .....	11.6-7
	11.6.5 AREA RADIATION MONITORING SYSTEMS .....	11.6-8
	11.6.5.1 Design Basis .....	11.6-8
	11.6.5.2 System Description.....	11.6-8
	11.6.5.3 Testing and Maintenance .....	11.6-9
	11.6.6 HEALTH PHYSICS .....	11.6-9
	11.6.6.1 Facilities.....	11.6-9
	11.6.6.2 Tool and Equipment Decontamination Facility	11.6-10
	11.6.6.3 Calibration Facility.....	11.6-11
	11.6.6.4 Radiation Control.....	11.6-11
	11.6.6.5 Shielding.....	11.6-11
	11.6.6.6 Access Control.....	11.6-11
	11.6.6.7 Facility Contamination Control.....	11.6-13
	11.6.6.8 Personnel Contamination Control.....	11.6-14
	11.6.6.9 Airborne Contamination Control .....	11.6-15
	11.6.6.9.1 Respiratory Protection Program .....	11.6-15
	11.6.6.10 External Radiation Dose Determination.....	11.6-17
	11.6.6.11 Internal Radiation Dose Determination.....	11.6-17

**TABLE OF CONTENTS**

---

<b>11.6.7 RADIATION PROTECTION INSTRUMENTATION.....</b>	<b>11.6-18</b>
11.6.7.1 Counting Room Instrumentation .....	11.6-18
11.6.7.2 Portable Radiation Detecting Instrumentation .	11.6-18
11.6.7.3 Air Sampling Instrumentation .....	11.6-18
11.6.7.4 Personal Monitoring Instrumentation .....	11.6-19
11.6.7.5 Emergency Instrumentation.....	11.6-19
<b>11.6.8 TESTS AND INSPECTIONS .....</b>	<b>11.6-19</b>
11.6.8.1 Shielding .....	11.6-19
11.6.8.2 Area and Process Radiation Monitors .....	11.6-20
11.6.8.3 Continuous Air Monitors .....	11.6-20
11.6.8.4 Radiation Protection Instrumentation .....	11.6-20
<b>11.6.9 CONTROL OF BYPRODUCT, SOURCE OR SPECIAL NUCLEAR MATERIAL (SNM) SOURCES .....</b>	<b>11.6-21</b>
<b>11.6.10 RADIOACTIVE MATERIAL STORAGE FACILITIES.....</b>	<b>11.6-22</b>

<b>REFERENCES.....</b>	<b>11-1</b>
------------------------	-------------

**LIST OF TABLES**

11-1	Primary Coolant Fission and Corrosion Product Activities
11-2	Radioactive Waste Quantities of Significant Activity
11-3	Equipment Ratings and Construction Codes - Original Equipment
11-4	Equipment Ratings and Construction Codes - Additional Equipment Installed 1971-1973
11-5	Primary System Drain Tank
11-6	Equipment Drain Tank
11-7	Dirty Waste Drain Tank
11-8	Liquid Radwaste
11-9	Maximum Calculated Tritium Release Due to Evaporation From Refueling Cavity and Spent Fuel Pool
11-10	LADTAP Input Data and Results Maximum Individual Dose Calculations
11-11	Activity in Coolant and Gaseous Waste
11-12	Special Location GASPAP Input Data
11-13	Dose Results for Special Locations, Maximum Individual Doses by Age Group and Organ
11-14	Deleted
11-15	Process Radiation Service and Equipment
11-16	Area Radiation Detectors
11-17	Primary Coolant Fission and Corrosion Product Activities for AST Dose Analyses

**TABLE OF CONTENTS**

---

**LIST OF FIGURES**

11-1 Sh 1	P&ID Radioactive Waste Treatment System Clean
11-1 Sh 1A	P&ID Radioactive Waste Treatment System Clean
11-1 Sh 1B	P&ID Radioactive Waste Treatment System Clean
11-1 Sh 1C	P&ID Radioactive Waste Treatment System Clean
11-1 Sh 2	P&ID Radioactive Waste Treatment System Clean
11-1 Sh 3	P&ID Radwaste Evaporator System Clean Wastes
11-2 Sh 1	P&ID Dirty Waste & Gaseous Waste
11-2 Sh 2	P&ID Radwaste Evaporator System Miscellaneous Waste
11-2 Sh 2A	P&ID Radwaste Evaporator System Miscellaneous Waste
11-2 Sh 2B	P&ID Radwaste Evaporator System Miscellaneous Waste
11-3 Sh 1	P&ID Radioactive Waste Treatment System Gaseous Waste
11-3 Sh 2	P&ID Radioactive Waste Treatment System Gaseous Waste
11-4 Sh 1	Spent Resin Storage and Radwaste Packaging System
11-4 Sh 2	P&ID Radwaste Solidification System
11-4 Sh 3	P&ID Liquid Volume Reduction System
11-5 Sh 1	P&ID Radiation Monitoring and Sampling Systems
11-5 Sh 1A	P&ID Radiation Monitoring and Sampling Systems
11-5 Sh 1B	P&ID Radiation Monitoring and Sampling Systems
11-5 Sh 2	P&ID Radiation Monitoring and Sampling Systems
11-6	Gaseous Effluent Monitoring System
11-7	Architectural Access Control and Radiation Zoning (Plant in Operation)
11-8	Architectural Access Control and Radiation Zoning (Plant in Operation)
11-9	Architectural Access Control and Radiation Zoning (Plant in Operation)

**SECTIONS**

**12.1 ORGANIZATION AND RESPONSIBILITY ..... 12.1-1**  
**12.1.1 MANAGEMENT AND TECHICAL SUPPORT ORGANIZATIONS ..... 12.1-1**

**12.2 TRAINING ..... 12.2-1**  
**12.2.1 PLANT STAFF TRAINING PROGRAM..... 12.2-1**  
 12.2.1.1 Plant Access Training..... 12.2-1  
 12.2.1.2 Radiation Worker Training (RWT)..... 12.2-1  
 12.2.1.3 Licensed and Nonlicensed Operator Training Program ..... 12.2-2  
 12.2.1.4 Instrumentation and Controls (I&C) Technician Training Programs ..... 12.2-2  
 12.2.1.5 Mechanical and Electrical Maintenance Personnel Training Program ..... 12.2-3  
 12.2.1.6 Radiological Protection Technician Training Program ..... 12.2-3  
 12.2.1.7 Chemistry Technician Training Program ..... 12.2-3  
 12.2.1.8 Engineering Support Personnel Training Program ..... 12.2-3  
 12.2.1.9 Fire Protection Training..... 12.2-4  
**12.2.2 TRAINING EFFECTIVENESS EVALUATION ..... 12.2-4**

**12.3 PLANT PROCEDURES ..... 12.3-1**  
 12.3.1 PROCEDURE CONTROL REQUIREMENTS..... 12.3-1  
 12.3.2 UPGRADE AND MAINTENANCE OF EMERGENCY OPERATING PROCEDURES ..... 12.3-2  
 12.3.3 OPERATING REQUIREMENTS MANUAL (ORM)..... 12.3-2

**12.4 REVIEW AND ASSESMENT ..... 12.4-1**

**12.5 EMERGENCY PLANNING ..... 12.5-1**

**12.6 INDUSTRIAL SECURITY ..... 12.6-1**

**REFERENCES ..... None**

**TABLES ..... None**

**LIST OF FIGURES**

12-1 Entergy Nuclear Site Leadership  
 12-2 Plant Specific Titles for Generic Titles Located in the Technical Specifications  
 12-3 Deleted



**SECTIONS**

**13.1 TESTS PRIOR TO REACTOR FUELING ..... 13.1-1**

**13.2 REACTOR FUELING AND PHYSICS TESTS ..... 13.2-1**

**13.2.1 CORE LOADING ..... 13.2-1**

**13.2.2 POST-LOADING TESTS ..... 13.2-2**

**13.2.3 INITIAL CRITICALITY ..... 13.2-2**

**13.3 POST CRITICALITY AND POWER ESCALATION ..... 13.3-1**

**13.3.1 ZERO POWER TESTING ..... 13.3-1**

**13.3.2 POWER ESCALATION ..... 13.3-1**

**13.3.3 ESCALATION TO 2,650 MWt ..... 13.3-2**

**13.4 OPERATION RESTRICTIONS ..... 13.4-1**

**13.4.1 SAFETY PRECAUTIONS ..... 13.4-1**

**13.4.2 SUMMARY ..... 13.4-1**

**REFERENCES ..... None**

**TABLES ..... None**

**FIGURES ..... None**

**SECTIONS**

<b>14.1</b>	<b>INTRODUCTION.....</b>	<b>14.1-1</b>
14.1.1	BACKGROUND.....	14.1-1
14.1.2	ANALYSES AT NOMINAL POWER LEVEL OF 2,650 MWt..	14.1-5
14.1.3	ANALYSES PERFORMED AT 2,580.6 MWt INCLUDING UNCERTAINTY .....	14.1-5
<b>14.2</b>	<b>UNCONTROLLED CONTROL ROD WITHDRAWAL.....</b>	<b>14.2-1</b>
14.2.1	UNCONTROLLED CONTROL ROD BANK WITHDRAWAL FROM A SUBCRITICAL OR LOW POWER START-UP CONDITION .....	14.2-1
14.2.1.1	Event Description.....	14.2-1
14.2.1.2	Thermal-Hydraulic Analysis .....	14.2-2
14.2.1.2.1	Analysis Method.....	14.2-2
14.2.1.2.2	Bounding Event Input.....	14.2-2
14.2.1.2.3	Analysis of Results .....	14.2-3
14.2.1.3	Radiological Consequences .....	14.2-3
14.2.1.4	Conclusions .....	14.2-3
14.2.2	UNCONTROLLED CONTROL ROD BANK WITHDRAWAL AT POWER.....	14.2-4
14.2.2.1	Event Description.....	14.2-4
14.2.2.2	Thermal-Hydraulic Analysis .....	14.2-4
14.2.2.2.1	Analysis Method.....	14.2-4
14.2.2.2.2	Bounding Event Input.....	14.2-5
14.2.2.2.3	Analysis of Results .....	14.2-5
14.2.2.3	Radiological Consequences .....	14.2-6
14.2.2.4	Conclusions .....	14.2-6
14.2.3	SINGLE CONTROL ROD WITHDRAWAL .....	14.2-6
14.2.3.1	Event Description.....	14.2-6
14.2.3.2	Thermal-Hydraulics Analysis .....	14.2-7
14.2.3.2.1	Analysis Method.....	14.2-7
14.2.3.2.2	Bounding Event Input.....	14.2-7
14.2.3.2.3	Analysis of Results .....	14.2-8
14.2.3.3	Radiological Consequences .....	14.2-8
14.2.3.4	Conclusions .....	14.2-8

14.3	BORON DILUTION.....	14.3-1
14.3.1	EVENT DESCRIPTION.....	14.3-1
14.3.2	THERMAL-HYDRAULIC ANALYSIS .....	14.3-2
14.3.2.1	Analysis Method.....	14.3-2
14.3.2.2	Bounding Event Input.....	14.3-3
14.3.2.3	Analysis of Results .....	14.3-3
14.3.2.3.1	Dilution During Refueling (Mode 6) .....	14.3-3
14.3.2.3.2	Dilution During Cold Shutdown (Mode 5) .....	14.3-4
14.3.2.3.3	Dilution During Hot Shutdown (Mode 4) ..	14.3-6
14.3.2.3.4	Dilution During Hot Standby (Mode 3).....	14.3-7
14.3.2.3.5	Dilution During Power Operation and Startup (Modes 1 and 2).....	14.3-8
14.3.2.3.6	Failure to Add Boron to Compensate for Reactivity Changes After Shutdown.....	14.3-8
14.3.3	RADIOLOGICAL CONSEQUENCES .....	14.3-9
14.3.4	CONCLUSIONS.....	14.3-9
14.4	CONTROL ROD DROP .....	14.4-1
14.4.1	DROPPED ROD EVENT.....	14.4-1
14.4.1.1	Event Description.....	14.4-1
14.4.1.2	Thermal-Hydraulic Analysis.....	14.4-2
14.4.1.2.1	Analysis Methods.....	14.4-2
14.4.1.2.2	Bounding Event Input.....	14.4-2
14.4.1.2.3	Analysis of Results .....	14.4-2
14.4.1.3	Radiological Consequences .....	14.4-3
14.4.1.4	Conclusions .....	14.4-3
14.4.2	DROPPED BANK EVENT .....	14.4-3
14.4.2.1	Event Description.....	14.4-3
14.4.2.2	Thermal-Hydraulic Analysis.....	14.4-3
14.4.2.2.1	Analysis Methods.....	14.4-3
14.4.2.2.2	Bounding Event Input.....	14.4-4
14.4.2.2.3	Analysis of Results .....	14.4-4
14.4.2.3	Radiological Consequences .....	14.4-4
14.4.2.4	Conclusions .....	14.4-5
14.5	CORE BARREL FAILURE .....	14.5-1
14.5.1	EVENT DESCRIPTION.....	14.5-1
14.5.2	THERMAL-HYDRAULIC ANALYSIS .....	14.5-1
14.5.3	RADIOLOGICAL CONSEQUENCES .....	14.5-1
14.5.4	CONCLUSIONS.....	14.5-1

14.6	CONTROL ROD MISOPERATION.....	14.6-1
14.6.1	MALPOSITION OF THE PART-LENGTH CONTROL ROD GROUP .....	14.6-1
14.6.1.1	Event Description.....	14.6-1
14.6.1.2	Thermal-Hydraulic Analysis.....	14.6-1
14.6.1.3	Radiological Consequences .....	14.6-1
14.6.1.4	Conclusions .....	14.6-1
14.6.2	STATICALLY MISALIGNED CONTROL ROD/BANK .....	14.6-1
14.6.2.1	Event Description.....	14.6-1
14.6.2.2	Thermal-Hydraulics Analysis.....	14.6-2
14.6.2.2.1	Analysis Method.....	14.6-2
14.6.2.2.2	Bounding Event Input.....	14.6-2
14.6.2.2.3	Analysis of Results .....	14.6-3
14.6.2.3	Radiological Consequences .....	14.6-3
14.6.2.4	Conclusion .....	14.6-3
14.7	DECREASED REACTOR COOLANT FLOW.....	14.7-1
14.7.1	LOSS OF FORCED REACTOR COOLANT FLOW .....	14.7-1
14.7.1.1	Event Description.....	14.7-1
14.7.1.2	Thermal-Hydraulic Analysis.....	14.7-2
14.7.1.2.1	Analysis Method.....	14.7-2
14.7.1.2.2	Bounding Event Input.....	14.7-2
14.7.1.2.3	Analysis of Results .....	14.7-2
14.7.1.3	Radiological Consequences .....	14.7-3
14.7.1.4	Conclusions .....	14.7-3
14.7.2	REACTOR COOLANT PUMP ROTOR SEIZURE .....	14.7-3
14.7.2.1	Event Description.....	14.7-3
14.7.2.2	Thermal-Hydraulic Analysis.....	14.7-4
14.7.2.2.1	Analysis Method.....	14.7-4
14.7.2.3	Bounding Event Input.....	14.7-4
14.7.2.4	Analysis of Results .....	14.7-4
14.7.2.5	Radiological Consequences .....	14.7-4
14.7.2.6	Conclusions .....	14.7-5
14.8	START-UP OF AN INACTIVE LOOP .....	14.8-1
14.8.1	EVENT DESCRIPTION.....	14.8-1
14.9	EXCESSIVE FEEDWATER INCIDENT .....	14.9-1
14.10	INCREASE IN STEAM FLOW (EXCESS LOAD) .....	14.10-1
14.10.1	EVENT DESCRIPTION.....	14.10-1
14.10.2	THERMAL-HYDRAULIC ANALYSIS .....	14.10-2
14.10.2.1	Analysis Method.....	14.10-2
14.10.2.2	Bounding Event Input.....	14.10-2
14.10.2.3	Analysis of Results .....	14.10-3
14.10.3	RADIOLOGICAL CONSEQUENCES .....	14.10-3
14.10.4	CONCLUSIONS.....	14.10-4

14.11	POSTULATED CASK DROP ACCIDENTS.....	14.11-1
14.11.1	EVENT DESCRIPTION.....	14.11-1
14.11.2	STRUCTURAL ANALYSIS.....	14.11-2
14.11.2.1	Analysis Method.....	14.11-3
14.11.2.1.1	Analysis of Cask Drop Scenarios .....	14.11-3
14.11.2.1.2	Cask Overturn Due to Seismic Event .....	14.11-3
14.11.2.2	Bounding Event Input.....	14.11-4
14.11.2.2.1	Analysis of Cask Drop Scenarios .....	14.11-4
14.11.2.2.2	Cask Overturn Due to Seismic Event.....	14.11-4
14.11.2.3	Analysis Results .....	14.11-5
14.11.2.3.1	Analysis of Cask Drop Scenarios .....	14.11-5
14.11.2.3.2	Cask Overturn Due to Seismic Event.....	14.11-6
14.11.3	RADIOLOGICAL CONSEQUENCES .....	14.11-6
14.11.3.1	Analysis Method.....	14.11-6
14.11.3.1.1	Radiological Consequences of a Cask Drop in the Spent Fuel Pool. ...	14.11-6
14.11.3.1.2	Impact on MTC/MSB Due to Postulated Drop on the VCC in the Track Alley. ....	14.11-7
14.11.3.2	Bounding Event Input.....	14.11-8
14.11.3.2.1	Radiological Consequences of a Cask Drop in the Spent Fuel Pool. ...	14.11-8
14.11.3.3	Analysis Results .....	14.11-8
14.11.3.3.1	Radiological Consequences of a Cask Drop in the Spent Fuel Pool. ...	14.11-8
14.11.3.3.2	Drop of the Loaded MTC on to the VCC in the Track Alley .....	14.11-8
14.11.4	CONCLUSIONS.....	14.11-8
14.12	LOSS OF EXTERNAL LOAD .....	14.12-1
14.12.1	EVENT DESCRIPTION.....	14.12-1
14.12.2	THERMAL-HYDRAULIC ANALYSIS .....	14.12-1
14.12.2.1	Analysis Method.....	14.12-1
14.12.2.2	Bounding Event Input.....	14.12-2
14.12.2.3	Analysis of Results .....	14.12-3
14.12.3	RADIOLOGICAL CONSEQUENCES .....	14.12-3
14.12.4	CONCLUSIONS.....	14.12-4

14.13	LOSS OF NORMAL FEEDWATER .....	14.13-1
14.13.1	EVENT DESCRIPTION.....	14.13-1
14.13.2	THERMAL-HYDRAULIC ANALYSIS .....	14.13-3
14.13.2.1	Analysis Method.....	14.13-3
14.13.2.2	Bounding Event Input.....	14.13-3
14.13.2.3	Analysis of Results .....	14.13-5
14.13.3	RADIOLOGICAL CONSEQUENCES .....	14.13-10
14.13.4	CONCLUSIONS.....	14.13-10
14.14	STEAM LINE RUPTURE INCIDENT .....	14.14-1
14.14.1	EVENT DESCRIPTION.....	14.14-1
14.14.2	THERMAL-HYDRAULIC ANALYSIS .....	14.14-2
14.14.2.1	Analysis Method.....	14.14-2
14.14.2.2	Bounding Event Input.....	14.14-3
14.14.2.3	Analysis of Results .....	14.14-4
14.14.3	RADIOLOGICAL CONSEQUENCES .....	14.14-7
14.14.3.1	Analysis Method.....	14.14-7
14.14.3.2	Bounding Event Input.....	14.14-7
14.14.3.3	Analysis of Results .....	14.14-8
14.14.4	CONCLUSIONS.....	14.14-9
14.15	STEAM GENERATOR TUBE RUPTURE WITH A LOSS OF OFFSITE POWER .....	14.15-1
14.15.1	EVENT DESCRIPTION.....	14.15-1
14.15.2	THERMAL-HYDRAULIC ANALYSIS .....	14.15-2
14.15.2.1	Analysis Method.....	14.15-2
14.15.2.2	Bounding Event Input.....	14.15-2
14.15.2.3	Analysis of Results .....	14.15-4
14.15.3	RADIOLOGICAL ANALYSIS .....	14.15-6
14.15.3.1	Analysis Method.....	14.15-6
14.15.3.2	Bounding Event Input.....	14.15-7
14.15.3.3	Analysis of Results .....	14.15-8
14.15.4	CONCLUSIONS.....	14.15-9

14.16	CONTROL ROD EJECTION.....	14.16-1
14.16.1	EVENT DESCRIPTION.....	14.16-1
14.16.2	THERMAL-HYDRAULIC ANALYSIS .....	14.16-1
14.16.2.1	Analysis Method.....	14.16-1
14.16.2.2	Bounding Event Input.....	14.16-2
14.16.2.3	Analysis of Results .....	14.16-2
14.16.3	RADIOLOGICAL CONSEQUENCES .....	14.16-3
14.16.3.1	Induced LOCA .....	14.16-3
14.16.3.1.1	Analysis Method.....	14.16-3
14.16.3.1.2	Bounding Event Input.....	14.16-4
14.16.3.1.3	Analysis of Results .....	14.16-4
14.16.3.2	Steam Generator Release.....	14.16-4
14.16.3.2.1	Analysis Method.....	14.16-4
14.16.3.2.2	Bounding Event Input.....	14.16-5
14.16.3.2.3	Analysis of Results .....	14.16-5
14.16.4	CONCLUSION.....	14.16-5
14.17	LOSS OF COOLANT ACCIDENT .....	14.17-1
14.17.1	LARGE BREAK LOCA (LBLOCA) .....	14.17-1
14.17.1.1	Event Description.....	14.17-1
14.17.1.2	Thermal Hydraulics Analysis .....	14.17-3
14.17.1.2.1	Analysis Method.....	14.17-3
14.17.1.2.2	Bounding Event Input.....	14.17-5
14.17.1.2.3	Analysis of Results .....	14.17-6
14.17.1.3	Radiological Consequences .....	14.17-7
14.17.1.4	Conclusions .....	14.17-7
14.17.2	SMALL BREAK LOCA.....	14.17-8
14.17.2.1	Event Description.....	14.17-8
14.17.2.2	Thermal-Hydraulic Analysis.....	14.17-8
14.17.2.2.1	Analysis Models .....	14.17-8
14.17.2.2.2	Plant Description and Summary of Analysis Parameters .....	14.17-9
14.17.2.2.3	Analytical Results .....	14.17-10
14.17.2.3	Radiological Consequences .....	14.17-12
14.17.2.4	Conclusion .....	14.17-12
14.17.3	REACTOR INTERNALS STRUCTURAL BEHAVIOR FOLLOWING A LOCA .....	14.17-13
14.17.3.1	Event Description.....	14.17-13
14.17.3.2	Thermal-Hydraulic Analysis.....	14.17-14
14.17.3.2.1	Analysis Method.....	14.17-14
14.17.3.2.2	Bounding Event Input.....	14.17-14
14.17.3.2.3	Analysis of Results .....	14.17-14
14.17.3.3	Radiological Consequences .....	14.17-14
14.17.3.4	Conclusions .....	14.17-14

14.18	CONTAINMENT PRESSURE AND TEMPERATURE ANALYSIS .....	14.18-1
14.18.1	LOCA ANALYSIS.....	14.18-1
14.18.1.1	Event Description.....	14.18-1
14.18.1.2	Description of GOTHIC.....	14.18-1
14.18.1.3	Thermal-Hydraulic Analysis.....	14.18-3
14.18.1.3.1	Analysis Method.....	14.18-3
14.18.1.3.2	Bounding Event Input.....	14.18-6
14.18.1.3.3	Analysis of Results .....	14.18-7
14.18.1.4	Radiological Consequences .....	14.18-7
14.18.1.5	Conclusion .....	14.18-8
14.18.2	MSLB INSIDE CONTAINMENT.....	14.18-8
14.18.2.1	Event Description.....	14.18-8
14.18.2.2	Thermal-Hydraulic Analysis.....	14.18-9
14.18.2.2.1	Analysis Method.....	14.18-9
14.18.2.2.2	Bounding Event Input.....	14.18-12
14.18.2.2.3	Analysis of Results .....	14.18-13
14.18.2.3	Radiological Consequences .....	14.18-14
14.18.2.4	Conclusion .....	14.18-14
14.18.3	CONTAINMENT INTERNAL STRUCTURE EVALUATION	14.18-14
14.18.3.1	Event Description.....	14.18-14
14.18.3.2	Thermal Hydraulic Analysis .....	14.18-14
14.18.3.2.1	Analysis Method.....	14.18-14
14.18.3.2.2	Bounding Event Input.....	14.18-15
14.18.3.2.3	Analysis of Results .....	14.18-17
14.18.3.3	Radiological Consequences .....	14.18-18
14.18.3.4	Conclusion .....	14.18-18
14.19	FUEL HANDLING INCIDENT .....	14.19-1
14.19.1	EVENT DESCRIPTION.....	14.19-1
14.19.2	THERMAL-HYDRAULIC ANALYSIS .....	14.19-3
14.19.3	RADIOLOGICAL CONSEQUENCES .....	14.19-3
14.19.3.1	Analysis Method.....	14.19-3
14.19.3.2	Bounding Event Input.....	14.19-4
14.19.3.3	Analysis of Results .....	14.19-4
14.19.4	CONCLUSIONS.....	14.19-5
14.20	LIQUID WASTE INCIDENT .....	14.20-1
14.20.1	EVENT DESCRIPTION.....	14.20-1
14.20.2	THERMAL-HYDRAULIC ANALYSIS .....	14.20-1
14.20.3	RADIOLOGICAL CONSEQUENCES .....	14.20-1
14.20.3.1	Analysis Method.....	14.20-1
14.20.3.2	Bounding Event Input.....	14.20-2
14.20.3.3	Analysis of Results .....	14.20-2
14.20.4	CONCLUSIONS.....	14.20-3



14.21	WASTE GAS INCIDENT.....	14.21-1
14.21.1	GAS DECAY TANK RUPTURE.....	14.21-1
14.21.1.1	Event Description.....	14.21-1
14.21.1.2	Thermal-Hydraulic Analysis.....	14.21-1
14.21.1.3	Radiological Consequences .....	14.21-1
14.21.1.3.1	Analysis Method.....	14.21-1
14.21.1.3.2	Bounding Event Input.....	14.21-2
14.21.1.3.3	Analysis of Results .....	14.21-2
14.21.2	VOLUME CONTROL TANK RUPTURE.....	14.21-2
14.21.2.1	Event Description.....	14.21-2
14.21.2.2	Thermal-Hydraulic Analysis.....	14.21-3
14.21.2.3	Radiological Consequences .....	14.21-3
14.21.2.3.1	Analysis Method.....	14.21-3
14.21.2.3.2	Bounding Event Input.....	14.21-4
14.21.2.3.3	Analysis of Results .....	14.21-4
14.21.3	CONCLUSIONS.....	14.21-4
14.22	MAXIMUM HYPOTHETICAL ACCIDENT .....	14.22-1
14.22.1	EVENT DESCRIPTION.....	14.22-1
14.22.2	RADIOLOGICAL CONSEQUENCES .....	14.22-1
14.22.2.1	Analysis Method.....	14.22-1
14.22.2.2	Bounding Event Input.....	14.22-2
14.22.2.3	Analysis of Results .....	14.22-2
14.22.3	CONCLUSION.....	14.22-2
14.23	RADIOLOGICAL CONSEQUENCES OF FAILURE OF SMALL LINES CARRYING PRIMARY COOLANT OUTSIDE CONTAINMENT.....	14.23-1
14.23.1	EVENT DESCRIPTION.....	14.23-1
14.23.2	THERMAL-HYDRAULIC ANALYSIS .....	14.23-1
14.23.3	RADIOLOGICAL CONSEQUENCES .....	14.23-1
14.23.3.1	Analysis Method.....	14.23-1
14.23.3.2	Bounding Event Input.....	14.23-1
14.23.3.3	Analysis of Results .....	14.23-2
14.23.4	CONCLUSIONS.....	14.23-2
14.24	CONTROL ROOM RADIOLOGICAL HABITABILITY.....	14.24-1
14.24.1	EVENT DESCRIPTION.....	14.24-1
14.24.2	THERMAL-HYDRAULIC ANALYSIS .....	14.24-1
14.24.3	RADIOLOGICAL CONSEQUENCES .....	14.24-1
14.24.3.1	Analysis Method.....	14.24-1
14.24.3.2	Bounding Event Input.....	14.24-3
14.24.3.3	Analysis of Results .....	14.24-3
14.24.4	CONCLUSION.....	14.24-3

## LIST OF TABLES

14.1-1	Specified Acceptable Fuel Design Limits
14.1-3	Trip Setpoints for Analysis of Palisades Reactor at 2,530 MWt
14.1-4	Disposition of Events Summary for Palisades Cycle 27
14.1-5	Cycle 27 Summary of Results for Standard Review Plan Chapter 15 Events
14.1-6	Summary of Radiological Consequences of the Chapter 14 Events
14.2.1-1	Event Summary For The Uncontrolled Bank Withdrawal From A Low Power Event
14.2.2-1	Event Summary For The Uncontrolled Rod Bank Withdrawal Event From Power
14.7.1-1	Event Summary For The Loss of Forced Reactor Coolant Flow
14.7.2-1	Event Summary For The Reactor Coolant Pump Rotor Seizure
14.10-1	Sequence of Events for Excess Load Limiting MDNBR Case
14.11-1	Postulated Cask Drop Accidents
14.11-2	Spent Fuel Cask Drop Radiological Analysis – Source Terms
14.11-3	Spent Fuel Cask Drop Radiological Analysis – Inputs and Assumptions
14.12-1	Event Summary For Loss of Load
14.13-1	Initial Conditions for the Loss of Normal Feedwater Analysis
14.13-2	Sequence of Events for Loss of Normal Feedwater Flow Analysis with Offsite Power Available and Steam Dump System Disabled
14.13-3	Sequence of Events for Loss of Normal Feedwater Flow Analysis with Offsite Power Available and Steam Dump System Available
14.13-4	Sequence of Events for Loss of Normal Feedwater Flow Analysis without Offsite Power Available and Steam Dump System Disabled
14.13-5	Results Summary for Loss of Normal Feedwater
14.14-1	Main Steam Line Break Input Parameters and Assumptions
14.14-2	Steam Line Break Sequence of Events During LHR-Limiting Transient (HZP, Offsite Power Available)
14.14-3	Overall Core Conditions at Time of Peak LHR
14.14-4	Steam Line Break Sequence of Events During DNBR-Limiting Transient (HZP, Loss of Offsite Power)
14.14-5	Overall Core Conditions at Time of MDNBR
14.14-6	Main Steam Line Break (MSLB) Radiological Analysis – Inputs and Assumptions
14.14-7	Main Steam Line Break (MSLB) Radiological Analysis – Intact SG Steam Release Rate
14.15-1	Initial Conditions For The Steam Generator Tube Rupture With A Loss Of Offsite Power
14.15-2	Setpoints For The Steam Generator Tube Rupture With A Loss Of Offsite Power
14.15-3	Sequence Of Events For The Steam Generator Tube Rupture With A Loss Of Offsite Power
14.15-4	Integrated Parameters For The Steam Generator Tube Rupture With A Loss Of Offsite Power

14.15-5	Steam Generator Tube Rupture (SGTR) Radiological Analysis – Inputs and Assumptions
14.15-6	SGTR Radiological Analysis – Integrated Mass Releases
14.15-7	SGTR Radiological Analysis – Flashing Fraction for Flow From Broken Tube
14.18-8	SGTR Radiological Analysis – 40 $\mu\text{Ci/gm}$ D.E. I-131 Activities
14.15.9	SGTR Radiological Analysis – Iodine Equilibrium Appearance Assumptions
14.15-10	SGTR Radiological Analysis – Concurrent (335 x) Iodine Spike Appearance Rate
14.15-11	SGTR Radiological Analysis – Affected Steam Generator Water Level and Decontamination Factors for Flashed Flow
14.16-1	Event Summary For The EOC HZP Control Rod Ejection
14.16-2	Control Rod Ejection Radiological Analysis – Inputs and Assumptions
14.16-3	Control Rod Ejection Radiological Analysis – Steam Release
14.17.1-1	Sampled LBLOCA Parameters
14.17.1-2	Plant Operating Range Supported by the LOCA Analysis
14.17.1-3	Statistical Distributions Used for Process Parameters
14.17.1-4	Summary of Major Parameters for the Limiting PCT Case
14.17.1-5	Summary of Hot Rod Limiting PCT Results
14.17.1-6	Calculated Event Times for the Limiting PCT Case
14.17.1-7	Containment Heat Sink Data
14.17.1-8	Containment Initial and Boundary Conditions
14.17.2-1	System Parameters and Initial Conditions Used in the Palisades SBLOCA Analysis
14.17.2-2	PCT Results of the Palisades SBLOCA Analysis
14.17.2-3	Sequence of Events for the Palisades SBLOCA Event
14.17.2-4	SBLOCA Analysis Calculation Results
14.17.3-1	Maximum Stresses, Pressures and Deflections in Critical Reactor Internals Following a Major Loss of Coolant Accident
14.17.3-2	Asymmetric Loads Analysis - Reactor Vessel Internal Component Stress Margins
14.18.1-1	LOCA Analysis Containment Building Heat Sinks/Sources
14.18.1-2	LOCA Analysis Engineered Safeguards Equipment Alignment
14.18.1-3	LOCA Initial Conditions
14.18.1-4	Containment Building Response to LOCA Double Ended Guillotine Break in a Hot Leg
14.18.1-5	LOCA Analysis Parameter Assumptions
14.18.2-1	Initial Conditions For The MSLB Containment Analysis
14.18.2-2	Initial Conditions For The MSLB Containment Analysis
14.18.2-3	MSLB Containment Analysis Results
14.18.2-4	MSLB Analysis Containment Building Heat Sinks/Sources
14.18.3-1	Reactor Cavity Geometric Factors
14.18.3-2	Geometry and Peak Pressures in Steam Generator Compartments
14.18.3-3	Differential Pressures at Various Locations
14.19-1	Fuel Handling Accident (FHA) Radiological Analysis – Inputs and Assumptions

14.19-2	Fuel Handling Accident Radiological Analysis – Source Term
14.22-1	MHA Sequence of Events for the Dose Consequence Analysis
14.22-2	Maximum Hypothetical Accident / Loss of Coolant Accident (MHA/LOCA) Radiological Analysis – Inputs and Assumptions
14.22-3	MHA/LOCA Source Term
14.22-4	MHA/LOCA Release Phases
14.22-5	MHA/LOCA Time Dependent SIRWT pH
14.22-6	MHA/LOCA Time Dependent SIRWT Total Iodine Concentration
14.22-7	MHA/LOCA Time Dependent SIRWT Liquid Temperature
14.22-8	MHA/LOCA Time Dependent SIRWT Elemental Iodine Fraction
14.22-9	MHA/LOCA Time Dependent SIRWT Partition Coefficient
14.22-10	MHA/LOCA Adjusted Release Rate from SIRWT
14.23-1	Small Line Break Outside of Containment Radiological Analysis – Inputs and Assumptions
14.23-2	Small Line Break Outside of Containment Radiological Analysis – Concurrent (500 x) Iodine Spike Appearance Rate
14.24-1	Time Dependent Control Room Parameters
14.24-2	Control Room Atmospheric Dispersion (X/Q) Factors for AST Analysis Events
14.24-3	Release-Receptor Point Pairs Assumed for AST Analysis Events

#### **LIST OF FIGURES**

14.1-3	Palisades Scram Curve
14.2.1-1	Control Rod Withdrawal Incident HZP Reactivity Insertion Curve
14.2.1-2	Control Rod Withdrawal Incident HZP Reactivity Feedbacks
14.2.1-3	Control Rod Withdrawal Incident HZP Total Reactivity
14.2.1-4	Control Rod Withdrawal Incident HZP Power and Heat Flux
14.2.1-5	Control Rod Withdrawal Incident HZP System Pressure
14.2.1-6	Control Rod Withdrawal Incident HZP Inlet Enthalpy
14.2.2-1	Reactivities For Uncontrolled bank Withdrawal At Full Power
14.2.2-2	Reactor Power Level For Uncontrolled Bank Withdrawal Full Power
14.2.2-3	Core Average Heat Flux For Uncontrolled Bank Withdrawal At Full Power
14.2.2-4	Pressurizer Pressure For Uncontrolled Bank Withdrawal At Full Power
14.2.2-5	Pressurizer Liquid Level For Uncontrolled Bank Withdrawal At Full Power
14.2.2-6	PCS Mass Flow Rate For Uncontrolled Bank Withdrawal At Full Power
14.2.2-7	PCS Temperatures For Uncontrolled Bank Withdrawal At Full Power
14.2.2-8	Secondary Pressure For Uncontrolled Bank Withdrawal At Full Power
14.2.2-9	S/G Liquid Level For Uncontrolled Bank Withdrawal At Full Power
14.7.1-1	Primary Coolant System Mass Flow Rate For Loss Of Forced Flow
14.7.1-2	Reactor Power Level For Loss Of Forced Flow
14.7.1-3	Core Average Heat Flux For Loss Of Forced Flow
14.7.1-4	Pressurizer Pressure For Loss Of Forced Flow
14.7.1-5	Primary Coolant System Temperatures For Loss Of Forced Flow
14.7.2-1	Primary Coolant System Mass Flow Rate For Reactor Coolant Pump Rotor Seizure
14.7.2-2	Reactor Power Level For Reactor Coolant Pump Rotor Seizure
14.7.2-3	Core Average Heat Flux For Reactor Coolant Pump Rotor Seizure
14.7.2-4	Pressurizer Pressure For Reactor Coolant Pump Rotor Seizure

14.7.2-5	Primary Coolant System Temperatures For Reactor Coolant Pump Rotor Seizure
14.10-1	Power Comparisons – Excess Load
14.10-2	Primary Coolant System Temperatures - Excess Load
14.10-3	Pressurizer Pressure - Excess Load
14.10-4	Pressurizer Collapsed Liquid Level - Excess Load
14.10-5	Components of Reactivity – Excess Load
14.11-1	Partial Operating Floor Plan EL 649'-0"
14.12-1	Reactor Power Level For Loss Of External Load Event
14.12-2	Primary Pressures For Loss Of External Load Event
14.12-3	Pressurizer Liquid Volume For Loss Of External Load Event
14.12-4	Primary Coolant System Temperatures For Loss Of External Load Event
14.12-5	Secondary Pressures For Loss Of External Load Event
14.13-1	Reactor Power, LNFF with Offsite Power Available and Steam Dump System Disabled
14.13-2	Primary Coolant System Loop Temperatures, LNFF with Offsite Power Available and Steam Dump System Disabled
14.13-3	Primary Coolant System Loop Flow, LNFF with Offsite Power Available and Steam Dump System Disabled
14.13-4	Pressurizer Pressure, LNFF with Offsite Power Available and Steam Dump System Disabled
14.13-5	Pressurizer Spray Flow, LNFF with Offsite Power Available and Steam Dump System Disabled
14.13-6	Pressurizer SRV Flow, LNFF with Offsite Power Available and Steam Dump System Disabled
14.13-7	Pressurizer Level, LNFF with Offsite Power Available and Steam Dump System Disabled
14.13-8	SG Auxiliary Feedwater Flow, LNFF Analysis with Off-Site Power Available and Steam Dump System Disabled
14.13-9	SG Dome Pressure, LNFF Analysis with Off-Site Power Available and Steam Dump System Disabled
14.13-10	SG Liquid Mass Inventory, LNFF Analysis with Off-Site Power Available and Steam Dump System Disabled
14.13-11	Reactor Power, LNFF Analysis with Off-Site Power Available and Steam Dump System Available
14.13-12	Primary Coolant System Loop Temperatures, LNFF Analysis with Off-Site Power Available and Steam Dump System Available
14.13-13	Primary Coolant System Loop Flow, LNFF Analysis with Off-Site Power Available and Steam Dump System Available
14.13-14	Pressurizer Pressure, LNFF Analysis with Off-Site Power Available and Steam Dump System Available
14.13-15	Pressurizer Spray Flow, LNFF Analysis with Off-Site Power Available and Steam Dump System Available
14.13-16	Pressurizer SRV Flow, LNFF Analysis with Off-Site Power Available and Steam Dump System Available
14.13-17	Pressurizer Level, LNFF Analysis with Off-Site Power Available and Steam Dump System Available
14.13-18	SG Auxiliary Feedwater Flow, LNFF Analysis with Off-Site Power Available and Steam Dump System Available

14.13-19	SG Dome Pressure, LNFF Analysis with Off-Site Power Available and Steam Dump System Available
14.13-20	SG Liquid Mass Inventory, LNFF Analysis with Off-Site Power Available and Steam Dump System Available
14.13-21	Reactor Power, LNFF Analysis without Off-Site Power Available and Steam Dump Systems Disabled
14.13-22	Primary Coolant System Loop Temperatures, LNFF Analysis without Off-Site Power Available and Steam Dump Systems Disabled
14.13-23	Primary Coolant System Loop Flow, LNFF Analysis without Off-Site Power Available and Steam Dump Systems Disabled
14.13-24	Pressurizer Pressure, LNFF Analysis without Off-Site Power Available and Steam Dump Systems Disabled
14.13-25	Pressurizer Level, LNFF Analysis without Off-Site Power Available and Steam Dump Systems Disabled
14.13-26	SG Auxiliary Feedwater Flow, LNFF Analysis without Off-Site Power Available and Steam Dump Systems Disabled
14.13-27	SG Dome Pressure, LNFF Analysis without Off-Site Power Available and Steam Dump Systems Disabled
14.13-28	SG Liquid Mass Inventory, LNFF Analysis without Off-Site Power Available and Steam Dump Systems Disabled
14.14-1	Break Flow Rates During LHR-Limiting Transient
14.14-2	Steam Generator Pressures During LHR-Limiting Transient
14.14-3	Steam Generator Heat Transfer Rates During LHR-Limiting Transient
14.14-4	Steam Generator Secondary-Side Total Fluid Inventories During LHR-Limiting Transient
14.14-5	Core Inlet Temperatures During LHR-Limiting Transient
14.14-6	Core Inlet Flow Rates During LHR-Limiting Transient
14.14-7	Pressurizer Pressure During LHR-Limiting Transient
14.14-8	Pressurizer Liquid Level During LHR-Limiting Transient
14.14-9	Total HPSI Flow Rate During LHR-Limiting Transient
14.14-10	Reactivity During LHR-Limiting Transient
14.14-11	Reactor Power During LHR-Limiting Transient
14.14-12	Break Flow Rates During DNBR-Limiting Transient
14.14-13	Steam Generator Pressures During DNBR-Limiting Transient
14.14-14	Steam Generator Heat Transfer Rates During DNBR-Limiting Transient
14.14-15	Steam Generator Secondary-Side Total Fluid Inventories During DNBR-Limiting Transient
14.14-16	Core Inlet Temperatures During DNBR-Limiting Transient
14.14-17	Core Inlet Flow Rates During DNBR-Limiting Transient
14.14-18	Pressurizer Pressure During DNBR-Limiting Transient
14.14-19	Pressurizer Liquid Level During DNBR-Limiting Transient
14.14-20	Total HPSI Flow Rate During DNBR-Limiting Transient
14.14-21	Reactivity During DNBR-Limiting Transient
14.14-22	Reactor Power During DNBR-Limiting Transient
14.15-1	SGTR With LOAC: Core Power vs Time
14.15-2	SGTR With LOAC: Core Coolant Temperatures vs Time
14.15-3	SGTR With LOAC: Primary Coolant System Pressure vs Time
14.15-4	SGTR With LOAC: Steam Generator Pressure vs Time
14.15-5	SGTR With LOAC: Tube Leak Flow Rate vs Time

14.15-6	SGTR With LOAC: Integrated Tube Leak Flow vs Time
14.15-7	SGTR With LOAC: Pressurizer Liquid Volume vs Time
14.15-8	SGTR With LOAC: Affected Steam Generator Safety Valve (MSSV) Flow Rate vs Time
14.15-9	SGTR With LOAC: Affected Steam Generator Safety Valve (MSSV) Integrated Flow vs Time
14.15-10	SGTR With LOAC: Steam Generators Liquid Mass vs Time
14.15-11	SGTR With LOAC: Core Power vs Time
14.15-12	SGTR With LOAC: Core Coolant Temperatures vs Time
14.15-13	SGTR With LOAC: Primary Coolant System Pressure vs Time
14.15-14	SGTR With LOAC: Steam Generators Pressure vs Time
14.15-15	SGTR With LOAC: Pressurizer Liquid Volume vs Time
14.15-16	SGTR With LOAC: Tube Leak Flow Rate vs Time
14.15-17	SGTR Integrated Leak Flow vs Time
14.15-18	SGTR ADV Flow Rate vs Time
14.15-19	SGTR Integrated ADV Flow vs Time
14.15-20	SGTR PCS Subcooling vs Time
14.15-21	SGTR HPSI Flow Rate vs Time
14.16-1	Control Rod Ejection, EOC HZP Case: Core Power
14.16-2	Control Rod Ejection, EOC HZP Case: Core Average Heat-Flux-Based LHR
14.16-3	Control Rod Ejection, EOC HZP Case: Total Core Reactivity
14.17.1-1	Scatter Plot of Operational Parameters
14.17.1-2	PCT Versus PCT Time Scatter Plot From Transient Calculations
14.17.1-3	PCT Versus Break Size Scatter Plot From Transient Calculations
14.17.1-4	Total Oxidation Vs. PCT Scatter Plot from Transient Calculations
14.17.1-5	Maximum Oxidation Versus PCT Scatter Plot from Transient Calculations
14.17.1-6	Peak Cladding Temperature for the Limiting Case
14.17.1-7	Break Flow for the Limiting Case
14.17.1-8	Core Inlet Mass Flux for the Limiting Case
14.17.1-9	Core Outlet Mass Flux for the Limiting Case
14.17.1-10	Void Fraction at PCS Pumps for the Limiting Case
14.17.1-11	ECCS Flows (Includes SIT, HPSI, and LPSI) for the Limiting Case
14.17.1-12	Upper Plenum Pressure for the Limiting Case
14.17.1-13	Collapsed Liquid Level in the Downcomer for the Limiting Case
14.17.1-14	Collapsed Liquid Level in the Lower Plenum for the Limiting Case
14.17.1-15	Collapsed Liquid Level in the Core for the Limiting Case
14.17.1-16	Containment and Loop Pressures for the Limiting Case
14.17.1-17	Deleted
14.17.1-18	Deleted
14.17.1-19	Deleted
14.17.1-20	Deleted
14.17.1-21	Deleted
14.17.2-1	Break Mass Flow Rate (Limiting Case)
14.17.2-2	Primary and Secondary Pressures (Limiting Case)
14.17.2-3	Normalized Reactor Power (Limiting Case)
14.17.2-4	Total HPSI Mass Flow Rate (Limiting Case)
14.17.2-5	Total SIT Mass Flow Rate (Limiting Case)
14.17.2-6	Loop Seal Void Fractions (Limiting Case)

14.17.2-7	Break Void Fraction (Limiting Case)
14.17.2-8	Reactor Vessel and PCS Mass Inventories (Limiting Case)
14.17.2-9	Hot Channel Collapsed Level (Limiting Case)
14.17.2-10	Fluid and Cladding Temperatures (Limiting Case)
14.17.2-11	SG Narrow Range Liquid Levels (Limiting Case)
14.17.2-12	AFW Flow Rates (Limiting Case)
14.17.2-13	Total MSSV Flow (Limiting Case)
14.18.1-1	LOCA Containment Pressure Profile
14.18.1-2	LOCA Containment Temperature Profile
14.18.2-1	MSLB Containment Response Maximum Pressure Profile
14.18.2-2	MSLB Containment Response Environmental Qualification Profile
14.22-1	Deleted
14.22-2	Deleted



**SECTIONS**

15.1	<b><u>QUALITY ASSURANCE DURING THE OPERATIONAL PHASE</u></b> .....	15.1-1
	15.1.1 <b><u>QUALITY ASSURANCE PROGRAM MANUAL</u></b> .....	15.1-1
	15.1.2 <b><u>GENERIC QUALITY ASSURANCE REQUIREMENTS FOR</u></b> <b><u>AGING MANAGEMENT PROGRAMS</u></b> .....	15.1-2
15.2	<b><u>QUALITY ASSURANCE DURING ORIGINAL PLANT DESIGN</u></b> <b><u>AND CONSTRUCTION</u></b> .....	15.2-1
	15.2.1 <b><u>BECHTEL CORPORATION</u></b> .....	15.2-1
	15.2.1.1 <b><u>General</u></b> .....	15.2-1
	15.2.1.2 <b><u>Organization</u></b> .....	15.2-1
	15.2.2 <b><u>COMBUSTION ENGINEERING, INC</u></b> .....	15.2-2
	15.2.2.1 <b><u>General</u></b> .....	15.2-2
	15.2.2.2 <b><u>Organization</u></b> .....	15.2-3
	15.2.2.3 <b><u>Responsibilities</u></b> .....	15.2-4
	15.2.3 <b><u>CONSUMERS POWER COMPANY</u></b> .....	15.2-5
	15.2.3.1 <b><u>General</u></b> .....	15.2-5
	15.2.3.2 <b><u>Vendor Shops</u></b> .....	15.2-5
	15.2.3.3 <b><u>Nuclear Fuel</u></b> .....	15.2-7
	15.2.3.4 <b><u>Construction Activities</u></b> .....	15.2-8

**REFERENCES**..... None

**TABLES**..... None

**LIST OF FIGURES**

- 15-1      Quality Assurance Organization**
- 15-2      Combustion Engineering Incorporated Quality Assurance Organization**