


ck
SP

STEAM GENERATOR CREVICE FLOW TEST



for
Wisconsin Electric Power Company

Test Report
TR-ESE-411

CE POWER
SYSTEMS
COMBUSTION ENGINEERING, INC

8103090384

LEGAL NOTICE

THIS REPORT WAS PREPARED AS AN ACCOUNT OF WORK SPONSORED BY COMBUSTION ENGINEERING, INC. NEITHER COMBUSTION ENGINEERING NOR ANY PERSON ACTING ON ITS BEHALF:

A. MAKES ANY WARRANTY OR REPRESENTATION, EXPRESS OR IMPLIED INCLUDING THE WARRANTIES OF FITNESS FOR A PARTICULAR PURPOSE OR MERCHANTABILITY, WITH RESPECT TO THE ACCURACY, COMPLETENESS, OR USEFULNESS OF THE INFORMATION CONTAINED IN THIS REPORT, OR THAT THE USE OF ANY INFORMATION, APPARATUS, METHOD, OR PROCESS DISCLOSED IN THIS REPORT MAY NOT INFRINGE PRIVATELY OWNED RIGHTS; OR

B. ASSUMES ANY LIABILITIES WITH RESPECT TO THE USE OF, OR FOR DAMAGES RESULTING FROM THE USE OF, ANY INFORMATION, APPARATUS, METHOD OR PROCESS DISCLOSED IN THIS REPORT.

COMBUSTION ENGINEERING
DEVELOPMENT DEPARTMENT

TEST REPORT

STEAM GENERATOR TUBESHEET
CREVICE FLOW TEST

FOR

WISCONSIN ELECTRIC POWER COMPANY

CONTRACT NUMBER

14980

PREPARED BY: M. P. Chaplin
M. P. Chaplin

APPROVED BY: C. M. Rutz

REVIEWED BY: H. N. Gierman

DOCUMENT NO.: TR-ESE-411

DATE OF ISSUE: 1-15-1981

The information contained in this document
has been reviewed and satisfies the
applicable items contained on Checklist
No. 4 of the QADM.

Reviewer H. N. Gierman

Date Jan 15, 1981

The information contained in this report No. TR-ESE-411 is certified to be an accurate account of information obtained by performance of the tests, inspections or other objectives described herein.

Certified by: *C M Ross* Date: 1-15-51
Laboratory Manager

TABLE OF CONTENTS

<u>SECTION</u>	<u>TITLE</u>	<u>PAGE NO.</u>
1.0	Introduction	1
2.0	Summary	1
3.0	Details of Test Hardware	2
3.1	Test Setup	2
3.2	Instrumentation	2
3.2.1	Pressure Gages	4
3.2.2	Thermocouples	4
3.2.3	Flow	4
3.3	Test Section	5
3.4	Test Specimens	5
4.0	Discussion	5
4.1	Testing	5
4.2	Observations	7
5.0	Conclusions	11
APPENDIX A	Test Procedure	A1
APPENDIX B	Instrumentation Error Analysis	B1
APPENDIX C	Calculations	C1
APPENDIX D	Comparison of Flow Rates	D1
APPENDIX E	Data Sheets	E1

LIST OF FIGURES

<u>FIGURE NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
1	Test Facility Setup	3
2	Test Section Instrumentation	6
3	Test Facility Photo	10
4	Test Section Photo	12
5	Flow Curve Tube 2A	14
6	Flow Curve Tube 3A	15
7	Flow Curve Tube 4A	16
8	Flow Curve Tube 5A	17
9	Flow Curve Tube 6A	18
10	Flow Curve Tube 7A	19
11	Flow Curve Tube 8A	20
12	Flow Curve Tube 9A	21
13	Flow vs. Defect Location	22
14	Discharge Pressure vs. Flow Rate	23
15	Defect Area vs. Flow Rate	24
16	Defect Area Tube 2A	25
17	Defect Area Tube 3A	25
18	Defect Area Tube 4A	25
19	Defect Area Tube 5A	25
20	Defect Area Tube 6A	26
21	Defect Area Tube 7A	26
22	Defect Area Tube 8A	26
23	Defect Area Tube 9A	26

LIST OF TABLES

<u>TABLE NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
1	Steam Generator Crevice Leak Test Test Data Summary	13

1.0 INTRODUCTION

The Point Beach Nuclear Plant Unit 1 steam generators have experienced intergranular attack of the tubes in the tubesheet crevice area. A test program was undertaken to evaluate the potential rate of secondary leakage through simulated defective steam generator tubes in the tubesheet crevice.

This report details the testing which was performed to determine the secondary to primary leakage rate through tubes with simulated defects at various locations within the tubesheet crevice. All tests were performed with a nominal secondary side pressure of 1000 psig.

2.0 SUMMARY

The following summarizes the results of tests completed to determine flow characteristics through defective steam generator tubes during a postulated loss of primary pressure accident.

1. Nineteen tests were completed on samples having defects ranging from a .01 inch diameter hole to a .01" by 3 inch long slit.
2. The maximum steady state secondary to primary flow of 1460 lb/hr. was obtained with the .01 inch by 1/2 inch defect.
3. Defects greater than 1/2 inch long were found to reduce in size during test due to external pressure which caused deformation of the tube.
4. Flow is affected by primary side back pressure. Increasing the back pressure close to the saturation pressure resulted in a maximum flow that was almost twice as large as that obtained under maximum differential pressure.

5. Small defects yielded the maximum flow per unit area. Values ranged from 930,000 lbs. per hour per square inch for the .01 inch diameter hole to 46,000 lbs. per hour per square inch for the largest defect area tested.
6. An instrument error analysis showed that all tests were run with the test water entering the simulated tubesheet crevice in the liquid subcooled state.
7. Defects located 12 inches to 18 inches below the top of the tubesheet have leakage rates approximately 30% less than those located 5/8 inches below the top of the tubesheet.

3.0 DETAILS OF TEST HARDWARE

3.1 Test Facility Setup

The test facility is shown in Figure 1 and was assembled utilizing a 70 gallon autoclave with a nitrogen overpressure to provide a source of demineralized water at 550°F and a pressure of 1065 psig.

The system piping was 3/4 inch stainless steel tubing. Connectors and valves were 3/4 inch Swagelok. The discharge valve was a 1 1/2 inch fast-acting valve connected to an atmospheric drain line.

3.2 Instrumentation

All instrumentation was calibrated prior to and at the completion of the test. Instrumentation error analysis and calibration data are included as Appendix B.




Figure 1
TEST FACILITY SETUP

3.2.1 Pressure Gages

Pressure gages were installed in the autoclave (P_1), tubesheet inlet (P_2) and upstream of the discharge valve (P_3).

3.2.2 Thermocouples

Thermocouples were installed in the autoclave (T_1), tubesheet inlet (T_2), tubesheet I.D. (T_3), and inside the tube adjacent to the defect (T_4). The thermocouples were connected to a digital readout.

3.2.3 Flow

A Meriam ΔP gage was connected to a Flow-Dyne venturi flow meter with a 0.1985 inch throat diameter. Connected in parallel to the venturi was a Rosemont ΔP Transmitter and a Honeywell 1508A visicorder. This system provided both a visual and permanent record of flow.

For backup flow data, the autoclave level was monitored. The level was measured using a Rosemont ΔP transmitter connected to a meter. Using a stopwatch and the level indication, the flow per unit time could be established.

As the level instrumentation had been calibrated at 68°F , the calculation in Appendix C was used to determine the 550°F flow rate. Flow rates for the 0.010 inch hole defect were obtained solely by the autoclave level vs. time method.

3.3 Test Section

A 2 1/2 inch diameter carbon steel round was gun drilled to $0.892 \pm .001$ inches I.D. to simulate the tubesheet (Figure 2). Instrument taps and a vent tap were drilled perpendicular to the I.D. In addition, a tube deflection device was installed to deflect the test tube against the tubesheet I.D. to provide the maximum clearance area at the tube defect.

Eight strip heaters (of 250 watts each) were utilized to provide heat to the test section and inlet plenum. The test section temperature was stabilized at 600°F prior to initiation of the blowdown.

3.4 Test Specimens

The simulated steam generator tubes (Figures 15 through 22) were fabricated from 7/8 inch O.D. 316 stainless steel welded seam tubing. The tubes were cut to 24" in length and a plug welded into one end; they were then centerless ground to $0.872 \pm .001$ inches. Tube defects, with the exception of the 0.040 inch hole (3A) and the 0.010 X .500 inch slit (2A), were installed using Electron Discharge machining.

The tubes were installed in the test section (tubesheet) using Swagelok fittings. Defect positioning within the tubesheet crevice was measured to $\pm 1/16$ inches.

4.0 DISCUSSION

4.1 Testing

The test tubes were installed in the simulated tubesheet and




Figure 2
 TEST SECTION INSTRUMENTATION
 (SIMULATED TUBESHEET)

the defect location fixed. The tube was deflected to contact the tubesheet opposite the defect to allow maximum flow area at the defect. The system was heated and pressurized from the autoclave through the specimen tube up to the discharge valve. Upon reaching test conditions, the system was rapidly depressurized by opening the discharge valve. Temperature, flow and pressure were recorded before, during, and after blowdown.

An instrument error analysis (Appendix B) showed that all tests were run with the test water entering the simulated tubesheet crevice in the liquid subcooled state.

The testing was performed in accordance with Test Procedure 00000-ESE-298, "Wisconsin Electric Power Steam Generator Tubesheet Crevice Test", (Appendix A).

4.2 Observations

A total of 19 blowdown tests were performed using 9 tubes with various defects. Tests 1 through 12 and 17 through 19 were performed with the defect located 5/8 in. from the top of the tubesheet. Tests 13 through 16 were performed with the defect located 12 and 18 inches into the tubesheet. Flows with the defect located at these levels were, respectively, 590 and 500 lbs. per hour less than those with the defect located 5/8 in. into the tubesheet. See Figure 12. Flow rates for the other defects are displayed in Figures 5 through 11.

The flow rates during the initial ten seconds of each test were higher than those after test stabilization although significantly higher (50-100% higher) only for the first two (2) seconds. This corresponded to a freely discharging submerged flow condition as

the valve was being opened and the back pressure in the test section was being reduced to atmospheric pressure. As the internal tube back pressure decreased and vaporization across the defect was established, flow rates stabilized at significantly lower values.

Tube deformation at the simulated defect was noted in most of the tubes after test. Tube S/N 4A defect was measured prior to installation at .010 x 1.00 inches. The tube was then installed and brought to test conditions (550°F 1075 psig) and stabilized for 30 minutes. The I.D. of the tube was not depressurized, thus no differential pressure was established. The tube was cooled and reinspected. No change in tube diameter or defect area was noted. The tube was then tested normally, after which test measurements disclosed a reduction in the defect area of about .005 in² due to tube deformation during flow testing. It was thus verified that the defect reduction was due to the external pressure caused by the depressurization rather than thermal effects.

Figure 15 and Table 1 provide a correlation of the stabilized flow per unit area versus defect area after test. A trend seems to be established that the larger defects have lower flow per unit area than the small defects.

The measured flow rates and the defect size effect can be correlated by equations for critical flow through orifices. These correlations are provided in Appendix D. For initially subcooled water, Zaloudek (Ref. 1) found that a choking condition occurs at the orifice throat corresponding to the situation when the local pressure reaches the saturation pressure. This is referred to as upstream choking which is characterized by flow consisting

of a liquid core surrounded by a vapor annulus. The flow through the orifice remains constant even with further decreases in the back pressure.

This critical flow, G_1 , is given by:

$$G_1 = C_1 \sqrt{2 g c \rho_1 (P_{\text{upstream}} - P_{\text{sat}})} \quad (1)$$

where C_1 is a coefficient of discharge, ρ_1 is saturated water density, P_{upstream} is pressure upstream of orifice, and P_{sat} is saturation pressure at subcooled liquid temperature.

For highly metastable flow, the superheated liquid does not have time to flash and establish thermodynamic equilibrium. In this instance, the liquid flashes downstream of the orifice leading to a second critical flow situation. The value of this critical flow is determined from the data of Burnell as,

$$G_2 = \sqrt{2 g c \rho_1 [P_{\text{ups.}} - (1-C_2) P_{\text{sat}}]} \quad (2)$$

where C_2 is a function of the surface tension.

Comparison of the measured flow rates with the predicted values by Eqs. 1 and 2 (Appendix D) showed that the flow rates for the smaller size defects corresponded to G_2 and those of the large defects corresponded to G_1 . It is thus apparent that with the smaller flow areas (0.010" hole up to 0.10" x 0.50" slit), surface tension has a strong effect in suppressing flashing and metastable conditions are more apt to occur. Conversely, thermodynamic equilibrium is reached with the larger flow areas. The agreement between predicted and measured values is close (± 15 to ± 27 percent) except for the 0.010" hole and the longest slits.

Increasing the upstream pressure for Tube 2A (Runs 3 & 5) created only a small increase in flow (< 1% increase). This trend is also predicted by Eq. 2; a much larger increase is predicted by Eq. 1. This supports the conclusion of downstream choking for this tube.

Figure 13 shows the effect of back pressure on flow for Tube 5A. In this test, stabilized flow conditions were first established with the back pressure set at atmospheric conditions. The isolation valve was then slowly closed to increase the back pressure. When the back pressure reached a value in the vicinity of the saturation pressure (1003 psia), the flow reached a maximum, a factor 1.8 greater than stabilized flow rate, after which, with further increase in back pressure, the flow decreased to zero corresponding to a decreasing differential pressure as in single phase flow. Due to the difficulty of obtaining steady values of flow under high back pressures, the flow versus back pressure data of Figure 13 represent quasi-steady state values. However, the maximum flow reached can be compared to the maximum theoretically possible. Since Eq. 1 applies for Tube 5A, increasing the back pressure would propagate this pressure increase back towards the orifice and cause the local static pressure to exceed the saturation pressure. Consequently, the choking condition would be removed, and the flow would be increased by the increase of the discharge coefficient to the single phase value (i.e., 0.62 to 1.0 or a factor of 1.6). This provides an explanation of the increase in flow rate.

Two test runs were made to assess the effect of tube clearance within the simulated tubesheet. Runs 18 and 19, using the .01 by .5 inch long defect located 5/8 inches from the top, were placed undeflected in the test section. Leakage rates were

generally lower than those obtained with the maximum clearance runs but only by a small percentage, approximately 3%. Since other parameters, such as inlet temperature and pressure have a much larger effect, it is concluded that tube excentricity within the clearances tested does not significantly affect the leakage rates reported.


The test simulated a single tube and the adjacent tubesheet material. In an operational situation, unless adjacent tubes were also leaking, a larger heat source would be available thus maintaining a higher discharge/tubesheet temperature. This would tend to decrease the tube leak rate.

5.0 CONCLUSIONS


Based on the test data, it can be seen that the smaller defects yield larger leak rates per unit area. The maximum leak rate per unit area was obtained with the .01 inch diameter hole which yielded about 930,000 lbs. per hour per square inch. The measured leak rates can be correlated to previous data for critical flow in orifices based on upstream choking for the larger defect areas and downstream choking for the smaller defect areas.

An increased leak rate was observed when the simulated steam generator tube was internally pressurized to near saturation pressure of the water. The magnitude of this increase for large defects was twice that found while discharging at maximum ΔP .

With large defects, 12 inches to 18 inches from the top of the tubesheet, leak rates were reduced as much as 30%. Concentricity of the tube within the tubesheet crevice had minimal effect.



STEAM GENERATOR CREVICE LEAK RATE TEST FACILITY
FIGURE NO. 3



TEST SECTION - INSULATION REMOVED
FIGURE NO. 4

Table 1

TUBE		DEFECT		PRESSURE		TEMPERATURE		LEAK RATE				MINIMUM DEFECT WIDTH AFTER TEST	DEFECT AREA (IN ²)
RUN NO.	SERIAL NO.	SIZE (IN)	LOCATION	P ₁	P ₂	T ₁	T ₂	AUTOCLAVE †		CALCULATED ††			
								GPM	LB/HR	GPM F ₁	LB/HR		
1	2A	.010 x .500	5/8"	1075	1050	541	219	3.5	1300	3.8	1390	.0115"	.00595
2	2A	.010 x .500	5/8"	1050	1025	534	222	3.8	1400	3.9	1420	.0115"	.00595
3	2A	.010 x .500	5/8"	1160	1125	546	217	3.6	1325	4.1	1500	.0115"	.00595
4	2A	.010 x .500	5/8"	1080	1050	541	242	3.3	1225	3.7	1370	.0115"	.00595
5	2A	.010 x .500	5/8"	1075	1040	547	241	4.0	1475	3.7	1370	.0115"	.00595
6	2A	.010 x .500	5/8"	1050	1025	545	242	4.0	1475	3.5	1280	.0115"	.00595
7	3A	.040 Dia.	1/2"	1100	1060	541	214	.9	325	1.0	360	.040"	.00133
8	4A	.010 x 1.00	5/8"	1125	1090	543	220	1.3	475	1.6	580	.005"	.00625
9	4A	.010 x 1.00	5/8"	1100	1075	542	219	1.3	475	1.5	540	.005"	.00625
10	5A	.010 x 2.00	5/8"	1090	1050	546	244	1.4	525	1.8	670	.006"	.01419
11	5A	.010 x 2.00	5/8"	1100	1060	547	225	1.6	600	1.7	640	.006"	.01419
12	6A	.010 x 3.00	5/8"	1080	1050	547	238	2.1	775	2.3	840	.007"	.02861
13	8A	.010 x .500	12"	1090	1050	546	241	2.9	1075	2.6	970	.008"	.00486
14	8A	.010 x .500	12"	1090	1050	547	252	2.6	975	2.6	970	.008"	.00486
15	9A	.010 x .500	18"	1090	1050	545	242	2.1	775	2.4	880	.009"	.00556
16	9A	.010 x .500	18"	1090	1070	547	241	2.2	825	2.3	840	.009"	.00556
17	7A	.010 Dia.	5/8"	1100	1070	520	214	.1	37	—	—	.010"	3.96 x 10 ⁻⁵
18*	2A	.010 x .500	5/8"	1100	1040	547	250	3.3	1225	3.6	1330	.0115"	.00595
19*	2A	.010 x .500	5/8"	1090	1050	548	248	3.4	1250	3.6	1330	.0115"	.00595

* Tube not deflected within tubesheet


† Rounded to nearest 25-lb. increments (Run #17 - actual no.)

†† Rounded to nearest 10-lb. increments

TIME vs. FLOW RATE

TUBE ZA

- RUN 4
- RUN 5
- △ RUN 6
- DEFECT - .010" x .500"



TIME vs. FLOW RATE

TUBE No.
P.N. 7
DEFECT - .040" DIA. HOLE




Figure 6

TIME vs. FLOW RATE
FLOW RATE vs.

TUBE 4A
 O RUN 8
 □ RUN 7
 DEFECT - .0003 x 1.00"




Figure 7

TIME vs. FLOW RATE

TUBE 5A
○ RUN 10
□ RUN 11
DEFECT - .010" x 2.00"




Figure 8

TIME VS. FLOW RATE

TUBE 6A

RUN 12

DEFECT - .010" x 3.00"




Figure 9




Figure 10




Figure 11

TIME VS. FLOW RATE

TUBE 2A

- RUN 15
- RUN 16
DEFECT - 1/2" x .500" / 18" DOWN





Figure 12

FLOW vs. DEFECT LOCATION



SECONDS INTO BLOWDOWN

Figure 13




Figure 14

DEFECT AREA vs. MEAN STABILIZED FLOW RATE






Figure 15

FIGURE NO. 16




TUBE NO. 2A
.010" X .500" DEFECT/5/8" INTO TUBESHEET

FIGURE NO. 17




TUBE NO. 3A
.040" DIA. HOLE/1/2" INTO TUBESHEET

FIGURE NO. 18




TUBE NO. 4A
.010" X 1.00" DEFECT/5/8" INTO TUBESHEET

FIGURE NO. 19



TUBE NO. 5A
.010" X 2.00" DEFECT/5/8" INTO TUBESHEET

FIGURE NO. 20




TUBE NO. 6A
.010" X 3.00" DEFECT/5/8" INTO TUBESHEET

FIGURE NO. 21




TUBE NO. 7A
.010" X 1A HOLE/5/8" INTO TUBESHEET

FIGURE NO. 22



TUBE NO. 8A
.010" X 5.00" DEFECT/12" INTO TUBESHEET

FIGURE NO. 23



TUBE NO. 9A
.010" X 5.00" DEFECT/18" INTO TUBESHEET

STEAM GENERATOR CREVICE
FLOW TEST

APPENDIX A
TEST PROCEDURE

COMBUSTION ENGINEERING
DEVELOPMENT DEPARTMENT

TEST PROCEDURE

WISCONSIN ELECTRIC POWER STEAM GENERATOR
TUBESHEET CREVICE FLOW TEST

PO #59357

PREPARED BY: M. P. Chaplin
M. P. Chaplin

REVIEWED BY: C. M. Rous
Supervisor

APPROVED BY: J. E. Schuker
Lab. Manager

APPROVED BY: Gary Frieling
Gary Frieling

DOCUMENT NO.: 00000-ESE-298

DATE OF ISSUE: 8/25/80

1.0 OBJECTIVE

This procedure details tests to evaluate the potential rate of secondary leakage through simulated defective steam generator tubes in the event of a LOCA. The test section reflects the Point Beach Steam Generator Design in the support plate region.

2.0 TEST HARDWARE DESCRIPTION

The tests will be performed using a 70 gal. autoclave to provide fluid at the pressure and temperature required.

The test section, Figure 1, will be connected to the autoclave with insulated 3/4 tubing. A venturi will be located upstream of the test section for flow measurement, in addition, a fluid level indicator will be connected to the autoclave for volumetric comparison.

2.1 Test Section

The test section will consist of a 2" diameter carbon steel round, with a $0.892 \pm .002$ hole through the center to simulate the tubesheet. Attached to the tubesheet is a 4" section of 1 1/2" sch: 80 pipe which will provide a test fluid reservoir having pressure and temperature measurement capability adjacent to the tube being tested.

Strip heaters and a fluid bleed are provided to maintain a test section temperature of $600 \pm 10^{\circ}\text{F}$ prior to testing.*

Pressure gages and thermocouples will be provided at the tube sheet inlet and upstream of the 1 1/2" discharge valve. An additional TC will be located in the tubesheet adjacent to the test tube.

* To be adjusted per cognizant engineer.

2.2 Test Specimens

The test specimens will be fabricated from 7/8 O.D. x .049 wall welded tubing type 316. The tubes will be secured to the test section with swagelok fittings. Maximum tube to tubesheet eccentricity will be maintained during testing using a rod against the tube downstream of the tube defect (except for bottom defect). Eight 24" long tube sections will be fabricated with the top end plugged containing the following defects.

<u>Location</u>	<u>Defect</u>
1. 1" from plug	.010 diameter hole
2. 1" from plug	.010 x .250 Lg slit (.040 dia. hole)
3. 1" from plug	.010 x .500 Lg slit
4. 1" from plug	.010 x 1.00 Lg slit
5. 1" from plug	.010 x 2.00 Lg slit
6. 1" from plug	.010 x 3.00 Lg slit
7. Center of tubesheet	To be determined later
8. Bottom of tubesheet	To be determined later

2.3 Test Conditions

Ideal test conditions at the entrance to the tubesheet are 550°F at 1025 psia. By overcharging the autoclave by approximately 100 psi and using a Nitrogen overpressure a pressure of 1100 ± 10 psig at 550 ± 5°F should be possible. However, tests will be performed to determine the correct autoclave pressure that yields the closest possible test tubesheet inlet temperature 550 ± and pressure 1065 ± 10 psig.

The N₂ will be applied just prior to initiation of the test. The autoclave will be degassified prior to each additional test.

3.0 QUALITY CONTROL

Testing shall be performed and controlled in accordance with the applicable sections of the C-E Quality Assurance of Design Manual.

3.1 Instrumentation

3.1.1 Temperature - Thermocouples and readout instrumentation shall be calibrated prior to the test program and upon completion of the test program.

3.1.2 Pressure - All pressure gages and Δ pressure transmitters shall be calibrated prior to the test program and upon completion of the test program.

3.1.3 All instrumentation shall be calibrated per the procedure for Control of Measuring and Test Equipment Procedure No. 0000 NLE-070.

3.1.4 Pressure gages, thermocouples, level indicators, flow meters and valves will be identified per Table 1.

3.2 Error Analysis

The test report will provide an error analysis based on instrument calibration.

3.3 Records

The original data sheets and copies of the procedure and report will be filed in the Nuclear Laboratories Building 2 Records Room.

4.0 TEST SETUP

- 4.1 Log S/N and tube defect on data sheet.
- 4.2 Log defect location from top of the tubesheet on data sheet.
- 4.3 Utilizing the push rod deflect the tube against the tubesheet opposite the defect. Log on data sheet.
- 4.4 Tighten the swagelok fitting on the tubesheet.
- 4.5 Install the discharge test section and tighten the swagelok fitting.

5.0 TEST PROCEDURE

- 5.1 Fill the autoclave to the 72" level with demineralized water.
- 5.2 Start autoclave and stabilize at 550°F 1065 psig.
Utilize the tubesheet vent for venting operations as required.
- 5.3 Energize tubesheet heaters.
- 5.4 By venting through the tubesheet vent and using the tubesheet heaters, stabilize the tubesheet at 600 ± 10°F at T-3 1065 psig at P₂.
- 5.5 Set N₂ regulator at 1150 psig. Based on initial results the test engineer may change the N₂ regulator pressure.
- 5.6 Open N₂ charge valve.
- 5.7 Read and log the following; P₁, P₂, P₃, L₁, T₁, T₂, T₃, T₄.
- 5.8 Open discharge valve.
- 5.9 Read and log the following while discharging; P₂, T₂, P₃, T₄, L₁, Flow F₂ and a change in autoclave level versus time.
- 5.10 Close discharge valve V₃.
- 5.11 Close N₂ charge valve V₄.
- 5.12 Read and log the following; P₁, P₂, P₃, L₁, T₁, T₂, T₃, T₄, L₁.
- 5.13 Degasify autoclave for existing operating procedures.

- 5.14 Open charging Pump Valve V₆.
- 5.15 Log Gallons required to return to the autoclave level recorded in step 5.9.
- 5.16 If another test is scheduled, restabilize per step 5.4.
- 5.17 Sign data sheet.

THIS PAGE INTENTIONALLY LEFT BLANK

Table I

Pressure Gages

- P₁ Autoclave panel
- P₂ Test section inlet
- P₃ Test section discharge

Flow

- F₁ ΔPressure of venturi

Level

- L₁ Autoclave level, Δ pressure transmitter

Temperature

- T₁ Panel mounted autoclave temperature
- T₂ Test section inlet
- T₃ Tubesheet metal
- T₄ Test section discharge

Valves

- V₁ Upstream of venturi 3/4 swagelok
- V₂ Downstream of venturi 3/4 swagelok
- V₃ Discharge test section 2" gate
- V₄ N₂ regulator discharge
- V₅ Test section bleed
- V₆ Charge pump discharge

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N _____ Defect Size _____

4.2 Defect location _____

4.3 Tube deflected _____

5.5 Stabilized conditions

P₁ _____ psig L₁ _____ in H₂O T₁ _____ °F

P₂ _____ psig T₂ _____ °F

P₃ _____ psig T₃ _____ °F

T₄ _____ °F

5.9 Blowdown Readings

P₁ _____ psig T₂ _____ °F F₁ _____ in H₂O

P₂ _____ psig T₄ _____ °F L₁ _____ in H₂O

P₃ _____ psig

Blowdown time * Time _____ min _____ sec.

5.13 Stabilized Readings

P₁ _____ psig T₁ _____ °F L₁ _____ in H₂O

P₂ _____ psig T₂ _____ °F

P₃ _____ psig T₃ _____ °F


T₄ _____ °F

5.14 Recharge autoclave _____ gal.

Technicians _____ date _____

Engineer _____ date _____

* Time between step 5.9 L₁ and 5.13 L₁.



COMBUSTION ENGINEERING
 DEVELOPMENT DEPARTMENT
 EDS.
 WISCONSIN ELECTRIC POWER COMPANY
 TUBESHEET CREVICE FLOW TEST
 CUSTOMER NO. 6935T
 C-E 800035D18

STEAM GENERATOR CREVICE
FLOW TEST

APPENDIX B
INSTRUMENTATION
AND ERROR ANALYSIS

LIST OF INSTRUMENTS

INSTRUMENT	MANUFACTURER	MODEL #	SERIAL #	CE #	RANGE	ACCURACY
Visicorder	Honeywell	1508A	15-4641	FL90	0-10 in/sec	± 1%
Flow Δ Press	Meriam	—	1124GR15991	EL457	0-80 in/sec 0-600 in H ₂ O	± 4% ± .5%
Press Gage P ₃	Acco	2487	N/A	EL470	0-3000 psi	± 1%
Press Gage P ₂	Acco	2487	N/A	EL469	0-3000 psi	± 1%
Press Gage P ₁	U.S. Gage	—	N/A	EL468	0-3000 psi	± 1%
Temp T ₁	Honeywell	—	504	N/A	0-1000 psi °F (J)	± 1%
Chart Recorder P ₁	Honeywell	—	903827	EDL34	0-4000 psi	± 1%
Level L ₁	Rosemont	11P6E22MB	L	N/A	150"	± 1%
Temp Recorder	Ircon	—	1398	EL432	-30 + 1600 °F	± 1%

APPENDIX B

ERROR ANALYSIS OF MEASURED QUANTITIES

1.) PRESSURE READINGS (P2)

SOURCE	UNCERTAINTY
a.) Calibration: $\pm 0.25\%$ F.S. (3000 psig) (Standard gage)	± 7.5 psig
b.) Readability & Repeatability: [*] : 1/2 of 1 scale division	± 12.5 psig

^{*} Repeatability or random error is usually much less than Readability.

Total pressure uncertainty by the second power law (See No. 4 this Appendix)

$$\begin{aligned} &= \pm \sqrt{(7.5)^2 + (12.5)^2} \\ &= \pm 14.5 \text{ psig} \qquad \qquad \qquad (2 \sigma \text{ limits}) \\ & \qquad \qquad \qquad \qquad \qquad \qquad \qquad \text{or 95\% confidence interval} \end{aligned}$$

The above uncertainty can be considered to be within 2 σ limits since these are provided by the manufacturer. For a higher confidence, 3 σ limits (99.7% confidence interval) may be chosen.

$$\text{Total pressure uncertainty} = \frac{3}{2} \times 14.5 = 22 \text{ psig (3 } \sigma \text{)}$$

2.) TEMPERATURE READINGS (T2)

SOURCE	UNCERTAINTY
a.) Calibration	
Reference Temperature	$\pm 0.18^{\circ}\text{F}$
Readout (0.015% of Readings)	$\pm 0.08^{\circ}\text{F}$
b.) Readout (IRCON)	
Electronics ($\pm 0.05\%$ T $\pm 1.0^{\circ}\text{F}$)	$\pm 1.3^{\circ}\text{F}$
Digital Indicator (least significant digit)	$\pm 1.0^{\circ}\text{F}$

$$\begin{aligned} \text{Total Temperature uncertainty} &= \pm \sqrt{(0.18)^2 + (.08)^2 + (1.3)^2 + (1.0)^2} \\ &= \pm 1.65^{\circ}\text{F (2 } \sigma \text{)} \end{aligned}$$

APPENDIX B

3.) CHECK FOR SUBCOOLED STATE OF UPSTREAM CONDITIONS

To ensure that subcooled conditions existed at the upstream conditions and thus, that flashing did not occur at the venturi flowmeter, the uncertainties in the measured upstream pressure and in the saturation pressure as determined by temperature measurement will be determined. The indicated pressure difference ($P_{2\text{upstream}} - P_{2\text{sat.}}$) should be larger than the algebraic sum of the absolute values of the uncertainties $|\delta P_{2\text{upstream}}| + |\delta P_{2\text{sat.}}|$.

From (1)

$$\delta P_{2\text{upstream}} = \pm 22 \text{ psig} \quad (3 \sigma)$$

From (2)

$$\begin{aligned} \delta P_{2\text{sat.}} &= \pm 1.65^{\circ}\text{F} \times 8 \text{ psi}/^{\circ}\text{F} \\ &= \pm 13.2 \text{ psi} \quad (2 \sigma) \\ &\text{or } \pm 20 \text{ psi} \quad (3 \sigma) \end{aligned}$$

where at 540°F $\delta P_{\text{sat.}}/^{\circ}\text{F} = 8 \text{ psi}/^{\circ}\text{F}$

Thus $|\delta P_{2\text{upstream}}| + |\delta P_{2\text{sat.}}| = 22 + 20 = 42 \text{ psi}$

Run	$T_{2\text{corr.}}^*$ ($^{\circ}\text{F}$)	$P_{2\text{sat.}}$ (Psia) based on $T_{2\text{corr.}}$	P_2 (ups) Psia	Diff ($P_{2\text{ups.}} - P_{2\text{sat.}}$) Psi
1	540	963	1065	102
2	533	908	1040	132
3	545	1003	1140	137
4	540	963	1065	102
5	546	1012	1055	43
6	544	995	1040	45
7	540	963	1075	112
8	542	979	1105	126
9	541	971	1085	114
10	545	1003	1065	62
11	546	1012	1075	63
12	546	1012	1065	53
13	545	1003	1065	62
14	546	1012	1065	53
15	544	995	1065	70
16	546	1012	1085	73
17	519	806	1085	279
18	546	1012	1055	43
19	547	1020	1065	45

* $T_{2\text{corr.}}$ is the indicated temperature T_2 corrected from calibration curve of the thermocouple. At $\sim 540^{\circ}\text{F}$ ($T_{2\text{true}} - T_{2\text{indi}}$) = -0.8°F

APPENDIX B

Since $(P_{2\text{upstream}} - P_{2\text{sat.}}) > 42$ psi in all runs, we can safely say that subcooled conditions occurred upstream of the crevice.

4.) FLOW MEASUREMENT (VENTURI)

Venturi Equation:

$$Q = 5.573d^2ce \text{ fa} \left[2g \frac{\Delta P}{\rho} \right]^{1/2} \quad \text{A-1}$$

or simplifying,

$$Q = C \left[2g \frac{\Delta P}{\rho} \right]^{1/2}$$

where Q - flow rate
C - a calibration constant
g - gravitational constant
 ΔP - flowmeter reading (psi)
 ρ - density of water

The Kline & McClintock Method of combining uncertainties using the second power law equation is the following:

If R is a function of n independent variables $R = R(V_1, V_2, \dots, V_n)$
Then the uncertainty in R is

$$W_R = \left[\left(\frac{\partial R}{\partial V_1} \delta V_1 \right)^2 + \dots + \left(\frac{\partial R}{\partial V_n} \delta V_n \right)^2 \right]^{1/2} \quad \text{A-2}$$

Applying Eq. A-2 to A-1

$$\frac{W_Q}{Q} = \left[\left(\frac{\delta C}{C} \right)^2 + \left(\frac{1}{2} \frac{\delta \Delta P}{\Delta P} \right)^2 + \left(\frac{1}{2} \frac{\delta \rho}{\rho} \right)^2 \right]^{1/2}$$

a.) Calibration Constant

From the manufacturer
calibration const. uncertainty $\frac{\delta C}{C} = 2\%$ $= .02$ (2 σ)

APPENDIX B

b.) Δp readings

Instrument uncertainties (Meriam gauge)

$$\text{Calibration: } \pm .025\% \text{ F.S. (600-in H}_2\text{O)} = 0.15\text{-in H}_2\text{O}$$

$$\text{Readability \& Repeatability, } \pm 1/2 \text{ of 1 division} = 2.5\text{-in H}_2\text{O}$$

$$\begin{aligned} \Delta p_{\text{uncertainty}} &= \sqrt{(0.15)^2 + (2.5)^2} \\ &= 2.5\text{-in-H}_2\text{O} \quad (2 \sigma) \end{aligned}$$

c.) $\delta \rho$ uncertainty

$$\begin{aligned} \delta \rho \text{ for a } \Delta T = 1.65^\circ\text{F} &= \frac{(46.59 - 45.96)}{10^\circ\text{F}} 16/\text{ft}^3 \times 1.65^\circ\text{F} \\ &= 0.106 16_{\text{s}}/\text{ft}^3 \quad (2 \sigma) \end{aligned}$$

$$\frac{\Delta \rho}{\rho} = \frac{0.106}{46.6} = 0.0022 \text{ or } 0.22\%$$

Summarizing for the different tube specimen, (except 7A) the flow uncertainties are:

<u>Tube</u>	ΔP venturi (nominal)	$\frac{\Delta \rho}{\rho}$	Total Uncertainty $\frac{WQ}{Q}$
2A	215-in-H ₂ O	1.16%	2.3%
3A	13	19.2%	19.7%
4A	35	7.2%	8%
5A	48	5.2%	5.6%
6A	75	3.3%	3.9%
8A	100	2.5%	3.2%
9A	83	3.0%	3.6%

APPENDIX B

5.) FLOW MEASUREMENT UNCERTAINTY BY LEVEL CHANGE METHOD

For Tube 7A, the flow rate was so low that more confidence was placed on the level change in the autoclave than on the venturi reading.

The flow was calculated by:

$$Q = \frac{(L_1 - L_2) \frac{\rho_{\text{cold}}}{\rho_{\text{hot}}} \times 0.4896 \text{ gal/in.}}{\Delta t \text{ (min.)}}$$

Then by Eq. A-1

$$\frac{WQ}{Q} = \left[\left(\frac{\delta L}{L} \right)^2 + \left(\frac{\delta \rho_{\text{hot}}}{\rho} \right)^2 \right]^{1/2}$$

Level Monitor: Uncertainty

Calibration : 1/4% F.S. of 150-in. = 0.375 in-H₂O
Readability - Zero if scale marks are used.
Repeatability : 1/4% F.S. = 0.375 in-H₂O

$$\begin{aligned} \frac{\delta L}{L} &= \sqrt{(.0375)^2 + (.375)^2} \\ &= 0.53'' \end{aligned}$$

Total Flow uncertainty for Tube 7A, Run 17

where $L_1 - L_2 = 2$ in.

$$\begin{aligned} \frac{WQ}{Q} &= \left[\left(\frac{0.53}{2.0} \right)^2 + (.002)^2 \right]^{1/2} \\ &= 0.26 \text{ or } 26\% \end{aligned}$$

STEAM GENERATOR CREVICE
FLOW TEST

APPENDIX C
CALCULATIONS

APPENDIX C

1. Determine flow rate using autoclave level change.
Level instrument L₁ calibrated at 68°F

Autoclave

12" dia. 144" high

$$V = .7854 d^2 h$$

$$V = .7854 (12^2)(144) = \underline{16286.05 \text{ in}^3}$$

$$1 \text{ gal} = 231 \text{ in}^3$$

Machinery's Handbook

$$\frac{16286.05 \text{ in}^3}{231 \text{ in}^3/\text{gal}} = \underline{70.5 \text{ gal}}$$

$$\frac{70.5 \text{ gal}}{144 \text{ in.}} = \underline{.4896 \text{ gal/in.}}$$

$$\text{Autoclave Level} = \underline{.4896 \text{ gal/in.}}$$

Determine Flow rate in GPM using Autoclave Level change

Level - L₁

$$\frac{L_1 \text{ stand} - L_1 \text{ stop} (.4896 \text{ gal/in})}{\text{Test Time (sec)}/60 \text{ sec.}} = \text{gpm}$$

Example: Tube 1A Run 8

L₁ start = 79 in. L₁ stop = 74 in. Test time 150 sec.

$$\frac{79 - 74 (.4896)}{150/60} = \underline{.979 \text{ gal/min}}$$

Convert gpm @ 68°F to gpm @ 550°F

$$\frac{\text{Lb/Ft}^3 \text{ @ } 68^\circ\text{F}}{\text{Lb/Ft}^3 \text{ @ } 550^\circ\text{F}} = \frac{62.32 \text{ Lb/Ft}^3}{45.96 \text{ Lb/Ft}^3} = 1.36$$

Crane Tech
Paper #410

$$1.36 \times \text{gpm @ } 68^\circ\text{F} = \text{gpm @ } 550^\circ\text{F}$$

$$1.36(.979) = \underline{1.33 \text{ gpm @ } 550^\circ\text{F}}$$

APPENDIX C

Convert gpm to Lb/Hr.

$$\text{gpm} \times 60 \times \text{ft}^3/\text{gal} \times \text{Lb}/\text{ft}^3 = \text{Lb}/\text{Hr}$$

$$\text{gpm} \times 60 \times .134 \text{ ft}^3/\text{gal} \times 45.96 \text{ Lb}/\text{ft}^3 = \text{Lb}/\text{Hr}$$

$$1.33(60)(.134)(45.96) = \underline{\underline{491.5 \text{ Lb}/\text{Hr}}}$$

Crane Tech
Paper #410

Venturi Flow Meter

Mfg. Flowdyne

Throat = .1985 in.

Temp. = 550°F

Pressure = 1050 psi

- Ref (1) Flow dyne Engineering Manual
(2) Annubar Flow Hdbk Dietrich Std.

$$(1) Q = 5.573 d^2 c e f_a \left[\frac{2g \Delta P}{\rho} \right]^{1/2}$$

C = Coefficient of Discharge (2)

E = Velocity of Approach (1)

f_a = Thermal Expansion Factor (2)

ρ = Density Lb/Ft³ 550°F

g = Gravitation Constant ft/sec²

ΔP = Differential Press. in H₂O

C = for line size .195 to 2.5" dia 1.0

f_a = Thermal Expansion factor 536°F to 584°F 1.010

Example

$$Q = 5.573 (.1985)^2 (1.0)(1.010) \left[\frac{2(32.17)130.63}{45.935} \right]^{1/2}$$

$$Q = .2218 \left[\frac{2(32.17)130.63}{45.935} \right]^{1/2}$$

$$Q = 3.0 \text{ gpm}$$

STEAM GENERATOR CREVICE
FLOW TEST

APPENDIX D

COMPARISON OF FLOW RATES

APPENDIX D

COMPARISON OF MEASURED AND PREDICTED FLOW RATES

Several investigators have observed two distinct types of critical flow of flashing water through orifices. The first type occurs with flashing at the orifice throat, termed upstream choking.

Zaloudek gives a relation for this critical flow (reported in L. S. Tong, Boiling Heat Transfer and Two-Phase Flow, J. Wiley, 1965 pp. 108-110.

$$G_1 = C_1 \sqrt{2g_c \rho_1 (P_{\text{upstream}} - P_{\text{sat.}})} \quad (\text{critical flow for upstream choking})$$

where G_1 = critical mass flux in lbm/hr-ft²

C_1 = empirical constant, 0.61 - 0.64

g_c = gravitational const.

ρ_1 = saturated water density

P_{upstream} = Pressure upstream of orifice

P_{sat} = saturation pressure at subcooled liquid temperature

A second type of critical flow occurs when the water in a metastable state exits the orifice and only then flashes. This is downstream choking. The equation of Barnell or Kinderman & Wales (Also reported by Tong).

$$G_2 = \sqrt{2g_c \rho_1 P_{\text{upstream}} - (1-C_2) P_{\text{sat,upst.}}}$$

where $C_2 = 0.284 \frac{\sigma \text{ for } p_{\text{sat,upstream}}}{\sigma \text{ for } p_{\text{sat.}} = 200 \text{ psia}}$

σ = surface tension

at $p_{\text{sat}} = 1000 \text{ psia}$,

$C_2 = 0.20$

Table D-1

RUN	TUBE			COMMENTS
		$G_{\text{corr.}}^*$ LB/HR-FT ²	$G_{\text{Predicted}}$ LB/HR-FT ²	Equation used
1	2A	336×10^5	407×10^5	G ₂
2	2A	344	421	G ₂
3	2A	363	434	G ₂
4	2A	332	406	G ₂
5	2A	332	359	G ₂
6	2A	310	368	G ₂
7	3A	390	413	G ₂
8	4A	134	166	G ₁
9	4A	124	158	G ₁
10	5A	68	116	G ₁
11	5A	65	116	G ₁
12	6A	42	107	G ₁
13	8A	287	382	G ₂
14	8A	287	384	G ₂
15	9A	228	387	G ₂
16	9A	218	391	G ₂
17	7A	1346	503	G ₂
18	2A	322	369	G ₂
19	2A	322	372	G ₂

Effect of Long
L/D Before Orifice

High Flow Rate
Uncertainty

* G measured corrected for final flow area

STEAM GENERATOR CREVICE
FLOW TEST

APPENDIX E

DATA SHEETS

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 2A Defect Size .010 x 1/2" Long

4.2 Defect location 5/8" Into Tube sheet.

4.3 Tube deflected YES

5.5 Stabilized conditions

P ₁ <u>1150</u> psig	L ₁ <u>74</u> in H ₂ O	T ₁ <u>550</u> °F
P ₂ <u>1150</u> psig	<u>(70)</u>	T ₂ <u>556</u> °F
P ₃ <u>1150</u> psig		T ₃ <u>582</u> °F
		T ₄ <u>423</u> °F

5.9 Blowdown Readings

P₁ 1075 psig

T₂ 541 °F

F₁ 205 in H₂O

P₂ 1050 psig

T₄ 219 °F

L₁ 60 in H₂O

P₃ 0 psig

Blowdown time

* Time 1 min 54 sec.

5.13 Stabilized Readings

(AFTER 10 MINUTES)

P₁ 1150 psig

T₁ 550 °F

L₁ 59 in H₂O

P₂ 1150 psig

T₂ 502 °F

P₃ 1150 psig

T₃ 408 °F

T₄ 314 °F

5.14 Recharge autoclave 5 gal.

Technicians John Falkowski date 8-26-80

Engineer MPC Chaplin date 8-26-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test # 1

Tube Sheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 2A Defect Size .010 x 1/2" Long

4.2 Defect location 5/8" Into Tube Sheet.

4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1100 psig

L₁ 72 in H₂O

T₁ 540 °F

P₂ 1100 psig

(70)

T₂ 564 °F

P₃ 1075 psig

T₃ 588 °F

T₄ 447 °F

5.9 Blowdown Readings

P₁ 1050 psig

T₂ 534 °F

F₁ 215 in H₂O

P₂ 1025 psig

T₄ 222 °F

L₁ 60 in H₂O

P₃ 0 psig

Blowdown time

* Time 1 min 45 sec.

5.13 Stabilized Readings

(AFTER 5 MINUTES)

P₁ 1125 psig

T₁ 540 °F

L₁ 59 in H₂O

P₂ 1100 psig

T₂ 521 °F

P₃ 1100 psig

T₃ 4.21 °F

T₄ 316 °F

5.14 Recharge autoclave 5 gal.

Technicians John Falkowski date 8-26-80

Engineer M P Chapli date 8-26-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test # 2

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

- 4.1 Tube S/N 2A Defect Size .010 x 1/2" Long
4.2 Defect location 5/8" Into Tube sheet.
4.3 Tube deflected YES
5.5 Stabilized conditions

P ₁ <u>1200</u> psig	L ₁ <u>42</u> in H ₂ O	T ₁ <u>550</u> °F
P ₂ <u>1175</u> psig	(42)	T ₂ <u>554</u> °F
P ₃ <u>1150</u> psig		T ₃ <u>574</u> °F
		T ₄ <u>419</u> °F

5.9 Blowdown Readings

P ₁ <u>1160</u> psig	T ₂ <u>546</u> °F	F ₁ <u>238</u> in H ₂ O
P ₂ <u>1125</u> psig	T ₄ <u>217</u> °F	L ₁ <u>32</u> in H ₂ O
P ₃ <u>0</u> psig		

Blowdown time * Time 1 min 50 sec.

5.13 Stabilized Readings

(AFTER 1 MINUTE)

P ₁ <u>1175</u> psig	T ₁ <u>550</u> °F	L ₁ <u>31</u> in H ₂ O
P ₂ <u>1150</u> psig	T ₂ <u>561</u> °F	
P ₃ <u>1140</u> psig	T ₃ <u>432</u> °F	
	T ₄ <u>339</u> °F	

5.14 Recharge autoclave 5 gal.

Technicians John Falkowski date 8-26-80
Engineer M P Chaplin date 8-26-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test # 3

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 2A Defect Size .010 x 1/2" Long

4.2 Defect location 5/8" Into Tube sheet.

4.3 Tube deflected YES

5.5 Stabilized conditions

P ₁ <u>1100</u> psig	L ₁ <u>82</u> in H ₂ O	T ₁ <u>550</u> °F
P ₂ <u>1075</u> psig	<u>(80)</u>	T ₂ <u>573</u> °F
P ₃ <u>1070</u> psig		T ₃ <u>606</u> °F
		T ₄ <u>551</u> °F

5.9 Blowdown Readings

P ₁ <u>1080</u> psig	T ₂ <u>547</u> °F	F ₁ <u>200</u> in H ₂ O
P ₂ <u>1050</u> psig	T ₄ <u>242</u> °F	L ₁ <u>75</u> in H ₂ O
P ₃ <u>0</u> psig		

Blowdown time * Time 1 min 0 sec.

5.13 Stabilized Readings

(After 1 Minute)

P ₁ <u>1075</u> psig	T ₁ <u>550</u> °F	L ₁ <u>75</u> in H ₂ O
P ₂ <u>1050</u> psig	T ₂ <u>548</u> °F	
P ₃ <u>1040</u> psig	T ₃ <u>429</u> °F	
	T ₄ <u>448</u> °F	

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Fulkowski date 8-29-80

Engineer M P Chaplin date 8-29-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test # 4

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

- 4.1 Tube S/N 2A Defect Size .110 x 1/2" Long
4.2 Defect location 5/8" Into Tube Sheet.
4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1075 psig L₁ 75 in H₂O T₁ 550 °F
P₂ 1060 psig (73) T₂ 573 °F
P₃ 1040 psig T₃ 606 °F
T₄ 550 °F

5.9 Blowdown Readings

P₁ 1075 psig T₂ 547 °F F₁ 197 in H₂O
P₂ 1040 psig T₄ 241 °F L₁ 67 in H₂O
P₃ 0 psig
Blowdown time * Time 1 min 0 sec.

5.13 Stabilized Readings

(AFTER 1
MINUTE)

P₁ 1075 psig T₁ 550 °F L₁ 67 in H₂O
P₂ 1070 psig T₂ 552 °F
P₃ 1050 psig T₃ 419 °F
T₄ 446 °F

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Falkowski date 8-29-80

Engineer M P Chapli date 8-29-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test # 5

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 2A Defect Size .010 x 1/2" Long

4.2 Defect location 5/8" Into Tube sheet.

4.3 Tube deflected YES

5.5 Stabilized conditions

P ₁ <u>1050</u> psig	L ₁ <u>63</u> in H ₂ O	T ₁ <u>550</u> °F
P ₂ <u>1035</u> psig	(<u>62</u>)	T ₂ <u>580</u> °F
P ₃ <u>1010</u> psig		T ₃ <u>604</u> °F
		T ₄ <u>547</u> °F

5.9 Blowdown Readings

P ₁ <u>1050</u> psig	T ₂ <u>545</u> °F	F ₁ <u>175</u> in H ₂ O
---------------------------------	------------------------------	---

P ₂ <u>1025</u> psig	T ₄ <u>242</u> °F	L ₁ <u>56</u> in H ₂ O
---------------------------------	------------------------------	--

P₃ 0 psig

Blowdown time

* Time 1 min 0 sec.

5.13 Stabilized Readings

(AFTER 1 MINUTE)

P ₁ <u>1050</u> psig	T ₁ <u>550</u> °F	L ₁ <u>56</u> in H ₂ O
P ₂ <u>1040</u> psig	T ₂ <u>565</u> °F	
P ₃ <u>1030</u> psig	T ₃ <u>476</u> °F	
	T ₄ <u>480</u> °F	

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Falckowski date 8-29-80

Engineer MP Chapli date 8-29-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test # 6

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube IN 3A Defect Size .040

4.2 Defect location 1/2" IN To Tube Sheet

4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1100 psig

L₁ 87 in H₂O
(86)

T₁ 550 °F

P₂ 1080 psig

T₂ 588 °F

P₃ 1060 psig

T₃ 579 °F

T₄ 540 °F

5.9 Blowdown Readings

P₁ 1100 psig

T₂ 541 °F

F₁ 13 in H₂O

P₂ 1060 psig

T₄ 214 °F

L₁ 81 in H₂O

P₃ 0 psig

Blowdown time

* Time 3 min 50 sec.

5.13 Stabilized Readings

P₁ 1090 psig

T₁ 550 °F

L₁ 80 in H₂O

P₂ 1050 psig

T₂ 551 °F

P₃ 1040 psig

T₃ 384 °F

T₄ 403 °F

5.14 Recharge autoclave 214 gal.

Technicians John Falkowski date 9-2-80

Engineer RP Chupli date 9-2-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test #7

Tube Sheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N *4A Defect Size .010 x 1" Long

4.2 Defect location 5/8" Into Tube Sheet.

4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1150 psig

L₁ 80 in H₂O
(79)

T₁ 550 °F

P₂ 1135 psig

T₂ 555 °F

P₃ 1130 psig

T₃ 607 °F

T₄ 560 °F

5.9 Blowdown Readings

P₁ 1125 psig

T₂ 543 °F

F₁ 35 in H₂O

P₂ 1090 psig

T₄ 220 °F

L₁ 74 in H₂O

P₃ 0 psig

Blowdown time

* Time 2 min 30 sec.

5.13 Stabilized Readings

P₁ 1150 psig

T₁ 550 °F

L₁ 72 in H₂O

P₂ 1140 psig

T₂ 554 °F

P₃ 1130 psig

T₃ 331 °F

T₄ 490 °F

5.14 Recharge autoclave 2 1/2 gal.

Technicians Jahn Falkowski date 9-2-80

Engineer MP Chapli date 9-2-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test # 8

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N # 4A Defect Size .010 x 1" Long

4.2 Defect location 5/8" Into tube sheet.

4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1100 psig

L₁ 86 in H₂O
(85)

T₁ 547 °F

P₂ 1070 psig

T₂ 548 °F

P₃ 1060 psig

T₃ 617 °F

T₄ 553 °F

5.9 Blowdown Readings

P₁ 1100 psig

T₂ 542 °F

F₁ 30 in H₂O

P₂ 1075 psig

T₄ 219 °F

L₁ 80 in H₂O

P₃ 0 psig

Blowdown time

* Time 2 min 37 sec.

5.13 Stabilized Readings

P₁ 1090 psig

T₁ 547 °F

L₁ 80 in H₂O

P₂ 1065 psig

T₂ 550 °F

P₃ 1050 psig

T₃ 373 °F

T₄ 420 °F

5.14 Recharge autoclave 2 1/2 gal.

Technicians J. M. Falkowski date 9-3-80

Engineer M. D. Chapki date 9-3-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test #9

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

- 4.1 Tube S/N 5A Defect Size .010 x 2" Long
4.2 Defect location 5/8" Into Tube Sheet
4.3 Tube deflected YES
5.5 Stabilized conditions

P₁ 1100 psig

L₁ 81 in H₂O
(80)

T₁ 550 °F

P₂ 1075 psig

T₂ 550 °F

P₃ 1060 psig

T₃ 610 °F

T₄ 541 °F

5.9 Blowdown Readings

P₁ 1090 psig

T₂ 546 °F

F₁ 48 in H₂O

P₂ 1050 psig

T₄ 244 °F

L₁ 75 in H₂O

P₃ 0 psig

Blowdown time

* Time 2 min 25 sec.

5.13 Stabilized Readings

P₁ 1100 psig

T₁ 550 °F

L₁ 73 in H₂O

P₂ 1060 psig

T₂ 554 °F

P₃ 1050 psig

T₃ 497 °F

T₄ 541 °F

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Falkowski date 9-3-80

Engineer MD Chapli date 9-3-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test 10

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 5A Defect Size .010 x 2" Long

4.2 Defect location 5/8" In To Tube Sheet.

4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1100 psig

L₁ 72 in H₂O

T₁ 550 °F

P₂ 1080 psig

69

T₂ 550 °F

P₃ 1075 psig

T₃ 611 °F

T₄ 544 °F

5.9 Blowdown Readings

P₁ 1100 psig

T₂ 547 °F

F₁ 43 in H₂O

P₂ 1060 psig

T₄ 225 °F

L₁ 64 in H₂O

P₃ 0 psig

Blowdown time

* Time 2 min 06 sec.

5.13 Stabilized Readings

P₁ 1100 psig

T₁ 550 °F

L₁ 63 in H₂O

P₂ 1060 psig

T₂ 552 °F

P₃ 1050 psig

T₃ 488 °F

T₄ 524 °F

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Fallick date 9-3-80

Engineer MP Chappi date 9-3-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test 11

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 19 Defect Size .010 x 3" Long

4.2 Defect location 5/8" Into Tube Sheet

4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1100 psig

L₁ 82 in H₂O

T₁ 553 °F

P₂ 1080 psig

(80)

T₂ 551 °F

P₃ 1075 psig

T₃ 621 °F

T₄ 554 °F

5.9 Blowdown Readings

P₁ 1080 psig

T₂ 547 °F

F₁ 75 in H₂O

P₂ 1050 psig

T₄ 238 °F

L₁ 75 in H₂O

P₃ 0 psig

Blowdown time

* Time 1 min 33 sec.

5.13 Stabilized Readings

P₁ 1090 psig

T₁ 553 °F

L₁ 74 in H₂O

P₂ 1130 psig

T₂ 552 °F

P₃ 1070 psig

T₃ 430 °F

T₄ 500 °F

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Falkowski date 9-4-80

Engineer M.P. Chapin date 9-4-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test 12

Tube Sheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 8A Defect Size .010 x 1/2" Long

4.2 Defect location 12" Into Tube Sheet

4.3 Tube deflected YES

5.5 Stabilized conditions

P ₁ <u>1100</u> psig	L ₁ <u>80</u> in H ₂ O	T ₁ <u>550</u> °F
P ₂ <u>1070</u> psig	(78)	T ₂ <u>561</u> °F
P ₃ <u>1060</u> psig		T ₃ <u>602</u> °F
		T ₄ <u>550</u> °F

5.9 Blowdown Readings

P ₁ <u>1090</u> psig	T ₂ <u>546</u> °F	F ₁ <u>100</u> in H ₂ O
P ₂ <u>1050</u> psig	T ₄ <u>241</u> °F	L ₁ <u>73</u> in H ₂ O

P₃ 0 psig

Blowdown time

* Time 1 min 10 sec.

5.13 Stabilized Readings

P ₁ <u>1080</u> psig	T ₁ <u>550</u> °F	L ₁ <u>72</u> in H ₂ O
P ₂ <u>1040</u> psig	T ₂ <u>562</u> °F	
P ₃ <u>1030</u> psig	T ₃ <u>554</u> °F	
	T ₄ <u>501</u> °F	

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Falkowski date 9-4-80

Engineer W P Chupli date 9-4-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test 13

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 8A Defect Size .010 x 1/2" Long

4.2 Defect location 12" Into Tube Sheet.

4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1100 psig

P₂ 1070 psig

P₃ 1060 psig

L₁ 72 in H₂O
(70)

T₁ 550 °F

T₂ 558 °F

T₃ 601 °F

T₄ 544 °F

5.9 Blowdown Readings

P₁ 1090 psig

P₂ 1050 psig

P₃ 0 psig

Blowdown time

T₂ 547 °F

T₄ 252 °F

F₁ 100 in H₂O

L₁ 65 in H₂O

* Time 1 min 16 sec.

5.13 Stabilized Readings

P₁ 1080 psig

P₂ 1040 psig

P₃ 1030 psig

T₁ 550 °F

T₂ 552 °F

T₃ 553 °F

T₄ 490 °F

L₁ 64 in H₂O

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Falkowski date 9-4-80

Engineer MP Chapin date 9-4-80

* Time between step 5.9 L₁ and 5.13 L₁.

TEST 14

Tube-sheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 9A Defect Size .010 x 1/2" Long

4.2 Defect location 18" Into Tube Sheet

4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1100 psig

L₁ 83 in H₂O
(82)

T₁ 550 °F

P₂ 1060 psig

T₂ 559 °F

P₃ 1050 psig

T₃ 600 °F

T₄ 548 °F

5.9 Blowdown Readings

P₁ 1090 psig

T₂ 545 °F

F₁ 83 in H₂O

P₂ 1050 psig

T₄ 242 °F

L₁ 77 in H₂O

P₃ 0 psig

Blowdown time

* Time 1 min 34 sec.

5.13 Stabilized Readings

P₁ 1080 psig

T₁ 550 °F

L₁ 76 in H₂O

P₂ 1040 psig

T₂ 556 °F

P₃ 1060 psig

T₃ 556 °F

T₄ 530 °F

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Falkowski date 9-5-80

Engineer M P Chaplin date 9-5-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test 15

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 9A Defect Size .010 x 1/2 Long

4.2 Defect location 18" Into Tube sheet

4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1100 psig

P₂ 1080 psig

P₃ 1080 psig

L₁ 77 in H₂O
(75)

T₁ 550 °F

T₂ 560 °F

T₃ 603 °F

T₄ 551 °F

5.9 Blowdown Readings

P₁ 1090 psig

P₂ 1070 psig

P₃ 0 psig

Blowdown time

T₂ 547 °F

T₄ 241 °F

F₁ 75 in H₂O

L₁ 70 in H₂O

* Time 1 min 31 sec.

5.13 Stabilized Readings

P₁ 1100 psig

P₂ 1070 psig

P₃ 1075 psig

T₁ 550 °F

T₂ 560 °F

T₃ 566 °F

T₄ 530 °F

L₁ 70 in H₂O

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Falkowski date 9-5-80

Engineer MP Chaplin date 9-5-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test 16

Tubeheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 7A Defect Size .010 hole
4.2 Defect location 5/8" Into Tube sheet.
4.3 Tube deflected YES

5.5 Stabilized conditions

P₁ 1100 psig

L₁ 83 in H₂O

T₁ 554 °F

P₂ 1070 psig

82

T₂ 553 °F

P₃ 1060 psig

T₃ 620 °F

T₄ 546 °F

5.9 Blowdown Readings

P₁ 1100 psig

T₂ 520 °F

F₁ 0 in H₂O

P₂ 1070 psig

T₄ 214 °F

L₁ 80 in H₂O

P₃ 0 psig

Blowdown time

* Time 14 min 25 sec.

5.13 Stabilized Readings

P₁ 1100 psig

T₁ 554 °F

L₁ 80 in H₂O

P₂ 1070 psig

T₂ 532 °F

P₃ 1060 psig

T₃ 388 °F

T₄ 400 °F

5.14 Recharge autoclave _____ gal.

Technicians John Falkowski date 9-8-80

Engineer mp chopli date 9-8-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test 17

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N 2A Defect Size .010 x 1/2 Long
4.2 Defect location 5/8" Into Tube Sheet
4.3 Tube deflected NO

5.5 Stabilized conditions

P₁ 1100 psig

P₂ 1060 psig

P₃ 1050 psig

L₁ 74 in H₂O
73

T₁ 554 °F

T₂ 561 °F

T₃ 612 °F

T₄ 542 °F

5.9 Blowdown Readings

P₁ 1090 psig

P₂ 1040 psig

P₃ 0 psig

Blowdown time

T₂ 547 °F

T₄ 250 °F

F₁ 190 in H₂O

L₁ 68 in H₂O

* Time 1 min 0 sec.

5.13 Stabilized Readings

P₁ 1075 psig

P₂ 1030 psig

P₃ 1020 psig

T₁ 554 °F

T₂ 550 °F

T₃ 463 °F

T₄ 515 °F

L₁ 65 in H₂O

5.14 Recharge autoclave 2 1/2 gal.

Technicians John Falkowski date 9-9-80

Engineer M P Choplin date 9-9-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test 18

Tubesheet Crevice Leak Rate Test

Data Sheet

Step No.

4.1 Tube S/N # 2A Defect Size .010 x 1/2" Long

4.2 Defect location 5/8" Into Tube Sheet.

4.3 Tube deflected NO

5.5 Stabilized conditions

P₁ 1100 psig

L₁ 63 in H₂O

T₁ 554 °F

P₂ 1070 psig

62

T₂ 558 °F

P₃ 1060 psig

T₃ 603 °F

T₄ 540 °F

5.9 Blowdown Readings

P₁ 1090 psig

T₂ 548 °F

F₁ 187 in H₂O

P₂ 1050 psig

T₃ 248 °F

L₁ 57 in H₂O

P₃ 0 psig

Blowdown time

* Time 58 min 58 sec.

5.13 Stabilized Readings

P₁ 1080 psig

T₁ 554 °F

L₁ 55 in H₂O

P₂ 1050 psig

T₂ 557 °F

P₃ 1040 psig

T₃ 465 °F

T₄ 461 °F

5.14 Recharge autoclave 2 1/2 gal.

Technicians Julius Falkowski date 9-9-80

Engineer M P Chaplin date 9-9-80

* Time between step 5.9 L₁ and 5.13 L₁.

Test 19