

INTERIM REPORT

9-12-79

Accession No. 7909240700

Contract Program or Project Title:

Thermal Fuels Behavior Program

Subject of this Document:

Loss-of-Coolant Accident Test Series Test LOC 5
Experiment Operating Specification

Type of Document: EOS

Author(s): T. R. Yackle

Date of Document: August 1979

Responsible NRC Individual and NRC Office or Division: M. L. Picklesimer, RSR

This document was prepared primarily for preliminary or internal use. It has not received full review and approval. Since there may be substantive changes, this document should not be considered final.

for *Ray Rose*
H. P. Pearson, Supervisor
Information Processing
EG&G Idaho

Prepared for
U.S. Nuclear Regulatory Commission
Washington, D.C. 20555

NRC Fin #A6041

INTERIM REPORT

NRC Research and Technical
Assistance Report

998 217

TFBP-TR-309

Rev. 1

for U.S. Nuclear Regulatory Commission

**LOSS-OF-COOLANT ACCIDENT TEST SERIES
TEST LOC 5
EXPERIMENT OPERATING SPECIFICATION**

T.R. YACKLE

August 1975



EG&G Idaho, Inc.



IDAHO NATIONAL ENGINEERING LABORATORY

DEPARTMENT OF ENERGY

IDAHO OPERATIONS OFFICE UNDER CONTRACT DE-AC07-76IDO1570

998 218

NRC Research and Technical
Assistance Report

DOCUMENT REVISION REQUEST

① OPER. NO. _____

PAGE 1 OF 1

| | | |
|------------------------------------|-----------------------------|------------------------------|
| ② REQUESTER T. R. Yackle | ③ DRR DATE 9/4/79 | ④ DRR NO. TFBP-211 |
|------------------------------------|-----------------------------|------------------------------|

| | | |
|--|--|--|
| ⑤ DOCUMENT NO. (IF APPLICABLE) TFBP-TR-309, Rev. 1 | DOCUMENT TITLE LOSS OF COOLANT ACCIDENT TEST SERIES TEST LOC-5 EOS | DOCUMENT ISSUE DATE Aug 1979 |
|--|--|--|

| | |
|--|-------------------------------------|
| ⑥ CHECK APPLICABLE BLANK PERMANENT CHANGE <input checked="" type="checkbox"/> TEMPORARY CHANGE _____ BULLETIN _____ | ⑦ MANAGER APPROVAL _____ DATE _____ |
|--|-------------------------------------|

⑧ PRINT OR TYPE PROPOSED CHANGE — NUMBER EACH CHANGE SEQUENTIALLY IN 1ST COLUMN AND RECORD PAGE AND STEP OR PARAGRAPH NUMBER FOR EACH CHANGE.

| ITEM | PAGE | STEP OR PARA. | INSTRUCTIONS: REWRITE PARAGRAPH(S) OR FOR EXTENSIVE CHANGES ATTACH REVISED COPY AND STATE "REVISE PER ATTACHED COPY". FOR NEW DOCUMENT, ATTACH ROUGH DRAFT AND STATE "PREPARE NEW (SP, DOP, ETC.) PER ATTACHED DRAFT". |
|------|------|---------------|--|
| 1 | 34 | 13 | Change "X" in Cold Leg Blowdown Valve column to "0" |
| 2 | 34 | Note (1) | Change valve description to VALVbPOSbbLM1103PT and VALVbPOSbbLM1104PT |
| 3 | 37 | 1 | Change 0.086 1/s to 0.190 1/s |

⑨ FOR WRITER'S USE

USE CONTINUATION SHEET AS REQUIRED

NEXT ANTICIPATED NEED FOR DOCUMENT WITH THIS REVISION INCORPORATED: DATE/EVENT _____

| ⑩ JUSTIFICATION (REASON FOR CHANGE — NUMBER TO CORRESPOND TO ITEM NO. ABOVE): 1) The cold leg should remain open throughout blowdown until quench 2) Incorrect valve identity 3) Low flow reflood rate incorrectly specified in the text | ⑪ OTHER DOCUMENTATION AFFECTED: <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="width: 33%;">DOC. NO.</th> <th style="width: 33%;">DRR NO.</th> <th style="width: 33%;">DATE COMPLETED</th> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </table> | DOC. NO. | DRR NO. | DATE COMPLETED | | | | | | | | | | | | |
|---|---|----------------|---------|----------------|--|--|--|--|--|--|--|--|--|--|--|--|
| DOC. NO. | DRR NO. | DATE COMPLETED | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |

⑫ ORIGINATING DRR NO: _____

| ⑬ REVIEW | | | | | | | | | |
|---------------------|------|---------|---------------------|------|--------|----------------|---------------|--------------|------|
| NAME/SIGNATURE | ORG. | DATE | NAME/SIGNATURE | ORG. | DATE | NAME/SIGNATURE | ⑭ REVIEW CODE | ORG. | DATE |
| <i>T. R. Yackle</i> | 2810 | 9/04 | <i>CONROBERT</i> | 2600 | 9-4-79 | | | QUALITY DIV. | |
| <i>R. K. Warner</i> | 2810 | 9/04/79 | <i>R. K. Warner</i> | 2810 | 9-4-79 | | | SAFETY DIV. | |
| <i>D. H. ...</i> | 2700 | 9/4/79 | | | | | | PRAC | |

| | |
|------------|---|
| ⑮ COMMENTS | ⑯ ADDITIONAL DRRS IN THIS DOCUMENT REVISION |
|------------|---|

| | | |
|-----------------------|----------------|----------------------|
| ⑰ DOCUMENT CONTROLLER | ⑱ RELEASE DATE | ⑲ DRR COMPLETED DATE |
|-----------------------|----------------|----------------------|

DOCUMENT REVISION REQUEST

| | | |
|--|-------------------------------|---|
| ② REQUESTER M. E. Waterman | ③ DRR DATE August 22, 1979 | ④ DRR NO. TFBP-209 |
| ⑤ DOCUMENT NO. (IF APPLICABLE) TFBP-TR-309, Rev. 1 | | DOCUMENT TITLE LOSS-OF-COOLANT ACCIDENT TEST SERIES TEST LOC-5 EXPERIMENT OPERATING SPECIFICATION |
| ⑥ CHECK APPLICABLE BLANK PERMANENT CHANGE <input checked="" type="checkbox"/> TEMPORARY CHANGE _____ BULLETIN _____ | | ⑦ MANAGER APPROVAL _____ DATE _____ |
| ⑧ PRINT OR TYPE PROPOSED CHANGE — NUMBER EACH CHANGE SEQUENTIALLY IN 1ST COLUMN AND RECORD PAGE AND STEP OR PARAGRAPH NUMBER FOR EACH CHANGE | | ⑨ FOR WRITER'S USE |

| ITEM | PAGE | STEP OR PARA. | INSTRUCTIONS: REWRITE PARAGRAPH(S) OR FOR EXTENSIVE CHANGES ATTACH REVISED COPY AND STATE "REVISE PER ATTACHED COPY". FOR NEW DOCUMENT, ATTACH ROUGH DRAFT AND STATE "PREPARE NEW (SP, DOP, ETC.) PER ATTACHED DRAFT" |
|------|------|---------------|---|
| 1 | 37 | 5 | Change "CLAD808b2b19+0bb0Z" to "CLAD839b2b19+0bb0Z" |
| 2 | 47 | | Change "RODbPRESSbb808bbb0Z" to "RODbPRESSbb839bbb0Z" |
| 3 | | | With the exception of TABLE X, all references to Rods 934, 839, 935, and 912 should be changed to RODS 934, 839, 935, and 912 605-5, 605-6, 605-7, and 605-8, respectively. |

USE CONTINUATION SHEET AS REQUIRED
NEXT ANTICIPATED NEED FOR DOCUMENT WITH THIS REVISION INCORPORATED: DATE/EVENT _____

| ⑩ JUSTIFICATION: (REASON FOR CHANGE — NUMBER TO CORRESPOND TO ITEM NO. ABOVE): 1. Rod 308 replaced by Rod 339 2. Rod 808 replaced by Rod 839 3. Rod numbers replaced to establish rod identification consistency. | ⑪ OTHER DOCUMENTATION AFFECTED: <table style="width:100%; border-collapse: collapse;"> <tr> <th style="width:33%;">DOC NO.</th> <th style="width:33%;">DRR NO.</th> <th style="width:33%;">DATE COMPLETED</th> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </table> ⑫ ORIGINATING DRR NO: _____ | DOC NO. | DRR NO. | DATE COMPLETED | | | | | | | | | | | | | | | |
|--|--|----------------|---------|----------------|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
| DOC NO. | DRR NO. | DATE COMPLETED | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |

| REVIEW | | | | | | | | | |
|--------------------|------|---------|----------------|-----|------|----------------|---------------|-------------|------|
| NAME/SIGNATURE | ORG | DATE | NAME/SIGNATURE | ORG | DATE | NAME/SIGNATURE | ⑭ REVIEW CODE | ORG. | DATE |
| <i>[Signature]</i> | 2810 | 8/23/79 | | | | | | QUALITY DIV | |
| <i>[Signature]</i> | 2810 | 8/23/79 | | | | | | SAFETY DIV | |
| R. K. McCandless | 2810 | 8/24/79 | | | | | | PRAC | |

| | |
|-----------------------|---|
| ⑮ COMMENTS | ⑯ ADDITIONAL DRRS IN THIS DOCUMENT REVISION |
| ⑰ DOCUMENT CONTROLLER | ⑱ DRR COMPLETED DATE |
| ⑱ RELEASE DATE | ⑲ DRR COMPLETED DATE |


LOSS-OF-COOLANT ACCIDENT TEST SERIES
TEST LOC 5
EXPERIMENT OPERATING SPECIFICATION

August 1979


T. R. YACKLE

Thermal Fuels Behavior Program
EG&G Idaho, Inc.


Approved:




J. M. Broughton, Supervisor
LOCA and Inlet Flow Blockage Tests




R. K. McCardell, Manager
PBF Experiment Specification and Analysis Branch



P. E. MacDonald, Manager
LWR Fuel Research Division



J. P. Kester, Manager
TFPB Technical Support Division



C. O. Doucette, Manager
PBF Facility Division

998 221



FORM EG&G-398
(Rev. 12-78)

INTERIM REPORT

Accession No. _____

Report No. TFBP-TR-309
Revision 1

Contract Program or Project Title: Thermal Fuels Behavior Program

Subject of this Document: Loss-of-Coolant Accident Test Series Test LOC-5 Experiment Operating Specification

Type of Document: EOS

Author(s): T. R. Yackle

Date of Document: August 1979

Responsible NRC Individual and NRC Office or Division: Dr. M. L. Picklesimer, Reactor Safety Research

This document was prepared primarily for preliminary or internal use. It has not received full review and approval. Since there may be substantive changes, this document should not be considered final.

EG&G Idaho, Inc.
Idaho Falls, Idaho 83401

Prepared for the
U.S. Nuclear Regulatory Commission
and the U.S. Department of Energy
Idaho Operations Office
Under contract No. DE-AC07-76ID01570
NRC FIN No. A6041

INTERIM REPORT

998 222

CONTENTS

1. INTRODUCTION. 1

2. EXPERIMENT DESIGN 3

 2.1 Fuel Rods and Shroud 3

 2.2 Test Train 3

 2.3 LOCA Blowdown System 10

 2.4 Instrumentation. 13

3. EXPERIMENT OPERATING PROCEDURE. 21

 3.1 Instrument Status Check 26

 3.2 Heatup Phase 28

 3.3 Instrument Drift Recording and Status Check. 29

 3.4 Power Calibration Phase. 30

 3.5 Preconditioning Phase. 31

 3.6 Decay Heat Buildup Phase 31

 3.7 Blowdown and Reflood Phase 32

 3.8 Quench and Cooldown Phase. 37

 3.9 Shutdown and Abnormal Test Termination Requirements. . . . 37

4. DATA ACQUISITION AND REDUCTION REQUIREMENTS 39

 4.1 Data Acquisition Requirements. 39

 4.2 Data Reduction Requirements. 46

 4.2.1 Quick Look Report 48

 4.2.2 Experiment Data Report. 49

 4.2.3 Test Results Report 49

5. GENERAL POST IRRADIATION EXAMINATION. 50

6. REFERENCES. 52

APPENDIX A - STATUS CHECK LIST FOR INSTRUMENTATION 53

TABLES

| | | |
|-------|---|----|
| I. | Test LOC-5 Fuel Rod Design Characteristics. | 4 |
| II. | Test LOC-5 Fuel Rod Nominal Dimensions. | 5 |
| III. | Test LOC-5 Fuel Rod Shroud Characteristics. | 6 |
| IV. | Test LOC-5 Henry Nozzle Throat Diameters and Locations. | 12 |
| V. | Test LOC-5 Thermocouple Data. | 16 |
| VI. | Test LOC-5 Plant Instrumentation. | 20 |
| VII. | Operating Sequence for Test LOC-5 | 22 |
| VIII. | Programming and Monitoring System Controlled Event Sequence | 33 |
| IX. | Reflood Rates for Test LOC-5. | 36 |
| X. | Test LOC-5 Fuel Train Instrumentation, Data Channel Recording, and Display Requirements | 40 |
| XI. | Test LOC-5 Test Train Instrumentation, Data Channel Recording, and Display Requirements | 42 |
| XII. | Test LOC-5 Hot Leg, Cold Leg, and Initial Conditions Spool Piece Instrumentation, Data Channel Recording, and Display Requirements. | 43 |
| XIII. | Test LOC-5 Plant Instrumentation, Data Channel Recording, and Display Requirements. | 44 |

FIGURES

| | | |
|----|---|----|
| 1. | Test LOC-5 Fuel train orientation | 7 |
| 2. | Test LOC-5 test train illustration. | 9 |
| 3. | PBF-LOCA blowdown system illustration | 11 |
| 4. | PBF-LOCA blowdown measurement spool illustration. | 14 |
| 5. | Operating sequence for Test LOC-5 | 25 |
| 6. | Reactor power variation with time during the transient. | 35 |
| 7. | Strip chart setup for Test LOC-5 | 47 |

998 224

CONVERSION FACTORS FOR SI
AND U.S. CUSTOMARY UNITS

| <u>To Convert From</u> | <u>To</u> | <u>Multiply by</u> |
|------------------------|-------------------------|--------------------|
| K | °F | 1.8 K - 459.67 |
| kg/s-m ² | lb/ft ² -hr | 737.4 |
| kg/s | lb/s | 2.2046 |
| kW/m | kW/ft | 0.3048 |
| m | ft | 3.2083 |
| MPa | psi | 145.05 |
| W/m ² | Btu/ft ² -hr | 0.3169 |
| m ³ /s | ft ³ /s | 35.315 |
| /s | gal/min | 15.85 |

ASS BPP

998 225

1. INTRODUCTION

The Loss of Coolant Accident (LOCA) Program¹ is part of the Department of Energy Fuel Behavior Program² sponsored by the Nuclear Regulatory Commission, and is directed towards providing a detailed understanding of the response of nuclear fuel rods to off-normal accident conditions. This is one of several programs being conducted by the Thermal Fuels Behavior Program of EG&G Idaho, Inc., in the Power Burst Facility (PBF) that will provide data for development and assessment of fuel behavior computer models used to predict the response of light water reactor (LWR) fuel under hypothesized accident conditions.

The LOCA tests simulate accident conditions in a pressurized water reactor (PWR) core resulting in a loss of fuel rod coolant. During a LOCA the coolant conditions are characterized by a rapid core depressurization and drastic changes in both coolant mass flow and quality. Depending on the size and location of the break in the cold- or hot-leg, system depressurization will be completed within approximately 30 seconds. Cooling of the fuel rods will degrade during the accident. The fuel rod cladding will heat up and may balloon and rupture.

The purpose of this document is to specify the experiment operating procedure for Test LOC-5. The test will be performed using four, separately shrouded fuel rods of PWR 15x15 design. Two rods have been previously irradiated and two rods will be unirradiated. One unirradiated and one irradiated rod will be backfilled with helium to a pressure typical of beginning-of-life PWR fuel rods, and the other rods will be backfilled to a pressure typical of fuel rods at the end-of-operational life.

The behavior of PWR fuel rods during the LOCA conditions for Test LOC-5 will result in peak cladding temperatures stabilizing in the β -phase. Cladding ballooning with relatively large strain to

failure is expected on all four rods. Additionally, a comparison will be made between the behavior of irradiated and unirradiated fuel rods.

The test will be performed in five separate phases; loop heatup, preconditioning operation, blowdown, reflood, and quench. The tests will be sequenced as follows. The primary coolant loop condition will be increased up to the desired pressure and temperature. The test rods will be power cycled in the preconditioning phase and then operated at steady state for approximately 1-1/2 hours to build up the desired fission product inventory. The blowdown will follow, with a rapid depressurization of the PBF test train and LOCA system. The test will be terminated with reflood and quench followed by long-term cooling provided by the quench system.

Section 2 of this document describes the fuel train, test assembly, LOCA modifications, and instrumentation associated with each component. Section 3 presents the procedures of the experiment conduct for Test LOC-5. Section 4 lists the data acquisition and reduction requirements. The posttest operations support and the post irradiation examination requirements are presented in Sections 5 and 6. Appendix A provides the status check lists for instrumentation and flow balance sheets.

2. EXPERIMENT DESIGN

Test LOC-5 will be conducted with four separately shrouded PWR type fuel rods. The fuel rods, individual flow shrouds, and fuel rod instrumentation are supported by the test train. The Test LOC-5 experiment design is the same as the Test LOC-3 design presented by the Experiment Operating Specification (EOS)³ except for minor differences in fuel rod specifications. This section summarizes the design of fuel rods, test train, LOCA modification system, and the instrumentation associated with each component as presented by the Test LOC-3 EOS. Further information is available in the Experiment Specification Document⁴ and the Experiment Configuration Specification⁵.

2.1 Fuel Rods and Shroud

The fuel rods consist of two rods that were previously irradiated to about 16000 MWd/t in the Saxton reactor and two unirradiated rods of Saxton design. The two irradiated rods are designated 839 and 912, and the two unirradiated rods are designated 934 and 935. The fuel rod designation and burnup are given in Table I. The as-fabricated nominal design characteristics of these fuel rods are given in Table II. Rods 839 and 934 are prepressurized to 2.41 MPa, typical of the PWR rod beginning-of-life pressure and Rods 912 and 935 are prepressurized to 4.83 MPa, typical of the PWR rod end-of-life pressure. The unirradiated rods are contained in stainless steel shrouds, whereas the irradiated rods are contained in zircaloy shrouds. The flow shrouds are similar to the fluted shrouds used in Test LOC-11⁶. The characteristics of the individual flow shrouds are shown in Table III. A plane view of the fuel rod orientation and instrumentation within the in-pile tube (IPT) (Subsection 2.4.1) is shown in Figure 1.

998 228

PSS BPF

TABLE I

TEST LOC-5 FUEL ROD DESIGN CHARACTERISTICS

| <u>Test</u> | <u>Rod Type</u> | <u>Rod No.</u> | <u>Helium Pre- Pressurization (MPa)</u> | <u>Burnup (MWd/t)</u> | <u>U-235 Enrichment (%)</u> | <u>Fuel Theoretical Density (%)</u> |
|-------------|-----------------|----------------|---|---------------------------|---------------------------------|---|
| LOC-5 | Saxton | 934 | 2.41 | 0 | 12.5 | 94.5 + 0.5 |
| | Saxton | 935 | 4.83 | 0 | 12.5 | 94.5 + 0.5 |
| | Saxton | 839 | 4.83 | 17,660 | 12.5 | 92 + 0.5 |
| | Saxton | 912 | 2.41 | 16,050 | 12.5 | 89.5 + 0.5 |

4

998 229

TABLE II
TEST LOC-5 FUEL ROD NOMINAL DIMENSIONS


| |
|---|
| Cladding material - zircaloy-4 |
| Cladding outside diameter - 9.93 mm |
| Cladding inside diameter - 8.75 mm |
| Cladding wall thickness - 0.59 mm |
| Diametral gap - 0.216 mm (unirradiated) |
| Pellet diameter - 8.534 ± 0.013 mm (Rods 839, 934, 935), 8.484 ± 0.013 mm (Rod 912) |
| Pellet length - 15.24 ± 0.25 mm |
| Pellet dish depth - 0.34 mm, spherical radius - 16.08 mm |
| Pellet centerhole - 1.88 ± 0.05 mm (unirradiated) |
| Fuel length - 889 mm |
| Top insulating pellet length - 15.24 ± 0.25 mm |
| Bottom insulating pellet length - 6.35 ± 0.25 mm (unirradiated rods) |
| Plenum volume - 2.917 cm ³ (included plenum pressure transducer and sensor line volumes) |

TABLE III
TEST LOC-5 FUEL ROD SHROUD CHARACTERISTICS

| | <u>Irradiated Rods</u> | <u>Unirradiated Rods</u> |
|---|------------------------|--------------------------|
| Shroud material | Zircaloy | Stainless steel |
| Wall thickness (mm) | 1.24 | 1.33 |
| Initial outside diameter (mm) | 25.4 | 25.4 |
| Flow area per shroud (mm ²) | 229 | 225 |

UES 840

998 231



| Rod locations | Rod No. | Internal pressure |
|---------------|---------|-------------------|
| 1 | 934 | (2.41 MPa) |
| 2 | 839 | (2.41 MPa) |
| 3 | 935 | (4.83 MPa) |
| 4 | 912 | (4.83 MPa) |

- Rod to rod pitch - 49.39 mm
- Cladding thermocouples
- × Self powered neutron detectors
- ⊗ Self powered gamma detectors
- Zircaloy-4 support tube - 10.9 mm outer diameter
- △ Flux wires
- Inside shroud coolant thermocouples
- Outside shroud surface thermocouples
- * Differential thermocouple
- Inlet/outlet thermocouple

Fig. 1 Test LOC-5 fuel train orientation

INEL-A-10 340

998 232

2.2 Test Train

The LOC-5 test train positions and supports the four test fuel rods as shown in Figures 1 and 2. Major test train components are the fuel rod support plates, IPT flow shroud, the flux shaper, two particle screens and the catch basket, several filler pieces, and the reflood line.

The fuel rod support plates position each rod within the active core region. The upper support plate is fixed near the top of each rod allowing the rod to expand axially downward with the lower end of each rod positioned by the lower support plate.

The IPT flow shroud directs the coolant from the IPT inlet down to the lower plenum and into the individual fuel rod flow shrouds. The IPT shroud is fabricated in three sections, two stainless steel and one zircaloy. The zircaloy section is positioned in the central core region. A flux shaper is located within the zircaloy section to flatten the axial power profile within $\pm 5\%$ over a 31 cm section in the central core region.

All of the coolant passing the fuel rods is channeled through particle screens located in the lower and upper plenums. The screens are sized with equivalent openings as in the screens in the blowdown measurement spools. A catch basket is located below the lower plenum particle screen to catch molten fuel in the event of severe rod failure and to protect the IPT.

Filler pieces are located in the IPT exit volume, the upper plenum and the downcomer region to reduce the large volumes of water in the test train. Each filler piece is sized for the maximum reduction in water volume consistent with providing sufficient coolant flow area.

POOR ORIGINAL




Fig. 2 Test LOC-5 test train illustration

998 234

The controlled bypass flow path is fabricated as part of the upper plenum filler piece and is located between the IPT inlet and the upper plenum. The bypass provides a low resistance flow path between the upper plenum and the IPT inlet during blowdown and includes the capability of being orificed to control the relative flow resistance between the bypass flow path and the flow shrouds.

The capability of providing reflood water to the lower plenum is available through the zircaloy hanger rod tube. Test LOC-5 will use the reflood system to quench the rods with a controlled reflood rate.

2.3 LOCA Blowdown System

The PBF-LOCA blowdown loop is illustrated in Figure 3. The blowdown system provides the means to isolate the IPT from the primary coolant loop during blowdown and directs the coolant into the blowdown tank. The blowdown is initiated with quick opening and closing valves located in the hot- and cold-leg blowdown lines. Four Henry nozzles, two in the cold-leg and two in the hot-leg, provide the break plane for the desired break flow rate and depressurization rate. The Henry nozzle throat areas and locations for Test LOC-5 are tabulated in Table IV. Both cold-leg blowdown valves will be opened in Test LOC-5, after the IPT is isolated from the primary coolant loop, and the system will depressurize through the Henry nozzles and into the blowdown tank.

A small line connects the hot and cold blowdown piping legs with a controllable valve. This line provides a small flow rate to keep the hot-and cold-legs at the system temperature and pressure prior to blowdown. The valve and line also provide additional mechanisms for controlling the coolant mass flow through the fuel assembly.

The blowdown header and tank collect and contain the coolant ejected from the IPT and piping during blowdown, quench, and post blowdown cooling. It will also confine any fission products carried from the fuel rods by the coolant.

998 235

POOR ORIGINAL




Fig. 3 PBF-LOCA blowdown system illustration

998 236

TABLE IV
TEST LOC-5 HENRY NOZZLE THROAT
DIAMETERS AND LOCATIONS

| <u>Nozzle Designation</u> | <u>Location</u> | <u>Throat Diameter (mm)</u> |
|---------------------------|-----------------|-----------------------------|
| FE-11-1-1 | Hot leg | 14.22 |
| FE-11-1-2 | Hot leg | 13.56 |
| FE-11-1-3 | Cold leg | 14.22 |
| FE-11-1-4 | Cold leg | 13.56 |

DES
APP

998 237

Posttest quench cooling is accomplished by opening the quench valve (and closing the cold leg blowdown valves) to permit coolant from the quench tank to enter the IPT. The quench tank is pressurized by a nitrogen gas system and heated to about 366 K. If needed, longer term cooling is accomplished by reconnecting the IPT to the existing loop (opening the isolation valves and closing the bypass and blowdown valves) and permitting the primary coolant loop to recirculate through the IPT.

The LOCA system contains an initial condition measurement spool and blowdown measurement spool in each blowdown leg. This instrumentation is described in the Subsection 2.4.

The sequencing of the blowdown valve during the transient is controlled by a time-sequential programmer in the Programming and Monitoring System (P&MS). Signals for cladding temperature and elapsed time are input to the P&MS.

2.4 Instrumentation


A brief description of the Test LOC-5 instrumentation is provided in this section. The instrumentation of the Test LOC-5 fuel train is designed to measure the fuel rod surface and centerline temperature, plenum pressure and temperature, axial length change, and coolant pressure, temperature, density, and flow rate. The location of the fuel rod instrumentation is shown in Figure 1. An illustration of a blowdown measurement spool piece is shown in Figure 4.

The planned instrumentation for the measurement of parameters for each fuel rod consists of the following:

- (1) One Kaman strain gauge-type pressure transducer, fitted with a slip-fitting sleeve to protect the device from thermal transients is used to measure each fuel rod plenum pressure. The sleeve consists of a stainless steel annular jacket containing a silver cylinder on the inner surface and separated from the outer surface by a helium filled gap.

470 236

14



INEL-A-3082

- 1. Flow screen
- 2. Source cask of gamma densitometer
- 3. Detector cask of gamma densitometer
- 4. Pressure - water cooled standoff (saturated blowdown)
- 5. Resistance temperature detector (initial temperature)
- 6. Thermocouple (blowdown temperature)
- 7. Pressure difference (inter spool)
- 8. Pressure difference (across flow screen, fission product sample tap)
- 9. Pressure - flush mounted (subcooled blowdown)
- 10. Drag disk
- 11. Turbine flow meter and pickup coils

Fig. 4 PBF-LOCA blowdown measurement spool illustration

POOR ORIGINAL

998 239

- (2) Four cladding surface thermocouples spot welded to the cladding. The orientation of the junctions above the bottom of the fuel stack are shown in Figure 1. Table V lists additional data on the thermocouples.
- (3) One tungsten-rhenium centerline thermocouple located 570 mm above the bottom of the fuel stack in a 1.88-mm-diameter hole of previously unirradiated Rods 934 and 935.
- (4) One plenum temperature thermocouple located in the midregion of the plenum of each rod.
- (5) One EG&G Idaho, Inc., axial length change transducer located at the lower end of each rod. The device is not temperature compensated or thermally shielded, so it will detect rather than quantify length changes during the transient blowdown quench and cooling phases of the test.
- (6) Seven self-powered neutron detectors (SPND) used to correlate reactor power to calibrated fuel rod power and to determine the axial power profile with power level.
- (7) An aluminum-cobalt alloy flux wire located on each fuel rod flow shroud and on the hanger rod. The devices yield the time averaged neutron flux near the rod.
- (8) Three self-powered gamma detectors (SPGD) located at the core midplane and ± 228.6 mm, and used to determine the gamma flux.

Planned instrumentation for measurement of coolant parameters in the IPT includes:

- (1) A Flow Technology, Inc., bi-directional turbine meter located at the top and bottom of each fuel rod shroud. Two pickup coils of EG&G Idaho, Inc., design and manufacture are associated with each turbine to determine flow direction.

TABLE V

TEST LOC-5 THERMOCOUPLE DATA

| Thermocouple | Type | Insulation | Material | Sheath OD (mm) | Wall Thickness (mm) | Junction type |
|---------------------------------|--------------|----------------|----------|-------------------|---------------------------|------------------------|
| Centerline | W5%Re/W26%Re | BeO Hard Fired | MoRe | 1.575 | 0.254 | Ungrounded |
| Cladding surface | K | MgO | Ti | 1.17 | 0.229 | Grounded, spade tip |
| Coolant channel differential | K | MgO | SST | 1.575 | 0.254 | Ungrounded |
| Plenum | K | MgO | SST | 0.51 | a | Grounded |
| Coolant | K | MgO | SST | 1.575 | 0.254 | Grounded |
| Coolant shroud | K | MgO | SST | 1.02 | 0.203 | Grounded |
| Shroud outer surface | K | MgO | SST/Ti | 1.17 | 0.229 | Grounded, spade tip |

a. Wall is swaged at junction and thickness is not available.

998
241

- (2) A pair of differential thermocouples to measure the temperature increase across each fuel rod flow channel during steady state operation for power calibration purposes.
- (3) A pair of thermocouples for each fuel rod channel to measure the fuel rod flow inlet and outlet temperatures.
- (4) Three flow shroud coolant thermocouples located on standoffs at the core midplane and ± 120 mm from the core midplane, on the flow shrouds of Rods 839 and 935 to measure the coolant temperature during the transient.
- (5) Three thermocouples located at the core midplane and ± 120 mm from the core midplane, on the flow shroud of Rods 839 and 935 to measure the surface temperature.
- (6) Three thermocouples located in the IPT upper plenum above the fuel rod flow shroud outlet. These instruments aid in determining temperature gradients in the upper plenum region. The thermocouples are structurally attached to the hanger rod.
- (7) One thermocouple located in the nearly stagnant bypass volume at the midplane of the active fuel length.
- (8) Two thermocouples located in the lower plenum, 0.06 and 0.28 m below the lower support plate, are used to determine the coolant conditions in the lower plenum. The lower thermocouple junction is also below the pressure transducer located in the lower plenum.
- (9) One EG&G Idaho, Inc., pressure transducer (strain post-type) to measure any large IPT overpressure transients. The transducer is located 0.19 m below the lower support plate.

- (10) Two EG&G Idaho, Inc., pressure transducers (strain-post-type) located 0.04 m above the top of the fuel rod shroud and 0.19 m below the lower support plate to measure the pressure changes during the blowdown transient.
- (11) One Kaman pressure transducer (strain-gauge-type) located 0.04 m above the rod shroud outlet to measure the preblowdown and saturated blowdown pressure.
- (12) Two liquid level detectors inside the lower particle screen and one detector inside the lower end of each flow shroud.
- (13) One bidirectional flow turbine located in the downcomer to upper plenum bypass region.

Planned instrumentation for the measurement spools includes:

- (1) A Rosemount resistance temperature detector to measure the preblowdown temperature of the coolant in each spool.
- (2) An exposed Rosemount ribbon thermocouple (Type K) to measure the coolant temperature in each spool during the transient.
- (3) A flush mounted pressure transducer from Precise Sensors, Inc., (bounded strain gauge) to measure the preblowdown and subcooled decompression in each spool.
- (4) A water cooled, stand-off mounted, pressure transducer from Precise Sensors, Inc., (bounded strain gauge) to measure the preblowdown and saturated decompression in each spool.
- (5) A full flow turbine meter with graphite bearings from Flow Technology, Inc., to measure preblowdown coolant velocity to the IPT in the inlet condition spool and during the transient in the hot- and cold-leg spools.

SAS BPP

998 243

- (6) A Ramapo drag disk in the hot- and cold-leg spools to measure the coolant momentum flux during the transient.
- (7) An EG&G Idaho, Inc., three beam gamma densitometer on both the hot- and cold-leg spools to measure coolant density.
- (8) A pressure differential transducer connecting the hot- and cold-leg spools. This device will measure the preblowdown pressure difference across the test train and the spool-to-spool difference during the transient.
- (9) An Endevco accelerometer attached to each blowdown spool to measure the loadings on the gamma densitometer.

Plant instrumentation measurements that will be used in the analysis of the test results are listed in Table VI.

TABLE VI
TEST LOC-5 PLANT INSTRUMENTATION

| <u>Description</u> | <u>Designation</u> |
|-------------------------------------|---------------------|
| Position of Hot Leg Blowdown Valve | VALVbPOSbbLM1101PT |
| Position of Hot Leg Blowdown Valve | VALVbPOSbbLM1102PT |
| Position of Cold Leg Blowdown Valve | VALVbPOSbbLM1103PT |
| Position of Cold Leg Blowdown Valve | VALVbPOSbbLM1104PT |
| Position of Isolation Valve | VALVbPOSbbLM1105PT |
| Position of Isolation Valve | VALVbPOSbbLM1106PT |
| Position of Bypass Valve | VALVbPOSbbLM1107PT |
| Position of Quench Valve | VALVbPOSbbLM1108PT |
| Position of Warm Up Line Valve | VALVbPOSbbLM1116PT |
| Position of Cold Leg Shutoff Valve | VALVbPOSbbLM1118PT |
| Outlet Coolant Pressure Transducer | OUTbPRESbbPT-30bPT |
| Outlet Coolant Flow Transducer | OUTbFLOWbbFT-29bPT |
| Outlet Coolant Temperature | OUTbTEMPbbTT-29bPT |
| Quench Tank Coolant Level | QNCHbLEVbbLT-10bPT |
| Quench Tank Coolant Temperature | QNCHbTMPbbTIC27bPT |
| Quench Coolant Flow Rate | QNCHbFLObbFT-14bPT |
| Blowdown Tank Pressure | BLOWbPRSbbPT-12bPT |
| Blowdown Tank Liquid Level | BLOWbLEVbbLIT17bPT |
| Loop Pressure | SYSpPRESbbPRS10bPT |
| IPT Differential Pressure | IPTbDELbPbbDPR-10PT |
| Loop Flow Rate | LOOPbFLObbFRC-10PT |
| FPDS Gross Gamma Rate Detector 1 | FPDSGAMAbbNUMb01FP |
| FPDS Gross Gamma Rate Detector 2 | FPDSGAMAbbNUMb02FP |
| FPDS Gross Gamma Rate Detector 3 | FPDSGAMAbbNUMb03FP |
| FPDS Gross Neutron Rate | FPDSNEUTbbNEUTRNF |
| Reactor Power NMS-3 30 MW | REACTPOWbbNMS-03PT |
| Reactor Power NMS-4 30 MW | REACTPOWbbNMS-04PT |
| Reactor Power PPS-1 30 MW | REACTPOWbbPPS-01PT |
| Reactor Power PPS-2 30 MW | REACTPOWbbPPS-02PT |
| Transient Rod 1 Position | TRANSRODbbNUMb01PT |
| Transient Rod 2 Position | TRANSRODbbNUMb02PT |
| Transient Rod 3 Position | TRANSRODbbNUMb03PT |
| Transient Rod 4 Position | TRANSRODbbNUMb04PT |

AAS 899

998 245

3. EXPERIMENT OPERATING PROCEDURE

Details of the experiment procedure of Test LOC-5 are discussed in the following sections. Each experiment operating phase and the instrument status requirements are considered individually below. The test consists of the following phases:

- (1) Instrument status check
- (2) Heatup
- (3) Instrument drift checks
- (4) Power calibration
- (5) Preconditioning
- (6) Decay heat build-up
- (7) Blowdown and reflood
- (8) Quench and cooldown.

Nuclear operation will start with the power calibration phase and terminate in the blowdown phase of the transient. Nuclear operation will last approximately six hours duration at a reactor power less than or equal to 26 MW. The specific operating sequence for the test is shown in Table VII and Figure 5.

A representative sample of the liquid in the blowdown tank and in the loop should be taken prior to test operation and immediately after the test for chemical analysis. The samples should be analyzed for nitrogen, oxygen, and hydrogen. Disposition of these samples will be determined at a later time.

OPERATING SEQUENCE FOR TEST LOC-5

| Time Duration (Min or noted) | Peak Rod Power (kW/m) | Anticipated Reactor Power (MW or noted) | Inlet Temperature (K) | Flow Per Shroud (t/s) | System Pressure (MPa) | Comments |
|---------------------------------|--------------------------|--|--------------------------|--------------------------------|--------------------------|--|
| 30 | 0 | 0 | Ambient | 0 | 0.69 | Instrument status check, verify DARS. |
| 30 | 0 | 0 | 366 | 0.4,0.6,0.8,1.0 0.8,0.6,0.4 | 0.69 | Flow balance check with warm line closed. |
| 30 | 0 | 0 | 366 | 0.4,0.6,0.8,1.0 0.8,0.6,0.4 | 0.69 | Flow balance check with warmup line open. |
| 30 | 0 | 0 | 366 | 0.4 | 0.69 | Measurement status check at 366 K inlet temperature. |
| 360 | 0 | 0 | 366 to 590 | 0.4 | 15.51 | Heatup, DARS status checks. |
| 15 | 0 | 0 | 590 | 0.4 | 13.8 to 15.51 | Rod pressure transducer check in steps of 0.34 MPa. |
| 15 | 0 | 0 | 590 | 0.4,0.6,0.8,1.0 | 15.51 | Test train flow turbine calibration with warmup line open. |
| 15 | 0 | 0 | 590 | 1.0,0.8,0.6,0.4 | 15.51 | Flow turbine calibration with warmup line closed. |
| 5 | 0 | 0 | 590 | 0.4 to 1.0 | 15.51 | Return to full flow with warmup line closed. |
| 30 | 0 | 100 (kW) | 590 | 1.0 | 15.51 | Instrument status and drift check zero power offsets taken, transient rods inserted four inches. |
| 7 | 0 to 13 | 100 kW to 6.5 | 590 | 1.0 | 15.51 | Power calibration, ramp 1. |
| 10 | 13 | 6.5 | 590 | 1.0 | 15.51 | Calculation of rod powers |
| 5 | 13 to 22 | 6.5 to 11 | 590 | 1.0 | 15.51 | Power calibration, ramp 2. |
| 10 | 22 | 11 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 4 | 22 to 30 | 11 to 15 | 590 | 1.0 | 15.51 | Power calibration, ramp 3. |
| 10 | 30 | 15 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 5 | 30 to 38 | 15 to 19 | 590 | 1.0 | 15.51 | Power calibration, ramp 4. |
| 10 | 38 | 19 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 4 | 38 to 47 | 19 to 23.5 | 590 | 1.0 | 15.51 | Power calibration, ramp 5. |
| 10 | 47 | 23.5 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 5 | 47 to 53.5 | 23.5 to 25.5 | 590 | 1.0 | 15.51 | Power calibration, ramp 6. |
| 30 | 53.5 | 25.5 | 590 | 1.0 | 15.51 | Calculation of rod powers. |

TABLE VII (continued)

| Time Duration (Min or noted) | Peak Rod Power (kW/m) | Anticipated Reactor Power (MW-or noted) | Inlet Temperature (K) | Flow Per Shroud (l/s) | System Pressure (MPa) | Comments |
|---------------------------------|--------------------------|--|--------------------------|--------------------------|--------------------------|---|
| 30 | 53.5 to 2.37 | 25.5 to 0.1 | 590 | 1.0 | 15.51 | Ramp down power, 1st cycle of preconditioning finished. |
| 10 | 0 | 0.1 | 590 | 1.0 | 15.51 | Prepare for second ramp. |
| 12 | 0 to 22 | 0.1 to 11 | 590 | 1.0 | 15.51 | Power calibration, ramp 7, and 2nd cycle of preconditioning. |
| 5 | 22 | 11 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 9 | 22 to 38 | 11 to 19 | 590 | 1.0 | 15.51 | Power calibration, ramp 8. |
| 5 | 38 | 19 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 9 | 38 to 53.5 | 19 to 25.5 | 590 | 1.0 | 15.51 | Power calibration, ramp 9. |
| 5 | 53.5 | 25.5 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 10 | 53.5 | 25.5 | 590 | 1.0 | 15.51 | Constant power. |
| 30 | 53.5 to 0 | 25.5 to 0.1 | 590 | 1.0 | 15.51 | Ramp power decrease, 2nd cycle of preconditioning. |
| 10 | 0 | 0.1 | 590 | 1.0 | 15.51 | Prepare for third ramp. |
| 12 | 0 to 22 | 0.1 to 11 | 590 | 1.0 | 15.51 | Power calibration, ramp 10, and 3rd cycle of preconditioning. |
| 5 | 22 | 11 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 9 | 22 to 38 | 11 to 19 | 590 | 1.0 | 15.51 | Power calibration, ramp 11. |
| 5 | 38 | 19 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 9 | 38 to 53.5 | 19 to 25.5 | 590 | 1.0 | 15.51 | Power calibration, ramp 12. |
| 5 | 53.5 | 25.5 | 590 | 1.0 | 15.51 | Calculation of rod powers. |
| 10 | 53.5 | 25.5 | 590 | 1.0 | 15.51 | Constant power. |
| 10 s | 53.5 to 40 | 25.5 to 20 | 590 | 1.0 | 15.51 | |
| 5 | 40 | 20 | 590 | 1.0 | 15.51 | |
| 10 s | 40 to 30 | 20 to 15 | 590 | 1.0 | 15.51 | |
| 5 | 30 | 15 | 590 | 1.0 | 15.51 | |
| 10 s | 30 to 20 | 15 to 10 | 590 | 1.0 | 15.51 | |
| 5 | 20 | 10 | 590 | 1.0 | 15.51 | |
| 10 | 20 to 0 | 10 to 0 | 590 | 1.0 | 15.51 | |
| 10 | 0 | 0 | 590 | 1.0 | 15.51 | Prepare for 4th cycle (decay heat buildup). Remove cladding screws. |

TABLE VII (continued)

| <u>Time Duration</u> <u>(Min or noted)</u> | <u>Peak Rod</u> <u>Power (kW/m)</u> | <u>Anticipated Reactor</u> <u>Power (MW-or noted)</u> | <u>Inlet</u> <u>Temperature (K)</u> | <u>Flow Per</u> <u>Shroud (l/s)</u> | <u>System</u> <u>Pressure (MPa)</u> | <u>Comments</u> |
|---|--|--|--|--|--|---|
| 30 | 0 to 53.5 | 25.5 | 590 | 1.0 | 15.5i | Ramp power increase, 4th cycle. |
| 90 | 53.5 | 25.5 | 590 | 1.0 | 15.5i | Decay heat buildup, instrument status checks, initial conditions checked. |
| 50 (s) | 53.5 to 0 | 25.5 to 0 | - | - | - | Transient sequence commences with reactor power controlled by transient rod servo controller. |
| 240 | 0 | 0 | 370 | 1.0 | 0.1 | Cooldown phase. |

24

998 24




Fig. 5 Operating sequence for LOC-5

Prior to the Test LOC-5 a REDCOR checkout of the blowdown transient sequence described in Section 3.7 will be conducted. This test may be performed before the test train is installed. The objectives are to:

- (1) Provide a checkout of the servo control system
- (2) Determine the proper REDCOR timing sequence to ensure that blowdown events are initiated as specified.

The timing of each event (valve opening and closing, simulated reactor power and power demand function, and transient rod position) should be recorded to ensure that the sequence is properly set. This test may be deleted if the Thermal Fuels Behavior Program (TFBP) LOCA Project Engineer or Management is satisfied that the blowdown transient can be programmed as specified.

3.1 Instrument Status Check

To monitor the experiment and to meet test objectives, it is necessary that certain instrumentation be operable throughout the experiment or during specific phases of the experiment. The loss of a critical instrument will require test procedures to be suspended. Therefore, after data acquisition and reduction system DARS checkout is completed, measurement status checks are to be made (a) prior to heatup at ambient conditions, (b) during heatup, (c) after achieving critical reactor conditions, unless requested otherwise by the Experiment Specification and Analysis (ES&A) representative of Fuel Research Division. Checklists, which are to be incorporated in the experiment operating procedure and detailed operating procedure, will be completed during the status checks (Appendix A). Certification that each instrument is within range must be made by the LWRD Representative or his alternate. If the readings are not within range, or at any time during the test there is an apparent malfunction in an instrument or data channel, remedial actions must be completed or the ES&A representative's approval must be obtained in order to

continue test operation. If it is determined that an instrument has failed or that repairs can be made only by removing the test train, test procedure will be suspended pending a decision by the LOCA Project Engineer, TFBP Management, and appropriate Directorate management.

Prior to any data acquisition, the PBF/DARS output will be verified by inputting voltages to the low level amplifiers or in accordance with a checklist to be supplied by the Instrument and Data Systems Section. This checklist will be incorporated in the experiment operating procedures and will be signed off by the supervisor of the Instrument and Data Section or his alternate prior to loop heatup.

The PBF/DARS readiness for test will be verified by performing the following:

- (1) Run the seven Teledyne System Tests and the PDP-11/05 processor diagnostics and verify the successful completion of each.
- (2) Introduce a five step voltage signal (0%, 25%, 50%, 75%, and 100%) of the full-scale measurement range into all active inputs via the calibration bus of the data system low-level amplifiers.
- (3) Record the calibration voltages on each of the data acquisition systems.
- (4) Reduce the calibration data from the DARS for all active channels. Produce data tapes and verification plots for review by the data integrity review committee (DIRC).

During the cold hydrostat test an instrument status check at pressures of 10%, 20%, 30%, . . . , 100%, 90%, 80%, . . . , 10% of the 15.51 MPa system pressure will be performed as follows:

- (1) Allow the system to come to equilibrium.
- (2) Obtain a DARS printout of measurement data and statistics while simultaneously recording the Heise gauge pressure at each pressure step.

In the event of a DARS channel failure, permission must be obtained from the supervisor of the Instrumentation and Data Section or his alternate before the failed channel can be changed and channels must be reverified. In addition, any channels being doubly recorded on the surveillance system channel electronics cannot be changed after verification. A posttest integrated data systems calibration will be performed after reactor building reentry is permitted.

3.2 Heatup Phase

Immediately prior to loop heatup or during heatup at a loop temperature less than 370 K, a flow balance check will be performed. With the warmup line closed, the flow as indicated by a test train turbine should be increased from 0.4 l/s to as high as possible and not to exceed 1.0 l/s and then reduced to 0.4 l/s. The warmup line should be opened and the sequence should be repeated. Readings should then be recorded as specified in the flow balance checklist, which should be incorporated in the experiment operating procedure. This checklist is given in Appendix A, Table A-IV. The information will be used to determine the bypass flow ratios for comparison with test train design specifications. In the event of unexpected bypass flow ratios, as determined by the LOCA Project Engineer, test procedure will be suspended pending resolution of discrepancies by the LOCA Project Engineer, TFBP Management and appropriate Directorate management. The flow indicated by the test train turbines should then be set to the flows stipulated in Table VII and the heatup continued.

998 253

SCS 8PP

When the loop coolant temperature has reached about 540 K the reactor may be brought to criticality, if deemed necessary, and then to about 2 MW until the coolant inlet temperature reaches the desired level of 590 K. Reactor shutdown is required before proceeding.

During heatup an instrument status check shall be performed at 5 equispaced temperatures by obtaining a DARS printout of measurement data and statistics while simultaneously recording Heise gauge pressure at each step. The DIRC will review the following during this testing period:

- (1) Instrument status
- (2) DARS status
- (3) Data system changes
- (4) Flow verification and drift check data.

After obtaining a coolant temperature of 590 K and pressure of 13.8 MPa, the system pressure will be increased in steps of 0.34 MPa. A DARS printout of measurement data and statistics to check and calibrate the system pressure transducers will be obtained at each step. System pressure will be re-established at 15.51 MPa for the remainder of the heatup following the pressure transducer checkout.

The loop and test train flow meters will be intercalibrated at a constant inlet temperature and pressure by increasing the test flow rates from 0.4 l/s to 1.0 l/s with the warmup line open, and then decreasing the flow to 0.4 l/s with the warmup line closed. During this flow calibration, instruments will be checked for possible undesirable temperature and flow sensitivities.

3.3 Instrument Drift Recording and Status Check

Data channels will be recorded for at least 30 minutes to establish instrument drift rates. This recording should be completed

998 254

after heatup at stable system conditions of 590 ± 1 K inlet temperature, 15.51 ± 0.14 MPa IPT pressure, and 1000 ± 15 cm³/s flow through each shroud.

3.4 Power Calibration Phase

After the reactor is critical at about 100 kW to 2 MW and just prior to beginning the power calibration cycle the transient rods should be inserted four inches into the core. The reactor critical measurements check should then be completed.

Power calibration will be performed during the three preconditioning cycles. It will provide data to intercalibrate the test rod powers determined by thermal-hydraulic measurements with reactor power and data from the self-powered neutron detectors mounted on the test train. After the intercalibration, the reactor can be operated with reference to the calibrated SPNDs to provide the desired fuel rod power.

The calibration phase of the experiment will be initiated by establishing the coolant pressure, temperature, and flow rate at the predetermined values of Table VII. To perform the calibration, the reactor power will be increased to a known level, the system allowed to reach equilibrium (~5 minutes), and the test rod power and neutron detector outputs recorded. This procedure will be repeated at a number of power levels up to a maximum reactor power of approximately 25.5 MW and maximum rod power of 53.5 kW/m. The maximum power ramp rate for the calibration phase of the test is 2 kW/m per minute.

During power calibration an instrument status check shall be performed by obtaining a DARS printout of measurement data and statistics while simultaneously recording the Heise gauge pressure at each step in the power calibration. DIRC review of the following will be accomplished during the power calibration and preconditioning phase of testing.

- (1) Instrument status
- (2) Power calibration data
- (3) Drift check data
- (4) Data system configuration and calibration status

The figure-of-merit, relating fuel rod peak power to driver core power, has been calculated to be 2.37 kW/m/MW. The preliminary results of Test LOC-3 determined the figure-of-merit to be 2.0. This value will be compared with the figure-of-merit determined during the test. In the event of a large discrepancy between calculated and measured figure-of-merit, as determined by the LOCA Project Engineer, test procedure will be suspended pending resolution of the discrepancy by the LOCA Project Engineer and TFBP Management.

3.5 Preconditioning Phase

The four fuel rods will be preconditioned by cycling the power to promote fuel pellet cracking and restructuring and to allow the initiation of pellet-cladding mechanical interaction to stabilize. A ramp rate of 2 kW/m per minute will be used with constant peak power levels of 53.5 kW/m for 10 to 30 minutes and zero to 100 kW reactor power for 10 minutes between the cycles.

3.6 Decay Heat Buildup Phase

After completion of the preconditioning phase the reactor power should be increased, at a corresponding fuel rod power ramp rate of 2 kW/m per minute, to approximately 25.5 MW, or whatever is necessary (maximum of 26.5 MW) to provide a fuel rod peak power of 53.5 kW/m, and held at that power for approximately 90 minutes. This length of time is necessary to build up approximately 78% of the maximum possible decay heat in the rods. If the reactor is shut down during the decay heat buildup, this phase will have to be repeated.

Approximately 15 minutes before blowdown, the reactor power will be switched to transient rod servo-control (transient rods inserted 4 inches into the bottom of the core region).

3.7 Blowdown and Reflood Phase

The specific steps of the blowdown phase are provided in Table VIII. Immediately prior to blowdown, readings should be taken from the quench and blowdown tank transducers as specified in Appendix A Table A-V. After establishing the required initial conditions of the Table VII, and approximately 20 seconds before blowdown, the warmup line will be shut by the reactor operator and the test rod flows reset to 1.0 l/s. The TFBP Project Engineer will then verify proper setting of all initial conditions before the transient is initiated.

The blowdown sequence will then be initiated. The reactor power will be controlled with the transient rods (TR) during the blowdown, as detailed in Table VIII and Figure 6. The TR servo-controller will be in the steady state mode of operation during the entire test. During blowdown the power demands will be controlled by the function generator which is interfaced with the TR servo-control system. The function generator will be started at the appropriate time by REDCOR.

Proper designation of the REDCOR-timed sequence is extremely important to ensure that the timed events occur as specified. The PBF Operations Branch will determine offsets to be applied for each step so as to ensure the correct timed sequence.

After 70 s into blowdown when the lower plenum pressure is at approximately 0.45 MPa, the reflood portion of the test will begin as listed in Table IX. The controlled reflood is performed by injecting the coolant from the quench tank through the reflood system directly into the IPT upper head, down the center hanger rod into the plenum volume beneath the lower particle screen. System operation involves:

- (1) filling the lower plenum to the bottom of the active fuel as soon

998 257

025 899

TABLE VIII
PROGRAMMING AND MONITORING SYSTEM CONTROLLED EVENT SEQUENCE

| Step | Estimated Time REDCOR Signal Is Initiated (s)(a) | Time Event Is Initiated (s) | Loop Bypass Valve(b) | Isolation Valve(c) | Hot Leg Blowdown Valves(d) | Cold Leg Blow- down Valves(e) | Quench Water Valve(f) | Warm-up Line Valve(g) | Cold Leg Shutoff Valve(h) | Comments |
|---------|--|--------------------------------|-------------------------|-----------------------|-------------------------------|----------------------------------|-----------------------------|-----------------------------|---------------------------------|---|
| Initial | -- | -- | X(i) | 0 | X | X | X | 0 | 0 | Cladding scram set points turned off. |
| 1 | -- | -20.0 | X | 0 | X | X | X | X | 0 | Operator closes warmup line and verifies test rod coolant flow to 1.0 l/s per shroud. Action is verified by TFBP Project En- gineer before in- itiation of the transient. |
| 2 | -2.0 | -2.0 | X | 0 | X | X | X | X | 0 | REDCOR initiates function gener- ator routine. |
| 3 | -0.07 | 0.00 | 0 | X | X | X | X | X | 0 | Isolate loop and open bypass valve. |
| 4 | -0.03 | 0.10 | 0 | X | X | 0 | X | X | 0 | Open cold leg valves. |
| 5 | 0.00 | 2.50 | 0 | X | X | 0 | X | X | 0 | Maintain 100% of reactor power. |
| 6 | 2.50 | 2.80 | 0 | X | X | 0 | X | X | 0 | Linearly reduce reactor power to 25.50% in 0.3 s. |

33

998 258

TABLE VIII (continued)

| Step | Estimated Time REDCOR Signal Is Initiated (s) ^(a) | Time Event Is Initiated (s) | Loop Bypass Valve ^(b) | Isolation Valve ^(c) | Hot Leg Blowdown Valves ^(e) | Cold Leg Blowdown Valves | Quench Water Valve ^(f) | Warm-up Line Valve ^(g) | Cold Leg Shutoff Valve ^(h) | Comments |
|------|--|-----------------------------|----------------------------------|--------------------------------|--|--------------------------|-----------------------------------|-----------------------------------|---------------------------------------|---|
| 7 | 2.80 | 2.80 | 0 | X | X | 0 | X | X | 0 | Linearly reduce reactor power to 12.75% in 2.2 s. |
| 8 | 5.00 | 5.00 | 0 | X | X | 0 | X | X | 0 | Linearly reduce reactor power to 7.95% in 5.0 s. |
| 9 | 10.00 | 10.00 | 0 | X | X | 0 | X | X | 0 | Linearly reduce reactor power to 6.80% in 2.0 s. |
| 10 | 12.00 | 12.00 | 0 | X | X | 0 | X | X | 0 | Linearly reduce reactor power to 6.37% in 8.0 s. |
| 11 | 20.00 | 20.00 | 0 | X | X | 0 | X | X | 0 | Maintain reactor power at 6.37%. |
| 12 | 50.00 | 50.10 | 0 | X | X | 0 | X | X | 0 | Scram reactor. |
| 13 | 70.00 | 70.00 | 0 | X | X | X | X | X | 0 | Reflood cycle. |
| 14 | 240 | 240 | 0 | X | 0 | X | 0 | X | X | Quench. |

(a) Times are estimated for REDCOR signal. Final signal specification will be determined by the PBF Operations Branch.

(b) VAL VbPOSbbLM1107PT

(c) VAL VbPOSbbLM1105PT and VAL VbPOSbbLM1106PT

(d) VAL VbPOSbbLM1101PT and VAL VbPOSbbLM1102PT

(e) VAL VbPOSbbLM11RC1PT and VAL VbPOSbbLM11RC2PT

(f) VAL VbPOSbbLM1108PT

(g) VAL VbPOSbbLM1116PT

(h) VAL VbPOSbbLM1118PT

(i) X indicates closed, 0 indicates open.

998
259




Fig. 6 Reactor power variation with time during the transient.

POOR ORIGINAL

998
2690

TABLE IX

REFLOOD RATES FOR TEST LOC-5

| | <u>Initiation Time (s)</u> | <u>Termination Time (s)</u> |
|---|----------------------------|-----------------------------|
| Initial reflood high flow rate (1.58 l/s) | 70 | 75 |
| Final reflood low flow rate (0.19 l/s) | 75 | > 240 |

005 844

998 261

as possible, within 5 seconds at a rate of 1.58 l/s and maintaining this level prior to reflood of the fuel, and (2) providing the constant cold reflood rate to the flow shrouds at a rate of 0.086 l/s. The reflood coolant temperature will be approximately 311 K (100°F) when entering the IPT through the upper head penetration.

3.8 Quench and Cooldown Phase

After 240 seconds, posttest quench cooling water heated to about 366 K will commence with the mass flow rate sized at 4 l/s for 60 seconds.

After the quench phase, cooling water will be pumped from the storage tank provided by the demineralization pump and the quench tank will be pressurized at 1.03 MPa for 60 s of quench flow. Beyond this time, the cooling water will be reduced to 0.4 l/s. The flow rate can be adjusted to keep the cladding surface temperature below 590 K. Longer term cooling may be provided if necessary by the existing flow loop after reconnection to the IPT.

3.9 Shutdown and Abnormal Test Termination Requirements

The test will be shutdown if a failure of all the system pressure measurements occurs. The test may also be terminated by the responsible LWR Fuel Research Division ES&A representative if there is no more useful data to be gained by continuing operation.

The electronics to initiate an automatic reactor scram in the event of unexpected cladding film boiling will be used for Test LOC-5. The system will be installed for the power calibration, preconditioning, and decay heat buildup phases, and must be removed before the blowdown transient is initiated. The circuit should scram the reactor if cladding thermocouples CLAD934b1b19+0bb01 and CLAD808b2b19+0bb02 measures 700 K. A 2-second delay in scram should be included to account for signal noise.

In the event the TR servo-controller malfunctions at any time while in operation the controller must be programmed to fully insert the transient rods into the core.

In case of unexpected cladding temperatures in excess of 1700 K at any time during the transient, the quench system will be activated based on an average temperature computed automatically from thermocouple measurements on each test rod.

505 8PP

998 263

4. DATA ACQUISITION AND REDUCTION REQUIREMENTS

Instrumentation displays in the PBF/DARS will identify the fuel rod, flow shroud, test train, spoolpiece, and plant instruments according to the identifiers in Tables X through XIII. Prior to each nuclear operation, it will be verified that through data are being recorded and are retrievable.

4.1 Data Acquisition Requirements

The data channels should be set to record the data based on the requirements of Tables X through XIII. All of the narrow-band DARS channels should be available for display on the Vector General. The surveillance system is an acceptable backup system. The PBF/DARS will record data during the cold hydrostatic pressure check, the flow calibration, the heatup phases, during all nuclear operation, and will be left on until the loop has been depressurized after the blowdown. The surveillance system (SS) need not record data during heatup and 30 minutes after test termination unless requested by the ES&A representative.

Prior to heatup, the PBF/DARS should be checked as specified in the Integrated Data System Calibration Procedure (IDSCP), as supplied by the Data Systems Test Cognizant Project Engineer^b. Following the IDSCP check, it should be verified that all recorders are recording data as specified in the Data Recording Verification Procedure^a. After all discrepancies have been corrected and heatup initiated, the surveillance system recorders may be turned off unless otherwise requested by the ES&A representative. The DARS should

- a. Prior to nuclear operation and the blowdown, it should be verified that data are being recorded.
- b. All recorders should be monitored when in recording mode in a manner determined by the Data System Branch.

998 264

TABLE X
TEST LOC-5 FUEL TRAIN INSTRUMENT IDENTIFICATION, DATA CHANNEL RECORDING,
AND DISPLAY REQUIREMENTS

| Measurement | Instrument Type | Location* | Rod Number | Instrument Identifier ^b | Recording Ranges | Minimum Frequency Recording Required (Hz) ^c |
|-------------------------------------|----------------------------------|---|------------|------------------------------------|------------------|--|
| Fuel Rod | | | | | | |
| Fuel centerline temperature | W5%Re/W26%Re thermocouple | 0.130 m | 1 | TFCL934b1b13bbTC01 | 300 to 2500 K | 10 |
| Cladding surface temperature | Type K thermocouple | 0.130 m | 3 | TFCL935b3b13bbTC03 | 300 to 1500 K | 10 |
| | | 0.186 m - 0° | 1 | CLAD934b1b19+0bb01 | | 10 |
| | | 0.186 m - 180° | 1 | CLAD934b1b19+18001 | | 10 |
| | | 0.236 m - 90° | 1 | CLAD934b1b24+90b01 | | |
| | | 0.236 m - 270° | 1 | CLAD934b1b24+27001 | | |
| | | 0.186 m - 0° | 2 | CLAD839b2b19+0bb02 | | |
| | | 0.186 m - 180° | 2 | CLAD839b2b19+18002 | | |
| | | 0.236 m - 90° | 2 | CLAD839b2b24+90b02 | | |
| | | 0.236 m - 270° | 2 | CLAD839b2b24+27002 | | |
| | | 0.186 m - 0° | 3 | CLAD935b3b19+0bb03 | | |
| | | 0.186 m - 180° | 3 | CLAD935b3b19+18003 | | |
| | | 0.236 m - 90° | 3 | CLAD935b3b24+90b03 | | |
| | | 0.236 m - 270° | 3 | CLAD935b3b24+27003 | | |
| | | 0.186 m - 0° | 4 | CLAD912b4b19+0bb04 | | |
| | | 0.186 m - 180° | 4 | CLAD912b4b19+18004 | | |
| | | 0.236 m - 90° | 4 | CLAD912b4b24+90b04 | | |
| 0.236 m - 270° | 4 | CLAD912b4b24+27004 | | | | |
| Plenum temperature | Type K thermocouple | Fuel rod plenum | 1 | PLNMbTMPbb934bbb01 | 300 to 1100 K | 10 |
| Plenum pressure | Kaman 17-MPa pressure transducer | Fuel rod plenum | 2 | PLNMbTMPbb839bbb02 | 0 to 18 MPa | 10 |
| | | | 3 | PLNMbTMPbb935bbb03 | | |
| | | | 4 | PLNMbTMPbb912bbb04 | | |
| | | | 1 | RODbPRESbb934bbb01 | | |
| Cladding axial strain | LVDT | Inlet end of rod | 2 | RODbPRESbb839bbb02 | -12 to 12 mm | 100 |
| | | | 3 | RODbPRESbb935bbb03 | | |
| | | | 4 | RODbPRESbb912bbb04 | | |
| | | | 1 | CLADb0SPbb934bbb01 | | |
| FLOW SHROUD | Flux wire 99.5% Al and 0.5% Co | One on the outside of each flow shroud (180°) and the hanger rod (236°) | 2 | CLADb0SPbb839bbb02 | | |
| | | | 3 | CLADb0SPbb935bbb03 | | |
| | | | 4 | CLADb0SPbb912bbb04 | | |
| | | | 1 | FLUX934b1b180bbb01 | | |
| Fuel rod power profile ^d | Flux wire 99.5% Al and 0.5% Co | One on the outside of each flow shroud (180°) and the hanger rod (236°) | 2 | FLUX839b2b180bbb02 | | |
| | | | 3 | FLUX935b3b180bbb03 | | |
| | | | 4 | FLUX912b4b180bbb04 | | |
| | | | 1 | FLUXHR0bb236bbb0R | | |

- a. All elevations are measured from axial midplane of the fuel stack. The positive direction is with the coolant flow. Radial orientations are defined by Figure 1.
- b. b denotes blank.
- c. Minimum recording frequency is calculated from required instrument response time. Final designation of the instrument response time will be completed by the Instrument and Data section.
- d. Not recorded.

POOR ORIGINAL

ADS BPP

TABLE X (continued)

| Measurement | Instrument Type | Location ^a | Rod Number | Instrument Identifier ^b | Recording Ranges | Minimum Frequency Recording Required (Hz) ^c |
|----------------------------------|---------------------------------|------------------------|---------------------------|------------------------------------|------------------|--|
| Flow Shroud | | | | | | |
| Shroud coolant flow | Bidirectional turbine flowmeter | Lower shroud extension | 1 | FLOWRATEbbINLETb01 | -2.5 to 1.5 l/s | 100 |
| | | | 2 | FLOWRATEbbINLETb02 | | |
| | | | 3 | FLOWRATEbbINLETb03 | | |
| | | | 4 | FLOWRATEbbINLETb04 | | |
| Shroud liquid level | Liquid level detectors | Lower shroud extension | 1 | FLOWRATEbbOUTLET01 | OFF=0, ON=1 | 10 |
| | | | 2 | FLOWRATEbbOUTLET02 | | |
| | | | 3 | FLOWRATEbbOUTLET03 | | |
| | | | 4 | FLOWRATEbbOUTLET04 | | |
| Outer shroud wall temperature | Type K thermocouple | -0.120 m - 225° | 1 | SHRDbLEVbbINLETb01 | 300 to 1200 K | 10 |
| | | | 2 | SHRDbLEVbbINLETb02 | | |
| | | | 3 | SHRDbLEVbbINLETb03 | | |
| | | | 4 | SHRDbLEVbbINLETb04 | | |
| Bulk coolant temperature | Type K thermocouple | 0 m - 225° | 2 | SHRDbTMPbb000bb02 | 339 to 820 K | 10 |
| | | | 2 | SHRDbTMPbb+120bb02 | | |
| | | | 3 | SHRDbTMPbb-120bb03 | | |
| | | | 3 | SHRDbTMPbb000bb03 | | |
| | | | 3 | SHRDbTMPbb+120bb03 | | |
| | | | 2 | BULKbTMPbb-120bb02 | | |
| | | | 2 | BULKbTMPbb000bb02 | | |
| | | | 2 | BULKbTMPbb+120bb02 | | |
| | | | 3 | BULKbTMPbb-120bb03 | | |
| | | | 3 | BULKbTMPbb000bb03 | | |
| | | | 3 | BULKbTMPbb+120bb03 | | |
| | | | Inlet coolant temperature | Type K thermocouple | | |
| 2 | INLTbTMPbb839bbb02 | | | | | |
| 3 | INLTbTMPbb935bbb03 | | | | | |
| 4 | INLTbTMPbb912bbb04 | | | | | |
| Outlet coolant temperature | Type K thermocouple | +0.439 m - 135° | 1 | OUTbTEMPbb934bbb01 | 339 to 820 K | 10 |
| | | | 2 | OUTbTEMPbb839bbb02 | | |
| | | | 3 | OUTbTEMPbb935bbb03 | | |
| | | | 4 | OUTbTEMPbb912bbb04 | | |
| Coolant differential temperature | Type K thermocouple pair | +0.439 m - 225° | 1 | DELbTEMPbb45bbb01 | 0 to 15 K | 10 |
| | | | 1 | DELbTEMPbb225bbb01 | | |
| | | | 2 | DELbTEMPbb45bbb02 | | |
| | | | 2 | DELbTEMPbb225bbb02 | | |
| | | | 3 | DELbTEMPbb45bbb03 | | |
| | | | 3 | DELbTEMPbb225bbb03 | | |
| | | | 4 | DELbTEMPbb45bbb04 | | |
| | | | 4 | DELbTEMPbb225bbb04 | | |
| | | | 4 | DELbTEMPbb45bbb04 | | |
| | | | 4 | DELbTEMPbb225bbb04 | | |
| | | | 4 | DELbTEMPbb45bbb04 | | |
| | | | 4 | DELbTEMPbb225bbb04 | | |

a. All elevations are measured from axial midplane of the fuel stack. Radial orientations are defined by Figure 1.

b. b denotes blank.

c. Minimum frequency is calculated from required instrumentation response time. Final designation of the instrument response time will be completed by the Instrument and Data Section.

POOR ORIGINAL

998 266

105 308

005

TABLE XI

TEST LOC-5 TEST TRAIN INSTRUMENT IDENTIFICATION, DATA CHANNEL RECORDING,
AND DISPLAY REQUIREMENTS

| Measurement | Instrument Type | Location ^a | Instrument Identifier | Recording Ranges | Minimum Recording Frequency Required (Hz) |
|---------------------------------|---------------------------------|--|-----------------------|------------------|---|
| <u>Test Train</u> | | | | | |
| IPT liquid level | Liquid level detector | Lower particle screen | IPTbLEVLbbNO.1bLTT | OFF=0, ON=1 | 10 |
| Bypass temperature | Type K thermocouple | Hanger rod, lower particle screen | IPTbLEVLbbNO.2bLTT | OFF=0, ON=1 | 10 |
| | | Hanger rod, fuel midplane | BYPbTEMPbbNO.LTTLC | 300 to 800 K | 10 |
| | | Hanger rod, shroud outlet plus 50 mm | BYPbTEMPbbNO.2bTT | | |
| | | Hanger rod, IPT outlet | BYPbTEMPbbNO.3bUTT | | |
| | | Hanger rod between shroud & IPT outlet | BYPbTEMPbbNO.5bUTT | | |
| Lower plenum temperature | Type K TC | Lower support plate | PLATbTMPbbbbbLTT | 300 to 800 K | 10 |
| Neutron flux No. 1 ^b | SPND | -0.343 m | NEUTbFLXbb-34.3bTT | 0 to 160 nA | 10 |
| No. 2 | | -0.229 m | NEUTbFLXbb-22.9bTT | | |
| No. 3 | | -0.114 m | NEUTbFLXbb-11.4bTT | | |
| No. 4 | | 0.0 | NEUTbFLXbbb0.0bTT | | |
| No. 5 | | +0.142 m | NEUTbFLXbb+14.2bTT | | |
| No. 6 | | +0.229 m | NEUTbFLXbb+22.9bTT | | |
| No. 7 | | +0.343 m | NEUTbFLXbb+34.3bTT | | |
| System pressure | EG&G, Idaho, Inc., 69 MPa PXD | Center tie rod, below shroud inlets | SYSbPRESbb69EGbLTT | 0 to 69 MPa | 100 |
| System coolant pressure | EG&G, Idaho, Inc., 17 MPa PXD | Center tie rod, below shroud inlets | SYSbPRESbb17EGbLTT | 0 to 18 MPa | 100 |
| System coolant pressure | EG&G, Idaho, Inc., 17 MPa PXD | Hanger rod, above shroud outlets | SYSbPRESbb17EGbUTT | 0 to 18 MPa | 100 |
| System coolant pressure | Kaman 17 MPa PXD | Hanger rod, above shroud outlets | SYSbPRESbb17KAbUTT | 0 to 18 MPa | 100 |
| Gamma flux No. 1 ^c | SPGD | -0.229 m | GAMAbFLXbb-22.9bTT | 0 to 100 nA | 10 |
| Gamma flux No. 2 | SPGD | 0.0 | GAMAbFLXbbb0.0bTT | 0 to 100 nA | 10 |
| Gamma flux No. 3 | SPGD | +0.229 m | GAMAbFLXbb+22.9bTT | 0 to 100 nA | 10 |
| Controlled bypass turbine | Bidirectional turbine flowmeter | Upper plenum filler piece | FLOWRATEbbCONTBYTT | -40 to 12 r/s | 100 |

- a. All elevations are measured from axial midplane of the fuel stack.
- b. Include a channel for gamma compensation and measure the "sign" or direction of the current.
- c. Include a channel for gamma compensation.

42

998 267

TABLE XII

TEST LOC-5 HOT LEG, COLD LEG, AND INITIAL CONDITIONS POOL PIECES INSTRUMENT IDENTIFICATION
DATA CHANNEL RECORDING, AND DISPLAY REQUIREMENTS

| Measurement | Instrument Type | Instrument Identifier ^a | Recording Ranges | Minimum Recording Frequency Required (Hz) ^b |
|---|-----------------------------------|--|--|--|
| Coolant volumetric flow rate | Bidirection turbine flowmeter | ICSVFLOWbbFE05SPIC CLSVFLOWbbFE06SPCL HLSVFLOWbbFE09SPHL | 0 to 20 l/s 0 to 100 l/s | 100 |
| Momentum flux | Drag disk | CLMOMFLXbbFE07SPHL ICMOMFLXbbFE10SPIC | -10 to 10 l/s 0 to 40000 kg/m-s ² 0 to 2000 kg/m-s ² | 100 |
| Steady-state coolant temperature | RTD | HLMOMFLXbbFE08SPCL ICSSTEMPbbTE20SPIC CLSSTEMPbbTE22SPCL HLSSTEMPbbTE23SPCL | 280 to 650 K | 10 |
| Transient coolant temperature | Type K thermocouple | ICTCTEMPbbTE21SPIC CLTCTEMPbbTE24SPCL HLTCTEMPbbTE25SPHL | 280 to 650 K | 10 |
| Subcooled coolant pressure (flush mounted) | Pressure transducer | ICPRESSFbbPE08SPIC CLPRESSFbbPE10SPCL HLPRESSFbbPE12SPHL | 0 to 21 MPa | 100 |
| Saturated coolant pressure | Pressure transducer, water cooled | ICPRESSWbbPE09SPIC CLPRESSWbbPE11SPCL HLPRESSWbbPE13SPHL | 0 to 21 MPa | 100 |
| Coolant pressure differential (hot to cold leg) | Pressure transducer | DELPCLHLbbDPE-0SHL | 0 to 1 MPa | 100 |
| Coolant density | Gamma densitometer | CLDENSUPbbDENS1UCL CLDENSCEbbDENS1CCL CLDENSLOBbbDENS1LCL HLDENSUPbbDENS2UHL HLDENSCEbbDENS2CHL HLDENSLOBbbDENS2LHL | 0 to 800 kg/m ³ | 100 |
| Henry nozzle PXD | Pressure difference strain gage | HENRYPXDbbFE11-1PT HENRYPXDbbFE11-2PT HENRYPXDbbFE11-3PT HENRYPXDbbFE11-4PT | 0 to 12 MPa | 100 |
| Sample pipe temperature ^c | Type K thermocouple | FPbTEMPbbbPIPE01FP FPbTEMPbbbPIPE02FP FPbTEMPbbbPIPE03FP FPbTEMPbbbPIPE04FP FPbTEMPbbbPIPE05FP FPbTEMPbbbPIPE06FP FPbTEMPbbbPIPE07FP FPbTEMPbbbPIPE08FP FPbTEMPbbbPIPE09FP | 0 to 800 K | 10 |
| Densitometer temperature | Type K thermocouple | CLbDNTMPbbDENTC1CL CLbDNTMPbbDENTC2CL CLbDNTMPbbDENTC3CL HLbDNTMPbbDENTC1HL HLbDNTMPbbDENTC2HL HLbDNTMPbbDENTC3HL | 280 to 650 K | 10 |

a. b denotes blank

b. Minimum frequency is calculated from required instrumentation response time. Final designation of the instrument response time will be completed by the Instrument and Data Section.

c. Not required.

POOR ORIGINAL

998 268

TABLE XIII

TEST LOC-5 PLANT INSTRUMENT IDENTIFICATION, DATA CHANNEL RECORDING,
AND DISPLAY REQUIREMENTS

| Measurement | Instrument Type | Location | Instrument Identifier | Recording Ranges | Minimum Recording Frequency Required (Hz) |
|----------------------------------|----------------------------------|---|--|--------------------------------|---|
| Valve position | Limit switches | Cold-leg Cold-leg Hot-leg Hot-leg Bypass Isolation Isolation Quench Warmup line Cold leg shutoff | VALVbPOSbbLM1RC1PT VALVbPOSbbLM1RC2PT VALVbPOSbbLM1101PT VALVbPOSbbLM1102PT VALVbPOSbbLM1107PT VALVbPOSbbLM1105PT VALVbPOSbbLM1106PT VALVbPOSbbLM1108PT VALVbPOSbbLM1109PT VALVbPOSbbLM1110PT | Open, closed | 1000 |
| Outlet coolant pressure | Transducer | Outlet | OUTbPRESbbPT-30bPT | 0 to 21 MPa | 100 |
| Outlet coolant flow | Transducer | Outlet | OUTbFLOWbbFT-29bPT | 0 to 20 ℓ/s | 10 |
| Outlet coolant thermocouple | Thermocouple | Outlet | OUTbTEMPbbTT-29bPT | 0 - 700 K | 10 |
| Quench tank coolant level | Level detector | Quench tank | QNCHbLEVbbLT-10bPT | 0 to 100% | 10 |
| Quench tank coolant thermocouple | Thermocouple | Quench tank | QNCHbTMPbbTIC27bPT | 0 to 500 K | 10 |
| Quench tank flow | Turbine meter | Quench tank | QNCHbFLObbFT-L4bPT | 0 to 5 ℓ/s | 10 |
| Blowdown tank liquid level | Level detector | Blowdown tank | BLOWbLEVbbLIT17bPT | 0 to 100% | 10 |
| Blowdown tank PXD | Pressure transducer | Blowdown tank | BLOWbPRsbbPT-12bPT | 0 to 1 MPa | 10 |
| Transient rod position 1 | LVDT | TR drive 1 | TRANSRODbbNUMb01PT | 0 to 2 m | 100 |
| Transient rod position 2 | LVDT | TR drive 2 | TRANSRODbbNUMb02PT | 0 to 2 m | 100 |
| Transient rod position 3 | LVDT | TR drive 3 | TRANSRODbbNUMb03PT | 0 to 2 m | 100 |
| Transient rod position 4 | LVDT | TR drive 4 | TRANSRODbbNUMb04PT | 0 to 2 m | 100 |
| Gross gamma rate | No.1 NaI gamma detector | FPDS | FPDSGAMAbbNUMb01FP | 10 to 10 ⁶ counts/s | 10 |
| Gross gamma rate | No.2 NaI gamma detector | FPDS | FPDSGAMAbbNUMb02FP | | |
| Gross gamma rate | No.3 NaI gamma detector | FPDS | FPDSGAMAbbNUMb03FP | | |
| Gross neutron rate | BF ₃ neutron detector | FPDS | FPbNEUTbbbNEUTRNFP | | |
| Core power (30 MW) | NMS-3 Ionization chamber | Reactor vessel wall | REACbPOWbbNMS-03PT | 0 to 30 MW | 10 |
| Core power (30 MW) | NMS-4 Ionization chamber | Reactor vessel wall | REACbPOWbbNMS-04PT | 0 to 30 MW | 10 |
| Core power (30 MW) | PPS-1 Ionization chamber | Reactor vessel wall | REACbPOWbbPPS-01PT | 0 to 30 MW | 10 |
| Core power (30 MW) | PPS-2 Ionization chamber | Reactor vessel wall | REACbPOWbbPPS-02PT | 0 to 30 MW | 10 |
| System pressure | Heise pressure gauge | Plant | SYSbPRESbbHEISEbPT | 0 to 17 MPa | 10 |
| IPT pressure drop | ΔP PXD | Plant | IPTbDELbPbbDPR-10PT | 0 to 0.69 MPa | 10 |
| Loop flow | Venturi flowmeter | Plant | LOOPbFLObbFRC-10PT | 0 to 0.07 m ³ /s | 10 |
| Low flow reflood turbine | Turbine meter | Reflood system | REFLOODbLOWbFLObbb | 0 to 0.25 ℓ/s | 10 |
| High flow reflood turbine | Turbine meter | Reflood system | REFLOODbHIGHbFLObb | 0 to 2 ℓ/s | 10 |

44

998
269

continue to record data on the narrow band channels^a through heatup and for as long as four to eight hours after test termination. The surveillance system need not record data during heatup and after test termination unless requested by the ES&A representative. The Experiment and Analysis Data System will not be utilized for Test LOC-5 purposes. The programming and monitoring system (PM&S) should record the IRIG time and identification of opening and closing the system valves listed in Table IX. No channels^b should be disconnected or adjusted in any fashion until after the test has been terminated, unless, otherwise requested by the ES&A representative and approved by the Instrumentation and Data Section Supervisor. The DARS channel setup should then be verified by a controlled voltage insertion into the low levels or front end of the DARS using a procedure established in the standard practice for data acquisition⁷ for the PBF system. After the DARS verification, no changes should be made in the electronics beyond and including the low levels and the front of the DARS, up through the on-line display or tape recorders, unless requested by the ES&A or a data system representative and approved by the Instrumentation and Data Section Supervisor. Data systems maintenance to be performed prior to and during the testing, and systems operating practices and procedures are detailed in Reference 8 for the PBF Data Acquisition System.

As an additional backup to the data being recorded on the DARS, the on-line trend and 20-minute files should be dumped to magnetic tape. The 8-hour trend data should be dumped every 8 hours starting

-
- a. Wide band tapes could be used if requested by the ES&A representative. During the power calibration phase, a new tape should be used.
 - b. Those channels recorded on the surveillance system necessary for plant operation may be changed if the TFBP representative is notified and an appropriate entry made in the TFBP experimenters console logbook.

998 270

with heatup through blowdown and until test termination. The 20-minute files should be dumped after blowdown so that the 20-minutes will span blowdown.

Figure 7 indicates the data channels which will be required to be displayed on the strip charts during power calibration and fuel conditioning and the blowdown phase. Tables X through XIII present the ES&A designation and explanation of the instrumentation. The display and recording requirements are subject to change at the discretion of the TFBP representative in case of instrument failure or unusual test behavior.

4.2 Data Reduction Requirements

Upon termination of the test, the ES&A representative should be given copies of the checklists contained in Appendix A, Surveillance System strip charts and any other documentation necessary to establish specific data requirements and to prepare the Quick Look Report. A complete list of the required information is given in Appendix A, Table A-VI .

The data reduction requirements are: (a) a data set on disc (with a copy on tape), containing the reduced data channels in a MACRAN format⁹, (b) a tape directory in EDF format which lists pertinent guidelines for using the tape (a MACRAN listing showing channel names and statistics is sufficient), and (c) a reduction and calibration directory in EDF format which defines how the data were reduced. The data should be in one file with the following digitizing intervals:

- (1) Heatup phase up to the point where inlet temperature and flow are varied to determine instrument temperature and flow sensitivity (about four hours prior to nuclear operation) - 5 minutes

QTS 8PP

See Tables X-XII for designation and detailed explanation of instrumentation

| | | |
|--|--|--|
| CLAD934b1b19+0bb01 Cladding Temperature CLAD934b1b19+18001 | RODbPRESSbb934bbb01 Rod Pressure RODbPRESSbb808bbb02 | FLOWRATEbbINLET03 Shroud Turbine Meter FLOWRATEbbINLET04 |
| CLAD935b3b19+0bb03 Cladding Temperature CLAD935b3b19+18003 | RODPRESSbb935bbb03 Rod Pressure RODPRESSbb912bbb04 | ICSSTEMPbbTE20SPIC Spool Temperature CLTCTEMPbbTE23SPCL |
| CLADbDSPbb839bbb02 Cladding Axial Strain CLADbDSPbb912bbb04 | DELTbTEMPbb45bbb01 Differential Temperature DELTbTEMPbb45bbb02 | INLTbTMPbb934bbb01 Coolant Inlet Temperature Reactor Power REACbPOWbbNMS-03PT |
| TFCL934b1b13bbTC01 Centerline Temperature TFCL935b3b13bbTC03 | DELTbTEMPbb45bbb03 Differential Temperature DELTbTEMPbb45bbb04 | CLSVFLOWbbFE06SPCL Spool Turbine Meter ICSVFLOWbbFE05SPIC |
| | FLOWRATEbbINLETb01 Shroud Turbine Meter FLCWRATEbbINLETb02 | ICPRESSFbbPE08SPIC Spool Pressure CLPRESSWbbPE11SPCL |

Fig. 7 Strip chart setup for Test LOC-5

- (2) Remainder of heatup, preconditioning and decay heat buildup phases - 30 seconds
- (3) Blowdown and quench phase - 0.02 seconds (test train and spool pressure transducers will be digitized at 0.001-second intervals for 0.05 seconds and stored on a second file)
- (4) Cooldown - 10 seconds.

If possible, representative channels will be analyzed on the PBF/DARS for frequency content. The digitizing intervals will then be modified to accommodate the required frequencies. If necessary, a third file will be used to store selected channels at shorter digitizing intervals.

Data reduction and plotting requirements are separated into three segments in the following subsections. The first segment concerns data reduction and plot requirements needed for the preparation of the Test LOC-5 Quick Look Report. The second concerns data reduction for the Experimental Data Report; and the third, the Test Results (Topical) Report. Additional plotting requirements will be stipulated for the test analysis, based on test performance and posttest code analyses.

4.2.1 Quick Look Report

Test data plots and data pretest calculation comparison plots for the Quick Look Report are to be prepared within 72 hours of the completion of the test. Due to the short time allocated for preparation of this document, it is mandatory that this requirement be met. The Quick Look Report will only contain plots of data from the blowdown portion of the test.

The plots generated will go directly into the Quick Look Report without redrawing or handling by graphics personnel. The size of the plots should conform to 8-1/2 x 11-inch paper with conventional

998 273

margins and two plots per page. All plotted data are to be in standard SI units.

A complete list of the plots that are required for the Quick Look Report will be provided by the TFBP LOC Project Engineer within two weeks of the test.

4.2.2 Experiment Data Report

Data plots presented in the Test LOC-5 Experiment Data Report will be used by ES&A personnel in analyzing test performance. All test train and test rod measurement transducer outputs should be plotted as functions of time during the power calibration, preconditioning, blowdown and reflood periods of the test. Due to the possibility of failure of some of the fuel temperature measurement transducers, the specific transducer outputs and test rod power levels to be plotted during the power oscillation portion of the test will be specified following the test.

4.2.3 Test Results Report

Data plot requirements for the Test Results Report are expected to evolve during the analysis of the test data. These requirements will be transmitted to the data system group as the need arises.

PTS BPC

5. GENERAL POSTIRRADIATION EXAMINATION
REQUIREMENTS

If the fuel rod internal thermocouple leads do not have a fission gas seal in place, special precautions must be taken to seal the leads manually prior to cutting the instrument leads. Special care should be taken when disassembling the test train to clearly identify the axial position and orientation of each of the circumferential flux wires on the shrouds.

The usual postirradiation examination tasks (PIE) for fuel rods from previous PBF tests should apply for Test LOC-5 purposes. This involves:

- (1) Test train removal, transport, and storage. This task includes:
 - (a) transfer of the test assembly from the PBF canal to the MTR canal for storage prior to beginning the PIE,
 - (b) transfer of the test assembly from the MTR canal to the ARA-I hot cell for the nondestructive PIE,
 - (c) transfer of the test assembly from the ARA-I hot cell to the TRA hot cells for PIE completion,
 - (d) transfer of the test rods, metallography samples, and remains from the TRA hot cells to the MTR canal for a six-month "holding period" storage,
- (2) Detailed postirradiation examination. This task includes:
 - (a) disassembly of each of the test rods from its flow shroud,
 - (b) flux wire removal and counting,

998 275

- (c) visual examination of rods,
- (d) neutron radiography,
- (e) void volume and internal gas pressure and composition evaluations,
- (f) gamma scanning,
- (g) sectioning,
- (h) metallography,
- (i) burnup analyses,
- (j) special examinations, such as scanning electron microscopy and electron microprobe analysis.

Additional information regarding PIE capabilities and requirements will be provided in a revision to this document.

6. REFERENCES

1. J. M. Broughton and P. E. MacDonald, Light Water Reactor Fuel Behavior Program Description: PBF-LOCA Experiment Requirements, ANC (January 1975).
2. United States Nuclear Regulatory Commission, Reactor Safety Research Program, Description of Current and Planned Reactor Safety Research Sponsored by the Nuclear Regulatory Commission's Division of Reactor Safety Research, NUREG-75/058 (June 1975).
3. T. R. Yackle, Loss-of-Coolant Accident Test Series, Test LOC-3 Experiment Operating Specification, TFBP-TR-306, December 1978.
4. T. R. Yackle, PBF-LOCA Tests Program Experiment Specification Document, TFBP-TR-279 (July 1978).
5. B. R. Helm, PBF LOC-3 Experiment Configuration Specification, ES-50425, (Nov. 1978).
6. J. R. Larson, PBF-LOCA Test Series Test LOC-11 Experiment Operating Specification, TFBP-TR-209, (Oct. 1977).
7. C. M. Allison, PBF Integrated Data System Test Standard Practice, (to be published).
8. E. E. Felix, Recommendations for Data Systems Maintenance and Operation, EEF-19-78, (July 1978).
9. R. W. Otnes, Reference Manual: MAC/RAN III-Time Series Data Analysis System, Agababian Associates, 1973.

055 894

APPENDIX A
STATUS CHECK LISTS FOR INSTRUMENTATION

998 278

PTS 8PF

TABLE-AI (Prior to Heatup)

MEASUREMENT STATUS CHECK DURING HEATUP AT AMBIENT CONDITIONS

| | | |
|---------------------|---------|-----|
| REACTOR POWER | 0.0 | KW |
| COOLANT TEMPERATURE | Ambient | K |
| COOLANT PRESSURE | Ambient | MPa |
| SHROUD FLOW RATE | 0 | 1/s |

| <u>PARAMETER ID</u> | <u>PBF, DARS READING</u> | <u>REQUIRED RANGE</u> | <u>CERTIFICATION^a THAT INSTRUMENT IS WITHIN RANGE</u> |
|---------------------|--------------------------|-----------------------|--|
| RODbPRESbb934bbb01 | _____ MPa | 2.4 + 0.1 MPa | _____ |
| RODbPRESbb839bbb02 | _____ MPa | 2.4 + 0.1 MPa | _____ |
| RODbPRFSbb935bbb03 | _____ MPa | 4.8 + 0.1 MPa | _____ |
| RODbPRL bb912bbb04 | _____ MPa | 4.8 + 0.1 MPa | _____ |

- a. This certification must be signed by the LWRD Representative or his alternate. For all required instruments that are not within range the TFBP Project Engineer's approval must be obtained to continue the test procedure. Instrumentation listed which is not required shall be marked NA and initialed by the LWRD Representative.

BTS BPP

TABLE-AII (Power Calibration)

MEASUREMENT STATUS CHECK DURING POWER CALIBRATION

| | | |
|---------------------|-------|--|
| REACTOR POWER | 0 | KW |
| COOLANT TEMPERATURE | 590 | K (Average of test train inlet TC's) |
| COOLANT PRESSURE | 15.51 | MPa (Heise) |
| SHROUD FLOW RATE | 1.0 | l/s (Average of test train inlet flowmeters) |

| PARAMETER ID | PBF/DARS READING | REQUIRED RANGE | CERTIFICATION ^a THAT INSTRUMENT IS WITHIN RANGE |
|--------------------|------------------|-----------------------|--|
| CLAD934b1b19+0bb01 | _____ K | Temperature \pm 4 K | _____ |
| CLAD934b1b19+18001 | _____ K | Temperature \pm 4 K | _____ |
| CLAD934b1b24+90b01 | _____ K | Temperature \pm 4 K | _____ |
| CLAD934b1b24+27001 | _____ K | Temperature \pm 4 K | _____ |
| CLAD839b2b19+0bb02 | _____ K | Temperature \pm 4 K | _____ |
| CLAD839b2b19+18002 | _____ K | Temperature \pm 4 K | _____ |
| CLAD839b2b24+90b02 | _____ K | Temperature \pm 4 K | _____ |
| CLAD839b2b24+27002 | _____ K | Temperature \pm 4 K | _____ |
| CLAD935b3b19+0bb03 | _____ K | Temperature \pm 4 K | _____ |
| CLAD935b3b19+18003 | _____ K | Temperature \pm 4 K | _____ |
| CLAD935b3b24+90b03 | _____ K | Temperature \pm 4 K | _____ |
| CLAD935b3b24+27003 | _____ K | Temperature \pm 4 K | _____ |
| CLAD912b4b19+0bb04 | _____ K | Temperature \pm 4 K | _____ |
| CLAD912b4b19+18004 | _____ K | Temperature \pm 4 K | _____ |
| CLAD912b4b24+90b04 | _____ K | Temperature \pm 4 K | _____ |
| CLAD912b4b24+27004 | _____ K | Temperature \pm 4 K | _____ |
| TFCL934b1b13bbTC01 | _____ K | Temperature \pm 4 K | _____ |
| TFCL935b3b13bbTC03 | _____ K | Temperature \pm 4 K | _____ |
| CLADbDSPbb934bbb01 | _____ mm | 1.0 \pm 0.5 mm | _____ |
| CLADbDSPbb839bbb02 | _____ mm | 1.0 \pm 0.5 mm | _____ |
| CLADbDSPbb935bbb03 | _____ mm | 1.0 \pm 0.5 mm | _____ |
| CLADbDSPbb912bbb04 | _____ mm | 1.0 \pm 0.5 mm | _____ |
| RODbPRESbb934bbb01 | _____ MPa | 5.0 \pm 0.1 MPa | _____ |
| RODbPRESbb839bbb02 | _____ MPa | 5.0 \pm 0.1 MPa | _____ |

182 390

998 280

| <u>PARAMETER ID</u> | <u>PBF/DARS READING</u> | <u>REQUIRED RANGE</u> | <u>CERTIFICATION^a THAT INSTRUMENT IS WITHIN RANGE</u> |
|-----------------------------------|-------------------------|-----------------------|--|
| RODbPRESbb935bbb03 | _____ MPa | 10.0 \pm 0.7 MPa | _____ |
| RODbPRESbb912bbb04 | _____ MPa | 10.0 \pm 0.7 MPa | _____ |
| PLNMBTMPbb934bbb01 | _____ K | Temperature \pm 4 K | _____ |
| PLNMBTMPbb839bbb02 | _____ K | Temperature \pm 4 K | _____ |
| PLNMBTMPbb935bbb03 | _____ K | Temperature \pm 4 K | _____ |
| PLNMBTMPbb912bbb04 | _____ K | Temperature \pm 4 K | _____ |
| INLTbTMPbb934bbb01 | _____ K | Temperature \pm 4 K | _____ |
| INLTbTMPbb839bbb02 | _____ K | Temperature \pm 4 K | _____ |
| INLTbTMPbb935bbb03 | _____ K | Temperature \pm 4 K | _____ |
| INLTbTMPbb912bbb04 | _____ K | Temperature \pm 4 K | _____ |
| OUTbTEMPbb934bbb01 | _____ K | Temperature \pm 4 K | _____ |
| OUTbTEMPbb839bbb02 | _____ K | Temperature \pm 4 K | _____ |
| OUTbTEMPbb935bbb03 | _____ K | Temperature \pm 4 K | _____ |
| OUTbTEMPbb912bbb04 | _____ K | Temperature \pm 4 K | _____ |
| DElbTEMPbb45bbbb01 | _____ K | \pm 0.05 K | _____ |
| DElbTEMPbb225bbb01 | _____ K | \pm 0.05 K | _____ |
| DElbTEMPbb45bbbb02 | _____ K | \pm 0.05 K | _____ |
| DElbTEMPbb225bbb02 | _____ K | \pm 0.05 K | _____ |
| DElbTEMPbb45bbbb03 | _____ K | \pm 0.05 K | _____ |
| DElbTEMPbb225bbb03 | _____ K | \pm 0.05 K | _____ |
| DElbTEMPbb45bbbb04 | _____ K | \pm 0.05 K | _____ |
| DElbTEMPbb225bbb04 | _____ K | \pm 0.05 K | _____ |
| BULKbTMPbb-120bb02 ^(b) | _____ K | Temperature \pm 4 K | _____ |
| BULKbTMPbbb000bb02 | _____ K | Temperature \pm 4 K | _____ |
| BULKbTMPbb+120bb02 | _____ K | Temperature \pm 4 K | _____ |
| BULKbTMPbb-120bb03 | _____ K | Temperature \pm 4 K | _____ |
| BULKbTMPbbb000bb03 | _____ K | Temperature \pm 4 K | _____ |
| BULKbTMPbb+120bb03 | _____ K | Temperature \pm 4 K | _____ |
| SHRDbTMPbb-120bb02 ^(b) | _____ K | Temperature \pm 4 K | _____ |
| SHRDbTMPbbb000bb02 | _____ K | Temperature \pm 4 K | _____ |
| SHRDbTMPbb+120bb02 | _____ K | Temperature \pm 4 K | _____ |

085 899

998 281

| <u>PARAMETER ID</u> | <u>PBF/DARS READING</u> | <u>REQUIRED RANGE</u> | <u>CERTIFICATION^a THAT INSTRUMENT IS WITHIN RANGE</u> |
|---------------------|-------------------------|-----------------------|--|
| SHRDbTMPbb-120bb03 | _____ K | Temperature \pm 4 K | _____ |
| SHRDbTMPbbb000bb03 | _____ K | Temperature \pm 4 K | _____ |
| SHRDbTMPbb+120bb03 | _____ K | Temperature \pm 4 K | _____ |
| FLOWRATEbbINLETb01 | _____ 1/s | Flow \pm 0.001 1/s | _____ |
| FLOWRATEbbINLETb02 | _____ 1/s | Flow \pm 0.001 1/s | _____ |
| FLOWRATEbbINLETb03 | _____ 1/s | Flow \pm 0.001 1/s | _____ |
| FLOWRATEbbINLETb04 | _____ 1/s | Flow \pm 0.001 1/s | _____ |
| FLOWRATEbbOUTLET01 | _____ 1/s | Flow \pm 0.001 1/s | _____ |
| FLOWRATEbbOUTLET02 | _____ 1/s | Flow \pm 0.001 1/s | _____ |
| FLOWRATEbbOUTLET03 | _____ 1/s | Flow \pm 0.001 1/s | _____ |
| FLOWRATEbbOUTLET04 | _____ 1/s | Flow \pm 0.001 1/s | _____ |
| NEUTbFLXbb-34.3bTT | _____ N/A | N/A | _____ N/A |
| NEUTbFLXbb-22.9bTT | _____ N/A | N/A | _____ N/A |
| NEUTbFLXbb-11.4bTT | _____ N/A | N/A | _____ N/A |
| NEUTbFLXbbbb0.0bTT | _____ N/A | N/A | _____ N/A |
| NEUTbFLXbb+14.2bTT | _____ N/A | N/A | _____ N/A |
| NEUTbFLXbb+22.9bTT | _____ N/A | N/A | _____ N/A |
| NEUTbFLXbb+34.3bTT | _____ N/A | N/A | _____ N/A |
| BYPbTEMPbbNO.1bLTT | _____ K | Temperature \pm 4 K | _____ |
| BYPbTEMPbbNO.2bbTT | _____ K | Temperature \pm 4 K | _____ |
| BYPbTEMPbbNO.3bUTT | _____ K | Temperature \pm 4 K | _____ |
| BYPbTEMPbbNO.4bUTT | _____ K | Temperature \pm 4 K | _____ |
| BYPbTEMPbbNO.5bUTT | _____ K | Temperature \pm 4 K | _____ |
| PLATbTMPbbbbbbLTT | _____ K | Temperature \pm 4 K | _____ |
| SYSbPRESbb69EGbLTT | _____ MPa | Heise \pm 3.5 MPa | _____ |
| SYSbPRESbb17EGbLTT | _____ MPa | Heise \pm 0.7 MPa | _____ |
| SYSbPRESbb17EGbUTT | _____ MPa | Heise \pm 0.7 MPa | _____ |
| SYSbPRESbb17KAbUTT | _____ MPa | Heise \pm 0.7 MPa | _____ |
| GAMAbFLXbb-22.9bTT | _____ N/A | N/A | _____ N/A |
| GAMAbFLXbbbb00.0bTT | _____ N/A | N/A | _____ N/A |
| GAMAbFLXbb+22.9bTT | _____ N/A | N/A | _____ N/A |

285

896

| <u>PARAMETER ID</u> | <u>PBF/DARS READING</u> | <u>REQUIRED RANGE</u> | <u>CERTIFICATION^a THAT INSTRUMENT IS WITHIN RANGE</u> |
|---------------------|-------------------------|--------------------------------|--|
| FLOWRATEbbCONTBYTT | _____ 1/s | 16 ± 1.0 1/s | _____ |
| SHRDbleVbbINLETb01 | _____ N/A | N/A | _____ N/A |
| SHRDbleVbbINLETb02 | _____ N/A | N/A | _____ N/A |
| SHRDbleVbbINLETb03 | _____ N/A | N/A | _____ N/A |
| IPTbleVLbbNO.1bLTT | _____ N/A | N/A | _____ N/A |
| IPTbleVLbbNO.2bLTT | _____ N/A | N/A | _____ N/A |
| ICSVFLOWbbFE05SPIC | _____ 1/s | Flow ^(c) ± 0.02 1/s | _____ |
| CLSVFLOWbbFE06SPCL | _____ 1/s | (c) ± 0.02 1/s | _____ |
| HL SVFLOWbbFE09SPHL | _____ 1/s | (c) ± 0.02 1/s | _____ |
| CLMOMFLXbbFE07SPCL | _____ N/A | N/A | _____ N/A |
| HLMOMFLXbbFE08SPHL | _____ N/A | N/A | _____ N/A |
| ICSSTEMPbbTE20SPIC | _____ K | temperature ± 4 K | _____ |
| CLSSTEMPbbTE22SPCL | _____ K | Temperature ± 4 K | _____ |
| HL SSTEMPbbTE23SPHL | _____ K | Temperature ± 4 K | _____ |
| ICTCTEMPbbTE21SPIC | _____ K | Temperature ± 4 K | _____ |
| CLTCTEMPbbTE24SPCL | _____ K | Temperature ± 4 K | _____ |
| HLTCTEMPbbTE25SPHL | _____ K | Temperature ± 4 K | _____ |
| ICPRESSFbbPE08SPIC | _____ MPa | Heise ± 0.2 MPa | _____ |
| CLPRESSFbbPE10SPCL | _____ MPa | Heise ± 0.2 MPa | _____ |
| HLPRESSFbbPE12SPHL | _____ MPa | Heise ± 0.2 MPa | _____ |
| ICPRESSWbbPE09SPIC | _____ MPa | Heise ± 0.2 MPa | _____ |
| CLPRESSWbbPE11SPCL | _____ MPa | Heise ± 0.2 MPa | _____ |
| HLPRESSWbbPE13SPHL | _____ MPa | Heise ± 0.2 MPa | _____ |
| DELPCLHLbbDPE-05HL | _____ N/A MPa | N/A | _____ N/A |
| CLDENSUPbbDENS1UCL | _____ N/A | N/A | _____ N/A |
| CLDENSCEbbDENS1CCL | _____ N/A | N/A | _____ N/A |
| CLDENSLOBbbDENS1LCL | _____ N/A | N/A | _____ N/A |
| HLDENSUPbbDENS2UHL | _____ N/A | N/A | _____ N/A |
| HLDENSCEbbDENS2CHL | _____ N/A | N/A | _____ N/A |
| HLDENSLOBbbDENS2LHL | _____ N/A | N/A | _____ N/A |
| CLbACCELbbAE-1-1CL | _____ N/A | N/A | _____ N/A |

998 283

S8S 89F

| <u>PARAMETER ID</u> | <u>PBF/DARS READING</u> | <u>REQUIRED RANGE</u> | <u>CERTIFICATION^a THAT INSTRUMENT IS WITHIN RANGE</u> |
|---------------------|-------------------------|-----------------------|--|
| CLbACCELbbAE-1-2CL | N/A | N/A | N/A |
| CLbACCELbbAE-1-3CL | N/A | N/A | N/A |
| HLbACCELbbAE-2-1HL | N/A | N/A | N/A |
| HLbACCELbbAE-2-2HL | N/A | N/A | N/A |
| HLbACCELbbAE-2-3HL | N/A | N/A | N/A |
| HENRYPXDbbFE11-1PT | MPa | Heise \pm 0.2 MPa | |
| HENRYPXDbbFE11-2PT | MPa | Heise \pm 0.2 MPa | |
| HENRYPXDbbFE11-3PT | MPa | Heise \pm 0.2 MPa | |
| HENRYPXDbbFE11-4PT | MPa | Heise \pm 0.2 MPa | |
| FRbTEMPbbbPIPE01FP | N/A | N/A | N/A |
| FRbTEMPbbbPIPE02FP | N/A | N/A | N/A |
| FRbTEMPbbbPIPE03FP | N/A | N/A | N/A |
| FRbTEMPbbbPIPE04FP | N/A | N/A | N/A |
| FRbTEMPbbbPIPE05FP | N/A | N/A | N/A |
| FRbTEMPbbbPIPE06FP | N/A | N/A | N/A |
| FRbTEMPbbbPIPE07FP | N/A | N/A | N/A |
| FRbTEMPbbbPIPE08FP | N/A | N/A | N/A |
| FRbTEMPbbbPIPE09FP | N/A | N/A | N/A |
| CLbDNTMPbbDENTC1CL | N/A | N/A | N/A |
| CLbDNTMPbbDENTC2CL | N/A | N/A | N/A |
| CLbDNTMPbbDENTC3CL | N/A | N/A | N/A |
| HLbDNTMPbbDENTC1HL | N/A | N/A | N/A |
| HLbDNTMPbbDENTC2HL | N/A | N/A | N/A |
| HLbDNTMPbbDENTC3HL | N/A | N/A | N/A |
| VALVbPOSbbLM1101PT | N/A | N/A | N/A |
| VALVbPOSbbLM1102PT | N/A | N/A | N/A |
| VALVbPOSbbLMLRC1PT | N/A | N/A | N/A |
| VALVbPOSbbLMLRC2PT | N/A | N/A | N/A |
| VALVbPOSbbLM1105PT | N/A | N/A | N/A |
| VALVbPOSbbLM1106PT | N/A | N/A | N/A |
| VALVbPOSbbLM1107PT | N/A | N/A | N/A |

285

80

998

284

| <u>PARAMETER ID</u> | <u>PBF/DARS READING</u> | <u>REQUIRED RANGE</u> | <u>CERTIFICATION^a THAT INSTRUMENT IS WITHIN RANGE</u> |
|-------------------------|-----------------------------|-------------------------------|--|
| VALVbPOSbbLM1108PT | <u>N/A</u> | N/A | <u>N/A</u> |
| VALVbPOSbbLM1109PT | <u>N/A</u> | N/A | <u>N/A</u> |
| VALVbPOSbbLM1110PT | <u>N/A</u> | N/A | <u>N/A</u> |
| OUTbPRESbbPT-30bPT | <u>MPa</u> | Heise + 0.7 MPa | <u></u> |
| OUTbFLOWbbPT-29bPT | <u>1/s</u> | Flow ^(c) + 0.3 1/s | <u></u> |
| OUTbTEMPbbTT-29bPT | <u>K</u> | Temperature + 4 K | <u></u> |
| QNCHbLEVbbLT-10bPT | <u>N/A</u> | N/A | <u>N/A</u> |
| QNCHbTMPbbTIC27bPT | <u>N/A</u> | N/A | <u>N/A</u> |
| QNCHbFLObbFT-14bPT | <u>N/A</u> | N/A | <u>N/A</u> |
| BLOWbPRSbbPT-12bPT | <u>N/A</u> | N/A | <u>N/A</u> |
| BLOWbLEVbbLIT17bPT | <u>N/A</u> | N/A | <u>N/A</u> |
| SYSbPRESbbPRS10bPT | <u>N/A</u> | N/A | <u>N/A</u> |
| IPTbDELPbbDPR-10PT | <u>N/A</u> | N/A | <u>N/A</u> |
| LOOPbACTbbFBM-01PT | <u>N/A</u> | N/A | <u>N/A</u> |
| LOOPbFLObbFRC-10PT | <u>N/A</u> | N/A | <u>N/A</u> |
| FPbGAMMAbbNO.1bbFP | <u>N/A</u> | N/A | <u>N/A</u> |
| FPbGAMMAbbNO.2bbFP | <u>N/A</u> | N/A | <u>N/A</u> |
| FPbGAMMAbbNO.3bbFP | <u>N/A</u> | N/A | <u>N/A</u> |
| FPbNEUTbbbbbbsbbFP | <u>N/A</u> | N/A | <u>N/A</u> |
| REACbPOWbbNMS-03PT | <u>N/A</u> | N/A | <u>N/A</u> |
| REACbPOWbbNMS-04PT | <u>N/A</u> | N/A | <u>N/A</u> |
| REACbPOWbbPPS-01PT | <u>N/A</u> | N/A | <u>N/A</u> |
| REACbPCWbbPPS-02PT | <u>N/A</u> | N/A | <u>N/A</u> |

- a. This certification must be signed by the LWRD Representative or his alternate. For all cases where the instruments are not within range the TFBP Project Engineer's approval must be obtained to continue the test procedures.
- b. One per shroud required as minimum operable instrumentation.
- c. Flow determined during flow split.

ABS 8PF

998 285

TABLE-AIII

MEASUREMENT STATUS CHECK AT 80 - 100 KW

| | | |
|---------------------|-----------|----------------------------------|
| REACTOR POWER | 80 - 100 | KW |
| COOLANT TEMPERATURE | 590 K | Average of test train inlet TC's |
| COOLANT PRESSURE | 15.51 MPa | |
| SHROUD FLOW RATE | 1.0 1/s | |

| PARAMETER ID | PBF/DARS READING | REQUIRED RANGE | CERTIFICATION ^a THAT INSTRUMENT IS WITHIN RANGE |
|----------------------|------------------|----------------|--|
| NEUTbFLXbb-34.3bTi | nA | + 0.8 nA | _____ |
| NEUTbFLXbb-22.7bTT | nA | + 0.8 nA | _____ |
| NEUTbFLXbb-11.4bTT | nA | + 0.8 nA | _____ |
| NEUTbFLXbbbb0.0bTT | nA | + 0.8 nA | _____ |
| NEUTbFLXbb+14.2bTT | nA | + 0.8 nA | _____ |
| NEUTbFLXbb+22.9bTT | nA | + 0.8 nA | _____ |
| NEUTbFLXbb+34.3bTT | nA | + 0.8 nA | _____ |
| GAMMAbFLXbb-22.9bTT | nA | + 0.8 nA | _____ |
| GAMMAbFLXbbbb00.0bTT | nA | + 0.8 nA | _____ |
| GAMMAbFLXbb+22.9bTT | nA | + 0.8 nA | _____ |

- a. This certification must be signed by the LWRD Representative or his alternate. For all required instruments that are not within range the TFBP Project Engineer's approval must be obtained to continue the test procedure. Instrumentation listed which is not required shall be marked NA and initialed by the LWRD Representative.

P85 990

TABLE A1Y (Continued)
FLOW BALANCE CHECK

| DESIRED SHROUD FLOW | WARMUP LINE | LOWER TEST TRAIN FLOW (1) | AVERAGE LOWER TEST TRAIN FLOW (2) | UPPER TEST TRAIN FLOW (3) | AVERAGE UPPER TEST TRAIN FLOW (4) | AVERAGE TEST TRAIN FLOW (5) | IC SPOOL FLOW (6) | COLD LEG FLOW (7) | HOT LEG FLOW (8) | IPT CONTROLLED BY-PASS FLOW (15) | LOOP FLOW (9) | PCS LOOP(b) BYPASS FLOW RATIO (10) | WARMUP LINE FLOW (14)(c) |
|---------------------|-------------|---|-----------------------------------|---|-----------------------------------|------------------------------------|-------------------|-------------------|------------------|----------------------------------|---------------|------------------------------------|-------------------------------------|
| 0.4 | Open | Turbine(d)-1 -1 -2 -3 -4 1/s | 1/s | Turbine-1 -1 -2 -3 -4 1/s | 1/s | $\frac{(2) + (4)(*)}{2} = 1/s$ | 1/s | 1/s | 1/s | | 1/s | | |
| 0.6 | Open | -1 -2 -3 -4 | | -1 -2 -3 -4 | | | | | | | | $\frac{(9) - (6)}{(9)}$ | $(6) - (15) - 4(5)(1 + (13)) = 1/s$ |
| 0.8 | Open | -1 -2 -3 -4 | | -1 -2 -3 -4 | | | | | | | | | |
| 1.0 | Open | -1 -2 -3 -4 | | -1 -2 -3 -4 | | | | | | | | | |
| 0.8 | Open | -1 -2 -3 -4 | | -1 -2 -3 -4 | | | | | | | | | |
| 0.6 | Open | -1 -2 -3 -4 | | -1 -2 -3 -4 | | | | | | | | | |
| 0.4 | Open | -1 -2 -3 -4 | | -1 -2 -3 -4 | | | | | | | | | |
| Example | | Turbine-1 0.50 1/s -2 0.25 -3 0.50 -4 0.55 | 0.50 | Turbine-1 0.50 1/s -2 0.25 -3 0.50 -4 0.55 | 0.50 1/s | $\frac{0.50 + 0.50}{2} = 0.50$ 1/s | 0.2 1/s | 1.0 1/s | -1.0 1/s | 6.0 1/s | 12.0 1/s | $\frac{12.0 - 0.2}{12.0} = 0.23$ | $0.2 - 6 - 0.5(1.006) = 1.03$ 1/s |

(a) This symbol(s) writes like the results from column (2) and column (4) adding and dividing by 2 to get the average.
 (b) Downstream of primary coolant pump LOOPFLOW(C) [05]
 (c) Downstream of primary coolant pump LOOPFLOW(C) [05]
 (d) Turbine-1 = _____ Turbine-2 = _____
 Turbine-3 = _____ Turbine-4 = _____

63

998 288

POOR ORIGINAL

TABLE A11 (Cont'd)
FLOW BALANCE CHECK

| DESIRED SHROUD FLOW | WARMUP LINE | LOWER TEST TRAIN FLOW (1) | AVERAGE LOWER TEST TRAIN FLOW (2) | UPPER TEST TRAIN FLOW (3) | AVERAGE UPPER TEST TRAIN FLOW (4) | AVERAGE TEST TRAIN FLOW (5) | IC SHOUL FLOW (6) | COLD LEG FLOW (7) | HOT LEG FLOW (8) | IPT COM- TROLLED BY- PASS FLOW (15) | LOOP FLOW (9) | PSS LOOP BYPASS FLOW RATIO (10) | IPT VOLUME BYPASS FLOW RATIO (11) |
|------------------------|----------------|---|---|--|---|------------------------------------|-------------------------|-------------------------|------------------------|--|---------------------|--|---|
| 0.4 | Closed | Turbine-1 1/4 -2 -4 | 1/4 | Turbine-1 1/4 -2 -3 -4 | 1/4 | (2) + (3) + (4) 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | (9) - (6) (9) | (6) - (4) - (5) - (15) (11) |
| 0.6 | Closed | -1 -2 -3 -4 | 1/4 | -1 -2 -3 -4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 |
| 0.8 | Closed | -1 -2 -3 -4 | 1/4 | -1 -2 -3 -4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 |
| 1.0 | Closed | -1 -2 -3 -4 | 1/4 | -1 -2 -3 -4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 | 1/4 |
| Example | | Turbine-1 0.5 1/4 -2 0.5 -3 0.5 -4 0.5 | 0.50 | Turbine-1 0.50 1/4 -2 0.5 -3 0.5 -4 0.5 | 0.50 1/4 | 0.50 + 0.50 + 0.50 1/4 1.50 1/4 | 0.0 1/4 | 0.0 1/4 | 0.0 1/4 | 6.0 1/4 | 10.0 1/4 | 10.0 - 6.0 + 0.20 10.20 | 8.0 - 4 - 1.15 - 3.0 + 0.085 1.15 |

AVERAGE LOOP
BYPASS RATIO (12)

AVERAGE IPT
BYPASS RATIO (13)

POOR ORIGINAL

POOR ORIGINAL

TABLE A11 (Cont Inued)
FLOW BALANCE CHECK

| DESIRED SHROUD FLOW | WARPUP LINE | LOWER TEST TRAIN FLOW (1) | AVERAGE LOWER TEST TRAIN FLOW (2) | UPPER TEST TRAIN FLOW (3) | AVERAGE UPPER TEST TRAIN FLOW (4) | AVERAGE TEST TRAIN FLOW (5) | IC LOOP FLOW (6) | COLD LEG FLOW (7) | HOT LEG FLOW (8) | SPT CON-TRILLED BY-PASS FLOW (15) | LOOP FLOW (9) | PCS LOOP(b) BYPASS FLOW (10) | WARPUP LINE FLOW (14)(c) |
|---------------------|-------------|--------------------------------|-----------------------------------|---|-----------------------------------|-----------------------------|------------------------------|------------------------------|------------------------------|-----------------------------------|------------------------------|------------------------------|---|
| 1.0 | Open | Turbine(d) 1 -2 -3 -4 | 1/8 1/8 1/8 1/8 | Turbine-1 -2 -3 -4 -2 -3 -4 -2 -3 -4 -2 -3 -4 | 1/8 1/8 1/8 1/8 | $\frac{-(2) + (4)}{2}$ | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | $\frac{(9) - (6)}{(9)}$ | $(6) - (15) - 4 (5) (1 + (13)) + \dots$ |
| 0.6 | Open | Turbine(d) 1 -2 -3 -4 | 1/8 1/8 1/8 1/8 | Turbine-1 -2 -3 -4 -2 -3 -4 -2 -3 -4 -2 -3 -4 | 1/8 1/8 1/8 1/8 | $\frac{-(2) + (4)}{2}$ | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | $\frac{(9) - (6)}{(9)}$ | $(6) - (15) - 4 (5) (1 + (13)) + \dots$ |
| 0.6 | Open | Turbine(d) 1 -2 -3 -4 | 1/8 1/8 1/8 1/8 | Turbine-1 -2 -3 -4 -2 -3 -4 -2 -3 -4 -2 -3 -4 | 1/8 1/8 1/8 1/8 | $\frac{-(2) + (4)}{2}$ | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | $\frac{(9) - (6)}{(9)}$ | $(6) - (15) - 4 (5) (1 + (13)) + \dots$ |
| 0.4 | Open | Turbine(d) 1 -2 -3 -4 | 1/8 1/8 1/8 1/8 | Turbine-1 -2 -3 -4 -2 -3 -4 -2 -3 -4 -2 -3 -4 | 1/8 1/8 1/8 1/8 | $\frac{-(2) + (4)}{2}$ | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | 1/8 1/8 1/8 1/8 | $\frac{(9) - (6)}{(9)}$ | $(6) - (15) - 4 (5) (1 + (13)) + \dots$ |
| Example | | Turbine-1 -2 -3 -4 | 0.50 0.45 0.50 0.55 | Turbine-1 -2 -3 -4 | 0.50 0.45 0.50 0.55 | $\frac{0.50 + 0.50}{2}$ | 0.50 0.50 0.50 0.50 | 0.50 0.50 0.50 0.50 | 0.50 0.50 0.50 0.50 | 0.50 0.50 0.50 0.50 | 0.50 0.50 0.50 0.50 | $\frac{0.50 + 0.50}{2}$ | $9.2 - 6 - 4 \cdot 0.5 (1.006) - 1.01$ |

a) This Symbolic denotes take the results from column (2) and column (4) adding and dividing by 2 to get the average.
 b) Downstream of primary coolant pump LOOP-1/3/5-10/PT.
 c) Downstream of primary coolant pump LOOP-2/3/5-10/PT.
 d) Turbine-1 = Turbine-2 = Turbine-3 = Turbine-4 =

998 290

TABLE A-V

QUENCH AND BLOWDOWN TANK READING IMMEDIATELY PRIOR TO BLOWDOWN

| <u>Measurement</u> | <u>Designation</u> | <u>Reading (Eng.)</u> | <u>Reading (SI)</u> |
|---------------------------------|--------------------|-----------------------|---------------------|
| Quench Tank Coolant Level | QNCHbLEVbbLT-10bPT | _____ % | _____ % |
| Quench Tank Coolant Temperature | QNCHbTMPbbTIC27bPT | _____ F/1.8 + 255.37 | _____ K |
| Blowdown Tank Pressure | BLOWbPRSbbPT-12bPT | _____ PSIA 145.05 | _____ MPa |
| Blowdown Tank Liquid Level | BLOWbbLEVbLIT17bPT | _____ % | _____ % |

99

POOR ORIGINAL

998

291

095

89

TABLE A-VI

POSTTEST CHECK LIST AND DARS SETUP
DOCUMENTATION CHECKLIST

| | |
|---|-------|
| Integrated Data System Calibration Procedure Checklist | _____ |
| Data Recording Verification Procedure Checklist | _____ |
| Measurement Status - Ambient | _____ |
| - 340 K (During Heatup) | _____ |
| - 600 K (After Heatup Prior to Nuclear Operation) | _____ |
| - Reactor Critical (80 KW) | _____ |
| Posttest Checklist and DARS Setup Documentation Checklist | _____ |
| Quench Tank and Blowdown Tank Readings | _____ |
| Flow Balance Readings | _____ |
| DARS Channel Setup Log Sheet | _____ |
| SS Channel Setup Log Sheet | _____ |
| DARS Narrow Band and Wide Band Tape Log Sheets | _____ |
| DARS Parameter/Sensor Directory | _____ |
| DARS Inactive Parameter Directory | _____ |
| REDCOR Printout | _____ |
| SS Strip Charts | _____ |

998 292