


Georgia Power Company
230 Peachtree Street
Post Office Box 4545
Atlanta, Georgia 30307
Telephone 404 522-6060

T.C.

Power Generation Department

October 24, 1979 26 All : 06



United States Nuclear Regulatory Commission
Office of Inspection and Enforcement
Region II - Suite 2000
101 Marietta Street
Atlanta, Georgia 30303

Reference:
RII: JPO
50-321/50-366
I&E Bulletin 79-23

ATTENTION: Mr. James P. O'Reilly

Gentlemen:

Georgia Power Company hereby submits the following information in response to your letter of September 12, 1979, which transmitted Bulletin 79-23, "Potential Failure of Emergency Diesel Generator Field Exciter Transformer". This bulletin addressed possible deficiencies in the wiring of field exciter transformers such as those found during a test of the diesel generators at an operating facility. Specifically, two questions were raised and are answered herein:

QUESTION 1

Determine whether or not connections have been made between low KVA rated transformers and high KVA rated EDG's without adequate limitations on the flow of circulating currents. If applicable, provide a description of the corrective action being taken to address this problem.

RESPONSE 1

It was determined that no ground/neutral connections have been made between low KVA rated transformers and high KVA rated Emergency Diesel Generators. A review of applicable drawings indicated that this type of connection was not included in system design. A physical inspection of the circuits was made to ensure no unauthorized connections had been made.

QUESTION 2

Provide a schedule for the completion of a sustained full-load operation test of the EDG's for a duration of not less than 24 hours, or provide the results of the similar long duration, full-load test which has already been completed on the EDG's installed at your facility. The test should demonstrate full-load carrying capability for an interval of not less than 24 hours, of which 22 hours should be at a load equivalent to the continuous rating of the diesel generator and 2 hours at a load equivalent to the 2 hour rating of the diesel generator. The test should also verify that voltage and frequency requirements are maintained and that the cooling system functions within design limits.

1311 244

790467
OFFICIAL COPY
7911120 06-3

United States Nuclear Regulatory Commission
Office of Inspection and Enforcement
October 24, 1979
Page Two

RESPONSE 2

A sustained 24 hour full-load test was successfully completed on the two Unit 2 diesel generators on September 16, 1977. Unit 2 will again be performing this test as part of the Unit 2 Technical Specification surveillance requirement.

A sustained 24 hour full-load test will be performed on the three Unit 1 diesel generators by February 1, 1980.

If there are further questions in this regard, please contact this office.

Sincerely,

W.A. Widner

W. A. Widner
Manager of Nuclear Operations

WEB/mb

xc: U. S. Nuclear Regulatory Commission
Office of Inspection and Enforcement
Division of Reactor Operations Inspection
Washington, D. C. 20555

R. F. Rogers, III

1311-245