TECHNICAL SPECIFICATION CHANGE REQUEST NO. 57 (APPENDIX A)

Replace pages 3/4 6-15, 3/4 6-17, 3/4 6-18, 3/4 6-19, 3/4 6-20 and 3/4 6-21 with the attached revised pages 3/4 6-15, 3/4 6-17, 3/4 6-18, 3/4 6-19, 3/4 6-20, and 3/4 6-21.

Proposed Change

- A. For ACTION statements b and c of Specification 3.6.3, add a footnote 1 to read: "These valves may be reopened on an intermittent basis under administrative control for up to 4 hours in any 24-hour period as necessary for sampling or surveillance testing."
- B. Add ACTION statement e to read: "The provisions of Specification 3.0.4 are not applicable to those values in Table 3.6-1 annotated by double asterisks (**)." Double asterisks have been added to appropriate values in Table 3.6-1.
- C. Add asterisk note to Table 3.6-1 to read: "May be opened on an intermittent basis under administrative control." Asterisks have been added to appropriate valves in Table 3.6-1.

Reason for the Proposed Change

- A. ACTION statements b and c of Specification 3.6.3.1 require penetrations with one or more inoperable isolation valves(s) to be isolated. However, other specifications require cycling of the valves used to complete the isolation for either surveillance testing or to draw samples to complete required analyses. It is for this reason that the footnote has been proposed.
- B. ACTION e has been proposed for Specification 3.6.3.1 for valves that, if they are inoperable and ACTION Statement b or c is in effect, are in their post-containment isolation configuration. Since these valves are already in their post-containment isolation configuration they neither perform an emergency core cooling function, nor offer any hindrance to normal plant operations while shut or isolated. There is no reason to restrain the entry into other OPERATIONAL MODES. Therefore, the exception to the provisions of Specification 3.0.4 is proposed.
- C. The table note is being proposed to Table 3.6-1 because there are times in MODES 1, 2, 3 and 4 that it is necessary to cycle these manual valves to perform surveillance, draw samples, or support entry into the containment. Additionally, this note is currently included in B&W Standard (NUREG-0103, Rev. 3).

Safety Analysis of the Proposed Change

A. The footnote to ACTION statment b and c will allow the intermittent operation of the isolated valves for sampling or surveillance testing purposes under administrative control. This sampling and surveillance

TSCRN57(DN89)

1749 157

Safety Analysis of Proposed Change (Continued)

testing is necessary to ensure the continued safe operation of Crystal River - Unit 3. To prevent these activities would cause the unit to shutdown due to the failure to fulfill the other specifications. This is not a reasonable course of action because the sampling and surveillance testing can be completed under administrative control. This administrative control is sufficient to re-isolate these valves upon receipt of a containment isolation signal.

- B. Entry into an OPERTIONAL MODE is restricted in that the conditions of the Limiting Conditions for Operation (LCO) must be met without reliance on ACTION statements unless specifically excepted. Specific exceptions can be granted when the ACTION statement places the unit in a condition which is equivalent to meeting the LCO. In this case, ACTION statement b or c will place the valves in their post-containment isolation positions. Therefore, the entry into other OPERATIONAL MODES should not be prohibited because the valves will be in their isolation positions and would not contribute to an accident if containment isolation was required.
- C. Intermittent operation of manual isolation valves under administrative control in MODES 1, 2, 3 and 4 is acceptable. The administrative control is sufficient to re-isolate these valves upon the receipt of a containment isolation signal.

CONTAINMENT SYSTEMS

3/4.6.3 CONTAINMENT ISOLATION VALVES

LIMITING CONDITION FOR OPERATION

3.6.3.1 The containment isolation valves specified in Table 3.6-1 shall be OPERABLE with isolation times as shown in Table 3.6-1.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With one or more of the isolation valve(s) specified in Table 3.6-1 inoperable, either:

- a. Restore the inoperable valve(s) to OPERABLE status within 4 hours, or
- b. Isolate each affected penetration within 4 hours by use of at least one deactivated automatic valve secured in the isolation position, 1/or
- c. Isolate each affected penetration within 4 hours by use of at least one closed manual valve or blind flange, 1/ or
- d. Be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.
- e. The provisions of Specification 3.0.4 are not applicable to those valves in Table 3.6-1 annotated by double asterisks (**).

SUR VEILLANCE REQUIREMENTS

4.6.3.1.1 The isolation valves specified in Table 3.6-1 shall be demonstrated OPERABLE prior to returning the valve to service after maintenance, repair or replacement work is performed on the valve or its associated actuator, control or power circuit by performance of a cycling test and verification of isolation time.

1/ These valves may be re-opened on an intermittent basis under administra-Tive control for up to 4 hours in any 24 hour period as necessary for sampling or surveillance testing.

CRYSTAL RIVER - UNIT 3 3/4 6-15

TABLE 3.6-1 (Continued)

CONTAINMENT ISOLATION VALVES

VALVE	NUMBER	FUNCTION	ISOLATION TIME (seconds)
CONTA	INMENT ISOLATION		
1	RSV-27 check	iso, dur. nor. operation	NA
**	BSV-3	and open dur. RB spray	60
	BSV-26 check #		NA
	BSV-4 #		60
2.	CAV-126**	iso. CA sys. fr. RC letdn.	60
	CAV-1**	iso. CA sys. fr. pzr.	60
	CAV-3**		60
	CAV-2**	iso. CA sys.	60
	CAV-4 #**	isolate liquid sampling	60
	CAV-6 #**	system	60
	CAV-5 #**	문 정강하는 것이 많이 같은 것이 없는 것이다.	60
	CAV-7 #**		60
2	CEV-20 check	iso. No supply fr. CFT-1A	NA
3.	CFV-28**		60
	CFV-17 check	iso. N ₂ supply fr. CFT-1B	NA
	CF V-27**		60
	CFV-18 check	iso. MU system fr. CFT-1B	NA
	CF V-26**	- 승규가 열 것 이 것 같아요. ^ ^ ^ ^ ^ ^ ^ ^ ^ ^ ^ ^ ^ ^ ^ ^ ^ ^ ^	60
	CFV-19 check	isol MU system fr. CFT-1A	NA
	CF V-25**		60
	CFV-42**	iso. liquid sampling fr.	60
		CF system	
	CFV-15**	iso. WD sys. fr. CF tanks	60
	CFV-16**		60
	CFV-29**		60
	CFV-11**	iso. CF tanks fr. liquid	60
	CFV-12**	sampling system	60
4.	CIV-41**	iso. CI sys. fr. RB	60
	CIV-40**		60
	CIV-34**		60
	CIV_35**		60

A.

τ,

CRYSTAL RIVER - UNIT 3

3/4 6-17

ABLE 3.6-1 (Continued)

CONTAINMENT ISOLATION VALVES

VALV	E NUMBER	FUNCTION	ISOLATION TIME (seconds)
5.	DHV-93 check DHV-91	iso. DH system fr. pzr.	NA 60
	DHV-43 # DHV-42 #	iso. DH sys. fr. RB sump	120 120
	DHV-4# & 41#	iso. DH sys. Fr. RC	120
	DHV-6 # DHV-5 #	iso. DH system from Reactor Vessel	60 60
6.	DWV-162 check DWV-160	iso. system	NA 60
7.	FWV-44 check # FWV-45 check #	iso. feedwater from RCSG-1A	NA NA
	FWV-43 check # FWV-45 check #	iso. feedwater from RCSG-1B	NA NA
8.	MSV-130 #**	from RCSG-1A	60
	MSV-148 #**	from RCSG-1B	60
	MSV-411 #	iso. main steam lines from RCSG-1A	60
	MSV-412 #	iso. main steam lines from RCSG-1A	60
	MSV-413 #	iso. main steam lines from RCSG-1B	60
	MSV-414 #	iso. main steam lines from RCSG-1B	60
9.	MUV-40** MUV-41** MUV-49 MUV-253	iso. MU system from RC	60 60 60 60
	MUV-261 MUV-260 MUV-259 MUV-258	iso. MU system from control bleed-off	60 60 60 60

CRYSTAL RIVER - UNIT 3

3/4 6-18

1749 161

TABLE 3.6-1 (Continued)

CONTAINMENT ISOLATION VALVES

VAL VE NUMBER

FUNCTION

ISOLATION TIME (seconds)

9. (Continued)

	MUV-163 check #	open during HPI and	NA 60
	MUV-25 #	iso. dur. nor. operación	NA
	MUV-164 Check #		60
	MUV-20 #	anon during HDI and	NA
	MUV-160 Check #	ice during hri and	60
	MUV-23 #	1so. dur. nor. operación	00
	MUV-161 check #	open during HPI and	NA
	MUV-24 #	iso. dur. nor. operation	60
	MUV-27 #	open dur. nor. operation	60
		and closed during RB Isolation	
10.	SWV-39 #	iso. NSCCC from AHF-1C	60
	SWV-45 #	특별 경험 이야지 않는 것이 있는 것이 없다.	60
	SWV-35 #	iso. NSCCC from AHF-1A	60
	SWV-41 #		60
	SWV-37 #	iso. NSCCC from AHF-1B	60
	SWV-43 #	정한 방법에 전화 방법 것 같아요.	60
	SWV-48 #**	to isolate NSCCC from	60
	SWV-47 #**	MUHE-1A & 1B and WDT-5	60
	SWV-49 #**		60
	SWV-50 #**		60
	SWV-80 #	iso. NSCCC from RCP-1A	60
	SWV-84 #		60
	SWV-82 #	iso. NSCCC from RCP-1C	60
	SWV-86 #		60
	SWV-81 #	iso. NSCCC from RCP-1D	60
	SWV-85 #		60
	SWV-79 #	iso. NSCCC from RCP-1B	60
	SWV-83 #		60
	SWV-109#	NSCCC to DRRD-1	60
	SWV-110#		60
	SHITTOF		

CRYSTAL RIVER - UNIT 3 3/4 6-19

TABLE 3.6-1 (Cont'nued)

CONTAINMENT ISOLATION VALVES

VAL	VE NUMBER	FUNCTION	ISOLATION TIME (seconds)
10.	WD V-4** WD V-3**	iso. WDT-4 from RB sump	60 60
	WDV-60** & 61** WDV-94** & 62**	iso. WDT-4 from WDT-5 iso. WDT-4 from WDP-8	60 60
	WD V-406** WD V-405**	iso. gas waste disposal from vents in RC system	60 60
12.	WSV-3 WSV-4 WSV-5 WSV-6	iso. containment monitoring system from RB	60 60 60 60
. CONT	AINMENT PURGE AND EX	HAUST	
1.	AHV-1C & 1D	iso. pur. sup. system	60
	AHV-18 & 1A	iso. pur. exhaust system	60
. MANU	AL		
1.	IAV-28* IAV-29*	iso. IA from RB	NA NA
2.	LRV-50 LRV-36	iso. leak rate test system from RB	NA NA
	LRV-51 LRV-35 & 47	iso. atmos. vent and RB purge exhaust system from RB	NA NA
	LRV-49 LRV-38 & 52	iso. atmos. vent from RB	NA NA
	LR V-45 LR V-44	iso. LR test panel from RB	NA NA
3.	MSV-146#	iso. NG system from tank from RCSG-1B	NA
4.	NG V-62* NG V-82 #*	iso. NG system from steam generators	NA NA
	NG V-82*	iso. NG system from pzr.	NA
RYSTAL	RIVER - UNIT 3	3/4 6-20	

TABLE 3.6-1 (Continued)

CONTAINMENT ISOLATION VALVES

VAL	E NUMBER	FUNCTION	ISOLATION TIME (seconds)
5.	SA V-24*	iso. SA from RB	NA
6.	SFV-18 SFV-19	iso. SF system	NA NA
	SFV-119 # SFV-120 #	iso. Fuel Transfer tubes from F.T. Canal	NA NA
7.	WSV-1* WSV-2*	containment monitoring system from RB	NA NA
		THE D TEST	

D. PENETRATIONS REQUIRING TYPE B TESTS

Blind Flange 119	iso. RB	NA
Blind Flange 120		NA
Blind Flange 116		NA
Blind Flange 202		NA
Blind Flange 348	iso. fuel transfer tube from	NA
Blind Flange 436	Transfer Canal	NA
Equipment Hatch	iso. RB	NA
Personnel Hatch	iso. RB	NA

Not subject to Type C Leakage Test * May be opened on an intermittent basis under administrative control

1749 164

CRYSTAL RIVER - UNIT 3 3/4 6-21