



UNITED STATES
NUCLEAR REGULATORY COMMISSION
REGION II
101 MARIETTA ST., N.W., SUITE 3100
ATLANTA, GEORGIA 30303

TIC
50-413
414

OCT 19 1979

In Reply Refer To:

- RII:JPO
- 50-413, 50-414
- 50-488, 50-489
- 50-490, 50-491
- 50-492, 50-493

Duke Power Company
 Attn: L. C. Dail, Vice President
 Design Engineering
 P. O. Box 33189
 Charlotte, North Carolina 28242

Gentlemen:

Enclosed is IE Circular No. 79-21, "Prevention of Unplanned Releases of Radioactivity," which provides information in inadvertent releases/on-site spills of radioactivity. Should you have any questions related to the enclosed suggested preventive measures, please contact this office.

Sincerely,

James P. O'Reilly
Director

Enclosures:

- 1. IE Circular 79-21
- 2. IE Circulars Issued
in the Last Six Months

1296 179

7911080 291

Q

OCT 19 1979

Duke Power Company

-2-

cc w/encl:

D. G. Beam, Project Manager

Post Office Box 223

Clover, South Carolina 29710

J. T. Moore, Project Manager

Post Office Box 422

Gaffney, South Carolina 29340

1296 180

UNITED STATES
NUCLEAR REGULATORY COMMISSION
OFFICE OF INSPECTION AND ENFORCEMENT
WASHINGTON, D.C. 20555

October 19, 1979

IE Circular No. 79-21

PREVENTION OF UNPLANNED RELEASES OF RADIOACTIVITY

Numerous incidents of unplanned releases of radioactivity have been reported to the NRC within the past few months. These incidents of leaks, overflows and spills have resulted in contamination of areas outside of plant buildings. The attached table provides you with summary information on these events, their apparent causes, the radiological consequences and the corrective actions.

We believe that a number of these incidents could have been avoided and preventive actions for these types of unplanned releases should be instituted by all reactor licensees. Based on the reported incidents, the following preventive measures can minimize the occurrence of such events.

1. Review of procedures for transfer of radioactive liquids. Errors in written procedures have led to mistakes in valve line-ups and tank overflows. Written procedures, including check lists for valve line-ups, should be developed and followed for operations which could cause spills of radioactivity. Management controls, including audits, should be employed to assure verbatim compliance with such procedures.
2. Review of "as built" systems having the potential of inadvertent releases because of design or construction errors. Consider items such as:
 - a. Tank overflows should be routed to liquid radwaste tanks.
 - b. Storm drains should be located away from areas with a high potential for spills.
 - c. Consideration should be given to drip pans under equipment, such as pumps and valves, from which leakage is expected.
 - d. Cofferdams should be installed under doors to areas with a potential for radioactive spills.
 - e. Preoperational testing should be done that would permit radioactivity unit(s) under construction.
3. Periodically functionally test and repair of systems that could cause an inadvertent corrosion degradation have occurred to cause leaks. New permanent and temporary repairs should be made.

DUPLICATE DOCUMENT

Entire document previously entered into system under:

ANO

7908220128

No. of pages: 7

1296 181