



Portland General Electric Company

Donald J. Broehl Assistant Vice President

December 13, 1979

Mr. R. H. Engelken, Director
U. S. Nuclear Regulatory Commission
Region V
Suite 202, Walnut Creek Plaza
1990 N. California Blvd.
Walnut Creek, CA 94596

Dear Sir:

Enclosed are responses to the five questions posed at the exit meeting on December 6, 1979 in Bethesda, Maryland regarding LER 79-15 and supplements thereto.

Sincerely,

c: Mr. A. Schwencer, Chief
Operating Reactors Branch #1
Division of Operating Reactors
U. S. Nuclear Regulatory Commission

Mr. Lynn Frank, Director
State of Oregon
Department of Energy

95001142

8001100097

Describe the state of stress at the interface of the masonry block and the mortar, for mortared double-wythe masonry walls, and at the interface of the masonry and core concrete for composite walls considering the following:

- a. In-plane seismic loads
- b. Out-of-plane seismic loads including pipe restraint reactions
- c. Interstory displacements

Provide the above information for three representative walls of each type (mortared, double-wythe and composite wall types) which have the highest loading conditions per a, b, and c above. Show each interface load (stress) separately.

Answer:

The predicted interface shear stresses between masonry block and mortar for three highly stressed double wythe masonry walls and between masonry block and core concrete for three highly stressed composite walls, as well as the vertical reinforcing steel stresses for these walls, are shown in Tables 1 through 6.

Walls at el. 5 ft are selected for investigation because they resist large pipe support reactions. Walls at el. 61 ft and 72 ft are selected because they resist large seismic in-plane and out-of-plane forces. These forces include the global building shear forces, the forces produced by interstory displacement and the wall inertial loads.

95001143

This analysis is performed for the Safe Shutdown Earthquake condition using the criteria specified in Supplement 1 to LER 79-15. The effects of wall dead load and vertical seismic load were neglected to provide conservatism in the analyses of the vertical reinforcing steel stresses. The results indicate that for the walls analyzed, the interface shear stresses are substantially lower than the allowables (18 psi for double wythe masonry walls and 40 psi for composite walls) specified in Supplements 1 and 2 to LER 79-15. The stresses in the reinforcing steel are also within the limits specified in those supplements.

95001144

TABLE 1
STRESSES IN 30 IN/H COMPOSITE WALL AT EL. 5'-0"
ON COLUMN LINE 54 BETWEEN COLUMN LINES D AND E

Loads			In-Plane Stresses			Out-of-Plane Stresses				
						V (lbs/ft)	Base of Wall		Mid-Section of Wall	
			V (lbs/ft)	v (psi)	f _s (psi)		V (lbs/ft)	v (psi)	f _s (psi)	v (psi)
E-W	E'	Inertial Acceleration	780	3.2	1,850	-	-	-	-	-
		Building Response	-	-	-	-	-	-	-	-
		Interstory Displacement	-	-	-	-	-	-	-	-
	H ₀		560	2.3	1,300	1,550	7.2	7,660	1.0	4,600
N-S	E'	Inertial Acceleration	-	-	-	780	3.2	5,500	0.0	2,800
		Building Response	-	-	-	-	-	-	-	-
		Interstory Displacement	-	-	-	-	-	-	-	-
	H ₀		560	2.3	1,300	1,550	7.2	7,660	1.0	4,600

DEFINITIONS

- E' = Safe Shutdown Earthquake resulting from ground surface acceleration of 0.25g.
H₀ = Forces on structure from pipe supports on wall including seismic load, thermal, etc.
V = Shear force on wall in the in-plane or out-of-plane direction.
v = Concrete shear stress.
f_s = Vertical reinforcing steel stress.

TABLE 2
STRESSES IN 27 INCH COMPOSITE WALL AT EL. 61'-0"
ON COLUMN LINE 51 BETWEEN COLUMN LINES E AND F

Loads			In-Plane Stresses			Out-of-Plane Stresses				
						V (lbs/ft)	Base of Wall		Mid-Section of Wall	
			V (lbs/ft)	v (psi)	f _s (psi)		V (lbs/ft)	v (psi)	f _s (psi)	v (psi)
E-W	E'	Inertial Acceleration	1,220	5.6	1,310	680	3.1	4,900	0	2,440
		Building Response	11,300	52.0	22,010	-	-	-	-	-
		Interstory Displacement	-	-	-	50	0.2	1,060	0.2	0
	H ₀		250	1.2	400	240	1.1	1,750	0	1,240
N-S	E'	Inertial Acceleration	680	3.1	730	1,000	4.6	7,220	0	3,610
		Building Response	-	-	-	-	-	-	-	-
		Interstory Displacement	4,360	20.1	7,030	110	0.5	2,340	0.5	0
	H ₀		250	1.2	400	240	1.1	1,750	0	1,240

DEFINITIONS

E' = Safe Shutdown Earthquake resulting from ground surface acceleration of 0.25g.

H_0 = Forces on structure from pipe supports on wall including seismic load, thermal, etc.

V = Shear force on wall in the in-plane or out-of-plane direction.

τ = Concrete shear stress.

f_s = Vertical reinforcing steel stress.

TABLE 3
STRESSES IN 34 INCH COMPOSITE WALL AT EL. 72'-0"
ON COLUMN LINE F BETWEEN COLUMN LINES 55 AND 60

Loads			In-Plane Stresses			Out-of-Plane Stresses				
						V (lbs/ft)	Base of Wall		Mid-Section of Wall	
			V (lbs/ft)	v (psi)	f _s (psi)		V (lbs/ft)	v (psi)	f _s (psi)	v (psi)
E-W	E'	Inertial Acceleration	980	3.6	1,050	1,640	6.0	11,170	0	5,590
		Building Response	-	-	-	-	-	-	-	-
		Interstory Displacement	6,540	24.0	21,100	160	0.6	3,270	0.6	0
	H ₀		250	1.0	270	250	1.0	1,700	0	850
N-S	E'	Inertial Acceleration	1,640	6.0	1,755	980	3.6	6,680	0	3,340
		Building Response	7,250	26.7	23,440	-	-	-	-	-
		Interstory Displacement	-	-	-	160	0.6	3,270	0.6	0
	H ₀		250	1.0	270	250	1.0	1,700	0	850

DEFINITIONS

E' = Safe Shutdown Earthquake resulting from ground surface acceleration of 0.25g.

H₀ = Forces on structure from pipe supports on wall including seismic load, thermal, etc.

V = Shear force on wall in the in-plane or out-of-plane direction.

v = Concrete shear stress.

f_s = Vertical reinforcing steel stress.

TABLE 4
STRESSES IN 14 INCH BLOCK WALL AT EL. 5'-0"
ON COLUMN LINE 49 BETWEEN COLUMN LINES D AND E

Loads			In-Plane Stresses			Out-of-Plane Stresses				
						V (lbs/ft)	Base of Wall		Mid-Section of Wall	
			V (lbs/ft)	v (psi)	f _s (psi)		V (lbs/ft)	v (psi)	f _s (psi)	v (psi)
E-W	E'	Inertial Acceleration	400	3.6	1,140	-	-	-	-	-
		Building Response	-	-	-	-	-	-	-	-
		Interstory Displacement	-	-	-	-	-	-	-	-
	H ₀		60	0.5	170	400	3.7	24,600	1.0	14,600
N-S	E'	Inertial Acceleration	-	-	-	560	5.4	25,100	0	12,600
		Building Response	-	-	-	-	-	-	-	-
		Interstory Displacement	-	-	-	-	-	-	-	-
	H ₀		60	0.5	170	33	0.3	1,820	0.5	2,140

DEFINITIONS

- E' = Safe Shutdown Earthquake resulting from ground surface acceleration of 0.25g.
H₀ = Forces on structure from pipe supports on wall including seismic load, thermal, etc.
V = Shear force on wall in the in-plane or out-of-plane direction.
v = Concrete shear stress.
f_s = Vertical reinforcing steel stress.

75001149

TABLE 5
STRESSES IN 14 INCH BLOCK WALL AT EL. 61'-0"
ON COLUMN LINE 55 BETWEEN COLUMN LINES C AND D

Loads			In-Plane Stresses			Out-of-Plane Stresses				
						V (lbs/ft)	Base of Wall		Mid-Section of Wall	
			V (lbs/ft)	v (psi)	f _s (psi)		V (lbs/ft)	v (psi)	f _s (psi)	v (psi)
E-W	E'	Inertial Acceleration	290	2.6	320	160	1.4	2,900	0	1,450
		Building Response	4,200	36.3	14,800	-	-	-	-	-
		Interstory Displacement	-	-	-	30	0.3	1,620	0.3	0
	H ₀		-	-	-	350	3.3	4,900	0	4,500
N-S	E'	Inertial Acceleration	160	1.4	530	290	2.6	4,300	0	2,150
		Building Response	-	-	-	-	-	-	-	-
		Interstory Displacement	870	7.9	3,200	40	0.4	2,160	0.4	0
	H ₀		-	-	-	350	3.3	4,900	0	4,500

DEFINITIONS

- E' = Safe Shutdown Earthquake resulting from ground surface acceleration of 0.25g.
H₀ = Forces on structure from pipe supports on wall including seismic load, thermal, etc.
V = Shear force on wall in the in-plane or out-of-plane direction.
v = Concrete shear stress.
f_s = Vertical reinforcing steel stress.

95001150

TABLE 6
STRESSES IN 14 INCH BLOCK WALL AT EL. 61'-0"
ON COLUMN LINE 55 BETWEEN COLUMN LINES C AND D

Loads			In-Plane Stresses			Out-of-Plane Stresses				
						V (lbs/ft)	v (psi)	f _s (psi)	Base of Wall	
			V (lbs/ft)	v (psi)	f _s (psi)				v (psi)	f _s (psi)
E-W	E'	Inertial Acceleration	340	3.0	250	340	3.0	7,700	0	3,850
		Building Response	1,900	17.0	9,410	-	-	-	-	-
		Interstory Displacement	-	-	-	15	0.1	1,030	0.1	0
	H ₀		150	1.4	750	370	3.3	13,000	3.3	13,000
N-S	E'	Inertial Acceleration	340	3.0	250	340	3.0	7,700	0	3,850
		Building Response	-	-	-	-	-	-	-	-
		Interstory Displacement	700	6.2	3,420	40	0.4	320	0.4	0
	H ₀		150	1.4	750	370	3.3	13,000	3.3	13,000

DEFINITIONS

E' = Safe Shutdown Earthquake resulting from ground surface acceleration of 0.25g.

H₀ = Forces on structure from pipe supports on wall including seismic load, thermal, etc.

V = Shear force on wall in the in-plane or out-of-plane direction.

v = Concrete shear stress.

f_s = Vertical reinforcing steel stress.

Provide the basis for the stress distribution considered at the interface between the masonry block and concrete core due to pipe restraint anchor bolt loads.

Answer:

The resistance to tension developed in an expansion anchor bolt occurs in the flared section at the end of the anchor bolt. If a tensile force is placed on the bolt, shear and compression stresses develop in the zone adjacent to and above the flared portion. The load is thereby distributed horizontally to the surface of the wall. The load spreading may be considered as a 45° shear cone which projects to the surface (see Figure 2-1). To estimate the tension at the interface between the masonry block and concrete core, the vertical component of the stress on the shear cone is assumed to be uniformly distributed over the circular area formed by the intersection of the cone and the block surface. The tension on the masonry block-concrete core interface due to the surface stresses can be estimated using theories developed by Boussinesq for determination of stress distributions in an elastic media⁽¹⁾. The normal stress at the block-core interface as derived from this theory is shown on Figure 2-1. The maximum stress was calculated from the Boussinesq equation for a circular area with a uniform load, and the stress distribution was obtained from stress curves⁽²⁾. Also shown is an average normal stress for a cone with 2:1 slope (Cone 1). It can be seen that this cone gives a good approximation of the stress calculated from the Boussinesq equation at the interface.

The tension on the masonry block-concrete core interface due to the surface stresses can also be calculated using theories developed by Westergaard for calculation of soil stresses under circular foundations. The stress coefficients are shown in Table 2-1 along with a comparison

of the stress if cone 1 (2:1 slope) and cone 2 (1:1 slope) shown in Figure 2-1 are used. This table gives the ratio of the maximum stress at depth Z with the applied uniform stress at the surface for the four methods indicated. For expansion anchor bolts ranging in size from 1/2 in. to 7/8 in. in diameter, the ratio $Z/2R$ ranges from 1.7 to 1.0 where R is the radius of the shear cone at the surface. For this range, cone 2 underestimates the stress and cone 1 provides an overestimate. For the upper range of $Z/2R$, the overestimate is by a factor of 2 to 3. Therefore, cone 1 is considered to provide a reasonable representation of the stress distribution and was used for calculating distribution for the tension stress at the concrete core-block interface.

References:


- (1) Timoshenko and Goodier, Theory of Elasticity, McGraw-Hill, 1951, p 97 ff
- (2) Lambe and Whitman, Soil Mechanics, Wiley & Sons, 1969, p 101

95001152

TABLE 2-1
MAXIMUM STRESS COEFFICIENTS

Z/2R	Stress Coefficients			
	Westergaard (Maximum)	Boussinesq (Maximum)	Cone 1 (Average)	Cone 2 (Average)
0.25	0.66	0.89	0.64	0.44
0.50	0.44	0.65	0.44	0.25
0.75	0.26	0.43	0.38	0.16
1.00	0.16	0.29	0.25	
1.25	0.12	0.20	0.20	0.0
1.50	0.05	0.09	0.16	0.06
1.75	0.04	0.06	0.13	0.05
2.00	0.03	0.05	0.11	0.04

95001153



BLOCK-CORE INTERFACE NORMAL STRESS DISTRIBUTION

N.T.S.

NRC Question (12/6/79)

Question 3 Page 1 of 2

Provide documentation which will substantiate the extent of inspection performed on masonry construction to support your claim that the masonry construction at Trojan qualifies under the category of "special inspection" per the UBC. Also provide additional verification of the completeness of mortar between masonry wythes based on field testing and inspection (1" \pm diameter core drills).

Answer:

Installation of the concrete unit masonry was performed by L. C. Pardue, a subcontractor to Hoffman Construction Company. This subcontractor implemented a QA Program in conformance with applicable sections of Appendix B to 10 CFR 50, which contained inspection responsibilities that were performed on a daily basis. Hoffman Construction Company's QA procedures assured the quality of L. C. Pardue's effort. In addition, both the Construction Manager (CM) and the Licensee implemented QA programs which contained inspection and monitoring requirements. The CM performed daily inspection of the masonry work to assure conformance with drawing and specification requirements. The implementation of such programs and procedures is evidenced by QA audit reports, nonconformance reports, and inspection reports. Attachment 3-1 provides a sampling of such reports.

To assure that the specified requirements were met during the construction period, the Licensee contracted with Northwest Testing Laboratory (an independent testing laboratory) to provide on-site inspection and testing services for masonry and concrete. One of the services they provided was furnishing qualified inspectors to perform daily inspection of masonry wall construction and testing of materials used therein. This laboratory implemented a QA program approved by the CM. Attachment 3-2 is a letter from Northwest Testing Laboratory which documents the fact that their inspection of the masonry construction at Trojan qualifies the work under the UBC classification of "Special Inspection".

95001155

The inspection of walls identified in Attachment 5, Supplement 2 to LER 79-15 disclosed some void areas in the inter-wythe mortar. As voids were found, they were filled with Five Star Grout in accordance with manufacturer's instructions. In addition to those walls, the N-line wall at elevation 65, the 46-line wall at elevations 61 and 77, and the east wall of the Control Building Mechanical Room at elevations 61 and 77 have been field checked for the presence of inter-wythe mortar by random sampling with a 1-1/2" core drill of 10 locations at different elevations in each wall. Based on this sampling, greater than 90% mortar was determined to be present in each wall, which is substantially greater than that required to develop the 18 psi shear capacity allowed by 1.5 UBC.

NORTHWEST TESTING LABORATORIES

4118 N. MISSISSIPPI AVENUE
PORTLAND 17, OREGONON FEDERAL HIGHWAYS
GENERAL CONSTRUCTION INSPECTION
PORTLAND, OREGON
EASTERN DISTRICTGENERAL CONSTRUCTION INSPECTION
DAILY REPORTBUILDING CODES 121-00
20081-00
OBS. TEST NO.
DATE 9.5.51Project: Trinity Nuclear PlantEngineer: BechtelArchitect: deContractors: PardueMasonry: PardueConcrete: HoffmanSteel: JimNo.: 648Location: Trinity Nuclear PlantDate: 28 April 72Time: 5:00 - Midnight

Mix Proportions:

Masonry

Grout

Mortar 1:2:4 Cement to Sand
and 3/4" coarse sand

Concrete

Compression Tests Prepared

Set No.

Ref. No.

Slump

1

M-2

44-20-20

Source

Ticket No.

Load No.

Temp.

41°

Weather Clear to Cloudy Quantity

Pour Location and Notes: Trinity Nuclear Plant
Wall, Containment Building. Constructed small copper dam along
block line to go to West dry on low side. This area
later removed.
Spills in this wall, which show, are being worked out
thus making a very neat appearing job.

Reinforcing Steel Inspection and Notes:

Steel in tie for floor and drainage
also 1 additional row of 3 bars was installed 2' of
space to prevent this from from kicking out when being
filled in core area later.

95001157

POOR ORIGINAL

Inspector's Signature
Concrete Permit No.
Masonry Permit No.



POOR ORIGINAL

Attachment 3.7

NONCONFORMANCE REPORT				PAGE 1 OF 1		No. 13	
PARDUE		Class 1 <input checked="" type="checkbox"/> Other <input type="checkbox"/>		SKETCH ATTACHED <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO		DATE 11/2/73	
ITEM FIELD		AREA/BLDG		DWG/PART NO		REV & ITEM NAME	
Main Area 3 A. BLDG		647E		A-70		9 Void in Cell 611	
INSPECTION CRITERIA				DOCUMENT NUMBER & TITLE			
DWG <input type="checkbox"/> SPEC <input type="checkbox"/> MRI <input type="checkbox"/> OTHER <input type="checkbox"/> (EXPLAIN)							
SOURCE SUPPLIER <input checked="" type="checkbox"/> ENGRG <input type="checkbox"/> CONSTR <input type="checkbox"/>				ADDRESS		P.O. No.	
						NA	
11. NONCONFORMANCE (DISCREPANCY) DESCRIPTION (LIST IDENTIFICATION NUMBERS WHERE APPLICABLE)							
1 3-61-19 East West side Small on Floor 21-22							
2 3-61-19 1/2 m. East West side of partition between Rm 192-193-200							
3 3-61-20 North side of small on Floor 21							
4 3-61-24 North side of small on Floor 203-204							
5 3-61-23 East West side of wall between Rm 203-204							
6 3-61-24 North side of wall between Rm 203-204							
7 3-61-20 Small wall around sewage tank Rm 204							
8 3-61-24 East West side of wall between Rm 204-205							
9 3-61-27 East West side of wall between Rm 203-205-200							
All 8" walls							
12. FIELD PRELIMINARY DISPOSITION							
Provide clean cut holes at bottom of Void. Remove debris & inspect with a mission to detect any obstructions in the wall. A hole will be provided at the top of Void and 6-1 Grout used to fill void area. No repair work will be done until approved by the engineer. A properly signed pour card will be provided.							
13. NCR PREPARED BY John King				14. APPROVAL OF FIELD PRELIMINARY DISPOSITION Hoffman Const. Co. 11/5/73			
15. FINAL DISPOSITION REPAIR <input type="checkbox"/> REJECT <input type="checkbox"/> USE AS IS <input type="checkbox"/> SEE BELOW <input checked="" type="checkbox"/>				NEW DCN REQD YES <input type="checkbox"/> NO <input type="checkbox"/> DCN NO			
FORCED AS INDICATED IN ITEM #12							
RECEIVED NOV 12 1973 HOFFMAN CONST. CO./FOA TROMAN NUCLEAR PLANT							
APPROVAL OF FINAL DISPOSITION		DATE 11/11/73		REINSPECTION ACCEPT <input checked="" type="checkbox"/> REJECT <input type="checkbox"/>		SIGNATURE John King 11/22/73	

SHOTS ORIGINATOR
YELLOW-PARDUE OR

PINE DE ENGR
SOLDENRADO OR ENGR

95001158

POOR ORIGINAL

Attachment 3-1



BECHTEL CORPORATION
FIELD INSPECTION/SURVEILLANCE REPORT OC-5C

1. SHEET / OF L

TROJAN PROJECT - JOB 6478

7. CRITERIA SEE BELOW

2. DATE 7 May 74 3. SHIFT DAY

4. LOCATION SEE BELOW

8. CONTRACTOR SEE BELOW

5. ELEVATION SEE BELOW

9. CONTRACTOR (OTHER)

6. "O" LIST NO. SEE BELOW

10. WEATHER CLOUDY

AREA 3, EIC 93, G 1.113, A-1, PARDUE

WRITER OBSERVED CONTRACTOR QA MANAGER AND A CIVIL
FIELD ENGINEER MONITORING THE GRADING OF WALL ON
THIS LEVEL. NO DISCREPANCIES WERE NOTED.

AREA 3, EIC 77, G 1.113, A-1, PARDUE

WRITER OBSERVED CONTRACTOR QA MANAGER AND A CIVIL
FIELD ENGINEER MONITORING BLOCK MASONRY IN THIS AREA.

AREA 3, EIC 77, G 4.52, E 83, F12

WRITER OBSERVED ELECTRICAL CABLES RESTING ON SHARP
EDGE OF TRAY RIE 305. WRITER WILL INFORM CONTRACTOR
QA MANAGER ON 10 MAY 74.

AREA 3, EIC 95, G 3.2410, H-1, F03

WRITER OBSERVED SALT DEPOSITS ON THE SIDE OF TUGSD
SIC ACCUMULATED. INFORMED ENGINEER.

95001159

12. PREPARED BY

Patrick M. O'Brien

DATE

7 May 74

13. REVIEWED BY

DATE

Attachment 3-1
NORTHWEST TESTING LABORATORIES

POOR ORIGINAL

4115 N. Mississippi Avenue
Eugene, Oregon 97217
766-7086

4427 N. Eugene Way
Eugene, Oregon 97105
766-8049

CONCRETE COMPRESSION TESTS

Tested For: P.G.E. Cert. No. M-19
 Cast By: W. Carter Slump: _____
 Project: Trojan Date Made: 10-17-73
 Proportions: _____ Plus _____ % psi concrete _____ Date Rec'd. _____
 _____ sack mix _____ max. sized aggregate _____
 Additives: 1 lb. Cement, 1 lb. lime, 2.4 cu ft. Sand
 Source: Contractors Supply Bn.
 Condition of Storage: _____
 Ticket No.: _____ Air Temp: 50° Time: 11:00 am cy. yds. _____
 Load No.: _____ Conc. Temp: _____ Weather: Overcast % Air _____
 Location of Pour: Room 312 Elev 72 Area 2 North Wall

Test Date	Notes	Weight Pounds	Max. Load	Load (lb. per cu. ft.)	Average	Air Temp	Remarks
10-24			7.6	2420		7	
"			7.4	2360		7	
11-14			14.8	4715		2.8	
"			14.5	4615		2.8	

Test No. _____ Prepared By: (Signature)

95001160

NORTHWEST TESTING LABORATORIES

4115 N. MISSISSIPPI AVENUE
PORTLAND 17, OREGONMATERIALS INSPECTOR
CONSTRUCTION INSPECTOR
PHYSICAL TESTS
CHEMICAL ANALYSIS

GENERAL CONSTRUCTION INSPECTION

WELDING CERTIFICATION
ASBESTOS
SOIL TESTING
BACTERIOLOGY

DAILY REPORT

Project: Trojan Nuclear PlantEngineer: Richard C. CadyPermit No.: 54178

Architect: _____

Location: Reiner, OregonContractors: PardeeDate: 2-15-74

Masonry: _____

Concrete: H. J. ManSteel: T. M.

Time: _____

Mix Proportions:

Masonry

Grout _____

Mortar _____

Concrete _____

Compression Tests Prepared

Set No.	Ref. No.	Stamp

Source _____ Ticket No. _____ Load No. _____

Temp. 48° Weather Rain Quantity _____

Four Location and Notes: No work performed today. (Continued) Line
Block area 12 elev 45' to top of wall 11 10 x 4.
Continued on line 8 area 9 elev 415

Reinforcing Steel Inspection and Notes: Reinforcing steel placed as per
approved drawings & specifications

Inspector's Signature

Concrete Permit No.

Masonry Permit No.

B. Smith
399

NORTHWEST TESTING LABORATORIES

A-1

5 N. Mississippi Avenue
Portland, Oregon 97217
255-7088

POOR ORIGINAL

6427 Nugget Way
Eugene, Oregon 97403
746 9649

MORTAR Cyls

CONCRETE COMPRESSION TESTS

Tested For: DGE Cert. No. M-3
 Cast By: JOHN B. NO - DAN REED Slump: MORTAR
 Project: TRAVAN Date Made: 8 MAY 72
 Proportions: FOCO Plus % pci concrete Date Rec'd. 8 MAY 72
 sack mix max. sized aggregate

Address: 1 SACK CEMENT 1 1/2 SACK LIME 3.4 cu ft. SAND
 Source: VERSITE

Condition of Storage: ASTM

Ticket No.: N/A Air Temp: 62 Time: 1 PM of yr. N/A

Prod No.: 3 Conc. Temp: 60 Weather: CLEAR % Air

Location of Pour: REPRESENTATIVE OF MORTAR USED IN 41 LINE
INTER WALL - CENTRAL BLDG 55 LEVEL 2

Test Spec	Mark	Weight Pounds	Max. Load	Load (lb. per sq. in.)	Average	Age Years	Remarks
S.M.H.			220	2290		7 days	
do			195	2180		do	
JULY			9.0	2765		28 days	
do			9.2	2780		do	

Pl. No. Prepared by (initial)

12

95001162

POOR ORIGINAL WLY

NORTHWEST TESTING LABORATORIES

4110 N. MISSISSIPPI AVENUE
PORTLAND 17 OREGONGENERAL CONSTRUCTION INSPECTION
DAILY REPORTBUILDING LEAD TIME
2000 - 100
5000 - 100
10000 - 100
20000 - 100DATE OF REPORT
CONTRACTOR'S REPRESENTATIVE
PROJECT NO.
SHEET NO.Project: TERTAN NUCLEAR PLANTEngineer: BECHTEL CORP.Permit No.: 6478

Architect: _____

Location: Reinier, Oregon

Contractor: _____

Date: 10-15-74Masonry: PurdueTime: 8:00 to 4:30Concrete: HoffmanSteel: Tri-MMix Proportions
Masonry

Compression Tests Prepared

Set No.	Ref. No.	Slump

Concrete

Source _____ Ticket No. _____ Load No. _____

Temp. 63° Weather Cloudy Quantity _____

Pour Location and Notes: No grout placed this date. Continued laying block at the following locations: Room 260, Wall 8 Elev. 66' Area 3. Room 192 Wall 8 Elev. 61' Area 3. Room 201 Wall 16 Elev. 61' Area 3 - Heavy W. block used at all locations.

Reinforcing Steel Inspection and Notes: Reinforcing steel placed as per approved drawings & specifications.

 Inspector's Signature: [Signature]
 Concrete Permit No. _____
 Masonry Permit No. _____

95001163

NORTHWEST TESTING LABORATORIES

4118 N. MISSISSIPPI AVENUE
PORTLAND 17, OREGONGENERAL CONSTRUCTION INSPECTION
DAILY REPORTWELDING CERTIFICATE NO.
ASSAYING
100% TESTING
BACTERIOLOGYProject: Super Nuclear PlantEngineer: BeckelPermit No.: 6478Architect: -de-Location: Rainier OregonContractors: IndueDate: May 72Concrete: StopmanTime: 4:30 MidnightSteel: Gr 60

Mix Proportions:

Masonry

Compression Tests Prepared

Grout

Set No.	Ref. No.	Slump

Mortar Black Cement 1/2 sack lime2.5 bags sand

Concrete

Source _____ Ticket No. _____ Load No. _____

Temp. 50 Weather Clear Quantity _____Pour Location and Notes: Topping out East shielding wallContainment bldg. Part of shift cleaning up & repairingscaffolding. Stocking Control bldg.Reinforcing Steel Inspection and Notes: Steel in as per spec &drawings.Inspector's Signature David ReedConcrete Permit No. Reed

Masonry Permit No. _____

PGOR ORIGINAL

L. C. PARDUE, INC.

TELEPHONE 222-0606

3605 S.W. CURRIET AVE. W. PORTLAND, OREGON 97201

October 17, 1972

Hoffman Construction Co.
900 S.W. Fifth
Portland, Oregon

Re: Portland General Electric Audit of L. C. Pardue Inc.

Gentlemen:


In regards to the recent audit performed by PGE of our QA records I would like to make the following statements regarding corrective action.

- 1) QA Manual: An Bechtel approved copy of the L. C. Pardue QA manual is now available in the L. C. Pardue site office as of October 6, 1972.
- 2) NRR #10263: NRR#10263 stated that all records and material were received on 7/19/72. On close examination of the test results accompanying the certification a discrepancy was found by L.C. Pardue QA personnel. The material in question was put on hold at that time until a typographical error could be corrected by Northwest Testing on 7/21/72 at which time the material was released for use. A note has been added to NRR#10263 stating the reason for the date discrepancy.
- 3) Drawings: A complete audit of all drawings was initiated upon completion of the PGE audit. Upon completion of our audit all noncurrent drawings were brought to a current status with Hoffmans drawing log.
- 4) Audits: Three audits of Empire Building Material were present in the L.C. Pardue files at the time of the PGE audit. Unfortunately one of the audit reports was filed with the field inspection reports. This brings the amount of audits of Empire to three which is in accordance with the L.C. Pardue QA manual. An audit check list has been initiated for L.C. Pardue inhouse audits.
- 5) Storage Report: A material storage and protection report has been incorporated in the Pardue field inspection report file and will be maintained.
- 6) NCR Log: L.C. Pardue NCR#3 has been closed out in the NCR log.

95001165

- 7) Pour Cards: The use of one pour card for more than one lift or pour will not be permitted in the future. The invoice number of all grout invoices will be listed on each pour card and the pour card wall numbers listed on each invoice for cross reference and material control. All pour cards and grout invoices in the L.C. Pardue file now contain this information.

Yours truly,



L. C. Pardue Jr.

POOR ORIGINAL

95001166

NORTHWEST TESTING LABORATORIES

4115 N. MISSISSIPPI AVENUE
P.O. BOX 17126
PORTLAND, OREGON 97217

CONSTRUCTION INSPECTION
MATERIALS INSPECTION
CHEMICAL ANALYSIS
PHYSICAL TESTING

NON-DESTRUCTIVE TESTING
WELDING CERTIFICATION
SOIL TESTING
ASSAYING

December 11, 1979

Portland General Electric Co.
121 SW Salmon
Portland, Oregon

Re: Masonry Inspection
Trojan Nuclear Plant
Rainier, Oregon

Gentlemen:

We would like to confirm our telephone conversation of the last few days regarding the masonry inspection at the Trojan Nuclear Plant at Rainier, Oregon.

We did as a course of our work (inspection and testing) provide special inspection of the masonry work during its construction at the Trojan Nuclear Plant.

The full time inspection of the masonry work at Trojan was performed by qualified personnel and thus would qualify for the classification in the U.B.C. as masonry work performed under special inspection.

If we can be of further service please call on us.

Very truly yours,

NORTHWEST TESTING LABORATORIES, INC.

Charles R. Lane
Charles R. Lane, P.E.
General Manager

CRL:sb

95001167

Provide documentation which supports the use of an allowable value of 18 psi (ie 12 psi x 1.5) for shear transfer at the interface between masonry block and mortar for the mortared double wythe walls.

Answer:

The following information substantiates the design criteria given in Supplements 1 and 2 to LER 79-15 relative to shear values at block-mortar interfaces.

The most relevant tests to establish shear values for vertical mortar joints in masonry construction are shear tests to demonstrate adhesion between masonry veneer and masonry backing. Albyn MackIntosh* has reviewed these test reports and has characterized them as consistently showing a value for shear stress exceeding 50 psi and ranging as high as 200 psi. The test laboratory where these tests were performed (Smith-Emery Test Laboratory, Los Angeles, California) will not release these test results since they are considered to be proprietary reports by the organizations requesting the tests. However, Bechtel was informed by the test laboratory that such consistently high shear values formed the basis for the 50 psi allowable shear stress at the veneer mortar interface in UBC Chapter 29, 1967 edition.

The most relevant available test data concerns transverse bending of multiple wythe unreinforced masonry. Failure consistently occurred in tension between mortar and masonry units at the wall surface. At this failure load, the shear stress present in the inter-wythe space can be computed even though failure has not occurred at this location. Transverse bending tests have been performed on 8 in. double wythe

* Chairman of ACI Committee 531 which is specifically charged with providing requirements for design and construction of concrete masonry and composite elements.

brick walls (Attachment 1) and 10 in. brick-hollow block "composite" walls (Reference 1). The tests performed on the 8 in. brick with metal truss wall ties (Attachment 1) provide useful information in evaluating the performance of the inter-wythe joint of the double wythe masonry wall construction at Trojan. As expected, these walls failed in tension at the horizontal brick-mortar interface when subjected to lateral bending. It is important to note that the 8 in. brick walls demonstrated an average transverse strength of over four times the average strength of similarly tested 4 in. brick walls, thus demonstrating composite action of the two wythes. At the load level at which the tensile bond failed, the inter-wythe shear can be computed to be from 9.0 psi to 14.5 psi for these brick walls (Tests TS-1 thru TS-5, Table 5-1). Because of the tension failure mode, inter-wythe shear was never fully developed. Considering the fact that the Trojan masonry walls are reinforced concrete masonry with equivalent ties and type M rather than the type S mortar used in these tests, we believe that these tests demonstrate that composite action will occur and the 12 psi allowable stress in UBC (multiplied by 1.5) is reasonable for masonry block walls. Similar results were derived from the 10 in. composite walls, tests 4C2, 4C9 through 4C11 in Reference 1.

The lateral load tests of unreinforced masonry cavity walls referred to by Mr. Mackintosh at the December 5, 1979 meeting in Bethesda, Maryland as demonstrating composite action using masonry ties only are identified in Reference 2.

References:

1. Fattal and Cattaneo, "Structural Performance of Masonry Walls under Compression and Flexure". National Bureau of Standards Building Science, Series 73. 57 pages, 1976.
2. Whittmore, Stang and Parsons, "Structural Properties of a Concrete Block Cavity Wall Construction", sponsored by the National Concrete Masonry Association. National Bureau of Standards, Building Materials and structures Report BMS 21. 10 pages, 1939.

95001169