

TABLE 4.1-3 (Continued)

	<u>Check</u>	<u>Frequency</u>	<u>Maximum Time Between Tests</u>
13. Turbine Inspection	Visual, Magnaflux and Die Penetrant	Every five years	6 years
14. Fans and Associated Charcoal and Absolute Filters for Control Room and Residual Heat Removal Compartments (HVE-19, HVE-5a and 5b respectively)	Fans functioning. Laboratory tests on charcoal must show > 99% iodine removal. In-place test must show > 99% removal of polydispersed DOP particles by the HEPA filters and Praon by the charcoal filters.	Once per operating cycle.	NA
15. Isolation Seal Water System	Functioning	Each refueling shutdown	NA
16. Overpressure Protection System	Functioning	Each refueling shutdown	NA

\*NA - Not applicable