

U.S. Department of Energy

Idaho Operations Office • Idaho National Engineering Laboratory

**Experiment Data Report For
LOFT Anticipated Transient Experiment L6-5**

**Benjamin D. Stitt
Janice M. Carpenter**

July 1980

Prepared for the
U.S. Nuclear Regulatory Commission
Under DOE Contract No. DE-AC07-76ID01570

8007280683



NOTICE

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, expressed or implied, or assumes any legal liability or responsibility for any third party's use, or the results of such use, of any information, apparatus, product or process disclosed in this report, or represents that its use by such third party would not infringe privately owned rights.

Available from

GPO Sales Program
Division of Technical Information and Document Control
U. S. Nuclear Regulatory Commission
Washington, D. C. 20555

and

National Technical Information Service
Springfield, Virginia 22161



P.O. BOX 1625, IDAHO FALLS, IDAHO 83415

July 8, 1980

Mr. R. E. Tiller, Director
Reactor Operations and Programs Division
Idaho Operations Office - DOE
Idaho Falls, Idaho 83401

EXPERIMENT DATA REPORT FOR LOFT EXPERIMENT L6-5 - Kau-153-80

Dear Mr. Tiller:

This letter transmits the Experiment Data Report (EDR) for the Loss-of-Fluid Test (LOFT) Anticipated Transient Experiment L6-5, Technical Report EGG-2045, NUREG/CR-1520.

Experiment L6-5 was conducted on May 29, 1980 and was the first experiment in the non-Loss-of-Coolant Experiment (LOCE) Test Series (Experiment Series L6). The experiment was successful and the objectives were met. Experiment L6-5 provided data for comparison of a pressurized water reactor to a loss-of-feedwater transient.

The Experiment Data Report (EDR) presents selected thermal hydraulic data from Experiment L6-5 graphically in Standard International Units. The data have been analyzed to ensure that they are reasonable and consistent.

Very truly yours,

A handwritten signature in dark ink, appearing to read 'N. C. Kaufman', is written over the typed name.

N. C. Kaufman
Director, LOFT

JMC:jlb

Enclosure:
As Stated

cc: D. L. Alf, DOE-HQ
M. Akimoto, JAERI
H. D. Axtell, EW&EB
S. Banerjee, McMaster Univ.
R. W. Barber, DSE, DOE-HQ (2)
C. H. Berlinger, NRC-HQ
W. Binner, IFR (4)
J. Block, Creare
K. J. Brinkmann, ECN (4)
G. F. Brockett, ITI
D. M. Chapin, MPR
R. Denning, BCL
S. Fabric, NRC-HQ
W. Farmer, NRC
T. Fernandez, EPRI
M. Firnhaber, GRS
R. F. Fraley, ACRS
K. P. Galbraith, NSE
G. Geissler, B&W
D. Goddard, ODE
P. Griffith, MIT
E. Hellstrand, SEAB
H. Holmstrom, VTT/YDI
J. Jackson, LASL
W. V. Johnston, NRC-HQ
W. Kato, BNL
S. Kellman, W
T. D. Knight, LASL
G. W. Knighton, NRC
N. N. Kondic, NRC-HQ
R. T. Lahey, FPI
R. R. Landry, NRC-HQ
A. J. Levine, GE
W. Loewensteir, EPRI
P. A. Lottes, ANL
D. Lummerzheim, BMFT
D. Malnes, IFA
G. Markoczy, SFIFR (5)
R. J. Mattson, NRC-HQ
F. Mayinger, LuIfV
G. D. McPherson, RSR, NRC-HQ (5)
M. Meerbaum, B&W
G. Menzel, CE
C. Moser, EI
T. E. Murley, NRC-HQ
H. Nakamura, JAERI (4)
P. E. Norian, NRC-HQ
A. Olsen, Riso (4)
G. F. Owsley, Exxon
Dr. Pfeiffer, GRS-FB (10)
D. Primeau, AECL
D. F. Ross, NRC
Z. R. Rosztoczy, NRC-HQ
L. S. Rubenstein, NRC
F. Schroeder, RNC
S. Shannor, BADL
M. Shiba, JAERI
J. M. Sicilian, LASL
R. Smith, Jr., NRC-ID
J. E. Solecki, DOE-ID
T. P. Speis, NRC
R. L. Tedesco, NRC-HQ
B. Teitlman, KAPL
D. G. Thomas, ORNL
L. S. Tong, NRC-HQ
D. Trent, PNL
J. Voglewede, NRC-HQ
D. Vreeland, LLL
B. Washburn, DOE-HQ
B. Woods, NUS
Public Document Room, NRC-HQ
R. W. Kiehn, EG&G Idaho w/o enc

NUREG/CR-1520
EGG-2045
Distribution Category: R2

EXPERIMENT DATA REPORT FOR LOFT ANTICIPATED TRANSIENT EXPERIMENT L6-5

Benjamin D. Stitt
Janice M. Carpenter

Published July 1980

EG&G Idaho, Inc.
Idaho Falls, Idaho 83415

Prepared for the
U.S. Nuclear Regulatory Commission
Washington, D.C. 20555
Under DOE Contract No. DE-AC07-76ID01570
NRC FIN No. A6048

ABSTRACT

Uninterpreted experimental data from the first anticipated transient experiment (Experiment L6-5) conducted in the Loss-of-Fluid Test (LOFT) facility are presented. The LOFT facility is a 50-MW(t) pressurized water reactor (PWR) system with instrumentation to measure and provide data on the thermal-hydraulic conditions throughout the system. Operation of the LOFT system is typical of a large [~ 1000 MW(e)] commercial PWR system. Experiment L6-5 was a loss of secondary feedwater anticipated transient. At experiment initiation, the LOFT system was operating at 36.7 ± 1 MW(t) (yielding a maximum linear heat generation rate of 39.6 ± 2 kW/m) with a primary flow rate of 479.4 ± 6.3 kg/s, hot leg temperature of

568.2 ± 0.5 K, and hot leg pressure of 14.79 ± 0.25 MPa in the primary coolant system. The transient was initiated by turning off the secondary coolant system main feedwater pump. The reactor was scrammed manually when steam generator secondary liquid level dropped to its low setpoint. The liquid levels in the steam generator and pressurizer were recovered through operator action. The experiment ended when the liquid levels in the steam generator and pressurizer reached their normal operating bands. The data presented from Experiment L6-5 show the effect that a loss of secondary feedwater would have on the thermal-hydraulic conditions in an operating PWR system.

SUMMARY

This report presents experimental data from the first anticipated transient experiment (Experiment L6-5) conducted in the Loss-of-Fluid Test (LOFT) facility. The data are uninterpreted but readily usable for the nuclear community in advance of detailed analysis and interpretation. Experiment L6-5 was a loss of secondary feedwater anticipated transient, and was performed on May 29, 1980, as part of the LOFT Experimental Program conducted by EG&G Idaho, Inc., for the U.S. Nuclear Regulatory Commission. This experiment is part of the LOFT Non-LOCE Test Series L6 which was designed to provide data for investigating the thermal-hydraulic response of the LOFT reactor system from transient initiation to plant restabilization after reactor scram. Experiment L6-5 was conducted at 36.7 ± 1 MW (yielding a maximum linear heat generation rate of 39.6 ± 2 kW/m). The general objectives for Experiment Series L6 are as follows:

1. To provide data required for evaluation of the plant and control systems performance during each of the anticipated transient causing scram (ATCS) tests.
2. To determine the important thermal, hydraulic, operational, and neutronic phenomena during an ATCS at the LOFT facility. Identify and explain any unexpected behavior.
3. Provide data to evaluate reactor transient analysis techniques used to analyze anticipated transients.
4. Provide data to analyze the relationship between LOFT and large pressurized water reactor (PWR) behavior during anticipated transients.
5. To determine the effectiveness of instruments normally provided in large PWRs for identifying anticipated transients and monitoring the resulting plant response.
6. To determine what additional information and/or measurements would assist a plant operator in his diagnosis and/or control of an anticipated transient.

7. Continue development and testing of the Operational Diagnostic and Display System (ODDS) by operation of the ODDS during each test.

The specific objectives for Experiment L6-5 are as follows:

1. Investigate plant response to a transient in which the feedwater flow to the secondary system is stopped.
2. Provide continued evaluation on automatic recovery methods.
3. Provide continued data for assessment of code capabilities to predict secondary system initiated events.

The LOFT integral test facility has been designed to simulate the major components and system responses of a commercial four-loop PWR [~ 1000 MW(e)] during a hypothetical loss-of-coolant accident. The LOFT facility consists of

1. A reactor vessel with a nuclear core (Core 1)
2. An intact loop with active steam generator, pressurizer, and two primary coolant pumps connected in parallel
3. A broken loop with simulated pump, simulated steam generator, and two quick-opening blowdown valve assemblies
4. A blowdown suppression system consisting of a header, suppression tank, and a suppression tank spray system
5. An emergency core coolant (ECC) injection system consisting of two low-pressure injection system pumps, two high-pressure injection system pumps, and two accumulators.

The blowdown suppression system and ECC injection system were not used in Experiment L6-5. The broken loop was stagnant throughout the experiment and, therefore, served only a passive role.

Experiment L6-5 was initiated from primary coolant system initial conditions of: hot leg temperature, 568.2 ± 0.5 K; cold leg temperature, 554.7 ± 3 K; hot leg pressure, 14.79 ± 0.25 MPa; and intact loop flow rate, 479.4 ± 6.3 kg/s. The preexperiment power level was 36.7 ± 1 MW, with a maximum linear heat generation rate of 39.6 ± 2 kW/m. The experiment was initiated by turning the secondary coolant system main feedwater pump off. The reactor was scrammed manually on indication of low liquid level in the steam generator secondary

side. The experiment was terminated when the operators refilled the steam generator to its operating range and restored the pressurizer to its normal operating level.

Experiment L6-5 satisfied the specified objectives. This report presents data in the form of graphs in engineering (standard international) units. In conjunction with data obtained from direct measurement, chosen computed variables are included to facilitate the analysis of the system thermal-hydraulic behavior.

ACKNOWLEDGMENTS

Appreciation is expressed to the Data Systems Branch, particularly to J. B. Marlow for the preparation of data plots. Appreciation is also expressed to the LOFT Data Analysis Branch,

particularly S. A. Ploger and R. H. Averill for uncertainty analysis and instrument calibration, respectively. Special appreciation is expressed to G. Hammer for the technical editing.

CONTENTS

| | |
|--|-----|
| ABSTRACT | ii |
| SUMMARY | iii |
| ACKNOWLEDGMENTS | v |
| ACRONYMS | ix |
| 1. INTRODUCTION | 1 |
| 1.1 LOFT Experimental Program Objectives | 1 |
| 1.2 Experiment Objectives and Brief Description of Experiment L6-5 | 2 |
| 2. SYSTEM CONFIGURATION | 3 |
| 3. MEASUREMENTS AND INSTRUMENTATION | 7 |
| 4. EXPERIMENTAL PROCEDURE AND INITIAL CONDITIONS | 26 |
| 4.1 Experimental Procedure | 26 |
| 4.2 Initial Conditions | 29 |
| 5. DATA PRESENTATION | 34 |
| 6. REFERENCES | 80 |
| APPENDIX A — DATA CONSISTENCY CHECKS | 81 |
| APPENDIX B — EXPERIMENT L6-5 INSTRUMENTATION LIST | 85 |

FIGURES

| | |
|---|----|
| 1. LOFT major components | 4 |
| 2. LOFT piping schematic | 5 |
| 3. LOFT Core 1 configuration showing rod designations | 6 |
| 4. Relation of source and detectors to pipe for gamma densitometers | 8 |
| 5. LOFT piping schematic with instrumentation | 10 |
| 6. LOFT secondary coolant system with instrumentation | 11 |
| 7. LOFT thermal-hydraulic instrumentation for intact loop | 14 |
| 8. LOFT thermal-hydraulic instrumentation for broken loop | 15 |
| 9. LOFT reactor vessel instrumentation | 16 |

| | | |
|-----|--|----|
| 10. | LOFT reactor vessel pressure and differential pressure instrumentation | 17 |
| 11. | LOFT reactor vessel upper plenum DTT, LE, and TE elevations | 18 |
| 12. | In-core thermocouple locations for LOFT Core 1 | 19 |
| 13. | LOFT pressurizer instrumentation | 20 |
| 14. | LOFT steam generator instrumentation | 21 |
| 15. | LOFT intact loop pump instrumentation | 22 |
| 16. | LOFT accumulator instrumentation | 23 |
| 17. | LOFT ECCS instrumentation | 24 |
| 18. | LOFT blowdown suppression tank instrumentation | 25 |
| 19. | LOFT power history prior to Experiment L6-5 reactor scram [full power = 50 MW(t)] | 27 |
| 20. | LOFT decay heat following Experiment L6-5 reactor scram | 29 |

SHORT-TERM PLOTS

(-10 to 30 s)

| | | |
|-----|----------------------------------|----|
| 21. | Valve position | 43 |
| 22. | Differential pressure | 43 |
| 23. | Liquid level | 44 |
| 24. | Local heat generation rate | 44 |
| 25. | Local average power | 45 |

MEDIUM-TERM PLOTS

(-50 to 200 s)

| | | |
|--------|-----------------------------|-------|
| 26. | Valve position | 47 |
| 27. | Fluid velocity | 47 |
| 28-29. | Flow rate | 48 |
| 30-31. | Liquid level | 49 |
| 32-34. | Differential pressure | 50-51 |
| 35-44. | Pressure | 51-56 |
| 45-67. | Temperature | 56-67 |

LONG-TERM PLOTS
(0 to 3000 s)

| | | |
|--------|----------------------|-------|
| 68. | Valve position | 69 |
| 69-71. | Flow rate | 69-70 |
| 72-74. | Liquid level | 71-72 |
| 75-78. | Pressure | 72-74 |
| 79-85. | Temperature | 74-77 |

COMPUTED VARIABLES

| | | |
|--------|------------------------|----|
| 86-87. | Fluid subcooling | 79 |
|--------|------------------------|----|

TABLES

| | | |
|------|--|----|
| 1. | Nomenclature for LOFT Instrumentation | 12 |
| 2. | Sequence of Events for Experiment L6-5 | 28 |
| 3. | Initial Conditions for Experiment L6-5 | 30 |
| 4. | Linear Heat Generation Rate Prior to Experiment L6-5 | 31 |
| 5. | Primary Coolant Temperatures at Experiment L6-5 Initiation | 32 |
| 6. | Water Chemistry Results for Experiment L6-5 | 33 |
| 7. | Measured Variables for Experiment L6-5 | 35 |
| 8. | Computed Variables for Experiment L6-5 | 42 |
| B-1. | Experiment L6-5 Instrumentation List | 88 |

ACRONYMS

| | | | |
|-------|--|------|-------------------------------|
| ATCS | Anticipated transient causing scram | LOFT | Loss-of-Fluid Test |
| BST | Blowdown suppression tank | LPIS | Low-pressure injection system |
| BWST | Borated water storage tank | PCP | Primary coolant pump |
| DAVDS | Data acquisition and visual display system | PCS | Primary coolant system |
| DTT | Drag disc turbine transducer | PNA | Pulsed neutron activation |
| ECC | Emergency core coolant | PWR | Pressurized water reactor |
| ECCS | Emergency core cooling system | QOBV | Quick-opening blowdown valve |
| ESF | Engineered safety features | RABV | Reflood assist bypass valve |
| FM | Frequency modulation | RV | Reactor vessel |
| HPIS | High-pressure injection system | SCS | Secondary coolant system |
| LOCA | Loss-of-coolant accident | SG | Steam generator |
| LOCE | Loss-of-coolant experiment | TIP | Traversing in-core probe |

EXPERIMENT DATA REPORT FOR LOFT ANTICIPATED TRANSIENT EXPERIMENT L6-5

1. INTRODUCTION

This report presents data from Experiment L6-5, which was conducted in the Loss-of-Fluid Test (LOFT) facility on May 29, 1980. The LOFT facility is a 50-MW(t) pressurized water reactor (PWR) with instrumentation to measure and provide data on the thermal-hydraulic conditions throughout the system. Operation of the LOFT system is typical of a large [~ 1000 MW(e)] commercial PWR. Experiment L6-5 was the first anticipated transient experiment performed in the LOFT facility and simulated a loss of secondary feedwater to a PWR system.

Experiment L6-5 was planned and supervised by the LOFT Experimental Program. The LOFT Experimental Program is one of several water reactor research experimental programs conducted by EG&G Idaho, Inc., for the U.S. Nuclear Regulatory Commission and administered by the U.S. Department of Energy at the Idaho National Engineering Laboratory.

The data presented in this report are from 53 of the 631 instruments that provided data during Experiment L6-5. Only the data considered pertinent to the understanding of this experiment are presented. The data are in an uninterpreted but readily usable form for use by the nuclear community in advance of detailed analysis and interpretation. The data, in the form of graphs in engineering units, have been analyzed only to the extent necessary to ensure that they are reasonable and consistent.

Section 1.1 of this introduction states the LOFT Experimental Program objectives. Section 1.2 presents the Experiment L6-5 objectives and briefly describes the experiment conditions and operation. Section 2 of this report briefly describes the LOFT configuration. Section 3 discusses the LOFT instrumentation system and the methods of obtaining certain measurements. Section 4 summarizes Experiment L6-5 initial conditions and experimental procedure. Section 5 presents the data with supporting information for data interpretation. Appendix A discusses the

methods used to verify the consistency and accuracy of the data. Appendix B contains a complete list of LOFT instrumentation available for use during Experiment L6-5.

1.1 LOFT Experimental Program Objectives

The LOFT integral^a test facility was designed to simulate the major components of a four-loop, commercial PWR, thereby producing data on the thermal, hydraulic, nuclear, and structural processes expected to occur during accidents in a PWR. Reference 1 describes the LOFT facility in detail. The specific objectives of the LOFT Experimental Program are to:

1. Provide data required to evaluate the adequacy of and to improve the analytical methods currently used to predict the response of large PWRs to postulated accident conditions, the performance of engineered safety features (ESF) with particular emphasis on emergency core cooling system (ECCS), and the quantitative margins of safety inherent in the performance of the ESF.
2. Identify and investigate any unexpected event(s) or threshold(s) in the response of either the plant or the ESF and develop analytical techniques that adequately describe and account for the unexpected behavior(s).
3. Evaluate and develop methods to prepare, operate, and recover systems and plant for and from reactor accident conditions.

a. The term "integral" is used to describe an experiment combining the nuclear, thermal, hydraulic, and structural processes occurring during an accident as distinguished from separate effects, nonnuclear, small-scale, and thermal-hydraulic experiments conducted for accident analysis.

4. Identify and investigate methods by which reactor safety can be enhanced, with emphasis on the interaction of the operator with the plant.

1.2 Experiment Objectives and Brief Description of Experiment L6-5

The LOFT Non-LOCE Test Series L6 was designed to provide large-scale system data for several PWR anticipated transients. The transients to be studied include: loss of steam load, loss of primary coolant system (PCS) flow, excessive load increase, unintentional rod bank withdrawal, loss of feedwater, and uncontrolled boron dilution.

The general objectives for Test Series L6 are as follows:

1. To provide data required for evaluation of the plant and control system performance during each of the anticipated transient causing scram (ATCS) tests.
2. To determine the important thermal, hydraulic, operational, and neutronic phenomena during an ATCS at the LOFT facility. Identify and explain any unexpected behavior.
3. Provide data to evaluate reactor transient analysis techniques used to analyze anticipated transients.
4. Provide data to analyze the relationship between LOFT and large PWR behavior during anticipated transients.
5. To determine the effectiveness of instruments normally provided in large PWRs for identifying anticipated transients and monitoring the resulting plant response.
6. To determine what additional information and/or measurements would assist a plant

operator in his diagnosis and/or control of an anticipated transient.

7. Continue development and testing of the Operational Diagnostic and Display System (ODDS) by operation of the ODDS during each test.

The specific objectives for Experiment L6-5 are as follows:

1. Investigate plant response to a transient in which the feedwater flow to the secondary system is stopped.
2. Provide continued evaluation on automatic recovery methods.
3. Provide continued data for assessment of code capabilities to predict secondary system initiated events.

LOFT Experiment L6-5 simulated a loss of secondary feedwater anticipated transient in a commercial PWR. At the time of experiment initiation, the LOFT reactor was operating (a) at a maximum linear heat generation rate of 39.6 ± 2 kW/m and a power of 36.7 ± 1 MW, which is about 75% of the LOFT rated thermal power of 50 MW, (b) at temperatures in the PCS intact loop of 568.2 ± 0.5 and 554.7 ± 3 K in the hot and cold legs, respectively, and (c) a pressure in the PCS intact loop of 14.95 ± 0.34 MPa in the hot leg. The experiment was initiated by turning the secondary coolant system main feedwater pump off. The reactor was scrammed manually at 23.7 ± 0.1 s, when the secondary water level in the steam generator dropped to a level corresponding to a low steam generator water level that would initiate a scram in a commercial PWR. The steam flow control valve received a signal to begin closure at reactor scram. After that signal, the valve was allowed to cycle normally at its predetermined setpoints. The experiment was terminated when the operators restored the liquid levels in the steam generator secondary and pressurizer to their normal operating ranges.

2. SYSTEM CONFIGURATION

The LOFT facility¹ has been designed to simulate the major components and system responses of a commercial PWR during a loss-of-coolant accident (LOCA). The experiment assembly comprises five major subsystems that have been instrumented such that system variables can be measured and recorded during an experiment. The subsystems include: (a) the reactor vessel, (b) the intact loop, (c) the broken loop, (d) the blowdown suppression system, and (e) the ECCS. The LOFT major components are shown in Figure 1, and the LOFT piping configuration is shown in Figure 2.

The LOFT reactor vessel, which simulates the reactor vessel of a commercial PWR, has an annular downcomer, a lower plenum, lower core support plates, a nuclear core, and an upper plenum. The downcomer is connected to the cold legs of the intact and broken loops and contains two instrument stalks. The upper plenum is connected to the hot legs of the intact and broken loops. The core contains 1300 unpressurized nuclear fuel rods arranged in five square (15 x 15 assemblies) and four triangular (corner) fuel modules, shown in Figure 3 and described in Reference 2. The center assembly is highly instrumented. Two of the corner and one of the square assemblies are not instrumented. The fuel rods have an active length of 1.67 m and an outside diameter of 10.72 mm.

The fuel consists of UO₂ sintered pellets with an average enrichment of 4.0 wt% fissile uranium (²³⁵U) and with a density that is 93% of theoretical density. Fuel pellet diameter and length are 9.29 and 15.24 mm, respectively. Both ends of the pellets are dished with the total dish


volume equal to 2% of the pellet volume. Cladding material is zircaloy-4. Cladding inside and outside diameters are 9.48 and 10.72 mm, respectively.

The intact loop simulates the three unbroken loops of a commercial four-loop PWR and contains a steam generator, two circulating coolant pumps in parallel, a pressurizer, a venturi flowmeter, and connecting piping.

The broken loop consists of a hot leg and a cold leg that are connected to the reactor vessel and the blowdown suppression tank (BST) header. Each leg consists of a break plane orifice, a quick-opening blowdown valve (QOBV), a recirculation line, an isolation valve, and connecting piping. The recirculation lines establish a small flow from the broken loop to the intact loop to maintain approximately equal loop temperatures. The broken loop hot leg also contains a simulated steam generator and a simulated pump. The broken loop was connected to the system and was full of water during Experiment L6-5; however, it played only a passive role during the experiment.


The blowdown suppression system, which consists of the BST header, the BST, the nitrogen pressurization system, and the BST spray system, was not used in Experiment L6-5.

The LOFT ECCS simulates the ECCS of a commercial PWR. It consists of two accumulators, a high-pressure injection system (HPIS), and a low-pressure injection system (LPIS). Each system is arranged to inject scaled flow rates of emergency core coolant (ECC) directly into the PCS. The ECCS was not used for Experiment L6-5.



L6-5
INEL-B-10 057-7

Figure 1. LOFT major components.



LOFT piping schematic.




Figure 3. LOFT Core 1 configuration showing rod designations.




Figure 2

3. MEASUREMENTS AND INSTRUMENTATION

The LOFT instrumentation system was designed to measure and record the important parameters and events that occur during an experiment.

Temperatures at all major locations in the system were obtained from thermocouples and resistance temperature detectors.

Pressure measurements were obtained with strain-gage transducers with pressure transmission lines connecting the transducers to the measurement points.

Differential pressures were measured by strain-gage transducers with double chambers. The transducers were externally located and connected to the measurement points with pressure transmission lines.

A turbine flowmeter directly measured fluid velocity in the reactor vessel upper plenum, above Fuel Assembly 5. The data presented for fluid velocity (from the turbine flowmeter) are based on an area of 0.125 m^2 .

Fluid density was measured by gamma densitometers, each of which consists of a source and detectors. Three detectors (A, B, and C shown in Figure 4) were aligned with collimated gamma ray beams passing through the pipe; the attenuation of the gamma rays varied inversely with the density of the fluid in the pipe. Each densitometer also had a detector (D) located so that it measured background radiation continuously, except for DE-PC-3, which checked the background by alternately exposing and storing the source. DE-PC-3 was a nonnuclear-hardened densitometer, had a ^{137}Cs source, and was located in a vertical piping section. The rest of the densitometers were nuclear-hardened, had ^{60}Co sources, and were located in horizontal piping. Figure 4 shows the gamma densitometer configuration relative to the piping.

Liquid levels were obtained by means of differential pressure transducers in the pressurizer, steam generator secondary side, and condensate receiver.

Control rod position was indicated by means of proximity switches. The circuitry associated with

the proximity switches controls a set of lamps. Each set of lamps consists of a "rod bottom" lamp and four "rod location" lamps. The rod bottom lamp lights only when the control rod is bottomed. Each rod location lamp lights as the leadscrew on the control rod passes its switch position during withdrawal, and it remains lit whenever the leadscrew is above this position.


Valve positions (analog indication from 0 to 100% of opening) were measured by either resistance potentiometers or differential transformers.

Mechanical pump speed was measured by an eddy current displacement transducer which used a slotted metallic target attached to the top of the pump motor shaft. The target contains six asymmetrical slots so that pump speed can be determined. Electrical pump power was measured by a wattmeter.


The steady state local linear heat generation rate was measured by self-powered neutron detectors. Each detector consists of a cylindrical ^{59}Co emitter, a layer of aluminum oxide for electrical insulation, and an outer sheath of Inconel. The cable connected to the detector consists of two Inconel wires in an Inconel sheath with magnesium oxide insulation. One of the wires is connected to the cobalt emitter and the other is open ended. The open-ended wire gives a background subtraction signal to compensate for the radiation sensitivity of the cable.

The steady state linear heat generation rates were also determined from neutron flux measurements taken with a traversing in-core probe (TIP) at four guide tube locations in the core. This instrument consists of a ^{235}U fission chamber attached to a flexible cable and its own data recording system. The probe was withdrawn and stored outside the core prior to experiment initiation.

The data acquisition and visual display system (DAVDS) was used to record measured data from the various instrumentation systems on a combination of digital recorders, wide-band frequency modulation (FM) tape recorders, and oscillographic recorders.³ Redundant records were made where use dictated more than one



(a) for densitometers except DE-PC-3



(b) for DE-PC-3

L6-5
INEL-A-2709-3

Figure 4. Relation of source and detectors to pipe for gamma densitometers.

recording mode or where an extra measure of assurance was desired for critical measurements.


A digital computer was used to collect the experimental data in a multiplexed format at the LOFT facility and to perform equipment calibrations, posttest data reduction, and plotting.⁴ The recorded FM data were converted into digital form and then demultiplexed to be compatible with the CDC CYBER 176 computer system.

The CDC CYBER 176 computer system was used to further reduce the data. Calibration factors were first applied to produce data plots in engineering units so that engineering specialists could examine each channel for discrepancies or unexpected events. Where possible, instrument channel outputs and computed variables were compared with test predictions, previous tests, corresponding parameter channels, and calculated quantities. Instruments were labeled as qualified if the measurement comparisons were determined to be within the accuracy of the particular instrument.


Most transducers were calibrated under laboratory conditions prior to installation in LOFT. Verification of calibration constants was accomplished by special tests performed during heatup and by analysis of initial conditions data. In addition, postexperiment checks were performed to pinpoint questionable data and to verify data consistency. Appendix A discusses the

techniques used to perform data consistency checks.

Figures 5 and 6 are piping schematics showing instrument locations in the primary and secondary coolant systems, respectively. Table I gives the nomenclature for LOFT experimental and process instrumentation. Both types of instrumentation are included in this report. Thermocouples and neutron flux detectors located in the nuclear core have special identification. Each of these transducers has been given an identification number which identifies the type of transducer and its location within the core as follows:



Figures 7 and 8 show isometric views of the major system components with instrument locations indicated, and Figures 9 through 18 give more specific locations for instruments located on individual components. Some of the temperature instruments shown in the figures were not recorded during the experiment. Reference 1 may be consulted if additional details of instrument design and locations are desired.



- ▲ ECC Rake 1
- △ ECC Rake 2
- 4 Pipe diameter in inches
- ⊘ Reducer

th instrumentation.




Figure 6. LOFT secondary coolant system with instrumentation.

TABLE 1. NOMENCLATURE FOR LOFT INSTRUMENTATION

Designations for the different types of experimental instruments:

| | |
|-----|-------------------------------|
| AE | Accelerometer |
| DE | Densitometer |
| DIE | Displacement element |
| FE | Coolant flow element |
| LE | Coolant level element |
| ME | Momentum flux detector |
| NE | Neutron detector |
| PCP | Primary coolant pump |
| PdE | Differential pressure element |
| PE | Pressure element |
| RPE | Pump speed element |
| TE | Temperature element |

Designations for the different experimental systems except the core:

| | |
|-----|-----------------------------|
| BL | Broken loop |
| LP | Lower plenum |
| PC | Primary coolant intact loop |
| RV | Reactor vessel |
| SG | Steam generator |
| SGS | Steam generator secondary |
| 1ST | Downcomer Stalk 1 |
| 2ST | Downcomer Stalk 2 |
| SV | Suppression tank |
| UP | Upper plenum |

TABLE 1. (continued)

Designations for the different types of process instruments:

| | |
|-----|-----------------------------------|
| CV | Control valve |
| FE | Flow element |
| FT | Flow transmitter |
| LIT | Level indicating transmitter |
| LT | Liquid level transmitter |
| PdT | Differential pressure transmitter |
| PT | Absolute pressure transmitter |
| RE | Radiation element |
| TE | Temperature element |
| TT | Temperature transmitter |

Designations for the different systems associated with process instruments:

| | |
|------------|---|
| P004 | Secondary coolant system |
| P120 | Emergency core cooling system |
| P128 | Primary coolant addition and control system and HPIS |
| P138 | Broken loop and pressure suppression system |
| P139 | Intact loop |
| P141 | Primary component cooling system |
| T-77, T-87 | Power range |




Figure 7. LOFT thermal-hydraulic instrumentation for intact loop.







Figure 8. LOFT thermal-hydraulic instrumentation for broken loop.



L6-5
INEL-B-14 588-1



* Station numbers are a dimensionless measure of relative elevation within the reactor vessel. They are assigned in increments of 2.54 centimeters with station 300.00 defined at the core barrel support ledge inside the reactor vessel flange.

- Thermocouples
- ▲ Liquid level stings
- Pressure
- ⊗ Drag discs
- ▨ Turbinometer
- ⊠ Drag disc turbinometer } (DTT)

Figure 9. LOFT reactor vessel

* Station numbers are a dimensionless measure of relative elevation within the reactor vessel. They are assigned in increments of 25.4 mm with Station 300.00 defined at the core barrel support ledge inside the reactor vessel flange.





Figure 10. LOFT reactor vessel pressure and differential pressure instrumentation.



*Station numbers are a dimensionless measure of relative elevation within the reactor vessel. They are assigned in increments of 25.4 mm with station 300.00 defined at the core barrel support ledge inside the reactor vessel flange.

L6-5
INEL-A-7373-1

Figure 11. LOFT reactor vessel upper plenum DTT, LE, and TE elevations.





Figure 13. LOFT pressurizer instrumentation.



L6-5
INEL-A-10 329-5

Figure 14. LOFT steam generator instrumentation.






Figure 15. LOFT intact loop pump instrumentation.



L6-5
INEL-B-7167-4



L6-5
INEL-A-4890-1

Figure 16. LOFT accumulator instrumentation.








Figure 17. LOFT ECCS instrument



L6-5
INEL B-7854-2

4. EXPERIMENTAL PROCEDURE AND INITIAL CONDITIONS

This section summarizes the experimental procedure, initial conditions, and the significant events recorded during the experiment.

4.1 Experimental Procedure

In preparation for Experiment L6-5, the PCS was filled and vented and the specified system water chemistry was established. Prior to the primary system heatup, the following tests were performed on the LOFT system: plant requalification tests, pump coastdown runs, and operational verification of newly installed instrumentation. Selected system process instrumentation was calibrated and an electrical calibration was performed on the DAVDS.

The PCS pressure was hydrostatically increased to 1.46, 3.53, 6.98, 10.43, 13.87, and 15.60 MPa at cold plant temperature and zero flow conditions. The pressure was then decreased through these same pressure plateaus. The DAVDS recorded 20 s of data at each pressure plateau in both the increasing and decreasing directions to determine the degree of sensitivity of the pressure sensing instruments. The system was concurrently inspected for leakage at the various test pressures. The pumps were operated at 15, 20, 30, 40, 50, and 60 Hz with 20 s of data taken at each frequency.

The plant was stabilized at 383 and 555 K during heatup. At each of these temperatures, 20 to 30 s of data were recorded for calibration checks and to determine the degree of instrument temperature sensitivity. At the 555-K stabilization point, the pumps were stopped and 20 s of data were recorded during flow coastdown and zero flow conditions. With the pumps off at the 555-K stabilization point, the pressure in the system was again increased, and then decreased. The DAVDS recorded 20 s of data at the 14.95-, 13.87-, 12.50-, 11.12-, and 9.74-MPa pressure plateaus in both the increasing and decreasing directions. Frequency tests were performed by varying the primary coolant pump frequency from 20 to 60 Hz in 10-Hz increments at 555 K. Before the reactor was brought critical, the DAVDS was calibrated.

Initial reactor criticality occurred approximately 71 h prior to experiment initiation. Following this time, there were two periods of time when the reactor was at zero power. At approximately 28 h prior to the experiment, the reactor was brought to criticality for the last time. At 7 h prior to the experiment, the power level reached ~ 37 MW and was maintained at that level until experiment initiation. (A plot of the power level versus time for the 80-hr period prior to the experiment is given in Figure 19.) During the 80-hr period, measurements of power level were performed using a secondary calorimetric calculation and the following specified initial conditions were established: The PCS flow rate was set at the specified 478.8 ± 8.8 kg/s and adjustment of the secondary coolant system (SCS) was made to maintain the specified power level. The PCS boron concentration was adjusted to establish a specified reactor vessel inlet temperature of 552.6 ± 2.2 K at a hot leg pressure of 14.95 ± 0.34 MPa.

Prior to experiment initiation, a DAVDS calibration and a data integrity check were performed. During this period, the initial-condition water samples were taken from the PCS and SCS. The intact loop conditions were checked, and adjusted as necessary, to ensure the specified conditions were met at experiment initiation.

The DAVDS was activated and data recording was started 1 min prior to experiment initiation. The reactor was scrammed manually at 23.7 ± 0.1 s after experiment initiation when the steam generator liquid level dropped to -0.126 m (all steam generator levels are based on a zero power reference liquid level which is 2.94 m above the top of the tube sheet). This level corresponds to the automatic low steam generator liquid level scram in a commercial PWR. The normal operating liquid level for the steam generator at 75% power is 0.194 ± 0.05 m. The top of the tubes in the steam generator are at approximately -0.816 m. The primary coolant pumps were allowed to run normally throughout the transient. The operators used charging pumps to recover the liquid levels in the pressurizer and steam generator beginning approximately 15 min after experiment initiation. The experiment terminated approximately 45 min after initiation. The sequence of events for the experiment is provided in Table 2.




Figure 18.




Figure 19. LOFT power history prior to Experiment L6-5 reactor scram [full power = 50 MW(t)]

TABLE 2. SEQUENCE OF EVENTS FOR EXPERIMENT L6-5

| Event | Time after Experiment Initiation (s) |
|---|--|
| Experiment initiated | 0 |
| Main feedwater pump shut down | 0.128 \pm 0.1 |
| Reactor scrammed | 23.7 \pm 0.1 |
| Control rods on bottom | 25.8 \pm 0.1 |
| Main feedwater isolation valve (CV-P004-73) closed | 27.6 \pm 0.1 |
| Steam flow control valve (CV-P004-10) closed | 35.4 \pm 0.2 |
| Steam flow control valve (CV-P004-10) opened | 767.6 \pm 0.2 |
| Steam flow control valve (CV-P004-10) closed | 791.1 \pm 0.2 |
| PCS charging initiated | 937.2 \pm 0.1 |
| Steam generator fill initiated | 954.8 \pm 0.1 |
| PCS charging terminated | 1112.7 \pm 0.1 |
| Steam flow bypass valve (CV-P004-90) opened | 2142 \pm 2 |
| Steam flow bypass valve (CV-P004-90) closed | 2200 \pm 2 |
| PCS charging initiated | 2377.3 \pm 0.1 |
| PCS charging terminated | 2511.3 \pm 0.1 |
| Experiment completed | 3100 \pm 10 |

Figure 20 shows the calculated decay heat for the experiment using the American Nuclear Society Standard 5.1.⁵

The steam flow control valve automatically regulated steam generator pressure and steam flow after reactor scram. It operates on the following setpoints: at 7.03 ± 0.18 MPa the valve begins to open at 5% per second, at 6.96 ± 0.18 MPa it stops opening, at 6.34 ± 0.18 MPa it begins to close at 5% per second, and at 6.41 ± 0.18 MPa it stops closing. The pressurizer was also allowed to cycle at normal setpoints. Pressurizer sprayers turn on at 15.3 ± 0.12 MPa and turn off at 15.16 ± 0.12 MPa. The main pressurizer heaters turn on at 14.85 ± 0.12 MPa and turn off at 15.05 ± 0.12 MPa. The pressurizer backup heaters turn on at 14.81 ± 0.12 MPa and turn off at 14.92 ± 0.12 MPa.

The DAVDS recorded approximately 52 min of data during the transient. An electrical calibration of the DAVDS was performed following the experiment.

4.2 Initial Conditions

The specified initial conditions (except for the linear heat generation rate conditions) and tolerance bands for Experiment L6-5 are presented in Table 3 along with the values measured immediately prior to experiment initiation. All initial conditions were within specified tolerances except the water level in the steam generator secondary side which did not impair the results of the experiment. Table 4 gives the linear heat generation rate versus height above the bottom of the core for three fuel assemblies prior to experiment initiation. The data for Table 4 were obtained from the TIP system.

Table 5 gives the measured fluid temperatures of the PCS immediately prior to experiment initiation.

Table 6 specifies the required water chemistry for the PCS and the SCS. In addition, the results of the water chemistry analysis for these systems are presented for preexperiment conditions.




Figure 20. LOFT decay heat following Experiment L6-5 reactor scram.

TABLE 3. INITIAL CONDITIONS FOR EXPERIMENT L6-5

| <u>Parameter</u> | <u>Specified Value</u> | <u>Measured Value</u> |
|---|-------------------------------------|-----------------------|
| <u>Primary Coolant System</u> | | |
| Mass flow rate (kg/s) | 478.8 ± 8.8 | 479.4 ± 6.3 |
| Hot leg pressure (MPa) | 14.9 ± 0.34 | 14.79 ± 0.25 |
| Cold leg temperature (K) | 557.5 ± 2.2 | 554.7 ± 3 |
| Hot leg temperature (K) | -- | 568.2 ± 0.5 |
| Boron concentration (ppm) | As required to maintain temperature | 1054 ± 15 |
| <u>Reactor Vessel</u> | | |
| Power level (MW) | 37.5 ± 2 | 36.7 ± 1 |
| Maximum linear heat generation rate (kWm) | 39.37 ± 2 | 39.6 ± 2 |
| Control rod position (above full-in position) (m) | 1.372 ± 0.013 | 1.372 ± 0.01 |
| <u>Pressurizer</u> | | |
| Steam volume (m ³) | 0.32 ± 0.1 | 0.36 ± 0.02 |
| Liquid volume (m ³) | 0.61 ± 0.1 | 0.57 ± 0.02 |
| Water temperature (K) | -- | 614.1 ± 1.3 |
| Pressure (MPa) | 14.95 ± 0.34 | 14.79 ± 0.25 |
| Level (m) | 1.13 ± 0.18 | 1.06 ± 0.04 |
| <u>Broken Loop</u> | | |
| Cold leg temperature near reactor vessel (K) | -- | 554.2 ± 2.5 |
| Hot leg temperature near reactor vessel (K) | -- | 558.8 ± 2.5 |
| <u>Steam Generator Secondary Side</u> | | |
| Water level (m) ^a | 0.19 ± 0.05 | 0.27 ± 0.06 |
| Water temperature (K) | -- | 554.0 ± 0.2 |
| Pressure (MPa) | -- | 5.58 ± 0.012 |
| Mass flow rate (kg/s) | -- | 20.6 ± 0.4 |

a. Out of specification, but did not impair results.

TABLE 4. LINEAR HEAT GENERATION RATE PRIOR TO EXPERIMENT L6-5
 (Reading Uncertainty \pm 7.6%)

| Height Above Core Bottom (m) | Linear Heat Generation Rate for Core Position (kW/m) | | |
|------------------------------------|--|-------|-------|
| | 1C7 | 5H8 | 5M3 |
| 0.152 | 7.88 | 13.41 | 13.41 |
| 0.305 | 16.82 | 27.39 | 27.41 |
| 0.406 | 19.62 | 31.08 | 31.48 |
| 0.460 | 19.03 | 30.15 | 30.54 |
| 0.508 | 19.77 | 32.20 | 32.23 |
| 0.559 | 22.12 | 35.04 | 35.49 |
| 0.660 | 23.13 | 36.64 | 37.11 |
| 0.762 | 23.01 | 36.44 | 36.91 |
| 0.838 | 21.85 | 34.62 | 35.07 |
| 0.891 | 19.34 | 30.64 | 31.03 |
| 0.940 | 20.03 | 31.73 | 32.15 |
| 1.067 | 18.75 | 29.70 | 30.08 |
| 1.219 | 15.24 | 23.10 | 23.37 |
| 1.270 | 13.03 | 19.74 | 19.98 |
| 1.303 | 10.39 | 16.46 | 16.68 |
| 1.372 | 9.17 | 14.53 | 14.72 |
| 1.524 | 4.46 | 7.44 | 6.98 |
| 1.626 | 2.29 | 3.81 | 3.58 |
| 1.676 | 1.44 | 2.40 | 2.25 |

TABLE 5. PRIMARY COOLANT TEMPERATURES AT EXPERIMENT L6-5 INITIATION

| Location | Detector | Temperature (K) |
|---|--------------|--------------------|
| Intact loop hot leg (near vessel) | TE-P139-32-1 | 570.8 \pm 1.4 |
| Intact loop steam generator inlet | TE-SG-001 | 569.8 \pm 2.7 |
| Intact loop steam generator outlet | TE-SG-002 | 555.6 \pm 2.7 |
| Intact loop cold leg (near vessel) | TE-PC-004 | 556.0 \pm 3.0 |
| Reactor vessel downcomer: | | |
| Instrument Stalk 1 | TE-1ST-001 | 557.6 \pm 2.7 |
| Instrument Stalk 2 | TE-2ST-001 | 559.3 \pm 2.7 |
| Reactor vessel lower plenum | TE-1LP-001 | 558.1 \pm 2.7 |
| Reactor vessel upper plenum | TE-1UP-001 | 578.1 \pm 2.7 |
| | TE-5UP-001 | 580.2 \pm 2.7 |
| Intact loop pressurizer (from saturation pressure) | PE-PC-004 | 614.1 \pm 1.3 |

TABLE 6. WATER CHEMISTRY RESULTS FOR EXPERIMENT L6-5

| Parameter | Primary Coolant System | | Secondary Coolant System | |
|---|------------------------|----------------------------|----------------------------|---------------|
| | Specified | Preexperiment ^a | Specified | Preexperiment |
| pH (each at 298 K) | 4.2 to 10.5 | 5.57 | 9.0 to 10.2 | 10.18 |
| Conductivity ($\mu\text{mho}/\text{cm}^3$) (each at 298 K) | 60 maximum | 3.06 | 2 maximum ^b | -- |
| Total gas (cm^3/kg) | 100 maximum | 41.6 | -- | -- |
| Dissolved oxygen (ppm) | -- | -- | 0.005 maximum | 0.020 |
| Chloride (ppm) | 0.15 maximum | <0.1 | 0.15 maximum | <0.1 |
| Undissolved solids (ppm) | 1.0 maximum | <0.5 | 1.0 maximum | 2.5 |
| Boron (ppm) | -- | 1054 | -- | -- |
| Fluoride (ppm) | 0.1 maximum | <0.02 | -- | -- |
| Hydrogen (cm^3/kg) | 10 to 60 | 17.2 | -- | -- |
| Total gross activity ($\mu\text{c}/\text{mL}$) | 375 maximum | 0.025 | -- | -- |
| Gross beta and gamma ($\mu\text{c}/\text{mL}$) | -- | 0.025 | -- | -- |
| ^{131}I ($\mu\text{c}/\text{mL}$) | 0.37 maximum | 0 | 9×10^{-4} maximum | 0 |
| ^{135}I ($\mu\text{c}/\text{mL}$) | 0.76 maximum | 0 | -- | 0 |

a. Sample taken upstream of the primary coolant system ion exchanger.

b. Cation conductivity.

5. DATA PRESENTATION

The data presented in this report include selected pertinent thermal-hydraulic and nuclear data from LOFT Experiment L6-5.

The selected data have been divided into two categories, "Qualified" and "Failed." The qualified designation was applied to measurements that have been found to be within the uncertainty of the instrument. The absence of a comment following the qualified designation indicates that the data are valid, within specified uncertainty bands, over the entire time span presented. Restrictive statements accompany data that are invalid over a portion of the presented time span. Instrument channels were not presented if the data were in the instrument dead band or showed a similar response to nearby like instruments (such as the core thermocouples). These data are available from EG&G Idaho, Inc., upon special request. The checks on data consistency and instrument performance are discussed in detail in Appendix A.

The data were processed and are presented in graphical form in SI units. Measurements were combined to produce computed variables, and graphs of similar variables at several locations were overlaid to facilitate comparison. The number of data points shown for each instrument have been reduced to 4000 for ease of plotting. To accomplish this reduction, the data were passed through a low-pass filter and then decimated.

Computed parameter data from the turbine flowmeter were filtered with a 4-Hz, low-pass filter prior to presentation.

The 2- σ confidence intervals have been determined from knowledge of the systematic and random errors of the sensors, data system, calibration procedures, and the channel random noise during preexperiment calibrations. These are

presented as functions of output level so that the user may determine the approximate uncertainty over each range of interest for a given variable.

Table 7 lists Experiment L6-5 instrumentation providing data presented in this report and gives the detector location, range, initial condition uncertainty, uncertainty at specific readings, and recording frequency along with the figure numbers. This table also contains a "Comments" column which gives information relative to the usability of the data. A complete list of the LOFT instrumentation available for use during Experiment L6-5 is contained in Appendix B.

Table 8 lists the variables that were computed from the transducer outputs and other factors, such as geometrical constants. This table also gives the equations used to compute these variables, the figure number, and comments which may reflect on the usefulness of the data.

The data are divided into four major sections, with the individual plots in each section being presented in alphanumeric order to facilitate comparison and location of desired variables. These data sections include

1. Experiment L6-5 Measured Variables, Short-Term Plots (10 to 30 s), Figures 21 through 25
2. Experiment L6-5 Measured Variables, Medium-Term Plots (-50 to 200 s), Figures 26 through 67
3. Experiment L6-5 Measured Variables, Long-Term Plots (0 to 3000 s), Figures 68 through 85
4. Experiment L6-5 Computed Variables, Figures 86 and 87.

TABLE 7. MEASURED VARIABLES FOR EXPERIMENT L6-5

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (+) | After Experiment Initiation | | Figure | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------|---|--------|---|
| | | | | | Reading | Uncertainty (+) | | |
| VALVE OPENING | | | | | | | | |
| <u>Intact Loop</u> | | | | | | | | |
| CV-P004-008 | Main feedwater control valve. | 0 to 100% | 1 Hz | 3.2% | 0% 25% 50% 100% | 3.0% 3.13% 3.47% 4.61% | 21 | Qualified. |
| CV-P004-010 | Main steam control valve. | 0 to 100% | 1 Hz | 3.9% | 0% 25% 50% 100% | 3.0% 3.13% 3.47% 4.61% | 26,68 | Qualified. |
| FLUID VELOCITY | | | | | | | | |
| <u>Reactor Vessel</u> | | | | | | | | |
| FE-5UP-001 | Above upper end box of Fuel Assembly 5. | 0.5 to 10.0 m/s | 1 Hz | 0.23 m/s | 1 m/s 5 m/s 10 m/s | 0.06 m/s ^b 0.28 m/s 0.56 m/s | 27 | Qualified. |
| FLOW RATE | | | | | | | | |
| <u>Intact Loop</u> | | | | | | | | |
| FT-P004-012 | Inlet to air-cooled condenser inlet header. | 0 to 40 kg/s | 1 Hz | 0.8 kg/s | -- | 0.8 kg/s | 28,69 | Qualified, magnitude uncertain after scram. |
| FT-P004-072A | Main feedwater pump discharge flow. | 0 to 25 kPa | Hz | 0.17 kPa | -- | 0.17 kPa | 22 | Qualified. |
| <u>Emergency Core Cooling System</u> | | | | | | | | |
| FT-P128-085 | Charging pump AC-P-48 discharge. | 0 to 1.89 L/s | 1 Hz | 0.02 L/s | -- | 0.02 L/s | 70 | Qualified. |
| <u>Intact Loop</u> | | | | | | | | |
| FT-P139-27-3 | Intact loop hot leg venturi flowmeter [left side facing steam generator (SG)]. | 0 to 630.6 kg/s | 1 Hz | 17 kg/s | -- | 17 kg/s | 29,71 | Qualified. |

TABLE 7. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (+) | After Experiment Initiation | | Figure | Comments |
|--------------------------------------|--|-----------------------------|-------------------------------------|--|-----------------------------|-------------------------------------|----------------|---|
| | | | | | Reading | Uncertainty (+) | | |
| LIQUID LEVEL | | | | | | | | |
| <u>Secondary Coolant System</u> | | | | | | | | |
| LT-P004-008B | SG feedwater level (wide range). | -3.6 to 1.4 m ^c | 1 Hz | 0.05 m | -- | 0.05 m | 23 30 72 | Qualified, data not density compensated. |
| <u>Intact Loop</u> | | | | | | | | |
| LT-P004-042 | Condensate receiver level, 183 m south of condensate receiver centerline. | 0 to 1.2 m | 1 Hz | 0.02 m | -- | 0.02 m | 73 | Qualified. |
| LT-P139-007 | Pressurizer level on southwest side. | 0 to 1.9 m | 1 Hz | 0.04 m | -- | 0.04 m | 31,74 | Qualified for relative changes only. |
| NEUTRON DETECTION | | | | | | | | |
| <u>Reactor Vessel</u> | | | | | | | | |
| NE-2H8-26 | Neutron detector in Fuel Assembly 2. | 0 to 52.5 kW/m (local) | 1 Hz | 2.03 kW/m | -- | 2.03 kW/m ^d | 24 | Qualified through reactor scram, relative changes only. |
| DIFFERENTIAL PRESSURE | | | | | | | | |
| <u>Intact Loop</u> | | | | | | | | |
| PdE-PC-001 | Intact loop cold leg across primary coolant pumps (PCPs). | +700 kPa (differential) | 1 Hz | 1.8 kPa | 0 kPa 350 kPa 700 kPa | 1.7 kPa 1.7 kPa 1.9 kPa | 32 | Qualified. |
| PdE-PC-008 | Intact loop across pressurizer surge line. | +10.34 kPa (differential) | 1 Hz | 0.025 kPa | 0 kPa 5 kPa 10 kPa | 0.025 kPa 0.026 kPa 0.028 kPa | 33 | Qualified. |
| PdT-P139-030 | Across reactor vessel (RV) just beyond intact loop inlet and outlet nozzles. | 0 to 300 kPa (differential) | 1 Hz | 3 kPa | -- | 3 kPa | 34 | Qualified. |

TABLE 7. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (+) | After Experiment Initiation | | Figure | Comments |
|--------------------------------------|---|------------------------------|-------------------------------------|--|---------------------------------|-------------------------------------|--------|------------|
| | | | | | Reading | Uncertainty (+) | | |
| <u>PRESSURE^c</u> | | | | | | | | |
| <u>Intact Loop</u> | | | | | | | | |
| PE-PC-001 | Intact loop cold leg at drag disc turbine transducer (JTT) flange. | 0.1 to 20.8 MPa ^e | 1 Hz | 0.251 MPa | 0 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | 35 | Qualified. |
| PE-PC-004 | Intact loop pressur- izer vapor space. | 0.1 to 20.8 MPa | 1 Hz | 0.251 MPa | 0.1 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | 36,75 | Qualified. |
| PE-PC-006 | Intact loop reference pressure between SG outlet and pump inlet. | 0.1 to 17.0 MPa | 1 Hz | 0.028 MPa | -- | 0.028 MPa | 37,76 | Qualified. |
| PE-SCS-001 | SG dome pressure. | 0.1 to 7.0 MPa | 1 Hz | 0.012 MPa | -- | 0.012 MPa | 38,77 | Qualified. |
| <u>Reactor Vessel</u> | | | | | | | | |
| PE-1ST-001A | Downcomer Stalk 1, 0.62 m above RV bottom, wide range (0 to 20.8 MPa). | 0.1 to 20.8 MPa | 1 Hz | 0.200 MPa | 0.1 MPa 10.0 MPa 20.5 MPa | 0.199 MPa 0.199 MPa 0.200 MPa | 39 | Qualified. |
| PE-1UP-001A1 | Above Fuel Assembly 1 upper end box, high range. | 0.1 to 20.8 MPa | 1 Hz | 0.25 MPa | 0.1 MPa 10 MPa 20 MPa | 0.2 MPa 0.22 MPa 0.28 MPa | 40,78 | Qualified. |
| <u>Secondary Coolant System</u> | | | | | | | | |
| PT-P004-010A | In 10-in. line from SG. | 0.1 to 8.4 MPa | 1 Hz | 0.110 MPa | -- | 0.110 MPa | 41 | Qualified. |
| PT-P004-085 | Upstream of inlet to air-cooled condenser header. | 0 to 2.8 MPa | 1 Hz | 0.075 MPa | -- | 0.075 MPa | 42 | Qualified. |
| <u>Intact Loop</u> | | | | | | | | |
| PT-P139-003 | Intact loop hot leg at venturi on left side when looking toward SG. | 0.1 to 20.8 MPa | 1 Hz | 0.25 MPa | -- | 0.25 MPa | 43 | Qualified. |
| PT-P139-005 | 1.88 m above pres- surizer bottom (vapor space). | 10.3 to 17.2 MPa | 1 Hz | 0.12 MPa | -- | 0.12 MPa | 44 | Qualified. |

TABLE 7. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (+) | After Experiment Initiation | | Figure | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|--------|--|
| | | | | | Reading | Uncertainty (+) | | |
| REACTIVITY | | | | | | | | |
| <u>Reactor Vessel</u> | | | | | | | | |
| RE-T-77-2A2 | Power range, Channel B level. | 0 to 100% power | 1 Hz | 3% | -- | 3% | 25 | Qualified. |
| TEMPERATURE | | | | | | | | |
| <u>Intact Loop</u> | | | | | | | | |
| TE-PC-004 | Bottom of emergency core coolant (ECC) Rake 1 (between PdE-PC-014 and PdE-PC-018). | 270 to 1530 K | 1 Hz | 3.1 K | 350 K 450 K 550 K 650 K | 2.8 K 2.9 K 3.0 K 3.6 K | 45,79 | Qualified. |
| TE-P139-019 | Pressurizer vapor space, 0.86 m above the heater rods. | 588.6 to 644.1 K | 1 Hz | 0.5 K | -- | 0.5 K | 46,80 | Qualified. |
| TE-P139-020 | Pressurizer liquid volume, 0.36 m above heater rods. | 283 to 644.1 K | 1 Hz | 3.0 K | -- | 3.0 K | 47,81 | Qualified. |
| TE-P139-029 | Intact loop cold leg. | 280 to 620 K | 1 Hz | 2.1 K | -- | 2.1 K | 45,79 | Qualified, process instrument, slow response time. |
| TE-P139-32-1 | Intact loop hot leg. | 280 to 620 K | 1 Hz | 1.43 K | -- | 1.43 K | 48 | Qualified, process instrument, slow response time. |
| TE-SG-001 | Intact loop cold leg SG outlet. | 253.2 to 977.4 K | 1 Hz | 2.8 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | 49,82 | Qualified. |
| TE-SG-002 | Intact loop hot leg SG inlet. | 253.2 to 977.4 K | 1 Hz | 2.8 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | 50,83 | Qualified. |
| <u>Secondary Coolant System</u> | | | | | | | | |
| TE-SG-003 | SG secondary side. | 253.2 to 588.6 K | 1 Hz | 2.5 K | 350 K 450 K 550 K 650 K | 2.4 K 2.5 K 2.5 K 3.2 K | 51,84 | Qualified. |

TABLE 7. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (+) | After Experiment Initiation | | Figure | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|--------|------------|
| | | | | | Reading | Uncertainty (+) | | |
| TEMPERATURE (continued) | | | | | | | | |
| <u>Reactor Vessel</u> | | | | | | | | |
| TE-1LP-001 | Fuel Assembly 1 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 52 | Qualified. |
| TE-1ST-013 | Downcomer Stalk 1, 0.24 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | 53 | Qualified. |
| TE-1UP-001 | Fuel Assembly 1 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 54 | Qualified. |
| TE-2ST-014 | Downcomer Stalk 2, 1.17 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | 55 | Qualified. |
| TE-2UP-003 | Fuel Assembly 2 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 56 | Qualified. |
| TE-3LP-001 | Fuel Assembly 3 lower end box. | 311 to 977.4 K | 1 Hz | 2.6 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 57 | Qualified. |
| TE-3UP-001 | Fuel Assembly 3 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 58 | Qualified. |
| TE-4LP-003 | Fuel Assembly 4 lower end box. | 311 to 977.4 K | 1 Hz | 2.6 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 59 | Qualified. |
| TE-4UP-001 | Fuel Assembly 4 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 60 | Qualified. |

TABLE 7. (continued)

| Variable, System, and Detector | Location | Measurement Range | Rec. ding Frequency ^a | Initial Condition Uncertainty (*) | After Experiment Initiation | | Figure | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|----------------|------------|
| | | | | | Reading | Uncertainty (*) | | |
| TEMPERATURE (continued) | | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | | |
| TE-5D6-030 | Cladding on Fuel Assembly 5, Row D, Column 6 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | 61 | Qualified. |
| TE-5F9-045 | Cladding on Fuel Assembly 5, Row F, Column 9 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | 62 | Qualified. |
| TE-5F9-062 | Cladding on Fuel Assembly 5, Row F, Column 9 at 1.57 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | 61 | Qualified. |
| TE-5G8-008 | Cladding on Fuel Assembly 5, Row G, Column 8 at 0.20 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | 61 | Qualified. |
| TE-5G8-026 | Cladding on Fuel Assembly 5, Row G, Column 8 at 0.66 m above bottom of fuel rod. | 410 to 1620 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 5.2 K 6.7 K | 63 | Qualified. |
| TE-5LP-001 | Fuel Assembly 5 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.9 K 3.3 K | 64,85 | Qualified. |
| TE-5UP-001 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 64 65 85 | Qualified. |
| TE-5UP-005 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 65 | Qualified. |

TABLE 7. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (+) | After Experiment Initiation | | Figure | Comments |
|--------------------------------------|-----------------------------------|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|--------|------------|
| | | | | | Reading | Uncertainty (+) | | |
| TEMPERATURE (continued) | | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | | |
| TE-5UP-008 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 65 | Qualified. |
| TE-6LP-001 | Fuel Assembly 6 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 66 | Qualified. |
| TE-6UP-001 | Fuel Assembly 6 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | 67 | Qualified. |

- a. Recording frequency is the measurement channel bandwidth at the ± 3 dB level.
- b. Reference 6.
- c. The steam generator level is defined as 0 at 2.95 m above the top of the tube sheet.
- d. Reference 7.
- e. Pressure measurements are presented as absolute values.

TABLE 8. COMPUTED VARIABLES FOR EXPERIMENT L6-5

| <u>Variable, Location, and Detector</u> | <u>Units</u> | <u>Uncertainty</u> | <u>Calculation Method</u> | <u>Figure</u> | <u>Comments</u> |
|---|--------------|--------------------|--|---------------|-----------------|
| FLUID SUBCOOLING | | | | | |
| <u>Upper Plenum</u> | | | | | |
| PE-1UP-001A1 | K | 6 K | The subcooling is defined as $T_{sat} - T$. The saturation temperature is calculated from the pressure reading of PE-1UP-001A1 using the following curve fits of steam table data: for $P < 1.4$ MPa, $T_{sat} = 348.225 - 290.13P + 399.543P^2 + 298.730P^3 - 84.196P^4$ for $1.4 \text{ MPa} \leq P \leq 12 \text{ MPa}$, $T_{sat} = 419.024 + 42.6705P - 5.63957P^2 + 0.433108P^3 - 0.0130329P^4$ for $P > 12 \text{ MPa}$, $T_{sat} = 508.252 + 8.84806P - 0.114572P^2$. | 86,87 | Qualified. |
| TE-5UP-1 through TE-5UP-8 | | | The measured temperature is an average of TE-5UP-1 through TE-5UP-8. | | |




Figure 21. Valve position for secondary feedwater flow control valve (CV-P004-008) (Qualified).




Figure 22. Differential pressure across venturi flowmeter at secondary coolant system main feedwater pump discharge (PT-P004-72A) (Qualified).




Figure 23. Liquid level in steam generator secondary side, wide range (LT-P004-008B) (Qualified, data not density compensated).




Figure 24. Local heat generation rate for Fuel Assembly 2 (NE-2H8-26) (Qualified through reactor scram, relative changes only).




Figure 25. Local average power, Channel B (RE-T-77-2A2) (Qualified).




Figure 26. Valve position for secondary coolant system steam flow control valve (CV-P004-010) (Qualified).




Figure 27. Fluid velocity above upper end box of Fuel Assembly 5 (FE-5UP-001) (Qualified).




Figure 28. Steam flow rate at condenser inlet (PT-P004-012)
(Qualified, magnitude uncertain after scram).




Figure 29. Flow rate in intact loop hot leg venturi
(FT-P139-27-3) (Qualified).




Figure 30. Liquid level in steam generator secondary side, wide range (LT-P004-008B) (Qualified, data not density compensated).




Figure 31. Liquid level in pressurizer (LT-P139-007) (Qualified for relative changes only).




Figure 32. Differential pressure in intact loop across primary coolant Pumps 1 and 2 (PdE-PC-001) (Qualified).




Figure 33. Differential pressure in intact loop across pressurizer surge line (PdE-PC-008) (Qualified).




Figure 34. Differential pressure in intact loop across reactor vessel (PdT-P139-030) (Qualified).




Figure 35. Pressure in intact loop cold leg (PE-PC-001) (Qualified).




Figure 36. Pressure in pressurizer (PE-PC 004) (Qualified).




Figure 37. Reference pressure in intact loop between steam generator outlet and pump inlet (PE-PC-006) (Qualified).




Figure 38. Pressure in steam generator dome (PE-SGS-001) (Qualified).




Figure 39. Pressure in reactor vessel Downcomer Stalk 1 (PE-1ST-001A) (Qualified).




Figure 40. Pressure in reactor vessel above upper end box of Fuel Assembly 1 (PE-1UP-001A1) (Qualified).




Figure 41. Pressure in steam generator secondary side 10-inch outlet (PT-P004-010A) (Qualified).




Figure 42. Pressure in secondary coolant system condenser 12-inch inlet (PT-P004-085) (Qualified).




Figure 43. Pressure in intact loop hot leg venturi on left side looking toward steam generator (PT-P139-003) (Qualified).




Figure 44. Pressure in pressurizer 1.88 m above pressurizer bottom (vapor space) (PT P139 005) (Qualified).




Figure 45. Coolant temperature in intact loop cold leg at bottom of ECC Rake 1 and upstream of DTT flange (TE PC 004 and (TE-P139-029) (Qualified. TE P139 029 is a process instrument with slow response time).




Figure 46. Fluid temperature in pressurizer vapor space (TE-P139-019) (Qualified).




Figure 47. Fluid temperature in pressurizer liquid space (TE-P139-020) (Qualified).




Figure 48. Fluid temperature in intact loop hot leg (TE-P139-32-1)
(Qualified, process instrument, slow response time).




Figure 49. Fluid temperature in intact loop steam generator primary side inlet plenum (TE-SG-001) (Qualified).




Figure 50. Fluid temperature in intact loop steam generator primary side outlet plenum (TE-SG-002) (Qualified).




Figure 51. Fluid temperature in steam generator secondary side downcomer (TE-SG-003) (Qualified).




Figure 52. Coolant temperature in reactor vessel at lower end box of Fuel Assembly 1 (TE-1LP-001) (Qualified).




Figure 53. Coolant temperature in reactor vessel Downcomer Stalk 1 at 0.24 m from reactor vessel bottom (TE-1ST-013) (Qualified).




Figure 54. Coolant temperature in reactor vessel at upper end box of Fuel Assembly 1 (TE-1UP-001) (Qualified).




Figure 55. Coolant temperature in reactor vessel Downcomer Stalk 2 at 1.17 m from reactor vessel bottom (TE-2ST-014) (Qualified).




Figure 56. Coolant temperature in reactor vessel at upper end box of Fuel Assembly 2 (TE-2UP-003) (Qualified).




Figure 57. Coolant temperature in reactor vessel at lower end box of Fuel Assembly 3 (TE-3LP-001) (Qualified).




Figure 58. Coolant temperature in reactor vessel at upper end box of Fuel Assembly 3 (TE-3UP-001) (Qualified).




Figure 59. Coolant temperature in reactor vessel at lower end box of Fuel Assembly 4 (TE-4LP-003) (Qualified).




Figure 60. Coolant temperature in reactor vessel at upper end box of Fuel Assembly 4 (TE-4UP-001) (Qualified).




Figure 61. Cladding temperature in reactor vessel at Fuel Assembly 5, Row D, Column 6 at 0.76 m, Row F, Column 9 at 1.57 m, Row G, Column 8 at 0.20 m above bottom of fuel rod (TE-5D6-030, -5F9-062, and -5G8-008) (Qualified).




Figure 62. Cladding temperature in reactor vessel at Fuel Assembly 5, Row P, Column 9 at 1.14 m above bottom of fuel rod (TE-5F9-045) (Qualified).




Figure 63. Cladding temperature in reactor vessel at Fuel Assembly 5, Row G, Column 8 at 0.66 m above bottom of fuel rod (TE-5G8-026) (Qualified).




Figure 34. Coolant temperature in reactor vessel at lower and upper end boxes of Fuel Assembly 5 (TE-5LP-001 and -5UP-001) (Qualified).




Figure 65. Coolant temperature in reactor vessel at upper end box of Fuel Assembly 5 (TE-5UP-001, -005, and -008) (Qualified).




Figure 66. Coolant temperature in reactor vessel at lower end box of Fuel Assembly 6 (TE-6LP-001) (Qualified).




Figure 67. Coolant temperature in reactor vessel at upper end box of Fuel Assembly 6 (TE-6UP-001) (Qualified).




Figure 68. Valve position for secondary coolant system steam flow control valve (CV-P004-010) (Qualified).




Figure 69. Steam flow rate at condenser inlet (FT-P004-012) (Qualified, magnitude uncertain after scram).




Figure 70. Flow rate in EXC charging pump AC P-48 discharge (FT-P128-085) (Qualified).




Figure 71. Flow rate in intact loop hot leg venturi (FT-P139-27-3) (Qualified).




Figure 72. Liquid level in steam generator secondary side, wide range (LT-P004-008B) (Qualified, data not density compensated).




Figure 73. Liquid level in condensate receiver at centerline (LT-P004-042) (Qualified).




Figure 74. Liquid level in pressurizer (LT-P139-007) (Qualified for relative changes only).




Figure 75. Pressure in pressurizer (PE-PC-004) (Qualified).




Figure 76. Reference pressure in intact loop between steam generator outlet and pump inlet (PE-PC-006) (Qualified).




Figure 77. Pressure in steam generator dome (PE-SGS-001) (Qualified).




Figure 78. Pressure in reactor vessel above upper end box of Fuel Assembly 1 (PE-1UP-001A1) (Qualified).




Figure 79. Coolant temperature in intact loop cold leg at bottom of ECC Rake 1 and upstream of DTT flange (TE-PC-004 and TE-P139-029) (Qualified. TE-P139-029 is a process instrument with slow response time).




Figure 80. Fluid temperature in pressurizer vapor space (TE-P139-019) (Qualified).




Figure 81. Fluid temperature in pressurizer liquid space (TE-P139-020) (Qualified).




Figure 82. Fluid temperature in intact loop steam generator primary side inlet plenum (TE-SG-001) (Qualified).




Figure 83. Fluid temperature in intact loop steam generator primary side outlet plenum (TE-SG-002) (Qualified).




Figure 84. Fluid temperature in steam generator secondary side downcomer (TE-SG-003) (Qualified).




Figure 85. Coolant temperature in reactor vessel at lower and upper end boxes of Fuel Assembly 5 (TE-5LP-001 and -5UP-001) (Qualified).




Figure 86. Fluid subcooling in reactor vessel upper plenum (SC-5UP-102) (Qualified).




Figure 87. Fluid subcooling in reactor vessel upper plenum (SC-5UP-102) (Qualified).

6. REFERENCES

1. D. L. Reeder, *LOFT System and Test Description (5.5-ft. Nuclear Core 1 LOCEs)*, NUREG/CR-0247, TREE-1208, July 1978.
2. M. L. Russell, *LOFT Fuel Modules Design, Characterization, and Fabrication Program*, TREE-NUREG-1131, June 1977.
3. F. S. Miyasaki, *Digital Data Acquisition Program*, ANCR-1250, August 1975.
4. N. L. Norman, *LOFT Data Reduction*, ANCR-1251, August 1975.
5. *Proposed ANS Standard 5.1 Decay Heat Power in Light Water Reactors*, September 1978.
6. S. Silverman, *LOFT Experimental Measurements Uncertainty Analyses, VolumeXIV, LOFT Drag Disc-Turbine Transducer Uncertainty Analysis*, NUREG/CR-0169, TREE-1089, November 1978.
7. G. D. Lassahn, *LOFT Experimental Measurements Uncertainty Analyses, VolumeVII, LOFT Self-Powered Neutron Detector Uncertainty Analysis*, NUREG/CR-0169, TREE-1089, August 1978.

APPENDIX A
DATA CONSISTENCY CHECKS

APPENDIX A

DATA CONSISTENCY CHECKS

The following discussion describes several techniques used to perform consistency checks on the data presented in this report. The purpose of these checks is to establish data integrity and to evaluate the performance of a given transducer. Tests were performed on data before, during, and after the experiment. The tests conducted during and after the experiment were similar to those conducted on preexperiment data, so only the procedure for the preexperiment tests is given.

A series of tests was conducted at various temperatures, pressures, and flow rates prior to the experiment initiation. These tests included static pressure, steady state flow, zero flow, pump coastdown, and isothermal tests. Using the data from these tests, the following checks were performed.

1. ABSOLUTE PRESSURE DATA

During the approach to initial conditions, a series of static pressure tests was performed. After each test, the absolute pressure measurements were compared with two reference pressures (PE-PC-005 and -006). The pressure tests were used to evaluate the slope coefficient of the calibration equations, and to evaluate the pressure sensitivity of the transducers.

The steam generator pressure transducer was checked against the pressure obtained from the steam tables using the steam generator temperature.

2. FLOW DATA

Measurements of fluid flow included pump speed, differential pressure, venturi, turbines, and drag discs. The measurements were analyzed

primarily to check the zero offset. Turbine and drag-disc measurements were also analyzed to check slope coefficient (gain) changes.

2.1 Pump Speed Data

The reference measurement for all intact loop flow measurements was primary coolant pump speed, because it is the most accurate and stable of the flow measurements. The pump speed measurement was adjusted using a square wave generator to calibrate the digital to analog conversion.

During heatup, the zero reading was checked at every zero flow point, and during flow tests, the pump speed was checked against pump frequency. Pump speed measurements were checked for consistency by comparison with pump speed as calculated from the primary system motor generator frequencies. Prior to the experiment, the pump speed was further checked by reviewing the agreement with previous LOFT experiments.

Pump run voltages and currents were evaluated prior to the experiment by calculating the pump electrical horsepower input, the pump water power, and finally the combined pump efficiency. These calculated efficiencies were then compared with previously recorded efficiencies determined during pump requalification tests.

2.2 Differential Pressure Data

Zero offsets were determined from flow data, static pressure tests, and temperature sensitivity data derived during the heatup. Steady state flow conditions for the primary coolant system (PCS) were then established, and selected PCS pressure

drops were compared with predicted values. At various flow conditions, intact loop flow resistance coefficients were calculated and verified to remain essentially constant and to agree with previously tabulated data. Further consistency checks were performed on the intact loop differential pressure measurements by plotting the square root of the differential pressure against pump speed using data from the pump frequency tests. The results of the curve fits performed on those plots were then used to confirm zero offsets. Both prior to and during the experiment, differential pressure measurements were compared with the differential pressure computed by subtracting appropriate absolute pressure measurements. Finally, pressure closure was calculated for the PCS intact loop.

2.3 Venturi Data

Consistency checks were performed by comparing the venturi mass flow rate with venturi mass flow rates from previous LOFT experiments (with the same loop resistance) and to each other. A comparison of the venturi with the pump speed consisted of performing a least squares fit of the venturi data versus the pump data (derived from the pump speed frequency test). The results were used to correct any zero offset in the venturi. The corrected venturi data were then used to calculate the average fluid velocity and momentum flux of the intact loop. The computed velocity was

compared to the differential pressure measured across the pumps, the steam generator, and the reactor vessel.

In addition, the computed fluid velocity and the momentum flux were compared to the output of the turbines and drag discs in the reactor vessel.

2.4 Drag-Disc Turbine (DTT) Data

Data from the reactor vessel drag discs were compared with values calculated from venturi mass flow, assuming the full flow area. Slope coefficients were calculated and the effect of temperature on the calibration coefficients was determined.

After the slope coefficients had been verified, the data for a given transducer were plotted against pump speed and a least squares fit performed. The zero offset from this curve fit was used to modify the zero offset of the transducers.

As an independent check, the turbine flowmeter and drag-disc data were used to calculate fluid density. These values were then compared to the known density prior to the experiment. This analysis was performed on all the turbine flowmeter and drag disc measurements in the reactor vessel with the exception of those that failed.

3. GAMMA DENSITOMETER DATA

To evaluate the PCS average fluid densities, calculations were performed using the gamma densitometers. The densitometers were checked for normal operation by recording and observing

spectra, count rate data, and live-time data on the densitometer system display console during and immediately before the experiment.

4. LEVEL MEASUREMENT DATA

Liquid level measurements for the pressurizer and the steam generator secondary side were

evaluated. Both liquid levels were reviewed by redundant level measurements.

5. THERMOCOUPLE DATA

Temperature measurements were analyzed by comparing them with other temperature data obtained during the isothermal tests. Resistance temperature measurements were used for

reference where they existed. Temperature measurements outside the PCS were compared with a known temperature in the same area.

APPENDIX B
EXPERIMENT L6-5 INSTRUMENTATION LIST

APPENDIX B

EXPERIMENT L6-5 INSTRUMENTATION LIST

Table B-1 contains a list of all the instruments in the Loss-of-Fluid Test (LOFT) system that were available to be used for Experiment L6-5. Included in Table B-1 are the instrument location, range, initial condition uncertainty, uncertainty at specific readings, and recording frequency. The "Comments" column contains information

relative to the usability of the data. No entry under the "Comments" column means that the instrument was recorded, but the data were not reviewed or presented. No entry under the "Initial Condition Uncertainty" column means that the instrument was recorded only on the plant log and surveillance system.

TABLE B-1. EXPERIMENT L6-5 INSTRUMENTATION LIST

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (%) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------|--------------------|---------------------|
| | | | | | Reading | Uncertainty (%) | |
| <u>VALVE OPENING</u> | | | | | | | |
| <u>Intact Loop</u> | | | | | | | |
| CV-P004-008 | Main feedwater control valve. | 0 to 100% | 1 Hz | 3.2% | 0% | 3.0% | Qualified to 200 s. |
| | | | | | 25% | 3.13% | |
| | | | | | 50% | 3.47% | |
| | | | | | 100% | 4.61% | |
| CV-P004-010 | Main steam control valve. | 0 to 100% | 1 Hz | 3.9% | 0% | 3.0% | Qualified. |
| | | | | | 25% | 3.13% | |
| | | | | | 50% | 3.47% | |
| | | | | | 100% | 4.61% | |
| CV-P004-090 | Main steam bypass valve. | 0 to 100% | 1 Hz | — | 0% | 3.0% | |
| | | | | | 25% | 3.13% | |
| | | | | | 50% | 3.47% | |
| | | | | | 100% | 4.61% | |
| CV-P004-091 | Main feedwater bypass valve. | 0 to 100% | 1 Hz | 3.0% | 0% | 3.0% | |
| | | | | | 25% | 3.13% | |
| | | | | | 50% | 3.47% | |
| | | | | | 100% | 4.61% | |
| <u>Broken Loop</u> | | | | | | | |
| CV-P138-001 | Broken loop cold leg between break plane and suppression tank. | 0 to 100% | 1 Hz | 3.0% | 0% | 3.0% | |
| | | | | | 25% | 3.13% | |
| | | | | | 50% | 3.47% | |
| | | | | | 100% | 4.61% | |
| CV-P138-015 | Quick-opening blowdown valve (QOBV) in hot leg. | 0 to 100% | 1 Hz | 3.0% | 0% | 3.0% | |
| | | | | | 25% | 3.13% | |
| | | | | | 50% | 3.47% | |
| | | | | | 100% | 4.61% | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------------|-------------------------------------|--|-----------------------------|---------------------------------|----------|
| | | | | | Reading | Uncertainty (±) | |
| VALVE OPENING (continued) | | | | | | | |
| <u>Broken Loop (continued)</u> | | | | | | | |
| CV-P138-070A | Blowdown system bypass valve. | 0 to 100% | 1 Hz | 4.61% | 0% 25% 50% 100% | 3.0% 3.13% 3.47% 4.61% | |
| CV-P138-071A | Blowdown system bypass valve. | 0 to 100% | 1 Hz | 4.61% | 0% 25% 50% 100% | 3.0% 3.13% 3.47% 4.61% | |
| CV-P138-123 | 1.3-L/s spray header control valve. | 0 to 100% | 1 Hz | 3.0% | 0% 25% 50% 100% | 3.0% 3.13% 3.47% 4.61% | |
| CV-P138-124 | 3.8-L/s spray header control valve. | 0 to 100% | 1 Hz | 3.0% | 0% 25% 50% 100% | 3.0% 3.13% 3.47% 4.61% | |
| CV-P138-125 | 13.9-L/s spray header control valve. | 0 to 100% | 1 Hz | 3.05% | 0% 25% 50% 100% | 3.0% 3.13% 3.47% 4.61% | |
| CHORDAL DENSITY | | | | | | | |
| <u>Broken Loop</u> | | | | | | | |
| DE-BL-001A | Broken loop cold leg at drag disc turbine trans- ducer (DTT) flange. Beam A is 14° 21 min from Beam B [CW looking toward reactor vessel (RV)]. | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | 0.072 Mg/m ^{3b} | |
| DE-BL-001B | Broken loop cold leg at DTT flange. Beam B through centerline of pipe 45° from vertical (CCW looking toward RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | 0.072 Mg/m ³ | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------------|-------------------------------------|--|-----------------------------|-------------------------|----------------|
| | | | | | Reading | Uncertainty (±) | |
| CHORDAL DENSITY (continued) | | | | | | | |
| <u>Broken Loop</u> (continued) | | | | | | | |
| DE-BL-001C | Broken loop cold leg at DTT flange. Beam C is 22° 7 min from Beam B (CCW looking toward RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | 0.116 Mg/m ³ | |
| DE-BL-002A | Broken loop hot leg at DTT flange. Beam A is 14° 21 min. from Beam (CCW looking toward RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | 0.068 Mg/m ³ | |
| DE-BL-002B | Broken loop hot leg at DTT flange. Beam B through centerline of pipe 45° from vertical (CW looking toward RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | Not available. | |
| DE-BL-002C | Broken loop hot leg at DTT flange. Beam C is 22° 7 min from Beam B (CW looking toward RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | Not available. | Not installed. |
| <u>Intact Loop</u> | | | | | | | |
| DE-PC-001A | Intact loop cold leg at DTT flange. Beam A is 14° 21 min from Beam B (CW looking away from RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | Not available. | |
| DE-PC-001B | Intact loop cold leg at DTT flange. Beam B through centerline of pipe 45° from vertical (CCW looking away from RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | 0.072 Mg/m ³ | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------------|-------------------------------------|--|-----------------------------|--------------------|----------|
| | | | | | Reading | Uncertainty (±) | |
| CHORDAL DENSITY (continued) | | | | | | | |
| <u>Intact Loop</u> (continued) | | | | | | | |
| DE-PC-001C | Intact loop cold leg at DTT flange. Beam C is 22° 7 min from Beam B (CCW looking away from RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | Not available. | |
| DE-PC-002A | Intact loop hot leg at DTT flange. Beam A is 14° 21 min from Beam B (CW looking away from RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | Not available. | |
| DE-PC-002B | Intact loop hot leg at DTT flange. Beam B through centerline of pipe 45° from vertical (CCW looking away from RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | Not available. | |
| DE-PC-002C | Intact loop hot leg at DTT flange. Beam C is 22° 7 min from Beam B (CCW looking away from RV). | 0 to 1.0 Mg/m ³ | 10 Hz | -- | -- | Not available. | |
| DE-PC-003A | Intact loop below steam generator (SG) at DTT flange. Beam C is 14° 21 min from Beam B (CCW looking away from RV). | 0 to 1.0 Mg/m ³ | 1 Hz | -- | -- | Not available. | |
| DE-PC-003B | Intact loop below SG at DTT flange. Beam B through centerline of pipe 45° from vertical (CW looking away from RV). | 0 to 1.0 Mg/m ³ | 1 Hz | -- | -- | Not available. | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (*) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------------|-------------------------------------|--|-----------------------------|---|---------------------|
| | | | | | Reading | Uncertainty (*) | |
| CHORDAL DENSITY (continued) | | | | | | | |
| <u>Intact Loop</u> (continued) | | | | | | | |
| DE-PC-003C | Intact loop below SG at DTT flange. Beam C is 22° 7 min from Beam B (CW looking away from RV). | 0 to 1.0 Mg/m ³ | 1 Hz | -- | -- | Not available. | |
| FUEL ASSEMBLY DISPLACEMENT | | | | | | | |
| <u>Assembly 5</u> | | | | | | | |
| DIE-5UP-001 | At top center of Fuel Assembly 5. | +12.7 mm | 100 Hz | 0.3 mm | 0 mm 6.35 mm 12.7 mm | 0.3 mm ^c 0.33 mm 0.39 mm | |
| DIE-5UP-002 | At top center of Fuel Assembly 5. | +12.7 mm | 100 Hz | 0.3 mm | 0 mm 6.35 mm 12.7 mm | 0.3 mm 0.33 mm 0.39 mm | |
| FLUID VELOCITY | | | | | | | |
| <u>Intact Loop</u> | | | | | | | |
| FE-PC-002A | Hot leg DTT flange at bottom of pipe. | 0.6 to 15.0 m/s | 1 Hz | 0.18 m/s | 1 m/s 8 m/s 15 m/s | 0.16 m/s ^d 0.48 m/s 0.86 m/s | Not installed. |
| FE-PC-002B | Hot leg DTT flange at middle of pipe. | 0.6 to 15.0 m/s | 1 Hz | 0.16 m/s | 1 m/s 8 m/s 15 m/s | 0.16 m/s 0.48 m/s 0.86 m/s | Not installed. |
| FE-PC-002C | Hot leg DTT flange at top of pipe. | 0.6 to 15.0 m/s | 1 Hz | 0.20 m/s | 1 m/s 8 m/s 15 m/s | 0.16 m/s 0.48 m/s 0.86 m/s | Not installed. |
| <u>Reactor Vessel</u> | | | | | | | |
| FE-5UP-001 | Above upper end box of Fuel Assembly 5. | 0.5 to 10.0 m/s | 1 Hz | 0.23 m/s | 1 m/s 5 m/s 10 m/s | 0.06 m/s 0.28 m/s 0.56 m/s | Qualified to 200 s. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|---|---|----------------------|-------------------------------------|--|-----------------------------|----------------------------------|---|
| | | | | | Reading | Uncertainty (±) | |
| <u>FLOW RATE</u> | | | | | | | |
| <u>Blowdown Sup- pression Tank Spray System</u> | | | | | | | |
| FE-P138-138 | Blowdown suppression tank (BST) spray flow rate in the 3.79-L/s header. | 0 to 6.3 L/s | 1 Hz | 0.07 L/s | 0 L/s 4 L/s 6 L/s | 0.06 L/s 0.23 L/s 0.35 L/s | |
| FE-P138-139 | BST spray flow rate from pump discharge. | 0 to 25.2 L/s | 1 Hz | 0.26 L/s | 0 L/s 12 L/s 25 L/s | 0.25 L/s 0.72 L/s 1.43 L/s | |
| FE-P138-140 | BST spray flow rate in 13.9-L/s header. | 0 to 18.9 L/s | 1 Hz | 0.26 L/s | 0 L/s 10 L/s 18.9 L/s | 0.19 L/s 0.60 L/s 1.08 L/s | |
| FE-P138-153 | BST spray flow rate in the spray pump recirculation line. | 0 to 9.5 L/s | 1 Hz | 0.10 L/s | 0 L/s 5 L/s 9.5 L/s | 0.10 L/s 0.30 L/s 0.54 L/s | |
| <u>Intact Loop</u> | | | | | | | |
| FT-P004-012 | Inlet to air-cooled condenser inlet header. | 0 to 40 kg/s | 1 Hz | 0.8 kg/s | -- | 0.8 kg/s | Qualified, magnitude uncertain after scram. |
| FT-P004-072A | Main feedwater pump discharge flow. | 0 to 25 kPa | 10 Hz | 0.17 kPa | -- | 0.17 kPa | Qualified. |
| FT-P004-72-2 | Flow out of main feedwater pump. | 0 to 40 kg/s | 1 Hz | 0.8 kg/s | -- | 0.8 kg/s | |
| <u>Emergency Core Cooling System</u> | | | | | | | |
| FT-P120-36-1 | Accumulator A in 6-in. line downstream of orifice. | 0 to 126.2 L/s | 1 Hz | 3.5 L/s | -- | 3.5 L/s | |
| FT-P120-36-5 | Accumulator A in 6-in. line downstream of orifice. | 0 to 37.9 L/s | 1 Hz | 3.5 L/s | -- | 3.5 L/s | |
| FT-P120-085 | Low-pressure injection system (LPIS) Pump A in 4-in. line between heat exchanger and orifice. | 0 to 25.2 L/s | 1 Hz | -- | -- | 2.5 L/s | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--|---|----------------------|-------------------------------------|--|-----------------------------|--------------------|--|
| | | | | | Reading | Uncertainty (±) | |
| FLOW RATE (continued) | | | | | | | |
| <u>Emergency Core Cooling System (continued)</u> | | | | | | | |
| FT-P128-085 | Charging pump AC-7-48 discharge. | 0 to 1.89 L/s | 1 Hz | 0.02 L/s | -- | 0.02 L/s | Qualified. |
| FT-P128-104 | High-pressure injection system (HPIS) Pump A discharge. | 0 to 1.89 L/s | 1 Hz | 0.02 L/s | -- | 0.02 L/s | |
| <u>Intact Loop</u> | | | | | | | |
| FT-P139-27-1 | Intact loop hot leg venturi flowmeter (right side facing SG). | 0 to 630.0 kg/s | 1 Hz | 17 kg/s | -- | 17 kg/s | Qualified to 200 s. |
| FT-P139-27-2 | Intact loop hot leg venturi flowmeter (bottom of pipe). | 0 to 630.0 kg/s | 1 Hz | 17 kg/s | -- | 17 kg/s | Qualified to 200 s. |
| FT-P139-27-3 | Intact loop hot leg venturi flowmeter (left side facing SG). | 0 to 630.0 kg/s | 1 Hz | 17 kg/s | -- | 17 kg/s | Qualified. |
| <u>Primary Com- ponent Cooling System</u> | | | | | | | |
| FT-P141-022 | Primary component cooling system. | 0 to 22 L/s | 10 Hz | 0.11 L/s | -- | 0.11 L/s | |
| LIQUID LEVEL | | | | | | | |
| <u>Emergency Core Cooling System System</u> | | | | | | | |
| LIT-P120-044 | Accumulator A. | 0 to 3.0 m | 1 Hz | 0.02 m | -- | 0.02 m | |
| <u>Secondary Coolant System</u> | | | | | | | |
| LT-P004-008A | SG feedwater level (narrow range). | -1.1 to 1.5 m | 1 Hz | -- | -- | 0.03 m | Qualified, not density compensated. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|---|--|---------------------------------|-------------------------------------|--|---|--|---|
| | | | | | Reading | Uncertainty (±) | |
| LIQUID LEVEL (continued) | | | | | | | |
| <u>Secondary Coolant System (continued)</u> | | | | | | | |
| LT-P004-0088 | SG feedwater level (wide range). | -3.6 to 1.4 m ^e | 1 Hz | 0.05 m | -- | 0.05 m | Qualified, data not density compensated. |
| <u>Intact Loop</u> | | | | | | | |
| LT-P004-042 | Condensate receiver level, 183 m south of condensate receiver centerline. | 0 to 1.2 m | 1 Hz | 0.02 m | -- | 0.02 m | Qualified to 200 s. |
| <u>Blowdown Sup- pression Tank</u> | | | | | | | |
| LT-P138-033 | BST level on north end of tank. | 0 to 3.4 m | 1 Hz | 0.03 m | -- | 0.03 m | |
| LT-P138-058 | BST level on south end of tank. | 0 to 3.4 m | 1 Hz | 0.03 m | -- | 0.03 m | |
| <u>Intact Loop</u> | | | | | | | |
| LT-P139-006 | Pressurizer level on southeast side. | 0 to 1.9 m | 1 Hz | 0.04 m | -- | 0.04 m | Qualified to 200 s. |
| LT-P139-007 | Pressurizer level on southwest side. | 0 to 1.9 m | 1 Hz | 0.04 m | -- | 0.04 m | Qualified for rela- tive changes only. |
| LT-P139-008 | Pressurizer level on north side. | 0 to 1.9 m | 1 Hz | 0.04 m | -- | 0.04 m | |
| MOMENTUM FLUX | | | | | | | |
| <u>Intact Loop</u> | | | | | | | |
| ME-PC-002A | Hot leg DTI flange at bottom of pipe. | 1.0 to 21.0 Mg/m·s ² | 1 Hz | 0.20 Mg/m·s ² | 1.0 Mg/m·s ² 11.0 Mg/m·s ² 21.0 Mg/m·s ² | 0.20 Mg/m·s ² 0.27 Mg/m·s ² 0.38 Mg/m·s ² | Not installed. |
| ME-PC-002B | Hot leg DTI flange at middle of pipe. | 1.0 to 21.0 Mg/m·s ² | 1 Hz | 0.20 Mg/m·s ² | 1.0 Mg/m·s ² 11.0 Mg/m·s ² 21.0 Mg/m·s ² | 0.20 Mg/m·s ² 0.27 Mg/m·s ² 0.38 Mg/m·s ² | Not installed. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|---------------------------------|-------------------------------------|--|---|--|---|
| | | | | | Reading | Uncertainty (±) | |
| <u>MOMENTUM FLUX</u> (continued) | | | | | | | |
| <u>Intact Loop</u> (continued) | | | | | | | |
| ME-PC-002C | Hot leg DTT flange at top of pipe. | 1.0 to 21.0 Mg/m·s ² | 1 Hz | 0.20 Mg/m·s ² | 1.0 Mg/m·s ² 11.0 Mg/m·s ² 21.0 Mg/m·s ² | 0.20 Mg/m·s ² 0.27 Mg/m·s ² 0.33 Mg/m·s ² | Not installed. |
| <u>Reactor Vessel</u> | | | | | | | |
| ME-1ST-001 | Downcomer Stalk 1, 1.16 m above RV bottom. | 0.3 to 5.2 Mg/m·s ² | 1 Hz | 0.78 Mg/m·s ² | -- | 0.78 Mg/m·s ² | |
| ME-2ST-001 | Downcomer Stalk 2, 1.16 m above RV bottom. | 0.3 to 5.2 Mg/m·s ² | 1 Hz | 0.78 Mg/m·s ² | -- | 0.78 Mg/m·s ² | |
| ME-1UP-001 | Fuel Assembly 1 above upper end box. | 0.3 to 5.2 Mg/m·s ² | 1 Hz | 0.78 Mg/m·s ² | -- | 0.78 Mg/m·s ² | |
| ME-3UP-001 | Fuel Assembly 3 above upper end box. | 0.3 to 5.2 Mg/m·s ² | 1 Hz | 0.78 Mg/m·s ² | -- | 0.78 Mg/m·s ² | |
| ME-5UP-001 | Fuel Assembly 5 above upper end box. | 0.3 to 5.2 Mg/m·s ² | 1 Hz | 0.78 Mg/m·s ² | -- | 0.78 Mg/m·s ² | |
| <u>NEUTRON DETECTION</u> | | | | | | | |
| <u>Reactor Vessel</u> | | | | | | | |
| NE-2H8-26 | Neutron detector in Fuel Assembly 2. | 0 to 52.5 kW/m (local) | 1 Hz | 2.03 kW/m | -- | 2.03 kW/m ^E | Qualified through reactor scram, relative changes only. |
| NE-4H8-26 | Neutron detector in Fuel Assembly 4. | 0 to 52.5 kW/m (local) | 1 Hz | 2.03 kW/m | -- | 2.03 kW/m | Qualified through reactor scram, relative changes only. |
| NE-5D8-26 | Neutron detector in Fuel Assembly 5. | 0 to 52.5 kW/m (local) | 1 Hz | 2.03 kW/m | -- | 2.03 kW/m | Qualified through reactor scram, relative changes only. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|-----------------------------|-------------------------------------|--|------------------------------------|--|---|
| | | | | | Reading | Uncertainty (±) | |
| NEUTRON DETECTION (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| NE-6H8-26 | Neutron detector in Fuel Assembly 6. | 0 to 52.5 kW/m (local) | 1 Hz | 2.03 kW/m | -- | 2.03 kW/m | Qualified through reactor scram, relative changes only. |
| ELECTRICAL FREQUENCY | | | | | | | |
| <u>Intact Loop</u> | | | | | | | |
| PCP-1-F | Intact loop Pump 1. | 0 to 75 Hz | 10 Hz | 0.75 Hz | -- | 0.75 Hz ⁸ | |
| PCP-2-F | Intact loop Pump 2. | 0 to 75 Hz | 10 Hz | 0.75 Hz | -- | 0.75 Hz | |
| ELECTRICAL POWER | | | | | | | |
| <u>Intact Loop</u> | | | | | | | |
| PCP-1-P | Intact loop Pump 1. | 0 to 1 MW | 10 Hz | 0.05 MW | -- | 0.05 MW | |
| PCP-2-P | Intact loop Pump 2. | 0 to 1 MW | 10 Hz | 0.05 MW | -- | 0.05 MW | |
| DIFFERENTIAL PRESSURE | | | | | | | |
| <u>Broken Loop</u> | | | | | | | |
| PdE-BL-002 | Broken loop cold leg across small break orifice. | +17.5 MPa (differential) | 1 Hz | 0.025 MPa | 0 MPa 5 MPa 10 MPa 15 MPa | 0.025 MPa 0.026 MPa 0.028 MPa 0.032 MPa | |
| PdE-BL-003 | Broken loop cold leg across 5- to 8-inch expansion. | +3.5 MPa (differential) | 1 Hz | 0.009 MPa | 0 MPa 2 MPa 3.5 MPa | 0.009 MPa 0.010 MPa 0.010 MPa | |
| PdE-BL-009 | Broken loop from end to middle of 5-inch pipe. | +700 kPa (differential) | 1 Hz | 1.7 kPa | 0 kPa 350 kPa 700 kPa | 1.7 kPa 1.7 kPa 1.9 kPa | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|------------------------------|-------------------------------------|--|-----------------------------|-------------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| DIFFERENTIAL PRESSURE (continued) | | | | | | | |
| <u>Broken Loop (continued)</u> | | | | | | | |
| PdE-BL-010 | Broken loop from middle to end of 5-inch pipe. | +700 kPa (differential) | 1 Hz | -- | 0 kPa 350 kPa 700 kPa | 1.7 kPa 1.7 kPa 1.9 kPa | |
| PdE-BL-013 | SG simulator, inlet to top. | +40 kPa | 1 Hz | 0.28 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-BL-014 | SG simulator, outlet to top. | +40 kPa | 1 Hz | 0.291 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | Not installed. |
| <u>Intact Loop</u> | | | | | | | |
| PdE-PC-001 | Intact loop cold leg across primary coolant pumps (PCPs). | +700 kPa (differential) | 1 Hz | 1.8 kPa | 0 kPa 350 kPa 700 kPa | 1.7 kPa 1.7 kPa 1.9 kPa | Qualified to 200 s. |
| PdE-PC-002 | Intact loop across SG. | +350 kPa (differential) | 1 Hz | 0.94 kPa | 0 kPa 150 kPa 300 kPa | 0.89 kPa 0.90 kPa 0.98 kPa | Qualified to 200 s. |
| PdE-PC-003 | Intact loop hot leg piping, RV to SG inlet. | +100 kPa (differential) | 1 Hz | 0.50 kPa | 0 kPa 50 kPa 100 kPa | 0.49 kPa 0.50 kPa 0.52 kPa | Failed. |
| PdE-PC-004 | Intact loop hot leg piping, surge line junction to SG inlet. | +100 kPa (differential) | 1 Hz | 0.50 kPa | 0 kPa 50 kPa 100 kPa | 0.49 kPa 0.50 kPa 0.52 kPa | |
| PdE-PC-005 | Intact loop cold leg PCPs to RV nozzle. | +100 kPa (differential) | 1 Hz | 0.50 kPa | 0 kPa 50 kPa 100 kPa | 0.49 kPa 0.50 kPa 0.52 kPa | Qualified to 200 s. |
| PdE-PC-006 | Intact loop RV outlet to inlet. | +100 kPa (differential) | 1 Hz | 0.51 kPa | 0 kPa 50 kPa 100 kPa | 0.49 kPa 0.50 kPa 0.52 kPa | |
| PdE-PC-008 | Intact loop across pressurizer surge line. | +10.34 kPa (differential) | 1 Hz | 0.025 kPa | 0 kPa 5 kPa 10 kPa | 0.025 kPa 0.026 kPa 0.028 kPa | Qualified to 200 s. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|---|--|----------------------------|-------------------------------------|--|-----------------------------|------------------------------------|----------------|
| | | | | | Reading | Uncertainty (±) | |
| DIFFERENTIAL PRESSURE (continued) | | | | | | | |
| <u>Intact Loop (continued)</u> | | | | | | | |
| PdE-PC-009 | Intact loop across Pump 1. | +700 kPa (differential) | 1 Hz | 1.8 kPa | 0 kPa 350 kPa 700 kPa | 1.7 kPa 1.7 kPa 1.9 kPa | |
| PdE-PC-010 | Intact loop across Pump 2. | +700 kPa (differential) | 1 Hz | 1.8 kPa | 0 kPa 350 kPa 700 kPa | 1.7 kPa 1.7 kPa 1.9 kPa | |
| PdE-PC-011 | Pitot tube at top of emergency core coolant (ECC) Rake 1 (facing RV). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-012 | Pitot tube next to top of ECC Rake 1 (facing RV). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-015 | Pitot tube at top of ECC Rake 1 (facing pump). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-016 | Pitot tube next to top of ECC Rake 1 (facing pump). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-017 | Pitot tube next to bottom of ECC Rake 1 (facing pump). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-17B | Pitot tube next to bottom of ECC Rake 1 (facing pump). | +5 kPa (differential) | 1 Hz | 0.037 kPa | -- | 0.037 kPa | |
| PdE-PC-018 | Pitot tube at bottom of ECC Rake 1 (facing pump). | +40 kPa (differential) | 1 Hz | -- | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | Not installed. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|---|--|---------------------------|-------------------------------------|--|-----------------------------|------------------------------------|----------|
| | | | | | Reading | Uncertainty (±) | |
| DIFFERENTIAL PRESSURE (continued) | | | | | | | |
| <u>Intact Loop (continued)</u> | | | | | | | |
| PdE-PC-18B | Pitot tube at bottom of ECC Rake 1 (facing pump). | +5 kPa (differential) | 1 Hz | 0.037 kPa | -- | 0.037 kPa | |
| PdE-PC-019 | Pitot tube at top of ECC Rake 2 (facing RV). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-020 | Pitot tube next to top of ECC Rake 2 (facing RV). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-023 | Pitot tube at top of ECC Rake 2 (facing pump). | +40 kPa (differential) | 1 Hz | 0.284 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-024 | Pitot tube next to top of ECC Rake 2 (facing pump). | +40 kPa (differential) | 1 Hz | 0.286 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-025 | Pitot tube next to bottom of ECC Rake 2 (facing pump). | +40 kPa (differential) | 1 Hz | 0.287 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-25B | Pitot tube next to bottom of ECC Rake 2 (facing pump). | +5 kPa (differential) | 1 Hz | 0.037 kPa | -- | 0.037 kPa | |
| PdE-PC-026 | Pitot tube at bottom of ECC Rake 2 (facing pump). | +40 kPa (differential) | 1 Hz | -- | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-26B | Pitot tube at bottom of ECC Rake 2 (facing pump). | +5 kPa (differential) | 1 Hz | 0.037 kPa | -- | 0.037 kPa | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|---|--|----------------------------|-------------------------------------|--|-----------------------------|------------------------------------|----------|
| | | | | | Reading | Uncertainty (±) | |
| DIFFERENTIAL PRESSURE (continued) | | | | | | | |
| <u>Intact Loop (continued)</u> | | | | | | | |
| PdE-PC-027 | SG outlet to pump suction (lowest point). | +40 kPa | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-028 | Pump suction (lowest point) to Pump 2 inlet. | +40 kPa | 1 Hz | 0.284 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-029 | Pitot tube next to bottom of ECC Rake 1 (facing RV). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-030 | Pitot tube at bottom of ECC Rake 1 (facing RV). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-031 | Pitot tube next to bottom of ECC Rake 2 (facing RV). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| PdE-PC-032 | Pitot tube at bottom of ECC Rake 2 (facing RV). | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| <u>Reactor Vessel</u> | | | | | | | |
| PdE-RV-002 | Fuel Assembly 1 from lower end box to upper end box. | +175 kPa (differential) | 1 Hz | 1.3 kPa | 0 kPa 100 kPa 175 kPa | 1.3 kPa 1.3 kPa 1.4 kPa | |
| PdE-RV-003 | Intact loop cold leg inlet to bottom of downcomer. | +100 kPa (differential) | 1 Hz | 0.50 kPa | 0 kPa 50 kPa 100 kPa | 0.49 kPa 0.50 kPa 0.52 kPa | |
| PdE-RV-004 | Fuel Assembly 1 lower end box to the RV out- let nozzle in the in- tact loop hot leg. | +175 MPa (differential) | 1 Hz | -- | 0 kPa 100 kPa 175 kPa | 1.3 kPa 1.3 kPa 1.4 kPa | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (*) | After Experiment Initiation | | Comments |
|--|---|--------------------------------|-------------------------------------|--|-----------------------------|------------------------------------|---------------------|
| | | | | | Reading | Uncertainty (*) | |
| <u>DIFFERENTIAL PRESSURE (continued)</u> | | | | | | | |
| <u>Reactor Vessel (continued)</u> | | | | | | | |
| PdE-RV-005 | Top of RV to intact loop hot leg. | +40 kPa (differential) | 1 Hz | 0.29 kPa | 0 kPa 20 kPa 40 kPa | 0.28 kPa 0.285 kPa 0.291 kPa | |
| <u>Blowdown Suppression Tank</u> | | | | | | | |
| PdE-SV-001 | BST. | 0 to 1.27 m | 1 Hz | -- | 0 m 0.7 m 1.4 m | 0.005 m 0.006 m 0.008 m | |
| PdE-SV-009 | BST across the vacuum breaker line. | +70 kPa (differential) | 10 Hz | 0.55 kPa | 0 kPa 30 kPa 70 kPa | 0.55 kPa 0.56 kPa 0.56 kPa | |
| <u>Reactor Vessel</u> | | | | | | | |
| PdE-2ST-001 | Bottom of Downcomer Stalk 2 to Fuel Assembly 3 upper end box. | +70 kPa (differential) | 1 Hz | -- | 0 kPa 30 kPa 70 kPa | 0.55 kPa 0.56 kPa 0.56 kPa | |
| PdE-2ST-003 | Top of Downcomer Stalk 2 to Fuel Assembly 3 upper plenum. | +175 kPa (differential) | 2.3 Hz | -- | 0 kPa 100 kPa 175 kPa | 1.3 kPa 1.3 kPa 1.4 kPa | |
| PdE-2ST-004 | Bottom of Downcomer Stalk 2 to Fuel Assembly 3 lower end box. | +70 kPa (differential) | 1 Hz | -- | 0 kPa 30 kPa 70 kPa | 0.55 kPa 0.56 kPa 0.56 kPa | |
| <u>Intact Loop</u> | | | | | | | |
| PdT-P139-27-1 | Intact loop venturi, Channel A. | 0 to 200 kPa (differential) | 1 Hz | 2 kPa | -- | 2 kPa | Qualified to 200 s. |
| PdT-P139-27-2 | Intact loop venturi, Channel B. | 0 to 200 kPa (differential) | 1 Hz | 2 kPa | -- | 2 kPa | |
| PdT-P139-27-3 | Intact loop venturi, Channel C. | 0 to 200 kPa (differential) | 1 Hz | 2 kPa | -- | 2 kPa | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|------------------------------|-------------------------------------|--|-----------------------------|-------------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| DIFFERENTIAL PRESSURE (continued) | | | | | | | |
| <u>Intact Loop (continued)</u> | | | | | | | |
| PdT-P139-030 | Across RV just beyond intact loop inlet and outlet nozzles. | 0 to 300 kPa (differential) | 1 Hz | 3 kPa | -- | 3 kPa | Qualified to 200 s. |
| PRESSURE ^b | | | | | | | |
| <u>Broken Loop</u> | | | | | | | |
| PE-BL-001 | Broken loop cold leg at DTT flange. | 0.1 to 20.8 MPa ^h | 1 Hz | 0.251 MPa | 0 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | Qualified to 200 s. |
| PE-BL-002 | Broken loop hot leg at DTT flange. | 0.1 to 20.8 MPa | 1 Hz | 0.277 MPa | 0 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | Failed. |
| PE-BL-003 | Broken loop hot leg downstream of pump simulator. | 0.1 to 20.8 MPa | 1 Hz | 0.251 MPa | 0 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | |
| PE-BL-004 | Broken loop cold leg at inlet of spool piece. | 0.1 to 20.8 MPa | 1 Hz | -- | 0 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | |
| PE-BL-006 | Broken loop hot leg at outlet of SG simulator. | 0.1 to 20.8 MPa | 1 Hz | -- | 0 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | |
| PE-BL-008 | Broken loop cold leg in 8-in. pipe downstream of break. | 0.1 to 20.8 MPa | 1 Hz | 0.251 MPa | 0 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | |
| <u>Intact Loop</u> | | | | | | | |
| PE-PC-001 | Intact loop cold leg at DTT flange. | 0.1 to 20.8 MPa | 1 Hz | 0.251 MPa | 0 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | Qualified to 200 s. |
| PE-PC-002 | Intact loop hot leg at DTT flange. | 0.1 to 20.8 MPa | 1 Hz | 0.282 MPa | 0 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | Not installed. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--|---|----------------------|-------------------------------------|--|-----------------------------|-------------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| PRESSURE (continued) | | | | | | | |
| <u>Intact Loop (continued)</u> | | | | | | | |
| PE-PC-004 | Intact loop pressurizer vapor space. | 0.1 to 20.8 MPa | 1 Hz | 0.251 MPa | 0.1 MPa 10 MPa 20 MPa | 0.199 MPa 0.223 MPa 0.282 MPa | Qualified. |
| PE-PC-005 | Intact loop reference pressure between SG outlet and pump inlet. | 0.1 to 17.0 MPa | 1 Hz | 0.028 MPa | -- | 0.028 MPa | Qualified to 200 s. |
| PE-PC-006 | Intact loop reference pressure between SG outlet and pump inlet. | 0.1 to 17.0 MPa | 1 Hz | 0.028 MPa | -- | 0.028 MPa | Qualified. |
| PE-SGS-001 | SG dome pressure. | 0.1 to 7.0 MPa | 1 Hz | 0.012 MPa | -- | 0.012 MPa | Qualified. |
| <u>Blowdown Sup- pression System</u> | | | | | | | |
| PE-SV-003 | BST across from Downcomer 1 (south end), 157.5° from top vertical (CW looking north). | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |
| PE-SV-014 | BST header above Downcomer 4, 37° from top vertical (CW looking north). | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |
| PE-SV-015 | BST across from Downcomer 4, 230° from top vertical (CW looking north). | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |
| PE-SV-016 | BST across from Downcomer 1, 230° from top vertical (CW looking north). | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |
| PE-SV-017 | BST, 1.38 m north of Downcomer 3 centerline, 0° from top vertical (CW looking north). | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (\pm) | After Experiment Initiation | | Comments |
|--|---|----------------------|-------------------------------------|--|---------------------------------|-------------------------------------|---------------------|
| | | | | | Reading | Uncertainty (\pm) | |
| PRESSURE (continued) | | | | | | | |
| <u>Blowdown Sup- pression System (continued)</u> | | | | | | | |
| PE-SV-018 | BST header above Downcomer 1. | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |
| PE-SV-043 | BST tank bottom under Downcomer 2. | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |
| PE-SV-044 | BST bottom under Downcomer 3. | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |
| PE-SV-055 | BST top, 0.15 m north of Downcomer 4 center- line. | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |
| PE-SV-060 | BST top above Down- comer 1. | 0.1 to 0.7 MPa | 1 Hz | 0.008 MPa | -- | 0.008 MPa | |
| <u>Reactor Vessel</u> | | | | | | | |
| PE-1ST-001A | Downcomer Stalk 1, 0.62 m above RV bottom, wide range (0 to 20.8 MPa). | 0.1 to 20.8 MPa | 1 Hz | 0.200 MPa | 0.1 MPa 10.0 MPa 20.5 MPa | 0.199 MPa 0.199 MPa 0.200 MPa | Qualified to 200 s. |
| PE-1ST-003A | Downcomer Stalk 1, 5.32 m above RV bottom, wide range (0 to 20.8 MPa). | 0.1 to 20.8 MPa | 1 Hz | 0.25 MPa | 0.1 MPa 10 MPa 20 MPa | 0.2 MPa 0.22 MPa 0.28 MPa | Qualified to 200 s. |
| PE-1UP-001A | Above Fuel Assembly 1 upper end box, high range. | 0.1 to 20.8 MPa | 1 Hz | 0.25 MPa | 0.1 MPa 10 MPa 20 MPa | 0.2 MPa 0.22 MPa 0.28 MPa | Qualified. |
| PE-1UP-001A1 | Above Fuel Assembly 1 upper end box, high range. | 0.1 to 20.8 MPa | 1 Hz | 0.25 MPa | 0.1 MPa 10 MPa 20 MPa | 0.2 MPa 0.22 MPa 0.28 MPa | Qualified. |
| PE-2ST-001A | Downcomer Stalk 2, 0.62 m above RV bottom, wide range (0 to 20.8 MPa). | 0.1 to 20.8 MPa | 1 Hz | 0.25 MPa | 0.1 MPa 10 MPa 20 MPa | 0.2 MPa 0.22 MPa 0.28 MPa | Qualified to 200 s. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^d | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--|---|----------------------|-------------------------------------|--|-----------------------------|--------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| PRESSURE (continued) | | | | | | | |
| <u>Secondary Coolant System</u> | | | | | | | |
| PT-P004-010A | In 10-in. line from SG. | 0.1 to 8.4 MPa | 1 Hz | 0.110 MPa | -- | 0.110 MPa | Qualified to 200 s. |
| PT-P004-022 | Condensate receiver pressure. | 0 to 2.8 MPa | 1 Hz | -- | -- | 0.075 MPa | |
| PT-P004-034 | Downstream of main feedwater pump. | 0 to 10.3 MPa | 10 Hz | 0.07 MPa | -- | 0.07 MPa | |
| PT-P004-085 | Upstream of inlet to air-cooled condenser header. | 0 to 2.8 MPa | 1 Hz | 0.075 MPa | -- | 0.075 MPa | Qualified to 200 s. |
| <u>Emergency Core Cooling System</u> | | | | | | | |
| PT-P120-029 | Accumulator B, 0.69 m above water outlet. | 0.1 to 7.0 MPa | 1 Hz | 0.055 MPa | -- | 0.055 MPa | |
| PT-P120-043 | Accumulator A, 0.69 m above water outlet. | 0.1 to 7.0 MPa | 1 Hz | 0.055 MPa | -- | 0.055 MPa | |
| PT-P120-061 | ECC injection. | 0.1 to 20.8 MPa | 1 Hz | 0.158 MPa | -- | 0.158 MPa | |
| PT-P120-074 | LPIS Pump B discharge. | 0.1 to 7.0 MPa | 1 Hz | 0.055 MPa | -- | 0.055 MPa | |
| PT-P120-083 | LPIS Pump A discharge. | 0.1 to 7.0 MPa | 1 Hz | 0.04 MPa | -- | 0.04 MPa | |
| <u>Broken Loop</u> | | | | | | | |
| PT-P138-023 | Blowdown header. | 0.1 to 1.4 MPa | 10 Hz | -- | -- | 0.007 MPa | |
| PT-P138-111 | Broken loop cold leg QOBV inlet between iso- lation valve and QOBV. | 0.1 to 13.9 MPa | 100 Hz | -- | -- | 0.20 MPa | |
| PT-P138-112 | Broken loop hot leg QOBV inlet between iso- lation valve and QOBV. | 0.1 to 13.9 MPa | 100 Hz | -- | -- | 0.20 MPa | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|--|---|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| PRESSURE (continued) | | | | | | | |
| <u>Intact Loop</u> | | | | | | | |
| PT-P139-002 | Intact loop hot leg at venturi on bottom. | 0.1 to 20.8 MPa | 1 Hz | 0.25 MPa | -- | 0.25 MPa | Qualified to 200 s. |
| PT-P139-003 | Intact loop hot leg at venturi on left side when looking toward SG. | 0.1 to 20.8 MPa | 1 Hz | 0.25 MPa | -- | 0.25 MPa | Qualified to 200 s. |
| PT-P139-004 | Intact loop hot leg at venturi on right side when looking toward SG. | 0.1 to 20.8 MPa | 1 Hz | 0.25 MPa | -- | 0.25 MPa | Qualified to 200 s. |
| PT-P139-005 | 1.88 m above pres- surizer bottom (vapor space). | 10.3 to 17.2 MPa | 1 Hz | 0.12 MPa | -- | 0.12 MPa | Qualified to 200 s. |
| PUMP SPEED | | | | | | | |
| <u>Intact Loop</u> | | | | | | | |
| RPE-PC-001 | Intact loop Pump 1. | 0 to 10 000 rpm | 1 Hz | 10.26 rpm | 1000 rpm 2000 rpm 3000 rpm 4000 rpm | 7.65 rpm 8.825 rpm 10.10 rpm 11.66 rpm | |
| RPE-PC-002 | Intact loop Pump 2. | 0 to 10 000 rpm | 1 Hz | 10.27 rpm | 1000 rpm 2000 rpm 3000 rpm 4000 rpm | 7.65 rpm 8.825 rpm 10.10 rpm 11.66 rpm | |
| REACTIVITY | | | | | | | |
| <u>Reactor Vessel</u> | | | | | | | |
| RE-TRM-86-5 | Transient reactivity meter in shield tank. | +0.145 Rho | 10 Hz | 0.01 Rho | -- | 0.01 Rho | |
| RE-TRM-86-6 | Transient reactivity meter in shield tank. | +0.145 Rho | 10 Hz | 0.01 Rho | -- | 0.01 Rho | |
| RE-T-77-1A2 | Power range, Channel A level. | 0 to 100% power | 1 Hz | 3% | -- | 3% | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| REACTIVITY (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| RE-T-77-2A2 | Power range, Channel B level. | 0 to 100% power | 1 Hz | 3% | -- | 3% | Qualified to 200 s. |
| RE-T-77-3A2 | Power range, Channel C level. | 0 to 100% power | 1 Hz | 3% | -- | 3% | |
| RE-T-87-4A2 | Power range, Channel D level. | 0 to 100% power | 10 Hz | 3% | -- | 3% | |
| TEMPERATURE | | | | | | | |
| <u>Broken Loop</u> | | | | | | | |
| TE-BL-001B | Broken loop cold leg at DTT rake center. | 255.2 to 588.6 K | 1 Hz | 2.5 K | 350 K 450 K 550 K 650 K | 2.4 K 2.5 K 2.5 K 3.2 K | |
| TE-BL-002B | Broken loop hot leg at middle of DTT flange. | 255.2 to 588.6 K | 1 Hz | 2.5 K | 350 K 450 K 550 K 650 K | 2.4 K 2.5 K 2.5 K 3.2 K | |
| <u>Intact Loop</u> | | | | | | | |
| TE-PC-002A | Intact loop hot leg DTT flange at bottom of pipe. | 422 to 1533 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Not installed. |
| TE-PC-002B | Intact loop hot leg DTT flange at middle of pipe. | 422 to 1533 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Not installed. |
| TE-PC-002C | Intact loop hot leg DTT flange at top of pipe. | 422 to 1533 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Not installed. |
| TE-PC-004 | Bottom of ECC Rake 1 (between PdE-PC-014 and PdE-PC-018). | 270 to 1530 K | 1 Hz | 3.1 K | 350 K 450 K 550 K 650 K | 2.8 K 2.9 K 3.0 K 3.6 K | Qualified. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--|--|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Intact Loop</u> (continued) | | | | | | | |
| TE-PC-005 | Next to bottom of ECC Rake 1 (between PdE-PC-013 and PdE-PC-017). | 270 to 1530 K | 1 Hz | 3.1 K | 350 K 450 K 550 K 650 K | 2.8 K 2.9 K 3.0 K 3.6 K | |
| TE-PC-006 | Next to top of ECC Rake 1 (between PdE-PC-012 and PdE-PC-016). | 270 to 1530 K | 1 Hz | 3.1 K | 350 K 450 K 550 K 650 K | 2.8 K 2.9 K 3.0 K 3.6 K | |
| TE-PC-007 | Top of ECC Rake 1 (between PdE-PC-011 and PdE-PC-015). | 270 to 1530 K | 1 Hz | 3.1 K | 350 K 450 K 550 K 650 K | 2.8 K 2.9 K 3.0 K 3.6 K | Qualified to 200 s. |
| TE-PC-008 | Bottom of ECC Rake 2 (between PdE-PC-022 and PdE-PC-026). | 270 to 1530 K | 1 Hz | 3.1 K | 350 K 450 K 550 K 650 K | 2.8 K 2.9 K 3.0 K 3.6 K | |
| TE-PC-009 | Next to bottom of ECC Rake 2 (between PdE-PC-021 and PdE-PC-025). | 270 to 1530 K | 1 Hz | 3.1 K | 350 K 450 K 550 K 650 K | 2.8 K 2.9 K 3.0 K 3.6 K | |
| TE-PC-010 | Next to top of ECC Rake 2 (between PdE-PC-020 and PdE-PC-024). | 270 to 1530 K | 1 Hz | 3.1 K | 350 K 450 K 550 K 650 K | 2.8 K 2.9 K 3.0 K 3.6 K | |
| TE-PC-011 | Top of ECC Rake 2 (between PdE-PC-019 and PdE-PC-023). | 270 to 1530 K | 1 Hz | 3.1 K | 350 K 450 K 550 K 650 K | 2.8 K 2.9 K 3.0 K 3.6 K | |
| <u>Emergency Core Cooling System</u> | | | | | | | |
| TE-P120-027 | Accumulator B temperature. | 255.2 to 366.3 K | 1 Hz | 0.7 K | -- | 0.7 K | |
| TE-P120-041 | Accumulator A temperature. | 255.2 to 366.3 K | 1 Hz | 0.7 K | -- | 0.7 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|---|--|----------------------|-------------------------------------|--|-----------------------------|--------------------|---|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Blowdown Sup- pression Tank Spray System</u> | | | | | | | |
| TE-P138-127 | Outlet of BST spray system heat exchanger. | 250 to 420 K | 1 Hz | 0.7 K | -- | 0.7 K | |
| TE-P138-141 | Temperature of spray in 3.79-L/s header. | 255.2 to 420 K | 1 Hz | 1.3 K | -- | 1.3 K | |
| TE-P138-142 | Temperature of spray pump discharge. | 255.2 to 420 K | 1 Hz | 1.3 K | -- | 1.3 K | Not installed. |
| TF-P138-143 | Temperature of spray in 13.88-L/s header. | 255.2 to 420 K | 1 Hz | 1.3 K | -- | 1.3 K | Not installed. |
| <u>Broken Loop</u> | | | | | | | |
| TE-P138-170 | Hot leg warm-up line. | 73 to 622 K | 1 Hz | -- | -- | No. available. | |
| TE-P138-171 | Cold leg warm-up line. | 172 to 672 K | 1 Hz | -- | -- | Not available. | Failed. |
| <u>Intact Loop</u> | | | | | | | |
| TE-P139-019 | Pressurizer vapor space, 0.86 m above the heater rods. | 588.6 to 644.1 K | 1 Hz | 0.5 K | -- | 0.5 K | Qualified. |
| TE-P139-020 | Pressurizer liquid volume, 0.36 m above heater rods. | 283 to 644.1 K | 1 Hz | 3.0 K | -- | 3.0 K | Qualified. |
| TE-P139-028-2 | Intact loop cold leg. | 530 to 620 K | 1 Hz | 0.6 K | -- | 0.6 K | Qualified to 200 s, process instrument, slow response time. |
| TE-P139-029 | Intact loop cold leg. | 280 to 620 K | 1 Hz | 2.1 K | -- | 2.1 K | Qualified, process instrument, slow response time. |
| TE-P139-32-1 | Intact loop hot leg. | 280 to 620 K | 1 Hz | 1.43 K | -- | 1.43 K | Qualified to 200 s, process instrument, slow response time. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|---|---|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Primary Com- ponent Cooling System</u> | | | | | | | |
| TE-P141-94 | Downstream from pri- mary component cooling system heat exchanger. | 275 to 350 K | 10 Hz | 0.32 K | -- | 0.32 K | |
| TE-P141-95 | Upstream from primary component cooling system heat exchanger. | 275 to 350 K | 10 Hz | 0.32 K | -- | 0.32 K | |
| <u>Intact Loop</u> | | | | | | | |
| TE-SG-001 | Intact loop cold leg SG outlet. | 253.2 to 977.4 K | 1 Hz | 2.8 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | Qualified. |
| TE-SG-002 | Intact loop hot leg SG inlet. | 253.2 to 977.4 K | 1 Hz | 2.8 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | Qualified. |
| <u>Secondary Coolant System</u> | | | | | | | |
| TE-SG-003 | SG secondary side. | 253.2 to 588.6 K | 1 Hz | 2.5 K | 350 K 450 K 550 K 650 K | 2.4 K 2.5 K 2.5 K 3.2 K | Qualified. |
| <u>Blowdown Sup- pression System</u> | | | | | | | |
| TE-SV-001 | BST, 0.3 m north of Downcomer 1, 0.53 m east of tank center- line, 2.72 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| TE-SV-002 | BST, 0.3 m north of Downcomer 1, 0.53 m east of tank center- line, 2.36 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty ([±]) | After Experiment Initiation | | Comments |
|---|---|----------------------|-------------------------------------|---|-----------------------------|---------------------------------|----------|
| | | | | | Reading | Uncertainty ([±]) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Blowdown Sup- pression System</u> (continued) | | | | | | | |
| TE-SV-003 | BST, 0.3 m north of Downcomer 1, 0.53 m east of tank center- line, 1.90 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| TE-SV-004 | BST, 0.3 m north of Downcomer 1, 0.53 m east of tank center- line, 1.45 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| TE-SV-005 | BST, 0.3 m north of Downcomer 1, 0.53 m east of tank center- line, 0.99 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | -- | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| TE-SV-006 | BST, 0.3 m north of Downcomer 1, 0.53 m east of tank center- line, 0.37 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| TE-SV-007 | BST, 0.3 m north of Downcomer 3, 0.53 m east of tank center- line, 2.72 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| TE-SV-008 | BST, 0.3 m north of Downcomer 3, 0.53 m east of tank center- line, 2.36 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|---|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|----------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Flowdown Sup- pression System</u> (continued) | | | | | | | |
| TE-SV-009 | BST, 0.3 m north of Downcomer 3, 0.53 m east of tank center- line, 1.90 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| TE-SV-010 | BST, 0.3 m north of Downcomer 3, 0.53 m east of tank center- line, 1.45 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| TE-SV-011 | BST, 0.3 m north of Downcomer 3, 0.53 m east of tank center- line, 0.99 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| TE-SV-012 | BST, 0.3 m north of Downcomer 3, 0.53 m east of tank center- line, 0.37 m from tank bottom. | 253.2 to 477.4 K | 1 Hz | 0.9 K | 300 K 350 K 400 K | 0.9 K 1.0 K 1.3 K | |
| <u>Reactor Vessel</u> | | | | | | | |
| TE-1A11-030 | Fuel Assembly 1, Row A, Column 11, 0.762 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-1B10-037 | Fuel Assembly 1, Row B, Column 10, 0.940 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-1B12-026 | Fuel Assembly 1, Row B, Column 12, 0.660 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| Reactor Vessel (continued) | | | | | | | |
| TE-1C11-021 | Fuel Assembly 1, Row C, Column 11, 0.533 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-1C11-039 | Fuel Assembly 1, Row C, Column 11, 0.991 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-1F7-015 | Fuel Assembly 1, Row F, Column 7, 0.381 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-1F7-021 | Fuel Assembly 1, Row P, Column 7, 0.533 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-1F7-026 | Fuel Assembly 1, Row F, Column 7, 0.660 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-1F7-030 | Fuel Assembly 1, Row F, Column 7, 0.762 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-1LP-001 | Fuel Assembly 1 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-1ST-001 | Downcomer Stalk 1, 4.8 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|---------------------------------------|---|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel (continued)</u> | | | | | | | |
| TE-1ST-002 | Downcomer Stalk 1, 4.2 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | |
| TE-1ST-005 | Downcomer Stalk 1, 2.37 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | Qualified to 200 s. |
| TE-1ST-009 | Downcomer Stalk 1, 0.64 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | |
| TE-1ST-013 | Downcomer Stalk 1, 0.24 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | Qualified to 200 s. |
| TE-1ST-014 | Downcomer Stalk 1, 1.17 m from RV bottom (inside of DTT). | 253.2 to 977.4 K | 1 Hz | -- | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-1UP-001 | Fuel Assembly 1 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | Qualified to 200 s. |
| TE-1UP-002 | Fuel Assembly 1 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-1UP-003 | Fuel Assembly 1 support column above RV nozzle. | 311 to 977.4 K | 1 Hz | -- | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-1UP-004 | Fuel Assembly 1 support column above RV nozzle. | 311 to 977.4 K | 10 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-1UP-005 | DTT FE-1UP-1 above Fuel Assembly 1. | 311 to 977.4 K | 10 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-1UP-006 | Fuel Assembly 1 support column. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-2E8-045 | Cladding on Fuel Assembly 2, Row E, Column 8 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 10 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-2F7-037 | Cladding on Fuel Assembly 2, Row F, Column 7 at 0.94 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-2G14-011 | Cladding on Fuel Assembly 2, Row G, Column 14 at 0.28 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-2G14-030 | Cladding on Fuel Assembly 2, Row G, Column 14 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.7 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty ([±]) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|---|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty ([±]) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-2G14-045 | Cladding on Fuel Assembly 2, Row G, Column 14 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 400 K 600 K 800 K 1000 K | 2.7 K 3.2 K 4.7 K 6.2 K | Qualified. |
| TE-2H01-037 | Cladding on Fuel Assembly 2, Row H, Column 1 at 0.94 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 400 K 600 K 800 K 1000 K | 2.7 K 3.2 K 4.7 K 6.2 K | |
| TE-2H02-028 | Cladding on Fuel Assembly 2, Row H, Column 2 at 0.71 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 400 K 600 K 800 K 1000 K | 2.7 K 3.2 K 4.7 K 6.2 K | |
| TE-2H02-032 | Cladding on Fuel Assembly 2, Row H, Column 2 at 0.81 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 400 K 600 K 800 K 1000 K | 2.7 K 3.2 K 4.7 K 6.2 K | |
| TE-2H08-039 | Guide tube for Fuel Assembly 2, Row H, Column 8 at 0.99 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 400 K 600 K 800 K 1000 K | 2.7 K 3.2 K 4.7 K 6.2 K | |
| TE-2LP-001 | Fuel Assembly 2 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-2LP-003 | Fuel Assembly 2 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-2ST-001 | Downcomer Stalk 2, 4.8 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | |
| TE-2ST-005 | Downcomer Stalk 2, 2.37 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | |
| TE-2ST-009 | Downcomer Stalk 2, 0.64 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | |
| TE-2ST-013 | Downcomer Stalk 2, 0.24 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | |
| TE-2ST-014 | Downcomer Stalk 2, 1.17 m from RV bottom. | 253.2 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.7 K 3.3 K | Qualified. |
| TE-2UP-001 | Fuel Assembly 2 upper end box. | 311 to 977.4 K | 1 Hz | -- | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-2UP-002 | Fuel Assembly 2 upper end box. | 311 to 977.4 K | 10 Hz | -- | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-2UP-003 | Fuel Assembly 2 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|----------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-3B12-026 | Cladding on Fuel Assembly 3, Row B, Column 12 at 0.66 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-3C11-021 | Cladding on Fuel Assembly 3, Row C, Column 11 at 0.53 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-3C11-039 | Cladding on Fuel Assembly 3, Row C, Column 11 at 0.99 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-3F7-015 | Cladding on Fuel Assembly 3, Row F, Column 7 at 0.38 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-3F7-021 | Cladding on Fuel Assembly 3, Row F, Column 7 at 0.53 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-3F7-026 | Cladding on Fuel Assembly 3, Row F, Column 7 at 0.66 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-3F7-030 | Cladding on Fuel Assembly 3, Row F, Column 7 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (*) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (*) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-3LP-001 | Fuel Assembly 3 lower end box. | 311 to 977.4 K | 1 Hz | 2.6 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-3UP-001 | Fuel Assembly 3 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-3UP-002 | Fuel Assembly 3 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-3UP-003 | Fuel Assembly 3 support column above RV nozzle. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-004 | Fuel Assembly 3 support column above RV nozzle. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-005 | DTT FE-3UP-1 above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | -- | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-006 | Support column. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-007 | Support column. | 311 to 977.4 K | 1 Hz | -- | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-3UP-008 | Liquid level transducer above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-009 | Liquid level transducer above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | -- | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-010 | Liquid level transducer above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-011 | Liquid level transducer above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-3UP-012 | Liquid level transducer above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-013 | Liquid level transducer above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-014 | Liquid level transducer above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-3UP-015 | Liquid level transducer above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|----------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| Reactor Vessel (continued) | | | | | | | |
| TE-3UP-016 | Liquid level transducer above Fuel Assembly 3. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-4G14-011 | Cladding on Fuel Assembly 4, Row G, Column 14 at 0.28 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-4G14-030 | Cladding on Fuel Assembly 4, Row G, Column 14 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-4G14-045 | Cladding on Fuel Assembly 4, Row G, Column 14 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-4H01-037 | Cladding on Fuel Assembly 4, Row H, Column 1 at 0.94 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-4H02-028 | Cladding on Fuel Assembly 4, Row H, Column 2 at 0.71 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-4H02-032 | Cladding on Fuel Assembly 4, Row H, Column 2 at 0.81 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-4H08-039 | Cladding on Fuel Assembly 4, Row H, Column 8 at 0.99 m above bottom of fuel rod. | 422 to 1533 K | 10 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-4LP-001 | Fuel Assembly 4 lower end box. | 311 to 977.4 K | 1 Hz | 2.6 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-4LP-003 | Fuel Assembly 4 lower end box. | 311 to 977.4 K | 1 Hz | 2.6 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-4UP-001 | Fuel Assembly 4 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-4UP-002 | Fuel Assembly 4 upper end box. | 311 to 977.4 K | 1 Hz | -- | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-4UP-003 | Fuel Assembly 4 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-5C6-024 | Guide tube for Fuel Assembly 5, Row C, Column 6 at 0.61 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| Reactor Vessel (continued) | | | | | | | |
| TE-5D6-030 | Cladding on Fuel Assembly 5, Row D, Column 6 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5D6-032 | Cladding on Fuel Assembly 5, Row D, Column 6 at 0.81 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5D6-037 | Cladding on Fuel Assembly 5, Row D, Column 6 at 0.94 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5D6-039 | Cladding on Fuel Assembly 5, Row D, Column 6 at 0.99 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5E8-002 | Cladding on Fuel Assembly 5, Row E, Column 8 at 0.05 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | — | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5E8-015 | Cladding on Fuel Assembly 5, Row E, Column 8 at 0.38 m above bottom of fuel rod. | 420 to 1810 K | 1 Hz | 4.1 K | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 5.2 K 6.7 K | |
| TE-5E8-034.5 | Cladding on Fuel Assembly 5, Row E, Column 8 at 0.88 m above bottom of fuel rod. | 420 to 1810 K | 1 Hz | 4.1 K | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 5.2 K 6.7 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (\pm) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (\pm) | |
| TEMPERATURE (continued) | | | | | | | |
| Reactor Vessel (continued) | | | | | | | |
| TE-5E8-049 | Cladding on Fuel Assembly 5, Row E, Column 8 at 1.24 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5F3-024 | Cladding on Fuel Assembly 5, Row F, Column 3 at 0.61 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 300 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5F4-015 | Cladding on Fuel Assembly 5, Row F, Column 4 at 0.38 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5F4-021 | Cladding on Fuel Assembly 5, Row F, Column 4 at 0.53 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5F4-026 | Cladding on Fuel Assembly 5, Row F, Column 4 at 0.66 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5F4-030 | Cladding on Fuel Assembly 5, Row F, Column 4 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5F7-005 | Cladding on Fuel Assembly 5, Row F, Column 7 at 0.13 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|----------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-5F7-021 | Cladding on Fuel Assembly 5, Row F, Column 7 at 0.53 m above bottom of fuel rod. | 420 to 1810 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 4.7 K 6.2 K | |
| TE-5F7-039 | Cladding on Fuel Assembly 5, Row F, Column 7 at 0.99 m above bottom of fuel rod. | 420 to 1810 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 5.2 K 6.7 K | Failed. |
| TE-5F7-054 | Cladding on Fuel Assembly 5, Row F, Column 7 at 1.37 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5F8-024 | Cladding on Fuel Assembly 5, Row F, Column 8 at 0.61 m above bottom of fuel rod. | 420 to 1810 K | 1 Hz | 4.1 K | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 5.2 K 6.7 K | Failed. |
| TE-5F8-028 | Cladding on Fuel Assembly 5, Row F, Column 8 at 0.71 m above bottom of fuel rod. | 420 to 1810 K | 1 Hz | 4.1 K | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 5.2 K 6.7 K | |
| TE-5F8-032 | Cladding on Fuel Assembly 5, Row F, Column 8 at 0.81 m above bottom of fuel rod. | 420 to 1810 K | 1 Hz | 4.1 K | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 5.2 K 6.7 K | |
| TE-5F8-037 | Cladding on Fuel Assembly 5, Row F, Column 8 at 0.94 m above bottom of fuel rod. | 420 to 1810 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 5.2 K 6.7 K | Failed. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-5F9-011 | Cladding on Fuel Assembly 5, Row F, Column 9 at 0.28 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5F9-030 | Cladding on Fuel Assembly 5, Row F, Column 9 at 0.76 m above bottom of fuel rod. | 420 to 1810 K | 1 Hz | 4.2 K | 450 K 600 K 800 K 1000 K | 3.8 K 4.2 K 5.2 K 6.7 K | |
| TE-5F9-045 | Cladding on Fuel Assembly 5, Row F, Column 9 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5F9-062 | Cladding on Fuel Assembly 5, Row F, Column 9 at 1.57 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5G6-011 | Cladding on Fuel Assembly 5, Row G, Column 6 at 0.28 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5G6-030 | Cladding on Fuel Assembly 5, Rod G, Column 6 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5G6-045 | Cladding on Fuel Assembly 5, Row G, Column 6 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-5G6-062 | Cladding on Fuel Assembly 5, Row G, Column 6 at 1.57 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5G8-008 | Cladding on Fuel Assembly 5, Row G, Column 8 at 0.20 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5G8-026 | Cladding on Fuel Assembly 5, Row G, Column 8 at 0.66 m above bottom of fuel rod. | 410 to 1820 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 3.3 K 4.2 K 5.2 K 6.7 K | Qualified to 200 s. |
| TE-5G8-041 | Cladding on Fuel Assembly 5, Row G, Column 8 at 1.04 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5G8-058 | Cladding on Fuel Assembly 5, Row G, Column 8 at 1.47 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5H5-002 | Cladding on Fuel Assembly 5, Row H, Column 5 at 0.05 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5H5-015 | Cladding on Fuel Assembly 5, Row H, Column 5 at 0.38 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| Reactor Vessel (continued) | | | | | | | |
| TE-5H5-034.5 | Cladding on Fuel Assembly 5, Row H, Column 5 at 0.88 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5H5-049 | Cladding on Fuel Assembly 5, Row H, Column 5 at 1.24 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5H6-024 | Cladding on Fuel Assembly 5, Row H, Column 6 at 0.61 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5H6-028 | Cladding on Fuel Assembly 5, Row H, Column 6 at 0.71 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5H6-032 | Cladding on Fuel Assembly 5, Row H, Column 6 at 0.81 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5H6-037 | Cladding on Fuel Assembly 5, Row H, Column 6 at 0.94 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Failed. |
| TE-5H7-008 | Cladding on Fuel Assembly 5, Row H, Column 7 at 0.20 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (\pm) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|----------|
| | | | | | Reading | Uncertainty (\pm) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-5H7-026 | Cladding on Fuel Assembly 5, Row H, Column 7 at 0.66 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5H7-041 | Cladding on Fuel Assembly 5, Row H, Column 7 at 1.04 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5H7-058 | Cladding on Fuel Assembly 5, Row H, Column 7 at 1.47 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-516-005 | Cladding on Fuel Assembly 5, Row I, Column 6 at 0.13 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-516-021 | Cladding on Fuel Assembly 5, Row I, Column 6 at 0.53 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-516-039 | Cladding on Fuel Assembly 5, Row I, Column 6 at 0.99 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-516-054 | Cladding on Fuel Assembly 5, Row I, Column 6 at 1.37 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (\pm) | After Experiment Initiation | | Comments |
|---------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|----------|
| | | | | | Reading | Uncertainty (\pm) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel (continued)</u> | | | | | | | |
| TE-518-008 | Cladding on Fuel Assembly 5, Row I, Column 8 at 0.20 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-518-026 | Cladding on Fuel Assembly 5, Row I, Column 8 at 0.66 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-518-041 | Cladding on Fuel Assembly 5, Row I, Column 8 at 1.04 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-518-058 | Cladding on Fuel Assembly 5, Row I, Column 8 at 1.47 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J3-024 | Cladding on Fuel Assembly 5, Row J, Column 3 at 0.61 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J4-015 | Cladding on Fuel Assembly 5, Row J, Column 4 at 0.38 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J4-021 | Cladding on Fuel Assembly 5, Row J, Column 4 at 0.53 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|----------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-5J4-026 | Cladding on Fuel Assembly 5, Row J, Column 4 at 0.66 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | -- | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J4-030 | Cladding on Fuel Assembly 5, Row J, Column 4 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J7-011 | Cladding on Fuel Assembly 5, Row J, Column 7 at 0.28 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J7-030 | Cladding on Fuel Assembly 5, Row J, Column 7 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J7-045 | Cladding on Fuel Assembly 5, Row J, Column 7 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J7-062 | Cladding on Fuel Assembly 5, Row J, Column 7 at 1.57 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J8-024 | Cladding on Fuel Assembly 5, Row J, Column 8 at 0.61 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (\pm) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|----------|
| | | | | | Reading | Uncertainty (\pm) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-5J8-028 | Cladding on Fuel Assembly 5, Row J, Column 8 at 0.71 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J8-032 | Cladding on Fuel Assembly 5, Row J, Column 8 at 0.81 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J8-037 | Cladding on Fuel Assembly 5, Row J, Column 8 at 0.94 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J9-005 | Cladding on Fuel Assembly 5, Row J, Column 9 at 0.13 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J9-021 | Cladding on Fuel Assembly 5, Row J, Column 9 at 0.53 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J9-039 | Cladding on Fuel Assembly 5, Row J, Column 9 at 0.99 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5J9-054 | Cladding on Fuel Assembly 5, Row J, Column 9 at 1.37 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (⁺) | After Experiment Initiation | | Comments |
|--------------------------------------|--|----------------------|-------------------------------------|---|-----------------------------|---------------------------------|------------|
| | | | | | Reading | Uncertainty (⁺) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-5K8-002 | Cladding on Fuel Assembly 5, Row K, Column 8 at 0.05 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K | 2.8 K | |
| | | | | | 600 K | 3.2 K | |
| | | | | | 800 K | 4.7 K | |
| | | | | | 1000 K | 6.2 K | |
| TE-5K8-013 | Cladding on Fuel Assembly 5, Row K, Column 8 at 0.38 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K | 2.8 K | |
| | | | | | 600 K | 3.2 K | |
| | | | | | 800 K | 4.7 K | |
| | | | | | 1000 K | 6.2 K | |
| TE-5K8-034.5 | Cladding on Fuel Assembly 5, Row K, Column 8 at 0.88 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K | 2.8 K | |
| | | | | | 600 K | 3.2 K | |
| | | | | | 800 K | 4.7 K | |
| | | | | | 1000 K | 6.2 K | |
| TE-5K8-049 | Cladding on Fuel Assembly 5, Row K, Column 8 at 1.24 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K | 2.8 K | |
| | | | | | 600 K | 3.2 K | |
| | | | | | 800 K | 4.7 K | |
| | | | | | 1000 K | 6.2 K | |
| TE-5LP-001 | Fuel Assembly 5 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K | 2.5 K | Qualified. |
| | | | | | 450 K | 2.6 K | |
| | | | | | 550 K | 2.6 K | |
| | | | | | 650 K | 3.3 K | |
| TE-5LP-002 | Fuel Assembly 5 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K | 2.5 K | |
| | | | | | 450 K | 2.6 K | |
| | | | | | 550 K | 2.6 K | |
| | | | | | 650 K | 3.3 K | |
| TE-5LP-003 | Fuel Assembly 5 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K | 2.5 K | |
| | | | | | 450 K | 2.6 K | |
| | | | | | 550 K | 2.6 K | |
| | | | | | 650 K | 3.3 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-5LP-004 | Fuel Assembly 5 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-5L6-030 | Cladding on Fuel Assembly 5, Row L, Column 6 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5L6-032 | Cladding on Fuel Assembly 5, Row L, Column 6 at 0.81 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5L6-037 | Cladding on Fuel Assembly 5, Row L, Column 6 at 0.94 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5L6-039 | Cladding on Fuel Assembly 5, Row L, Column 6 at 0.99 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5L8-011 | Guide tube for Fuel Assembly 5, Row L, Column 8 at 0.28 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5L8-024 | Guide tube for Fuel Assembly 5, Row L, Column 8 at 0.61 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty ([±]) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|---|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty ([±]) | |
| TEMPERATURE (continued) | | | | | | | |
| Reactor Vessel (continued) | | | | | | | |
| TE-5L8-039 | Guide tube for Fuel Assembly 5, Row L, Column 8 at 0.99 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5L8-045 | Guide tube for Fuel Assembly 5, Row L, Column 8 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | Qualified to 200 s. |
| TE-5M6-024 | Guide tube for Fuel Assembly 5, Row M, Column 6 at 0.61 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-5UP-001 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified. |
| TE-5UP-002 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified. |
| TE-5UP-003 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified. |
| TE-5UP-004 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | Hz | 2.7 K | 350 K 450 K 500 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (±) | |
| TEMPERATURE (continued) | | | | | | | |
| Reactor Vessel (continued) | | | | | | | |
| TE-5UP-005 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified. |
| TE-5UP-006 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 370 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified. |
| TE-5UP-007 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified. |
| TE-5UP-008 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified. |
| TE-5UP-009 | Fuel Assembly 5 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-6E8-045 | Cladding on Fuel Assembly 6, Row E, Column 8 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-6G14-011 | Cladding on Fuel Assembly 6, Row G, Column 14 at 0.28 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (\pm) | After Experiment Initiation | | Comments |
|--------------------------------------|---|----------------------|-------------------------------------|--|-----------------------------------|----------------------------------|---------------------|
| | | | | | Reading | Uncertainty (\pm) | |
| TEMPERATURE (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-6G14-030 | Cladding on Fuel Assembly 6, Row G, Column 14 at 0.76 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-6G14-045 | Cladding on Fuel Assembly 6, Row G, Column 14 at 1.14 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.2 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-6H01-037 | Cladding on Fuel Assembly 6, Row H, Column 1 at 0.94 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-6H02-028 | Cladding on Fuel Assembly 6, Row H, Column 2 at 0.71 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-6H02-032 | Cladding on Fuel Assembly 6, Row H, Column 2 at 0.81 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-6H08-039 | Cladding on Fuel Assembly 6, Row H, Column 8 at 0.99 m above bottom of fuel rod. | 422 to 1533 K | 1 Hz | 3.1 K | 450 K 600 K 800 K 1000 K | 2.8 K 3.2 K 4.7 K 6.2 K | |
| TE-6LP-001 | Fuel Assembly 6 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (*) | After Experiment Initiation | | Comments |
|--|---|----------------------|-------------------------------------|--|----------------------------------|----------------------------------|---|
| | | | | | Reading | Uncertainty (*) | |
| <u>TEMPERATURE</u> (continued) | | | | | | | |
| <u>Reactor Vessel</u> (continued) | | | | | | | |
| TE-SLP-003 | Fuel Assembly 6 lower end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | |
| TE-6UP-001 | Fuel Assembly 6 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| TE-6UP-003 | Fuel Assembly 6 upper end box. | 311 to 977.4 K | 1 Hz | 2.7 K | 350 K 450 K 550 K 650 K | 2.5 K 2.6 K 2.6 K 3.3 K | Qualified to 200 s. |
| <u>Secondary Coolant System</u> | | | | | | | |
| TT-PC04-004 | Secondary coolant system feedwater. | 366 to 505 K | 1 Hz | 0.9 K | -- | 0.9 K | |
| <u>Emergency Core Cooling System</u> | | | | | | | |
| TT-P120-062 | Cold leg injection in 4-in. line upstream of cold leg injection point. | 280 to 620 K | 1 Hz | 2.1 K | -- | 2.1 K | |
| <u>Intact Loop</u> | | | | | | | |
| TT-P139-032 | Intact loop hot leg primary coolant, Channel A. | 533 to 616 K | 1 Hz | 0.5 K | -- | 0.5 K | Qualified to 200 s, process instrument, response limited. |
| TT-P139-033 | Intact loop hot leg primary coolant, Channel B. | 533 to 616 K | 1 Hz | 0.5 K | -- | 0.5 K | Qualified to 200 s, process instrument, response limited. |
| TT-P139-034 | Intact loop hot leg primary coolant, Channel C. | 533 to 616 K | 1 Hz | 0.5 K | -- | 0.5 K | Qualified to 200 s, process instrument, response limited. |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (±) | After Experiment Initiation | | Comments |
|--------------------------------------|------------------------------|----------------------|-------------------------------------|--|-----------------------------|--------------------|---------------|
| | | | | | Reading | Uncertainty (±) | |
| TRANSIT TIME | | | | | | | |
| <u>Broken Loop</u> | | | | | | | |
| TTE-BL-01A-1 | Cold leg, bottom, front. | +76 m/s | 1 Hz | -- | 0 m/s | 0.75 m/s | Not recorded. |
| | | | | | 40 m/s | 2.36 m/s | |
| | | | | | 76 m/s | 4.33 m/s | |
| TTE-BL-01A-2 | Cold leg, bottom, center. | +76 m/s | 1 Hz | -- | 0 m/s | 0.75 m/s | Not recorded. |
| | | | | | 40 m/s | 2.36 m/s | |
| | | | | | 76 m/s | 4.33 m/s | |
| TTE-BL-01A-3 | Cold leg, bottom, rear. | +76 m/s | 1 Hz | -- | 0 m/s | 0.75 m/s | Not recorded. |
| | | | | | 40 m/s | 2.36 m/s | |
| | | | | | 76 m/s | 4.33 m/s | |
| TTE-BL-01B-1 | Cold leg, center, front. | +76 m/s | 1 Hz | -- | 0 m/s | 0.75 m/s | Not recorded. |
| | | | | | 40 m/s | 2.36 m/s | |
| | | | | | 76 m/s | 4.33 m/s | |
| TTE-BL-01B-3 | Cold leg, center, rear. | +76 m/s | 1 Hz | -- | 0 m/s | 0.75 m/s | Not recorded. |
| | | | | | 40 m/s | 2.36 m/s | |
| | | | | | 76 m/s | 4.33 m/s | |
| TTE-BL-01C-1 | Cold leg, top, front. | +76 m/s | 1 Hz | -- | 0 m/s | 0.75 m/s | Not recorded. |
| | | | | | 40 m/s | 2.36 m/s | |
| | | | | | 76 m/s | 4.33 m/s | |
| TTE-BL-01C-2 | Cold leg, top, center. | +76 m/s | 1 Hz | -- | 0 m/s | 0.75 m/s | Not recorded. |
| | | | | | 40 m/s | 2.36 m/s | |
| | | | | | 76 m/s | 4.33 m/s | |
| TTE-BL-01C-3 | Cold leg, top, rear. | +76 m/s | 1 Hz | -- | 0 m/s | 0.75 m/s | Not recorded. |
| | | | | | 40 m/s | 2.36 m/s | |
| | | | | | 76 m/s | 4.33 m/s | |

TABLE B-1. (continued)

| Variable, System, and Detector | Location | Measurement Range | Recording Frequency ^a | Initial Condition Uncertainty (\pm) | After Experiment Initiation | | Comments |
|--|----------|----------------------|-------------------------------------|--|-----------------------------|--------------------------|----------|
| | | | | | Reading | Uncertainty (\pm) | |
| <p>a. Recording frequency is the measurement channel bandwidth at the +3 dB level.</p> <p>b. Reference B-1.</p> <p>c. Reference B-2.</p> <p>d. Reference B-3.</p> <p>e. The steam generator level is defined as 0 at 2.95 m above the top of the tube sheet.</p> <p>f. Reference B-4.</p> <p>g. Reference B-5.</p> <p>h. Pressure measurements are presented as absolute values.</p> | | | | | | | |

REFERENCES

- B-1. G. D. Lassahn, *LOFT Experimental Measurements Uncertainties Analyses, Volume XVI, LOFT Three-Beam Gamma Densitometer System*, TREE-NUREG-1089, February 1979.
- B-2. G. L. Biladeau, *LOFT Experimental Measurements Uncertainty Analyses, Volume VI, LOFT Linear Variable Differential Transformer Displacement Transducer Uncertainty Analysis*, TREE-NUREG-1089, February 1978.
- B-3. S. Silverman, *LOFT Experimental Measurements Uncertainty Analyses, Volume XIV, LOFT Drag Disc-Turbine Transducer Uncertainty Analysis*, NUREG/CR-0169, TREE-1089, November 1978.
- B-4. G. D. Lassahn, *LOFT Experimental Measurements Uncertainty Analyses, Volume VII, LOFT Self-Powered Neutron Detector Uncertainty Analysis*, NUREG/CR-0169, TREE-1089, August 1978.
- B-5. L. D. Goodrich, Jr., *LOFT Experimental Measurements Uncertainty Analyses, Volume XV, LOFT Primary Coolant Pump Speed Measurement Uncertainty Analysis*, TREE-NUREG-1089, April 1978.